

Cynthia Vodopivec Illinois Power Generating Company Luminant 6555 Sierra Dr. Irving, TX 75039

September 29, 2020

Sent via email

Mr. Andrew R. Wheeler, EPA Administrator Environmental Protection Agency 1200 Pennsylvania Avenue, N.W. Mail Code 5304-P Washington, DC 20460

Re: Coffeen Power Station Alternative Closure Demonstration

Dear Administrator Wheeler:

Illinois Power Generating Company (IPGC) hereby submits this request to the U.S. Environmental Protection Agency (EPA) for approval for a site-specific alternative deadline to initiate closure pursuant to 40 C.F.R. § 257.103(f)(1) for the two CCR surface impoundments (Gypsum Management Facility Gypsum Stack Pond and the GMF Recycle Pond, collectively referred to as the GMF Ponds) located at the Coffeen Power Station near Coffeen, Illinois. IPGC is requesting an alternative deadline to continue to receive CCR and non-CCR wastestreams at the GMF Ponds after April 11, 2021 in order to install a new landfill leachate management system at Coffeen.

Enclosed is a demonstration prepared by Burns & McDonnell that addresses all of the criteria in 40 C.F.R. § 257.103(f)(1)(i)-(iii) and contains the documentation required by 40 C.F.R. § 257.103(f)(1)(iv). As allowed by the agency, in lieu of hard copies of these documents, electronic files were to Kirsten Hillyer, Frank Behan, and Richard Huggins via email. If you have any questions regarding this submittal, please contact Phil Morris at 618-343-7794 or phil.morris@vistracorp.com.

Sincerely,

Cynthin E. Ubdy

Cynthia Vodopivec VP - Environmental Health & Safety

Enclosure

cc: Kirsten Hillyer Frank Behan Richard Huggins





## Coffeen CCR Surface Impoundment Demonstration for a Site-Specific Alternative to Initiation of Closure Deadline



### **Illinois Power Generating Company**

Coffeen Power Station Project No. 122702

Revision 0 September 28, 2020



# Coffeen CCR Surface Impoundment Demonstration for a Site-Specific Alternative to Initiation of Closure Deadline

**Prepared for** 

Illinois Power Generating Company Coffeen Power Station Project No. 122702 Coffeen, Illinois

> Revision 0 September 28, 2020

> > Prepared by

Burns & McDonnell Engineering Company, Inc. Kansas City, Missouri

#### INDEX AND CERTIFICATION


#### Illinois Power Generating Company Coffeen CCR Surface Impoundment Demonstration for a Site-Specific Alternative to Initiation of Closure Deadline

#### Report Index

<u>Chapter</u> Number	Chapter Title	<u>Number</u> of Pages
1.0 2.0	Introduction Workplan	3 12
4.0	Conclusion	1
Appendix A	Site Plan and Water Balance Diagram	2
Appendix B	Schedule	1

#### Certification

I hereby certify, as a Professional Engineer in the state of Illinois, that the information in this document as noted in the above Report Index was assembled under my direct personal charge. This report is not intended or represented to be suitable for reuse by the Illinois Power Generating Company or others without specific verification or adaptation by the Engineer.



Edward T. Tohill, P.E. (Illinois License No. 062-056915)

Date: September 28, 2020

#### TABLE OF CONTENTS

#### Page No.

WC	RKPLAN		2-1
2.1		ernative Disposal Capacity and Approach to Obtain Alternative	
		ty - § 257.103(f)(1)(iv)(A)(1)	
	2.1.1	CCR Wastestreams	
	2.1.2	Non-CCR Wastestreams	2-2
	2.1.3	Site-Specific Conditions Supporting Alternative Capacity Approach - § 257.103(f)(1)(iv)(A)(1)(i)	23
	2.1.4	Impact to Plant Operations if Alternative Capacity Not Obtained –	
		§ 257.103(f)(1)(iv)(A)(1)(ii)	
	2.1.5	Options Considered Both On and Off-Site to Obtain Alternative	
		Capacity	
	2.1.6	Approach to Obtain Alternative Capacity	2-6
	2.1.7	Technical Infeasibility of Obtaining Alternative Capacity prior to April 11, 2021	2-7
	2.1.8	Justification for Time Needed to Complete Development of	
		Alternative Capacity Approach - § 257.103(f)(1)(iv)(A)(1)(iii)	2-7
2.2		d Schedule to Obtain Alternative Disposal Capacity -	
	§ 257.1	03(f)(1)(iv)(A)(2)	2-8
2.3		ve of Schedule and Visual Timeline - § 257.103(f)(1)(iv)(A)(3)	2-8
2.4		ss Towards Obtaining Alternative Capacity -	
	§ 257.1	03(f)(1)(iv)(A)(4)	2-11
DO	CUMENT	ATON AND CERTIFICATION OF COMPLIANCE	3-1
3.1	Owner	's Certification of Compliance - § 257.103(f)(1)(iv)(B)(1)	3-1
3.2		Representation of Hydrogeologic Information -	
		03(f)(1)(iv)(B)(2)	3-1
3.3		lwater Monitoring Results - § 257.103(f)(1)(iv)(B)(3)	
3.4		otion of Site Hydrogeology - § 257.103(f)(1)(iv)(B)(4)	
3.5		tive Measures Assessment - § 257.103(f)(1)(iv)(B)(5)	
3.6		y Selection Progress Report - § 257.103(f)(1)(iv)(B)(6)	
3.7		ral Stability Assessment - § 257.103(f)(1)(iv)(B)(7)	
3.8		Factor Assessment - § 257.103(f)(1)(iv)(B)(8)	

#### APPENDIX A – SITE PLAN AND WATER BALANCE DIAGRAM APPENDIX B – SCHEDULE APPENDIX C – COMPLIANCE DOCUMENTS

#### LIST OF TABLES

#### Page No.

Table 2-1: Coffeen CCR Surface Impoundment Summary	
Table 2-2: Coffeen Non-CCR Wastestreams	
Table 2-3: Alternatives for Disposal Capacity	
Table 2-4: Alternatives Considered for Non-CCR wastestreams	
Table 2-5: Compliance Project Progress Milestones	
Table 5-1: Anticipated Permitting Requirements	

#### LIST OF ABBREVIATIONS

Abbreviation	Term/Phrase/Name
AP1	Ash Pond No. 1
AP2	Ash Pond No. 2
CCR	Coal Combustion Residual
C.F.R.	Code of Federal Regulations
Coffeen	Coffeen Power Station
СҮ	Cubic Yards
ELG	Effluent Limitations Guidelines and Standards for the Steam Electric Power Generating Point Source Category
EPA	Environmental Protection Agency
FGD	Flue Gas Desulfurization
gal	Gallons
GCL	Geosynthetic Clay Liner
GMF	Gypsum Management Facility
gpd	Gallons per Day
GWPS	Groundwater Protection Standards
HDPE	High Density Polyethylene
IPGC	Illinois Power Generating Company
RCRA	Resource Conservation and Recovery Act
SAP	Sampling and Analysis Plan
SSI(s)	Statistically Significant Increases
SSL(s)	Statistically Significant Levels

i

#### 1.0 INTRODUCTION

On April 17, 2015, the Environmental Protection Agency (EPA) issued the federal Coal Combustion Residual (CCR) Rule, 40 C.F.R. Part 257, Subpart D, to regulate the disposal of CCR materials generated at coal-fueled electric generating units. The rule is being administered under Subtitle D of the Resource Conservation and Recovery Act (RCRA, 42 U.S.C. § 6901 et seq.).

On August 28, 2020, the EPA Administrator issued revisions to the CCR Rule that require all unlined surface impoundments to cease receipt of CCR and non-CCR waste and initiate closure by April 11, 2021, unless an alternative deadline is requested and approved. 40 C.F.R. § 257.101(a)(1) (85 Fed. Reg. 53,516 (Aug. 28, 2020)). Specifically, owners and operators of a CCR surface impoundment may seek and obtain an alternative closure deadline by demonstrating that there is currently no alternative capacity available on or off-site and that it is not technically feasible to complete the development of alternative capacity prior to April 11, 2021. 40 C.F.R. § 257.103(f)(1). To make this demonstration, the facility is required to provide detailed information regarding the process the facility is undertaking to develop the alternative capacity. 40 C.F.R. § 257.103(f)(1). Any extensions granted cannot extend past October 15, 2023, except an extension can be granted until October 15, 2024, if the impoundment qualifies as an "eligible unlined CCR surface impoundment" as defined by the rule. 40 C.F.R. § 257.103(f)(1)(vi). Regardless of the maximum time allowed under the rule, EPA explains in the preamble to the Part A rule that each impoundment "must still cease receipt of waste as soon as feasible, and may only have the amount of time [the owner/operator] can demonstrate is genuinely necessary." 85 Fed. Reg. at 53,546.

This document serves as Illinois Power Generating Company's (IPGC's) Demonstration for a sitespecific alternative deadline to initiate closure pursuant to 40 C.F.R. § 257.103(f)(1) for the CCR surface impoundments at the Coffeen Power Station (Coffeen), which include the following:

- Gypsum Management Facility (GMF) Gypsum Stack Pond, also referred to as the GMF Pond
- GMF Recycle Pond

EPA should note there are two other CCR surface impoundments onsite at Coffeen. Ash Pond No. 1 (AP1) will initiate closure prior to April 11, 2021, and Ash Pond No. 2 (AP2) is expected to complete closure in October 2020; therefore, these facilities are not included within this demonstration.

To obtain an alternative closure deadline under 40 C.F.R. § 257.103(f)(1), a facility must meet the following three criteria:

- 1. § 257.103(f)(1)(i) There is no alternative disposal capacity available on-site or off-site. An increase in costs or the inconvenience of existing capacity is not sufficient to support qualification;
- 2. § 257.103(f)(1)(ii) Each CCR and/or non-CCR wastestream must continue to be managed in that CCR surface impoundment because it was technically infeasible to complete the measures necessary to obtain alternative disposal capacity either on or off-site of the facility by April 11, 2021; and
- 3. § 257.103(f)(1)(iii) The facility is in compliance with all the requirements of the CCR rule.

To demonstrate that the first two criteria above have been met, 40 C.F.R. § 257.103(f)(1)(iv)(A) requires the owner or operator to submit a work plan that contains the following elements:

- A written narrative discussing the options considered both on and off-site to obtain alternative capacity for each CCR and/or non-CCR wastestream, the technical infeasibility of obtaining alternative capacity prior to April 11, 2021, and the option selected and justification for the alternative capacity selected. The narrative must also include all of the following:
  - An in-depth analysis of the site and any site-specific conditions that led to the decision to select the alternative capacity being developed;
  - An analysis of the adverse impact to plant operations if the CCR surface impoundment in question were to no longer be available for use; and
  - A detailed explanation and justification for the amount of time being requested and how it is the fastest technically feasible time to complete the development of the alternative capacity.
- A detailed schedule of the fastest technically feasible time to complete the measures necessary for alternative capacity to be available, including a visual timeline representation. The visual timeline must clearly show all of the following:
  - How each phase and the steps within that phase interact with or are dependent on each other and the other phases;
  - All of the steps and phases that can be completed concurrently;
  - The total time needed to obtain the alternative capacity and how long each phase and step within each phase will take; and
  - At a minimum, the following phases: engineering and design, contractor selection, equipment fabrication and delivery, construction, and start up and implementation.
- A narrative discussion of the schedule and visual timeline representation, which must discuss the following:
  - Why the length of time for each phase and step is needed and a discussion of the tasks that occur during the specific step;

- Why each phase and step shown on the chart must happen in the order it is occurring;
- The tasks that occur during each of the steps within the phase; and
- Anticipated worker schedules.
- A narrative discussion of the progress the owner or operator has made to obtain alternative capacity for the CCR and/or non-CCR wastestreams. The narrative must discuss all the steps taken, starting from when the owner or operator initiated the design phase up to the steps occurring when the demonstration is being compiled. It must discuss where the facility currently is on the timeline and the efforts that are currently being undertaken to develop alternative capacity.

To demonstrate that the third criterion above has been met, 40 C.F.R. § 257.103(f)(1)(iv)(B) requires the owner or operator to submit the following information:

- A certification signed by the owner or operator that the facility is in compliance with all of the requirements of 40 C.F.R. Part 257, Subpart D;
- Visual representation of hydrogeologic information at and around the CCR unit(s) that supports the design, construction and installation of the groundwater monitoring system. This includes all of the following:
  - Map(s) of groundwater monitoring well locations in relation to the CCR unit(s);
  - Well construction diagrams and drilling logs for all groundwater monitoring wells; and
  - Maps that characterize the direction of groundwater flow accounting for seasonal variations.
- Constituent concentrations, summarized in table form, at each groundwater monitoring well monitored during each sampling event;
- A description of site hydrogeology including stratigraphic cross-sections;
- Any corrective measures assessment conducted as required at § 257.96;
- Any progress reports on corrective action remedy selection and design and the report of final remedy selection required at § 257.97(a);
- The most recent structural stability assessment required at § 257.73(d); and
- The most recent safety factor assessment required at § 257.73(e).

#### 2.0 WORKPLAN

To demonstrate that the criteria in 40 C.F.R. § 257.103(f)(1)(i) and (ii) have been met, the following is a workplan, consisting of the elements required by § 257.103(f)(1)(iv)(A). Specifically, this workplan documents that there is no alternative capacity available on or off-site for each non-CCR wastestream that IPGC plans to continue to manage in the GMF Pond and GMF Recycle Pond (collectively the GMF Ponds) at Coffeen and discusses the options considered for obtaining alternative disposal capacity. As discussed in more detail below, **IPGC has elected to install a new landfill leachate management system at Coffeen.** The workplan provides a detailed schedule for the project, including a narrative description of the schedule and an update on the progress already made toward obtaining the alternative capacity. In addition, the narrative includes an analysis of the site-specific conditions that led to the decision to install a landfill leachate management system and an analysis of the adverse impact to plant operations if Coffeen were no longer able to use the GMF Ponds.

## 2.1 No Alternative Disposal Capacity and Approach to Obtain Alternative Capacity - § 257.103(f)(1)(iv)(A)(1)

IPGC owns Coffeen, a former two-unit coal-fired facility located near Coffeen, IL that was retired from operation on November 1, 2019. Coffeen has four CCR surface impoundments (listed in Table 2-1) which were used to manage the plant's various CCR and non-CCR wastestreams. An aerial view of the Coffeen site and the CCR surface impoundments can be found on Figure 1 in Appendix A. Each impoundment has its own groundwater monitoring network. AP1 and AP2 are not included within this demonstration. The GMF Pond and GMF Recycle Pond must continue to receive CCR landfill leachate after the April 11, 2021 cease placement date.

CCR Surface Impoundment Name	Year Placed in Service	Impoundment Size (acres) / Storage Volume (acre-feet)	Lined?	Meets Location Restrictions?	Groundwater Status
GMF Gypsum Stack Pond	2010	77.3 / 1150	Yes	No	Detection Monitoring began in October 2017. SSIs have been detected for calcium in intermittent sampling events; however, successful ASDs have been completed for each such sampling event to date. The unit remains in Detection Monitoring.
GMF Recycle Pond	2010	17.1 / 470	No	No	Assessment Monitoring was initiated in May 2018. No SSLs have been identified to date and the unit remains in Assessment Monitoring.

#### Table 2-1: Coffeen CCR Surface Impoundment Summary

#### 2.1.1 CCR Wastestreams

The generating units at Coffeen have been retired and their CCR wastestreams are no longer generated.

#### 2.1.2 Non-CCR Wastestreams

The existing site water balance is included in Appendix A of this demonstration (see Figure 2).

IPGC evaluated each non-CCR wastestream placed in the GMF Pond at Coffeen. The generating units at Coffeen have been retired and decommissioning activities are underway. For the reasons discussed below in Table 2-2, each of the following non-CCR wastestreams must continue to be placed in the GMF Ponds due to lack of alternative capacity both on and off-site. The water balance diagram shows AP2 dewatering flows being routed to the GMF Ponds; however, that flow has ceased and AP2 will complete closure in October 2020. Consequently, this wastestream has not been included in the table below.

#### Table 2-2: Coffeen Non-CCR Wastestreams

Non-CCR Wastestream	Average Flow (gpm)	Description	IPGC Notes
Landfill Leachate	Unknown (Intermittent, depends on rainfall)	Landfill contact storm water flows to the Landfill Stormwater Pond to the southwest of the landfill and ultimately to Coffeen Lake via Outfall 018. Leachate discharge is not allowed to the pond nor to the lake. Leachate is collected in one of three sumps at the landfill and then pumped to the GMF Pond via a wet well submersible pump system. The landfill at Coffeen is still active and available for receiving materials during impoundment closure and/or plant decommissioning activities.	The landfill was designed and constructed with a historical permit exemption for CCR landfills in Illinois. Consequently, no leachate treatment or management systems were designed for post-closure or plant retirement conditions. Those systems must now be added to support removing this wastestream from the GMF Ponds at Coffeen.

# 2.1.3 Site-Specific Conditions Supporting Alternative Capacity Approach - § 257.103(f)(1)(iv)(A)(1)(i)

As shown on Figure 1 in Appendix A, Coffeen is equipped with several ponds and potential treatment facilities; however, none of these facilities are currently permitted to receive and discharge the remaining non-CCR wastestreams (leachate) that are still generated onsite. This landfill leachate cannot be eliminated as it is sourced from rain events. There is not an existing storage facility onsite that is either permitted to receive and discharge leachate or large enough to capture these flows to support offsite disposal. Additionally, IPGC has contacted seven publicly-owned treatment works locations within a 75-mile radius of the site to inquire about hauling leachate offsite for disposal; however, each of these locations has either been non-responsive or has responded to indicate they will not accept additional wastewater at this time.

Consequently, Coffeen must continue to use the GMF Ponds for storage of landfill leachate until the following activities can occur:

- Construct alternative storage and treatment capacity (or repurpose an existing site impoundment for this storage)
- Add an evaporation system or modify the site discharge permit to allow for the new storage facility to evaporate or discharge the non-CCR wastestreams (with or without additional treatment), thus eliminating the need for the additional storage within the GMF Ponds
- Reroute the non-CCR wastestreams to the new storage and evaporation/treatment facilities

# 2.1.4 Impact to Plant Operations if Alternative Capacity Not Obtained – § 257.103(f)(1)(iv)(A)(1)(ii)

There are no longer any plant operations at the Coffeen site beyond the current landfill management and decommissioning efforts. The GMF Ponds currently receive landfill leachate from the site landfill that must remain available throughout the decommissioning efforts prior to receiving its final cap. This leachate flow will be significantly reduced once the cap is installed but will continue indefinitely and will need to be managed throughout the post-closure care period for the landfill. As described in Sections 2.1.1 through 2.1.3 of this demonstration, in order to continue decommissioning efforts and comply with both the CCR Rule and the discharge permit conditions, Coffeen must continue to use the GMF Ponds for storage of non-CCR wastestreams until alternative disposal capacity can be developed. The flows currently routed to the GMF Ponds are sourced from stormwater which IPGC cannot cease or control with any other available systems onsite. A permit modification would be required if this flow is discharged from a current site impoundment or another storage/treatment system that must be developed.

IPGC intends to maintain storage capacity of both the GMF Pond and the GMF Recycle Pond. Neither of these ponds are permitted to discharge (except in emergency conditions). During the historical plant operations, this was sustainable based on the evaporative capacity of the plant scrubber systems. The GMF Ponds are both required to maintain adequate storage capacity over the duration of this extension without the need for discharge of the leachate flows. During rain events, these ponds have approached capacity limits within the last year.

#### 2.1.5 Options Considered Both On and Off-Site to Obtain Alternative Capacity

The options considered for alternative disposal capacity of the wastestreams currently routed to the GMF Ponds are summarized in Table 2-3. Additional details on the non-CCR wastestreams included in this demonstration request are found in Table 2-2.

Alternative Capacity Technology	Average Time (Months) <sup>1</sup>	Feasible at Coffeen?	Selected?	IPGC Notes
Conversion to dry handling	33.8	No	No	The Coffeen plant has been retired and CCR wastestreams are no longer being generated. Consequently, a dry ash handling system would not address Coffeen's capacity needs.

Alternative Capacity Technology	Average Time (Months) <sup>1</sup>	Feasible at Coffeen?	Selected?	IPGC Notes
Non-CCR wastewater basin	23.5	Yes	No	A new non-CCR wastewater basin could be constructed to receive, treat, and discharge the landfill leachate; however, the time required to design, permit, and construct this facility is expected to take longer than the selected approach.
Wastewater treatment facility	22.3	Yes	No	A new wastewater treatment facility could be constructed to receive, treat, and discharge the landfill leachate; however, the time required to design, permit, and construct this facility is expected to take longer than the selected approach.
New CCR surface impoundment	31	No	No	The Coffeen plant has been retired and CCR wastestreams are no longer being generated. Consequently, a new CCR surface impoundment would not address Coffeen's capacity needs.
Retrofit of a CCR surface impoundment	29.8	Yes	No	The Coffeen plant has been retired and CCR wastestreams are no longer being generated. Retrofit of the CCR impoundments could be performed to allow continued receipt of non-CCR wastestreams if the facility could be permitted to discharge these flows. The schedule for this effort is expected to take longer than the selected solution to manage leachate.
Multiple technology system	39.1	Yes	Yes	This is being implemented at Coffeen to include onsite storage of the leachate followed by evaporation and land application. Implementing this system is expected to take another 14 months (until December 2021). This approach will not require the addition of a new site outfall (and the associated anti-degradation study and permit modification efforts) to discharge leachate.
Temporary treatment system	Not defined	No	No	Temporary (frac tank) storage is being implemented as part of the selected approach; however, IPGC is not aware of any offsite alternatives for disposal or temporary evaporation of the leachate. IPGC has chosen to focus on implementing the necessary measures for the selected technologies described above rather than try to develop temporary solutions for treatment of the remaining non-CCR wastestreams.

<sup>1</sup>From Table 3. See 85 Fed. Reg. at 53,534.

#### 2.1.6 Approach to Obtain Alternative Capacity

In order to initiate closure of the GMF Ponds, either the Coffeen discharge permit must be modified by Illinois EPA to allow for treatment and discharge of the landfill leachate, or a separate storage and evaporation system must be installed to manage this non-CCR wastestream. Modifications to the discharge permit to use other settling ponds onsite is not the preferred method based on concerns with any future discharge limits that may become applicable to leachate as a result of the Fifth Circuit Court's decision in April 2019 (*Southwestern Electric Power Company v. EPA*, 920 F.3d 999, 1018 n.20 (5th Cir. 2019)). In December 2019, IPGC began developing a request for proposal and selected Hanson Professional Services to provide an analysis of the following leachate alternatives, including site plans, process flow diagrams, and capital and O&M cost estimates.

System	Technology	Practicability or Feasibility for Coffeen
Leachate	Onsite storage with recycling of leachate by land application to the landfill (for dust control during dry periods)	Feasible
Leachate	Onsite storage with offsite disposal	Not practical; there are a lack of offsite disposal locations that will accept the leachate within a reasonable distance from the plant location
Leachate	Onsite storage with thermal evaporation	Feasible
Leachate	Onsite storage with chemical precipitation/reverse osmosis	Not practical; Reverse osmosis reject water quality will likely require an evaporation system and this option likely extends the compliance schedule compared to the other feasible alternatives since modifications to the site discharge permit and associated anti-degradation studies would be required to discharge the treated wastewater as part of this approach

#### Table 2-4: Alternatives Considered for Non-CCR wastestreams

Hanson prepared a report detailing their analysis which was provided to IPGC in July 2020. IPGC believes the hybrid approach is the best solution. This preferred solution will require:

- Improvements to the leachate pumping system, including replacing existing sump pumps and installing flow monitoring equipment to establish the evaporation system design basis
- A propane-powered forced thermal evaporator (container-based system for 40 gallons per hour)

- A 1,000-gallon propane tank
- Four frac tanks with an approximate total storage volume of 20,000 gallons
- A package booster pump located in an insulated enclosure adjacent to the tanks
- Foundations for the new tanks and booster pumps
- Power feed to the new evaporator and pump systems (from local distribution system)
- A grid with multiple large bore impact or similar sprinklers zoned to dose the landfill for dust control and prevent runoff (preliminary design basis indicated approximately 40 gpm per sprinkler, 120 gpm per zone, 10 zones to cycle through)
- Over 2,000 linear feet (estimated) of piping from the tanks and booster pumps to the sprinkler system

## 2.1.7 Technical Infeasibility of Obtaining Alternative Capacity prior to April 11, 2021

IPGC began developing a request for proposal and selected Hanson Professional Services to provide an analysis of the following leachate alternatives, including site plans, process flow diagrams, and capital and O&M cost estimates in December 2019. Hanson prepared a report detailing their analysis which was provided to IPGC in July 2020 and IPGC evaluated the solutions and selected a preferred hybrid approach that consists of onsite storage for land application at the landfill as well as a thermal evaporation system. This work is expected to be completed in late 2021 as described in Sections 2.2 and 2.3. Consequently, it is not possible to implement the measures discussed above by April 11, 2021.

# 2.1.8 Justification for Time Needed to Complete Development of Alternative Capacity Approach – § 257.103(f)(1)(iv)(A)(1)(iii)

The schedule for developing alternative disposal capacity is described in more detail in Sections 2.2 and 2.3. The expected milestones for progress are summarized in Table 2-52-5 below, which summarizes the phasing required to complete the project. IPGC believes this represents the fastest technically feasible timeframe for compliance at Coffeen, and recognizes this timeframe is completed faster than the estimated average time identified by EPA to implement a multiple technology system (see Table 2-3).

Year or Progress Reporting Period	Status	Milestone Description	IPGC Notes
2020	Completed	Selection of leachate solution, procurement of pumps and flow meters.	
2020	On Schedule	Install new forwarding pumps and flow meters, prepare specifications and issue bids for leachate management equipment.	Detailed design for pumps, evaporator, and BOP systems and initiation of permitting activities.
April 30, 2021	Scheduled	Award equipment contracts, submit permit applications, and initiate detailed design.	
October 31, 2021	Scheduled	Award construction contracts and initiate construction for foundations, set equipment/tanks/pumps, and near completion of electrical and mechanical piping installation.	Startup and punch list items will be completed within one month of this progress report, projected to cease by December 1, 2021.

#### 2.2 Detailed Schedule to Obtain Alternative Disposal Capacity -

#### § 257.103(f)(1)(iv)(A)(2)

The required visual timeline representation of the schedule is included in Appendix B of this demonstration and described further in Section 2.3 below.

#### 2.3 Narrative of Schedule and Visual Timeline - § 257.103(f)(1)(iv)(A)(3)

The third section for the workplan is a "detailed narrative of the schedule and the timeline discussing all the necessary phases and steps in the workplan, in addition to the overall timeframe that will be required to obtain capacity and cease receipt of waste." 85 Fed. Reg. at 53,544. As EPA explained in the preamble to the Part A rule, this section of the workplan must discuss "why the length of time for each phase and step is needed, including a discussion of the tasks that occur during the specific stage of obtaining alternative capacity. It must also discuss the tasks that occur during each of the steps within the phase." 85 Fed. Reg. at 53,544. In addition, the schedule should "explain why each phase and step shown on the chart must happen in the order it is occurring and include a justification for the overall length of the phase" and the "anticipated worker schedule." 85 Fed. Reg. at 53,544. EPA notes the overall "discussion of the schedule assists EPA in understanding why the time requested is accurate." 85 Fed. Reg. at 53,544.

Initial Design and Equipment Procurement: IPGC has initiated the improvements to the existing landfill leachate management system to include new leachate pumps, controls (as needed) and flow meters. IPGC has awarded a contract to procure new pumps to forward leachate from the existing leachate collection sumps to the new leachate management system. Once the new leachate pumps are operable, leachate flow rates will be monitored to provide a basis of design for the leachate management system discussed in Section 2.1.6. These pumps, and their associated flow monitoring equipment, will be installed to replace the existing forwarding pumps to route water from the landfill collection sumps to the GMF Ponds once they arrive onsite and while the remainder of the leachate system is being procured and constructed. The projected lead time is 6 weeks for this equipment. Once installed, the flow monitoring equipment will provide a better estimate of the leachate production at the site. Leachate flow data will be recorded throughout the first month of operation so the data may be included in the new system design specifications.

IPGC will award a contract for engineering to design the leachate management system. The design will be used for the procurement and permitting activities necessary for the project. IPGC will procure the storage tanks, new evaporation system, and pumps required to forward water from the tanks to the evaporator or to the landfill sprinkler system. The equipment specifications will be prepared concurrently (and finishing one week after) the flow monitoring period to confirm the design basis. The equipment will be bid out over a three-week period and will be awarded within one month of receiving bids. Based on Burns & McDonnell experience on similar projects, leachate management system equipment including the tanks, evaporators, and pumps are expected to have lead times of 4 to 6 months from contract award to delivery. Consequently, the equipment should be onsite in August of 2021 and will be installed as shown in the schedule in Appendix B.

<u>Permitting Activities:</u> Once the initial submittals are received from the equipment suppliers, IPGC's engineer will prepare the required permit applications. The design submittals should be received within one month of contract award, allowing for completion of the preliminary design and submittal of the necessary permit applications at this time. Table 2-6 provides a list of the anticipated permits required for the leachate management system at Coffeen. As shown in Appendix B, these permits will be acquired concurrently with the fabrication and delivery of the equipment, such that the construction can begin as soon as possible following receipt of these items.

	Permits Needed for Construction of Leachate Management System	Time to Develop Permit Application	Anticipated Time to Receive Permit							
1.	Wastewater Treatment Construction Permit for new system (includes evaporator, tanks, pumps, etc.). Required by Subpart B to 35 IAC 309.									
2.	Land Disturbance Permit (three submittals and approvals are required from three different agencies).									
	<ul> <li>a. IEPA Notice of Intent (NOI) to Disturb &gt; 1 acre</li> <li>i. Need to submit Stormwater Plan</li> <li>b. Illinois Historic Preservation Request/Approval</li> <li>c. IDNR Threatened and Endangered Species Request/Approval</li> </ul>	3 Months	5 Months for All							
3.	New Emission Source Air Permit as required by 35 IAC 201.	1 Month	3 Months							
Total Time for Permitting (assuming Concurrent Activities):										

Detailed Design and Construction Procurement: As stated previously, the equipment design submittals should be received within one month of contract award, allowing for the start of the detailed design for the foundations and power supply systems. This detailed design will be completed approximately three months after receipt of the equipment submittals based on typical preparation and review time for the technical documents and includes IPGC development of the construction contract will be bid and awarded. IPGC has assumed the bid period will be four weeks long and that it will take two weeks to evaluate bids and select the preferred contractor and another six weeks to negotiate the commercial terms for the soft award of the contract. This bid and award phase will be performed concurrently with acquiring the necessary permits for this project and the equipment delivery phase.

<u>Leachate System Construction Activities:</u> The durations shown on the project schedule are estimates by Burns & McDonnell and are based on an average work schedule of five days per week and ten hours per day, are subject to delays from periods with significant rain events, and are based on the following scope of work which must be performed in the sequence listed below:

Contractor will order necessary materials and mobilize to the site upon award of the contract. The lead time for the piping materials are shown on the Appendix B schedule and are based on Burns & McDonnell estimates for this scope of work. The permits listed in Table 2-6 will be received prior to mobilization.

- Contractor will construct the HDPE piping for the landfill sprinkler system. These lines are each approximately 2,400 feet in length and will require fusion of the piping, trenching, and backfill operations. This work is anticipated to require 6-8 weeks of effort. It can be completed prior to having the tank and pumps in place and available, but not until the initial deliveries of pipe material are completed. This work is anticipated to begin upon mobilization and cannot finish until at least two weeks after the final delivery of pipe material is completed.
- Contractor will construct the foundation for the new tanks and pump skid. This can be completed once the contractor is onsite and the necessary materials have been received. Four weeks were allotted for preparing subgrade, formwork, rebar, pouring this foundation, and concrete curing. Burns & McDonnell has assumed that deep foundations and piling will not be required for this equipment.
- Contractor will erect the tanks once the foundations are complete. Burns & McDonnell has included 5 days to set the tanks in place on the new foundations.
- Contractor will set the evaporator and pump skid(s) following (1) construction of the foundation and (2) delivery of the equipment. The pump skids will be installed after the tank erection is completed due to exclusion zone requirements for safe construction. These will be set in place and final piping tie-ins completed after the equipment is installed.
- Contractor will install raceway and cable for the evaporator and new pump power feeds. These activities are based on a four-week duration. They will begin once the first equipment is set in place (evaporator) and cannot be completed until after the final equipment is set in place (assumed to be the pumps installed after the tanks are in place).
- Once the tanks, evaporator, pumps, piping, and power systems are installed, the Contractor can start up the new system and divert the non-CCR wastestreams away from the GMF Ponds. At this time, IPGC can initiate closure of these impoundments. IPGC has assumed two weeks will be required for startup/checkout and an additional two weeks to close out any punchlist items or issues with the new equipment.

#### 2.4 Progress Towards Obtaining Alternative Capacity - § 257.103(f)(1)(iv)(A)(4)

In the preamble to the final Part A rule, EPA explains that this "section [of the workplan] must discuss all of the steps taken, starting from when the owner or operator initiated the design phase all the way up to the current steps occurring while the workplan is being drafted." 85 Fed. Reg. at 53,544. The discussion also "must indicate where the facility currently is on the timeline and the processes that are currently being undertaken at the facility to develop alternative capacity." 85 Fed. Reg. at 53,545.

As shown in Appendix B and described in Section 2.1.6, IPGC has already undertaken planning and implementation steps towards providing additional storage and treatment capacity to remove non-CCR flows from the Coffeen CCR surface impoundments, specifically the GMF Ponds. IPGC has evaluated and selected the preferred solution. IPGC has also procured the new pumps and metering equipment necessary to forward leachate from the landfill to the eventual leachate management system and perform flow monitoring to confirm the design basis for the new evaporation and land application system. The pumps are being fabricated and will be installed later this fall, which will allow for flow measurement and continuation of the preliminary design and permitting support activities.

#### 3.0 DOCUMENTATON AND CERTIFICATION OF COMPLIANCE

To demonstrate that the criteria in 40 C.F.R. § 257.103(f)(1)(iii) has been met, the following information and submissions are submitted pursuant to 40 C.F.R. § 257.103(f)(1)(iv)(B) to demonstrate that the GMF Ponds at Coffeen are in compliance with the CCR rule.

#### 3.1 Owner's Certification of Compliance - § 257.103(f)(1)(iv)(B)(1)

In accordance with 40 C.F.R. § 257.103(f)(1)(iv)(B)(1), I hereby certify that, based on my inquiry of those persons who are immediately responsible for compliance with environmental regulations for the GMF Pond and the GMF Recycle Pond at Coffeen, the facilities are in compliance with all of the requirements contained in 40 C.F.R. Part 257, Subpart D – Standards for the Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments. Coffeen's CCR compliance website is up-to-date and contains all the necessary documentation and notification postings.

#### ILLINOIS POWER GENERATING COMPANY

inthin E cody

Cynthia Vodopivec VP – Environmental Health & Safety September 28, 2020

#### 3.2 Visual Representation of Hydrogeologic Information -§ 257.103(f)(1)(iv)(B)(2)

Consistent with the requirements of § 257.103(f)(1)(iv)(B)(2)(i) - (iii), IPGC has attached the following items to this demonstration:

- Map(s) of groundwater monitoring well locations in relation to the CCR unit (Appendix C1)
- Well construction diagrams and drilling logs for all groundwater monitoring wells (Appendix C2)
- Maps that characterize the direction of groundwater flow accounting for seasonal variations (Appendix C3)

#### 3.3 Groundwater Monitoring Results - § 257.103(f)(1)(iv)(B)(3)

Tables summarizing constituent concentrations at each groundwater monitoring well through the first 2020 semi-annual monitoring period are included as Appendix C4.

#### 3.4 Description of Site Hydrogeology - § 257.103(f)(1)(iv)(B)(4)

A description of site hydrogeology and stratigraphic cross-sections of the site are included as Appendix C5.

#### 3.5 Corrective Measures Assessment - § 257.103(f)(1)(iv)(B)(5)

For the GMF Pond, detection monitoring has indicated statistically significant increases (SSIs) above the background concentrations; however, IPGC has completed successful alternate source demonstrations and the facility remains in detection monitoring. Accordingly, an assessment of corrective measures is not required for the GMF Pond.

For the GMF Recycle Pond, the first assessment monitoring samples were collected in May 2018. The results, through the first 2020 semi-annual monitoring period, indicate there have been no SSLs for any Appendix IV constituents, and the facility remains in assessment monitoring. Accordingly, an assessment of corrective measures is not required for the GMF Recycle Pond.

IPGC will continue to conduct groundwater monitoring in accordance with all state and federal requirements.

#### 3.6 Remedy Selection Progress Report - § 257.103(f)(1)(iv)(B)(6)

As noted above, assessments of corrective measures and the resulting remedy selection efforts are not currently required for the GMF Ponds.

#### 3.7 Structural Stability Assessment - § 257.103(f)(1)(iv)(B)(7)

Pursuant to § 257.73(d), the initial structural stability assessments for the GMF Pond and GMF Recycle Pond were prepared in October 2016 and are included as Appendix C6. As required for compliance, additional stability assessments will be completed in October 2021.

#### 3.8 Safety Factor Assessment - § 257.103(f)(1)(iv)(B)(8)

Pursuant to § 257.73(e), the initial safety factor assessments for the GMF Pond and GMF Recycle Pond were prepared in October 2016 and are included as Appendix C7. As required for compliance, additional safety factor assessments will be completed in October 2021.


3-2


#### 4.0 CONCLUSION

Based upon the information submitted in this demonstration, it has been shown that the GMF Ponds at Coffeen qualify for the site-specific alternative deadline for the initiation of closure as allowed by 40 C.F.R. 257.103(f)(1).

Therefore, IPGC requests that EPA approve the demonstration and grant an alternative deadline of December 1, 2021 to cease routing all remaining non-CCR flows to the GMF Ponds at Coffeen and initiate closure as required under 40 C.F.R. § 257.101(a) or (b)(1). IPGC will update EPA on the project and any potential schedule impacts as part of the semi-annual progress reports required at 40 C.F.R. § 257.103(f)(1)(x), and if a need for a later compliance deadline is determined, IPGC will seek additional time as described in 40 C.F.R. § 257.103(f)(1)(vii).

APPENDIX A – SITE PLAN AND WATER BALANCE DIAGRAM






s: 1	Flows shown a	s: Average [Ma	iximum]					
2	Flow units = M		-					
3	1/1/2010 throu	ugh 11/30/201	ws from Coffeen Total Flow Reports 1 and 1/1/2015 through 6/30/2015.					
4	through 8/5/202	15	grator and pump capacity data 1/1/2008					
5	8/5/2015		tor and pump capacity data 1/1/2008 through					
6	Appllication Wa	ter Balance, upo	Idicated is the Coffeen NPDES Permit lated July 27, 2012.					
7			iler wash water have been added. Boiler cycle pump discharge water and collected in					
8			erflow to East Fork Shoal Creek, Clarfier WTS "Proof Tank" have been added.					
9		mineralizer Rege	tenance Building (Tractor Shed) STP, Raw water en Waste (B01), and Fuel Unloading Oil/Water					
10	"A" includes one Wastewaters: Precipitator Clea Economizer Clean Air Heater Clean Boiler Waterside Condenser Tube Misc. Non-Chem	aning aning e Cleaning e Cleaning	following Non-Chemical Metal Cleaning					
11	"B" includes one Wastewaters: Boiler Tube Clea Condenser Tube Misc. Chemical I	ning Cleaning	following Chemical Metal Cleaning					
12	FGD	Coal Combustio Flue Gas Desulfi Oil Water Separ Ultrasonic Resir Reverse Osmosi Gypsum Mana Storm Water F	urization ator I Cleaner S gement Facility					
er:			Engineer:					
Dγ	NEG	Y Y	Sargent & Lundy					
		Dyn	egy					
Effl	Effluent Limitation Guidelines Compliance Planning Study Preliminary Water Balance - Coffeen							
		MSK-CO	F-WB-001					


**APPENDIX B – SCHEDULE** 


ID	Task Name	Duration	Start	Finish	D	j	Half 1, 2 F M	020 A M	J I	Hal A S	f 2, 2020 O N	J J
1	CCR Compliance Efforts	1729 days	Fri 4/17/15	Wed 12/1/21		•			<u> </u>			
2	Final CCR Rule Published in Federal Register	0 days	Fri 4/17/15	Fri 4/17/15								
3	Background Groundwater Sampling	434 days	Wed 11/18/15	Mon 7/17/17								
4	Hanson/AECOM Completed Liner Documentation	0 days	Thu 10/13/16	Thu 10/13/16	-							
5	AECOM Prepared Surface Impoundment History of Construction	0 days	Mon 10/17/16	Mon 10/17/16								
6	First Detection Monitoring Samples	9 days	Wed 10/25/17	Sat 11/4/17								
7	Recycle Pond Assessment Monitoring Program - First Round	15 days	Fri 5/11/18	Thu 5/31/18								
8	Recycle Pond Assessment Monitoring Program - Second Round	6 days	Fri 8/3/18	Fri 8/10/18								
9	H&A completed Location Restriction Demonstrations	0 days	Tue 10/16/18	Tue 10/16/18								
10	Recycle Pond Assessment Monitoring Program - Third Round	3 days	Mon 1/21/19	Wed 1/23/19								
11	Recycle Pond Assessment Monitoring Program - Fourth Round	8 days	Thu 8/15/19	Mon 8/26/19								
12	EPA Released CCR Holistic Approach to Closure Part A Rule	0 days	Mon 12/2/19	Mon 12/2/19	12/2							
13	Semi-Annual Progress Report #1	0 days	Fri 4/30/21	Fri 4/30/21								
14	Semi-Annual Progress Report #2	0 days	Sun 10/31/21	Sun 10/31/21								
15	Cease leachate flow to GMF Ponds	0 days	Wed 12/1/21	Wed 12/1/21								
16	Leachate Management - Engineering/Permitting/Procurement	423 days	Mon 1/6/20	Wed 8/18/21								
17	Bid and Award Engineering Services for Alternatives Assessment	60 days	Mon 1/6/20	Fri 3/27/20								
18	Hanson Performed Alternatives Analysis for Leachate	68 days	Mon 3/30/20	Wed 7/1/20					ſ			
19	IPGC Reviewed/Selected Preferred Alternative	10 days	Thu 7/2/20	Wed 7/15/20								
20	Spec/Bid/Award Leachate Pumps	40 days	Thu 7/16/20	Wed 9/9/20						۲ ا		
21	Pump Fabrication/Delivery	30 days	Thu 9/10/20	Wed 10/21/20								
22	Pumps Installed by IPGC Contractors	5 days	Thu 10/22/20	Wed 10/28/20								
23	Flow Monitoring to establish Evaporation System Design Basis	20 days	Thu 10/29/20	Wed 11/25/20								
24	Preliminary Design: Leachate Management System	80 days	Thu 10/29/20	Wed 2/17/21							· •	
25	Spec/Bid/Award Evaporator, Tank, and Pumps	60 days	Thu 10/29/20	Wed 1/20/21								
26	Fabricate/Deliver Equipment	140 days	Thu 1/21/21	Wed 8/4/21								
27	Permitting (Wastewater Treatment Construction Permit, Land Disturbance Permits, Air Permit)	130 days	Thu 2/18/21	Wed 8/18/21								
28	Detailed Design: Leachate Management System	60 days	Thu 2/18/21	Wed 5/12/21								
29		60 days	Thu 5/13/21	Wed 8/4/21	-							
30	Leachate Management System Construction	85 days	Thu 8/5/21	Wed 12/1/21								
31	Pipe Material and Sprinkler System Acquisition (by Contractor)	30 days	Thu 8/5/21	Wed 9/15/21								
32	Contractor Mobilization to Site	15 days	Thu 8/5/21	Wed 8/25/21								
33	Install piping from tank location to landfill sprinklers	40 days	Thu 8/26/21	Wed 10/20/21								
34	Construct Foundations for Tank/Pumps	20 days	Thu 8/26/21	Wed 9/22/21								
35	Erect Tank	5 days	Thu 9/23/21	Wed 9/29/21								
36	Set Evaporator, propane tank, sprinklers, and ancillary equipmen	10 days	Thu 9/23/21	Wed 10/6/21								
37	Set Pumps	10 days	Thu 9/30/21	Wed 10/13/21	-							
38	Provide Electrical Supply and finish piping tie ins	20 days	Thu 10/7/21	Wed 11/3/21								
39	Startup new Systems	10 days	Thu 11/4/21	Wed 11/17/21	-							
40	Punchlist and Contract Closeout	10 days	Thu 11/18/21	Wed 12/1/21								
	Task		Project	Summary			Inactive N	lilestone	\$		 Manual Summary R	ollup
Project	: Coffeen CCR Surface Impoundment		Externa			u	Inactive Su				Manual Summary N	
Data	Extension Demonstration	▲		l Milestone	<u></u>		Manual Ta	-			Start-only	
Date:		·			~						•	
	Summary		Inactive	lask			Duration-o	only			Finish-only	3



**APPENDIX C – COMPLIANCE DOCUMENTS** 

**APPENDIX C1 – MAP OF GROUNDWATER MONITORING WELL LOCATIONS** 






APPENDIX C2 – WELL CONSTRUCTION DIAGRAMS AND DRILLING LOGS

			BOR					CONTRACTOR. Testing Service Com						ANSON			
CLIENT: AEG Coffeen Power Station       CONTRACTOR: Testing Service Corp.         Site: CCB Management Facility       Rig mfg/model: CME-650 Track Drill         Location: Coffeen, Illinois       Drilling Method: 3¼" HSA w/SS & CME samplers											<b>D:</b> G200						
WE	DATES	S: St Fin	S3004A art: 2/2: iish: 2/2: vercast, c	5/20 5/20			FIELD STAFF: Driller: B. Williamson Helper: R. Keedy Eng/Geo: .						Completio	<ul> <li>v: 624.20 ft. MSL</li> <li>n: 18.00 ft. BGS</li> <li>n: 877,930.59N</li> <li>2,515,649.96E</li> </ul>			
S	AMPL	E	Т	EST	INC	3	TOPOGR	APHIC MAP INFORMATION:	WATE	R LF	EV	EL	INFORMA	TION:			
	l (in)				(H <sup>3</sup> )	(tsf)	Quadr	angle: Coffeen, IL	Ţ	<b>ATER LEVEL INFORMATION:</b> $\mathbf{\Psi} = 13.50$ - While drilling							
	Number Recov / Total (in) % Recovery Type Blows / 6 in N - Value RQD Moisture (%) Dry Den. (lb/ft <sup>3</sup> ) Qu (tsf) <i>Qp</i> (tsf) Failure Type				r (lb/	Qp (Jype		hip: East Fork 1 2, Tier 7N; Range 3W	¥ ∑		2.7:	5 - 3	3/12/08				
Number					Dry Den	Qu (tsf) Failure 7	Depth ft. BGS	Lithologic Description		Borehole Elevation Detail ft. MSL Remarks							
	24/24 100%	ss	3-2 3-3					Very dark grayish brown (10YR3/2), moist, firm, friable clayey SILT	e, 7			<u>, 1/</u> 1/ . <u>1/</u> 1/ .1/	624				
1A 2A	19/24	ss	N=5 3-3 6-6	31 26		1.36 B 1.94 BSh	2	Dark gray (10YR4/1) with 5% yellowish brown (10YR5, mottles, moist, firm, silty CLAY	/6)				622				
2B	79%	A 33	0-0 N=9	26		2.33	4	Dark gray (10YR4/1) with 70% yellowish brown (10YR5/8) mottles, moist, firm, silty CLAY									
3A	19/24 79%	ss	3-3 4-5	26		Sh 1.59		Dark gray (10YR4/1) with 70% yellowish brown (10YR5/8) mottles, moist, firm, silty CLAY, slight trace sand	{				620				
3B	/ 9 / 0		N=7	23		B 1.55 B	6	Very dark gray (10YR3/1), moist, firm, silty CLAY, slig trace sand	sht 				618				
4A	22/24 92%	ss	5-5 5-5 N=10	29		0.31 B		Dark gray (10YR4/1) with 10% yellowish brown (10YR5/8) mottles, moist, firm, silty CLAY, trace coars sand	se								
5A	20/24 83%	ss	2-2 3-5 N=5	25		1.09 B	8	Dark gray (10YR4/1) with 10% yellowish brown					616				
6A	22/24 92%	ss	<i>1-3</i> <i>2-3</i> N=5	22		1.01	10	(10YR578) mottles, moist, firm, silty CLAY, sand and slight trace gravel					614				
7.	24/24 100%	ss	3-3 5-6 N=8	1.5		0.50		Yellowish brown (10YR5/8), moist, soft, sandy CLAY									
7A 7B 8A				15 18 24		0.50 B 0.27 B	14	Gray (10YR5/1), wet, soft, fine- to coarse-grained SANI Gray (10YR5/1), wet, soft, silty CLAY, trace sand and gravel					610				
8B 9A	19/24 79%	ss	0-3 5-8 N=8 8-15	17 13			16	Yellowish brown (10YR5/4), wet, soft, fine- to coarse-grained SAND, trace gravel					608				
0.0	24/24 100%	ss	30-50 N=45					Gray (10YR5/1), moist, hard, silty CLAY, trace sand an gravel	nd								
9B       8						I	18 -	End of Boring = 18.0 ft. BGS	£	///24	~~~	<u>.///</u>	<u>1</u>				
NO	)TE(S):													Page 1 of 1			

1	CLIEN Sit Location Projec DATE	F: Al e: Co n: Co et: 05 S: St Fin	BOR EG Coffe CB Mana offeen, III 5S3004A tart: 10/ nish: 10/ unny, war	en Po gem linois 14/20 14/2	ower ent F s 010 010	Station Facility	n	CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill Drilling Method: 4 <sup>1</sup> /4" HSA w/SS samplers FIELD STAFF: Driller: D. Mahurin Helper: J. Litsch/D. Smail Eng/Geo: .	Event         Event <th< th=""><th>SL GS N</th></th<>	SL GS N
S	SAMPL	E	Т	EST	INC		TOPOGR	APHIC MAP INFORMATION:	WATER LEVEL INFORMATION:	
er	Recov / Total (in) % Recovery		<i>Blows / 6 in</i> N - Value <b>RQD</b>	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Quadra Townsl Section	angle: Coffeen, IL hip: East Fork 11, Tier 7N; Range 3W	$\Psi$ = 22.00 - While drilling $\Psi$ = 21.54 - Upon completion $\overline{\Psi}$ =	
Number	Recov % Rec	Type	Blows N - Vi <b>RQD</b>	Moist	Dry D	Qu (ts Failur	Depth ft. BGS	Lithologic Description	Borehole Elevation Detail ft. MSL Remarks	
1A	12/24 50%	ss	2-2 3-2 N=5	18			2	FILL - Grayish brown (10YR5/2), moist, firm, silty CLA with trace sand and gravel.	AY	
2A	20/24 83%	ss	2-2 3-5 N=5	16						
3A	20/24 83%	ss	4-9 6-8 N=15	19			4 4 6	FILL - Dark gray (10YR4/1) with 30% dark yellowish brown (10YR4/6) mottles, moist, firm, silty CLAY with trace sand and gravel.	h th	
4A	19/24 79%	ss	2-4 5-6 N=9	20					624	
5A	17/24 71%	ss	2-3 4-5 N=7	30				Very dark gray (10YR3/1) with 20% dark yellowish brow (10YR4/6) mottles, moist, firm, silty CLAY with trace <u>sand, trace roots.</u> Dark grayish brown (10YR4/2) with 35% dark yellowis brown (10YR4/6) mottles, moist, firm, silty CLAY with trace sand.	e ish - 622	
6A	22/24 92%	ss	2-3 4-6 N=7	19				Gray (10YR5/1) with 20% dark yellowish brown (10YR4/6) mottles, moist, firm, clayey SILT with trace sand and gravel.	2e	
7A	23/24 96%	ss	1-2 3-4 N=5	23				Gray (10YR5/1) with 15% dark yellowish brown (10YR4/6) mottles, moist, firm, silty CLAY with trace sa and gravel.	and 618	
8A	22/24 92%	ss	<i>1-1</i> <i>3-3</i> N=4	22				Gray (10YR5/1) with 15% dark yellowish brown (10YR4/6) mottles, moist, soft, silty CLAY with trace sa and gravel.	and 616	
9A	24/24 100%	ss	1-1 2-2 N=3	21				Dark yellowish brown (10YR4/6) with 30% gray (10YR5/1) mottles, moist, soft, silty CLAY with trace sa and gravel. Gray (10YR5/1) with 15% dark yellowish brown (10YR4/6) mottles, moist, soft, silty CLAY with trace sa and gravel.	'	
10A	24/24 100%	ss	woh-wol 1-5	25				Gray (10YR5/1) with 15% dark yellowish brown (10YR4/6) mottles, moist, very soft, silty CLAY with tra <u>sand and gravel.</u> Gray (10YR5/1), moist, very soft, very fine- to fine-grain sandy CLAY with trace gravel.	612	
NC	) )TE(S):	G20	 6 installe	 d in∃	 bore	 hole.	20 I	Gray (10YR5/1), moist, firm, very fine- to fine-grained	d	



F	ELI		BOR	IN	JG	G L(	OG				ANSON
	Site	e: C	EG Coffe CB Mana	ıgem	ent F		1	CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill	BO	REHOLE II	<b>D:</b> G209
]			offeen, Ill 5S3004A		5			<b>Drilling Method:</b> 4 <sup>1</sup> / <sub>4</sub> " HSA w/SS samplers			D: G209 v: 630.57 ft. MSL
WE		Fir	tart: 10/ nish: 10/	7/20	10			FIELD STAFF: Driller: D. Mahurin Helper: J. Litsch/D. Smail Eng/Geo: .			n: 24.00 ft. BGS n: 875,298.23N 2,515,149.56E
	SAMPL		inny, coo		SUS)		TOPOCD	0		NEODIA	
	(in)				ft <sup>3</sup> )	tsf)		APHIC MAP INFORMATION: ngle: Coffeen, IL	WATER LEVEL $\underline{\Psi} = Dry -$	While drilling	
	Total 'ery		5 in Ie	(%) 0	(lb/	Qp (		ip: East Fork 11, Tier 7N; Range 3W	$\underline{\Psi} = 22.40 - $ $\overline{\nabla} =$	Upon comple	etion
Number	Recov / Total (in) % Recovery	Type	Blows / 6 in N - Value RQD	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Depth ft. BGS	Lithologic Description	Borehole Detail	Elevation ft. MSL	Remarks
~	24/24	Ī	4-4	2						630	
1A	100%	ss	4-6 N=8	21							
							2				
	24/24 100%	ss	3-4 6-6 N=10							628	
2A			N-10	13			4-	FILL - Brown (10YR5/3) with 10% gray (10YR5/1) ar 5% dark yellowish brown (10YR4/6) mottles, moist, firn silty CLAY with trace sand and gravel.	ıd n,		
3A	24/24	$\int$	2-3	19				sity CLAT with trace sand and graver.		626	
JA	100%	ss	6-8 N=9	19							
							6				
4A	22/24 92%	ss	2-3 6-8	17						624	
			N=9				8	Grayish brown (10YR5/2), moist, firm, clayey SILT wit trace sand and gravel.	th		
5A	18/24	$\int$	2-3	20						622	
Л	75%	ss	3-5 N=6	20							
							10	Dark gray (10YR4/1) with 15% dark yellowish brown (10YR4/6) mottles, moist, firm, silty CLAY with trace sand.			
	24/24 100%	ss	1-2 2-5 N=4					Sand.		620	
6A			11-4	26			12				
7A	22/24	$\langle$	1-3	22				Dark gray (10YR4/1) with 25% dark yellowish brown		618	
	92%	ss	4-4 N=7				14	(10YR4/6) mottles, moist, firm, silty CLAY with trace sand.			
							14				
	24/24 100%	ss	woh-1 2-3 N=3							616	
8A				25			16				
9A	19/24	$\mathbb{N}$	woh-1	24				Gray (10YR5/1) with 15% dark yellowish brown		614	
	79%	ss	2-3 N=3	24 				(10YR4/6) mottles, moist, soft, silty ČLAY with trace sa and gravel.	nd		
										612	
10A	14/24 58%	ss	woh-2 3-3 N=5	20							
							20				
NO	OTE(S):	G20	9 installe	d in	borel	nole.					Page 1 of 2

Page 1 of 2

F	[EL]	DI	BOR	I	NG	G L(	OG		<b>HANSON</b>					
	CLIEN	Г: А	EG Coffe	en P	ower	Station	n	CONTRACTOR: Layne-Western Co						
	Sit	e: C	CB Mana	ıgem	ent F	acility		Rig mfg/model: CME-750 ATV Drill	BOREHOLE ID: G209					
]	Locatio	n: C	offeen, Ill	inois	5			Drilling Method: 4 <sup>1</sup> / <sub>4</sub> " HSA w/SS samplers	<b>Well ID:</b> G209					
	Projec	t: 05	5S3004A						Surface Elev: 630.57 ft. MSL					
	DATES	5: St	t <b>art:</b> 10/	7/20	10			FIELD STAFF: Driller: D. Mahurin	<b>Completion:</b> 24.00 ft. BGS					
		Fir	nish: 10/	7/20	10			Helper: J. Litsch/D. Smail	Station: 875,298.23N					
WE	ATHE	R: Su	inny, coo	l (lo-	-50's)	)		Eng/Geo: .	2,515,149.56E					
S	SAMPLE       TESTING       TOPOGRAPHIC MAP INFORMATION:       WATER LEVEL INFORMATION: $\widehat{\underline{\exists}}$ $\widehat{\underline{\uparrow}}$ $\widehat{\underline{\uparrow}}$ $\widehat{\underline{\frown}}$ $\widehat{\underline{\frown}$													
er	Recov / Total (in) % Recovery		s / 6 in alue	Moisture (%)	Den. (lb/ft <sup>3</sup> )	f) $Qp$ (tsf) e Type	Quadra Townsl							
Number	Recov % Rec	Type	Blows N - Va RQD	Moistı	Dry D	Qu (tsf) Failure 7	Depth ft. BGS	Lithologic Description	Borehole Elevation Detail ft. MSL Remarks					
11A	1/24 <i>4%</i>	ss	woh-1 1-1 N=2	21				Gray (10YR5/1) with 15% dark yellowish brown (10YR4/6) mottles, moist, soft, silty CLAY with trace s and gravel. [Continued from previous page]	sand					
12A	20/24 83%	ss	9-16 17-26 N=33	7			¥ <sup>22</sup> <u>↓</u>	Dark gray (10YR4/1), slightly moist, hard, very silt CLAY with sand and gravel.	y 608					
			-					End of Boring = 24.0 ft. BGS						

]	CLIENT Sit Location Projec DATES	F: A e: C n: C t: 05 S: St Fir	BOR EG Coffe CB Mana offeen, III 5S3004A tart: 10/ hish: 10/ unny, war	en P Igem inois 11/2 11/2	ower ent F s 010 010	Station Facility		CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill Drilling Method: 4 <sup>1</sup> / <sub>4</sub> " HSA w/SS samplers FIELD STAFF: Driller: D. Mahurin Helper: J. Litsch/D. Smail Eng/Geo:		BOREHOLE Well Surface El Completi	HANSON D: G212 D: G212 ev: 630.59 ft. MSL on: 24.00 ft. BGS on: 875,486.50N 2,515,583.03E
	SAMPL				CINC		TOPOCP	APHIC MAP INFORMATION:	WATER LEV	FI INFORM	
r	Recov / Total (in) % Recovery		6 in ue	re (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Quadr Towns	angle: Coffeen, IL hip: East Fork 11, Tier 7N; Range 3W	<b>T</b> = 19.0	<ul><li>0 - While drilli</li><li>2 - Upon comp</li></ul>	ng
Number	Recov	Type	Blows / 6 in N - Value RQD	Moisture (%)	Dry De	Qu (tsf Failure	Depth ft. BGS	Lithologic Description	Boreho		Remarks
1A	24/24 100%	ss	4-3 3-6 N=6	17				FILL - Brown (10YR4/3), slightly moist, firm, silty CL/ with trace sand and gravel.	AY	630	
2A	24/24 100%	ss	2-3 4-5 N=7	21			2	FILL - Dark gray (10YR4/1) with 20% brown (10YR4, and 10% dark yellowish brown (10YR4/6) mottles, moi firm, silty CLAY with trace sand.	(3) st,	-628	
3A	24/24 100%	ss	2-5 6-7 N=11	13			4 6 8 8	FILL - Brown (10YR4/3) with 15% dark gray (10YR4, and 10% dark yellowish brown (10YR4/6) mottles, moi firm, silty CLAY with trace sand and gravel.	(1) st,	626	
4A	24/24 100%	ss	2-5 7-10 N=12	15			8			624	
5A	24/24 100%	ss	2-2 4-7 N=6	29			I	Dark gray (10YR4/1) with 10% dark yellowish brown (10YR4/6) mottles, moist, firm, silty CLAY, slight trac roots.	n xe	622	
6A	18/24 75%	ss	2-3 4-6 N=7	23			10	Dark gray (10YR4/1) with 10% dark yellowish brown (10YR4/6) mottles, moist, firm, silty CLAY with trace sand.		620	
7A	17/24 71%	ss	1-2 2-2 N=4	25			12			618	
8A	24/24 100%	ss	woh-1 2-3 N=3	27			14	Dark gray (10YR4/1) with 15% dark yellowish brown (10YR4/6) mottles, moist, soft, silty CLAY with trace sa and gravel.		616	
9A	22/24 92%	ss	1-1 2-2 N=3	25						614	
10A	24/24 100%	ss	woh-wol 1-2	19			18 <b>Y</b> 20	Gray (10YR5/1) with 30% dark yellowish brown (10YR4/6) mottles, very moist, very soft, silty, very fine fine-grained sandy CLAY with trace gravel. Gray (10YR5/1), loose, wet, silty, very fine- to	- to	612	
10B NO	TE(S):		2 installe	22 d in 1	 borel	 nole.	l <sub>20</sub> .∃	Gray (101183/1), 10055, wet, Sifty, very line-10			

FI	EL	DI	BOR	I	NG	G L(	<b>DG</b>		<b>HANSON</b>
(	CLIEN	Г: А	EG Coffe	en P	ower	Station	1	<b>CONTRACTOR:</b> Layne-Western Co	
	Sit	e: C	CB Mana	ıgem	ent F	Facility		Rig mfg/model: CME-750 ATV Drill	BOREHOLE ID: G212
1	Locatio	n: Co	offeen, Ill	linois	5			Drilling Method: 4 <sup>1</sup> / <sub>4</sub> " HSA w/SS samplers	Well ID: G212
	Projec	et: 05	5S3004A						Surface Elev: 630.59 ft. MSL
	DATE	S: St	art: 10/	11/2	010			FIELD STAFF: Driller: D. Mahurin	<b>Completion:</b> 24.00 ft. BGS
		Fir	<b>ish:</b> 10/	11/2	010			Helper: J. Litsch/D. Smail	Station: 875,486.50N
WE	ATHE	R: Su	inny, wai	rm (le	0-80	's)		Eng/Geo: .	2,515,583.03E
S	SAMPL	E	Т	EST	INC	3	TOPOGRA	PHIC MAP INFORMATION:	WATER LEVEL INFORMATION:
	(in)				<u></u>	Ĵ.Ĵ		gle: Coffeen, IL	$\mathbf{V} = 19.00$ - While drilling
	نا (		1	0	$(lb/ft^3)$	e (ts	-	p: East Fork	$\mathbf{\Psi} = 20.72$ - Upon completion
	verJ		s/6in alue	e (9	р. (]	$T_{\rm Ype}^{Qp (tsf)}$		1, Tier 7N; Range 3W	$\overline{\nabla} =$
Number	Recov / Total ( % Recovery	Type	Blows / N - Val RQD	Moisture (%)	Dry Den.	Qu (tsf) Failure 7	Depth ft. BGS	Lithologic Description	Borehole Elevation Detail ft. MSL Remarks
11.4				19				medium-grained SAND.	
11A		VI	1-6	19			Ā	Brown (10YR5/3), moist, medium dense, SILT with tr sand and gravel.	ace610
	7/24 29%	ss	10-22				=`	Sund and graver.	
	2770	Λ	N=16						
		/ \					22		
								Dark gray (10YR4/1), slightly moist, hard, very silty CLAY with sand and gravel.	
12A	20/24	VI	5-21	12				CLATT with Sund and Braver.	608
12A	20/24 83%	ss	18-27 N=39	12					
		$\Lambda$	1N-39						
							24	End of Boring = 24.0 ft. BGS	
								End of Doring – 24.0 ft. DG5	

F	EL	DI	BOR	I	NG	G L(	COG		•	HAN	NSON
'			EG Coffe CB Mana				1	CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill	BO	REHOLE ID: G21	
	Location	n: Co	offeen, Ill S3004A	inois		2		Drilling Method: 4 <sup>1</sup> / <sub>4</sub> " HSA w/SS samplers		Well ID: G21 Surface Elev: 630	
	-	S: St	art: 10/	13/2				FIELD STAFF: Driller: D. Mahurin		<b>Completion:</b> 24	1.31 ft. BGS
WE	ATHEF		n <b>ish:</b> 10/ nny, war			, (hi-60	's)	Helper: J. Litsch/D. Smail Eng/Geo: .		<b>Station:</b> 87 2,51	5,810.19N .5,971.55E
5	SAMPL	E	Т	EST	INC		TOPOGR	APHIC MAP INFORMATION:	WATER LEVEL	INFORMATION	:
	al (in			()	b/ft <sup>3</sup> )	e (tsf) e	-	angle: Coffeen, IL hip: East Fork		While drilling Upon completion	
er	/ Tot		/6 in alue	ure (%	en. (l	$(1) \frac{Q_{f}}{D_{f}}$		n 11, Tier 7N; Range 3W	$\underline{\nabla}$ = 22.52 -		
Number	Recov / Total (in) % Recovery	Type	Blows / 6 in N - Value RQD	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Depth ft. BGS	Lithologic Description	Borehole Detail	Elevation ft. MSL	Remarks
1A	23/24 96%	ss	5-3 3-5 N=6	18						- 630	
2A	19/24 79%	ss	3-3 5-6 N=8	17			2	FILL - Brown (10YR4/3) with 30% dark gray (10YR4/1 and 10% dark yellowish brown (10YR4/6) mottles, moist firm, silty CLAY with trace sand and gravel.		628	
3A	20/24 83%	ss	2-3 7-7 N=10	13					<u>د و و و و و و و</u> و و و و و و و و و و و و و	626	
4A	23/24 96%	ss	3-6 6-7 N=12	16				FILL - Dark grayish brown (10YR4/2), moist, firm, silty CLAY with trace sand and gravel.		- 624	
4B		4		27			8	FILL - Gray (10YR5/1) with 15% dark yellowish brown (10YR4/6) mottles, moist, firm, silty CLAY with trace			
5A	20/24 83%	ss	3-3 3-5 N=6	20			httini	sand. Very dark gray (10YR3/1), moist, firm, silty CLAY with 		622	
6A	13/24 54%	ss	2-2 3-5 N=5	24				Dark gray (10YR4/1) with 30% dark yellowish brown (10YR4/6) moist, firm, silty CLAY with trace sand.		620	
7A	19/24 79%	ss	2-3 4-6 N=7	17			12	Gray (10YR5/1) with 30% dark yellowish brown (10YR4/6) mottles, moist, firm, clayey SILT with trace sand.		618	
8A	20/24 83%	ss	2-3 4-5 N=7	19			14	Dark gray (10YR4/1), moist, firm, clayey SILT with trace sand.		616	
9A	22/24 92%	ss	N=7 1-3 3-4 N=6	19			16	Dark gray (10YR4/1) with 30% Dark yellowish brown (10YR4/6) mottles, moist, firm, silty CLAY with trace san and gravel.	d	614	
10A	24/24 100%	ss	woh-1 2-2 N=3	17			18	Dark gray (10YR4/1) with 30% Dark yellowish brown (10YR4/6) mottles, moist, soft, sandy CLAY with trace gravel.		612	
NC	DTE(S):	G21	5 installe	d in 1	borel	nole.	-				

F	EL	)]	BOR	I	NG	LC	<b>DG</b>				
WF	CLIENT Sit Location Projec DATES	F: A e: C n: C t: 05 S: St S: St Fir R: St	EG Coffe CB Mana offeen, Ill 5S3004A tart: 10/ hish: 10/ inny, war	een P igem inois 13/2 13/2 m, v	ower ent F s 010 010 vindy	Station Facility	1	CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill Drilling Method: 4¼" HSA w/SS samplers FIELD STAFF: Driller: D. Mahurin Helper: J. Litsch/D. Smail Eng/Geo: .	Well ID:         G215           Surface Elev:         630.48 ft. MSL           Completion:         24.31 ft. BGS           Station:         875,810.19N           2,515,971.55E		
	SAMPL	£	Т	EST	TINC	J	TOPOGR	APHIC MAP INFORMATION:	WATER LEVEL INFORMATION:		
ber	Recov / Total (in) % Recovery		s / 6 in ⁄alue	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	sf) <i>Qp</i> (tsf) re Type	Townsh	ngle: Coffeen, IL ip: East Fork 11, Tier 7N; Range 3W			
Number	Reco % Re	Type	Blows N - Va RQD	Mois	Dry I	Qu (tsf) Failure 7	Depth ft. BGS	Lithologic Description	Borehole Elevation Detail ft. MSL Remarks		
11A		ss	2-4 4-4 N=8	17			22	Dark yellowish brown (10YR4/6), moist, medium der clayey SILT with sand and trace gravel. Yellowish brown (10YR5/6), moist, medium dense, si very fine- to fine-grained SAND. Dark yellowish brown (10YR4/6) with 30% dark gra (10YR4/1) mottles, moist, firm, sandy CLAY with tra	lty,		
12A	100%	ss	7-11 17-19 N=28	11			✓     gravel.       Grayish brown (10YR5/2), slightly moist, very firm, very silty CLAY with sand and gravel.       Dark gray (10YR4/1), slightly moist, hard, very silty				
12B	0/4 0%	BD		9			24	CLAY with sand and gravel. End of Boring = 24.3 ft. BGS			

F	EL		BOR	IN	NG	G L(	OG		6	HANSON
•			EG Coffe CB Mana				n	CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill	BOF	REHOLE ID: G218
1			offeen, Ill 5S3004A		5			<b>Drilling Method:</b> 4 <sup>1</sup> / <sub>4</sub> " HSA w/SS samplers		Well ID: G218 Surface Elev: 630.64 ft. MSL
	-	5: St	art: 10/	12/2				FIELD STAFF: Driller: D. Mahurin	·	Completion: 26.00 ft. BGS
WE	ATHEF		nish: 10/ artly cloud			(lo-70	s)	Helper: J. Litsch/D. Smail Eng/Geo: .		Station: 876,380.92N 2,515,962.16E
	SAMPL			-	INC	-	-	APHIC MAP INFORMATION:	WATER LEVEL	INFORMATION:
	l (in)				(ft <sup>3</sup> )	(tsf)	-	angle: Coffeen, IL	<b>T</b> = 24.00 - 1	While drilling
	Tota very		6 in ue	e (%)	n. (lb	$_{\rm Type}^{\rm Cp}$		hip: East Fork n 11, Tier 7N; Range 3W	$\underline{\Psi} = 24.76 - $ $\underline{\nabla} =$	Upon completion
Number	Recov / Total (in) % Recovery	Type	Blows / 6 in N - Value RQD	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Depth ft. BGS	Lithologic Description	Borehole Detail	Elevation ft. MSL Remarks
~	Her	Ī		~		H		2 compiler		
1A	18/24 75%	ss	$\begin{array}{c} 4-1\\ 2-1\\ \end{array}$	20				FILL - Brown (10YR4/3) with 15% dark gray (10YR4/1 and 5% dark yellowish brown (10YR4/6) mottles, moist	) 🛞 🕅	630
		$\langle \rangle$	N=3					soft, silty CLAY with trace sand and gravel.	' 🛞 🕷	<u>-</u>
2A	22/24	ss	2-2 3-5	20						628
	92%	$\mathbb{N}$	N=5							
	{						4	FILL - Dark gray (10YR4/1) with 30% brown (10YR4/3 and 10% dark yellowish brown (10YR4/6) mottles, mois	))	
3A	19/24	$\left\  \right\ _{\infty}$	2-3	17				firm, silty CLAY with trace sand and gravel.		626
54	79%	ss	4-8 N=7	1/						
							6-			
	22/24		2-5							- 624
4A	22/24 92%	ss	6-8 N=11	14						
							8	FILL - Brown (10YR5/3) with 10% dark gray (10YR4/1 mottles, slightly moist, firm, clayey SILT with trace sand		
			2.4					and gravel.		622
5A	20/24 83%	ss	3-4 8-7	17						
		$\langle \rangle$	N=12					Dark grayish brown (10YR4/2) with 5% dark yellowish		
6A				19			10	brown (10YR4/6) mottles, moist, firm, clayey SILT with trace sand.		
	19/24 79%	ss	2-2 3-5							620
6B	/ ///	$\langle \rangle$	N=5	25			12	Gray (10YR5/1) with 30% dark yellowish brown		
							12-	(10YR4/6) mottles, moist, firm, silty CLAY with trace sand, slight trace roots.		
7A	22/24	ss	2-3 5-7	22						618
	92%	$\mathbb{N}$	N=8				14			
	{						14-	Dark gray (10YR4/1) with 15% dark yellowish brown (10YR4/6) mottles, moist, firm, clayey SILT with trace		
8A	18/24	$\langle  $	2-3	19				sand.		616
бЛ	75%	ss	4-5 N=7	19						
							16			
	24/24		2-2							614
9A	24/24 100%	ss	2-4 N=4	19				Gray (10YR5/1) with 10% dark yellowish brown		
				17				(10YR4/6) mottles, moist, soft, silty CLAY with trace sar and gravel.	nd	
			1.2							612
	24/24 100%	ss	1-2 2-3							
10A		1	N=4	18			16 18 18 18 18			
NO	)TE(S):	G21	8 installe	d in	borel	hole.	20 -		Y///#***\$  #**¥///	i I
										Dago 1 of 7

FI	ELI		BOR	IN	JG	G L(	<b>DG</b>			<b>K</b> AH	ANSON
			EG Coffe				1	CONTRACTOR: Layne-Western Co			
			CB Mana	0		Facility		Rig mfg/model: CME-750 ATV Drill	BO	REHOLE ID:	
			offeen, Ill		5			<b>Drilling Method:</b> 4 <sup>1</sup> / <sub>4</sub> " HSA w/SS samplers		Well ID:	
			5S3004A								: 630.64 ft. MSL
	DATES		art: 10/					FIELD STAFF: Driller: D. Mahurin		-	26.00 ft. BGS
WE	ATHE		<b>ish:</b> 10/			(1. 70)	-)	Helper: J. Litsch/D. Smail		Station	876,380.92N
			urtly cloud	2,		·	s)	Eng/Geo: .			2,515,962.16E
S	AMPL	E	Т	EST	INC	-	TOPOGE	APHIC MAP INFORMATION:	WATER LEVEL	INFORMAT	TION:
	(in)				£	$T_{\rm Ype}^{Op (tsf)}$	Quadi	angle: Coffeen, IL	<b>T</b> = 24.00 -	While drilling	
	y Y		и	(%	lb/f	<i>p</i> e (1)	Towns	hip: East Fork	<b>⊻</b> = 24.76 -	Upon completi	on
н	/ Tc		s / 6 in alue	re (	ü.	$\mathcal{Q}_{\mathcal{V}}^{\mathrm{T}}$	Section	n 11, Tier 7N; Range 3W	<u> </u>		
Number	Recov / Total (in) % Recovery	Type	Blows / N - Val RQD	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) Failure J	Depth ft. BGS	Lithologic Description	Borehole Detail	Elevation ft. MSL	Remarks
11A	22/24 92%		woh-wol woh-woh				22	Gray (10YR5/1) with 10% dark yellowish brown (10YR4/6) mottles, moist, very soft, clayey, very fine- coarse-grained SAND with trace gravel.	• to	610	
12A 12B	24/24 100%	ss	1-1 1-3 N=2	10 16				Yellowish brown, wet, loose, silty, very fine- to coarse-grained SAND with trace gravel. Dark gray (10YR4/1) with 10% dark yellowish brow (10YR4/6) mottles, moist, soft, silty CLAY with trace s and gravel.	n sand	608	
13A	24/24 100%	ss	<i>1-5</i> <i>9-13</i> N=14	20			¥ 24	Gray (10YR5/1), wet, loose, silty, very fine- to coarse-grained SAND with trace gravel. Dark gray (10YR4/1), slightly moist, very firm, very s CLAY with sand and gravel.	ilty	606	
13B				17			26	End of Boring = 26.0 ft. BGS			

			BOR EG Coffe					<b>CONTRACTOR:</b> Layne-Western Co			H	ANSON
	Si	te: C	CB Mana offeen, Illi	ıgem	nent F		1	Rig mfg/model: CME-750 ATV Drill Drilling Method: 4¼" HSA (blind drill)	В	BORE	HOLE ID: Well ID:	
	Proje	ct: 05 2S: St	5S3004A tart: 10/1 nish: 10/2	15/20	010			FIELD STAFF: Driller: D. Mahurin Helper: J. Litsch/D. Smail			ompletion	: 624.02 ft. MSL : 17.22 ft. BGS : 877,925.26N
	CATHE SAMPL		unny (mid		's) FINC			Eng/Geo: R. Hasenyager				2,514,841.96E
	Recov / Total (in) %				Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Quadra	APHIC MAP INFORMATION: ngle: Coffeen, IL ip: East Fork				
ber	/ / To cover.		s / 6 i alue	ure (	Den. (	$^{(1)}_{(2)}Q$	Section	2, Tier 7N; Range 3W				
Number	Recov % Re	Type	Blows / 6 in N - Value RQD	Moisture (%)	Dry D	Qu (ts Failur	Depth ft. BGS	Lithologic Description			Elevation ft. MSL	Remarks
								Very dark grayish brown (10YR3/2), moist, soft, friable, clayey SILT, slight trace sand and gravel				
								Dark brown (10YR3/3), moist, soft, silty CLAY			- 622	
								Yellowish brown (10YR5/8) with 20% gray (10YR5/1) mottles, moist, firm, silty CLAY, trace sand, slight trace gravel				
								Gray (10YR5/1) with 5% yellowish brown (10YR5/6) mottles, moist, firm, silty CLAY, sand and trace gravel			- 620	
							6	Gray (10YR5/1), moist, firm, sandy CLAY, trace silt and			- 618	
							8-	slight trace gravel			- 616	
							10	Yellowish brown (10YR5/8) with 10% gray (10YR5/1) mottles, moist, firm, sandy CLAY, trace gravel			- 614	
							12	Yellowish brown (10YR5/8), wet, soft, silty SAND, trace gravel			- 612	
								Yellowish brown (10YR5/8), moist, firm, clayey SILT			- 012	
							14	Greenish gray (5GY6/1), moist, firm, interbedded clayey SILT and SILT			- 610	
							16	Yellowish brown (10YR5/8), wet, soft, fine- to coarse-grained SAND, slight trace gravel			- 608	
								Yellowish brown (10YR5/8), wet, firm, very fine-to			-	
							١	Gray (10YR5/1), moist, hard, very silty CLAY, trace sand and gravel				
								End of Boring = 17.22 ft. BGS				
NC	)TE(S):	R20	1 blind dr	rilled	l in b	orehole	e approximate	ly 8 ft. west of G201. Lithology taken from G201.				
												Page 1 of 1

			BOR									0		ANSON
			EG Coffe CB Mana				1	CONTRACTOR: Testing Service Corp. Rig mfg/model: CME-650 Track Drill			В	OR	EHOLE II	
1			offeen, Ill 5S3004A		5			Drilling Method: 3 <sup>1</sup> / <sub>4</sub> " HSA w/SS & CME sam	plers			s		: G270 7: 622.92 ft. MSL
WE	DATES	S: St Fir	<b>art:</b> 2/20 <b>iish:</b> 2/20 vercast, co	6/20 6/20				FIELD STAFF: Driller: B. Williamson Helper: R. Keedy Eng/Geo: .					Completion	<b>18.27 ft. BGS</b> <b>18.27 ft. BGS</b> <b>18.27 ft. BGS</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1</b> <b>19.1111111111111</b>
S	AMPL	E	Т	EST	INC	Ĵ	TOPOGR	APHIC MAP INFORMATION:	WAT	ER LE	V	ELI	INFORMA	TION:
	al (in)				/ft³)	(tsf)	-	angle: Coffeen, IL hip: East Fork	-	L = 16 L = 5			While drilling	Ş
5	/ Toti		/ 6 in lue	re (%	n. (lt	QD Type		11, Tier 7N; Range 3W	_	$\underline{Z} = 3$	.02		/12/08	
Number	Recov / Total (in) % Recovery	Type	Blows / 6 in N - Value RQD	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Depth ft. BGS	Lithologic Description		Bore De			Elevation ft. MSL	Remarks
	20/24 83%	ss	2-2 2-4					Dark grayish brown (10YR4/2), moist, firm, clayey SII	LT			<u>711</u>	622	
	0370	Ą	N=4					Dark grayish brown (10YR4/2), moist, firm, silty CLA	Y					
1A	19/24		3-4	24			2	Dark grayish brown (10YR4/2) with 5% yellowish brow (10YR5/8) mottles, moist, firm, silty CLAY, slight trac sand	wn xe				  	
2A	79%	ss	5-9 N=9	22		2.33 B		Gray (10YR5/1) with 70% vellowish brown (10YR5/8	 3)				620 	
2B				20		5.04 Sh	4	mottles, moist, firm, silty CLAY, slight trace sand and gravel	l 					
	20/24 83%	ss	14-5 7-8 N=12										618	
3A			IN-12	17		2.52 Sh	<b>⊻</b> 6	Dark gray (10YR4/1) with 5% yellowish brown (10YR5 mottles, moist, firm, silty CLAY, trace sand, slight trac gravel	5/8) ce					
4A	24/24 100%	ss	8-6 7-5 N=13	21		1.24 BSh							616	
4B				21		1.20 B	8	Gray (10YR5/1) with 10% yellowish brown (10YR5/8	3)				- - -	
	22/24 92%	ss	2-3 4-4					mottles, moist, firm, silty CLAY, trace sand, slight trac gravel	é				614	
5A			N=7	21		1.36 B	10	Gray (10YR5/1) with 60% yellowish brown (10YR5/8					- - 	
6A	24/24 100%	ss	1-2 2-3	21		0.74		mottles, moist, firm, silty CLAY, trace sand, slight trac gravel	xe				612	
6B	10070	$\Lambda$	N=4	24		BSh 0.78	12	Gray (10YR5/1), moist, soft, sandy CLAY					-	
	17/24	ss	2-2			В		Gray (10YR5/1), moist, soft, sandy CLAY, trace grave	əl				 610	
7A	71%	N 55	2-3 N=4	21										
8A	Ī	7		20			14	Gray (10YR5/1), moist, soft, fine- to coarse-grained SAN <u>trace gravel</u> <u>Dark yellowish brown (10YR4/4), moist, soft, sandy CL</u>	í					
8B	19/24 79%	ss	<i>1-3</i> <i>5-6</i> N=8	17		4.46 Sh		Gray (10YR5/1) with 10% yellowish brown (10YR5/8 mottles, moist, firm, silty CLAY, slight trace sand and gravel	3)					
9A	24/24 100%	ss	6-8 30-35	20			<b>⊻</b> 16	Yellowish brown (10YR5/4), wet, soft, fine to coarse SAND				<u>////</u> 	 606	
9B	10070	$\langle \rangle$	N=38	8			18-	Gray (10YR5/1), moist, hard, silty CLAY, trace sand as gravel	nd					
	l		I	I	I	I		End of Boring = 18.27 ft. BGS		V///	111	////		
NO	TE(S):													

(	CLIEN Sit Location Projec	Г: А е: С п: С яt: 05	BOR EG Coffe CB Mana offeen, Ill 5S3004A cart: 9/9/	en Po gemo inois	ower ent F	Station		CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill Drilling Method: 4¼" HSA w/SS & CME samp FIELD STAFF: Driller: G. Mills	blers	1	S	EHOLE ID Well ID urface Elev	
WF	атнғі		nish: 9/10 nny, war					Helper: J. Twellman Eng/Geo: R. Hasenyager				Station	874,239.38N 2,515,517.12E
	SAMPL				OS) TINC	y J	TOPOCD						
er .	Recov / Total (in) % Recovery		Blows / 6 in N - Value RQD	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Quadra Townsh	APHIC MAP INFORMATION: ngle: Coffeen, IL ip: East Fork 11, Tier 7N; Range 3W	Ţ	= 12.7 = 12.5	0 - V	NFORMAT Vhile drilling /21/09	10N:
Number	Recov % Rei	Type	Blows N - V RQD	Moist	Dry D	Qu (ts Failur	Depth ft. BGS	Lithologic Description		Boreho Detai		Elevation ft. MSL	Remarks
1A	20/24 83%	ss	2-5 5-6 N=10	27			munthum	FILL - Yellowish brown (10YR5/4), moist, firm, silty CLAY with trace sand. Grayish brown (10YR5/2), dry, friable, clayey SILT.				622	
2A	24/24 100%	ss	2-6 5-5 N=11	23			2	Yellowish brown (10YR5/6) with 10% gray (10YR6/1 mottles, moist, firm, silty CLAY with trace sand and slig trace gravel.	ht 			620	
3A	23/24 96%	ss	4-5 4-5 N=9	18				Gray (10YR6/1), moist, firm, very silty CLAY with slig	nt - — — -			618	
4A	24/24 100%	ss	2-4 4-5 N=8	17			6	Gray (10YR5/1) with 30% brownish yellow (10YR6/6 mottles, moist, firm, silty CLAY with sand and trace grav				616 	
5A	24/24 100%	ss	2-4 4-6 N=8	20				Very dark gray (10YR3/1), organic-rich (PEAT), silty CLAY and trace sand.				614	
6A	24/24 100%	ss	2-4 4-5 N=8	22			10-	Brownish yellow (10YR6/8) with 20% gray (10YR5/1) mottles, moist, firm, silty CLAY with sand and trace grav	) el. - — — —			612	
6B 7A	20/24	ss	2-2 3-7	20 20			¥ <sup>12</sup>	Gray (10YR6/1) with 20% brownish yellow (10YR6/8 mottles, very moist, soft, sandy CLAY with silt and sligh trace gravel. Brownish yellow (10YR6/6), very moist to wet, soft, sand	nt			  610	
7B	83%		N=5	19				<u>CLAY with silt and slight trace gravel</u> Gray (10YR6/1), wet, loose, very fine to medium SANI with silt.					
8A	24/24 100%	ss	10-19 30-33 N=49	7				Gray (10YR5/1), slightly moist, hard, very silty CLAY with sand and gravel.	-			608	
I	, <u>1</u>			ı		ı	16 —	End of Boring = 16.0 ft. BGS	<i>k</i>		<u>ar 1 / /</u>		

NOTE(S):

I WE	FIELD BORING ICLIENT: AEG Coffeen Power StatSite: CCB Management FaciliLocation: Coffeen, IllinoisProject: 05S3004ADATES: Start: 9/10/2009Finish: 9/10/2009WEATHER: Sunny, warm (70's)SAMPLE							CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill Drilling Method: 4 <sup>1</sup> / <sub>4</sub> " HSA w/SS & CME samp FIELD STAFF: Driller: G. Mills Helper: J. Twellman Eng/Geo: R. Hasenyager	blers BOREHOLE ID: G273 Well ID: G273 Surface Elev: 620.17 ft. MSL Completion: 16.00 ft. BGS Station: 874,235.24N 2,515,975.49E
						CAPHIC MAP INFORMATION: rangle: Coffeen, IL	WATER LEVEL INFORMATION: $\mathbf{\nabla} = 13.50$ - While drilling		
	Total ( ery		5 in Ie	(%) \$	llb/fl	Qp (t) Type	Towns	ship: East Fork n 11, Tier 7N; Range 3W	$\bar{\Psi} = 9.89 - 9/21/09$ $\bar{\nabla} =$
Number	Recov / Total (in) % Recovery	Type	Blows / 6 in N - Value RQD	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Depth ft. BGS	Lithologic Description	Borehole Elevation Detail ft. MSL Remarks
1A	16/24 67%	ss	3-3 3-3 N=6	24			2	FILL -Dark yellowish brown (10YR4/6), moist, firm, silt CLAY with slight trace sand.	
2A	24/24 100%	ss	3-4 5-7 N=9	28			4	FILL - Gray (10YR5/1) with 20% dark yellowish brown (10YR4/6) mottles, moist, firm, silty CLAY with slight trace sand and gravel.	
3A 3B	24/24 100%	ss	3-5 6-8 N=11	18 25			6	Brownish yellow (10YR6/8) with 40% gray (10YR5/1) mottles, moist, firm, silty CLAY with trace sand and sligh trace gravel.	) ht
4A	24/24		3-5	19			6	Gray (10YR6/1) with 10% brownish yellow(10YR6/6) mottles, moist, firm, silty CLAY with trace sand and sligh trace gravel.	ht 614
4B	100%	ss	5-6 N=10	16			8	Gray (10YR5/1), moist, firm, silty CLAY with sand and trace gravel.	d 612
5A	23/24 96%	ss	2-4 5-4 N=9	19				Yellowish brown (10YR5/8) with 30% gray (10YR6/1)	
5B				21			<b>₽</b> <sub>10</sub>	mottles, moist, soft, sandy CLAY with silty and slight trac	/ce 610
6A	24/24 100%	ss	1-2 3-4 N=5	19			12	Brownish yellow (10YR6/8) with 10% gray (10YR6/1) mottles, very moist, soft, sandy CLAY with silt and sligh trace gravel.	
7A	24/24 100%	ss	4-8 17-24 N=25	11				Gray (10YR6/1), moist, hard, very silty CLAY with sand trace gravel.	
7B			1. 25	11				Light yellowish brown (10YR6/4), wet, loose, very fine- very coarse-grained SAND with trace silt. Light yellowish brown (10YR6/4), wet, dense, sandy, silt	
8A	22/24 92%	ss	9-22 22-23 N=44	8				CLAY. Gray (10YR6/1), moist, hard, very silty CLAY with sam and trace gravel.	
	. 1					•	16	End of Boring = 16.0 ft. BGS	

NOTE(S):

FIELD BORING LC CLIENT: AEG Coffeen Power Station Site: CCB Management Facility Location: Coffeen, Illinois Project: 05S3004A DATES: Start: 9/16/2009 Finish: 9/16/2009 WEATHER: Sunny, mild (70'S)								CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill Drilling Method: 4¼" HSA w/SS & CME samp FIELD STAFF: Driller: G. Mills Helper: J. Twellman Eng/Geo: R. Hasenyager	BOREHOLE ID:         G276           blers         Well ID:         G276           Surface Elev:         629.14 ft. MSL           Completion:         28.00 ft. BGS           Station:         874,438.60N           2,516,358.83E
SAMPLE TESTING				_			RAPHIC MAP INFORMATION: rangle: Coffeen, IL	WATER LEVEL INFORMATION: $\mathbf{\nabla} = \text{Dry}$ - While drilling	
	Total ( <i>very</i>		6 in ue	e (%)	n. (lb/ff	$\begin{array}{c} Qp \ (\mathrm{ts}) \\ \mathrm{Type} \end{array}$	Towns	ship: East Fork n 11, Tier 7N; Range 3W	$\Psi = 25.55 - 9/21/09$ $\Psi = 25.55 - 9/21/09$
Number	% Recov / Total (in) % Recovery	Type	Blows / 6 in N - Value RQD	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Depth ft. BGS	Lithologic Description	Borehole Elevation Detail ft. MSL Remarks
lA	17/24 71%	ss	5-8 9-10 N=17	10			2		628
2A	19/24 79%	ss	7-7 10-14 N=17	15				FILL - Yellowish brown (10YR5/4) with 20% gray (10YR5/1) mottles, moist, hard, silty CLAY with trace say and slight trace gravel.	ind
A	11/24 46%	ss	5-10 14-27 N=24	14					624 Rock fragment in split spoon shoe
A	24/24 100%	ss	5-9 10-14 N=19	8			6	FILL - Yellowish brown (10YR5/4) with 20% gray (10YR5/1) mottles, slightly moist, hard, silty CLAY with trace sand and slight trace gravel. FILL - Yellowish brown (10YR5/4) with 10% gray	
B				5			8-	(10YR5/1) mottles, slightly moist, hard, friable, clayey SILT with sand and trace gravel.	
A	17/24 71%	ss	4-4 8-19 N=12	22			10		
A	17/24 71%	ss	4-5 8-14 N=13	14			10	FILL - Yellowish brown (10YR5/4) with 25% gray (10YR5/1) mottles, slightly moist, firm, silty CLAY with slight trace sand and gravel.	h - 618
A	16/24 67%	ss	6-7 2-4 N=9	20					616
SA	20/24 <i>83%</i>	ss	2-4 6-6 N=10	21				Gray (10YR6/1) with 10% yellowish brown (10YR5/8) mottles, moist, firm, silty CLAY with slight trace sand an gravel.	) nd 614
θA			1-4	17			16		
ЭВ	22/24 92%	ss	5-7 N=9	13			18	Gray (10YR6/1) with 20% yellowish brown (10YR5/6) mottles, moist, soft, sandy CLAY with silt and slight trac gravel.	). 
0A	23/24 96%	ss	2-3 8-12 N=11	20			20	Gray (10YR6/1) with 30% yellowish brown (10YR5/8) mottles, moist, firm, silty CLAY with sand and slight trac gravel.	610

F	ELI		BOR	IP	NG	G L(	OG		6		ANSON		
WE	CLIENT: AEG Coffeen Power Statis         Site: CCB Management Facility         Location: Coffeen, Illinois         Project: 05S3004A         DATES: Start: 9/16/2009         Finish: 9/16/2009         WEATHER: Sunny, mild (70'S)         SAMPLE       TESTING				ent F 5 09 09 0'S)	Facility	1	CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill Drilling Method: 4¼" HSA w/SS & CME samp FIELD STAFF: Driller: G. Mills Helper: J. Twellman Eng/Geo: R. Hasenyager		BOREHOLE ID:         G276           Well ID:         G276           Surface Elev:         629.14 ft. MSL           Completion:         28.00 ft. BGS           Station:         874,438.60N           2,516,358.83E			
	) ((isf)							APHIC MAP INFORMATION: angle: Coffeen, IL		ER LEVEL INFORMATION:			
er	Recov / Total (in) % Recovery		/6 in alue	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type		hip: East Fork 11, Tier 7N; Range 3W	$\underline{\Psi} = 25.55 - \underline{\nabla} =$	9/21/09			
Number	Recov % Rec	Type	Blows / 6 in N - Value RQD	Moist	Dry D	Qu (ts Failur	Depth ft. BGS	Lithologic Description	Borehole Detail	Elevation ft. MSL	Remarks		
11A	24/24 100%	ss	1-3 5-7 N=8	21			22	Gray (10YR6/1) with 30% yellowish brown (10YR5/8 mottles, moist, firm, silty CLAY with sand and slight trad gravel. [Continued from previous page]	).e	608			
12A	24/24 100%	ss	1-4 6-7 N=10	16			24	Yellowish brown (10YR5/8), moist, firm, silty CLAY wi sand and slight trace gravel.		606			
13A	24/24 100%	ss	2-3 4-6 N=7	16			<b>⊻</b> 26-	Gray (10YR6/1) with 25% yellowish brown (10YR5/6 mottles, very moist, soft, silty CLAY with sand and trace gravel. Gray (10YR6/1), very moist, loose, very fine- to fine-grained, SAND Gray (10YR6/1) with 25% yellowish brown (10YR5/6	e	604			
14A	24/24 100%	ss	1-5 15-29 N=20	16				mottles, very moist, soft, silty CLAY with sand and trace gravel. Gray (10YR6/1), very moist, firm, clayey SILT with trace very fine-grained sand. Gray (10YR6/1) with 40% yellowish brown (10YR5/4 mottles, moist, hard, very silty CLAY with sand and trace	e 	602			
							- \	Yellowish brown (10YR5/4), moist, hard, very silty CLA with sand and trace gravel. End of Boring = 28.0 ft. BGS	Image: Transformed state				

			BOR					CONTRACTOR: Lours Western Co	<b>HANSON</b>
	Sit	e: C	EG Coffe CB Mana offeen, Ill	gem	ent F		1	CONTRACTOR: Layne-Western Co Rig mfg/model: CME-750 ATV Drill Drilling Method: 4¼" HSA w/SS & CME sam	BOREHOLE ID: G279 well ID: G279
	Projec DATES	t: 05 5: St Fin	5S3004A cart: 9/10 nish: 9/10 nny, war	0/20 0/20	09 09			FIELD STAFF: Driller: G. Mills Helper: J. Twellman Eng/Geo: R. Hasenyager	Surface Elev:         6273           Surface Elev:         629.19 fl. MSL           Completion:         28.00 fl. BGS           Station:         875,028.06N           2,516,245.60E
S	SAMPL	E	Т	EST				APHIC MAP INFORMATION:	WATER LEVEL INFORMATION:
ber	Recov / Total (in) % Recovery		Blows / 6 in N - Value RQD	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Towns	angle: Coffeen, IL hip: East Fork 11, Tier 7N; Range 3W	$\Psi = 23.60 - While drilling$ $\Psi = 24.68 - 9/21/09$ $\Psi =$
Number	Reco % Re	Type	Blow N - V RQD	Mois	Dry I	Qu (t Failu	Depth ft. BGS	Lithologic Description	Borehole Elevation Detail ft. MSL Remarks
1A	24/24 100%	ss	3-3 5-6 N=8	18			2 4 6 8 8	FILL - Brown (10YR4/3) with 30% yellowish browr (10YR5/6) mottles, moist, firm, silty CLAY with sand a trace gravel.	h and
2A	24/24 100%	ss	5-9 10-11 N=19	14			4		
3A	24/24 100%	ss	5-9 9-10 N=18	17			6		624
4A	24/24 100%	ss	4-5 7-6 N=12	21					622
5A	24/24 100%	ss	3-3 5-7 N=8	19			8	FILL - dark gray (10YR4/1) with 10% brownish yello (10YR6/6) mottles, moist, hard, silty CLAY with sand a trace gravel.	w and - 620
6A	24/24 100%	ss	3-4 6-9 N=10	17					618
7A	23/24 96%	ss	2-5 5-6 N=10	23			10		
0.4	24/24 100%	ss	2-3 7-6 N=10					Brownish yellow (10YR6/8) with 30% gray (10YR5/ mottles, moist, firm, silty CLAY with slight trace sand a gravel.	1) md 614
8A 9A	18/24 75%	ss	4-7 8-9 N=15	23 25			16	Yellowish brown (10YR5/8) with 20% gray (10YR6/ mottles, moist, firm, silty CLAY with slight trace sand a gravel.	1) and 612
10A	24/24 100%	ss	3-6 7-10 N=13	17			18-	Gray (10YR6/1) with 25% yellowish brown (10YR5/3 mottles, moist, firm, silty CLAY with sand and trace gra	8) vel.
NC	DTE(S):						20		Page 1 of 2

FI	ELI	D	BOR	I	NG	G L(	OG		•		ANSON	
	CLIENT	[: A]	EG Coffe	en P	ower	Station	n	CONTRACTOR: Layne-Western Co				
	Site	e: Co	CB Mana	gem	ent F	acility		Rig mfg/model: CME-750 ATV Drill	B	BOREHOLE ID: G279		
]			offeen, Ill		5			Drilling Method: 4 <sup>1</sup> / <sub>4</sub> " HSA w/SS & CME sar	nplers		<b>D:</b> G279	
			5S3004A							Surface Elev: 629.19 ft. MSL		
	DATES		tart: 9/10					FIELD STAFF: Driller: G. Mills		-	<b>n:</b> 28.00 ft. BGS	
WE			nish: 9/10					1	Helper: J. Twellman Station: 875,028.06			
			unny, war	`				Eng/Geo: R. Hasenyager			2,516,245.60E	
<u> </u>	SAMPLE TESTING			Ĵ	TOPOGR	APHIC MAP INFORMATION:	WATER LEVE	L INFORMA	TION:			
	(in)				ť3)	sf)	Quadra	angle: Coffeen, IL	<b>X</b> = 23.60	- While drilling	g	
	v		2	9	lb/f	e (t	Towns	hip: East Fork	$\bar{\Psi} = 24.68$	- 9/21/09		
	To ver		/ 6 in lue	() () ()	Ľ.	$Q_{\rm IV}^{\rm T}$	Section	11, Tier 7N; Range 3W	<u> </u>			
Number	Recov / Total (in) % Recovery	Type	<i>Blows / 6 i</i> , N - Value <b>RQD</b>	Moisture (%)	Dry Den. (lb/ft <sup>3</sup> )	Qu (tsf) <i>Qp</i> (tsf) Failure Type	Depth ft. BGS	Lithologic Description	Borehol Detail	e Elevation ft. MSL	Remarks	
~	K %	<u>–</u>	M Z M	~		0 <sup>H</sup>	n. DOS	Description			Remarks	
11A	23/24 96%	ss	2-4 5-7 N=9	18			22	Gray (10YR6/1) with 25% yellowish brown (10YR5/ mottles, moist, firm, silty CLAY with sand and trace gra [Continued from previous page]	8) ivel.	608		
12A	19/24 79%	ss	4-9 8-9 N=17	13			 Ţ	Yellowish brown (10YR5/8), moist, firm, clayey SILT very fine-grained SAND with slight trace gravel.	and	606		
12B	L f			12			24-					
13A	17/24 71%	ss	1-5 5-7 N=10	18			24 – ¥ 26 –	Light brownish gray (10YR6/2), wet, loose, very fine- coarse-grained SAND.	to	604		
14A	24/24 100%	ss	10-10 18-18	16				Brownish yellow (10YR6/6), moist, hard, very silty CL	AY	602		
14B	10070	N=28 14 Gray (10YR6/1), moist, hard, very silty CLAY with sand and trace gravel.					and					
							20	End of Boring = 28.0 ft. BGS				

1	CLIENT Sit Location Projec DATES	F: Al e: Co n: Co t: 05 5: St Fin	EG Coffe CB Mana offeen, III 5S3004A cart: 2/2 hish: 2/2 vercast, c	en P agem linois 6/20 6/20	ower ent F s 08	Station	n	CONTRACTOR: Testing Service Corp. Rig mfg/model: CME-650 Track Drill Drilling Method: 3¼" HSA w/SS & CME sam FIELD STAFF: Driller: B. Williamson Helper: R. Keedy Eng/Geo: .	plers		23	BO	S	EHOLE II Well II urface Ele Completio	<b>HANSON</b> D: G280 D: G280 v: 622.95 ft. MSL n: 17.98 ft. BGS n: 875,045.11N 2,515,679.48E
s	SAMPL	E	Т	EST	TING		TOPOGRAPHIC MAP INFORMATION: WATH					VЕ	LI	NFORMA	TION:
r	Number Recov / Total (in) % Recovery Type Blows / 6 in N - Value RQD Moisture (%) Dry Den. (lb/ft <sup>3</sup> ) Qu (tsf) <i>Qp</i> (tsf)			Qu (tsf) <i>Qp</i> (tsf) Failure Type	Towns	rangle: Coffeen, IL ship: East Fork n 11, Tier 7N; Range 3W	Ţ					/hile drillin /12/08	g		
Number	Recov % Reco	Type	<i>Blows / 6 ii</i> N - Value <b>RQD</b>	Moisture (%)	Dry De	Qu (tsf Failure	Depth ft. BGS	Lithologic Description			oreh Deta		e	Elevation ft. MSL	Remarks
1A	24/24 100%	ss	5-3 4-4	23				Dark grayish brown (10YR4/2), moist, firm, clayey SII	LT	1/ · · · ·					
1D	10070	$\mathbb{A}$	N=7	20		2.22		Brown (10YR4/3) with 20% yellowish brown (10YR5/ mottles, moist, firm, silty CLAY	(8)			X		-	
1B 2A		]		26 30		2.33 B 1.28	2	Dark yellowish brown (10YR4/4), moist, firm, silty CL4	AY -		1	Y		 	
211	24/24 100%	ss	3-4 4-6	50		BSh								- 620	
2B	10070	$\langle \rangle$	N=8	25			4	Dark gray (10YR4/1) with 40% yellowish brown (10YR5/8) mottles, moist, firm, silty CLAY						-	
			2.4				ĮĮ <sup>4</sup> ≣							_	
3A	19/24 79%	ss	3-4 6-6 N=10	14		3.10 Sh	6	Dark gray (10YR4/1) with 40% yellowish brown (10YR5/8) mottles, moist, firm, silty CLAY, slight trac						618	
	İ						6-	(101K5/8) moties, moist, min, sity CLA1, sight tax sand	<i>L</i> C					-	
4A	22/24 92%	ss	9-11 10-8 N=21	18		1.67 BSh	8	Dark gray (10YR4/1) with 40% yellowish brown (10YR5/8) mottles, moist, firm, silty CLAY, trace sand slight trace gravel	— — — d,						
							8							-	
5A	19/24 79%	ss	2-2 4-4	20		1.47 B		Dark gray (10YR4/1) with 40% yellowish brown						- 614	
5B		$\langle \rangle$	N=6	21		1.28		(10YR5/8) mottles, moist, firm, silty CLAY, sand, trac gravel	æ					-	
50						B	10							-	
	22/24 92%	ss	2-3 3-3 N=6											612	
6A			IN-0	20			12-	Yellowish brown (10YR5/8) with 20% light gray (10YR6/1) mottles, moist, soft, sandy CLAY						- - 	
		$\Lambda$	3-14					Yellowish brown (10YR5/8), moist, soft, fine to coars	e	<u>    </u> 				_	
	23/24 96%	ss	23-21 N=37					<u>SAND, trace gravel</u> Yellowish brown (10YR5/8), moist, firm, sandy CLAY	' (,/					- 610	
7A				13				Yellowish brown (10YR5/4), moist, firm, clayey SILT trace sand and gravel	 ,						
	23/24 96%	ss	12-17 24-26											- 608	
8A 8B		/\	N=41	9 15			₹ ‡					• •		-	
9A		1	11-27	26			16	Yellowish brown (10YR5/4), wet, soft, fine- to coarse-grained SAND, trace gravel						-	
	24/24 100%	ss	54-43 N=81					Gray (10YR5/1), moist, hard, silty CLAY, trace sand as gravel	nd						
9B	i L		I	ı /	I	I		End of Boring = 17.98 ft. BGS		V///	etti B	<u></u>			
NO	)TE(S):														

Illinois Enviro	onmental Protectio	n Agency	7		Well	Completion	n Report
Site #:	Co	ounty: Mor	itgome	rv		Well #: G2	200
Site Name: <u>AEG Coffeen P</u> State- Plant						Borehole #:	
PlaneCoordinate: X 877,9.	<u>30.6</u> Y <u>2,515,650.0</u> (or	r) Latitude:			_ Longitu	de:°	· · ·
Surveyed By: <u>Jeffrey D. Em</u>	rick		IL Re	gistration #: <u>035</u>	-003507		
Drilling Contractor: <u>Testing S</u>	Service Corporation		Drille	r: <u>B. Williamso</u>	n		
Consulting Firm: <u>Hanson Pro</u>	ofessional Services Inc.		Geolo	gist: <u>Rhonald V</u>	V Hasenyage	er, LPG #196-00	0246
Drilling Method: <u>Hollow ster</u>	n auger		Drillir	ng Fluid (Type):			
Logged By: <u>Suzanna L Simp</u>	oson		Date S	Started: 2/25/2	2008 Dat	te Finished: 2/2	25/2008
Report Form Completed By: S	uzanna L Simpson		Date:	2/29/2008			
ANNULAR SPA	ACE DETAILS			Elevation: (MSL)*	s Depths (BGS)	(0.01 ft.)	)
				626.54	. ,	Top of Protective	e Casing
				625.94		Top of Riser Pipe	-
Type of Surface Seal: Concrete				624.20	0.00	Ground Surface	
				620.70	<u> </u>	Top of Annular S	aplant
Type of Annular Sealant: Bento	onite chips	. 🕅	H	020.70		TOP OF Annuar 5	searant
Installation Method: Gravi	ty	-					
Setting Time: <u>&gt;24 hr.</u>		.    Į	7	621.45		Static Water Leve (After Completion)	
Type of Bentonite Seal Gra	ular) Pellet Slurry						
	(choose one)		1	(00 =0			
Installation Method: <u>Gravi</u>	ty	·		_620.70_	3.50	Top of Seal	
Setting Time: <u>&gt;24 hr.</u>			×	_614.20		Top of Sand Pack	۲
Type of Sand Pack: <u>Quartz san</u>	d	. []					
Grain Size: 10/20 (si	eve size)			612.01	12.19	Top of Screen	
Installation Method: <u>Gravit</u>	Ty						
				607.22		Bottom of Screen	
Type of Backfill Material: Forn	(if applicable)	.   L		606.84	17.36	Bottom of Well	
Installation Method: <u>Sloug</u>	h			<u>606.20</u>	18.00	Bottom of Boreho	ole
				Kelerencea (	a National Geode	cue Datum	
				CA	SING MEA	SUREMENTS	
WELL CON	STRUCTION MATERIAL	.S		Diameter of Bore	hole	(inches)	8.0
	ne type of material for each area)			ID of Riser Pipe		(inches)	2.0
				Protective Casing		(feet)	5.0
Protective Casing	SS304 SS316 PTFE PV	C OTHER: (	Steel	Riser Pipe Lengt		(feet)	13.93
Riser Pipe Above W.T.	SS304 SS316 PTFE PV			Bottom of Screen		(feet)	0.38
Riser Pipe Below W.T.		C OTHER:		Screen Length ( Total Length of C			<u>4.79</u> 19.10
Screen	SS304 SS316 PTFE (PV	C OTHER:		Screen Slot Size		(fect) (inches)	0.010
Well Completion Form (revised 02/06/02	<u></u>			**Hand-Slotted Well 9			

Illinois Environm	ental Protection	Agency			Wel	l Completior	n Report
Site #:	C	ounty: <u>Mor</u>	ntgomery	7	V	Vell #:G	206
Site Name:CCB Management Fa	cility				B	Borehole #:	G206
State Plane Coordinate: X 2,514,669.2	Y <u>875,103.9</u> (o	r) Latitude:	39°		Longitud	le: <u>-89°</u> <u>2</u> .	<u>3' 54.800"</u>
Surveyed By: <u>Jeffrey D. Emrick</u>			IL Regi	stration #:	003507		
Drilling Contractor: Layne-Wester	n Co		Driller:	D. Mahurin			
Consulting Firm: <u>Hanson Profession</u>	onal Services Inc.		Geolog	ist: <u>Rhonald W</u>	. Hasenyage	r, LPG #196-000	246
Drilling Method: <u>Hollow stem aug</u>	ger		Drilling	g Fluid (Type): <u>n</u>	/a		
Logged By: <u>Suzanna Simpson</u>			Date St	arted: <u>10/14/2</u>	2010 Dat	te Finished: <u>10</u> /	/14/2010
Report Form Completed By: <u>Suzan</u>	na Simpson		Date:	10/15/2010			
ANNULAR SPACE	DETAILS			Elevations (MSL)*	Depths (BGS)	(0.01 ft.)	)
		<b></b>		633.07	-2.53	Top of Protective	Casing
				632.82	-2.28	Top of Riser Pipe	2
Type of Surface Seal: <u>Concrete</u>			V D		0.00	Ground Surface	
Type of Annular Sealant: <u>High-solid</u>	ls hentonite			627.84	2.70	Top of Annular S	Sealant
Installation Method: <u>Tremie</u>		- 4					
Setting Time:24 hr.			Z	611.96	18.58	Static Water Leve (After Completion)	
Type of Bentonite Seal Granular	Pellet Slurry (choose one)						
Installation Method: <u>Gravity</u>	()	-	×	616.24	14.30	Top of Seal	
Setting Time: <u>15 min</u>		- 🕅	×	615.04	15.50	Top of Sand Pack	k
Type of Sand Pack: <u>Quartz sand</u> Grain Size: <u>10/20</u> (sieve siz	ze)			613.03	17.51	Top of Screen	
Installation Method: <u>Gravity</u>				608.62	21.92	Bottom of Screen	1
Type of Backfill Material:	(if applicable)	_   L		608.12	22.42	Bottom of Well	
Installation Method: <u>n/a</u>				606.54 * Referenced to	24.00 a National Geode	Bottom of Boreh	ole
				CA	SING MEA	SUREMENTS	
				Diameter of Borel		(inches)	8.0
	UCTION MATERIAL e of material for each area)	S		ID of Riser Pipe		(inches)	2.0
	·			Protective Casing	Length	(feet)	5.0
Destastive Cooling	204 55217 5755 5		]	Riser Pipe Length		(feet)	19.79
		VC OTHER:		Bottom of Screen		(feet)	0.50
		VC OTHER:		Screen Length ( Total Length of C		(feet) (feet)	4.41 24.70
	6304 SS316 PTFE P	VC OTHER:		Screen Slot Size *	-	(inches)	0.010

Illinois Environmental Protection	Agency			Well	Completio	n Report
Site #: C	County: <u>Montg</u>	gomery		W	/ell #:G	209
Site Name: CCB Management Facility				В	orehole #:	G209
State Plane Coordinate: X 2,515,149.6 Y 875,298.2 (c	or) Latitude:	<u> </u>	4' 4.500"	Longitud	e: <u>-89°</u> 2	<u>3' 48.700"</u>
Surveyed By:Jeffrey D. Emrick	I	IL Registr	ation #: <u>035-0</u>	03507		
Drilling Contractor: <u>Layne-Western Co</u>	I	Driller:	D. Mahurin			
Consulting Firm: <u>Hanson Professional Services Inc.</u>	(	Geologist:	Rhonald W.	Hasenyager	r, LPG #196-000	)246
Drilling Method: <u>Hollow stem auger</u>	I	Drilling F	luid (Type): <u>n/a</u>	ì		
Logged By: Suzanna Simpson	I	Date Start	ed: <u>10/7/20</u>	<u>10</u> Dat	e Finished: <u>1</u>	0/7/2010
Report Form Completed By: <u>Suzanna Simpson</u>	I	Date:	10/8/2010			
ANNULAR SPACE DETAILS			Elevations (MSL)*	<b>Depths</b> (BGS)	(0.01 ft.	)
			_633.16_	2.59	Top of Protectiv	e Casing
		7	632.91	-2.34	Top of Riser Pip	e
Type of Surface Seal: <u>Concrete</u>			630.57	0.00	Ground Surface	
Type of Annular Sealant: _ High-solids bentonite			627.57	3.00	Top of Annular	Sealant
Installation Method: Tremie	- 9					
Setting Time:>24 hr.			615.52		Static Water Lev (After Completion)	
Type of Bentonite Seal Granular Pellet Slurry (choose one)						
Installation Method: <u>Gravity</u>	- 😽	<del>KX</del>	_616.07_	14.50	Top of Seal	
Setting Time: <u>15 min</u>		×	614.67	15.90	Top of Sand Pac	k
Type of Sand Pack: <u>Quartz sand</u> Grain Size: <u>10/20</u> (sieve size)			612.83	17.74	Top of Screen	
Installation Method: <u>Gravity</u> Type of Backfill Material: <u>n/a</u>			<u>608.29</u> 607.76	<u>22.28</u> 22.81	Bottom of Scree Bottom of Well	n
(if applicable)		-				
Installation Method: <u>n/a</u>			606.57 * Referenced to a		Bottom of Borel ic Datum	iole
			CAS	ING MEA	SUREMENTS	
	_	D	biameter of Boreho		(inches)	8.0
WELL CONSTRUCTION MATERIAL (Choose one type of material for each area)	.S	П	O of Riser Pipe		(inches)	2.0
			rotective Casing L	ength	(feet)	
Protective Casing SS304 SS316 PTFE 1	PVC OTHER:		iser Pipe Length	End C	(feet)	
	PVC OTHER:		ottom of Screen to creen Length (1s		t) (feet)	
	PVC OTHER:		otal Length of Cas		(feet)	
Screen SS304 SS316 PTFE	PVC OTHER:		creen Slot Size **	-	(inches)	

Illinois Environmental Pro	otection Agency			Wel	l Completior	Report
Site #:	County: <u>Mor</u>	ntgomery		V	Vell #: 62	212
Site Name: CCB Management Facility				В	orehole #:	G212
State Plane Coordinate: X_2,515,583.0 Y_875	6,486.5 (or) Latitude:	39°	4' 6.300"		le: <u>-89°</u> 23	
Surveyed By:Jeffrey D. Emrick		IL Regis	tration #: <u>035-0</u>	03507		
Drilling Contractor: <u>Layne-Western Co</u>		Driller:	D. Mahurin			
Consulting Firm: <u>Hanson Professional Service</u>	es Inc.	Geologis	st: <u>Rhonald W.</u>	Hasenyage	r, LPG #196-000	246
Drilling Method: Hollow stem auger		Drilling	Fluid (Type): <u>n/a</u>	a		
Logged By: <u>Suzanna Simpson</u>		Date Sta	urted: <u>10/11/20</u>	010 Dat	e Finished: <u>10</u> /	/11/2010
Report Form Completed By: <u>Suzanna Simpson</u>	L	Date:	10/19/2010			
ANNULAR SPACE DETAIL	S		Elevations (MSL)*	<b>Depths</b> (BGS)	(0.01 ft.)	
			633.12	-2.53	Top of Protective	Casing
			632.89	2.30	Top of Riser Pipe	
Type of Surface Seal: <u>Concrete</u>			630.59	0.00	Ground Surface	
			627.59	3.00	Top of Annular S	ealant
Type of Annular Sealant: <u>High-solids bentonite</u>	Ÿ	TP -			1	
Installation Method: <u>Tremie</u>						
Setting Time: <u>&gt;24 hr.</u>		☑	616.10	14.49	Static Water Leve (After Completion)	
Type of Bentonite Seal Granular Pellet	Slurry					
Installation Method: <u>Gravity</u>	,		616.89	13.70	Top of Seal	
Setting Time: <u>17 min</u>			615.79	14.80	Top of Sand Pacl	ζ
Type of Sand Pack: <u>Quartz sand</u> Grain Size: 10/20 (sieve size)			613.85	16.74	Top of Screen	
Installation Method: <u>Gravity</u>			609.30	21.29	Bottom of Screen	L
Type of Backfill Material: <u>n/a</u> (if applica	ble)		608.78	21.81	Bottom of Well	
Installation Method:n/a	, 		_606.59_	_24.00	Bottom of Boreh	ole
			* Referenced to a	National Geode	tic Datum	
			CAS	SING MEA	SUREMENTS	
			Diameter of Boreho	ole	(inches)	8.0
WELL CONSTRUCTION N (Choose one type of material for e		-	ID of Riser Pipe		(inches)	2.0
			Protective Casing L	ength	(feet)	5.0
Protective Casing SS304 SS316	PTFE PVC OTHER: (		Riser Pipe Length		(feet)	19.04
Riser Pipe Above W.T. SS304 SS316	PTFE PVC OTHER:		Bottom of Screen to Screen Length (1s		(feet) ot) (feet)	0.52 4.55
Riser Pipe Below W.T.SS304SS316	PTFE PVC OTHER:		Total Length of Ca		(feet)	24.11
Screen SS304 SS316	PTFE <b>PVC</b> OTHER:		Screen Slot Size **	-	(inches)	0.010

Illinois Environmental Protection	Agency			Wel	Completior	n Report
Site #: 0	County: <u>Mon</u>	tgomery		V	Vell #:G	215
Site Name: CCB Management Facility				В	orehole #:	G215
State Plane Coordinate: X_2,515,971.6 Y_875,810.2 (	or) Latitude:	<u> </u>		Longitud	e: <u>-89°</u> <u>2</u> 2	<u>3' 38.200"</u>
Surveyed By:Jeffrey D. Emrick		IL Regi	stration #:035-0	03507		
Drilling Contractor: <u>Layne-Western Co</u>		Driller:	D. Mahurin			
Consulting Firm: <u>Hanson Professional Services Inc.</u>		Geolog	st: <u>Rhonald W.</u>	Hasenyage	r, LPG #196-000	246
Drilling Method: Hollow stem auger		Drilling	;Fluid (Type): <u>n/a</u>	1		
Logged By: <u>Suzanna Simpson</u>		Date St	arted: <u>10/13/20</u>	010 Dat	e Finished: <u>10</u> /	/13/2010
Report Form Completed By: <u>Suzanna Simpson</u>		Date: _	10/19/2010			
ANNULAR SPACE DETAILS			Elevations (MSL)*	<b>Depths</b> (BGS)	(0.01 ft.)	
	<b></b>		633.30	2.82_	Top of Protective	Casing
			633.06	-2.58	Top of Riser Pipe	2
Type of Surface Seal: <u>Concrete</u>		Y D	<u> </u>	0.00	Ground Surface	
Type of Annular Sealant: <u>High-solids bentonite</u>			627.58	2.90	Top of Annular S	Sealant
Installation Method: Tremie	- 9					
Setting Time: _>24 hr.		Z	_607.64	22.84	Static Water Leve (After Completion)	
Type of Bentonite Seal Granular Pellet Slurry (choose one)		YT.				
Installation Method: <u>Gravity</u>	- 🙀	$\overline{\mathbf{x}}$	614.08	16.40	Top of Seal	
Setting Time: 20 min	- 🕅	×	612.98	17.50	Top of Sand Pack	x
Type of Sand Pack: <u>Quartz sand</u> Grain Size: <u>10/20</u> (sieve size)	_		_611.07_	19.41	Top of Screen	
Installation Method: <u>Gravity</u>	-   🗏		606.68	23.80	Bottom of Screen	L
Type of Backfill Material:	_   [		606.17	24.31	Bottom of Well	
Installation Method:			606.17 <ul> <li>Referenced to a</li> </ul>	24.31 National Geoder	Bottom of Boreh	ole
			CAS			
			Diameter of Boreho		SUREMENTS (inches)	8.0
WELL CONSTRUCTION MATERIAL (Choose one type of material for each area)	.S		ID of Riser Pipe	*	(inches)	2.0
· · · · · · · · · · · · · · · · · · ·			Protective Casing L	ength	(feet)	5.0
Destacting Continent and a second again and		]	Riser Pipe Length		(feet)	21.99
	PVC OTHER:		Bottom of Screen to		(feet)	0.51
	PVC ) OTHER:		Screen Length (1s Total Length of Cas		· · · ·	4.39 26.89
-	PVC OTHER:		Screen Slot Size **	-	(feet) (inches)	0.010

Illinois Environ	mental Protection Agency	•		Well	Completion	Report
Site #:	County: <u>M</u>	lontgomery	7	W	/ell #: G2	.18
Site Name: <u>CCB Managemen</u>	t Facility			В	orehole #:	G218
State Plane Coordinate: X_2,515,962	2.2 Y 876,380.9 (or) Latitud	le: <u>39°</u>	4' 15.200"	Longitud	e: <u>-89°</u> 23	<u>' 38.200"</u>
Surveyed By:Jeffrey D. Emric	ck	IL Regi	istration #: <u>035-00</u>	03507		
Drilling Contractor: Layne-We	estern Co	_ Driller:	D. Mahurin			
Consulting Firm: <u>Hanson Profe</u>	essional Services Inc.	_ Geolog	ist: <u>Rhonald W.</u>	Hasenyager	r, LPG #196-0002	246
Drilling Method: <u>Hollow stem</u>	auger	_ Drilling	g Fluid (Type): <u>n/a</u>	ı		
Logged By: <u>Suzanna Simpson</u>	1	_ Date St	arted: <u>10/12/20</u>	010 Dat	e Finished: <u>10/</u>	12/2010
Report Form Completed By:Su	izanna Simpson	Date: _	10/19/2010			
ANNULAR SPA	CE DETAILS		Elevations (MSL)*	<b>Depths</b> (BGS)	(0.01 ft.)	
			633.34	-2.70	Top of Protective	Casing
			633.11	2.47	Top of Riser Pipe	
Type of Surface Seal: <u>Concrete</u>				0.00	Ground Surface	
Type of Annular Sealant: <u>High-</u>	solids bentonite		627.14	3.50	Top of Annular S	ealant
Installation Method:						
		$\overline{\nabla}$	609.89	20.75	Static Water Leve (After Completion)	
Type of Bentonite Seal Gran	ular Pellet Slurry					
Installation Method: <u>Gravit</u>	<u>y</u>	<del>K X</del>	613.14	17.50	Top of Seal	
Setting Time: <u>17 min</u>	X		612.14	18.50	Top of Sand Pack	
Type of Sand Pack: <u>Quartz sand</u>	d					
Grain Size: <u>10/20</u> (sie	eve size)		610.31	20.33	Top of Screen	
Installation Method: <u>Gravit</u>	у		(05.97	24 77	D.#. 69	
Type of Backfill Material: <u>n/a</u>			<u>605.87</u> <u>605.37</u>	<u>24.77</u> 25.27	Bottom of Screen Bottom of Well	
Installation Method: <u>n/a</u>	(if applicable)		604.64 * Referenced to a	26.00	Bottom of Boreho	ble
			* Referenced to a	National Geodet	ic Datum	
					SUREMENTS	
	STRUCTION MATERIALS		Diameter of Boreho ID of Riser Pipe	le	(inches)	8.0
(Choose on	e type of material for each area)		Protective Casing L	ength	(inches) (feet)	5.0
	1		Riser Pipe Length		(feet)	22.80
Protective Casing	SS304 SS316 PTFE PVC OTHER		Bottom of Screen to		(feet)	0.50
Riser Pipe Above W.T. Riser Pipe Below W.T.	SS304 SS316 PTFE PVC OTHER SS304 SS316 PTFE PVC OTHER		Screen Length (1s			4.44
Screen	SS304 SS316 PTFE PVC OTHER		Total Length of Cas		(feet)	27.74

Illinois Environmental Protection Agency		Well Co	mpletion <b>R</b>	leport
Site #: County:	ntgomery	Well #:	R201	
Site Name: CCB Management Facility		Borehol	e#: <u>R2</u> (	)1
State Plane Coordinate: X 2,514,842.0 Y 877,925.3 (or) Latitude:	<u>39° 4' 30.500"</u>			
Surveyed By:Jeffrey D. Emrick	IL Registration #:035-00	3507		
Drilling Contractor: Layne-Western Co	Driller: D. Mahurin			
Consulting Firm: <u>Hanson Professional Services Inc.</u>	Geologist: <u>Rhonald W. H</u>	Hasenyager, LPC	<u>6 #196-000246</u>	)
Drilling Method: <u>Hollow stem auger</u>	Drilling Fluid (Type): <u>n/a</u>			
Logged By:Rhonald W. Hasenyager	Date Started:10/15/20	10 Date Finis	hed: <u>10/15/</u>	2010
Report Form Completed By:Suzanna Simpson	Date:10/19/2010			
ANNULAR SPACE DETAILS	Elevations (MSL)*	<b>Depths</b> (BGS)	(0.01 ft.)	
	626.51	<u>-2.49</u> Top	of Protective Ca	sing
	626.34	<u>-2.32</u> Top	of Riser Pipe	
Type of Surface Seal: <u>Concrete</u>	<u>624.02</u>	<u>0.00</u> Grou	ind Surface	
Ture of Annulus Scalants . With called humanity	621.52	<u>2.50</u> Top	of Annular Seala	int
Type of Annular Sealant: <u>High-solids bentonite</u>				
Installation Method: <u>Tremie</u> Setting Time: <u>&gt;24 hr.</u>			c Water Level er Completion) 11/1	5/2010
Type of Bentonite Seal Granular Pellet Slurry				
Installation Method: <u>Gravity</u>	614.47	<u>9.55</u> Top	of Seal	
Setting Time: <u>48 min</u>		<u>11.12</u> Top	of Sand Pack	
Type of Sand Pack:Quartz sand Grain Size:10/20 (sieve size)		<u>12.27</u> Top	of Screen	
Installation Method: <u>Gravity</u> Type of Backfill Material: <u>n/a</u> (if applicable)	<u>_607.36</u> _606.80		om of Screen om of Well	
Installation Method:		17.22 Botto National Geodetic Datum	om of Borehole	
	CASI	NG MEASURE	MENITS	
	Diameter of Borehol		(inches)	8.0
WELL CONSTRUCTION MATERIALS (Choose one type of material for each area)	ID of Riser Pipe		(inches)	2.0
	Protective Casing Le	ength	(feet)	5.0
Protective Casing SS304 SS316 PTFE PVC OTHER: (	Riser Pipe Length	F 10		14.59
Riser Pipe Above W.T.         SS304         SS316         PTFE         PVC         OTHER:	Bottom of Screen to Screen Length (1st		(feet)	0.56 4.39
Riser Pipe Below W.T.         SS304         SS316         PTFE         PVC         OTHER:	Total Length of Cast		· /	19.54
Screen SS304 SS316 PTFE PVC OTHER:	Screen Slot Size **	J.	(inches)	0.010

Illinois Enviror	mental Protection Agency	y		Wel	Completion	Report
Site #:	County:N	Aontgomery		V	Vell #: G2	270
Site Name: _CCB Managemen	t Facility			В	orehole #: 0	G270
State Plane Coordinate: X 2,514,990	6.8 Y <u>874,801.9</u> (or) Latitu	de: <u>39°</u>	3' <u>59.600"</u>			
Surveyed By:Jeffrey D. Emri	ck	IL Regist	ration #: <u>035-0</u>	03507		
Drilling Contractor: <u>Testing Sec</u>	ervice Corp.	Driller:	B. Williamson			
Consulting Firm: <u>Hanson Prof</u>	essional Services Inc.	Geologist	: <u>Rhonald W.</u>	Hasenyage	r, LPG #196-0002	246
Drilling Method: <u>Hollow stem</u>	auger	Drilling F	Fluid (Type):			
Logged By: <u>Suzanna Simpsor</u>	1	Date Star	ted: <u>2/26/20</u>	<u>08</u> Dat	e Finished:2/2	26/2008
Report Form Completed By: <u>Su</u>	izanna Simpson	Date:	2/29/2008			
ANNULAR SPA	CE DETAILS		Elevations (MSL)*	Depths (BGS)	(0.01 ft.)	
			626.41	-3.49	Top of Protective	Casing
			625.97	-3.05		
Type of Surface Seal: <u>Concrete</u>			622.92	0.00	Ground Surface	
Type of Annular Sealant: <u>Bento</u>	nite chips		619.92	3.00	Top of Annular S	ealant
Installation Method: _ Gravit	v l					
Setting Time: >24 hr.		Σ	617.30	5.62	Static Water Leve (After Completion)	
Type of Bentonite Seal Gran	ular Pellet Slurry					
Installation Method:Gravit	y	* **	619.92	3.00	Top of Seal	
Setting Time: <u>&gt;24 hr.</u>	Ž		610.92	12.00	Top of Sand Pack	
Type of Sand Pack: <u>Quartz sand</u>	<u>d</u>					
Grain Size: <u>10/20</u> (sig	eve size)		_609.79_	13.13	Top of Screen	
Installation Method:Gravit	<u>y</u>		(05.00	17.02		
Type of Backfill Material: <u>n/a</u>			<u>605.00</u> 604.65	<u>17.92</u> <u>18.27</u>	Bottom of Screen Bottom of Well	
Installation Method: n/a	(if applicable)		604.65	18.27	Bottom of Boreho	Ja
Instanation Method. <u>II/a</u>			* Referenced to a			ne
			CAS	SING MEA	SUREMENTS	
		Ι	Diameter of Boreho	ole	(inches)	8.0
	STRUCTION MATERIALS the type of material for each area)	I	D of Riser Pipe		(inches)	2.0
			Protective Casing L	ength	(feet)	5.0
Protective Casing	SS304 SS316 PTFE PVC OTHE		Riser Pipe Length		(feet)	16.18
Riser Pipe Above W.T.	SS304 SS316 PTFE (PVC) OTHE		Bottom of Screen to Screen Length (1s		(feet)	0.35 4.79
Riser Pipe Below W.T.	SS304 SS316 PTFE PVC OTHE		Fotal Length of Ca		(feet) (feet)	21.32
Screen	SS304 SS316 PTFE PVC OTHE		Screen Slot Size **		(inches)	0.010

Illinois Environmental Protection Agency		Well Completion Report					
Site #: County:	tgomery	Well #: G271					
Site Name: CCB Management Facility		Borehole #: G271					
State Plane Coordinate: X 2,515,517.1 Y 874,239.4 (or) Latitude:	<u>39° 3' 54.000"</u>	Longitude: <u>-89°</u> <u>23'</u> <u>44.100"</u>					
Surveyed By:Jeffrey D. Emrick	IL Registration #:035-003	3507					
Drilling Contractor: <u>Layne-Western Co</u>	Driller: <u>G. Mills</u>						
Consulting Firm: <u>Hanson Professional Services Inc.</u>	Geologist: <u>Rhonald W. H</u>	ologist: <u>Rhonald W. Hasenyager, LPG #196-000246</u>					
Drilling Method: Hollow stem auger	Drilling Fluid (Type):						
Logged By: <u>Rhonald W. Hasenyager</u>	Date Started:9/9/2009	Date Finished:9/10/2009					
Report Form Completed By: <u>Suzanna Simpson</u>	Date: 10/7/2009						
ANNULAR SPACE DETAILS	Elevations (MSL)*	Depths (0.01 ft.) (BGS)					
		<u>-2.99</u> Top of Protective Casing					
	625.57	-2.68 Top of Riser Pipe					
Type of Surface Seal: <u>Concrete</u>	<u>622.89</u>	0.00 Ground Surface					
Type of Annular Sealant: <u>High-solids bentonite</u>	619.89	3.00 Top of Annular Sealant					
Installation Method: <u>Tremie</u>							
Setting Time: >24 hr.	<u></u>	12.50 Static Water Level (After Completion) 9/21/2009					
Type of Bentonite Seal Granular Pellet Slurry							
(choose one) Installation Method: Gravity	616.16	6.73 Top of Seal					
Setting Time: 10 min	<u></u>	9.02 Top of Sand Pack					
Type of Sand Pack:Quartz sand							
Grain Size: <u>10/20</u> (sieve size)	<u></u>	9.96 Top of Screen					
Installation Method: <u>Gravity</u>	608.58	14.31 Bottom of Screen					
Type of Backfill Material:	608.10	14.79 Bottom of Well					
Installation Method:	606.89 * Referenced to a Na	16.00 Bottom of Borehole					
	Diameter of Borehole	NG MEASUREMENTS e (inches) 8.0					
WELL CONSTRUCTION MATERIALS (Choose one type of material for each area)	ID of Riser Pipe	(inches) 2.0					
	Protective Casing Ler						
Protective Casing SS304 SS316 PTFE PVC OTHER:	Riser Pipe Length	(feet) 12.64					
Riser Pipe Above W.T.         SS304         SS316         PTFE         PVC         OTHER:	Bottom of Screen to I Screen Length (1st s						
Riser Pipe Below W.T. SS304 SS316 PTFE PVC OTHER:	Total Length of Casir						
Screen SS304 SS316 PTFE (PVC) OTHER:	Screen Slot Size **	(inches) 0.010					

\*\*Hand-Slotted Well Screens Are Unacceptable

Illinois Environmental Protection Agency	Well Completio	Well Completion Report				
Site #: County:	ntgomery Well #:	3273				
Site Name: CCB Management Facility	Borehole #:	G273				
State Plane Coordinate: X 2,515,975.5 Y 874,235.2 (or) Latitude:	<u>39°</u> <u>3'</u> <u>53.900"</u> Longitude: <u>-89°</u> <u>2</u>	<u>23' 38.300"</u>				
Surveyed By:Jeffrey D. Emrick	IL Registration #:035-003507					
Drilling Contractor: <u>Layne-Western Co</u>	Driller: <u>G. Mills</u>					
Consulting Firm: <u>Hanson Professional Services Inc.</u>	Geologist: _ Rhonald W. Hasenyager, LPG #196-00	0246				
Drilling Method: <u>Hollow stem auger</u>	Drilling Fluid (Type):					
Logged By: <u>Rhonald W. Hasenyager</u>	Date Started:9/10/2009 Date Finished:9	/10/2009				
Report Form Completed By: <u>Suzanna Simpson</u>	Date:10/7/2009					
ANNULAR SPACE DETAILS	Elevations Depths (0.01 ft (MSL)* (BGS)	.)				
	<u></u>	ve Casing				
		pe				
Type of Surface Seal: Concrete	<u>620.17</u> <u>0.00</u> Ground Surface	<u>}</u>				
Type of Annular Sealant: <u>High-solids bentonite</u>	<u>617.17</u> <u>3.00</u> Top of Annular	Sealant				
Installation Method:						
Setting Time: >24 hr	$\underline{\nabla} \qquad \underline{610.28} \qquad \underline{9.89} \qquad \text{Static Water Le} \\ (After Completion)$					
Type of Bentonite Seal Granular Pellet Slurry						
Installation Method: Gravity	<u>614.07</u> <u>6.10</u> Top of Seal					
Setting Time: <u>10 min</u>	<u>612.45</u> <u>7.72</u> Top of Sand Pa	ck				
Type of Sand Pack:	611.00 0.08 Two of Gamers					
Grain Size: 10/20 (sieve size)	$\underbrace{\underline{611.09}}_{9.08} \underline{9.08} \text{ Top of Screen}$					
Installation Method: <u>Gravity</u>	605.61 14.56 Bottom of Scree	en				
Type of Backfill Material:	<u>605.07</u> <u>15.10</u> Bottom of Well					
Installation Method:	604.17 16.00 Bottom of Bore * Referenced to a National Geodetic Datum	hole				
	CASING MEASUREMENTS Diameter of Borehole (inches	s) 8.0				
WELL CONSTRUCTION MATERIALS (Choose one type of material for each area)	ID of Riser Pipe (inches					
	Protective Casing Length (fee					
Protective Casing SS304 SS316 PTFE PVC OTHER:	Riser Pipe Length (fee					
Riser Pipe Above W.T.         SS304         SS316         PTFE         PVC         OTHER:	Bottom of Screen to End Cap (fee Screen Length (1st slot to last slot) (fee	- 10				
Riser Pipe Below W.T. SS304 SS316 PTFE PVC OTHER:	Total Length of Casing (fee					
Screen SS304 SS316 PTFE PVC OTHER:	Screen Slot Size ** (inches					

\*\*Hand-Slotted Well Screens Are Unacceptable

Illinois Environmental Protection Agency			Well Completion Report			
Site #: County: _ Mon	tgomery	W	Vell #: G2	.76		
Site Name: CCB Management Facility		В	orehole #:	3276		
State Plane Coordinate: X_2,516,358.8 Y_874,438.6 (or) Latitude:	<u> </u>	Longitude	e: <u>-89°</u> 23	<u>' 33.400"</u>		
Surveyed By:Jeffrey D. Emrick	IL Registration #:035-0	03507				
Drilling Contractor: Layne-Western Co	Driller: <u>G. Mills</u>					
Consulting Firm: <u>Hanson Professional Services Inc.</u>	Geologist: <u>Rhonald W.</u>	Hasenyager	, LPG #196-0002	246		
Drilling Method: Hollow stem auger	Drilling Fluid (Type):					
Logged By: <u>Rhonald W. Hasenyager</u>	Date Started:9/16/20	<u>09</u> Date	e Finished: <u>9/1</u>	6/2009		
Report Form Completed By: <u>Suzanna Simpson</u>	Date: 10/7/2009					
ANNULAR SPACE DETAILS	Elevations (MSL)*	<b>Depths</b> (BGS)	(0.01 ft.)			
	632.40	. ,	Top of Protective	Casing		
	632.00	-2.86	Top of Riser Pipe			
Type of Surface Seal: <u>Concrete</u>	<u>629.14</u>	0.00	Ground Surface			
Type of Annular Sealant: <u>High-solids bentonite</u>	626.14	3.00	Top of Annular S	ealant		
Installation Method:						
Setting Time: _ >24 hr.	<u>603.59</u>	25.55	Static Water Leve (After Completion)			
Type of Bentonite Seal Granular Pellet Slurry (choose one)						
Installation Method: <u>Gravity</u>	610.06	19.08	Top of Seal			
Setting Time: <u>15 min</u>	608.11	21.03	Top of Sand Pack			
Type of Sand Pack: <u>Quartz sand</u> Grain Size: <u>10/20</u> (sieve size)	606.73	22.41	Top of Screen			
Installation Method: <u>Gravity</u> Type of Backfill Material: <u>Quartz sand</u>	<u>601.92</u> <u>601.49</u>	<u>27.22</u> 27.65	Bottom of Screen Bottom of Well			
(if applicable) Installation Method: Gravity	<u>601.14</u> * Referenced to a		Bottom of Boreho	le		
CASING MEASUREMENTS						
	Diameter of Boreho		(inches)	8.0		
WELL CONSTRUCTION MATERIALS (Choose one type of material for each area)	ID of Riser Pipe		(inches)	2.0		
	Protective Casing I	ength	(feet)	5.0		
Protective Casing SS304 SS316 PTFE PVC OTHER:	Riser Pipe Length           Bottom of Screen to	End Can	(feet)	<u>25.27</u> 0.43		
Riser Pipe Above W.T.         SS304         SS316         PTFE         PVC         OTHER:	Screen Length (1s			4.81		
Riser Pipe Below W.T.         SS304         SS316         PTFE         PVC         OTHER:	Total Length of Ca		(feet)	30.51		
Screen SS304 SS316 PTFE PVC OTHER:	Screen Slot Size **		(inches)	0.010		

\*\*Hand-Slotted Well Screens Are Unacceptable

Illinois Environmental Protection Agency			Well Completion Report				
Site #: County: Montgomery			W	/ell #:	G279		
Site Name: CCB Management		-				orehole #:	G279
State Plane Coordinate: X 2,516,245							
Surveyed By:Jeffrey D. Emric	k		IL Registra	ation #:035-0	03507		
Drilling Contractor: <u>Layne-We</u>	stern Co		Driller:	G. Mills			
Consulting Firm: <u>Hanson Profe</u>	essional Services Inc.			Rhonald W.			
Drilling Method: <u>Hollow stem</u>	auger		Drilling Fl	uid (Type):			
Logged By: <u>Rhonald W. Hase</u>	nyager		Date Starte	ed: <u>9/10/20</u>	)09 Date	e Finished:	9/10/2009
Report Form Completed By:Su	zanna Simpson		Date:	10/7/2009			
ANNULAR SPA	-			Elevations (MSL)*		(0.01	ft.)
				(MSL) <sup>1</sup> 632.33	· /	Top of Protec	tive Casing
					5.14_	Top of Plotec	live Casilig
			7	632.04	2.85	Top of Riser I	Pipe
Type of Surface Seal: <u>Concrete</u>		<u>a</u>		629.19	0.00	Ground Surfa	ce
Type of Annular Sealant: <u>High-s</u>	solids bentonite			626.19	3.00	Top of Annula	ar Sealant
Installation Method:							
				601.66	27.53	Static Water I	Level
						(After Completie	on) 9/21/2009
Type of Bentonite Seal Gram	ular Pellet Slurry (choose one)						
Installation Method: <u>Gravit</u>	у	<del>K X</del>	<del>KX</del>	610.45	18.74	Top of Seal	
Setting Time: <u>18 min</u>		X	×	_608.77_	20.42	Top of Sand H	Pack
Type of Cond Dealer O							
Type of Sand Pack: <u>Quartz sand</u>				606.79	22.40	Top of Screen	
Grain Size: <u>10/20</u> (sie							
Installation Method: <u>Gravit</u>	У			602.40	26.79	Bottom of Scr	een
Type of Backfill Material:Quar	tz Sand (if applicable)			604.51	24.68	Bottom of We	-11
Installation Method: Gravit				601.19	<b>27.3</b> 28.00	Bottom of Bo	rehole
	<u>,</u>				National Geodet		
				CAS	SING MEAS	SUREMENTS	3
			D	iameter of Boreh		(inch	
	TRUCTION MATERIALS e type of material for each area)			of Riser Pipe		(inch	es) 2.0
	,		Pı	otective Casing l	length	(fe	eet) 5.0
	1			iser Pipe Length		(fe	eet) 25.25
Protective Casing	SS304 SS316 PTFE PVC	OTHER:		ottom of Screen t			eet) 0.53
Riser Pipe Above W.T.		OTHER:		creen Length (1		t) (fe	eet) 4.39
Riser Pipe Below W.T.	SS304 SS316 PTFE PVC	OTHER:	Т	otal Length of Ca	sing	(fe	eet) 30.17

SS316 PTFE PVC OTHER:

SS304

## Well Completion Form (revised 02/06/02)

Screen

 Screen Slot Size \*\*


 \*\*Hand-Slotted Well Screens Are Unacceptable


0.010


(inches)


Illinois Enviro	onmental Protection Agency	7		Well	Completion	Report
Site #:	County: <u>N</u>	Iontgomery		W	/ell #:G2	280
Site Name:CCB Manageme	ent Facility			В	orehole #:	G280
State Plane Coordinate: X 2,515,6		le: <u>39°</u>	4' 2.000"	Longitud	e: <u>-89°</u> 23	<u>3' 42.000"</u>
Surveyed By:Jeffrey D. Em	rick	IL Registra	ation #: <u>035-0</u>	03507		
	Service Corp.	Driller:	B. Williamson			
Consulting Firm: <u>Hanson Press</u>	ofessional Services Inc.	Geologist:	Rhonald W.	Hasenyage	r, LPG #196-000	246
Drilling Method: <u>Hollow ste</u>	m auger	Drilling Fl	uid (Type):			
Logged By: <u>Suzanna Simps</u>	on	Date Starte	ed: <u>2/26/20</u>	08 Dat	e Finished:2/2	26/2008
Report Form Completed By:	Suzanna Simpson	Date:	2/29/2008			
ANNULAR SP	ACE DETAILS		Elevations (MSL)*	<b>Depths</b> (BGS)	(0.01 ft.)	
			625.79	-2.84	Top of Protective	Casing
			625.30	-2.35	-	C C
Type of Surface Seal: <u>Concrete</u>	·		622.95	0.00	Ground Surface	
True of Annular Scolanti Don	tomito china		620.85	2.10	Top of Annular S	lealant
Type of Annular Sealant: <u>Ben</u>						
	vity	I⊥	618.61	4.34	Static Water Leve	2
		×			(After Completion)	
Type of Bentonite Seal Gr	anular Pellet Slurry					
Installation Method:Grav	vity 📈	₹ <del>K.X</del>	620.85	2.10	Top of Seal	
Setting Time: <u>&gt;24 hr.</u>	X	1 🗖	611.75	11.20	Top of Sand Pack	c
Type of Sand Pack: <u>Quartz sa</u>	and					
Grain Size: <u>10/20</u>	(sieve size)		610.16	12.79	Top of Screen	
Installation Method:Grav	vity		(05.22	17 (2	D	
Type of Backfill Material: <u>n/a</u>			<u>605.32</u> <u>604.97</u>	<u>17.63</u> <u>17.98</u>	Bottom of Screen Bottom of Well	
In the life in Mathematic and	(if applicable)		604.97	17.09	Dettern of Devel	-1-
Installation Method: <u>n/a</u>			* Referenced to a	17.98 National Geodet	Bottom of Boreho ic Datum	ble
			CAS	SING MEA	SUREMENTS	
		D	iameter of Boreho	ole	(inches)	8.0
	NSTRUCTION MATERIALS one type of material for each area)	П	O of Riser Pipe		(inches)	2.0
		Pı	rotective Casing L	ength	(feet)	5.0
Protostivo Cosino	SS304 SS316 PTFE PVC OTHE		iser Pipe Length		(feet)	15.14
Protective Casing Riser Pipe Above W.T.	SS304         SS316         PTFE         PVC         OTHE           SS304         SS316         PTFE         (PVC)         OTHE		ottom of Screen to		(feet)	0.35
Riser Pipe Below W.T.	SS304 SS316 PTFE PVC OTHE	-	creen Length (1s		t) (feet) (feet)	4.84 20.33
Screen	SS304 SS316 PTFE PVC OTHE		creen Slot Size **		(inches)	0.010


APPENDIX C3 – MAPS OF THE DIRECTION OF GROUNDWATER FLOW

















d: Date/Time: 9/1/2017 4:55:10 P



d: Date/Time: 9/1/2017\_4-57-331







\_Coffeen\_GW\_Contours.mxd


















1/7/2020 12:16:43 PM




3Q\R2018\_3Q\_Coffeen\_GW\_Contours.mxd



4Q Coffeen GW Contours.mxd 4Q\R2018


#### LEGEND




**O'BRIEN & GERE ENGINEERS, INC.** 


Ν

1/7/2020 12:23:12 PM



1Q\R2019\_1Q\_Coffeen\_GW\_Contours.mxd





- NON-CCR RULE MONITORING WELL LOCATION
- ⊕ ABANDONED MONITORING WELL

GROUNDWATER ELEVATION CONTOUR (2-FT CONTOUR INTERVAL, NAVD88)

- - - INFERRED GROUNDWATER ELEVATION CONTOUR

#### GROUNDWATER FLOW DIRECTION

0 300 600 \_ Feet

#### SURFACE WATER FEATURE

#### NOTE:

\* = NOT USED FOR CONTOURING NM = NOT MEASURED <sup>1</sup> G307 WAS FROZEN DURING THE JANUARY 20, 2020 SAMPLING EVENT AND WATER LEVEL COULD NOT BE COLLECTED. <sup>2</sup> MW10S WAS DAMAGED PRIOR TO THE JANUARY 20, 2020 SAMPLING EVENT AND WATER LEVEL COULD NOT BE COLLECTED.

**GROUNDWATER ELEVATION CONTOUR MAP JANUARY 20, 2020** 

> RAMBOLL US CORPORATION A RAMBOLL COMPANY

#### **CCR RULE GROUNDWATER MONITORING**

COFFEEN POWER STATION COFFEEN, ILLINOIS



APPENDIX C4 – TABLES SUMMARIZING CONSTITUENT CONCENTRATIONS AT EACH MONITORING WELL

### Analytical Results - Appendix III Coffeen GMF Gypsum Stack Pond

Sample	Date	Boron, total	Calcium, total	Chloride, total	Fluoride, total	рН	Sulfate, total	Total Dissolved Solids
Location	Sampled	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(s.u.)	(mg/L)	(mg/L)
Background						· · · · ·		
G200	11/23/2015	0.39	100	75	0.337	7.2	94	520
G200	2/12/2016	0.014	150	93	0.415	7.2	97	540
G200	5/10/2016	<0.01	100	96	0.389	7.1	100	480
G200	7/30/2016	<0.01	88	82	0.384	7.1	100	520
G200	11/18/2016	0.010	88	75	0.431	7.2	110	520
G200	2/10/2017	<0.01	85	82	0.305	7.1	100	700
G200	5/18/2017	0.010	84	96	0.300	7.0	90	620
G200	7/13/2017	< 0.01	87	88	0.299	7.1	110	540
G200	10/28/2017	0.34	81	65	0.328	7.2	100	520
G200	1/25/2018	NA	NA	71	0.303	7.2	NA	NA
G200	5/11/2018	< 0.01	90	85	< 0.25	7.0	100	460
G200	11/2/2018	0.011	95	61	0.391	7.0	100	480
G200	1/16/2019	0.048	350	54	0.386	7.1	110	700
G200	8/12/2019	< 0.01	92	58	0.405	7.0	110	540
G200	1/21/2020	< 0.01	110	100	0.302	7.2	120	520
R201	11/23/2015	<0.01	85	37	0.377	7.3	150	560
R201	2/12/2016	0.014	120	75	0.398	7.0	240	740
R201	5/10/2016	< 0.01	120	85	0.447	7.0	260	840
R201	7/30/2016	< 0.01	120	85	0.368	7.1	260	750
R201	11/18/2016	< 0.01	81	39	0.494	7.2	160	580
R201	2/11/2017	< 0.01	100	79	0.285	7.1	230	900
R201	5/18/2017	0.011	120	74	0.354	7.2	300	820
R201	7/13/2017	0.010	120	81	0.284	7.0	250	780
R201	10/28/2017	0.017	93	30	0.380	7.1	89	660
R201	1/25/2018	NA	NA	31	0.338	7.0	NA	NA
R201	5/11/2018	<0.01	87	54	0.306	7.1	190	640
R201	11/2/2018	<0.01	82	24	0.419	7.1	110	470
R201	1/16/2019	<0.01	100	48	0.341	7.1	150	790
R201	8/12/2019	<0.01	120	71	0.466	7.1	220	760
R201	1/21/2020	0.010	130	66	0.309	7.2	210	770
Downgradier	nt Wells							
G206	11/18/2015	<0.01	79	32	0.433	7.1	95	460
G206	2/24/2016	0.033	78	26	0.507	6.7	150	500
G206	6/27/2016	<0.01	94	25	0.469	6.2	130	420
G206	8/6/2016	< 0.01	90	27	0.449	7.1	130	420
G206	11/22/2016	0.11	63	30	0.463	7.1	130	480
G206	2/11/2017	< 0.01	70	29	0.547	7.2	150	680
G206	5/18/2017	< 0.01	66	29	< 0.25	7.0	120	460
G206	7/15/2017	< 0.01	61	31	0.453	7.1	100	480
G206	10/30/2017	< 0.01	90	30	0.472	7.2	120	460
G206	5/15/2018	0.032	73	26	0.480	7.0	130	450
G206	11/2/2018	< 0.01	85	25	0.360	7.0	120	440
G206	1/17/2019	< 0.01	81	27	0.458	7.1	110	480
G206	8/14/2019	0.013	120	22	0.506	7.1	120	470
G206	1/21/2020	<0.01	84	24	0.389	7.5	120	470
G206	5/5/2020	NA	NA	NA	NA	7.5	NA	NA

### Analytical Results - Appendix III Coffeen GMF Gypsum Stack Pond

Sample Location	Date Sampled	Boron, total (mg/L)	Calcium, total (mg/L)	Chloride, total (mg/L)	Fluoride, total (mg/L)	рН (s.u.)	Sulfate, total (mg/L)	Total Dissolved Solids (mg/L)
G209	11/18/2015	< 0.01	160	67	0.398	7.0	280	810
G209	2/23/2016	< 0.01	150	70	0.475	7.0	280	760
G209	5/11/2016	< 0.01	160	59	0.461	7.1	280	800
G209	8/6/2016	0.014	160	67	0.468	7.2	270	760
G209	11/22/2016	0.015	100	70	0.420	7.1	270	750
G209	2/11/2017	< 0.01	120	60	0.358	7.0	260	960
G209	5/18/2017	<0.01	130	63	0.263	7.2	240	820
G209	7/15/2017	0.012	120	72	0.437	7.3	120	780
G209	10/31/2017	0.012	150	63	0.519	7.1	95	730
G209	1/25/2018	NA	120	NA	0.456	7.0	NA	NA
G209	5/15/2018	0.019	140	65	0.428	7.2	250	760
G209	11/2/2018	0.013	160	59	0.410	7.2	240	740
G209	1/17/2019	0.011	150	68	0.426	7.1	250	860
G209	5/3/2019	NA	150	NA	NA	7.7	NA	NA
G209	8/14/2019	0.011	160	61	0.586	7.2	240	830
G209	1/22/2020	0.017	150	59	0.406	6.9	250	730
G209	5/5/2020	NA	140	NA	NA	7.2	NA	NA
G212	11/18/2015	<0.01	55	38	0.340	7.2	54	380
G212	2/19/2016	< 0.01	58	41	0.339	7.3	59	380
G212	5/11/2016	< 0.01	58	37	0.421	7.3	59	400
G212	8/6/2016	0.016	59	37	0.369	7.3	55	330
G212	11/23/2016	<0.01	51	42	0.399	7.1	54	340
G212	2/15/2017	<0.01	53	37	0.369	7.1	55	420
G212	5/22/2017	<0.01	46	39	0.372	7.0	57	360
G212	7/15/2017	<0.01	46	44	0.377	7.6	53	430
G212	10/31/2017	<0.01	50	42	0.326	7.3	55	340
G212	5/14/2018	0.014	51	40	0.407	7.2	52	350
G212	11/2/2018	<0.01	53	43	0.289	7.3	49	600
G212	1/16/2019	<0.01	56	43	0.394	7.3	53	440
G212	8/14/2019	<0.01	53	43	0.437	7.3	51	380
G212	1/22/2020	0.012	61	42	0.283	7.2	58	340
G215	11/24/2015	0.037	110	47	0.340	7.2	110	500
G215	2/18/2016	0.027	100	52	0.359	7.2	130	520
G215	5/11/2016	0.026	89	43	0.463	6.9	110	460
G215	7/30/2016	0.015	89	47	0.432	6.9	110	480
G215	11/23/2016	0.023	68	48	0.429	6.9	100	500
G215	2/18/2017	0.021	86	46	0.369	7.3	110	510
G215	5/22/2017	0.024	82	42	<0.25	7.4	100	470
G215	7/15/2017	0.027	79	55	0.423	7.0	110	550
G215	10/31/2017	0.025	90	48	0.420	7.2	110	470
G215	5/15/2018	0.063	130	70	0.329	6.9	220	660
G215	11/2/2018	0.088	120	55	0.314	6.8	170	480
G215	1/16/2019	0.097	120	61	0.379	6.9	180	800
G215	8/14/2019	0.085	100	49	0.458	7.0	120	520
G215	1/22/2020	0.064	99	48	0.350	7.1	130	460

### Analytical Results - Appendix III Coffeen GMF Gypsum Stack Pond

Sample Location	Date Sampled	Boron, total (mg/L)	Calcium, total (mg/L)	Chloride, total (mg/L)	Fluoride, total (mg/L)	рН (s.u.)	Sulfate, total (mg/L)	Total Dissolved Solids (mg/L)
G218	11/24/2015	<0.01	120	99	0.300	7.1	94	620
G218	2/19/2016	<0.01	120	100	0.311	7.0	110	560
G218	5/10/2016	0.011	110	97	0.439	7.0	140	600
G218	7/30/2016	<0.01	130	100	0.382	7.0	120	620
G218	11/23/2016	<0.01	92	97	0.373	7.1	130	620
G218	2/18/2017	<0.01	110	88	0.308	7.2	130	630
G218	5/22/2017	<0.01	100	84	<0.25	7.1	140	600
G218	7/17/2017	<0.01	120	81	0.357	7.1	140	720
G218	10/31/2017	<0.01	110	91	0.437	6.9	140	660
G218	1/26/2018	NA	NA	NA	NA	6.9	NA	NA
G218	5/15/2018	0.014	110	91	0.413	7.0	140	640
G218	11/2/2018	<0.01	130	84	0.375	6.9	140	280
G218	1/17/2019	<0.01	120	82	0.361	7.0	140	600
G218	8/14/2019	<0.01	130	81	0.449	7.0	150	660
G218	1/22/2020	0.011	130	83	0.379	7.1	170	560

Notes:

1. Abbreviations: mg/L - milligrams per liter; NA - not analyzed; s.u. - standard units.

#### Analytical Results - Appendix IV Coffeen GMF Gypsum Stack Pond

Sample Location	Date Sampled	Antimony , total	Arsenic, total	Barium, total	Beryllium , total	Cadmium ,total	Chromium , total	Cobalt, total	Fluoride, total	Lead, total	Lithium, total	Mercury, total	Molybdenum , total	Radium- 226 + Radium 228, tot (pCi/L)	Selenium , total	Thallium, total
Background Wel		(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(poi/L)	(mg/L)	(mg/L)
G200	11/23/2015	< 0.003	0.0070	0.17	< 0.001	<0.001	0.012	0.0068	0.337	0.010	0.019	< 0.0002	0.0017	1.65	0.0041	< 0.001
G200	2/12/2016	< 0.003	0.0082	0.24	0.0013	< 0.001	0.013	0.0074	0.415	0.018	0.021	< 0.0002	< 0.001	3.84	0.0097	< 0.001
G200	5/10/2016	< 0.003	0.0025	0.13	< 0.001	< 0.001	0.0041	< 0.002	0.389	0.0058	< 0.01	< 0.0002	< 0.001	0.849	0.0071	< 0.001
G200	7/30/2016	< 0.003	< 0.001	0.059	< 0.001	< 0.001	0.0049	< 0.002	0.384	0.0012	< 0.01	< 0.0002	< 0.001	0.662	0.0032	< 0.001
G200	11/18/2016	< 0.003	< 0.001	0.053	< 0.001	< 0.001	< 0.004	< 0.002	0.431	< 0.001	< 0.01	< 0.0002	< 0.001	0.290	0.0032	< 0.001
G200	2/10/2017	< 0.003	<0.001	0.074	< 0.001	<0.001	0.0052	<0.002	0.305	0.0013	<0.01	< 0.0002	<0.001	0.534	0.0067	< 0.001
G200	5/18/2017	< 0.003	<0.001	0.063	< 0.001	< 0.001	<0.004	<0.002	0.300	< 0.001	<0.01	< 0.0002	<0.001	1.01	0.0062	< 0.001
G200	7/13/2017	< 0.003	<0.001	0.057	<0.001	<0.001	<0.004	<0.002	0.299	<0.001	<0.01	< 0.0002	<0.001	0.906	0.0034	<0.001
G200	10/28/2017	NA	NA	NA	NA	NA	NA	NA	0.328	NA	NA	NA	NA	NA	NA	NA
G200	1/25/2018	NA	NA	NA	NA	NA	NA	NA	0.303	NA	NA	NA	NA	NA	NA	NA
G200	5/11/2018	NA	NA	NA	NA	NA	NA	NA	<0.25	NA	NA	NA	NA	NA	NA	NA
G200	11/2/2018	NA	NA	NA	NA	NA	NA	NA	0.391	NA	NA	NA	NA	NA	NA	NA
G200	1/16/2019	NA	NA	NA	NA	NA	NA	NA	0.386	NA	NA	NA	NA	NA	NA	NA
G200	8/12/2019	NA	NA	NA	NA	NA	NA	NA	0.405	NA	NA	NA	NA	NA	NA	NA
G200	1/21/2020	NA	NA	NA	NA	NA	NA	NA	0.302	NA	NA	NA	NA	NA	NA	NA
R201	11/23/2015	<0.003	<0.001	0.078	<0.001	0.0012	<0.004	<0.002	0.377	<0.001	<0.01	<0.0002	0.0069	0.202	<0.001	<0.001
R201	2/12/2016	< 0.003	0.010	0.084	0.0067	<0.001	<0.004	<0.002	0.398	<0.001	<0.01	<0.0002	0.0010	0.543	0.0091	<0.001
R201	5/10/2016	< 0.003	<0.001	0.084	<0.001	<0.001	<0.004	<0.002	0.447	<0.001	<0.01	<0.0002	<0.001	1.12	<0.001	<0.001
R201	7/30/2016	< 0.003	0.0031	0.092	<0.001	<0.001	<0.004	<0.002	0.368	<0.001	<0.01	<0.0002	<0.001	0.697	<0.001	<0.001
R201	11/18/2016	< 0.003	0.0013	0.058	< 0.001	< 0.001	< 0.004	< 0.002	0.494	< 0.001	< 0.01	< 0.0002	< 0.001	0.055	< 0.001	< 0.001
R201	2/11/2017	< 0.003	0.0028	0.086	< 0.001	< 0.001	< 0.004	< 0.002	0.285	< 0.001	< 0.01	< 0.0002	< 0.001	1.02	< 0.001	< 0.001
R201	5/18/2017	< 0.003	0.0023	0.087	< 0.001	< 0.001	< 0.004	< 0.002	0.354	< 0.001	< 0.01	< 0.0002	< 0.001	1.51	< 0.001	< 0.001
R201	7/13/2017	< 0.003	0.0037	0.17	< 0.001	< 0.001	< 0.004	<0.002	0.284	<0.001	< 0.01	< 0.0002	< 0.001	2.75	< 0.001	< 0.001
R201 R201	10/28/2017	NA NA	NA NA	NA NA	NA NA	NA NA	NA NA	NA NA	0.380	NA NA	NA NA	NA NA	NA NA	NA NA	NA NA	NA NA
R201	1/25/2018 5/11/2018	NA	NA	NA	NA	NA	NA	NA	0.338	NA	NA	NA	NA NA	NA	NA	NA
R201	11/2/2018	NA	NA	NA	NA	NA	NA	NA	0.300	NA	NA	NA	NA	NA	NA	NA
R201	1/16/2019	NA	NA	NA	NA	NA	NA	NA	0.419	NA	NA	NA	NA	NA	NA	NA
R201	8/12/2019	NA	NA	NA	NA	NA	NA	NA	0.466	NA	NA	NA	NA	NA	NA	NA
R201	1/21/2020	NA	NA	NA	NA	NA	NA	NA	0.309	NA	NA	NA	NA	NA	NA	NA
Downgradient W		101		101	101	101	10.	101	0.000		101	101	101	101	101	101
G206	11/18/2015	< 0.003	0.0039	0.062	< 0.001	<0.001	0.0041	< 0.002	0.433	< 0.001	<0.01	< 0.0002	< 0.001	0.317	< 0.001	< 0.001
G206	2/24/2016	< 0.003	<0.000	0.056	< 0.001	<0.001	< 0.004	<0.002	0.507	< 0.001	<0.01	< 0.0002	0.0014	0.292	<0.001	< 0.001
G206	6/27/2016	< 0.003	0.0012	0.062	< 0.001	< 0.001	< 0.004	<0.002	0.469	< 0.001	< 0.01	< 0.0002	0.0025	0.647	< 0.001	< 0.001
G206	8/6/2016	< 0.003	0.0020	0.064	< 0.001	< 0.001	0.0042	<0.002	0.449	0.0022	< 0.01	< 0.0002	0.0024	0.857	< 0.001	< 0.001
G206	11/22/2016	< 0.003	< 0.001	0.048	< 0.001	< 0.001	< 0.004	<0.002	0.463	< 0.001	< 0.01	< 0.0002	0.0015	NA	< 0.001	< 0.001
G206	12/7/2016	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.62	NA	NA
G206	2/11/2017	< 0.003	< 0.001	0.052	< 0.001	< 0.001	< 0.004	<0.002	0.547	< 0.001	< 0.01	< 0.0002	0.0013	1.20	< 0.001	< 0.001
G206	5/18/2017	< 0.003	< 0.001	0.043	< 0.001	< 0.001	< 0.004	< 0.002	<0.25	< 0.001	< 0.01	< 0.0002	0.0011	0.555	< 0.001	< 0.001
G206	7/15/2017	< 0.003	0.0019	0.055	<0.001	<0.001	<0.004	<0.002	0.453	<0.001	<0.01	<0.0002	<0.001	1.33	<0.001	<0.001
G206	10/30/2017	NA	NA	NA	NA	NA	NA	NA	0.472	NA	NA	NA	NA	NA	NA	NA
G206	5/15/2018	NA	NA	NA	NA	NA	NA	NA	0.480	NA	NA	NA	NA	NA	NA	NA
G206	11/2/2018	NA	NA	NA	NA	NA	NA	NA	0.360	NA	NA	NA	NA	NA	NA	NA
G206	1/17/2019	NA	NA	NA	NA	NA	NA	NA	0.458	NA	NA	NA	NA	NA	NA	NA
G206	8/14/2019	NA	NA	NA	NA	NA	NA	NA	0.506	NA	NA	NA	NA	NA	NA	NA
G206	1/21/2020	NA	NA	NA	NA	NA	NA	NA	0.389	NA	NA	NA	NA	NA	NA	NA

#### Analytical Results - Appendix IV Coffeen GMF Gypsum Stack Pond

Sample Location	Date Sampled	Antimony , total	Arsenic, total	Barium, total	Beryllium , total	Cadmium ,total	Chromium , total	Cobalt, total	Fluoride, total	Lead, total (mg/L)	Lithium, total	Mercury, total	Molybdenum , total	Radium- 226 + Radium 228, tot (pCi/L)	Selenium , total	total
	11/18/2015	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L) <0.001	(mg/L)	(mg/L)	(mg/L)	u /	(mg/L)	(mg/L)
G209		< 0.003	0.0021	0.072	<0.001 <0.001	< 0.001	<0.004 <0.004	<0.002	0.398		<0.01 <0.01	< 0.0002	0.0023	0.469	0.0036	< 0.001
G209 G209	2/23/2016 5/11/2016	<0.003 <0.003	< 0.001	0.066	<0.001	<0.001 <0.001	<0.004	<0.002	0.475 0.461	<0.001 <0.001	< 0.01	<0.0002 <0.0002	0.0015	0.903	<0.001 <0.001	<0.001 <0.001
G209 G209	8/6/2016	< 0.003	0.0017	0.061	<0.001	<0.001	<0.004	<0.002	0.461	<0.001	<0.01	<0.0002	0.0013	0.673	<0.001	<0.001
G209 G209	11/22/2016	< 0.003	0.0017	0.005	<0.001	<0.001	<0.004	<0.002	0.400	<0.001	<0.01	<0.0002	< 0.0018	0.832	< 0.001	<0.001
G209 G209	2/11/2017	< 0.003	< 0.0022	0.045	<0.001	<0.001	<0.004	<0.002	0.420	<0.001	< 0.01	<0.0002	0.0027	0.832	< 0.001	<0.001
G209 G209	5/18/2017	< 0.003	0.0029	0.07	<0.001	<0.001	<0.004	<0.002	0.358	0.0012	< 0.01	<0.0002	0.0027	1.31	<0.001	0.001
G209	7/15/2017	<0.003	0.0023	0.063	<0.001	<0.001	<0.004	<0.002	0.437	<0.0012	<0.01	<0.0002	< 0.001	0.602	<0.001	< 0.001
G209	10/31/2017	NA	NA	0.003 NA	NA	NA	NA	×0.002 NA	0.519	NA	NA	NA	NA	NA	NA	NA
G209	1/25/2018	NA	NA	NA	NA	NA	NA	NA	0.456	NA	NA	NA	NA	NA	NA	NA
G209	5/15/2018	NA	NA	NA	NA	NA	NA	NA	0.428	NA	NA	NA	NA	NA	NA	NA
G209	11/2/2018	NA	NA	NA	NA	NA	NA	NA	0.410	NA	NA	NA	NA	NA	NA	NA
G209	1/17/2019	NA	NA	NA	NA	NA	NA	NA	0.426	NA	NA	NA	NA	NA	NA	NA
G209	8/14/2019	NA	NA	NA	NA	NA	NA	NA	0.586	NA	NA	NA	NA	NA	NA	NA
G209	1/22/2020	NA	NA	NA	NA	NA	NA	NA	0.406	NA	NA	NA	NA	NA	NA	NA
G212	11/18/2015	< 0.003	< 0.001	0.052	<0.001	< 0.001	< 0.004	<0.002	0.340	< 0.001	< 0.01	< 0.0002	0.0015	0.132	0.0037	< 0.001
G212	2/19/2016	< 0.003	<0.001	0.002	<0.001	<0.001	< 0.004	<0.002	0.339	<0.001	<0.01	< 0.0002	< 0.001	0.582	0.0048	<0.001
G212	5/11/2016	< 0.003	< 0.001	0.05	< 0.001	< 0.001	< 0.004	<0.002	0.421	< 0.001	<0.01	< 0.0002	< 0.001	0.759	0.0041	< 0.001
G212	8/6/2016	< 0.003	< 0.001	0.059	< 0.001	< 0.001	0.004	<0.002	0.369	0.0016	< 0.01	< 0.0002	0.0012	0.992	0.004	< 0.001
G212	11/23/2016	< 0.003	< 0.001	0.049	< 0.001	< 0.001	< 0.004	<0.002	0.399	< 0.001	< 0.01	< 0.0002	< 0.001	NA	0.0043	< 0.001
G212	12/7/2016	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.64	NA	NA
G212	2/15/2017	< 0.003	0.0010	0.058	<0.001	< 0.001	< 0.004	< 0.002	0.369	0.001	< 0.01	< 0.0002	< 0.001	0.488	0.0041	< 0.001
G212	5/22/2017	< 0.003	< 0.001	0.061	< 0.001	< 0.001	< 0.004	< 0.002	0.372	< 0.001	< 0.01	< 0.0002	0.0011	0.729	0.0039	< 0.001
G212	7/15/2017	< 0.003	< 0.001	0.052	< 0.001	< 0.001	< 0.004	< 0.002	0.377	< 0.001	< 0.01	< 0.0002	< 0.001	0.654	0.0046	< 0.001
G212	10/31/2017	NA	NA	NA	NA	NA	NA	NA	0.326	NA	NA	NA	NA	NA	NA	NA
G212	5/14/2018	NA	NA	NA	NA	NA	NA	NA	0.407	NA	NA	NA	NA	NA	NA	NA
G212	11/2/2018	NA	NA	NA	NA	NA	NA	NA	0.289	NA	NA	NA	NA	NA	NA	NA
G212	1/16/2019	NA	NA	NA	NA	NA	NA	NA	0.394	NA	NA	NA	NA	NA	NA	NA
G212	8/14/2019	NA	NA	NA	NA	NA	NA	NA	0.437	NA	NA	NA	NA	NA	NA	NA
G212	1/22/2020	NA	NA	NA	NA	NA	NA	NA	0.283	NA	NA	NA	NA	NA	NA	NA
G215	11/24/2015	< 0.003	0.11	0.23	<0.001	<0.001	< 0.004	0.0028	0.340	0.0039	<0.01	< 0.0002	0.0011	2.42	<0.001	<0.001
G215	2/18/2016	< 0.003	0.0034	0.095	<0.001	<0.001	< 0.004	<0.002	0.359	<0.001	<0.01	< 0.0002	< 0.001	0.852	< 0.001	< 0.001
G215	5/11/2016	0.0045	0.0068	0.088	< 0.001	< 0.001	< 0.004	<0.002	0.463	<0.001	< 0.01	< 0.0002	<0.001	0.468	0.0024	< 0.001
G215	7/30/2016	< 0.003	0.013	0.096	<0.001	<0.001	< 0.004	<0.002	0.432	<0.001	<0.01	< 0.0002	<0.001	0.0216	<0.001	<0.001
G215	11/23/2016	< 0.003	0.0086	0.082	<0.001	<0.001	< 0.004	<0.002	0.429	<0.001	<0.01	<0.0002	<0.001	NA	<0.001	<0.001
G215	12/7/2016	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.58	NA	NA
G215	2/18/2017	< 0.003	0.012	0.095	<0.001	<0.001	<0.004	<0.002	0.369	<0.001	<0.01	<0.0002	<0.001	0.344	<0.001	<0.001
G215	5/22/2017	< 0.003	0.036	0.15	<0.001	<0.001	<0.004	<0.002	<0.25	<0.001	<0.01	<0.0002	<0.001	1.24	<0.001	<0.001
G215	7/15/2017	< 0.003	0.044	0.13	<0.001	<0.001	<0.004	<0.002	0.423	<0.001	<0.01	<0.0002	<0.001	1.01	<0.001	<0.001
G215	10/31/2017	NA	NA	NA	NA	NA	NA	NA	0.420	NA	NA	NA	NA	NA	NA	NA
G215	5/15/2018	NA	NA	NA	NA	NA	NA	NA	0.329	NA	NA	NA	NA	NA	NA	NA
G215	11/2/2018	NA	NA	NA	NA	NA	NA	NA	0.314	NA	NA	NA	NA	NA	NA	NA
G215	1/16/2019	NA	NA	NA	NA	NA	NA	NA	0.379	NA	NA	NA	NA	NA	NA	NA
G215	8/14/2019	NA	NA	NA	NA	NA	NA	NA	0.458	NA	NA	NA	NA	NA	NA	NA
G215	1/22/2020	NA	NA	NA	NA	NA	NA	NA	0.350	NA	NA	NA	NA	NA	NA	NA

#### Analytical Results - Appendix IV Coffeen GMF Gypsum Stack Pond

Sample Location	Date Sampled	Antimony , total (mg/L)	Arsenic, total (mg/L)	Barium, total (mg/L)	Beryllium , total (mg/L)	Cadmium ,total (mg/L)	Chromium , total (mg/L)	Cobalt, total (mg/L)	Fluoride, total (mg/L)	Lead, total (mg/L)	Lithium, total (mg/L)	Mercury, total (mg/L)	Molybdenum , total (mg/L)	Radium- 226 + Radium 228, tot (pCi/L)	Selenium , total (mg/L)	Thallium, total (mg/L)
G218	11/24/2015	< 0.003	0.0084	0.17	< 0.001	<0.001	0.01	< 0.002	0.300	< 0.001	<0.01	< 0.0002	0.0015	1.23	< 0.001	<0.001
G218	2/19/2016	< 0.003	0.0018	0.15	< 0.001	< 0.001	< 0.004	< 0.002	0.311	< 0.001	< 0.01	< 0.0002	< 0.001	1.28	< 0.001	< 0.001
G218	5/10/2016	< 0.003	0.0015	0.14	< 0.001	<0.001	<0.004	<0.002	0.439	<0.001	<0.01	<0.0002	<0.001	0.601	< 0.001	<0.001
G218	7/30/2016	< 0.003	0.0011	0.15	< 0.001	<0.001	<0.004	<0.002	0.382	<0.001	<0.01	<0.0002	<0.001	0.543	< 0.001	<0.001
G218	11/23/2016	< 0.003	0.0014	0.13	< 0.001	<0.001	<0.004	<0.002	0.373	<0.001	<0.01	<0.0002	<0.001	NA	< 0.001	< 0.001
G218	2/18/2017	< 0.003	0.0011	0.13	< 0.001	<0.001	<0.004	<0.002	0.308	<0.001	<0.01	<0.0002	<0.001	0.779	< 0.001	<0.001
G218	5/22/2017	< 0.003	<0.001	0.15	< 0.001	<0.001	<0.004	<0.002	<0.25	<0.001	<0.01	<0.0002	<0.001	0.975	<0.001	<0.001
G218	7/17/2017	< 0.003	<0.001	0.14	< 0.001	<0.001	<0.004	<0.002	0.357	<0.001	<0.01	< 0.0002	<0.001	0.704	< 0.001	< 0.001
G218	10/31/2017	NA	NA	NA	NA	NA	NA	NA	0.437	NA	NA	NA	NA	NA	NA	NA
G218	5/15/2018	NA	NA	NA	NA	NA	NA	NA	0.413	NA	NA	NA	NA	NA	NA	NA
G218	11/2/2018	NA	NA	NA	NA	NA	NA	NA	0.375	NA	NA	NA	NA	NA	NA	NA
G218	1/17/2019	NA	NA	NA	NA	NA	NA	NA	0.361	NA	NA	NA	NA	NA	NA	NA
G218	8/14/2019	NA	NA	NA	NA	NA	NA	NA	0.449	NA	NA	NA	NA	NA	NA	NA
G218	1/22/2020	NA	NA	NA	NA	NA	NA	NA	0.379	NA	NA	NA	NA	NA	NA	NA

Notes:

1. Abbreviations: mg/L - milligrams per liter; NA - not analyzed; pCi/L - picocurie per liter;

### Analytical Results - Appendix III Coffeen GMF Recycle Pond

Sample	Date	Boron, total	Calcium, total	Chloride, total	Fluoride, total	рН	Sulfate, total	Total Dissolved Solids
Location	Sampled	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(s.u.)	(mg/L)	(mg/L)
Background	Wells							
G270	11/20/2015	<0.01	59	12	0.362	6.8	89	400
G270	2/10/2016	<0.01	49	16	0.472	6.7	77	340
G270	5/12/2016	<0.01	57	12	0.460	7.0	76	340
G270	8/1/2016	<0.01	50	15	0.397	7.0	76	360
G270	11/16/2016	0.018	48	12	0.327	7.1	63	450
G270	2/10/2017	<0.01	53	11	0.364	7.1	55	390
G270	5/16/2017	<0.01	54	9.7	0.358	7.2	50	380
G270	7/12/2017	<0.01	52	12	0.338	7.0	54	400
G270	10/25/2017	0.011	56	13	0.338	7.1	55	400
G270	5/11/2018	<0.01	53	7.9	0.270	7.1	53	400
G270	8/3/2018	<0.01	57	8.6	0.360	7.1	54	420
G270	1/21/2019	<0.01	56	9.6	0.375	7.0	49	480
G270	8/15/2019	<0.01	54	9.8	0.461	7.1	50	470
G270	1/24/2020	0.015	59	10	0.383	7.3	51	480
G280	11/24/2015	0.029	120	54	0.343	7.4	94	460
G280	2/10/2016	<0.01	60	52	0.466	6.5	84	400
G280	5/10/2016	<0.01	63	50	0.429	7.2	80	350
G280	8/3/2016	<0.01	65	46	0.397	7.2	55	350
G280	11/20/2016	<0.01	63	49	0.473	7.1	67	430
G280	2/15/2017	<0.01	64	46	0.362	7.0	94	440
G280	5/20/2017	<0.01	54	44	0.348	7.2	84	420
G280	7/18/2017	<0.01	67	46	0.378	7.3	58	400
G280	11/4/2017	0.013	63	48	0.490	7.2	57	350
G280	5/16/2018	<0.01	57	43	0.288	7.2	52	360
G280	8/10/2018	<0.01	62	55	0.414	7.1	63	400
G280	1/22/2019	0.026	82	52	0.373	7.1	69	500
G280	8/26/2019	0.011	72	60	0.438	7.1	81	480
G280	1/23/2020	0.015	73	64	0.486	7.7	84	1100
Downgradien	t Wells							
G271	11/23/2015	0.50	130	38	0.347	7.3	420	860
G271	2/16/2016	0.61	130	38	0.414	7.5	440	1000
G271	5/12/2016	0.98	170	39	0.472	7.2	540	940
G271	8/5/2016	0.63	110	37	0.414	7.2	440	840
G271	11/21/2016	0.40	110	29	0.484	7.2	400	910
G271	2/11/2017	0.71	100	30	0.392	7.2	430	1100
G271	5/20/2017	0.65	110	28	<0.25	7.1	390	870
G271	7/17/2017	0.58	110	29	0.466	7.1	380	950
G271	11/4/2017	0.67	100	24	0.426	7.3	360	820
G271	5/16/2018	0.41	76	38	0.602	7.3	330	820
G271	8/10/2018	0.45	86	32	0.439	7.1	470	880
G271	1/22/2019	0.88	100	21	0.530	7.2	420	770
G271	8/26/2019	0.78	100	21	0.570	7.2	340	690
G271	1/22/2020	2.5	180	51	0.278	7.2	610	1100

### Analytical Results - Appendix III Coffeen GMF Recycle Pond

Sample	Date	Boron, total	Calcium, total	Chloride, total	Fluoride, total	рН	Sulfate, total	Total Dissolved Solids
Location	Sampled	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(s.u.)	(mg/L)	(mg/L)
G273	11/24/2015	0.20	140	41	<0.25	7.1	420	890
G273	2/16/2016	0.42	150	45	0.388	7.2	550	1100
G273	5/12/2016	0.29	170	44	0.537	7.0	520	980
G273	8/5/2016	0.17	120	46	0.294	7.1	400	840
G273	11/21/2016	0.15	140	48	0.39	7.3	440	900
G273	2/15/2017	0.18	140	47	0.288	6.9	470	990
G273	5/20/2017	0.11	130	51	<0.25	7.1	390	890
G273	7/17/2017	0.066	140	48	0.333	7.3	360	920
G273	11/4/2017	0.079	120	50	0.333	7.0	380	820
G273	5/16/2018	0.25	160	50	0.390	7.2	490	1100
G273	8/10/2018	0.12	140	53	0.367	7.1	460	940
G273	1/22/2019	0.40	170	54	0.462	7.1	590	1300
G273	8/26/2019	0.14	150	59	0.432	7.0	440	1000
G273	1/22/2020	0.18	170	59	0.252	7.1	510	1000
G276	11/24/2015	0.043	120	28	0.345	7.3	190	710
G276	2/16/2016	0.021	120	23	0.456	7.2	230	760
G276	5/12/2016	<0.01	130	22	0.441	7.1	230	660
G276	8/3/2016	0.019	110	23	0.443	7.2	19	680
G276	11/21/2016	< 0.01	120	23	0.445	7.1	210	720
G276	2/17/2017	0.014	110	23	0.358	7.2	200	680
G276	5/20/2017	0.020	110	22	<0.25	7.0	220	750
G276	7/18/2017	0.011	130	23	0.395	7.2	220	780
G276	11/4/2017	0.023	120	20	0.431	7.1	210	720
G276	5/16/2018	0.021	110	24	0.466	7.1	220	740
G276	8/10/2018	0.017	120	24	0.399	7.1	230	760
G276	1/22/2019	0.027	120	26	0.421	7.1	240	860
G276	8/26/2019	0.028	140	21	0.443	7.2	260	880
G276	1/23/2020	0.037	140	25	0.255	7.0	270	1400
G279	11/24/2015	0.63	140	61	0.334	7.2	520	1100
G279	2/16/2016	0.23	180	130	0.386	7.2	610	1400
G279	5/13/2016	0.042	120	18	0.608	6.9	230	600
G279	8/3/2016	0.24	210	110	0.394	7.1	570	1300
G279	11/22/2016	0.49	170	130	0.272	7.2	720	1300
G279	2/15/2017	0.35	210	120	0.263	7.1	700	1500
G279 G279	5/20/2017	0.18	150	57	0.200	7.0	370	940
G279	7/18/2017	0.10	240	130	0.282	7.3	730	1600
G279	11/4/2017	0.42	240	170	0.507	7.2	870	1600
G279 G279	5/16/2018	0.37	180	76	0.492	7.1	540	1200
G279 G279	8/10/2018	0.53	250	160	0.492	7.1	940	1200
G279 G279	1/23/2019	0.021	120	7.3	0.427	7.1	240	740
G279 G279	8/26/2019	0.021	120	4.7	0.635	7.0	170	560
G279 G279	1/23/2020	0.048	120	4.7	0.635	7.0	400	830
9219	1/23/2020	0.33	190	12	0.007	1.0	400	030

Notes:

1. Abbreviations: mg/L - milligrams per liter; s.u. - standard units.

#### Analytical Results - Appendix IV Coffeen GMF Recycle Pond

Sample	Date	Antimony , total	Arsenic, total	Barium, total	Beryllium , total	Cadmium ,total	Chromium , total	Cobalt, total	Fluoride, total	Lead, total	Lithium, total	Mercury, total	Molybdenum , total	Radium- 226 + Radium 228, tot	Selenium , total	Thallium, total
Location	Sampled	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(pCi/L)	(mg/L)	(mg/L)
Background Wel	lls															
G270	11/20/2015	< 0.003	0.001	0.045	<0.001	<0.001	< 0.004	<0.002	0.362	0.0015	<0.01	< 0.0002	0.001	0.522	<0.001	<0.001
G270	2/10/2016	< 0.003	<0.001	0.032	<0.001	<0.001	< 0.004	<0.002	0.472	<0.001	<0.01	< 0.0002	<0.001	0.721	0.0012	<0.001
G270	5/12/2016	< 0.003	<0.001	0.034	<0.001	<0.001	< 0.004	<0.002	0.460	<0.001	<0.01	<0.0002	0.001	0.422	0.0012	<0.001
G270	8/1/2016	< 0.003	<0.001	0.037	<0.001	<0.001	< 0.004	<0.002	0.397	<0.001	<0.01	<0.0002	< 0.001	0.997	<0.001	<0.001
G270	11/16/2016	< 0.003	<0.001	0.031	<0.001	<0.001	<0.004	<0.002	0.327	<0.001	<0.01	<0.0002	<0.001	0.109	<0.001	<0.001
G270	2/10/2017	< 0.003	<0.001	0.036	<0.001	<0.001	< 0.004	<0.002	0.364	<0.001	<0.01	<0.0002	<0.001	0.620	<0.001	<0.001
G270	5/16/2017	< 0.003	<0.001	0.033	<0.001	<0.001	<0.004	<0.002	0.358	<0.001	<0.01	<0.0002	<0.001	1.52	<0.001	<0.001
G270	7/12/2017	< 0.003	<0.001	0.035	<0.001	<0.001	<0.004	<0.002	0.338	<0.001	<0.01	<0.0002	<0.001	0.413	<0.001	<0.001
G270	5/11/2018	< 0.003	<0.001	0.038	<0.001	<0.001	< 0.004	<0.002	0.270	<0.001	<0.01	<0.0002	0.0014	NA	<0.001	<0.001
G270	5/30/2018	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.283	NA	NA
G270	8/3/2018	NA	<0.001	0.036	NA	<0.001	<0.004	<0.002	0.360	<0.001	<0.01	NA	<0.001	0.990	NA	NA
G270	1/21/2019	< 0.003	<0.001	0.047	<0.001	<0.001	0.0043	<0.002	0.375	0.0013	<0.01	<0.0002	<0.001	0.651	<0.001	<0.001
G270	8/15/2019	NA	<0.001	0.040	<0.001	<0.001	< 0.004	<0.002	0.461	<0.001	0.012	NA	<0.001	1.34	<0.001	NA
G270	1/24/2020	< 0.003	<0.001	0.038	<0.001	<0.001	<0.004	<0.002	0.383	<0.001	<0.02	<0.0002	<0.001	0.471	0.0014	<0.001
G280	11/24/2015	< 0.003	0.0066	0.11	<0.001	<0.001	0.019	0.0059	0.343	0.012	0.019	< 0.0002	0.0045	1.39	0.0032	<0.001
G280	2/10/2016	< 0.003	< 0.001	0.045	< 0.001	< 0.001	< 0.004	<0.002	0.466	0.0011	<0.01	< 0.0002	0.0015	0.745	0.0029	< 0.001
G280	5/10/2016	< 0.003	<0.001	0.045	<0.001	<0.001	< 0.004	<0.002	0.429	<0.001	<0.01	< 0.0002	0.0014	0.666	0.0044	<0.001
G280	8/3/2016	< 0.003	< 0.001	0.045	< 0.001	< 0.001	< 0.004	< 0.002	0.397	0.0014	< 0.01	< 0.0002	0.0016	1.75	0.0048	< 0.001
G280	11/20/2016	< 0.003	< 0.001	0.044	< 0.001	< 0.001	< 0.004	<0.002	0.473	< 0.001	< 0.01	< 0.0002	0.0014	0.613	0.0034	< 0.001
G280	5/20/2017	< 0.003	< 0.001	0.042	< 0.001	< 0.001	< 0.004	< 0.002	0.348	< 0.001	< 0.01	< 0.0002	0.0013	1.10	0.0026	< 0.001
G280	7/18/2017	< 0.003	< 0.001	0.041	< 0.001	< 0.001	< 0.004	< 0.002	0.378	< 0.001	< 0.01	< 0.0002	0.0012	0.572	0.0034	< 0.001
G280	5/16/2018	< 0.003	0.0011	0.038	< 0.001	<0.001	< 0.004	<0.002	0.288	0.0011	< 0.01	< 0.0002	0.0012	NA	0.0042	<0.001
G280	5/31/2018	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA 10.01	NA	NA <0.001	0.397	NA 0.0022	NA
G280 G280	8/10/2018 1/22/2019	NA <0.003	< 0.001	0.038	NA <0.001	NA <0.001	NA 0.011	NA 0.0033	0.414	< 0.001	<0.01 <0.01	NA <0.0002	0.001	0.634	0.0022	NA <0.001
G280 G280		<0.003 NA	0.0035	0.070	<0.001 NA	<0.001 NA	<0.001	<0.0033	0.373 0.438	0.0061	< 0.01		0.0016	1.283 1.01	<0.0029	<0.001 NA
G280 G280	8/26/2019 1/23/2020	NA <0.003	<0.001	0.045	<0.001	NA <0.001	<0.004	<0.002	0.438	<0.001 <0.001	< 0.01	NA <0.0002	0.0014	0.484	<0.001 0.0012	<0.001
		<0.003	<b>\0.001</b>	0.041	<0.001	<b>NU.001</b>	<0.004	<b>NU.002</b>	0.400	<b>NU.001</b>	<b>NU.UZ</b>	<b>NU.0002</b>	0.0015	0.404	0.0012	<b>NU.001</b>
Downgradient W												·				
G271	11/23/2015	< 0.003	<0.001	0.031	<0.001	<0.001	<0.004	<0.002	0.347	0.0012	<0.01	<0.0002	0.0012	0.889	0.0024	<0.001
G271	2/16/2016	< 0.003	<0.001	0.028	<0.001	<0.001	<0.004	<0.002	0.414	<0.001	<0.01	<0.0002	<0.001	1.02	0.0018	<0.001
G271	5/12/2016	< 0.003	<0.001	0.028	<0.001	<0.001	<0.004	<0.002	0.472	<0.001	<0.01	<0.0002	<0.001	0.228	0.0021	<0.001
G271	8/5/2016	< 0.003	< 0.001	0.032	< 0.001	< 0.001	< 0.004	< 0.002	0.414	0.0027	< 0.01	< 0.0002	< 0.001	0.268	0.0022	< 0.001
G271	11/21/2016	< 0.003	< 0.001	0.031	< 0.001	< 0.001	< 0.004	< 0.002	0.484	< 0.001	< 0.01	< 0.0002	< 0.001	0.296	0.0029	< 0.001
G271	2/11/2017	< 0.003	< 0.001	0.027	< 0.001	< 0.001	< 0.004	< 0.002	0.392	< 0.001	< 0.01	< 0.0002	< 0.001	0.481	0.0025	< 0.001
G271	5/20/2017	< 0.003	0.0017	0.029	0.0021	0.0013	0.0053	0.0022	< 0.25	0.0024	< 0.01	< 0.0002	0.0031	0.652	0.0044	0.0021
G271	7/17/2017	< 0.003	< 0.001	0.028	< 0.001	<0.001	<0.004	<0.002	0.466	<0.001	< 0.01	< 0.0002	<0.001	0.737	0.0023	<0.001
G271	11/4/2017	NA (0.002)	NA 10.001	NA	NA	NA	NA 10.001	NA	0.426	NA	NA 10.01	NA	NA	NA	NA	NA 10.001
G271	5/16/2018	<0.003	<0.001	0.021	<0.001	<0.001	<0.004	<0.002	0.602	<0.001	<0.01	<0.0002	0.0015	NA 0.878	0.0025	<0.001
G271	5/31/2018	NA	NA	NA 0.024	NA	NA	NA	NA	NA 0.420	NA	NA	NA	NA		NA	NA
G271	8/10/2018	NA 10.002	< 0.001	0.024	NA	NA	NA 10.001	NA	0.439	< 0.001	< 0.01	NA	0.0013	1.16	0.0022	NA
G271 G271	1/22/2019	<0.003	<0.001 0.0020	0.023	<0.001	<0.001	<0.004 0.0049	<0.002	0.530	0.0012	< 0.01	<0.0002	0.0014 0.0011	0.644	0.0022	<0.001
-	8/26/2019	NA		0.042	NA	NA			0.570	0.0068	< 0.01	NA				NA
G271	1/22/2020	<0.003	<0.001	0.024	<0.001	<0.001	<0.004	<0.002	0.278	<0.001	<0.02	< 0.0002	<0.001	0.922	0.0010	<0.001

Sample	Date	Antimony , total	Arsenic, total	Barium, total	Beryllium , total	Cadmium ,total	Chromium , total	Cobalt, total	Fluoride, total	Lead, total	Lithium, total	Mercury, total	Molybdenum , total	Radium- 226 + Radium 228, tot	Selenium , total	Thallium, total
Location	Sampled	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(pCi/L)	(mg/L)	(mg/L)
G273	11/24/2015	< 0.003	< 0.001	0.049	< 0.001	< 0.001	< 0.004	<0.002	< 0.25	0.0011	< 0.01	< 0.0002	< 0.001	2.06	< 0.001	< 0.001
G273	2/16/2016	< 0.003	< 0.001	0.031	< 0.001	< 0.001	< 0.004	< 0.002	0.388	< 0.001	< 0.01	< 0.0002	< 0.001	1.51	< 0.001	< 0.001
G273	5/12/2016	< 0.003	0.0045	0.031	< 0.001	< 0.001	< 0.004	<0.002	0.537	< 0.001	< 0.01	< 0.0002	< 0.001	0.774	0.0051	< 0.001
G273	8/5/2016	< 0.003	< 0.001	0.032	< 0.001	< 0.001	< 0.004	<0.002	0.294	< 0.001	< 0.01	< 0.0002	< 0.001	0.657	< 0.001	< 0.001
G273	11/21/2016	< 0.003	< 0.001	0.036	< 0.001	< 0.001	< 0.004	<0.002	0.390	< 0.001	< 0.01	< 0.0002	< 0.001	0.376	< 0.001	< 0.001
G273	2/15/2017	< 0.003	< 0.001	0.033	< 0.001	< 0.001	< 0.004	< 0.002	0.288	< 0.001	< 0.01	< 0.0002	< 0.001	0	< 0.001	< 0.001
G273	5/20/2017	< 0.003	< 0.001	0.032	< 0.001	0.0018	< 0.004	0.0021	< 0.25	0.001	< 0.01	< 0.0002	0.0019	1.22	< 0.001	0.0012
G273	7/17/2017	< 0.003	< 0.001	0.035	<0.001	< 0.001	< 0.004	<0.002	0.333	<0.001	< 0.01	< 0.0002	< 0.001	1.28	< 0.001	< 0.001
G273	11/4/2017	NA	NA	NA	NA	NA	NA	NA	0.333	NA	NA	NA	NA	NA	NA	NA
G273	5/16/2018	< 0.003	< 0.001	0.032	<0.001	< 0.001	< 0.004	<0.002	0.390	<0.001	0.012	< 0.0002	<0.001	NA	< 0.001	< 0.001
G273	5/31/2018	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.386	NA	NA
G273	8/10/2018	NA	< 0.001	0.027	NA	NA	NA	NA	0.367	< 0.001	< 0.01	NA	< 0.001	0.760	< 0.001	NA
G273	1/22/2019	< 0.003	0.0015	0.049	<0.001	< 0.001	< 0.004	<0.002	0.462	< 0.001	< 0.01	< 0.0002	< 0.001	0.487	< 0.001	< 0.001
G273	8/26/2019	NA	< 0.001	0.027	NA	NA	< 0.004	< 0.002	0.432	< 0.001	0.011	NA	0.0011	0.151	< 0.001	NA
G273	1/22/2020	< 0.003	0.0011	0.03	<0.001	<0.001	<0.004	<0.002	0.252	<0.001	<0.02	< 0.0002	<0.001	0.641	<0.001	0.0012
G276	11/24/2015	< 0.003	< 0.001	0.077	<0.001	< 0.001	< 0.004	<0.002	0.345	<0.001	0.013	< 0.0002	0.0017	1.29	< 0.001	<0.001
G276	2/16/2016	< 0.003	<0.001	0.090	<0.001	<0.001	< 0.004	<0.002	0.456	0.0014	0.015	<0.0002	0.0013	0.181	0.0018	<0.001
G276	5/12/2016	< 0.003	< 0.001	0.078	<0.001	< 0.001	< 0.004	<0.002	0.441	<0.001	0.012	< 0.0002	<0.001	0.800	0.0017	< 0.001
G276	8/3/2016	< 0.003	< 0.001	0.085	<0.001	< 0.001	< 0.004	<0.002	0.443	<0.001	<0.01	< 0.0002	< 0.001	1.15	0.0017	<0.001
G276	11/21/2016	< 0.003	<0.001	0.081	<0.001	<0.001	< 0.004	<0.002	0.445	<0.001	0.011	<0.0002	< 0.001	0.105	0.0020	<0.001
G276	2/17/2017	< 0.003	< 0.001	0.082	<0.001	< 0.001	< 0.004	<0.002	0.358	<0.001	0.014	< 0.0002	<0.001	0.689	0.0014	< 0.001
G276	5/20/2017	< 0.003	< 0.001	0.081	< 0.001	< 0.001	< 0.004	<0.002	< 0.25	< 0.001	0.012	< 0.0002	0.0013	1.76	0.0023	< 0.001
G276	7/18/2017	< 0.003	< 0.001	0.084	<0.001	< 0.001	< 0.004	<0.002	0.395	<0.001	0.012	< 0.0002	<0.001	0.916	0.0018	< 0.001
G276	11/4/2017	NA	NA	NA	NA	NA	NA	NA	0.431	NA	NA	NA	NA	NA	NA	NA
G276	5/16/2018	< 0.003	< 0.001	0.073	< 0.001	< 0.001	< 0.004	<0.002	0.466	<0.001	0.015	< 0.0002	< 0.001	NA	0.0018	< 0.001
G276	5/31/2018	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.04	NA	NA
G276	8/10/2018	NA	< 0.001	0.069	NA	NA	NA	NA	0.399	< 0.001	0.013	NA	< 0.001	0.325	0.0011	NA
G276	1/22/2019	< 0.003	< 0.001	0.076	< 0.001	< 0.001	< 0.004	< 0.002	0.421	< 0.001	< 0.01	< 0.0002	< 0.001	0.510	0.0014	< 0.001
G276	8/26/2019	NA	< 0.001	0.066	NA	NA	< 0.004	< 0.002	0.443	< 0.001	0.016	NA	< 0.001	0.339	0.0023	NA
G276	1/23/2020	< 0.003	< 0.001	0.063	< 0.001	< 0.001	< 0.004	<0.002	0.255	<0.001	<0.02	< 0.0002	< 0.001	1.12	0.0026	< 0.001
G279	11/24/2015	< 0.003	< 0.001	0.053	< 0.001	< 0.001	< 0.004	< 0.002	0.334	0.0015	0.014	< 0.0002	< 0.001	1.05	0.0041	< 0.001
G279	2/16/2016	< 0.003	< 0.001	0.072	< 0.001	< 0.001	< 0.004	< 0.002	0.386	< 0.001	0.012	< 0.0002	0.043	1.43	0.017	< 0.001
G279	5/13/2016	< 0.003	< 0.001	0.054	< 0.001	< 0.001	< 0.004	< 0.002	0.608	< 0.001	< 0.01	< 0.0002	0.024	0.841	0.0027	< 0.001
G279	8/3/2016	< 0.003	< 0.001	0.069	< 0.001	< 0.001	< 0.004	< 0.002	0.394	< 0.001	< 0.01	< 0.0002	< 0.001	1.16	0.020	< 0.001
G279	11/22/2016	< 0.003	< 0.001	0.057	< 0.001	< 0.001	< 0.004	<0.002	0.272	<0.001	0.011	<0.0002	<0.001	NA 0.704	0.017	< 0.001
G279	12/7/2016	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.764	NA	NA
G279	2/15/2017	< 0.003	< 0.001	0.053	< 0.001	< 0.001	< 0.004	< 0.002	0.263	< 0.001	0.013	< 0.0002	< 0.001	0.672	0.013	< 0.001
G279	5/20/2017	< 0.003	< 0.001	0.089	< 0.001	< 0.001	< 0.004	< 0.002	0.280	< 0.001	< 0.01	< 0.0002	< 0.001	0.913	0.0055	< 0.001
G279	7/18/2017	<0.003	< 0.001	0.054	<0.001	<0.001	< 0.004	<0.002	0.282	<0.001	0.012	<0.0002	<0.001	1.27	0.014	< 0.001
G279	11/4/2017	NA	NA	NA	NA	NA	NA	NA	0.507	NA	NA	NA	NA	NA	NA 0.0070	NA
G279	5/16/2018	< 0.003	< 0.001	0.052	< 0.001	< 0.001	< 0.004	<0.002	0.492	<0.001	< 0.01	< 0.0002	<0.001	NA	0.0072	< 0.001
G279	5/31/2018	NA	NA	NA	NA	NA	NA	NA	NA 0.407	NA	NA	NA	NA	0.494	NA	NA
G279	8/10/2018	NA	< 0.001	0.044	NA	NA	NA	NA	0.427	< 0.001	0.011	NA	< 0.001	0.799	0.0092	NA
G279	1/23/2019	< 0.003	0.0030	0.083	< 0.001	< 0.001	0.01	0.0022	0.626	0.0063	< 0.01	< 0.0002	< 0.001	1.80	0.0020	< 0.001
G279	8/26/2019	NA (0.002)	< 0.001	0.050	NA 10.001	NA	< 0.004	< 0.002	0.635	< 0.001	< 0.01	NA	< 0.001	0.618	< 0.001	NA
G279 otes:	1/23/2020	< 0.003	<0.001	0.062	<0.001	<0.001	<0.004	<0.002	0.537	<0.001	<0.02	< 0.0002	<0.001	1.44	0.0036	<0.001

Notes:

1. Abbreviations: mg/L - milligrams per liter; NA - not analyzed; pCi/L - picocurie per liter;

### APPENDIX C5 – SITE HYDROGEOLOGY AND STRATIGRAPHIC CROSS-SECTIONS OF THE SITE

# CONCEPTUAL SITE MODEL AND DESCRIPTION OF SITE HYDROGEOLOGY (GYPSUM MANAGEMENT FACILITY GYPSUM STACK POND AND GYPSUM MANAGEMENT FACILITY RECYCLE POND)

The Coffeen Power Station (Power Station) conceptual site model (CSM) and Description of Site Hydrogeology for the Gypsum Management Facility (GMF) Gypsum Stack Pond (GSP) and GMF Recycle Pond (GRP), located near Coffeen, Illinois are described in the following sections.

#### **REGIONAL SETTING**

The Power Station is located in Montgomery County, in central Illinois, approximately 2 miles south of the City of Coffeen. Coffeen Lake was built by damming the McDavid Branch of the East Fork of Shoal Creek in 1963 for use as an artificial cooling lake for the Power Station. The Site is located between two lobes of the Coffeen Lake (identified as "Coffeen Lake" and "Unnamed Tributary" on Figures 1 and 2) to the west, east, and south, and is bordered by agricultural land to the north. Several underground coal mines were historically operated both beneath and in the vicinity of the Power Station.

The Quaternary deposits in the Coffeen area consist mainly of diamictons and intercalated outwash deposits that were deposited during Illinoian and Pre-Illinoian glaciations. Along East Fork Shoal Creek valley, east of the Power Station, the glacial deposits are overlain by modern day channel and floodplain deposits belonging to the Cahokia Formation. The Quaternary deposits are underlain by Pennsylvanian age bedrock, primarily shale, of the Bond Formation.

Pleistocene deposits of unlithified glacial diamictons, lacustrine/alluvial deposits, and windblown loess overlie Pennsylvanian-age bedrock throughout central Illinois. The most extensive glacial deposits are those from the Illinoian Stage which cover much of the state and are present at the Site. Windblown (aeolian) deposits, the Peoria and Roxana Silts, cover the glacial deposits over a majority of the state. These units are finegrained deposits blown from river valleys by prevailing winds.

Till members of the Glasford Formation include the Smithboro Member, the Mulberry Grove Member, the Vandalia Member, and the Hagarstown Member (oldest to youngest). The Smithboro Member is described as a gray, compact, silty till. The Smithboro is bounded below by the Yarmouth Soil. The Mulberry Grove Member is intermittent at the Power Station, and is described as a calcareous gray silt and fine sand containing some fossil mollusks. The Vandalia Member is a sandy till with thin lenticular bodies of silt, sand, and gravel. It is calcareous, except where weathered, generally gray, and moderately compact. The Hagarstown Member is bounded at the top by the Sangamon Soil. The member consists of gravelly till, poorly sorted gravel, well sorted gravel, and sand.

The Power Station and surrounding areas are underlain by rocks belonging to the Pennsylvanian Bond Formation. The Bond Formation is characterized by a high percentage of limestone and calcareous clays and shales. The elevation of the bedrock surface in the area ranges from 450 to 500 feet (ft) above mean sea level (msl). The bedrock surface slopes gently towards the west into a minor bedrock valley that runs north-south. Well logs indicate that the lithology of the uppermost bedrock is predominantly shale.



#### SITE GEOLOGY

The geology has been extensively evaluated during previous hydrogeologic investigations, groundwater quality assessments, and modeling since the first borings and monitoring wells were installed. Quaternary deposits in the Coffeen area consist mainly of glacial diamictons and outwash deposits that were deposited during Illinoian and Pre-Illinoian glaciations. The unconsolidated deposits which occur at the Power Station include the following units (beginning at the ground surface):

- Upper Confining Unit Low permeability clays and silts, including the Roxana Silt and Peoria Silt (Loess Unit) and the upper clayey till portion of the Hagarstown Member
- Uppermost Aquifer (Groundwater Monitoring Zone) Thin (generally less than 3 ft), moderate to high permeability sand, silty sand, and sandy silt/clay units which include the Hagarstown Member (also referred to as the Hagarstown Beds) and the upper Vandalia Till Member (where weathered).
- Lower Confining Unit Thick (generally greater than 15 ft), very low permeability sandy, silt till, or clay till that include the unweathered Vandalia Member, Mulberry Grove Member (discontinuous), and Smithboro Member.

Pennsylvanian-age Bond Formation bedrock is characterized by limestone and calcareous clays and shales. Bedrock was not encountered in any borings advanced onsite. A cross-section illustrating the thickness and extent of unconsolidated deposits across the GSP and GRP is included as an attachment to this demonstration.

The major unconsolidated materials present at the site are discussed in greater detail below:

#### Roxana Silt / Peoria Silt (Loess Unit)

The combined Roxana Silt and Peoria Silt are a Loess Unit which extends from beneath the topsoil, derived from the loess, to the top of the Hagarstown (Beds) Member. Thicknesses range from a minimum of less than 1.0 ft adjacent to and west/southwest of Ash Pond No. 2 (groundwater contour maps, which also show the location of each CCR unit are included as an attachment to this demonstration), to a maximum of less than 6 ft as measured within the footprint of the Landfill prior to construction. The loess has been variously classified as silt or clayey silt, with minor amounts of sand. The Loess Unit is generally considered unsaturated and the upper-most aquifer is recharged by precipitation that percolates through this unit. This unit was likely removed from within the footprint of Ash Pond No. 2. Construction of the Landfill and GMF units also required the excavation and removal of this layer.

The laboratory tests from recent geotechnical analysis reported vertical hydraulic conductivity values ranging from  $1.3 \times 10^{-8}$  to  $5.0 \times 10^{-7}$  centimeters per second (cm/s), with a geometric mean of  $1.0 \times 10^{-7}$  cm/s.

#### **Hagarstown Member**

The Hagarstown Member (also referred to as Hagarstown Beds) exhibits two units; the first unit, consisting of the gravelly clay till and the second consisting of sandy material overlying the Vandalia Member. The clay till portion had varying thicknesses ranging from 1.9 ft to over 12 ft as observed adjacent to, south and west of Ash Pond No. 2. The thickness of the sandy portion of the Hagarstown is generally 1 to 2 ft thick. The composition of the sandy portion of the Hagarstown unit varies across the site and was classified as gravelly till, poorly sorted gravel, well sorted gravel, sand and silty sand. The elevation of the top of the Hagarstown generally declines as the unit approaches Coffeen Lake or other topographic drainage features.



During construction of the landfill, the GSP, and the GRP, the Loess Unit and the Hagarstown Beds were excavated to facilitate construction by limiting groundwater flow into excavations. The excavations were backfilled with structural fill and an underdrain system was installed to mitigate inward hydraulic pressure and potential liner uplift damage before the CCR units were filled. The Landfill underdrain system remains active. The GRP is a gravity drain system, and the GSP remains in place, but the system is inactive. The hydraulic characteristics of the Hagarstown Member indicate the unit has a moderate hydraulic conductivity.

The results of single well field permeability tests show hydraulic conductivity values ranging from  $3.1 \times 10^{-5}$  to  $1.6 \times 10^{-3}$  cm/s, with a geometric mean of  $2.9 \times 10^{-4}$  cm/s. The upper Vandalia is hydraulically similar to the Hagarstown Beds and is likely connected to and continuous with the Hagarstown. The hydraulic conductivity values measured within wells screened across the Hagarstown Beds are significantly higher than both the overlying Roxana/Peoria Silts and lower Vandalia (Till) Member.

#### Vandalia Member

The Vandalia (Till) Member is a sandy/silty till with thin, discontinuous lenses of silt, sand, and gravel. The Vandalia Till was encountered in all borings advanced at the site. The Vandalia Till typically ranged in thickness from 11.7 ft in the northern portion of the Power Station, to 31.0 ft between the GMF Gypsum Stack Pond and the GMF Recycle Pond. Similar to the observed top elevation of the Hagarstown Beds, the top of the Vandalia unit declines in elevation near Coffeen Lake and topographic drainage features. This unit is relatively thick throughout the site, with an average thickness of over 15 ft (Hanson, 2009). Results from laboratory tests completed for vertical hydraulic conductivity indicate the Vandalia unit has a very low vertical hydraulic conductivity.

The laboratory tests reported hydraulic conductivity values ranging from  $6.8 \times 10^{-9}$  to  $4.5 \times 10^{-6}$  cm/s, with a geometric mean of  $4.9 \times 10^{-8}$  cm/s. Field hydraulic conductivity tests completed in temporary piezometers (T408 and T409) indicate horizontal conductivities of  $9.0 \times 10^{-7}$  and  $3.4 \times 10^{-5}$  cm/s, respectively. The maximum value was measured in a sand seam within the Vandalia Till, but likely is not representative of the diamicton because sand seams are infrequent and discontinuous.

#### **Mulberry Grove Member**

The Mulberry Grove (Silt) Member typically consists of a thin, lenticular unit of gray sandy silt (Willman et al., 1975). It represents the interval between the retreat of the glacier that deposited the Smithboro Member and the advance of the glacier that deposited the Vandalia Member. At the site, the Mulberry Grove Member is represented by pockets (generally less than 2 ft thick) of gray sandy silt. This unit was absent in many borings through the central portion of the site from south to north. Where sampled, the Mulberry Grove Member ranged in thickness from 0.5 to 4.9 ft near the GMF Gypsum Stack Pond (Hanson, 2009). The Mulberry Grove Silt was not encountered in the borings near Ash Pond No. 2. These silts appear to be deposited in depressions found in the surface of the underlying Smithboro Member.

The laboratory tests reported vertical hydraulic conductivity values of 1.6 x  $10^{-6}$  and 1.9 x  $10^{-6}$  cm/s, with a geometric mean of 1.7 x  $10^{-6}$  cm/s.

#### **Smithboro Member**

The Smithboro (Till) Member is described as a gray, compact, silty, clayey diamicton. The Smithboro Member ranges in thickness from 6.7 to 21.2 ft northwest of the landfill. Laboratory and field conductivity testing indicate the Smithboro Member has a low hydraulic conductivity.



Laboratory test reported vertical hydraulic conductivity values ranging from  $1.1 \times 10^{-9}$  to  $1.0 \times 10^{-7}$  cm/s with a geometric mean of  $1.3 \times 10^{-8}$  cm/s. Horizontal hydraulic conductivities calculated from single well tests performed in wells G45D and G46D were  $4.0 \times 10^{-8}$  and  $4.9 \times 10^{-7}$  cm/s, respectively.

#### Yarmouth Soil

Historical borings in the northern portion of the site which encountered the Yarmouth were summarized previously (Hanson, 2009). The Yarmouth Soil is described as the weathered zone on the Kansan drift, but in some places, it consists of accretionary deposits of fine sediment and organic material that accumulated in poorly drained areas on the surface of the Kansan deposits. Where encountered, the Yarmouth Soil ranged in thickness from 0.8 to 5.1 ft. The Yarmouth Soil (considered the deep water-bearing zone) possesses a moderate to moderately low hydraulic conductivity.

The single-well permeability tests conducted by Hanson (2009) reported moderate hydraulic conductivity values ranging from  $1.3 \times 10^{-4}$  to  $1.7 \times 10^{-3}$  cm/s, with a geometric mean of  $4.4 \times 10^{-4}$  cm/s.

#### **Lierle Clay Member**

The Lierle Clay Member is the uppermost member of the Kansan Stage Banner Formation. It is described as an accretion gley with clay, silt and some sand. It was encountered by Hanson (2009) in all but a few borings on site. No boring penetrated the full thickness of the Lierle Clay. The Lierle Clay has a very low hydraulic conductivity.

The laboratory tests reported very low vertical hydraulic conductivity values ranging from 3.4 x  $10^{-9}$  to 1.3 x  $10^{-8}$  cm/s, with a geometric mean of 6.6 x  $10^{-9}$  cm/s.

#### Bedrock

Pennsylvanian-age Bond Formation bedrock was not encountered in any borings advanced onsite so site specific information is not available.

#### SITE HYDROGEOLOGY

The GSP CCR groundwater monitoring system consists of seven monitoring wells installed in the uppermost aquifer and adjacent to the GSP (G200, R201, G206, G209, G212, G215, and G218). (see Monitoring Well Location Map, and Well Construction Diagrams and Drilling Logs attached to this demonstration). The GSP utilizes two background monitoring wells (G200, R201) as part of the CCR groundwater monitoring system.

The GRP CCR groundwater monitoring system consists of six monitoring wells installed in the uppermost aquifer and adjacent to the GRP (G270, G280, G271, G273, G276, and G279). (see Monitoring Well Location Map, and Well Construction Diagrams and Drilling Logs attached this demonstration). The GRP utilizes two background monitoring wells (G270, G280) as part of the CCR groundwater monitoring system.

The uppermost aquifer includes the Hagarstown Member and the weathered portions of the Vandalia Member, consisting of thin (generally less than 3 ft), moderate to high permeability sand, silty sand, and sandy silt/clay units. The uppermost aquifer is confined except where site excavations and ravines extend through the Loess Unit and the Hagarstown Member. Where exposed, groundwater within the Hagarstown Member may appear as seeps.

The lower hydrostratigraphic unit consists of the lower, unfractured, Vandalia Till Member, Smithboro Till Member, and the undifferentiated Banner Formation. This lower confining unit is generally greater than 15 ft thick and consists of very low permeability sandy, silt till, or clay till. Bedrock aquifers are composed of



sandstone and fractured limestone, which vary widely in permeability. Groundwater available from bedrock units is mostly mineralized and rarely used as a source for potable water.

#### **Hydraulic Conductivity**

Hydraulic conductivity/slug tests were completed in wells screened in the unlithified material during several site investigations. The hydraulic conductivity values determined from individual monitoring wells within the uppermost aquifer (Hagarstown Beds and Upper Vandalia Till) ranged from 1.6 x  $10^{-3}$  cm/s to  $3.1 \times 10^{-5}$  cm/s. The geometric mean of the hydraulic conductivity for tested monitoring wells in the uppermost aquifer is  $2.9 \times 10^{-4}$  cm/s.

The hydraulic conductivity values determined from individual monitoring wells within the Lower Confining Unit (Vandalia Till and Smithboro Till) ranged from  $3.4 \times 10^{-5}$  cm/s to  $4.0 \times 10^{-8}$  cm/s. The geometric mean of the hydraulic conductivity at all monitoring wells was  $5.6 \times 10^{-6}$  cm/s. The effective porosity of the clayey sand/silty sand aquifer (20%) was estimated from literature values (Sanders, 1998) to calculate the velocity of the groundwater.

#### **Groundwater Elevations, Flow Direction and Velocity**

Groundwater elevations obtained from measurements in monitoring wells from 2015 through 2016 (NRT, 2017) indicate that water levels in that area ranged from about 603 ft to 623 ft msl. The water table is often a subdued reflection of the surface topography. Groundwater flow will also be locally influenced by recharge from pond exfiltration and discharge to local ditches, streams and Coffeen Lake. A north/south trending groundwater mound is observed through the CCR units and groundwater flow is generally to the southeast or southwest, converging on the tributary valleys leading to Coffeen Lake on the east and west sides of the property. Groundwater flow south of the GRP is southward the discharge channel into Coffeen Lake. Groundwater flow south of the discharge channel flows north toward the channel. Representative groundwater contour maps are provided as an attachment to this demonstration.

Where the Hagarstown Beds have not been excavated for construction of the landfill and GMFs, moderate horizontal groundwater gradients on the order of 0.006 feet per feet (ft/ft) are typically observed. Groundwater velocities across the Power Station may vary significantly, depending on the thickness and continuity of sand seams within the Hagarstown Beds.

Vertical groundwater gradients were measured at two locations between the Hagarstown Beds and Vandalia Till. Vertical flow was upward into the more permeable Hagarstown Beds with gradients of 0.009 to 0.4. Vertical groundwater gradients measured in the lower confining unit between the Vandalia Till and underlying Smithboro Till indicated steeply downward gradients exceeding 1, indicating very low vertical hydraulic conductivity and that groundwater in the Vandalia Till is perched.


#### REFERENCES

Hanson, August 2009. Section 3: Hydrogeologic Investigation. Initial Facility Report, Hanson Professional Services, Inc.

Natural Resource Technology, Inc., 2017. Hydrogeologic Characterization Report, Coffeen Ash Pond No. 2, Coffeen Power Station, Coffeen, Illinois.

Sanders, L. L., 1998. A Manual of Field Hydrogeology, Prentice Hall, Inc.

Willman, H.B., E. Atherton, T.C. Buschbach, C. Collinson, J.C. Frye, M.E. Hopkins, J.A. Lineback, and J.A. Simon, 1975, Handbook of Illinois Stratigraphy: Illinois State Geological Survey, Bulletin 95, 261 p.



COFFEEN, ILLINOIS

**APPENDIX C6 – STRUCTURAL STABILITY ASSESSMENT** 



Submitted to Illinois Power Generating Company 134 Cips Lane Coffeen, IL 62017 Submitted by AECOM 1001 Highlands Plaza Drive West Suite 300 St. Louis, MO 63110

October 2016

# CCR Rule Report: Initial Structural Stability Assessment

# For

# **GMF** Pond

# **At Coffeen Power Station**

# 1 Introduction

This Coal Combustion Residual (CCR) Rule Report documents that the Gypsum Management Facility (GMF) Pond at the Illinois Power Generating Company Coffeen Power Station meets the structural stability assessment requirements specified in 40 Code of Federal Regulations (CFR) §257.73(d). The GMF Pond is located near Coffeen, Illinois in Montgomery County, approximately 0.6 miles north of the Coffeen Power Station. The GMF Pond serves as the primary wet impoundment basin for gypsum produced by the wet scrubber system at the Coffeen Power Station.

The GMF Pond is an existing CCR surface impoundment as defined by 40 CFR §257.53. The CCR Rule requires that an initial structural stability assessment for an existing CCR surface impoundment be completed by October 17, 2016. In general, the initial structural stability assessment must document that the design, construction, operation, and maintenance of the CCR unit is consistent with recognized and generally accepted good engineering practices.

The owner or operator of the CCR unit must obtain a certification from a qualified professional engineer stating that the initial structural stability assessment was conducted in accordance with the requirements of 40 CFR § 257.73(d). The owner or operator must prepare a periodic structural stability assessment every five years.

# 2 Initial Structural Stability Assessment

#### 40 CFR §257.73(d)(1)

The owner or operator of the CCR unit must conduct initial and periodic structural stability assessments and document whether the design, construction, operation, and maintenance of the CCR unit is consistent with recognized and generally accepted good engineering practices for the maximum volume of CCR and CCR wastewater which can be impounded therein. The assessment must, at a minimum, document whether the CCR unit has been designed, constructed, operated, and maintained with [the standards in (d)(1)(i)-(vii)].

An initial structural stability assessment has been performed to document that the design, construction, operation and maintenance of the GMF Pond is consistent with recognized and generally accepted good engineering practices and meets the standards in 257.73(d)(1)(i)-(vii). The results of the structural stability assessment are discussed in the following sections. Based on the assessment and its results, the design, construction, operation, and maintenance of the GMF Pond were found to be consistent with recognized and generally accepted good engineering practices.

# 2.1 Foundations and Abutments (§257.73(d)(1)(i))

CCR unit designed, constructed, operated, and maintained with stable foundations and abutments.

The stability of the foundations was evaluated using soil data from field investigations and reviewing design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM. Additionally, slope stability analyses were performed to evaluate slip surfaces passing through the foundations. The GMF Pond is a ring dike structure and does not have abutments.

The foundation consists of medium stiff to stiff soil, overlying soft to very soft soil, which in turn overlies very stiff to hard glacial till. Slope stability analyses exceed the criteria listed in §257.73(e)(1)(i) through (iii) for slip surfaces passing through the foundation. The slope stability analyses are discussed in the *CCR Rule Report: Initial Safety Factor Assessment for GMF Pond at Coffeen Power Station* (October 2016). Additional slope stability analyses were performed to evaluate the effects of liquefaction and cyclic softening in the foundation, and were found to satisfy the criteria listed in §257.73(e)(1)(iv) applicable to dikes. A review of operational and maintenance procedures as well as current and past performance of the dikes has determined appropriate processes are in place for continued operational performance.

Based on the conditions observed by AECOM, the GMF Pond was designed and constructed with stable foundations. Operational and maintenance procedures are in place to address any issues related to the stability of foundations. Therefore, the GMF Pond meets the requirements in §257.73(d)(1)(i).

# 2.2 Slope Protection (§257.73(d)(1)(ii))

CCR unit designed, constructed, operated, and maintained with adequate slope protection to protect against surface erosion, wave action and adverse effects of sudden drawdown.

The adequacy of slope protection was evaluated by reviewing design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM.

Based on this evaluation, adequate slope protection was designed and constructed at the GMF Pond. No evidence of significant areas of erosion or wave action was observed. The interior slopes are protected with a geomembrane liner that underlies the entire GMF Pond and extends up the interior slopes, and the exterior

slopes are protected with vegetation. The geomembrane liner on the interior slopes isolates the embankment soils from surface erosion or wave action. Operational and maintenance procedures to repair the vegetation (exterior slopes) and liner (interior slopes) as needed are appropriate to protect against surface erosion or wave action. Given the presence of a liner that serves to prevent saturation of the dike's soils below the normal pool, sudden drawdown, as well as the corresponding adverse effects, is not applicable to the GMF Pond. Therefore, the GMF Pond meets the requirements in §257.73(d)(1)(ii).

## 2.3 Dike Compaction (§257.73(d)(1)(iii))

CCR unit designed, constructed, operated, and maintained with dikes mechanically compacted to a density sufficient to withstand the range of loading conditions in the CCR unit.

The density of the dike materials was evaluated using soil data from field investigations and reviewing design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM. Additionally, slope stability analyses were performed to evaluate slip surfaces passing through the dike over the range of expected loading conditions as defined within §257.73(e)(1).

Based on this evaluation, the dike consists of medium stiff to stiff material, which is indicative of mechanically compacted dikes. As discussed in the *CCR Rule Report: Initial Safety Factor Assessment for GMF Pond at Coffeen Power Station* (2016), slope stability analyses exceed the criteria listed in §257.73(e)(1) for slip surfaces passing through the dike. Therefore, the original design and construction of the GMF Pond included sufficient dike compaction. Operational and maintenance procedures are in place to identify and mitigate deficiencies in order to maintain sufficient compaction of the dikes to withstand the range of loading conditions. Therefore, the GMF Pond meets the requirements in §257.73(d)(1)(iii).

### 2.4 Vegetated Slopes (§257.73(d)(1)(iv))<sup>1</sup>

CCR unit designed, constructed, operated, and maintained with vegetated slopes of dikes and surrounding areas, except for slopes which have an alternate form or forms of slope protection.

The adequacy of slope vegetation was evaluated by reviewing design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM.

Based on this evaluation, the vegetation on the exterior slopes is adequate as no substantial bare or overgrown areas were observed. Exposed geomembrane liners on the interior slopes are used as an alternate form of slope protection, which is adequate as significant tears or defects were not observed. Therefore, the original design and construction of the GMF Pond included adequate vegetation of the dikes and surrounding areas. Adequate operational and maintenance procedures are in place to regularly manage vegetation growth, including mowing and seeding any bare areas, as evidenced by the conditions observed by AECOM. Therefore, the GMF Pond meets the requirements in §257.73(d)(1)(iv).

<sup>&</sup>lt;sup>1</sup> As modified by court order issued June 14, 2016, Utility Solid Waste Activities Group v. EPA, D.C. Cir. No. 15-1219 (order granting remand and vacatur of specific regulatory provisions).

# 2.5 Spillways (§257.73(d)(1)(v))

CCR unit designed, constructed, operated, and maintained with a single spillway or a combination of spillways configured as specified in [paragraph (A) and (B)]:

(A) All spillways must be either:

(1) of non-erodible construction and designed to carry sustained flows; or

(2) earth- or grass-lined and designed to carry short-term, infrequent flows at non-erosive velocities where sustained flows are not expected.

- (B) The combined capacity of all spillways must adequately manage flow during and following the peak discharge from a:
  - (1) Probable maximum flood (PMF) for a high hazard potential CCR surface impoundment; or
  - (2) 1000-year flood for a significant hazard potential CCR surface impoundment; or
  - (3) 100-year flood for a low hazard potential CCR surface impoundment.

The spillway system was evaluated using design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM. Additionally, hydrologic and hydraulic analyses were completed to evaluate the capacity of the spillway relative to inflow estimated for the probable maximum flood (PMF) inflow design flood (IDF) event for the high hazard potential GMF Pond. The hazard potential classification assessment was performed by Stantec in 2016 in accordance with §257.73(a)(2).

The spillway system at the GMF Pond includes a geomembrane-lined transfer channel and a high-density polyethylene low-flow pipe. Both the lined channel and the low-flow pipe are constructed from non-erodible materials that are designed to carry sustained flows. The capacity of the spillway system was evaluated using hydrologic and hydraulic analysis performed per §257.82(a). The analysis found that the spillway system can adequately manage flow during peak discharge resulting from the PMF IDF without overtopping of the embankments. The hydrologic and hydraulic analyses are discussed in the *CCR Rule Report: Initial Inflow Design Flood Control System Plan for GMF Pond at Coffeen Power Station* (October 2016). Operational and maintenance procedures are in place to repair any tears in the spillway liner and remove debris or other obstructions from the transfer channel and low-flow pipe, as evidenced by the conditions observed by AECOM. As a result, these procedures are appropriate for maintaining the spillway system. Therefore, the GMF Pond meets the requirements in §257.73(d)(1)(v).

### 2.6 Stability and Structural Integrity of Hydraulic Structures (§257.73(d)(1)(vi))

CCR unit designed, constructed, operated, and maintained with hydraulic structures underlying the base of the CCR unit or passing through the dike of the CCR unit that maintain structural integrity and are free of significant deterioration, deformation, distortion, bedding deficiencies, sedimentation, and debris which may negatively affect the operation of the hydraulic structure.

Based on an evaluation of design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM, no hydraulic structures are present that underlie the base or pass through the dike of the GMF Pond. Therefore, the §257.73(d)(1)(vi) requirements are not applicable to the GMF Pond.

### 2.7 Downstream Slope Inundation/Stability (§257.73(d)(1)(vii))

CCR unit designed, constructed, operated, and maintained with, for CCR units with downstream slopes which can be inundated by the pool of an adjacent water body, such as a river, stream or lake, downstream slopes that maintain structural stability during low pool of the adjacent water body or sudden drawdown of the adjacent water body.

The structural stability of the downstream slopes of the GMF Pond was evaluated by comparing the location of the GMF Pond relative to adjacent water bodies using published Federal Emergency Management Agency (FEMA) Flood Insurance Rate Maps (FIRM), aerial imagery, and conditions observed in the field by AECOM.

Based on this evaluation, water bodies adjacent to the downstream slopes of the GMF Pond are not present. The nearest downstream water body is the GMF Recycle Pond, which is approximately 500 lateral feet beyond the

downstream slopes of the GMF Pond. The GMF Recycle Pond is a CCR unit, rather than a river, stream, or lake. Coffeen Lake is also located in the vicinity of the GMF Pond, but the GMF Pond is outside of the flood zone shown on the FEMA FIRM. Therefore, adjacent water bodies that can inundate the downstream slopes of the GMF Pond are not present.

Based on this evaluation, the requirements in §257.73(d)(1)(vii) are not applicable to the GMF Pond, as inundation of the downstream slopes is not expected to occur.

#### **Certification Statement** 3

CCR Unit: Illinois Power Generating Company; Coffeen Power Station; GMF Pond

I, Victor A. Modeer, being a Registered Professional Engineer in good standing in the State of Illinois, do hereby certify, to the best of my knowledge, information, and belief that the information contained in this CCR Rule Report, and the underlying data in the operating record, has been prepared in accordance with the accepted practice of engineering. I certify, for the above-referenced CCR Unit, that the initial structural stability assessment dated October 13, 2016 was conducted in accordance with the requirements of 40 CFR § 257.73(d).

Printed Name

- MODEER SR. Date



## CCR Rule Report: Initial Structural Stability Assessment

GMF Recycle Pond Coffeen Power Station Montgomery County, Illinois

Submitted to Illinois Power Generating Company October 2016



## 1. Introduction

The GMF Recycle Pond at the Coffeen Power Station is located in the NW 1/4 of Section 11, Township 7 North, Range 3 West of the Third Principal Meridian in Montgomery County, Illinois, approximately 1.5 miles south of Coffeen, Illinois.

The GMF Recycle Pond is lined with a 60-mil, high-density polyethylene (HDPE) geomembrane, has a maximum embankment height of 16 feet and has a maximum impounding capacity of 243 acre-feet (measured at the top elevation 629.0 feet). There is an additional 99 acre-feet of incised storage.

The owner or operator of the CCR unit must obtain a certification from a qualified professional engineer stating that the initial structural stability assessment was conducted in accordance with the requirements of 40 CFR 257.73(d).

## 2. Initial Structural Stability Assessment

### 40 CFR 257.73(d)(1) Periodic structural stability assessments.

(1) The owner or operator of the CCR unit must conduct initial and periodic structural stability assessments and document whether the design, construction, operation, and maintenance of the CCR unit is consistent with recognized and generally accepted good engineering practices for the maximum volume of CCR and CCR wastewater which can be impounded therein. The assessment must, at a minimum, document whether the CCR unit has been designed, constructed, operated, and maintained with: 40 CFR 257.73(d)(1)(i)-(vii)

An initial structural stability assessment has been performed in accordance with 40 CFR 257.73(d)(1)(i)-(vii), documenting that the design, construction, operation, and maintenance of the GMF Recycle Pond is consistent with recognized and generally accepted good engineering practices for the maximum volume of CCR and CCR wastewater, which can be impounded therein.

## 2.1 Stable Foundations and Abutments

40 CFR 257.73(d)(1)(i) - CCR unit designed, constructed, operated, and maintained with stable foundations and abutments.

The GMF Recycle Pond foundation soils are grayish brown to brown, firm, silty clay, having Standard Penetration Test (SPT) blow counts ranging from 4-7 blows/foot and unconfined compressive strengths of approximately 1.3 tons per square foot. The GMF Recycle Pond has no abutments. The structural stability of the foundation soils and embankment was assessed and found to meet the structural stability requirements of 40 CFR 257.73(e). Information related to this assessment is found in the CCR Rule Report: Initial Safety Factor Assessment for the GMF Recycle Pond, dated October 2016. Procedures are in place to maintain and operate the foundations in a stable manner. Therefore, the GMF Recycle Pond meets the requirements of 40 CFR 257.73(d)(1)(i).

## 2.2 Adequate Slope Protection

40 CFR 257.73(d)(1)(ii) - CCR unit designed, constructed, operated, and maintained with adequate slope protection to protect against surface erosion, wave action and adverse effects of sudden drawdown.

The interior slopes of the GMF Recycle Pond are designed and constructed using a high-density polyethylene (HDPE) geomembrane, which is not susceptible to surface erosion or wave action. The exterior slopes were designed and constructed with a 4H:1V slope and vegetation to protect against

surface erosion. The operational condition of the interior and exterior slopes were visually evaluated during the annual inspection performed per 40 CFR 257.83 on September 27, 2016, and found to be intact. Procedures are in place to maintain and operate the slope protection features.

Even though it is highly unlikely that the GMF Recycle Pond interior slopes will be subjected to a rapid drawdown condition because they are lined with an HDPE geomembrane, slope stability analyses of the critical cross section of the slope indicate that sudden drawdown will have no adverse effects.

Therefore, the GMF Recycle Pond meets the requirements in 40 CFR 257.73(d)(1)(ii).

## 2.3 Dike Compaction

40 CFR 257.73(d)(1)(iii) - CCR unit designed, constructed, operated, and maintained with dikes mechanically compacted to a density sufficient to withstand the range of loading conditions in the CCR unit.

Construction records for the GMF Recycle Pond indicate that the dike was constructed of sandy silty clay fill materials, having a maximum compacted lift thickness of 8 inches. Fill materials were compacted to a dry density equal to or greater than 95 percent of the maximum dry density obtained from the Standard Proctor Test, ASTM D698. Fill was compacted at a moisture content that is no more than 2 percent below and no more than 2 percent above optimum moisture content. In-place compacted densities range from 105.1 to 112.7 pounds per cubic foot.

These in-place parameters meet the criteria of the original slope stability analyses found in the design record. Procedures are in place to maintain and operate the dikes to withstand the range of loading conditions. Therefore, the GMF Recycle Pond meets the requirements in 40 CFR 257.73(d)(1)(iii).

## 2.4 Vegetated Slopes

40 CFR 257.73(d)(1)(iv) - CCR unit designed, constructed, operated, and maintained with vegetated slopes of dikes and surrounding areas, except for slopes which have an alternate form or forms of slope protection.

The GMF Recycle Pond exterior slopes were designed and constructed with vegetated slopes capable of providing protection against surface erosion. The interior slopes of the GMF Recycle Pond were designed and constructed using a HDPE geomembrane liner for slope protection. Operational and maintenance procedures are in place to operate and maintain the vegetation on the slopes. The operational condition of the exterior slopes was evaluated and found to be intact. Procedures are in place to maintain and operate the vegetated slopes and alternate slope protection. Therefore, the GMF Recycle Pond meets the requirements in 40 CFR 257.73(d)(1)(iv).

## 2.5 Spillways

40 CFR 257.73(d)(1)(v) - CCR unit designed, constructed, operated, and maintained with a single spillway or a combination of spillways configured as specified in [paragraph (A) and (B)]:

- (A) All spillways must be either:
  - (1) of non-erodible construction and designed to carry sustained flows; or
  - (2) earth- or grass-lined and designed to carry short-term, infrequent flows at non-erosive velocities where sustained flows are not expected.

- (B) The combined capacity of all spillways must adequately manage flow during and following the peak discharge from a:
  - (1) Probable maximum flood (PMF) for a high hazard potential CCR surface impoundment; or
  - (2) 1000-year flood for a significant hazard potential CCR surface impoundment; or
  - (3) 100-year flood for a low hazard potential CCR surface impoundment.

The emergency spillway for the GMF Recycle Pond consists of three 6-foot-by-6-foot precast reinforced concrete risers (drop inlets) each with a top elevation of 624 feet (5 feet below the top of the dam). The GMF Recycle Pond HDPE liner is attached to the exterior sides of each riser. A 4-foot-diameter HDPE outlet conduit that returns water to the power station was constructed at each riser, with an upstream invert of 615.0 feet and a downstream invert of 613.0 feet. Assuming a maximum normal pool elevation of 624.0 feet (control elevation of the risers), the emergency spillway has been designed to pass the 24-hour PMF storm event of 34 inches of precipitation, based on NOAA Hydrometeorolgical Report No. 51, with adequate freeboard to prevent overtopping of the GMF Recycle Pond crest by wind-generated waves. By contrast, the regulatory 1,000-year flood event was estimated to be 9.13 inches in 24 hours, based on NOAA Atlas 14, which is much less than the PMF. The downstream end of the emergency spillway is protected from scour by a riprap stilling basin. The emergency spillway is regularly inspected and maintained in accordance with the gypsum management facility operation and maintenance manual found in the Coffeen Power Station GMF Recycle Pond Documentation Report.

Therefore, the GMF Recycle Pond spillway meets the requirements in 40 CFR 257.73(d)(1)(v).

## 2.6 Stability and Structural Integrity of Hydraulic Structures

40 CFR 257.73(d)(1)(vi) - CCR unit designed, constructed, operated, and maintained with hydraulic structures underlying the base of the CCR unit or passing through the dike of the CCR unit that maintain structural integrity and are free of significant deterioration, deformation, distortion, bedding deficiencies, sedimentation, and debris which may negatively affect the operation of the hydraulic structure.

The emergency spillway drop inlet structures were constructed on structural soil fill materials. Discharge piping is composed of non-erodible butt-fusion HDPE piping, and a flowable backfill plug was installed at the location where the pipes exit the drop inlet structures to prevent seepage. Compacted structural soil backfill was installed around the discharge pipes as they pass through the GMF Recycle Pond dike. A riprap stilling basin was installed on the downstream end of the discharge pipes to prohibit scour.

The process water decant pipes that feed water to the GMF Recycle Pond pumphouse are composed of non-erodible butt-fusion HDPE piping. Compacted structural soil backfill was installed around the decant pipes as they pass through the GMF Recycle Pond dike. The pipes are booted through the HDPE geomembrane to prevent leakage.

A pond riser pipe that hydraulically connects the GMF Recycle Pond to the ultrasonic transducer manhole for the purpose of water level monitoring is composed of non-erodible butt-fusion HDPE piping. Compacted structural soil backfill was installed around the pipes beneath the GMF Recycle Pond dike. The pipe is booted through the HDPE geomembrane to prevent leakage.

A decant pipe that transfers water from the GMF Pond to the GMF Recycle Pond is composed of nonerodible butt-fusion HDPE piping. Flowable backfill was installed around the decant pipe as it passes beneath the process water transfer channel. The pipe is booted through the HDPE geomembrane to prevent leakage. A slurry pipe that can transfer FGD slurry from the plant scrubber system to the GMF Recycle Pond is composed of non-erodible butt-fusion HDPE piping. This pipe passes through the west dike of the GMF Recycle Pond and is not in operation. Compacted structural soil backfill was installed around the decant pipe as it passes through the dike. The pipe is booted through the HDPE geomembrane to prevent leakage.

The emergency spillway was visually inspected during the annual inspection on September 27, 2016, and no deficiencies were observed. Therefore, the stability and structural integrity of the emergency spillway was designed, constructed, operated and maintained to meet the requirements of 40 CFR 257.73(d)(1)(vi).

The September 27, 2016, inspection did not identify any observable deficiencies with the process water decant pipes, the pond riser pipe, the transfer channel decant pipe or the slurry pipe that may negatively affect operation of those hydraulic structures. However, thorough inspections of those pipes have not yet been performed to confirm the current condition of the pipes as free of significant deterioration, deformation, distortion, bedding deficiencies, sedimentation, and debris per 40 CFR 257.73(d)(1)(vi). Thus, while the design and construction of the process water decant pipes, the pond riser pipe, the transfer channel decant pipe and the slurry pipe meets the requirements of 40 CFR 257.73(d)(1)(vi), in accordance with 40 CFR 257.73(d)(2), Hanson recommends that a nondestructive inspection of these pipes be performed as soon as feasible and that this report be updated with inspection documentation at that time.

## 2.7 Downstream Slope Inundation/Stability

40 CFR 257.73(d)(1)(vii) - CCR unit designed, constructed, operated, and maintained with, for CCR units with downstream slopes which can be inundated by the pool of an adjacent water body, such as a river, stream or lake, downstream slopes that maintain structural stability during low pool of the adjacent water body or sudden drawdown of the adjacent water body.

A review of Federal Emergency Management Agency flood hazard maps indicates that adjacent water bodies, more specifically the intermittent stream east of the GMF Recycle Pond, are not prone to flooding. Therefore, the GMF Recycle Pond downstream slopes would not be inundated by the pool of an adjacent water body.

Copyright © 2016 by Hanson Professional Services Inc. All rights reserved. This document is intended solely for the individual or the entity to which it is addressed. The information contained in this document shall not be duplicated, stored electronically, or distributed, in whole or in part, by anyone other than the recipient without the express written permission of Hanson Professional Services Inc., 1525 S. Sixth St., Springfield, IL 62703, (217) 788-2450, www.hanson-inc.com. Unauthorized reproduction or transmission of any part of this document is a violation of federal law. Any concepts, designs and project approaches contained herein are considered proprietary. Any use of these concepts and approaches by others is considered a violation of copyright law.

### 3. Certification Statement

#### COFFEEN POWER STATION - GMF RECYCLE POND ILLINOIS POWER GENERATING COMPANY INITIAL STRUCTURAL STABILITY ASSESSMENT CERTIFICATION

As a Qualified Professional Engineer as defined by 40 CFR 257 Subpart D, I certify that I have personally examined and am familiar with the design information referenced below, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete.

The <u>Coffeen Power Station GMF Recycle Pond</u> Initial Structural Stability Assessment, as supported by the Coffeen Power Station GMF Recycle Pond Documentation Report in the operating record was conducted in accordance with the requirements set forth by 40 CFR 257.73 as published on April 17, 2015.

Steven M. Bishoff, P.E. Hanson Professional Services Inc. 1525 South Sixth Street Springfield, IL 62703-2886 (217) 788-2450 Registration No. 062-040449

Signature:

Seal: M. BISHOWSKING M. BISHOWSKING 062-040449 LICENSED PROFESSIONAL ENGINEER OF ILLING

Date: 10-13-2016

**APPENDIX C7 – SAFETY FACTOR ASSESSMENT** 



Submitted to Illinois Power Generating Company 134 Cips Lane Coffeen, IL 62017 Submitted by AECOM 1001 Highlands Plaza Drive West Suite 300 St. Louis, MO 63110

October 2016

# CCR Rule Report: Initial Safety Factor Assessment

# For

# **GMF** Pond

# At Coffeen Power Station

## 1 Introduction

This Coal Combustion Residual (CCR) Rule Report documents that the Gypsum Management Facility (GMF) Pond at the Illinois Power Generating Company Coffeen Power Station meets the safety factor assessment requirements specified in 40 Code of Federal Regulations (CFR) §257.73(e). The GMF Pond is located near Coffeen, Illinois in Montgomery County, approximately 0.6 miles north of the Coffeen Power Station. The GMF Pond serves as the primary wet impoundment basin for gypsum produced by the wet scrubber system at the Coffeen Power Station.

The GMF Pond is an existing CCR surface impoundment as defined by 40 CFR §257.53. The CCR Rule requires that the initial safety factor assessment for an existing CCR surface impoundment be completed by October 17, 2016.

The owner or operator of the CCR unit must obtain a certification from a qualified professional engineer stating that the initial safety factor assessment meets the requirements of 40 CFR § 257.73(e). The owner or operator must prepare a safety factor assessment every five years.

## 2 Initial Safety Factor Assessment

#### 40 CFR §257.73(e)(1)

The owner or operator must conduct initial and periodic safety factor assessments for each CCR unit and document whether the calculated factors of safety for each CCR unit achieve the minimum safety factors specified in (e)(1)(i) through (iv) of this section for the critical cross section of the embankment. The critical cross section is the cross section anticipated to be the most susceptible of all cross sections to structural failure based on appropriate engineering considerations, including loading conditions. The safety factor assessments must be supported by appropriate engineering calculations.

(i) The calculated static factor of safety under the long-term, maximum storage pool loading condition must equal or exceed 1.50.

(ii) The calculated static factor of safety under the maximum surcharge pool loading condition must equal or exceed 1.40.

(iii) The calculated seismic factor of safety must equal or exceed 1.00.

(iv) For dikes constructed of soils that have susceptibility to liquefaction, the calculated liquefaction factor of safety must equal or exceed 1.20.

A geotechnical investigation program and stability analyses were performed to evaluate the design, performance, and condition of the earthen dikes of the GMF Pond. The exploration consisted of cone penetration test soundings. Data collected from the geotechnical investigation, available design drawings, construction records, inspection reports, previous engineering investigations, and other pertinent historic documents were utilized to perform the safety factor assessment and geotechnical analyses.

In general, the subsurface conditions at the GMF Pond consist of medium stiff to stiff embankment fill (clay) overlying medium stiff to stiff clay, overlying soft to very soft clay, with in turn overlies stiff to hard glacial till (clay) with dense to very dense sand and gravel. Phreatic water is typically near the embankment/foundation interface at the GMF Pond.

Four (4) representative cross sections were analyzed using limit equilibrium slope stability analysis software to evaluate stability of the perimeter dike system and foundations. The cross sections were located to represent critical surface geometry, subsurface stratigraphy, and phreatic conditions across the site. Each cross section was evaluated for each of the loading conditions stipulated in §257.73(e)(1).

The Soils Susceptible to Liquefaction loading condition, §257.73(e)(1)(iv), was not evaluated because a liquefaction susceptibly evaluation did not find soils susceptible to liquefaction within the GMF Pond dikes. As a result, this loading condition is not applicable to the GMF Pond.

Results of the Initial Safety Factor Assessments, for the critical cross-section for each loading condition, are listed in **Table 1** (i.e., the table identifies the lowest calculated factor of safety for any one of the four analyzed cross sections for each loading condition).

Loading Conditions	§257.73(e)(1) Subsection	Minimum Factor of Safety	Calculated Factor of Safety
Maximum Storage Pool Loading	(i)	1.50	3.45
Maximum Surcharge Pool Loading	(ii)	1.40	3.45
Seismic	(iii)	1.00	1.47
Soils Susceptible to Liquefaction	(iv)	1.20	Not Applicable

 Table 1 – Summary of Initial Safety Factor Assessments

Based on this evaluation, the GMF Pond meets the requirements in §257.73(e)(1).


#### 3 **Certification Statement**

CCR Unit: Illinois Power Generating Company; Coffeen Power Station; GMF Pond

I, Victor A. Modeer, being a Registered Professional Engineer in good standing in the State of Illinois, do hereby certify, to the best of my knowledge, information, and belief that the information contained in this CCR Rule Report, and the underlying data in the operating record, has been prepared in accordance with the accepted practice of engineering. I certify, for the above-referenced CCR Unit, that the initial safety factor assessment dated October 13, 2016 meets the requirements of 40 CFR §257.73(e).

A MODEER JR. Printed Name

Date



CCR Rule Report: Initial Safety Factor Assessment

GMF Recycle Pond Coffeen Power Station Montgomery County, Illinois

Submitted to Illinois Power Generating Company October 2016



## 1. Introduction

The GMF Recycle Pond at the Coffeen Power Station is located in the NW 1/4 of Section 11, Township 7 North, Range 3 West of the Third Principal Meridian in Montgomery County, Illinois, approximately 1.5 miles south of Coffeen, Illinois.

The GMF Recycle Pond is lined with a 60-mil, high-density polyethylene (HDPE) geomembrane, has a maximum embankment height of 16 feet, and has a maximum impounding capacity of 243 acre-feet (measured at the top elevation 629.0 feet). There is an additional 99 acre-feet of incised storage.

The owner or operator of the CCR unit must obtain a certification from a qualified professional engineer stating that the initial safety factor assessment meets the requirements of 40 CFR 257.73(e).

## 2. Safety Factor Assessment

### 40 CFR 257.73(e)(1)

The owner or operator must conduct initial and periodic safety factor assessments for each CCR unit and document whether the calculated factors of safety for each CCR unit achieve the minimum safety factors specified in (e)(1)(i) through (iv) of this section for the critical cross section of the embankment. The critical cross section is the cross section anticipated to be the most susceptible of all cross sections to structural failure based on appropriate engineering considerations, including loading conditions. The safety factor assessments must be supported by appropriate engineering calculations.

- *(i)* The calculated static factor of safety under the long-term, maximum storage pool loading condition must equal or exceed 1.50.
- (ii) The calculated static factor of safety under the maximum surcharge pool loading condition must equal or exceed 1.40.
- *(iii)* The calculated seismic factor of safety must equal or exceed 1.00.
- (iv) For dikes constructed of soils that have susceptibility to liquefaction, the calculated liquefaction factor of safety must equal or exceed 1.20.

The fundamental design criteria of the GMF Recycle Pond is based on the need to provide for safe operation and maintenance of the embankment and the minimization of potential failure mechanisms common to earthen surface impoundments. Additionally, the design must also incorporate hydrologic and hydraulic evaluations to determine that the dimensions of the embankment and appurtenances are adequate to prevent damage to the surface impoundment during normal operations and extreme rainfall events.

Stability analyses were performed for the GMF Recycle Pond design. The analyses were performed using the program PCSTABL5, which was developed at Purdue University, and SlopeW, developed by Geo Studio international. At the location of the GMF Recycle Pond, the critical elements for stability are the earthen berms.

The soil parameters used for the preliminary stability analyses were selected using data obtained during the geotechnical investigation of the GMF Recycle Pond. Soil parameters for the interfaces between manufactured lining materials and soils, at the interfaces between layers of manufactured lining materials, and within lining materials were selected based on values obtained from engineering literature.

During the analyses for the GMF Recycle Pond, the location of the phreatic surface was modeled assuming that there is no synthetic lining within the construction (a highly conservative assumption

because the GMF Recycle Pond is lined with highly impermeable synthetic materials). For this assumption, the phreatic surface would develop through the embankment sections over time.

At the GMF Recycle Pond location, a cross section of the embankment with the highest embankment height was judged to be the critical cross section. Analyses were performed for a long-term, steady-state-seepage condition using drained soil parameters (Maximum Storage Pool Loading using an elevation of 624.0 and Maximum Surcharge Pool Loading using an elevation of 624.0, and a seismic loading condition using rapid load soil parameters and a pool elevation of 624.0 for the downstream slope. Based on evaluation of the engineering characteristic of the embankment and foundation soils, it was determined that the embankment is not susceptible to liquefiable during the design seismic event.

The results of the analyses required by 40 CFR 257.73(e)(1) are provided in the table below. Based on this evaluation, the GMF Recycle Pond meets the safety factor requirements in 40 CFR 257.73(e)(1)(i) though (iv).

Loading Conditions	40 CFR 257.73(e)(1) Subsection	Minimum Required Factor of Safety	Calculated Factor of Safety
Maximum Storage Pool Loading	(i)	1.50	1.55
Maximum Surcharge Pool Loading	(ii)	1.40	1.51
Seismic	(iii)	1.00	1.80
Soils Susceptible to Liquefaction	(iv)	1.20	Not Applicable

Copyright © 2016 by Hanson Professional Services Inc. All rights reserved. This document is intended solely for the individual or the entity to which it is addressed. The information contained in this document shall not be duplicated, stored electronically, or distributed, in whole or in part, by anyone other than the recipient without the express written permission of Hanson Professional Services Inc., 1525 S. Sixth St., Springfield, IL 62703, (217) 788-2450, www.hanson-inc.com. Unauthorized reproduction or transmission of any part of this document is a violation of federal law. Any concepts, designs and project approaches contained herein are considered proprietary. Any use of these concepts and approaches by others is considered a violation of copyright law.

### 3. Certification Statement

### COFFEEN POWER STATION - GMF RECYCLE POND ILLINOIS POWER GENERATING COMPANY INITIAL SAFETY FACTOR ASSESSMENT CERTIFICATION

As a Qualified Professional Engineer as defined by 40 CFR 257 Subpart D, I certify that I have personally examined and am familiar with the design information referenced below, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete.

The <u>Coffeen Power Station GMF Recycle Pond</u> Initial Safety Factor Assessment, as supported by the Coffeen Power Station GMF Recycle Pond Documentation Report in the operating record was conducted in accordance with the requirements set forth by 40 CFR 257.73 as published on April 17, 2015.

Steven M. Bishoff, P.E. Hanson Professional Services Inc. 1525 South Sixth Street Springfield, IL 62703-2886 (217) 788-2450 Registration No. 062-040449

Signature:







## CREATE AMAZING.



Burns & McDonnell World Headquarters 9400 Ward Parkway Kansas City, MO 64114 O 816-333-9400 F 816-333-3690 www.burnsmcd.com