

Cynthia Vodopivec Dynegy Midwest Generation, LLC Luminant 6555 Sierra Dr. Irving, TX 75039

September 29, 2020

Sent via email

Mr. Andrew R. Wheeler, EPA Administrator Environmental Protection Agency 1200 Pennsylvania Avenue, N.W. Mail Code 5304-P Washington, DC 20460

Re: Baldwin Power Station Alternative Closure Demonstration

Dear Administrator Wheeler:

Dynegy Midwest Generation, LLC (Dynegy) hereby submits this request to the U.S. Environmental Protection Agency (EPA) for approval of a site-specific alternative deadline to initiate closure pursuant to 40 C.F.R. § 257.103(f)(2) for the Bottom Ash Pond located at the Baldwin Power Station near Baldwin, Illinois. Dynegy is requesting an extension pursuant to 40 C.F.R. § 257.103(f)(2) so that the Bottom Ash Pond may continue to receive CCR and non-CCR wastestreams after April 11, 2021, and complete closure no later than October 17, 2028.

Enclosed is a demonstration prepared by Burns & McDonnell that addresses all of the criteria in 40 C.F.R. § 257.103(f)(2)(i)-(iv) and contains the documentation required by 40 C.F.R. § 257.103(f)(2)(v). As allowed by the agency, in lieu of hard copies of these documents, electronic files were submitted to Kirsten Hillyer, Frank Behan, and Richard Huggins via email. If you have any questions regarding this submittal, please contact Phil Morris at 618-343-7794 or phil.morris@vistracorp.com.

Sincerely,

Cynthin E Ubdy

Cynthia Vodopivec VP - Environmental Health & Safety

Enclosure

cc: Kirsten Hillyer Frank Behan Richard Huggins





CCR Surface Impoundment Demonstration for a Site-Specific Alternative to Initiation of Closure Deadline



Dynegy Midwest Generation, LLC

Baldwin Power Station Project No. 122702

> Revision 0 9/28/2020



CCR Surface Impoundment Demonstration for a Site-Specific Alternative to Initiation of Closure Deadline

prepared for

Dynegy Midwest Generation, LLC Baldwin Power Station Baldwin, Illinois

Project No. 122702

Revision 0 9/28/2020

prepared by

Burns & McDonnell Engineering Company, Inc. Kansas City, Missouri

INDEX AND CERTIFICATION

Dynegy Midwest Generation, LLC CCR Surface Impoundment Demonstration for a Site-Specific Alternative to Initiation of Closure Deadline Project No. 122702

Report Index

<u>Chapter</u>		Number
Number	Chapter Title	of Pages
1.0	Executive Summary	1
2.0	Introduction	2
3.0	Documentation of No Alternative Disposal Capacity	4
6.0	Documentation of Closure Completion Timeframe	3
7.0	Conclusion	1
Appendix A	Site Plan	1

Certification

I hereby certify, as a Professional Engineer in the state of Illinois, that the information in this document as noted in the above Report Index was assembled under my direct personal charge. This report is not intended or represented to be suitable for reuse by the Dynegy Midwest Generation, LLC or others without specific verification or adaptation by the Engineer.

Edward T. Tohill, P.E., (Illinois License No. 062-056915)

09/28/2 Date:



TABLE OF CONTENTS

Page No.

1.0	EXECUTIVE SUMMARY1-1
2.0	INTRODUCTION
3.0	DOCUMENTATION OF NO ALTERNATIVE DISPOSAL CAPACITY
4.0	RISK MITIGATION PLAN4-1
5.0	DOCUMENTATION AND CERTIFICATION OF COMPLIANCE5-15.1Owner's Certification of Compliance - $\S 257.103(f)(2)(v)(C)(1)$ 5-15.2Visual representation of hydrogeologic information - $\S 257.103(f)(2)(v)(C)(2)$ 5-15.3Groundwater monitoring results - $\S 257.103(f)(2)(v)(C)(3)$ 5-25.4Description of site hydrogeology including stratigraphic cross-sections - $\S 257.103(f)(2)(v)(C)(4)$ 5-25.5Corrective measures assessment - $\S 257.103(f)(2)(v)(C)(5)$ 5-25.6Remedy selection progress report - $\S 257.103(f)(2)(v)(C)(6)$ 5-25.7Structural stability assessment - $\S 257.103(f)(2)(v)(C)(7)$ 5-25.8Safety factor assessment - $\S 257.103(f)(2)(v)(C)(8)$ 5-2
6.0	DOCUMENTATION OF CLOSURE COMPLETION TIMEFRAME
7.0	CONCLUSION
	NDIX A – SITE PLAN NDIX B – WATER BALANCE DIAGRAM
	CHMENT 1 – RISK MITIGATION PLAN CHMENT 2 – MAP OF GROUNDWATER MONITORING WELL LOCATIONS
	CHMENT 3 – WELL CONSTRUCTION DIAGRAMS AND DRILLING LOGS
ΑΤΤΑ	CHMENT 4 – MAPS OF THE DIRECTION OF GROUNDWATER FLOW CHMENT 5 – TABLES SUMMARIZING CONSTITUENT CONCENTRATIONS AT EACH MONITORING WELL CHMENT 6 – SITE HYDROGEOLOGY AND STRATIGRAPHIC CROSS-
AHA	SECTIONS OF THE SITE

ATTACHMENT 7 – STRUCTURAL STABILITY ASSESSMENT ATTACHMENT 8 – SAFETY FACTOR ASSESSMENT ATTACHMENT 9 – ADDENDUM TO THE CLOSURE PLAN (SEPTEMBER 2020)

LIST OF TABLES

Page No.

Table 3-1: Baldwin CCR Wastestreams	3-2
Table 3-2: Baldwin Non-CCR Wastestreams	3-3
Table 6-1: Baldwin Bottom Ash Pond Closure Schedule	6-2

LIST OF ABBREVIATIONS

Abbreviation	Term/Phrase/Name	
Baldwin	Baldwin Power Station	
CCR	Coal Combustion Residual	
CFR	Code of Federal Regulations	
Dynegy	Dynegy Midwest Generation, LLC	
ELG Rule	Effluent Limitations Guidelines and Standards for the Steam Electric Power Generating Point Source Category	
EPA	Environmental Protection Agency	
RCRA	Resource Conservation and Recovery Act	
SWPPP	Stormwater Pollution Prevention Plan	

i

1.0 EXECUTIVE SUMMARY

Dynegy Midwest Generation, LLC ("Dynegy") submits this request to the U.S. Environmental Protection Agency ("EPA") for approval of a site-specific alternative deadline to initiate closure pursuant to 40 C.F.R. § 257.103(f)(2) — "Permanent Cessation of a Coal-Fired Boiler(s) by a Date Certain" — for the Bottom Ash Pond located at the Baldwin Energy Complex ("Baldwin") in Illinois. The Bottom Ash Pond is a 177-acre CCR surface impoundment used to manage CCR and non-CCR wastestreams at Baldwin. As discussed herein, the boilers at the station will retire, and the impoundment will complete closure no later than October 17, 2028. Therefore, Dynegy is requesting an extension pursuant to 40 C.F.R. § 257.103(f)(2) from EPA so that the Bottom Ash Pond may continue to receive CCR and non-CCR wastestreams after April 11, 2021, and complete closure no later than October 17, 2028.

2.0 INTRODUCTION

Baldwin is a 1,185-megawatt coal-fueled electric generating station near Baldwin, Illinois, that utilizes the 177-acre Bottom Ash Pond to manage sluiced bottom ash/boiler slag, economizer ash, SCR ash, air heater ash, dry fly ash (when not hauled offsite for beneficial use), and non-CCR wastewaters. The impoundment was constructed in the 1960's and has been in service for the life of the plant. Units 1 and 2 remain in operation, and Unit 3 has already ceased operation. The various non-CCR wastewaters routed to the Bottom Ash Pond originate from the Unit 1 boiler room sump, Unit 1 boiler low point drains, oil/water separator, demineralizer regeneration flows, SDA emergency discharge, floor drains, water treatment system wastes, chemical metal cleaning waste pond, nonchemical metal cleaning wastewater (including boiler wash water), sewage treatment plant, Unit 1 polisher precoat system wastewater and stormwater sources. All fly ash is now handled dry. The Fly Ash Pond system is no longer active and is in the process of being closed with CCR material in place; therefore, it is not subject to this demonstration request. A site plan is provided on Figure 1 in Appendix A, and the plant water balance diagram is included in Appendix B. Note that the Bottom Ash Pond is referred to as the Primary Slag Field on the water balance diagram.

On April 17, 2015, the Environmental Protection Agency ("EPA") issued the federal Coal Combustion Residual ("CCR") Rule, 40 C.F.R. Part 257, Subpart D, to regulate the disposal of CCR materials generated at coal-fueled units. The rule is being administered under Subtitle D of the Resource Conservation and Recovery Act (RCRA, 42 U.S.C. § 6901 et seq.). On August 28, 2020, the EPA Administrator issued revisions to the CCR Rule that require all unlined surface impoundments to initiate closure by April 11, 2021, unless an alternative deadline is requested and approved. 40 C.F.R. § 257.101(a)(1) (85 Fed. Reg. 53,516 (Aug. 28, 2020)). Specifically, owners and operators of a CCR surface impoundment may continue to receive CCR and non-CCR wastestreams if the facility will cease operation of the coal-fired boiler(s) and complete closure of the impoundments within certain specified timeframes. 40 C.F.R. § 257.103(f)(2). To qualify for an alternative closure deadline under § 257.103(f)(2), a facility must meet the following four criteria:

- 1. § 257.103(f)(2)(i) No alternative disposal capacity is available on-site or off-site. An increase in costs or the inconvenience of existing capacity is not sufficient to support qualification.
- 2. § 257.103(f)(2)(ii) Potential risks to human health and the environment from the continued operation of the CCR surface impoundment have been adequately mitigated;
- 3. § 257.103(f)(2)(iii) The facility is in compliance with the CCR rule, including the requirement to conduct any necessary corrective action; and

- 4. § 257.103(f)(2)(iv) The coal-fired boilers must cease operation and closure of the impoundment must be completed within the following timeframes:
 - a. For a CCR surface impoundment that is 40 acres or smaller, the coal-fired boiler(s) must cease operation and the CCR surface impoundment must complete closure no later than October 17, 2023.
 - b. For a CCR surface impoundment that is larger than 40 acres, the coal-fired boiler(s) must cease operation, and the CCR surface impoundment must complete closure no later than October 17, 2028.

Section 257.103(f)(2)(v) sets out the documentation that must be provided to EPA to demonstrate that the four criteria set out above have been met. Therefore, this demonstration is organized based on the documentation requirements of §§ 257.103(f)(2)(v)(A) - (D).

3.0 DOCUMENTATION OF NO ALTERNATIVE DISPOSAL CAPACITY

To demonstrate that the criteria in § 257.103(f)(2)(i) has been met, the following provides documentation that no alternative disposal capacity is currently available on-site or off-site for each CCR and non-CCR wastestream that Dynegy seeks to continue placing into the Bottom Ash Pond after April 11, 2021. Consistent with the regulations, neither an increase in costs nor the inconvenience of existing capacity was used to support qualification under this criteria. Instead, as EPA explained in the preamble to the proposed Part A revisions, "it would be illogical to require [] facilities [ceasing power generation] to construct new capacity to manage CCR and non-CCR wastestreams." 84 Fed. Reg. 65,941, 65,956 (Dec. 2, 2019). EPA again reiterated in the preamble to the final revisions that "[i]n contrast to the provision under § 257.103(f)(1), the owner or operator does not need to develop alternative capacity because of the impending closure of the coal fired boiler. Since the coal-fired boiler will shortly cease power generation, it would be illogical to require these facilities to construct new capacity to manage CCR and non-CCR wastestreams." 85 Fed. Reg. at 53,547. Thus, new construction or the development of new alternative disposal capacity was not considered a viable option for any wastestream discussed below.

3.1 Site-Layout and Wastewater Processes

The Bottom Ash Pond receives all the CCR sluice flows and many of the non-CCR wastewater flows onsite, as shown on the water balance diagram included in Appendix B. These wastestreams are discussed in more detail in the following sections.

3.2 CCR Wastestreams

Dynegy evaluated each CCR wastestream placed in the Bottom Ash Pond at Baldwin. For the reasons discussed below in, each of the following CCR wastestreams must continue to be placed in the Bottom Ash Pond due to lack of alternative capacity both on and off-site.

CCR Wastestreams	Average Flow (MGD)	Alternative Disposal Capacity Available? YES/NO	Details
Unit 1 & 2 dry fly ash	NA	NO	The fly ash is collected dry and is currently conditioned and beneficially used both on-site and off-site. On-site beneficial reuse consists of facilitating the current fly ash pond closure efforts by promoting improved drainage off the cap and minimizing long-term infiltration potential. This on- site fly ash usage is reflected in the IEPA-approved fly ash pond closure plan. The remaining conditioned fly ash is placed in the Bottom Ash Pond, which will facilitate pond closure in the near future. This beneficial reuse of the fly ash will be reflected in the Bottom Ash Pond closure plan. Dynegy does not have a CCR landfill or another CCR surface impoundment located onsite that would be available to accept this material. Consequently, there are no on-site alternatives for this wastestream. Dynegy does not have a contract with an offsite landfill for this material.
Unit 1 & 2 bottom ash sluice	2.8	NO	There is not another potential disposal alternative on-site or off-site for this wet-generated CCR wastestream.
Unit 1 & 2 SCR ash, air heater ash, and economizer ash sluice	0.03	NO	There is not another potential disposal alternative onsite or offsite for this wet- generated CCR wastestream.

Table 3-1: Baldwin CCR Wastestreams

For the bottom ash sluice flow, there is no currently available onsite infrastructure to support dry handling of bottom ash or elimination of this wastestream. As stated previously, since Dynegy has elected to pursue the option to permanently cease the use of the coal fired boilers by a date certain, developing alternative disposal capacity is "illogical," to use EPA's words, and also counterproductive to work to retire the boilers

and close the impoundments. As long as Dynegy continues to wet handle the bottom ash material and Unit 1 and 2 SCR ash, air heater ash and economizer ash material, there are no other on-site CCR impoundments available to receive and treat these flows. The remaining impoundments onsite (cooling pond, coal pile runoff pond, metal cleaning waste pond, sewage treatment ponds, cove pond, secondary pond, and tertiary pond) are not authorized to receive the CCR material. Also, it is not feasible to dispose of the wet-generated material off-site. As EPA explained in the preamble of the 2015 rule, it is not possible for sites that sluice CCR material to an impoundment to eliminate the impoundment and dispose of the material offsite. *See* 80 Fed. Reg. 21,301, 21,423 (Apr. 17, 2015) ("[W]hile it is possible to transport dry ash off-site to [an] alternate disposal facility that is simply not feasible for wet-generated CCR. Nor can facilities immediately convert to dry handling systems."). As a result, the conditions at Baldwin satisfy the demonstration requirement in § 257.103(f)(2)(i).

For the site-specific reasons discussed above, the fly ash must also continue to be placed in the Baldwin Bottom Ash Pond. Consequently, in order to continue to operate and generate electricity, Baldwin must continue to use the 177-acre CCR surface impoundment to manage the CCR wastestreams discussed above.

3.3 Non-CCR Wastestreams

Dynegy evaluated each non-CCR wastestream placed in the Bottom Ash Pond at Baldwin. For the reasons discussed below in Table 3-2, each of the following non-CCR wastestreams must continue to be placed in the Bottom Ash Pond due to lack of alternative capacity both on and off-site.

Non-CCR Wastestreams	Average Flow (MGD)	Alternative Disposal Capacity Currently Available? YES/NO	Details
Chemical Metal Cleaning Wastewater	intermittent	NO	Would need to install additional piping and discharge from effluent tank to an existing or new permitted outfall
Non-Chemical Metal Cleaning Wastewater	intermittent	NO	Would need to isolate from Unit 1&2 sluice flows, install additional sump and piping and discharge from effluent tank to an existing or new permitted outfall

Table 3-2: Baldwin Non-CCR Wastes

Non-CCR Wastestreams	Average Flow (MGD)	Alternative Disposal Capacity Currently Available? YES/NO	Details
Sewage Treatment Plant Effluent	0.028	NO	Would need to install additional piping and discharge to the cooling lake or a new permitted outfall
Unit 1 Polisher Precoat System Wastewater	intermittent	NO	Would need to install additional sump and piping and discharge to the cooling lake or a new permitted outfall
Water Treatment System Wastes (from Cove Pond)	intermittent	NO	Would need to install additional piping and discharge to the cooling lake or a new permitted outfall
Cove Area Discharge *	0.4	NO	Would need to install additional piping and discharge to the cooling lake or a new permitted outfall
Regen Wastewater	0.03	NO	Would need to install additional sump and piping and discharge from effluent tank to an existing or new permitted outfall

* Includes Unit 1 boiler room sump, Unit 1 boiler low point drains, oil/water separator, SDA emergency discharge, and floor drains

As noted in Table 3-2, there is potential to discharge a portion of these non-CCR flows to other locations/outfalls; however, this would require permit modifications and installation of new piping and potentially a new treatment system including ponds, clarifiers, and/or storage tank(s). As stated previously, since Dynegy has elected to pursue the option to permanently cease the use of the coal fired boilers by a date certain, developing the above-referenced alternative disposal capacity methods is "illogical," to use EPA's words, and also counterproductive to the work to retire the boilers and close the impoundments. There is no currently available infrastructure at the plant to support reroute of these flows. For the reasons discussed above, each of the non-CCR wastestreams must continue to be placed in the Bottom Ash Pond due to lack of alternative capacity both on and off-site. Consequently, in order to continue to operate and generate electricity, Baldwin must continue to use the 177-acre Bottom Ash Pond to manage the non-CCR wastestreams discussed above.

4.0 **RISK MITIGATION PLAN**

To demonstrate that the criteria in § 257.103(f)(2)(ii) has been met, Dynegy has prepared and attached a Risk Mitigation Plan for the Baldwin Bottom Ash Pond (see Attachment 1).

5.0 DOCUMENTATION AND CERTIFICATION OF COMPLIANCE

In the Part A rule preamble, EPA reiterates that compliance with the CCR rule is a prerequisite to qualifying for an alternative closure extension, as it "provides some guarantee that the risks at the facility are properly managed and adequately mitigated." 85 Fed. Reg. at 53,543. EPA further stated that it "must be able to affirmatively conclude that facility meets this criterion prior to any continued operation." 85 Fed. Reg. at 53,543. Accordingly, EPA "will review a facility's current compliance with the requirements governing groundwater monitoring systems." 85 Fed. Reg. at 53,543. In addition, EPA will also "require and examine a facility's corrective action documentation, structural stability documents and other pertinent compliance information." 85 Fed. Reg. at 53,543. Therefore, EPA is requiring a certification of compliance and specific compliance documentation be submitted as part of the demonstration. 40 C.F.R. § 257.103(f)(2)(v)(C).

To demonstrate that the criteria in § 257.103(f)(2)(iii) has been met, Dynegy is submitting the following information as required by § 257.103(f)(2)(v)(C):

5.1 Owner's Certification of Compliance - § 257.103(f)(2)(v)(C)(1)

I hereby certify that, based on my inquiry of those persons who are immediately responsible for compliance with environmental regulations for the Bottom Ash Pond, the facility is in compliance with all of the requirements contained in 40 C.F.R. Part 257, Subpart D – Standards for the Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments. The Baldwin CCR compliance website is up-to-date and contains all the necessary documentation and notification postings.

On behalf of Dynegy:

unthin E Ubdy

Cynthia Vodopivec VP - Environmental Health & Safety September 28, 2020

5.2 Visual representation of hydrogeologic information - § 257.103(f)(2)(v)(C)(2)

Consistent with the requirements of § 257.103(f)(2)(v)(C)(2)(i) - (iii), Dynegy has attached the following items to this demonstration:

- Map(s) of groundwater monitoring well locations in relation to the CCR unit (Attachment 2)
- Well construction diagrams and drilling logs for all groundwater monitoring wells (Attachment 3)
- Maps that characterize the direction of groundwater flow accounting for seasonal variations (Attachment 4)

5.3 Groundwater monitoring results - § 257.103(f)(2)(v)(C)(3)

Tables summarizing constituent concentrations at each groundwater monitoring well through the first 2020 semi-annual monitoring period are included as Attachment 5.

5.4 Description of site hydrogeology including stratigraphic cross-sections -

§ 257.103(f)(2)(v)(C)(4)

A description of site hydrogeology and stratigraphic cross-sections of the site are included as Attachment 6.

5.5 Corrective measures assessment - § 257.103(f)(2)(v)(C)(5)

Background sampling at Baldwin began in late 2015 and continued for eight consecutive quarters. The first semiannual detection monitoring samples were collected in November 2017. The first assessment monitoring samples were collected in June 2018. The results from the 2020 monitoring period indicate an SSL for Lithium, an Appendix IV constituent. Alternate Source Demonstrations were completed for the March 2019 and September 2019 sampling events and are in progress at this time for the March 2020 sampling event. The Bottom Ash Pond remains in assessment monitoring. Accordingly, an assessment of corrective measures is not currently required for the Bottom Ash Pond. Baldwin will continue to conduct groundwater monitoring in accordance with all state and federal requirements.

5.6 Remedy selection progress report - § 257.103(f)(2)(v)(C)(6)

As noted above, an assessment of corrective measures and the resulting selection of remedy are not currently required for the Bottom Ash Pond.

5.7 Structural stability assessment - § 257.103(f)(2)(v)(C)(7)

Pursuant to § 257.73(d), the initial structural stability assessment for the Bottom Ash Pond was prepared in October 2016 and is included as Attachment 7.

5.8 Safety factor assessment - § 257.103(f)(2)(v)(C)(8)

Pursuant to § 257.73(e), the initial safety factor assessment for the Bottom Ash Pond was prepared in October 2016 and is included as Attachment 8.

6.0 DOCUMENTATION OF CLOSURE COMPLETION TIMEFRAME

To demonstrate that the criteria in § 257.103(f)(2)(iv) has been met, "the owner or operator must submit the closure plan required by § 257.102(b) and a narrative that specifies and justifies the date by which they intend to cease receipt of waste into the unit in order to meet the closure deadlines." An addendum to the closure plan for the Bottom Ash Pond is included as Attachment 9.

In order for a CCR surface impoundment over 40 acres to continue to receive CCR and non-CCR wastestreams after the initial April 11, 2021 deadline, the coal-fired boiler(s) at the facility must cease operation and the CCR surface impoundment must complete closure no later than October 17, 2028. As discussed below, Baldwin will begin construction of the Bottom Ash Pond closure by April 17, 2025, and cease placing wastestreams into the impoundment by July 17, 2027 in order for closure to be completed by this deadline.

Table 6-1 is included below to summarize the major tasks and estimated durations associated with closing the Bottom Ash Pond in place. These durations are consistent with the durations experienced in the closure of over 500 acres of other CCR impoundments already completed by Dynegy and its affiliates to date. The design, permitting, and procurement efforts will take place while the unit is still in operation. The construction is expected to occur in a phased approach at Baldwin. The first major construction effort will be to modify the pond operations by relocating the influent lines, minimizing the pond water levels, and isolating flow to a smaller portion of the current 177-acre impoundment that can be closed during the last two construction seasons. Dynegy expects that the impoundment operating area will be reduced to approximately 40-50 acres during this effort. This reduction in footprint may require the addition of chemical feeds to provide adequate treatment with the reduction in residence time; however, it will simultaneously allow for continued operation of the plant to maintain generating capacity for the MISO markets and minimize the risk to the environment both by minimizing the potential for any impacts to groundwater and by opening up a significant portion of the remaining impoundment to allow for dewatering, grading, and closure.

Table 6-1 provides estimates for the durations required to close a portion of pond footprint after the date noted to begin closure (Phase 1), as well as the current estimates for the closure of the active area (Phase 2, remaining 40-50 acres). In order to dewater the closure area, Dynegy will likely release pond water through the existing Outfall 001 and employ pumps as necessary, and potentially an engineered dewatering system such as wellpoints to aid in stabilizing the material. As the water level is lowered and the material is stabilized, the contractor will work across the pond re-grading the existing CCR material to achieve positive

drainage. As grading is completed in certain areas, the contractor may begin placing the final cover system which will consist of an 18-inch infiltration layer and 6-inch erosion layer in accordance with the requirements of the CCR Rule (or an alternative cover system that meets these minimum standards). The schedule for the Phase 1 cover installation will overlap with the Phase 1 grading schedule and is expected to finish approximately two months after the grading effort is completed. Once cover is placed, the area will be seeded and stabilized. The schedule for seeding will overlap with cover installation and finish approximately one month after the cover system is placed. Closure is essentially completed once the erosion control layer is placed, so the final month of this activity provides additional float to the schedule.

Action	Estimated Timeline (Months)
Spec, bid, and Award Engineering Services for CCR Impoundment Closure	3
Finalize CCR unit closure plan and seek IEPA approval for CCR unit closure	12
 Obtain environmental permits (based on IEPA approval of closure plan): State Waste Pollution Control Construction/Operating Permit NPDES Industrial Wastewater Permit Modification General NPDES Permit for Storm Water Discharges from Construction Site Activities and Storm Water Pollution Prevention Plan (SWPPP) Proposed 35 III. Admin Code 845 operating permit application is due NLT September 2021. Construction permit application is anticipated to be due NLT July 2023. 	21
Spec, bid, and Award Construction Services for CCR Impoundment Closure	3
Begin Construction of Closure Date	April 17, 2025
Minimize Active Area of Impoundment / Dewater Phase 1 Area	6
Regrade CCR Material in Phase 1 Area	18
Install Cover System – Phase 1 Area*	13
Establish Vegetation – Phase 1 Area**	2

Table 6-1: Baldwin Bottom Ash Pond Closure Schedule

Action	Estimated Timeline (Months)
Cease Placement of Waste	July 17, 2027
Dewater Impoundment – Phase 2 Area	3
Regrade CCR Material – Phase 2 Area	6
Install Cover System – Phase 2 Area	5
Establish Vegetation, Perform Site Restoration Activities, Complete Closure, and Initiate Post-Closure Care**	2
Total Estimated Time to Complete Closure	81 months (including design, permitting, and procurement)
Date by Which Closure Must be Complete	October 17, 2028

* Activity expected to overlap with grading operations, finishing 2 months after grading is completed


** Activity expected to overlap with cover system installation, finishing 1 month after cover installation is completed

7.0 CONCLUSION


Based upon the information included in and attached to this demonstration, Dynegy has demonstrated that the requirements of 40 C.F.R. § 257.103(f)(2) are satisfied for the 177-acre Baldwin Pond System. This CCR surface impoundment is needed to continue to manage the CCR and non-CCR wastestreams identified in Section 3.2 and 3.3 above, is larger than 40 acres, and the boilers at the station will cease coal-fired operation and the Bottom Ash Pond will be closed by the October 17, 2028 deadline. Therefore, this CCR unit qualifies for the site-specific alternative deadline for the initiation of closure authorized by 40 C.F.R. § 257.103(f)(2).

Therefore, it is requested that EPA approve Dynegy's demonstration and authorize the Bottom Ash Pond at Baldwin to continue to receive CCR and non-CCR wastestreams notwithstanding the deadline in § 257.101(a)(1) and to grant the alternative deadline of October 17, 2028, by which to complete closure of the impoundment.

APPENDIX A – SITE PLAN



APPENDIX B – WATER BALANCE DIAGRAM



ATTACHMENT 1 – RISK MITIGATION PLAN

RISK MITIGATION PLAN - 40 C.F.R. § 257.103(f)(2)(v)(B)

INTRODUCTION

To demonstrate that the criteria in 40 C.F.R. § 257.103(f)(2)(ii) has been met, Dynegy Midwest Generation, L.L.C. (DMG) has prepared this Risk Mitigation Plan for the Baldwin Energy Complex (BEC) Bottom Ash Pond.

• EPA is requiring a risk mitigation plan to "address the potential risk of continued operation of the CCR surface impoundment while the facility moves towards closure of their coal-fired boiler(s), to be consistent with the court's holding in *USWAG* that RCRA requires EPA to set minimum criteria for sanitary landfills that prevent harm to either human health or the environment." 85 Fed. Reg. at 53,516, 53,548 (Aug. 28, 2020).

As required by § 257.103(f)(2)(v)(B), the Risk Mitigation Plan must describe the "measures that will be taken to expedite any required corrective action," and contain the three following elements:

- First, "a discussion of any physical or chemical measures a facility can take to limit any future releases to groundwater during operation." § 257.103(f)(2)(v)(B)(1). In promulgating this requirement, EPA explained that this "might include stabilization of waste prior to disposition in the impoundment or adjusting the pH of the impoundment waters to minimize solubility of contaminants [and that] [t]his discussion should take into account the potential impacts of these measures on Appendix IV constituents." 85 Fed. Reg. at 53,548.
- Second, "a discussion of the surface impoundment's groundwater monitoring data and any found exceedances; the delineation of the plume (if necessary based on the groundwater monitoring data); identification of any nearby receptors that might be exposed to current or future groundwater contamination; and how such exposures could be promptly mitigated." § 257.103(f)(2)(v)(B)(2).
- Third, "a plan to expedite and maintain the containment of any contaminant plume that is either present or identified during continued operation of the unit." § 257.103(f)(2)(v)(B)(3). In promulgating this final requirement, EPA explained that "the purpose of this plan is to demonstrate that a plume can be fully contained and to define how this could be accomplished in the most accelerated timeframe feasible to prevent further spread and eliminate any potential for exposures." 85 Fed. Reg. at 53,549. In addition, EPA stated that "this plan will be based on relevant site data, which may include groundwater chemistry, the variability of local hydrogeology, groundwater elevation and flow rates, and the presence of any surface water features that would influence rate and direction of contamination movement. For example, based on the rate and direction of groundwater flow and potential for diffusion of the plume, this plan could identify the design and spacing of extraction wells necessary to prevent further downgradient migration of contaminated groundwater." 85 Fed. Reg. at 53,549.

Consistent with these requirements and guidance, Dynegy plans to continue to mitigate the risks to human health and the environment from the BEC Bottom Ash Pond as detailed in this Risk Mitigation Plan.

1 OPERATIONAL MEASURES TO LIMIT FUTURE RELEASES TO GROUNDWATER - 40 C.F.R. § 257.101(F)(2)(V)(B)(1)

The BEC Bottom Ash Pond is a 177-acre CCR surface impoundment. Consistent with the requirements of the CCR rule, compliance documents on Baldwin's CCR public website reflect the characterization of the BEC Bottom Ash Pond as a single unit for purposes of groundwater monitoring and closure activities.

The Baldwin CCR surface impoundment receives CCR transport waters from bottom ash, economizer ash, SCR ash and air heater Ash plus non-CCR process waters onsite before discharging to the Baldwin Cooling Pond via Outfall 002 or the Tertiary Pond via Outfall 001 in accordance with NPDES Permit No. IL0004171.

At Baldwin, none of the Appendix IV parameter have reported SSLs, or SSLs above their respective Ground Water Protection Standards (GWPSs) as sampled and analyzed per the facility's groundwater monitoring program. Therefore, Baldwin's current physical treatment operation adequately limits potential risks to human health and the environment during operation. Baldwin will continue this treatment process for the CCR surface impoundment until such time as closure is required per 40 CFR 257. The facility's current physical treatment process is discussed below.

1.1 CURRENT OPERATION OF PHYSICAL TREATMENT

Fly ash is captured dry. Therefore, current operations do not add fly ash transport waters to the CCR Impoundment.

As part of normal operations, bottom ash, economizer ash, SCR ash and air heater ash are transported through the sluice lines into the CCR surface impoundment where it is dewatered and transported offsite for beneficial reuse. The CCR surface impoundment is also a wastewater treatment settling system which allows the solids to settle.

Therefore, since fly ash transport water is not conveyed to the impoundment and bottom ash solids are removed from the impoundment, the current operation of Edwards' CCR impoundment limits future releases to groundwater during operation, and consequently no potential safety impacts or exposure to human health or environmental receptors are expected to result.

If Appendix IV releases are discovered per the facility's groundwater monitoring program, DMG will test, evaluate, and implement a chemical treatment method (i.e. pH adjustment, coagulation, precipitation, or other method as determined) for the Baldwin CCR Impoundment to limit potential risks to human health and the environment during operation.

2 GROUNDWATER IMPACTS, RECEPTORS, AND POTENTIAL EXPOSURE MITIGATION - 40 C.F.R. § 257.101(F)(2)(V)(B)(2)

The Baldwin Bottom Ash Pond is currently in assessment monitoring, with the first statistically significant levels (SSLs) with groundwater protection standard (GWPS) exceedances reported in August 2019. As seen on Table 1, SSL exceedances have been reported for lithium at one monitoring well - MW-370 (see Figure 1 for well locations). Alternate Source Demonstrations (ASDs) have been completed for lithium following each SSL determination (see Attachment 1, 2019 Annual Groundwater Monitoring and Corrective Action Report, Baldwin Bottom Ash Pond [Ramboll, 2020]. The latest ASD for lithium was completed in April 2020 and will be included in the 2020 Annual Groundwater Monitoring and Corrective Action Report.

Since there have been no SSLs or GWPS exceedances for any Appendix IV constituents attributable to the Bottom Ash Pond to date, no plume delineation maps have been necessary.

Receptors

Should a release to groundwater for one or more Appendix IV constituents occur in the future, the two primary risks to human health and environmental receptors are via impacted groundwater and surface water. Groundwater potentially impacted by CCR constituents from the Bottom Ash Pond that is used for residential purposes, including for drinking water, is likely an incomplete pathway for the reasons listed below. Surface water exposure would be from potential impacts via groundwater discharge to nearby surface water bodies – specifically the Kaskaskia River to the west and the Baldwin Plant Cooling Lake to the north. The southerly-flowing Kaskaskia River is located approximately 1,110 feet west of the BEC property at its closest point and approximately 5,000 feet (0.95 miles) from the Bottom Ash Pond. Groundwater flow is to the southwest and away from the Baldwin Plant Cooling Lake, therefore the risk to the lake via a groundwater pathway from the Bottom Ash Pond is considered very low.

Ambient groundwater flow in the Uppermost Aquifer (Pennsylvanian and Mississippian bedrock; mainly shale and interbedded non-karst limestone) and overlying unlithified materials (clay, silt, and intermittent sand lenses) beneath the Bottom Ash Pond is generally to the west and southwest. Changes in groundwater elevation near the Bottom Ash Pond generally mimic bedrock surface topography. General groundwater flow direction is west and southwest toward the Kaskaskia River (i.e., regional discharge area) with localized flow toward bedrock surface lows, specifically the former bedrock valley feature beneath the non-CCR Secondary Pond and Tertiary Pond. The hydraulic gradient beneath the impoundments (Bottom Ash Pond and closed/capped Fly Ash Ponds) has ranged from 0.01 to 0.02 ft/ft as groundwater flows from east to west, with a flow velocity of approximately 0.0005 to 0.001 ft/day based on a bedrock hydraulic conductivity of 5 x 10^{-6} cm/s and a median effective porosity of 30 percent (refer to the description of hydrogeology attached to the alternative closure demonstration letter).

There are no industrial, commercial or domestic use water wells located in a downgradient or cross-gradient groundwater flow direction relative to the Bottom Ash Pond that are at risk of impacts from a release to groundwater. Two shallow Community Water Supply (CWS) wells for the villages of Baldwin and Red Bud, installed in sand and gravel alluvial deposits, are located along the opposite bank of the Kaskaskia River downstream from the BEC. The closest CWS well is located approximately 6,500 feet (1.2 miles) from the Bottom Ash Pond and 3,000 feet downstream from the BEC's outfall to the Kaskaskia River. Neither of these CWS wells are considered at risk because of their hydrogeologic location relative to the BEC property, including the Bottom Ash Pond. In addition, there is one CWS surface water intake for the village of Sparta (i.e., Sparta intake), located within a meander of the Kaskaskia River approximately 1,200 feet southwest of the nearest site boundary, approximately

4,800 feet (~0.9 mile) feet southwest of the Bottom Ash Pond, and 2,200 feet downstream from the NPDES permitted outfall for the ash pond system. The Sparta intake was studied by the Illinois State Water Survey (ISWS,1995). Based upon comprehensive field sampling and analysis of water from the Kaskaskia River, Sparta intake, and BEC's outfall, followed by modeling, statistical analysis, and risk-assessment analyses of the data, the ISWS concluded that the probability of the river standard for boron of 1.0 milligrams per Liter (mg/L) being exceeded was "small", with a proposed adjusted surface water quality standard of 1.23 mg/L being exceeded only once every 25 years downstream of BEC's outfall.

Exposure Mitigation

Mitigation of future potential exposures to groundwater contamination from continued operation of the Bottom Ash Pond is discussed in detail in the following section.

3 CONTAMINANT PLUME CONTAINMENT: OPTIONS EVALUATION AND PLAN - 40 C.F.R. § 257.101(F)(2)(V)(B)(3)

Appropriate corrective measure(s) to address future potential impacted groundwater associated with the Bottom Ash Pond are based on impacts to the Uppermost Aquifer (shale and non-karst limestone bedrock) and overlying unlithified materials. Since there has been no release of Appendix IV constituents to groundwater above GWPS(s), which would trigger a Corrective Measures Assessment (CMA) under 40 C.F.R. § 257.96 based on specific parameter concentrations and contaminant plume dimensions, several options are evaluated to address potential future plume containment. The evaluation criteria for assessing remedial options are the following: performance; reliability; ease of implementation; potential impacts of the remedies (safety, cross-media, and control of exposure to residual contamination); time required to begin and complete the remedy; and, institutional requirements that may substantially affect implementation of the remedy(s), such as permitting, environmental or public health requirements.

Although future potential source control measures (e.g. closure in place, closure by removal to off-site landfill, insitu solidification/stabilization) are typically considered as part of a CMA process, the shorter-term options considered for mitigating groundwater impacts relative to a potential future release of one or more Appendix IV constituents at Baldwin are as follows:

- Monitored Natural Attenuation (MNA)
- Groundwater Extraction
- Groundwater Cutoff Wall
- In-Situ Chemical Treatment/Permeable Reactive Barrier

These same groundwater remedial corrective measures will be evaluated for all Appendix IV constituents that present a future risk to human health or the environment.

Monitored Natural Attenuation (MNA)

Upon notification of a release of one or more Appendix IV parameter(s) to groundwater, MNA will be evaluated with site-specific characterization data and geochemical analysis as a long term remedial option, combined with source control measures, through application of the USEPA's tiered approach to MNA (USEPA 1999, 2007 and 2015):

- 1. Demonstrate that the area of groundwater impacts is not expanding.
- 2. Determine the mechanisms and rates of attenuation.
- 3. Determine that the capacity of the aquifer is sufficient to attenuate the mass of constituents in groundwater and that the immobilized constituents are stable and will not remobilize.
- 4. Design a performance monitoring program based on the mechanisms of attenuation and establish contingency remedies (tailored to site-specific conditions) should MNA not perform adequately.

All inorganic compounds are subject to physical attenuation processes. Physical mechanisms may be the primary natural attenuation processes acting upon CCR constituents such as boron, chloride and lithium, that are relatively mobile (poorly chemically attenuated). The performance of MNA as a groundwater corrective measure varies

based on site-specific conditions. Additional data collection and analysis may be required to support the USEPA's tiered approach to MNA (USEPA, 2015) and obtain regulatory approval.

MNA is not regarded as a short-term remedial option for contaminant plume containment, but as a potential long-term option following implementation of shorter term control measures.

Groundwater Extraction

This corrective measure includes installation of a series of groundwater pumping wells or trenches to control and extract impacted groundwater. Groundwater extraction captures and contains impacted groundwater and can limit plume expansion and/or off-site migration. Construction of a groundwater extraction system typically includes, but is not limited to, the following primary project components:

- Designing and constructing a groundwater extraction system consisting of a series of extraction wells or trenches located around the perimeter of the contaminant plume and operating at a rate to allow capture of CCR impacted groundwater.
- Designing a system to manage extracted groundwater, which may include modification to the existing NPDES permit, including treatment prior to discharge, if necessary.
- Ongoing inspection and maintenance of the groundwater extraction system.

Installation of a groundwater extraction system, whether wells or trenches, can be expedited with the assumption that there is a good conceptual site model (CSM) of the hydrogeological system around the CCR unit, groundwater flow and transport model, and aquifer test if a well system is the best option for intercepting the groundwater contaminant plume. The Baldwin Bottom Ash Pond has had full hydrogeological characterization, development of a CSM, and groundwater modeling performed. Upon notification of an SSL exceedance of a GWPS for one or more Appendix IV constituents, an aquifer test will be conducted, and groundwater model developed for designing a groundwater extraction system for optimization of contaminant plume capture.

Implementation of a groundwater extraction system presents design challenges due to the low permeability and heterogeneous lithology of the Uppermost Aquifer. Details of the bedrock bedding planes, fracture distribution and density, as well as the contaminant distribution within the fracture system, would be needed to effectively design the extraction system. Extracted groundwater would need to be managed, which may include modification to the existing NPDES permit and treatment prior to discharge, if necessary. Additional data collection and analyses would be required to design an extraction system. Construction could be completed within 1 year.

A schematic of a typical groundwater extraction well is shown on Figure 2. Based on site specific hydrogeology and future potential plume width and depth, a groundwater extraction system will typically consist of one to three extraction wells with pitless adapter's manifolded together with HDPE conveyance pipe to a common tank or lined collection vault prior to treatment, if necessary, and discharge.

Groundwater Cutoff Wall

Vertical cutoff walls are used to control and/or isolate impacted groundwater. Low permeability cutoff walls can be used to prevent horizontal off-site migration of potentially impacted groundwater. Cutoff walls act as barriers to migration of impacted groundwater and can isolate soils that have been impacted by CCR to prevent contact with unimpacted groundwater. Cutoff walls are often used in conjunction with an interior pumping system to establish a reverse gradient within the cutoff wall. The reverse gradient maintains an inward flow through the wall, keeping it from acting as a groundwater dam and controlling potential end-around or breakout flow of contaminated groundwater. A commonly used cutoff wall construction technology is the slurry trench method, which consists of excavating a trench and backfilling it with a soil-bentonite mixture, often created with the soils excavated from the trench. The trench is temporarily supported with bentonite slurry that is pumped into the trench as it is excavated. Excavation for cutoff walls is conducted with conventional hydraulic excavators, hydraulic excavators equipped with specialized booms to extend their reach (*i.e.*, long-stick excavators), or chisels and clamshells, depending upon the depth of the trench and the material to be excavated. For a cutoff wall to be technically feasible, there must be a low-permeability lower confining layer into which the barrier can be keyed, and it must be at a technically feasible depth.

Cutoff walls could be used in combination with groundwater extraction. The strength of the bedrock and the required cutoff wall design depth are not known; verifying whether a cutoff wall could be constructed in the Uppermost Aquifer would be necessary. The effectiveness of a cutoff wall as a hydraulic barrier also relies on the contrast between the hydraulic conductivity of the aquifer and the cutoff wall. The most effective barriers have hydraulic conductivity values that are several orders of magnitude lower than the aquifer that it is in contact with. A cutoff wall designed with hydraulic conductivity of 1×10^{-7} cm/sec would be less than two orders of magnitude lower than the aquifer with a mean conductivity of 5×10^{-6} cm/sec.

Additional data collection and analyses would be required to design a cutoff wall. Construction could be completed within 2 to 3 years following characterization, design, permitting and construction. To attain GWPS, cutoff walls require a separate groundwater corrective measures to operate in concert with the hydraulic barriers. Cutoff walls are commonly coupled with MNA and/or groundwater extraction as groundwater corrective measures. The time to attain GWPS is dependent on the selected groundwater corrective measures that are coupled with the cutoff walls. Cutoff walls require approval by the Illinois Environmental Protection Agency (IEPA) to be implemented.

In-Situ Chemical Treatment/Permeable Reactive Barrier

Chemical treatment via a Permeable Reactive Barrier (PRB) is defined as an emplacement of reactive materials in the subsurface designed to intercept a contaminant plume, provide a flow path through the reactive media, and transform or otherwise render the contaminant(s) into environmentally acceptable forms to attain remediation concentration goals downgradient of the barrier (Powell and Powell, 1998; Powell et al., 1998; cited by EPRI, 2006).

As groundwater passes through the PRB under natural gradients, dissolved constituents in the groundwater react with the media and are transformed or immobilized. A variety of media have been used or proposed for use in PRBs. Zero-valent iron has been shown to effectively immobilize some CCR constituents, including arsenic, chromium, selenium, sulfate and molybdenum. It has not been proven effective for boron, antimony, or lithium (EPRI, 2006).

System configurations include continuous PRBs, in which the reactive media extends across the entire path of the contaminant plume; and funnel-and-gate systems, where barrier walls are installed to control and direct groundwater flow through a permeable gate containing the reactive media. Continuous PRBs intersect the entire contaminant plume and do not materially impact the groundwater flow system. Design may or may not include keying the PRB into a low-permeability unit at depth. Funnel and gate systems utilize a system of barriers to groundwater flow (funnels) to direct the contaminant plume through the reactive gate. The barriers, typically some form of cutoff wall, are keyed into a low-permeability unit at depth to prevent short circuiting of the plume. Funnel and gate design must consider the residence time to allow chemical reactions to occur. Directing the

contaminant plume through the reactive gate can significantly increase the flow velocity, thus reducing residence time.

The Uppermost Aquifer is a Bedrock Unit consisting mainly of limestone and shale overlain by unlithified, finegrained soil deposits of variable thickness. Constructing an effective PRB system, including emplacement of reactive media, within the bedrock of the Uppermost Aquifer would be difficult, and may not be possible. In addition, CCR constituents in the Uppermost Aquifer that could potentially exceed their GWPS(s) may not be amenable to transformation or immobilization using reactive media. Therefore, in-situ chemical treatment and PRB are not retained as a viable corrective measure to address future potential SSLs above GWPS(s) in the Uppermost Aquifer.

3.1 CONTAINMENT PLAN

Based on the options evaluated for containment of a future potential groundwater contaminant plume originating from the Baldwin Bottom Ash Pond for one or more Appendix IV constituents exceeding their GWPS(s), the most viable short-term option of those evaluated is a groundwater extraction system, which would allow for capture of impacted groundwater and prevent further plume migration towards the principal receptor, which is the Kaskaskia River to the west and southwest.

In circumstances where there is not an immediate concern of endangerment to human health or the environment, other longer-term corrective measures may be more viable. The principal method under consideration for controlling potential future Appendix IV parameter releases is MNA. MNA is a potentially viable corrective measure that will be further evaluated for use at the Bottom Ash Pond.

Depending on the location and plume geometry of any future potential Appendix IV exceedances of GWPSs, the specific parameter(s) with exceedances, and the other groundwater corrective measures discussed as part of the corrective options evaluation, a groundwater cutoff wall is a secondary remedial alternative available for consideration following the current primary options of groundwater extraction for short-term application and MNA for long-term application.

4 **R**EFERENCES

Electric Power Research Institute (EPRI), 2006. Groundwater Remediation of Inorganic Constituents at Coal Combustion Product Management Sites, Overview of Technologies, Focusing on Permeable Reactive Barriers. Electric Power Research Institute, Palo Alto, California. Final Report 1012584, October 2006.

Illinois State Water Survey (ISWS), 1995. Illinois Power Company – Baldwin Power Plant Ash-Pond Effluent Boron Mixing with the Kaskaskia River. Office of River Water Quality, Peoria, IL and Office of Surface Water Resources, Champaign, IL; ISWS Contract Report 588. October 1995.

Ramboll, 2020. 2019 Annual Groundwater Monitoring and Corrective Action Report, Baldwin Bottom Ash Pond, Baldwin Energy Complex. Ramboll, Milwaukee, Wisconsin. January 31, 2020.

USEPA, 1999. Use of Monitored Natural Attenuation at Superfund, RCRA Corrective Action, and Underground Storage Tank Sites. Directive No. 9200.U-17P. Washington, D.C.: EPA, Office of Solid Waste and Emergency Response.

USEPA, 2007. Monitored Natural Attenuation of Inorganic Contaminants in Ground Water, Volume 1 – Technical Basis for Assessment. EPA/600/R-07/139. National Risk Management Research Laboratory, Office of Research and Development, U.S. Environmental Protection Agency, Cincinnati, Ohio. October 2007.

USEPA, 2015. Use of Monitored Natural Attenuation for Inorganic Contaminants in Groundwater at Superfund Sites. Directive No. 9283.1-36. U.S. Environmental Protection Agency, Office of Solid Waste and Emergency Response. August 2015.

TABLES


Table 1 - Assessment Monitoring Program Summary, Baldwin Bottom Ash Ponc

Sampling Dates	Analytical Data Receipt Date	Parameters Collected	SSL(s) Appendix IV	SSL(s) Determination Date	ASD Completion Date	CMA Completion / Status
June 26-27, 2018	August 22, 2018	Appendix III Appendix IV	NA	NA	NA	NA
September 26, 2018	October 24, 2018	Appendix III Appendix IV Detected ¹	Lithium (MW-370)	January 7, 2019	April 8, 2019	NA
March 19-20, 2019	April 15, 2019	Appendix III Appendix IV	Lithium (MW-370)	July 15, 2019	October 14, 2019	NA
September 24-25, 2019	October 24, 2019	Appendix III Appendix IV Detected ¹	Lithium (MW-370)	January 22, 2020	April 21, 2020	NA
March 25-26, 2020	April 28, 2020	Appendix III Appendix IV Detected	Lithium (MW-370)	July 27, 2020	TBD	TBD
						[O: RAB 9/11/20; C: EJT 9/14/20]

Notes: CMA = Corrective Measures Assessment NA = Not Applicable TBD = To Be Determined 1. Groundwater sample analysis was limited to Appendix IV parameters detected in previous events in accordance with 40 C.F.R. Part 257.95(d)(1).



FIGURES



BOTTOM ASH POND DOWNGRADIENT CCR MONITORING WELL LOCATION

- BOTTOM ASH POND BACKGROUND CCR MONITORING WELL LOCATION
- BOTTOM ASH POND POREWATER SAMPLE LOCATION
- BOTTOM ASH POND UNIT BOUNDARY

800 Feet MONITORING WELL AND BOTTOM ASH POND

1. 13

BOTTOM ASH POND

TPZ-164




FIGURE 1

RAMBOLL US CORPORATION A RAMBOLL COMPANY



WATER SAMPLE LOCATION MAP

BALDWIN BOTTOM ASH POND (UNIT ID: 601) ALTERNATE SOURCE DEMONSTRATION BALDWIN ENERGY COMPLEX BALDWIN, ILLINOIS




FIGURE 2

TYPICAL HYDRAULIC GRADIENT CONTROL WELL DETAIL

NOTES

1. NOT TO SCALE

DYNEGY MIDWEST GENERATION L.L.C BALDWIN BOTTOM ASH POND BALDWIN, ILLINOIS

RAMBOLL

A RAMBOLL COMPANY

RAMBOLL US CORPORATION

ATTACHMENT 1

Prepared for **Dynegy Midwest Generation, LLC** Document type **2019 Annual Groundwater Monitoring and Corrective Action Report** Date **January 31, 2020**

2019 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT BALDWIN BOTTOM ASH POND, BALDWIN ENERGY COMPLEX



2019 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT BALDWIN BOTTOM ASH POND, BALDWIN ENERGY COMPLEX

Project name	Baldwin Energy Complex
Project no.	72751
Recipient	Dynegy Midwest Generation, LLC
Document type	Annual Groundwater Monitoring and Corrective Action Report
Version	FINAL
Date	January 31, 2020
Prepared by	Kristen L. Theesfeld
Checked by	Jacob J. Walczak
Approved by	Eric J. Tlachac
Description	Annual Report in Support of the CCR Rule Groundwater Monitoring Program

Ramboll 234 W. Florida Street Fifth Floor Milwaukee, WI 53204 USA

T 414-837-3607 F 414-837-3608 https://ramboll.com

Kristen L. Theesfeld Hydrogeologist

Jacob J. Walczak, PG Senior Hydrogeologist

CONTENTS

EXECU	JTIVE SUMMARY	3
1.	Introduction	4
2.	Monitoring and Corrective Action Program Status	5
3.	Key Actions Completed in 2019	6
4.	Problems Encountered and Actions to Resolve the Problems	8
5.	Key Activities Planned for 2020	9
6.	References	10

TABLES

Table A	2018-2019 Assessment Monitoring Program Summary (in text)
Table 1	2019 Analytical Results – Groundwater Elevation and Appendix III Parameters
Table 2	2019 Analytical Results – Appendix IV Parameters
Table 3	Statistical Background Values
Table 4	Groundwater Protection Standards

FIGURES

Figure 1 Monitoring Well Location Map

APPENDICES

Appendix A Alternate Source Demonstrations

ACRONYMS AND ABBREVIATIONS

ASD	Alternate Source Demonstration
BAP	Bottom Ash Pond
CCR	Coal Combustion Residuals
GWPS	Groundwater Protection Standard
SAP	Sampling and Analysis Plan
SSI	Statistically Significant Increase
SSL	Statistically Significant Level

EXECUTIVE SUMMARY

This report has been prepared to provide the information required by Title 40 of the Code of Federal Regulations (40 C.F.R.) § 257.90(e) for Baldwin Bottom Ash Pond (BAP) located at Baldwin Energy Complex near Baldwin, Illinois.

Groundwater is being monitored at Baldwin BAP in accordance with the Assessment Monitoring Program requirements specified in 40 C.F.R. § 257.95.

No changes were made to the monitoring system in 2019 (no wells were installed or decommissioned).

The following Statistically Significant Levels (SSLs) of 40 C.F.R. Part 257 Appendix IV parameters were determined during one or more sampling events in 2019:

• Lithium at well MW-370

Alternate Source Demonstrations (ASDs) were completed for the SSLs referenced above and Baldwin BAP remains in the Assessment Monitoring Program.

1. INTRODUCTION

This report has been prepared by Ramboll on behalf of Dynegy Midwest Generation, LLC, to provide the information required by 40 C.F.R.§ 257.90(e) for Baldwin BAP located at Baldwin Energy Complex near Baldwin, Illinois.

In accordance with 40 C.F.R. § 257.90(e), the owner or operator of a Coal Combustion Residuals (CCR) unit must prepare an Annual Groundwater Monitoring and Corrective Action Report for the preceding calendar year that documents the status of the Groundwater Monitoring and Corrective Action Program for the CCR unit, summarizes key actions completed, describes any problems encountered, discusses actions to resolve the problems, and projects key activities for the upcoming year. At a minimum, the Annual Report must contain the following information, to the extent available:

- 1. A map, aerial image, or diagram showing the CCR unit and all background (or upgradient) and downgradient monitoring wells, to include the well identification numbers, that are part of the groundwater monitoring program for the CCR unit.
- 2. Identification of any monitoring wells that were installed or decommissioned during the preceding year, along with a narrative description of why those actions were taken.
- 3. In addition to all the monitoring data obtained under §§ 257.90 through 257.98, a summary including the number of groundwater samples that were collected for analysis for each background and downgradient well, the dates the samples were collected, and whether the sample was required by the Detection Monitoring or Assessment Monitoring Programs.
- 4. A narrative discussion of any transition between monitoring programs (e.g., the date and circumstances for transitioning from Detection Monitoring to Assessment Monitoring in addition to identifying the constituent(s) detected at a Statistically Significant Increase relative to background levels).
- 5. Other information required to be included in the Annual Report as specified in §§ 257.90 through 257.98.

This report provides the required information for Baldwin BAP for calendar year 2019.

2. MONITORING AND CORRECTIVE ACTION PROGRAM STATUS

No changes have occurred to the Monitoring Program status in calendar year 2019, and Baldwin BAP remains in the Assessment Monitoring Program in accordance with 40 C.F.R. § 257.95.

3. KEY ACTIONS COMPLETED IN 2019

The Assessment Monitoring Program is summarized in Table A. The groundwater monitoring system, including the CCR unit and all background and downgradient monitoring wells, is presented in Figure 1. No changes were made to the monitoring system in 2019 (no wells were installed or decommissioned). In general, one groundwater sample was collected from each background and downgradient well during each monitoring event. All samples were collected and analyzed in accordance with the Sampling and Analysis Plan (SAP) (NRT/OBG, 2017a). All monitoring data obtained under 40 C.F.R. §§ 257.90 through 257.98 (as applicable) in 2019 are presented in Tables 1 and 2. Analytical data were evaluated in accordance with the Statistical Analysis Plan (NRT/OBG, 2017b) to determine any SSLs of Appendix IV parameters over Groundwater Protection Standards (GWPSs).

Statistical background values are provided in Table 3 and GWPSs in Table 4.

Analytical results for the June and September 2018 sampling events were provided in the 2018 Annual Groundwater Monitoring and Corrective Action Report.

Potential alternate sources were evaluated as outlined in the 40 C.F.R. § 257.95(g)(3)(ii). ASDs were completed and certified by a qualified professional engineer. The dates the ASDs were completed are provided in Table A. The ASDs completed in 2019 are included in Appendix A.

Sampling Dates	Analytical Data Receipt Date	Parameters Collected	SSL(s)	SSL(s) Determination Date	ASD Completion Date
June 26-27, 2018	August 22, 2018	Appendix III Appendix IV	NA	NA	NA
September 26, 2018	October 24, 2018	Appendix III Appendix IV Detected ¹	Lithium (MW-370)	January 7, 2019	April 8, 2019
March 19-20, 2019	April 15, 2019	Appendix III Appendix IV	Lithium (MW-370)	July 15, 2019	October 14, 2019
September 24-25, 2019	October 24, 2019	Appendix III Appendix IV Detected ¹	NA	TBD	TBD

Table A – 2018-2019 Assessment Monitoring Program Summary

Notes:

NA: Not Applicable

TBD: To Be Determined

1. To confirm SSIs, as allowed by the Statistical Analysis Plan, groundwater samples were collected and analyzed for Appendix III parameters initially detected at concentrations greater than statistical background values in the preceding sampling event.

4. PROBLEMS ENCOUNTERED AND ACTIONS TO RESOLVE THE PROBLEMS

No problems were encountered with the Groundwater Monitoring Program during 2019. Groundwater samples were collected and analyzed in accordance with the SAP (NRT/OBG, 2017a), and all data were accepted.

5. KEY ACTIVITIES PLANNED FOR 2020

The following key activities are planned for 2020:

- Continuation of the Assessment Monitoring Program with semi-annual sampling scheduled for the first and third quarters of 2020.
- Complete evaluation of analytical data from the downgradient wells, using GWPSs to determine whether an SSL of Appendix IV parameters has occurred.
- If an SSL is identified, potential alternate sources (i.e., a source other than the CCR unit caused the SSL or that that SSL resulted from error in sampling, analysis, statistical evaluation, or natural variation in groundwater quality) will be evaluated.
 - If an alternate source is demonstrated to be the cause of the SSL, a written demonstration will be completed within 90 days of SSL determination and included in the 2020 Annual Groundwater Monitoring and Corrective Action Report.
 - If an alternate source(s) is not identified to be the cause of the SSL, the applicable requirements of 40 C.F.R. §§ 257.94 through 257.98 (e.g., assessment of corrective measures) as may apply in 2020 will be met, including associated recordkeeping/notifications required by 40 C.F.R. §§ 257.105 through 257.108.

6. **REFERENCES**

Natural Resource Technology, an OBG Company (NRT/OBG), 2017a. Sampling and Analysis Plan, Baldwin Bottom Ash Pond, Baldwin Energy Complex, Baldwin, Illinois, Project No. 2285, Revision 0, October 17, 2017.

Natural Resource Technology, an OBG Company (NRT/OBG), 2017b. Statistical Analysis Plan, Baldwin Energy Complex, Havana Power Station, Hennepin Power Station, Wood River Power Station, Dynegy Midwest Generation, LLC, October 17, 2017.

TABLES

TABLE 1.

2019 ANALYTICAL RESULTS - GROUNDWATER ELEVATION AND APPENDIX III PARAMETERS 2019 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

BALDWIN ENERGY COMPLEX

UNIT ID 601 - BALDWIN BOTTOM ASH POND

BALDWIN, ILLINOIS

ASSESSMENT MONITORING PROGRAM

				Depth to Groundwater (ft) ¹	Groundwater Elevation (ft NAVD88)	40 C.F.R. Part 257 Appendix III								
Well I dentification Number	Latitude (Decimal Degrees)	Longitude (Decimal Degrees)	Date & Time Sampled			Boron, total (mg/L)	Calcium, total (mg/L)	Chloride, total (mg/L)	Fluoride, total (mg/L)	pH (field) (S.U.)	Sulfate, total (mg/L)	Total Dissolved Solids (mg/L)		
						6020A ²	6020A ²	9251 ²	9214 ²	SM 4500 H+B ²	9036 ²	SM 2540C ²		
Background /	Upgradient Mo	nitoring Wells												
MW-304	-304 38.188332 -89.85	-89.853441	3/20/2019 15:03	9.33	446.16	1.82	13.7	148	1.88	7.7	177	1390		
10100-304	30.100332	-89.853441	9/25/2019 13:11	9.30	446.19	1.84	18.4	152	1.74	7.9	169	1350		
MW-306	38.201117	-89.846747	3/20/2019 14:16	16.98	436.19	0.174	50.4	62	0.65	11.4	32	330		
MW-306 38.20111	38.201117	-89.840/4/	9/25/2019 14:22	18.10	435.07	0.166	46.0	62	0.59	11.0	37	318		
Downgradient	t Monitoring We	lls												
MW-356 38.19	38,198963	-89.869578	3/19/2019 10:51	2.65	424.95	2.12	11.7	31	2.18	7.8	43	678		
10100-350	30.190903		9/24/2019 10:32	3.02	424.58	2.04	11.6	29	2.00	7.7	38	644		
MW-369	38,196986	-89.870258	3/19/2019 10:09	19.44	403.27	1.96	70.7	92	1.48	7.3	98	732		
10100-309	36.190960	-09.070236	9/24/2019 9:50	13.10	409.61	0.948	85.0	101	1.08	6.7	90	788		
MW-370	38.195603	-89.869669	3/19/2019 11:30	17.50	403.35	2.01	46.7	1280	3.45	7.7	224	2950		
10100-370	30.193003	-07.009009	9/24/2019 11:10	18.98	401.87	1.95	47.0	1290	3.00	7.5	237	2830		
MW-382	38,194540	90 969044	3/19/2019 12:26	15.42	415.77	1.86	21.5	36	3.30	7.6	426	1180		
10100-382	30.194540	-89.868044	9/24/2019 12:10	16.23	414.96	1.78	20.5	34	2.85	7.7	388	1150		

Notes:

40 C.F.R. = Title 40 of the Code of Federal Regulations

ft = foot/feet

mg/L = milligrams per liter

NAVD88 = North American Vertical Datum of 1988

S.U. = Standard Units

< = concentration is less than the concentration shown, which corresponds to the reporting limit for the method; estimated concentrations below the reporting limit and associated qualifiers are not provided since not

utilized in statistics to determine Statistically Significant Increases (SSIs) over background.

¹All depths to groundwater were measured on the first day of the sampling event.

²4-digit numbers represent SW-846 analytical methods.



TABLE 2. 2019 ANALYTICAL RESULTS - APPENDIX IV PARAMETERS

2019 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

BALDWIN ENERGY COMPLEX

UNIT ID 601 - BALDWIN BOTTOM ASH POND

BALDWIN, ILLINOIS

ASSESSMENT MONITORING PROGRAM

40 C.F.R. Part 257 Appendix IV																		
Well I dentification Number	Latitude (Decimal Degrees)	Longitude (Decimal Degrees)	Date & Time Sampled	Antimony, total (mg/L)	Arsenic, total (mg/L)	Barium, total (mg/L)	Beryllium, total (mg/L)	Cadmium, total (mg/L)	Chromium, total (mg/L)	Cobalt, total (mg/L)	Fluoride, total (mg/L)	Lead, total (mg/L)	Lithium, total (mg/L)	Mercury, total (mg/L)	Molybdenum, total (mg/L)	Radium 226/228, Combined (pCi/L)	Selenium, total (mg/L)	Thallium, total (mg/L)
				6020A ¹	6020A ¹	6020A ¹	6020A ¹	6020A ¹	6020A ¹	6020A ¹	6020A ¹	6020A ¹	6020A ¹	7470A ¹	6020A ¹	903/904 ¹	6020A ¹	6020A ¹
Background /	' Upgradient M	lonitoring Wells	6															
MW-304	38.188332	-89.853441	3/20/2019 15:03	<0.0010	0.0029	0.0214	<0.0010	<0.0010	<0.0015	<0.0010	1.88	<0.0010	0.0833	<0.00020	0.0019	0.55	<0.0010	<0.0020
10100-304	30.100332	-09.003441	9/25/2019 13:11 ²	<0.0010	0.0017	0.0211	<0.0010	<0.0010	<0.0015	<0.0010	1.74	<0.0010	0.0836	<0.00020	0.0017	0.42	<0.0010	<0.0020
MW-306	38.201117	-89.846747	3/20/2019 14:16	<0.0010	0.0030	0.0192	<0.0010	<0.0010	<0.0015	<0.0010	0.65	<0.0010	0.0143	<0.00020	0.0299	0.74	<0.0010	<0.0020
10100-306	38.201117	-89.840747	9/25/2019 14:22 ²	<0.0010	0.0021	0.0150	<0.0010	<0.0010	<0.0015	<0.0010	0.59	<0.0010	0.0133	<0.00020	0.0267	0.36	<0.0010	<0.0020
Downgradien	t Monitoring W	/ells																
MW-356	38.198963	-89.869578	3/19/2019 10:51	<0.0010	0.0011	0.0322	<0.0010	<0.0010	<0.0015	<0.0010	2.18	<0.0010	0.0578	<0.00020	<0.0015	0.19	<0.0010	<0.0020
10100-350	30.190903	-09.009370	9/24/2019 10:32 ²	NA	<0.0010	0.0307	NA	NA	<0.0015	NA	2.00	NA	0.0580	NA	<0.0015	0.10	NA	NA
MW-369	38.196986	-89.870258	3/19/2019 10:09	<0.0010	0.0021	0.0562	<0.0010	<0.0010	<0.0015	<0.0010	1.48	< 0.0010	0.0382	<0.00020	0.0263	0.34	<0.0010	<0.0020
10100-307	30.190900	-09.070230	9/24/2019 9:50 ²	NA	0.0059	0.0849	NA	NA	<0.0015	NA	1.08	NA	0.0259	NA	0.0186	0.84	NA	NA
MW-370	38.195603	-89.869669	3/19/2019 11:30	<0.0010	0.0015	0.0449	<0.0010	<0.0010	<0.0015	<0.0010	3.45	<0.0010	0.147	<0.00020	0.0238	0.61	<0.0010	<0.0020
WW-370 38.195603	30.173003	-89.869669	9/24/2019 11:10 ²	NA	<0.0010	0.0424	NA	NA	<0.0015	NA	3.00	NA	0.149	NA	0.0188	0.75	NA	NA
MW-382	38.194540	-89.868044	3/19/2019 12:26	<0.0010	0.0012	0.0170	<0.0010	<0.0010	0.0021	<0.0010	3.30	<0.0010	0.0625	<0.00020	0.0019	0.16	<0.0010	<0.0020
10100-302	30.174340	-07.008044	9/24/2019 12:10 ²	NA	0.0012	0.0221	NA	NA	0.0044	NA	2.85	NA	0.0623	NA	0.0025	0.51	NA	NA

[O: RAB 12/23/19, C: KLT 12/23/19]

Notes:

40 C.F.R. = Title 40 of the Code of Federal Regulations

mg/L = milligrams per liter

NA = Not Analyzed

pCi/L = picoCuries per liter

< = concentration is less than concentration shown, which corresponds to the reporting limit for the method; estimated concentrations below the reporting limit and associated qualifiers are not provided since not utilized in statistics to determine

Statistically Significant Levels (SSLs) over Groundwater Protection Standards.

¹4-digit numbers represent SW-846 analytical methods and 3-digit numbers represent Clean Water Act analytical methods.

²Only the parameters detected during the previous sampling events were analyzed during this sampling event, in accordance with 40 C.F.R. § 257.95(d)(1).

TABLE 3. STATISTICAL BACKGROUND VALUES 2019 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT BALDWIN ENERGY COMPLEX UNIT ID 601 - BALDWIN BOTTOM ASH POND BALDWIN, ILLINOIS ASSESSMENT MONITORING PROGRAM

Parameter	Statistical Background Value (UPL)				
40 C.F.R. Part 257 A	ppendix III				
Boron (mg/L)	2.11				
Calcium (mg/L)	33.5				
Chloride (mg/L)	155				
Fluoride (mg/L)	1.98				
pH (S.U.)	7.8 / 11.2				
Sulfate (mg/L)	200				
Total Dissolved Solids (mg/L)	1360				
[O: RAB 12/22/19, C: KLT 12/23/19]					

Notes:

40 C.F.R. = Title 40 of the Code of Federal Regulations

mg/L = milligrams per liter S.U. = Standard Units

UPL = Upper Prediction Limit







TABLE 4. GROUNDWATER PROTECTION STANDARDS 2019 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT BALDWIN ENERGY COMPLEX UNIT ID 601 - BALDWIN BOTTOM ASH POND BALDWIN, ILLINOIS ASSESSMENT MONITORING PROGRAM

Parameter	Groundwater Protection Standard ¹								
40 C.F.R. Part 257 Appendix IV									
Antimony (mg/L)	0.006								
Arsenic (mg/L)	0.032								
Barium (mg/L)	2								
Beryllium (mg/L)	0.004								
Cadmium (mg/L)	0.005								
Chromium (mg/L)	0.10								
Cobalt (mg/L)	0.006								
Fluoride (mg/L)	4								
Lead (mg/L)	0.015								
Lithium (mg/L)	0.069								
Mercury (mg/L)	0.002								
Molybdenum (mg/L)	0.10								
Radium 226+228 (pCi/L)	5								
Selenium (mg/L)	0.05								
Thallium (mg/L)	0.002								

[O: RAB 12/22/19, C: KLT 12/23/19]

Notes:

40 C.F.R. = Title 40 of the Code of Federal Regulations

mg/L = milligrams per liter

pCi/L = picoCuries per liter

 $^{\rm 1}{\rm Groundwater}$ Protection Standard is the higher of the Maximum Contaminant Level /

Health-Based Level or background.



FIGURES



DOWNGRADIENT MONITORING WELL LOCATION

- UPGRADIENT MONITORING WELL LOCATION
- CCR MONITORED UNIT

MONITORING WELL LOCATION MAP **BALDWIN BOTTOM ASH POND UNIT ID:601**

2019 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT VISTRA CCR RULE GROUNDWATER MONITORING BALDWIN ENERGY COMPLEX BALDWIN, ILLINOIS

400 800 ____ Feet

FIGURE 1

O'BRIEN & GERE ENGINEERS, INC. A RAMBOLL COMPANY



APPENDIX A ALTERNATE SOURCE DEMONSTRATIONS 40 C.F.R. § 257.95(g)(3)(ii): ALTERNATE SOURCE DEMONSTRATION BALDWIN BOTTOM ASH POND APRIL 8, 2019

April 8, 2019

This alternate source demonstration has been prepared on behalf of Dynegy Midwest Generation, LLC (DMG) by OBG, part of Ramboll (OBG) to provide pertinent information pursuant to 40 CFR § 257.95(g)(3)(ii) for the Baldwin Bottom Ash Pond (BAP) located at Baldwin Energy Complex near Baldwin, Illinois.

Initial background groundwater monitoring consisting of a minimum of eight samples as required under 40 CFR § 257.94(b) was initiated in December 2015 and completed prior to October 17, 2017. Comparison of background groundwater quality with concentrations of parameters in downgradient monitoring wells observed during the November 2017 Detection Monitoring Program sampling event identified a statistically significant increase (SSI) for one or more 40 CFR Part 257 Appendix III parameters at Baldwin BAP. Consequently, and in accordance with 40 CFR § 257.94(e) and 40 CFR § 257.95, an assessment monitoring program was established by April 9, 2018 for the Baldwin BAP.

The first Assessment Monitoring sampling event was completed on June 26, 2018 and June 27, 2018. As stipulated in 40 CFR § 257.95(d)(1), all wells were resampled on September 26, 2018 for all Appendix III parameters and the Appendix IV parameters detected during the first Assessment Monitoring sampling event. Groundwater data collected from the first Assessment Monitoring sampling event and resampling event are available in the 2018 Annual Groundwater Monitoring and Corrective Action Report for Baldwin Bottom Ash Pond completed January 31, 2019 (OBG, 2019). Analytical data from all sampling events from December 2015 through the resampling event were evaluated in accordance with the statistical analysis plan (NRT/OBG, 2017) to determine any SSIs of Appendix III parameters over background concentrations or statistically significant levels (SSLs) of Appendix IV parameters over Groundwater Protection Standards (GWPSs). That evaluation identified SSLs at downgradient monitoring wells as follows:

Lithium at well MW-370

Per 40 CFR § 257.95(g)(3)(ii), the owner or operator of a CCR unit may complete within 90 days from the date of an SSL determination a written demonstration that a source other than the CCR unit caused the SSL, or that the SSL resulted from error in sampling, analysis, statistical evaluation, or natural variation in groundwater quality ("alternate source demonstration"). Pursuant to 40 CFR § 257.95(g)(3)(ii), the following demonstrates that sources other than the Baldwin BAP were the cause of the SSL listed above. This alternate source demonstration (ASD) was completed within 90 days of determination of the SSLs (January 7, 2019) as required by 40 CFR § 257.95(g)(3)(ii).

ALTERNATE SOURCE DEMONSTRATION: LINES OF EVIDENCE

This ASD is based on the following lines of evidence (LOE):

- 1. The BAP water has a different ionic composition than groundwater.
- 2. Lithium concentrations in the BAP water are lower than the concentrations observed in groundwater.

These lines of evidence are described and supported in greater detail below. Monitoring wells and BAP water sample locations are shown Figure 1 (attached).



LOE #1: THE BAP WATER HAS A DIFFERENT IONIC COMPOSITION THAN GROUNDWATER.

Stiff diagrams graphically represent ionic composition of aqueous solutions. Figure 2 shows a series of Stiff diagrams that display the ionic compositions of the BAP water and groundwater from background and downgradient monitoring wells in the monitoring system. Polygons with similar shapes represent solutions with similar ionic compositions, whereas polygons with different shapes indicate solutions with dissimilar ionic compositions.




Figure 2. Stiff diagram showing ionic composition of samples of BAP background and downgradient groundwater and BAP water.



The ionic compositions of the BAP water and groundwater represented by Figure 2 are discussed in more detail below.

- The dominant cations in BAP groundwater at background and downgradient monitoring wells are sodiumpotassium.
- Figure 2 indicates that MW-369 has a relatively higher proportion of calcium and magnesium cations than other wells in the groundwater monitoring system, although sodium-potassium cations are still dominant.
- The polygon associated with the BAP water sample in Figure 2 is relatively flat on the left side indicating there is no overly dominant cation.
- The dominant anions in most BAP monitoring wells are carbonate-bicarbonate, with the exceptions of downgradient monitoring well locations MW-370 and MW-382.
- MW-370 is the only location analyzed where the major anions are dominated by chloride, this results in a distinct polygon shape when compared to other sample locations as illustrated in Figure 2.
- The dominant anions at MW-382 are sulfate and carbonate-bicarbonate.
- The dominant anion in the BAP water sample is sulfate.

The Stiff diagrams and analysis of ionic composition in the BAP water sample and groundwater indicate the ionic composition of water at MW-370 is not influenced by the BAP.

LOE #2: LITHIUM CONCENTRATIONS IN THE BAP WATER ARE LOWER THAN THE CONCENTRATIONS OBSERVED IN GROUNDWATER

Lithium concentrations in the BAP water, including samples from BAP water and TPZ-164 bottom ash porewater well (see boring log in Attachment A), are lower than lithium concentrations in groundwater. A time-series for lithium concentrations is provided in Figure 3 below.






Figure 3. Lithium Concentration Time-series for groundwater samples from the BAP monitoring system and BAP water.

The following observations can be made from Figure 3:

- BAP water ranges from 0.0167 to 0.0182 mg/L of lithium.
- Groundwater from downgradient wells MW-356, MW-369, MW-370 and MW-382 has one to ten times greater lithium concentrations than the maximum lithium concentration (0.0182 mg/L) observed in BAP water.
- Groundwater from background well MW-304 has three to five times greater lithium concentrations than the maximum lithium concentration (0.0182 mg/L) observed in BAP water.



If the BAP were the source of lithium in groundwater, BAP water concentrations would be anticipated to be higher than concentrations of lithium in groundwater monitoring wells. Therefore, the BAP is not the source of the lithium observed in groundwater samples. Background lithium concentrations at MW-304 were also shown to be significantly higher than water in the pond, indicating lithium concentrations are either naturally occurring due to geochemical variations within the Uppermost Aquifer or from upgradient anthropogenic sources.

Based on these two lines of evidence, it has been demonstrated that the Baldwin BAP has not caused the SSL in MW-370.

This information serves as the written alternate source demonstration prepared in accordance with 40 CFR § 257.95(g)(3)(ii) that the SSL observed during the assessment monitoring program was not due to the CCR unit, but was from a combination of naturally occurring conditions and potential upgradient anthropogenic impacts. Therefore, a corrective measures assessment is not required and the Baldwin BAP will remain in assessment monitoring.

Attachment A Boring Log for Porewater Well TPZ-164

REFERENCES

Natural Resource Technology, an OBG Company, 2017a, Statistical Analysis Plan, Baldwin Energy Complex, Havana Power Station, Hennepin Power Station, Wood River Power Station, Dynegy Midwest Generation, LLC, October 17, 2017.

O'Brien & Gere Engineers, Inc. (OBG), 2019, 2018 Annual Groundwater Monitoring and Corrective Action Report, Baldwin Bottom Ash Pond – CCR Unit ID 601, Baldwin Energy Complex, Dynegy Midwest Generation, LLC, January 31, 2019.



I, Eric J. Tlachac, a qualified professional engineer in good standing in the State of Illinois, certify that the information in this report is accurate as of the date of my signature below. The content of this report is not to be used for other than its intended purpose and meaning, or for extrapolations beyond the interpretations contained herein.

Eric J. Tlachac Qualified Professional Engineer 062-063091 Illinois OBG, part of Ramboll Date: April 8, 2019



I, Jacob J. Walczak, a professional geologist in good standing in the State of Illinois, certify that the information in this report is accurate as of the date of my signature below. The content of this report is not to be used for other than its intended purpose and meaning, or for extrapolations beyond the interpretations contained herein.


Jacob J. Walczak Professional Geologist 196-001473 Illinois OBG, part of Ramboll Date: April 8, 2019














Attachment A

Boring Log for Porewater Well TPZ-164



	KELRON ENVIRONMENTAL Incorporated		L	OG	OF	F PR	ROB	EH	OLE	TPZ-	164 (Page 1 of 1)
F	Phase II Hydrogeologic Investigation Baldwin Energy Complex Dynegy Midwest Generation, Inc.	Date Completed Hole Diameter Drilling Method Sampling Method Drilling Company	: 8 1 : HS : Sp	/26/20 1/2" OE SA (CN olit Spo Illdog E	0 / 4 1 IE-55 on / S	LC) Shelby 1	Гube	((Casing	Elevation	: John Gates : Stuart Cravens (Kelron) : 432.50 tion : 435.10 : 2383909, 556829
Depth in Feet	DESCRIPTION		Surf. Elev. 432.50	Samples	Blow Count	Recovery inches	Qp TSF	NSCS	GRAPHIC	Well: T Elev.: 4	PZ-164 I35.10 — Cover
0- - - 1-	FILL - Bottom Ash, coarse, black (10YR 2	1/1), dry									- Concrete
2- 3- 3- 5-	- moist <shelby 3-5<br="" @="" sample="" st164-5="" tube="">grain size analysis (Ash): 50% Sand, 42.9% Silt, 7.1% Clay - wet</shelby>	'>	- 430 - 429 - 428	1		17/24		AR			— Seal Bentonite Chips — Riser (Sch 40 PVC)
6- - 7- 8-			- 427 - 426 - 425								— Filter Pack — Screen (pre-pack) 2"ID/3.5"OD; 4.50' ope
9-	CLAY (lean), stiff, medium to high plastici (10YR 4/1), moist - @8.9' - light yellowish brown (10YR 6 light gray mottling - @9.3' - gray (10YR 6/1) with 25-50% brownish-yellow mottling (10YR 6/6)	6/4) with <10%	- 424 - 423	2	3 3 5	18/18		CL			-Bottom Cap
- - 11-	- light olive brown <shelby 10<br="" @="" sample="" st164-12="" tube="">grain size analysis: 7.2% Sand, 62.2% Silt, 30.6% Clay</shelby>)-12'>	- 422 - 421	3		23/24		CL			— Seal Bentonite Chips

- 420

- 419

October 14, 2019

Title 40 of the Code of Federal Regulations (C.F.R.) § 257.95(g)(3)(ii) allows the owner or operator of a Coal Combustion Residuals (CCR) unit 90 days from the date of determination of Statistically Significant Levels (SSLs) over Groundwater Protection Standards (GWPSs) of groundwater constituents listed in Appendix IV of 40 C.F.R. Part 257 to complete a written demonstration that a source other than the CCR unit being monitored caused the SSL(s), or that the SSL(s) resulted from error in sampling, analysis, statistical evaluation, or natural variation in groundwater quality (Alternate Source Demonstration [ASD]).

This ASD has been prepared on behalf of Dynegy Midwest Generation, LLC (DMG), by O'Brien & Gere Engineers, Inc, part of Ramboll (OBG), to provide pertinent information pursuant to 40 C.F.R. § 257.95(g)(3)(ii) for the Baldwin Bottom Ash Pond (BAP) located near Baldwin, Illinois.

The second Assessment Monitoring sampling event (A2) was completed on March 19-20, 2019 and analytical data were received on April 15, 2019. Analytical data from all sampling events, from December 2015 through A2, were evaluated in accordance with the Statistical Analysis Plan¹ to determine any Statistically Significant Increases (SSIs) of Appendix III parameters over background concentrations or SSLs of Appendix IV parameters over Groundwater Protection Standards (GWPSs). That evaluation identified SSLs at downgradient monitoring wells as follows:

Lithium at well MW-370

Pursuant to 40 C.F.R. § 257.95(g)(3)(ii), the following demonstrates that sources other than the Baldwin BAP were the cause of the SSL listed above. This ASD was completed by October 14, 2019, within 90 days of determination of the SSLs, as required by 40 C.F.R. § 257.95(g)(3)(ii).

ALTERNATE SOURCE DEMONSTRATION: LINES OF EVIDENCE

This ASD is based on the following lines of evidence (LOE):

- 1. Lithium concentrations in the BAP porewater are lower than the concentrations observed in groundwater.
- 2. The BAP porewater has a different ionic composition than groundwater.

These lines of evidence are described and supported in greater detail below. Monitoring wells and the BAP porewater sample location are shown Figure 1 (attached).

LOE #1: LITHIUM CONCENTRATIONS IN THE BAP POREWATER ARE LOWER THAN THE CONCENTRATIONS OBSERVED IN GROUNDWATER

Lithium concentrations in BAP porewater samples collected from TPZ-164 bottom ash porewater well (see boring log in Attachment A) are lower than lithium concentrations in groundwater. A time-series plot of lithium concentrations is provided in Figure 2 below.



¹ Natural Resource Technology, an OBG Company, 2017, Statistical Analysis Plan, Baldwin Energy Complex,

Havana Power Station, Hennepin Power Station, Wood River Power Station, Dynegy Midwest Generation, LLC, October 17, 2017.




Figure 2. Lithium concentration time-series for background (brown) and downgradient (blue) groundwater samples from the BAP monitoring system, and BAP porewater (green).

The following observations can be made from Figure 2:

- Concentrations of lithium in background wells ranged from 0.0132 to 0.0958 milligrams per liter (mg/L).
- Concentrations of lithium in downgradient wells MW-356, MW-369 and MW-382 ranged from 0.0234 to 0.0723 mg/L, generally within the range of background concentrations.
- Concentrations of lithium in MW-370, where the SSL was identified, ranged from 0.0983 to 0.178 mg/L, above the upper range of lithium concentrations detected in other groundwater monitoring wells.



Concentrations of lithium in BAP porewater range from 0.0142 to 0.0182 mg/L. These levels of lithium are at or below the lower end of the range of lithium concentrations detected in all groundwater monitoring wells. Lithium concentrations in MW-370 are five to nine times greater than the maximum lithium concentration (0.0182 mg/L) observed in BAP porewater.

If the BAP were the source of lithium in groundwater at MW-370, BAP porewater concentrations of lithium would be anticipated to be higher than concentrations at MW-370. Therefore, the BAP is not the source of the lithium observed at MW-370. Lithium concentrations at background monitoring well MW-304 are higher than BAP porewater, which also indicates lithium concentrations are from a source other than the CCR unit.

LOE #2: THE BAP POREWATER HAS A DIFFERENT IONIC COMPOSITION THAN GROUNDWATER.

Stiff diagrams graphically represent ionic composition of aqueous solutions. Figure 3 shows a series of Stiff diagrams that display the ionic compositions of groundwater from background monitoring wells (brown), downgradient monitoring wells (blue) and the BAP porewater (green). Polygons with similar shapes represent solutions with similar ionic compositions, whereas polygons with different shapes indicate solutions with dissimilar ionic compositions; the larger the area of the polygon, the greater the concentration of the various ions.

The ionic compositions of the groundwater and BAP porewater represented by Figure 3 are discussed in more detail below.

- The ionic composition of the groundwater in background and downgradient monitoring wells is similar, as represented by the similarity of the Stiff diagram sizes and shapes. The exception to this is MW-370.
 - » The dominant cations in groundwater monitoring wells (background and downgradient) are sodium-potassium. However, the concentration of sodium-potassium in downgradient groundwater monitoring well MW-370 is higher compared to other groundwater monitoring wells.
 - » With the exceptions of MW-370 and MW-382, the dominant anions in groundwater monitoring wells are carbonate-bicarbonate.
 - > MW-370 is the only location where the dominant anion is chloride. This, coupled with the relatively high concentration of sodium-potassium cations in MW-370, results in a distinct polygon shape when compared to other groundwater sample locations.
 - > The dominant anion at MW-382 is sulfate, however the concentration of carbonate-bicarbonate is consistent with the concentrations of carbonate-bicarbonate in other downgradient groundwater monitoring wells.
- The ionic composition of the BAP porewater is different than the ionic composition of the groundwater.
 - » The dominant cation in the BAP porewater sample is calcium and the dominant anion is carbonate-bicarbonate. The resulting Stiff diagram is different in both shape and size from the groundwater diagrams.






Figure 3. Stiff diagram showing ionic composition of samples of BAP background (brown) and downgradient (blue) groundwater and BAP porewater (green).




The Stiff diagrams and analysis of ionic composition in groundwater and the BAP porewater sample indicate that the ionic composition of groundwater at MW-370 is not influenced by the BAP.

Based on these two lines of evidence, it has been demonstrated that the lithium SSL at MW-370 is not due to the Baldwin BAP but is from a source other than the CCR unit being monitored.

This information serves as the written ASD prepared in accordance with 40 CFR § 257.95(g)(3)(ii) that the SSL observed during the A2 sampling event was not due to the BAP. Therefore, a corrective measures assessment is not required and the Baldwin BAP will remain in assessment monitoring.


Attachment A Boring Log for Porewater Well TPZ-164





I, Eric J. Tlachac, a qualified professional engineer in good standing in the State of Illinois, certify that the information in this report is accurate as of the date of my signature below. The content of this report is not to be used for other than its intended purpose and meaning, or for extrapolations beyond the interpretations contained herein.

Eric J. Tlachac Qualified Professional Engineer 062-063091 Illinois OBG, part of Ramboll Date: October 14, 2019



I, Jacob J. Walczak, a professional geologist in good standing in the State of Illinois, certify that the information in this report is accurate as of the date of my signature below. The content of this report is not to be used for other than its intended purpose and meaning, or for extrapolations beyond the interpretations contained herein.


Jacob J. Walczak Professional Geologist 196-001473 Illinois OBG, part of Ramboll Date: October 14, 2019













Attachment A

Boring Log for Porewater Well TPZ-164




	KELRON ENVIRONMENTAL Incorporated		L	OG	OF	F PR	ROB	EH	OLE	TPZ-	164 (Page 1 of 1)
F	Phase II Hydrogeologic Investigation Baldwin Energy Complex Dynegy Midwest Generation, Inc.	Date Completed Hole Diameter Drilling Method Sampling Method Drilling Company	: 8 1 : HS : Sp	/26/20 1/2" OE SA (CN olit Spo Illdog E	0 / 4 1 IE-55 on / S	LC) Shelby 1	Гube	((Casing	Elevation	: John Gates : Stuart Cravens (Kelron) : 432.50 tion : 435.10 : 2383909, 556829
Depth in Feet	DESCRIPTION		Surf. Elev. 432.50	Samples	Blow Count	Recovery inches	Qp TSF	NSCS	GRAPHIC	Well: T Elev.: 4	PZ-164 I35.10 — Cover
0- - - 1-	FILL - Bottom Ash, coarse, black (10YR 2	1/1), dry									- Concrete
2- 3- 3- 5-	- moist <shelby 3-5<br="" @="" sample="" st164-5="" tube="">grain size analysis (Ash): 50% Sand, 42.9% Silt, 7.1% Clay - wet</shelby>	'>	- 430 - 429 - 428	1		17/24		AR			— Seal Bentonite Chips — Riser (Sch 40 PVC)
6- - 7- 8-			- 427 - 426 - 425								— Filter Pack — Screen (pre-pack) 2"ID/3.5"OD; 4.50' ope
9-	CLAY (lean), stiff, medium to high plastici (10YR 4/1), moist - @8.9' - light yellowish brown (10YR 6 light gray mottling - @9.3' - gray (10YR 6/1) with 25-50% brownish-yellow mottling (10YR 6/6)	6/4) with <10%	- 424 - 423	2	3 3 5	18/18		CL			-Bottom Cap
- - 11-	- light olive brown <shelby 10<br="" @="" sample="" st164-12="" tube="">grain size analysis: 7.2% Sand, 62.2% Silt, 30.6% Clay</shelby>)-12'>	- 422 - 421	3		23/24		CL			— Seal Bentonite Chips

- 420

- 419

ATTACHMENT 2 – MAP OF GROUNDWATER MONITORING WELL LOCATIONS



BOTTOM ASH POND DOWNGRADIENT CCR MONITORING WELL LOCATION


- BOTTOM ASH POND BACKGROUND CCR MONITORING WELL LOCATION
- BOTTOM ASH POND POREWATER SAMPLE LOCATION
- BOTTOM ASH POND UNIT BOUNDARY

800 Feet MONITORING WELL AND BOTTOM ASH POND

1. 1. 23

BOTTOM ASH POND

TPZ-164



WATER SAMPLE LOCATION MAP

BALDWIN BOTTOM ASH POND (UNIT ID: 601) ALTERNATE SOURCE DEMONSTRATION BALDWIN ENERGY COMPLEX BALDWIN, ILLINOIS

RAMBOLL US CORPORATION A RAMBOLL COMPANY



ATTACHMENT 3 – WELL CONSTRUCTION DIAGRAMS AND DRILLING LOGS



				HNOLOGY								Paş		of	8
Facilit				nplex	License/	Permit/	Monit	oring Nu	umber		Boring	Numb	er 7-304		
				of crew chief (first, last) and Firm	Date Dri	Iling St	arted		Da	te Drilli	ng Cor				ling Method
Johi	1 Gate	es				-					-	-			1/4 HSA
Bul	ldog E	Drillin	g				/2015				10/20/	2015	-		nd rotary
				Common Well Name MW-304	Final Sta	atic Wa et (NA				e Eleva 3.03 Fe					Diameter 3.3 inches
Local	Grid Or	igin	(es	stimated:) or Boring Location						Local C			50)	C	
State 1				03 N, 2,386,608.77 E E/℗		at <u>38</u>		<u>1'</u> <u>17.9</u>	<u>952 "</u>				N		E
	1/4	of	1	1/4 of Section , T N, R	Lon	g <u>-89</u>	<u>)° 5</u>	<u>1'</u> <u>1</u>			Fe	et 🗌	S		Feet W
Facilit	y ID			County Randolph	State Illinois		Bald	Fown/Ci	ity/ or \	Village					
San	nle			Kandoiph	mmois		Daiu				Soil	Prop	erties		
	<u> </u>			Soil/Rock Description											-
	.tt. & d (ir	unts	Feet	And Geologic Origin For						sive (tsf)					ts
lber Гуре	gth A	CO	h In	Each Major Unit		CS	hic	ram		pres	sture	t id	icity x	0	o/ men
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet			U S O	Graphic Log	Well Diagram		Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
			-	0 - 5.8' SILTY CLAY CL/ML.			Z								0-35.4'
			_												Blind Drilled. See
			-1												log MW-104DR
															for soil
			-2												description details.
			_												
			-3			CL/ML									
			-4												
			-												
			-5												
			-												
			6	5.8 - 13.5' FAT CLAY: CH.											
			F				\mathbb{N}								
			-7				\mathbb{N}								
			F				\mathbb{N}								
			-8				\mathbb{N}								
			F				\mathbb{N}								
			-9			СН	\mathbb{N}								
			F				\mathbb{N}								
			-10				\mathbb{N}								
			Ē				\mathbb{N}								
							\mathbb{N}								
							\mathbb{N}								
			-12				$ \rangle$								
Lhorob	v cortif	w that t	I	rmation on this form is true and correct to the be	est of my ki	nowled									

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature Brook Proches	Firm Natural Resource Technology 234 W. Florida St., Fifth Floor, Milwaukee, WI 53204	Tel: (414) 837-3607 Fax: (414) 837-3608
	Template: ILLINOIS BORIN	NG LOG - Project: BALDWIN GINT.GPJ

Natural Resource TECHNOLOGY

SOIL BORING LOG INFORMATION SUPPLEMENT

	TEC	HNOLOGY Boring Number MW-304					Pag	ge 2	of	8
Sample						Soil	Prope			
Number and Type Length Att. & Recovered (in)	Blow Counts Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log Well Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
	_	5.8 - 13.5' FAT CLAY: CH. (continued)								
	-13		СН							
		13.5 - 15' LEAN CLAY: CL.	CL							
	-15	15 - 23.5' SILTY CLAY CL/ML.								
	-17									
	-18									
	-19		CL/ML							
	-20									
	-21									
	-22									
	-23									
	-24	23.5 - 24.5' SANDY FAT CLAY: s(CH).	s(CH)							
	-25	24.5 - 27.3' POORLY-GRADED SAND: SP.								
	-26		SP							
	-27	27.3 - 30' SILTY CLAY CL/ML.								
	-28									
	-29		CL/ML							
	-30	30 - 35.4' SHALE: BDX (SH).								
	-31		BDX (SH)							
	-32									



				Boring Number MW-304								ge 3	of	8
San	nple									Soil	Prope	erties		
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well	Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
			-	30 - 35.4' SHALE: BDX (SH). (continued)										
			-33		BDX (SH)									
1 CORE	60 31			 35.4 - 41.3' LEAN CLAY: CL, gray, 2" of wood on top of unit, stiff, dry. 36.3' stiff to very hard, dry. 36.7' trace chert gravel. 	CL									
2 CORE	60 59.5		-40 41 42 43	40.2' dry. 41.3 - 46.8' SHALEY LIMESTONE : BDX (LS/SH), thinly to medium bedded with shale, intensely to moderately fractured (extremely narrow apertures). 41.6' - 42' vertical fracture.										
3 CORE	60 63		-44 45 46 47	45.4' intensely fractured. 46.8 - 55.6' SHALE : BDX (SH), gray, trace chert gravel, thickly bedded, highly to moderately decomposed, intensely fractured.	BDX (LS/SH									Core 3, RQD=75%
4 CORIE	60 65		48 49 50 51 52	50.4' moderately fractured.	BDX (SH)									Core 4, RQD=95%



	/		TEC	HNOLOGY Boring Number MW-304						F	Page 4	of	8
Sar	nple								Soi	l Pro	perties		
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well	Compressive Strength (tsf)	Moisture	Liquid	Lumit Plasticity Index	P 200	RQD/ Comments
5 CORE	60		-53 -54 -55 -56 -57 -58 -59	46.8 - 55.6' SHALE : BDX (SH), gray, trace chert gravel, thickly bedded, highly to moderately decomposed, intensely fractured. <i>(continued)</i> 54.4' intensely fractured. 55.6 - 60.2' LIMESTONE: BDX (LS), shaley, thickly bedded, fossiliferous, unfractured to slightly fractured.	BDX (SH) BDX (LS)								Core 5, RQD=95%
6 CORE	60 64		-60 -61 -62 -63	60.2 - 81.6' SHALEY LIMESTONE: BDX (LS/SH), medium bedded, mostly fossiliferous limestone, highly decomposed dark gray shale beds, intensely to moderately fractured.									Bedrock corehole reamed 6" in diameter to 59' for well installation. Core 6, RQD=73%
7 ⁼ Core	60 66		-64 -65 -66 -67 -68		BDX (LS/SH								Core 7, RQD=64%
8 CORE	60 63			70.3' thickly bedded with dark gray shale.									Core 8, RQD=88%



			ILC	Boring Number MW-304								ge 5	of	8
Sar	nple									Soil	Prope	erties		-
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	U S C S	Graphic Log	Well Diagram		Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
9 CORE	60 60	I	-73 -74 -75 -76 -77 -78 -79 -80	60.2 - 81.6' SHALEY LIMESTONE : BDX (LS/SH), medium bedded, mostly fossiliferous limestone, highly decomposed dark gray shale beds, intensely to moderately fractured. <i>(continued)</i> 75' diagonal fracture (narrow aperture). 75.3' intensely fractured.	BDX (LS/SH								I	Core 9, RQD=50%
10 CORE	60 72			80.3' moderately fractured. 81.6 - 91.9' SHALE: BDX (SH), gray, highly decomposed, intensely fractured.										Core 10, RQD=43%
11 CORE	60 65		- 86 - 86 - 87 - 87 - 87 - 88 - 88 - 89 - 90	85.4' moderately to highly decomposed, intensely to moderately fractured.	BDX (SH)									Core 11, RQD=57%
12 CORE	60 61.5		-91 -91 -92	90.5' extremely narrow to very narrow apertures.				1						Core 12, RQD=50%



	/		TEC	HNOLOGY Boring Number MW-304						Pag	ge 6	of	8
Sar	nple								Soil	Prope			
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
13 CORE			-93 -94 -95 -96 -97 -98	91.9 - 115.3' SHALEY LIMESTONE : BDX (LS/SH), thinly to medium bedded with shale, slightly to moderately decomposed shale, intensely to moderately fractured (extremely narrow to narrow apertures). <i>(continued)</i> 95.3' tight to very narrow apertures.									Core 13, RQD=48%
14 CORE	60 65			100.4' thickly bedded, moderately fractured.	BDX (LS/SH								Core 14, RQD=65%
15 [■] CORE	60 60		103 104 105 106 107 107	105.3' medium bedded, slightly fractured (very narrow apertures).									Core 15, RQD=98%
16 CORE	60 72			110.3' moderately fractured.									Core 16, RQD=91%



NAN 204

				Boring Number MW-304								ge 7	of	8
Sar	nple									Soil	Prop	erties		_
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well	Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
17 CORE	60 60.5			91.9 - 115.3' SHALEY LIMESTONE : BDX (LS/SH), thinly to medium bedded with shale, slightly to moderately decomposed shale, intensely to moderately fractured (extremely narrow to narrow apertures). <i>(continued)</i> 115.3 - 135.4' LIMESTONE : BDX (LS), fossiliferous, thinly to medium bedded, slightly fractured (narrow apertures).	BDX (LS/SH									Core 17, RQD=100%
18 CORE	60 59		- 118 - 119 - 120 - 121 - 122	120.4' trace cherty limestone, slightly to moderately fractured (extremely narrow to very narrow apertures).										Core 18, RQD=97%
19 [≢] CORE	60 60.5		- 123 - 124 - 125 - 126 - 127 - 128	125.3' slightly fractured (very narrow to narrow apertures).	BDX (LS)									Core 19, RQD=98%
20 CORE	60 60		- 129 - 130 - 131 - 132	130.4' very narrow apertures.										Core 20, RQD=98%



NUX 204

				Boring Number MW-304						Pag		of	8
San	nple								Soil	Prope	rties		
	& (ii)	ts	et	Soil/Rock Description				e f)					
г S	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	And Geologic Origin For				essiv h (ts	e _		ţ		ents
Tyr	igth :ove:	M C	oth I	Each Major Unit	SCS	Graphic Log	Well Diagram	npre engtl	Moisture Content	uid nit	Plasticity Index	00	D/ nme
Number and Type	Len Rec	Blo	Dep		n s	Grap Log	Well Diag	Compressive Strength (tsf)	C or	Liquid Limit	Plastic Index	P 200	RQD/ Comments
			_	115.3 - 135.4' LIMESTONE: BDX (LS), fossiliferous, thinly to medium bedded, slightly			-						
			-	fractured (narrow apertures). <i>(continued)</i>									
			-133										
			-		BDX								
			-134		(LS)								
			_				-						
			-135										
				135.4' End of Boring.									
	. 1		. 1		•								

	RECORD	М	ONITORING WEL	ACE EXPLOR L BAMW-306 Renamed DB NO.: 124081	
DRILLIN DRILLEC LOGGED	PHASE II	I. AREA H.S.A. (ATE DRILLED: 09/25	/91
VATION DEPTH AN	SOIL SYMBOLS SAMPLER SYMBOLS © FIELD TEST DATA	USCS	DESCRIPTION	REMARKS	RECOVERY PENETROMETER RATIO in/in HAND, tsf
				Augered to 53.2', No Samples Taken See BAMM-124; BTB-39 for sample descriptions from 0-53 5'	
- 20					
- 25 - -					
L ₃₀ /	Boring ontinues				

00073

RECORD OF SUBSURFACE EXPLORATION

MONITORING WELL BAMW-306 Renamed MW-306

PROJECT: IP BALDWIN

A CONTRACTOR OF A CONTRACTOR OF

-21-01-02-02-0

Section.

-10.20

-printer-

JOB NO .: 124081

PHASE III. AREA 1

DATE DRILLED: 09/25/91

DRILLING METHOD: H.S.A. & NX Rock Core

DRILLED BY: Crank LOGGED BY: Brooks

BOREHOLE NUMBER: BTB-38

LEVATION DEPTH	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	DESCRIPTION	REMARKS	RECOVERY RATIO in/in	PENETROMETER. HAND, tsf
- 30	/p/			Augered to 53.2'. No Samples Taken. See BAMW-124; BTB-39 sample descriptions from 0-53.5		
r F						
- 35 -						
- 40						
-						
45						
F						
- 50 -						
- 55		e	Gray Clayey SHALE		4/10 62/108	
-						
60	Boring Continues	L	.ight Gray LIMESTONE			
	L					
H		– BL	JRLINGTON EN∨IRONM	ENTAL INC.		

DAILLI DAILLE LOGGED	T: IP BALD PHASE I	WIN II. A R H.S.A k s	EA 1 DATE D . & NX Rock Core	₩-306 Renam .: 124081	ed MW-306
EVATION DEPTH A	SOIL SYMBOLS SAMPLER SYMBOLS NO FIELD TEST DA	USCS	DESCRIPTION	REMARKS	RECOVERY PENETROMETER RATIO in/in HAND, tsf
- 60 - -			Light Gray LIMESTONE Gray Shaley CLAY		60/60
- - -			Light Gray LIMESTONE		
- - 70 -			Olive Clayey SHALE -Dark Gray, Calcareous below 70 3		37/60
- - 75 -		_	Light Gray LIMESTONE		60/60
- - 80 -					60760
- 85			Dark Gray Clayev SHALE		59/60

BURLINGTON ENVIRONMENTAL INC.



Facility	y/Proje	ct Nam	e			License/	Permit/	Monito	oring N	umber		Boring	Paş Numb		of	0	
			y Con											-356			
-		-	Name o	f crew chief (first, last) and Fin	m	Date Dri	lling St	arted		Da	te Drilli	ing Cor	npleted			ling Me	
	n Gate dog I		g	~ ~ ~				/2015				10/1/2	2015		an	1/4 H	ary
				Con	nmon Well Name MW-356	Final Sta		ter Lev AVD8			e Eleva					Diame .3 inc	
Local (Grid Or	igin	(es	stimated: 🗌) or Boring L							5.18 Fe Local C			50)	0	.5 IIIC	nes
State I				7 N, 2,381,958.49 E	E/(W)		t <u>38</u>		<u>1' 56.2</u>					N			E
	1/4	of	1	/4 of Section , T	N, R		<u>g89</u>	<u>° 52</u>	<u>2' 10.</u>	4808"		Fe		S		Feet	
Facility	y ID			County		State				ity/ or	Village						
Com	m 1a			Randolph		Illinois		Bald	win		T	Sail	Drom	antiac			
Sam	~											5011	Prop			-	
	t. & l (in)	nts	feet	Soil/Rock I	-						ive tsf)						
er vpe	h At erec	Cou	In I	And Geologi	-		s	Ľ.	l u		ress th (nte	_	ity			lent
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Each Ma	jor Unit		USC	Graphic Log	Well Diagram	0	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/	Comments
			-	0 - 10' SILTY CLAY CL/M	L.			Ē	<u>N</u>	3						0-37.3	3'
			_							Z						Blind Drilled	d. See
			-1							X						logs OW-1	56
																and	
			-2													OW-2 soil	.56 tor
			-													descri	iption.
			-3														
			_														
			-4														
			-5														
			_				CL/ML										
			-6														
			-														
			Ξ,														
			_														
			-8														
			-9														
			-														
			-10	10 - 17.7' LEAN CLAY WI			<u></u>										
			Ľ		(OL)S.												
			-				(CL)s										
			-12														
			14		d correct to the bes			<u> </u>	1	1		1	1			1	

Signature Brook Huches	Firm Natural Resource Technology 234 W. Florida St., Fifth Floor, Milwaukee, WI 53204	Tel: (414) 837-3607 Fax: (414) 837-3608
	Template: II J INOIS BORIN	IGLOG - Project: BALDWIN GINT GPL

Template: ILLINOIS BORING LOG - Project: BALDWIN GINT.GPJ



		TEC	HNOLOGY Boring Number MW-356						Pag	ge 2	of 8	8
Sample								Soil	Prope			
Number and Type Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
		$ \begin{array}{c} 13 \\ -14 \\ -15 \\ -16 \\ -17 \\ -18 \\ -19 \\ -20 \\ -21 \\ -22 \\ -23 \\ -24 \\ -25 \\ -26 \\ -27 \\ \end{array} $	10 - 17.7' LEAN CLAY WITH SAND: (CL)s. (continued) 17.7 - 27.3' SILTY CLAY CL/ML.	(CL)s								
		-28	27.3 - 28.6' POORLY-GRADED SAND: SP	SP								
		30 31 32		CL/ML								

NATURAL RESOURCE TECHNOLOG

SOIL BORING LOG INFORMATION SUPPLEMENT
--

			TEC	HNOLOGY Boring Number MW-356								Da	ge 3	of	8
San	nple			Boring Number 111 V -350							Soil		erties	01	0
Number and Type	Length Att. & H	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well	Diagram	-	Compressive Strength (tsf)	Moisture		ity	P 200	RQD/ Comments
4.0	IH	<u> </u>	-	28.6 - 33.9' SILTY CLAY CL/ML. (continued)		ĒĪ	Í				~ 0			H	
			-33	33.9 - 35.7' LEAN CLAY: to SHALE: CL.	CL/ML										
			-36	35.7 - 37.3' SHALE : BDX (SH).	BDX (SH)										
1 Core	28 24.5		38	37.3 - 53.8' SHALE: BDX (SH), weathered shale and clay, brown to dark gray, soft, slightly fractured.											Core 1, RQD=92%
2 CORE	60 57		40	39.6' light to dark gray to tan.											Core 2, RQD = 58%
3 CORIE	60 41		43	42.3' - 43.2' limestone. 43.2' light to dark gray/tan, very weak. 45' - 50' dark gray, intensely fractured.	BDX (SH)										Low recovery,
			46												possible washout. Core 3, RQD = 18%
4 Core	36 36			50' - 53.1' thin beds of limestone, limestone is more competent, slightly fractured, wet.											Core 4, RQD=92%



			TEC	HNOLOGY										
	anla			Boring Number MW-356	1			1		Sail	Pag	·	of	8
Number and Type	Length Att. & du Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram)	Compressive Strength (tsf)		Liquid Limit	Plasticity Index	P 200	RQD/ Comments
5 CORE	24 21.5		-53	 37.3 - 53.8' SHALE: BDX (SH), weathered shale and clay, brown to dark gray, soft, slightly fractured. <i>(continued)</i> 53.1' - 53.8' intensely fractured. 	BDX (SH)									Core 5, RQD=58%
6	60		-54	53.8 - 55.4' LIMESTONE: BDX (LS), white, thickly bedded, moderately fractured (moderately wide to very narrow apertures).	BDX (LS)									Core 6,
CORE	60.5		56	55.4 - 57.2' SHALE: BDX (SH), dark gray, trace limestone beds, moderately fractured.	BDX (SH)									RQD=84%
				56.8' soft, highly weathered bed, decomposed. 57.1' soft, highly weathered bed. 57.2 - 60' LIMESTONE: BDX (LS), trace shale beds, moderately fractured (moderately wide to very wide apertures).	BDX (LS)									
7 CORE	60 61		60	59.4' - 59.7' vertical fractures with pyrite mineralization. 60 - 65.8' SHALE : BDX (SH), gray, moderately fractured. 61' -62' dark gray.				· · ·						Core 7 RQD=75%
			-62 -63 -64	62' - 62.4' soft, clayey.	BDX (SH)									
8 CORE	60 61.5		65	65' dark gray, narrow to moderately wide apertures. 65.3' - 65.8' fossiliferous. 65.8 - 68.8' SHALEY LIMESTONE : BDX (LS/SH), fossiliferous, slightly to moderately fractured.										Core 8, RQD=67%
9 CORE	60 61		67 68 69 70	68.8 - 70' SHALE : BDX (SH), gray, fossiliferous, moderately fractured (moderately wide to narrow apertures). 70 - 75' SHALEY LIMESTONE : BDX (LS/SH), gray to dark gray, fossiliferous, medium bedded, moderately fractured (narrow apertures).	BDX (LS/SH BDX (SH)									Bedrock corehole reamed 6" in diameter to 69' for well installation.
			71 72		BDX (LS/SH									Core 9, RQD=87%



			TEC	HNOLOGY							_	-		0
Sar	nple			Boring Number MW-356						Soil	Pag Prope	ge 5 erties	of	8
Number and Type	t. & l (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	-	Compressive Strength (tsf)	Moisture Content		ţ	P 200	RQD/ Comments
10 CORE	60 60	H	-73 -74 -75 -76 -77	 70 - 75' SHALEY LIMESTONE: BDX (LS/SH), gray to dark gray, fossiliferous, medium bedded, moderately fractured (narrow apertures). <i>(continued)</i> 75 - 75.9' SHALE: BDX (SH), dark gray, soft, moderately fractured (narrow to moderately narrow apertures). 75.9 - 76.2' SHALEY LIMESTONE: BDX (LS/SH), fossiliferous, narrow to moderately narrow <i>[</i> apertures. <i>[</i> 76.2 - 101.8' LIMESTONE: BDX (LS), light gray, fossiliferous, thickly bedded, narrow to moderately narrow apertures. 	BDX (LS/SH BDX (SH) BDX (LS/SH				<u>S</u>			P II	4	Core 10, RQD=95%
11 CORIE	60 60.5		- 79 - 80 - 81 - 82	80' light gray to gray, unfractured.										Core 11, RQD=100%
12 CORIE	60 61.5				BDX (LS)									Core 12, RQD=100%
13 CORIE	60 59.5													Core 13, RQD=100%



				Boring Number MW-356								ge 6	of	8
Sar	nple							-		Soil	Prope	erties		
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram		Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
14 CORE	61 61		-93 -94 -95 -96 -97 -98	76.2 - 101.8' LIMESTONE: BDX (LS), light gray, fossiliferous, thickly bedded, narrow to moderately narrow apertures. <i>(continued)</i>	BDX (LS)									Core 14, RQD=100%
15 CORE	60 59.5			99.7' slightly weathered, decomposed. 100' gray, no fossils. 101.8 - 106.5' SHALE: BDX (SH), dark gray, thickly bedded, slightly fractured.										Core 15, RQD=100%
16 CORE	60 58.5			<u>106.2' weathered, decomposed.</u>	BDX (SH) BDX (LS)									Core 16, RQD=56%
17 CORE	60 55			highly disintegrated (healed dissolution cracks with green highly decomposed infilling). 109.9' - 110.7' angular gravel-sized fragments. 110.7' moderately decomposed, very intensely // \fractured.	BDX (SH) BDX (LS) BDX (SH)									Core 17, RQD=49%



			TEC	Boring Number MW-356								ge 7	of	8
San	nple									Soil	Prop	erties		
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Loo	Well	Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
			-113	111.1 - 114' SHALE: BDX (SH), dark gray, moderately to highly decomposed, moderately fractured. <i>(continued)</i>	BDX (SH)									
18 CORE	60 61		-114	114 - 116.3' LIMESTONE: BDX (LS), gray, moderately fractured.	BDX (LS)									Core 18, RQD=61%
			-117	116.3 - 116.7' SHALEY LIMESTONE : BDX (LS/SH), intensely fractured. 116.7 - 119.7' SHALE: BDX (SH), gray, slightly decomposed, intensely fractured.	BDX ,									
			-119	119.7 - 120.9' SHALEY LIMESTONE : BDX	BDX (SH)									
19 CORIE	60 64		-120	(LS/SH), gray, slightly decomposed, intensely fractured. 120.9 - 122.2' SHALE: BDX (SH), dark gray, moderately fractured.	BDX (LS/SH BDX (SH)									Core 19, RQD=86%
			-123	122.2 - 126.1' LIMESTONE: BDX (LS), gray, moderately fractured. 123.3' - 123.4' fossiliferous. 124.1' - 124.1' fossiliferous. 124.7' - 124.8' fossiliferous.	BDX (LS)									
20 CORI⊧	48 48		-126	126.1 - 127.6' SHALE: BDX (SH), dark gray, slightly decomposed. 126.7' - 127' limestone, gray. 127' moderately decomposed. 127.6 - 129.2' LIMESTONE: BDX (LS), slightly	BDX (SH)									Core 20, RQD =88%
21 CORE 22	12 12 60		- 128 - 129 - 130	127.6 - 129.2 LIMESTONE: BDX (LS), slightly decomposed. 129.2 - 130' SHALE: BDX (SH), gray, intensely fractured. 130 - 130.4' SHALEY LIMESTONE: BDX	BDX (LS) BDX (SH)									Core 21, RQD=0% Core 22,
CORE	60			130.4 130.4 131' LIMESTONE: BDX (LS), gray, 130.4 131' LIMESTONE: BDX (LS), gray, 155: 131 - 134' SHALEY LIMESTONE: BDX (LS/SH), 16ssiliferous, moderately fractured.	BDX (LS/SH) BDX (L(LS))									RQD=94%



MW 256

				Boring Number MW-356			-				ge 8	of	8
San	nple								Soil	Prope	erties		
	& in)	S	et	Soil/Rock Description				e [)					
. e	Att. red (ount	n Fe	And Geologic Origin For				ssiv 1 (tsi	e		y		nts
Typ	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Each Major Unit	SCS	phic	l gran	npre ngtŀ	stur tent	it di	ticit	00	⊃∕ ume
Number and Type	Length Att. & Recovered (in)	Blov	Dep		U S	Graphic Log	Well Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
			_	131 - 134' SHALEY LIMESTONE: BDX (LS/SH),									
				fossiliferous, moderately fractured. (continued)									
			-133		BDX (LS/SH								The casing
			-		20/011								dropped 3" during
			-134	134 - 135' LIMESTONE: BDX (LS), gray, thickly	<u> </u>								drilling.
			-	bedded, moderately fractured.	BDX								
			-135	135' End of Boring.	(LS)								
				135 End of Boring.									
			I		1	I	I			I			I



Facility/Project Name Baldwin Energy Complex						License/Permit/Monitoring Number						Page 1 of 4 Boring Number MW-369						
				f crew chief (first, last) and Firm		Date Drilling Started Date Dri									Dril	ling Method		
Mark Baetje												-			4 1/4 HSA			
	dog E		ıg			11/17/2015					11/18/2015					and rotary		
Common Well Name											ce Elevation Borehole Diameter (0.49 Feet (NAVD88) 8.3 inches							
MW-369												.49 Feet (NAVD88) 8. Local Grid Location						
Local Grid Origin □ (estimated: □) or Boring Location State Plane 557,329.71 N, 2,381,765.41 E E/(W)						Lat $_38^{\circ}$ $_11'$ $\underline{49.1496''}$					Local	Jrid Lo		_				
State Plane $337,329.71$ N, $2,381,703.41$ E E/W 1/4 of 1/4 of Section , T N, R				-	Long <u>-89°</u> <u>52'</u> <u>12.9288"</u>					Feet S					Feet			
Facility		01	1	County		tate	3	Civil'		City/ or	Village	Te		10				
5				Randolph		llinois		Balc		2	U							
Sam	ple											Soil	Prope	erties				
	<u>^</u>		L	Soil/Rock Descrip	otion													
	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	And Geologic Orig							Compressive Strength (tsf)					ts		
ype	h A vere	Col	l In	Each Major Un			S	ji.	E E		gth (ure ant	5	city	_	/ neni		
Number and Type	Length Att. Recovered (low	ept		III		SC	Graphic Log	Well Diam	Diagram	omp	Moisture Content	Liquid Limit	Plasticity Index	200	RQD/ Comments		
ZB	し と	В	Ω	¬ 0 - 0.2' SILT: ML.			n			2 2	ΣΩ	2 0		P. H	Р	0-43' Blind		
			E	0.2 - 2' SILTY CLAY CL/ML.		/	/_ML_			ÿ						Drilled. Se		
			-1					\leq		\leq						log PZ-16 for soil		
			F				CL/ML									descriptio		
			F_															
			-2	2 - 4' Shelby Tube Sample.														
			E															
			-3															
			F															
			-4															
			F	4 - 10' SILTY CLAY CL/ML.														
			5															
			E															
								\leq										
			-6															
			F															
			-7				CL/ML											
			F				CL/IVIL	\geq										
			F 。															
			-8															
			E															
			-9															
			F					\leq										
			-10															
			Ę	10 - 12' SILTY CLAY to LEAN C	JLAY: CL/ML													
			F					\mathbb{Z}										
			-11				CL/ML											
			E															
			-12	<u> </u>			<u> </u>	\sim										
				ormation on this form is true and corre														

Signature ///	Firm Natural Resource Technology	Tel: (414) 837-3607				
Mm mala	234 W. Florida St., Fifth Floor, Milwaukee, WI 53204	Fax: (414) 837-3608				
	Template: ILLINOIS BORING LOG - Project: BALDWIN GINT					



×			TEC	HNOLOGY Boring Number MW-369							F	age	2	of	4
Samp										Soi		perti			
Number and Type Lenoth Att &	Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram		Compressive Strength (tsf)	Moisture Content	Liquid	Lımıt Plasticity	Index	P 200	RQD/ Comments
			-	12 - 14' Shelby Tube Sample.											
			13 14 15 16 17 18	- 14 - 20' LEAN CLAY: CL.	CL										
					CL/ML										
			-23	22 - 24' Shelby Tube Sample.											
			-25	24 - 28' LEAN CLAY WITH SAND: (CL)s.	(CL)s										
			-28 -29 -30	28 - 30' SILTY CLAY CL/ML.	CL/ML										
			-31 -32		CL			1							



			TEC	HNOLOGY Boring Number MW-369						Pag	ge 3	of	4
San	nple								Soil	Prop	erties		
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	well Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
				32 - 38' LEAN CLAY: CL. 38 - 40' No Recovery. 40 - 42' LEAN CLAY: CL.	CL CL								
1 SS	24 0	10 18 30 40	42	42 - 45' No Recovery.									
2 SS	5 9	50/5"	45	45 - 45.3' LEAN CLAY: CL, dark brown (10YR 3/3), 30-50% pale brown (10YR 6/4) and brown (10YR 4/3) mottling, trace subrounded fine gravel, cohesive, low plasticity, moist. 45.3 - 48.7' SHALE: BDX (SH), dark grayish brown, highly decomposed.									
3 SS		50/5"	-47 48	47' trace clay layers (< 1" thick), highly decomposed, very weak.	BDX (SH)								
1 CORE	66 30		-49 -50 -51 -52	48.7 - 50.8' LIMESTONE: BDX (LS), white, fossiliferous, intensely fractured (extremely narrow to narrow apertures), microcrystalline, slightly to moderately decomposed. 50.8 - 53.4' SHALE: BDX (SH), dark gray, intensely fractured (extremely narrow to narrow apertures), highly decomposed, very weak.	BDX (LS) BDX (SH)		1 67						Core 1, RQD=17%



	,		1	Boring Number MW-369	1	1						ge 4	of	4
San	nple									Soil	Prope	erties		_
	& (ii)	ts	et	Soil/Rock Description					e f)					
, e	Att. red	uno	n Fe	And Geologic Origin For				_	ssiv 1 (ts	e .		N.		nts
Typ	gth over	Ŭ 8	th I	Each Major Unit	CS	phic		gran	ngth	stur	it fi	ticit x	0	⊃/
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet		U S	Graphic Log	Well	Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
			E	50.8 - 53.4' SHALE : BDX (SH), dark gray,										
			F	intensely fractured (extremely narrow to narrow apertures), highly decomposed, very weak.	BDX									
_ H	<u> </u>		-53	(continued)	(SH)									
2 CORE	60 46		E	53.4 - 59.3' LIMESTONE: BDX (LS), white,										Core 2,
H			-54	moderately fractured (very narrow to narrow apertures), fossiliferous, microcrystalline, slightly										RQD=83%
			-	decomposed, very strong, pitted, trace mineralization.										
			-55											
			-											
			-56				1							
			E		BDX (LS)		1 E							
			-57				1 E							
			F				1 E							
			- 58				ŧE							
L			-	EQ. 41 mound in family during			1 E							
3 🗖	60		-59	58.4' mud in fracture.			1 E							
3 CORE	64		- 59	59.3 - 64.9' SHALEY LIMESTONE : BDX (LS/SH),		╞┯╧┥	1							Core 3,
				dark gray, medium bedded shale, intensely			1 E							RQD=63%
			60 60	fractured (extremely narrow to narrow apertures), fossiliferous, microcrystalline, decomposed, very			1 E							
			-	weak to weak, weathered, highly weathered shale			1 E							
			-61	cementing segments together.			1 E							
			E				1 E							
			-62		BDX		1 E							
			E		(LS/SH		1 E							
			-63				1							
			F				1 E							
4 CORE	60		-64				1 E							Core 4,
CORE	62		F				1 E							RQD=79%
			-65	64.9 - 68.8' LIMESTONE: BDX (LS), white,			1 E							
			E	slightly fractured (tight to narrow apertures), fossiliferous, microcrystalline, slightly decomposed,			l E							
			-66	slightly disintegrated, pitted.			E							
			-				-							
			E 		BDX									
			- "		(LS)			. •						
			-68											
							200	87						
			F co	68.8 - 70.7' Overdrilled for Well Installation.		<u> </u>	鎫							
			69				贸	Ř						
			F				×	8A						
			-70				務	87						Bedrock corehole
			F	70.7' End of Poring			æ							reamed 6" in diameter
				70.7' End of Boring.										to 70.7' for
														well installation.



Balc	y/Projec lwin E	Energ	y Con	nplex		License/			oring N				MW	-370		
Boring	, Drilleo	By:]	Name of	f crew chief (first, last) and Fin	m	Date Dri	lling S	arted		Da	te Drilli	ng Con	npleted		Dril	ling Method
	k Bae														4	1/4 HSA
Bull	ldog E	Drillin	ıg)/201:				1/24/	2015			nd rotary
				Com	mon Well Name	Final Sta					e Eleva					Diameter
					MW-370	Fe	et (NA	AVD8	(8)		3.67 Fe			38)	8	.3 inches
Local (State I	Grid Or			stimated:) or Boring L 0 N, 2,381,936.14 E		La	.t38	3° 1	<u>1' 44.</u>	1702 "	Local C	Jrid Lo		_		_
State I					E/(W)				2' 10.			-]N		
Facility	1/4	of	1	/4 of Section , T County	N, R	Long	g <u>-0</u> ,	/	$\frac{2}{10.0}$	tity/ or	Villaga	Fe	et _] S		Feet
racint	уШ			Randolph		Illinois		Bald		lty/ 01	vinage					
Carr	1.			Kandolph		minois		Daiu	wiii			C	Duan			
San	-											5011	Prope			_
	Length Att. & Recovered (in)	ts	eet	Soil/Rock I	-						e (j					
. e	Att. red	uno	n Fe	And Geologi	e Origin For						ssiv 1 (ts	e		N.		nts
TyF	gth ove	S S	th L	Each Ma	jor Unit		CS	phic	l		ngth	stur tent	it di	ticit	0	⊃ /
Number and Type	Length Att. & Recovered (in	Blow Counts	Depth In Feet				U S	Graphic Log	Well Diagram		Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
~ ~		Η	_	0 - 2' SILTY CLAY CL/ML				ŽĪ							H	0-28' Blind
																Drilled. Se
			-1				CL/ML			4						log PZ-17 for soil
			F													description
			-2	2 - 4' Shelby Tube Sample												
			F													
			-3													
			EI													
			E ₁				L									
				4 - 8' SILTY CLAY CL/ML												
			-5													
			-													
			-6				CL/ML									
			F													
			F /													
			F													
			-8	8 - 10' SILTY CLAY to LE												
			E													
			-9													
			E´ I				CL/ML									
			t I													
			-10	10 - 12' LEAN CLAY: CL.				\swarrow								
			t I													
			-11													
			F				CL	\swarrow								
			-12					+								1

Signature ////	Firm Natural Resource Technology	Tel: (414) 837-3607
Mtm Mhald	234 W. Florida St., Fifth Floor, Milwaukee, WI 53204	Fax: (414) 837-3608
	Template: ILLINOIS BORING	G LOG - Project: BALDWIN GINT.GPJ



Boring Number MW-370

	/		TEC	HNOLOGY Boring Number MW-370						Pag	ge 2	of	4
San	nple								Soil	Prope			
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
			E	12 - 14' Shelby Tube Sample.									
			13 14 15 16 17 18 19 -20 -21 -22 -22 -23	14 - 24' SILTY CLAY CL/ML.	CL/ML								
			-24	24 - 26' Shelby Tube Sample.									
			-25	26 - 28' SILTY CLAY CL/ML.									
1 SS 1 CORE	10 10 60 18.5	23 50/4"	-27 -28 -29 -30 -31 -32	28 - 28.4' LEAN CLAY: CL, yellowish brown (10YR 5/4), trace angular limestone gravel, soft, medium plasticity, moist. 28.4 - 28.9' SHALE: BDX (SH), gray, highly decomposed, very weak. 28.9 - 38.1' SHALEY LIMESTONE: BDX (LS/SH), light gray to gray, intensely fractured (extremely narrow to moderately narrow apertures), medium to thickly bedded, microcrystalline, moderately decomposed, very strong.	CL/ML BDX (SH) BDX (LS/SH								Core 1, RQD=51%



			TEC	HNOLOGY										
				Boring Number MW-370		1	1		1			ge 3	of	4
San	<u> </u>									Soil	Prop	erties		_
	Length Att. & Recovered (in)	nts	feet	Soil/Rock Description					ive tsf)					ø
er ype	h At 'ered	Cou	InF	And Geologic Origin For	s	е.		am	ressi gth (i	nre nt	_	city		Jents
Number and Type	engtl ecov	Blow Counts	Depth In Feet	Each Major Unit	SC	Graphic Log	Well	iagr	Compressive Strength (tsf)	Moisture Content	Liquid	Plasticity Index	P 200	RQD/ Comments
z a	L R	В		28.9 - 38.1' SHALEY LIMESTONE: BDX (LS/SH),	D		≯		S C	20		L P	Ч	
			E	light gray to gray, intensely fractured (extremely narrow to moderately narrow apertures), medium to										
			-33	thickly bedded, microcrystalline, moderately										
			E	decomposed, very strong. (continued)										
2 CORE	51.5 12		-34	33.9' - 38.1' gray, greenish gray in fractures, trace fossils, moderately to highly decomposed, slightly to										Core 2, RQD=0%
CORE	12		E	moderately disintegrated, clay in shoe with a hard,										
			-35	reddish brown inclusion.	BDX (LS/SH									
			Ē											
			<u>-36</u>	36' - 37.9' vertical fracture.										
			Ē											
			-37											
			-											
3	24		-38	38.1 - 44' SHALE : BDX (SH), bluish gray,										Core 3,
CORE	25		- 20	intensely fractured (extremely narrow to narrow apertures), highly decomposed, weak.										RQD=40%
			-39											
			-40											
4	24		-40											Core 4,
CORE	11		-41	40.6' - 40.8 shaley limestone layer, light gray to										RQD=0%
5	36 32			gray, microcrystalline, moderately decomposed, very strong.	BDX (SH)									Core 5,
CORE	32		-42	41.1' - 43.2 gray, moderately to highly decomposed.										RQD=78%
-			- 12											
			-43											
			E											
c F	12		-44		<u> </u>									Coro 6
6 CORE	28		E	44 - 45.7' SHALEY LIMESTONE: BDX (LS/SH), light gray to gray, intensely fractured (extremely										Core 6, RQD=29%
			-45	narrow to narrow apertures), thin to medium bedded, microcrystalline, slightly decomposed, clay	BDX (LS/SH									
7 CORIE	45		E	cement in apertures, very strong. 45' shale layer, bluish gray, moderately fractured										Core 7,
CORE	27		-46	(extremely narrow to narrow apertures), highly / decomposed, weak.										RQD=65%
			F	45.7 - 52.2' SHALE: BDX (SH), bluish gray,										
			-47	moderately fractured (tight to narrow), highly decomposed, weak.										
			E											
			-48											
			Ē		BDX									
8	24		-49		(SH)									Core 8,
CORE	30		E											RQD=78%
			50											
			Ê											
Ц л л	24		-51											Coro
9 CORE	24 24		-											Core 9, RQD=0%
••			-52	l			ľ í	.			I	I	l	



			1	Boring Number MW-370						~	Pag		of	4
San	nple									Soil	Prop	erties		
	Length Att. & Recovered (in)	ts	et	Soil/Rock Description					eve tj					
ູ່ຊ	Att. red	Blow Counts	Depth In Feet	And Geologic Origin For					ssiv 1 (ts	9		Σ.		ants
Tyr	gth ove	M M	th I	Each Major Unit	CS	phic	l grar		npre	stur	it di	sticit ex	00	D/
Number and Type	Length Att. & Recovered (in	Blo	Dep		U S	Graphic Log	Well Diagram		Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
			_	√ <u>52' clay cement.</u>										
				52.2 - 61.7' SHALEY LIMESTONE : BDX (LS/SH), light gray to gray, intensely fractured (very narrow to										
			-53	narrow), thin to medium bedded, microcrystalline,		┝┯┷┑								
10 CORE	24 36		E	slightly decomposed, cemented clay in apertures, very strong.		FF-	1 目:							Core 10, RQD=0%
			-54	52.7' - 53' clayey sand in aperture. 53' - 53.1 shale bed, bluish gray, fossiliferous,			1 目:							
			F	moderately fractured (very narrow to narrow), highly										
			-55	decomposed, weak. 53.1' white to bluish gray, gray in the fractures			1 目.							
•			F	(extremely narrow to moderately narrow apertures),										
11 CORE	24 30		-56	thinly to medium bedded, slightly to moderately disintegrated.			目							Core 11,
CORE	30		E	55.7' moderately disintegrated.										RQD=18%
			-57		BDX		1目:							
			-		(LS/SH		目							
L			-58											
12 CORE	30			58.1' highly decomposed.			目							Core 12,
CORE	27		-											RQD=39%
			59 											
			F				に目							
			-60											
			E											
13 CORE	36 53		-61											Core 13, RQD=89%
0011	55		-		L									
			62	61.7 - 65.3' LIMESTONE: BDX (LS).										
			F											
			-63											
			E		BDX									
			-64		(LS)		-							
			E				-							
			65											
			-	65.3 - 66' Overdrilled for Well Installation.	<u> </u>	<u> </u>								
			66											
			00	66' End of Boring.										Bedrock corehole
														reamed 6"
														in diameter to 66' for
														well
														installation.
	i		I	1	1	I	1	I	I	I	I	1 1		I.



Facility/Project I Baldwin En	ergy			License/			oring N				MW	-382		
-	-	me of	crew chief (first, last) and Firm	Date Dri	illing St	tarted		Da	te Drilli	ing Cor	npleted		Drill	ing Method
Jim Dittmai Bulldog Dri					11/19					11/24/	2015		an	1/4 HSA d rotary
			Common Well Name					Surfac						Diameter
101101			MW-382	Fe	et (NA	AVD	38)		3.67 Fe			38)	8	.3 inches
State Plane 5	556,44	10.86	timated: \Box) or Boring Location \boxtimes 5 N, 2,382,404.51 E E/W		at <u>38</u>		<u>1' 40</u>).344 "	Local (]N		
1/4 of		1/4	4 of Section , T N, R	Lon	g <u>-89</u>	<u> </u>	<u> </u>	. <u>9578</u>	7:11	Fe	et	S		Feet
Facility ID			County	State Illinois		Balc		City/ or V	village					
C 1.			Randolph	minois		Баю	IWIN		1	0.1	D			
Sample										5011	Prop	erties		
Number and Type Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit		USCS	Graphic Log	Well Diagram	Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	P 200	RQD/ Comments	
		1 2 - 3 4 - 5 6 7 8 8 9 10 11	2 - 4' Shelby Tube Sample. 4 - 12' SILTY CLAY CL/ML.		CL/ML									Drilled. S log PZ-18 log for so descriptic details.

Signatur Rocks	Firm Natural Resource Technology	Tel: (414) 837-3607
Brad	234 W. Florida St., Fifth Floor, Milwaukee, WI 53204	Fax: (414) 837-3608
	Templeter II LINOIS POPIN	CLOC Project: PALDWIN CINT CDI

Template: ILLINOIS BORING LOG - Project: BALDWIN GINT.GPJ



/		TEC	HNOLOGY Boring Number MW-382							Pag	ge 2	of	4
Sample							_		Soil	Prope			
Number and Type Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram		Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
		_	12 - 14' Shelby Tube Sample.					_					
			14 - 22' SILTY CLAY CL/ML.										
				CL/ML									
		-20											
		-21 -21 -22											
		-23	22 - 24' Shelby Tube Sample.										
		-24	24 - 27' SILTY CLAY CL/ML.										
		-25 26		CL/ML									
		27	27 - 29.1' WELL-GRADED SAND: SW.										
		-28 29		sw									
		-30	29.1 - 30' SANDY LEAN CLAY WITH GRAVEL: s(CL)g. 30 - 34' SILTY CLAY CL/ML.	s(CL)g									
		-31		CL/ML									
		-32			r/11								



	/		TEC	HNOLOGY Boring Number MW-382							Pag	ge 3	of	4
San	~									Soil	Prope	erties		-
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic 1	Well	Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
a			-33	30 - 34' SILTY CLAY CL/ML. (continued)	CL/MI					20	I	H I	<u> </u>	
1 SS		12 20 25 50 for 5"	-35	34 - 36' SILTY CLAY CL/ML, dark gray (10YR 4/1), dark yellowish brown 10YR 4/6 mottling, highly decomposed shale at bottom of spoon, hard (>4.5 tsf).	CL/MI									
1 Core	53 48.5		-37	36 - 38.3' SHALE: BDX (SH), gray, highly decomposed.	BDX (SH)									Core 1, RQD=94%
			-39	38.3 - 40' LIMESTONE : BDX (LS), thinly laminated, intensely fractured (extremely narrow apertures).	BDX (LS)									
2 CORE	60 24.5		41	40 - 44.5' SHALE: BDX (SH), gray, highly decomposed.	BDX (SH)									Core 2, RQD=51%
3 ⁼ CORE	54 35		-44 -45 -46 -47	44.5 - 45.4' LIMESTONE: BDX (LS), thinly bedded. 45.4 - 58.4' SHALE: BDX (SH), gray, highly decomposed.	BDX (LS)									Core 3, RQD=51%
4 CORE	24 23.5		-48 -49 -50 -51 -52	50.1' - 51.2' reddish brown and dark gray mottling. 51.2' - 52.1' limestone, intensely fractured.	BDX (SH)									Core 4, RQD=19%




Boring Number MW-382

	/		TEC	HNOLOGY Boring Number MW-382						Pag	ge 4	of	4
San	nple								Soil	Prop	erties		
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Compressive Strength (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
5 CORE	41 41			45.4 - 58.4' SHALE : BDX (SH), gray, highly decomposed. <i>(continued)</i> 52.1' gray.	BDX								Core 5, RQD=63%
6 CORE	30 25			55.9' gray to dark gray, intensely fractured, few medium limestone beds.	(SH)								Core 6, RQD=50%
7 CORE	30 30		59 60	58.4 - 62' LIMESTONE: BDX (LS), cherty, moderately fractured. 59.5' - 59.9' vertical fracture. 60' shale (2" layer).	BDX								Core 7, RQD=53%
8 ⁼ CORE	60 59		61 62 63 64 65	60.4' - 61.4' shaley, intensely fractured.	(LS) BDX (SH)								Core 8, RQD=70%
9 CORE	60 59		66 67 68 69	67.1 - 70.6' SHALEY LIMESTONE : BDX (LS/SH), fossiliferous, slightly fractured, (very narrow apertures).	BDX (LS/SH								Core 9, RQD=88% Bedrock corehole reamed 6" in diameter to 69' for
				70.6' End of Boring.									well installation.



Facility/Project Name	Local Grid Location of Well			Well Name	
Baldwin Energy Complex	Local Grid Origin (estimate	ft.	\square E. \square W.		
Facility License, Permit or Monitoring No.	Local Grid Origin 🔲 (estimate	ed: 🗌) or W	Vell Location		
	Lat. <u>38° 11' 17.995"</u> I	Long. <u>-89°</u> _		MW-304	
Facility ID	St. Plane <u>554,194.03</u> ft. N,	2,386,608.77	_ ft. E. 🛛 E /🕅	Date Well Installed	
	Section Location of Waste/Source			10/20/2015	1
Type of Well	1/4 of1/4 of Sec	. T	N.R. $\square W$	Well Installed By: (Person's Name and	nd Firm)
mw Distance from Waste/ State	Location of well Relative to was	te/Source	Gov. Lot Number	John Gates	
Source		Sidegradient		Bulldog Drilling	
ft. Illinois	d 🗆 Downgradient n 🗆		L. Cap and lock?		
A. Protective pipe, top elevation	ft. (NAVD 88)		2. Protective cover p		
B. Well casing, top elevation 44	55.49 ft. (NAVD88)		a. Inside diameter:		4.0 in.
C. Land surface elevation4	53.03 ft. (NAVD88)		b. Length:		5.0 ft.
		10000	c. Material:	Steel	
D. Surface seal, bottom ft. (NAT	$\sqrt{D88}$ or 1.0 ft.	10010010		Other	
12. USCS classification of soil near screen:	<u> Miller (Miller)</u>	. Are are are		T	🗆 No
			If yes, describe:	Three steel bollards	_
$\begin{array}{ c c c c c c c c } SM \square & SC \square & ML \square & MH \square & Cl \\ Bedrock \boxtimes & & & & \\ \end{array}$			3. Surface seal:	Bentonite	_
13. Sieve analysis attached? \Box Ye	No. M No.			Concrete	
				Other	
14. Drilling method used: Rotar		₩ 4	A. Material between	well casing and protective pipe: Bentonite	
Hollow Stem Aug	er 🗆 🛛 🗰			SandOther	
15. Drilling fluid used: Water $\boxtimes 0.2$ A	ir 🗆 👹			l: a. Granular/Chipped Bentonite	
Drilling Mud □ 0.3 Nor				ud weight Bentonite-sand slurry	
			d. <u>30</u> % Benton	ud weight Bentonite slurry ite Bentonite-cement grout	
16. Drilling additives used?	es 🛛 No			volume added for any of the above	
		KXXI	f. How installed:		
Describe			1. How instance.	Tremie pumped	
17. Source of water (attach analysis, if required):			Gravity	
Village of Baldwin		₩ (6. Bentonite seal:	a. Bentonite granules	
		/`		$3/8$ in. $\Box 1/2$ in. Bentonite chips	
E. Bentonite seal, top413.0 ft. (NAV	D88) or 40.0 ft			Other	
				: Manufacturer, product name & mes	
F. Fine sand, top ft. (NAV	(D88) or ft. \		a		
			b. Volume added	ft ³	
G. Filter pack, top <u>410.0</u> ft. (NAV	D88) or 43.0 ft.		3. Filter pack materia	al: Manufacturer, product name & me	sh size
- · · ·			a. Unin	nin Corporation, FILTERSIL	
H. Screen joint, top408.0 ft. (NAV	D88) or 45.0 ft.		b. Volume added	ft ³	
			9. Well casing:	Flush threaded PVC schedule 40	\boxtimes
I. Well bottom 398.0 ft. (NAV	D88) or 55.0 ft.			Flush threaded PVC schedule 80	
				Other	
J. Filter pack, bottom ft. (NAV	D88) or 56.0 ft.	<u> </u>). Screen material:	Schedule 40 PVC	
		7777	a. Screen Type:	Factory cut	\boxtimes
K. Borehole, bottom ft. (NAV	D88) or 59.0 ft.			Continuous slot	
				Other	
L. Borehole, diameter <u>6.0</u> in.					0.010
		\backslash	c. Slot size:	_	$\frac{0.010}{10.0}$ in.
M. O.D. well casing 2.38 in.		\backslash	d. Slotted length:	_	<u>10.0</u> ft.
2.07		`1	1. Backfill material (
N. I.D. well casing 2.07 in.				os, 2' of bedrock drill cuttings Other	M
I hereby certify that the information on this form	D '			Date Modified: 2/4/2016	
Signature Brook Ruches		Resource Tech		Tel: (414) 837-3607	
No vov	234 W. Flor	rıda Street, Floor	5, Milwaukee, WI 5	3204 Fax: (414) 837-3608	





Facility/Project Name	Local Grid Location of Well			Well Name	
Baldwin Energy Complex	$ \begin{array}{c c} & \square \ N. \\ & \underline{ft.} \ \square \ S. \\ & \underline{Iocal Grid Origin} \ \square \ (estimat) \end{array} $	ft.	\square E. \square W.		
Facility License, Permit or Monitoring No.	Local Grid Origin 🔲 (estimat	ted: 🗌) or W	ell Location		
	Lat. <u>38°</u> <u>11'</u> <u>56.266"</u>	Long. <u>-89°</u>		MW-356	
Facility ID	St. Plane <u>558,050.37</u> ft. N,	2,381,958.49	_ ft. E. E / 🕅	Date Well Installed	
	Section Location of Waste/Source	e		10/01/2015	1.17'
Type of Well	1/4 of 1/4 of Sec.	, T	N, R. $\square W$	Well Installed By: (Person's Name a	nd Firm)
mw Distance from Waste/ State	Location of Well Relative to Was	ste/Source	Gov. Lot Number	John Gates	
Source		Sidegradient		Bulldog Drilling	
ft. Illinois	0		. Cap and lock?		□ No
A. Protective pipe, top elevation	ft. (NAVD 88)		. Cap and lock?		
B. Well casing, top elevation 42	27.60 ft. (NAVD88)		a. Inside diameter:		4.0 in.
C. Land surface elevation42	25.18 ft. (NAVD88)		b. Length:	_	<u>5.0</u> ft.
		10,000,00	c. Material:	Steel	\boxtimes
D. Surface seal, bottom <u>424.2</u> ft. (NA)	/D88) or 0 ft.			Other	
12. USCS classification of soil near screen:	<u> Mikov (Mikov</u>	. Aucoucouc			🗆 No
			If yes, describe:		_
$\begin{array}{ c c c c c c c c c c c c c c c c c c c$. Surface seal:	Bentonite	
13. Sieve analysis attached? Image: Yes	rs ⊠ No			Concrete Other	
				well casing and protective pipe:	
14. Drilling method used: Rotat Hollow Stem Aug				Bentonite	\boxtimes
				Sand Other	_
		5	Appular space seal	a. Granular/Chipped Bentonite	
15. Drilling fluid used: Water $\boxtimes 02$ A	ir 🗆 🛛 👹			ud weight Bentonite-sand slurry	
Drilling Mud 0 3 Nor	ie 🗆 👹			ud weight Bentonite slurry	
			d. 30 % Benton	ite Bentonite-cement grout	\boxtimes
16. Drilling additives used? \Box Ye	es 🛛 No			volume added for any of the above	_
		KXXI	f. How installed:	Tremie	
Describe	KXX			Tremie pumped	\boxtimes
17. Source of water (attach analysis, if required):			Gravity	
Village of Baldwin	👹	6	. Bentonite seal:	a. Bentonite granules	
				$3/8$ in. $\Box 1/2$ in. Bentonite chips	
E. Bentonite seal, top ft. (NAV	D88 <u>) or 49.1</u> ft.			Other	
			. Fine sand material	: Manufacturer, product name & mes	n size
F. Fine sand, top ft. (NAV	D88) or ft.		a	ft ³	
C Eilter reak ter 3713 ft (NA)	D88) or 53.9 ft.	X/.		ft ³ l: Manufacturer, product name & me	ah siza
G. Filter pack, top $3/1.3$ ft. (NAV	D88) or 55.5 II.	°	-	nin Corporation, FILTERSIL	SII SIZC
H. Screen joint, top 369.2 ft. (NAV	D88) or 56.0 ft.			ft ³	_
		<u> </u>	9. Well casing:	Flush threaded PVC schedule 40	\boxtimes
I. Well bottom <u>359.2</u> ft. (NAV	D88 <u>) or 66.0</u> ft. <		6	Flush threaded PVC schedule 80	
				Other	
J. Filter pack, bottom 358.2 ft. (NAV	D88) or 67.0 ft.	10	. Screen material:	Schedule 40 PVC	
			a. Screen Type:	Factory cut	\boxtimes
K. Borehole, bottom 356.2 ft. (NAV	D88 <u>) or 69.0</u> ft.			Continuous slot	
				Other	
L. Borehole, diameter 6.0 in.					<u>0.010</u> in.
238		$\langle \rangle$	c. Slot size:	-	10.010 m. 10.0 ft.
M. O.D. well casing 2.38 in.		11	d. Slotted length:. Backfill material (below filter pack): None	
N. I.D. well casing <u>2.07</u> in.		11		drock drill cuttings Other	
I hereby certify that the information on this form	n is true and correct to the best of r	my knowledge.		Date Modified: 2/26/2016	
Signature Brad Backs	D '	Resource Tech	nology	Tel: (414) 837-3607	
Brad Ruches			5, Milwaukee, WI 5		



Facility/Project Name	Local Grid Location of Well			Well Name	
Baldwin Energy Complex		ft.	\square E. \square W.		
Facility License, Permit or Monitoring No.				1	
	Lat. <u>38°</u> <u>11'</u> <u>49.150"</u> L	Long. <u>-89°</u> _	<u>52'</u> <u>12.929"</u> or	MW-369	
Facility ID	St. Plane557,329.71ft. N,	2,381,765.41	ft. EE / (W)	Date Well Installed	
	Section Location of Waste/Source	2		11/19/2015	
Type of Well	1/4 of 1/4 of Sec	. T.	N.R. $\Box E$	Well Installed By: (Person's Name and	id Firm)
mw	Location of Well Relative to Wast	te/Source	Gov. Lot Number	Mark Baetje	
Distance from Waste/ State		Sidegradient		Bulldog Drilling	
	d ⊠ Downgradient n □		1. Cap and lock?	∑ Yes	
A. Protective pipe, top elevation	ft. (NAVD 88)		2. Protective cover p		
B. Well casing, top elevation4	22.71 ft. (NAVD88)		a. Inside diameter:	-	<u>4.0</u> in.
C. Land surface elevation4	20.49 ft. (NAVD88)		b. Length:		5.0 ft.
		1.	c. Material:	Steel	\boxtimes
D. Surface seal, bottom ft. (NA	VD88)_or ^{1.0} ft.			Other	
12. USCS classification of soil near screen:	The second s	A ANCONCONC	d. Additional prote		🗆 No
			If yes, describe:	Two steel bollards	_
$ SM \square SC \square ML \square MH \square C $ Bedrock \boxtimes			3. Surface seal:	Bentonite	
	es ⊠ No			Concrete	_
				Other	
14. Drilling method used: Rota Hollow Stem Aug	5 883	ĺ 👹 í	+. Material between	well casing and protective pipe: Bentonite	
-	ier			Sand Other	
				1: a. Granular/Chipped Bentonite	
15. Drilling fluid used: Water $\boxtimes 0.2$ A	Air 🗆 🛛 👹	KXX	-	ud weight Bentonite-sand slurry	
Drilling Mud 0 3 No.	ne 🗆 🛛 👹	NVX1	-	ud weight Bentonite slurry	
			d. <u>30</u> % Benton		
16. Drilling additives used? \Box	es 🛛 No			volume added for any of the above	
			f. How installed:		
Describe				Tremie pumped	
17. Source of water (attach analysis, if required	1):			Gravity	
Village of Baldwin	🕅	- 💥 🖉	6. Bentonite seal:	a. Bentonite granules	
				$3/8$ in. $\Box 1/2$ in. Bentonite chips	
E. Bentonite seal, top ft. (NAV	/D88) or 46.8 ft.	₩ /.		Other	
				: Manufacturer, product name & mesh	1 SIZE
F. Fine sand, top ft. (NAV	/D88) or ft.	````	a	c_3	_
G. Filter pack, top368.7 ft. (NAV	VD88) or 51.8 ft.		b. Volume added Filter pack materia	ft ³ al: Manufacturer, product name & mes	sh size
G. Filter pack, top It. (NAV			- Linin	nin Corporation, FILTERSIL	SIT SIZE
H. Screen joint, top364.5 ft. (NAV	VD88) or 56.0 ft.		a. <u>Unin</u> b. Volume added	-	_
		= / (9. Well casing:	Flush threaded PVC schedule 40	\boxtimes
I. Well bottom 354.5 ft. (NAV	VD88).or 66.0 ft. <		i i i i i i i i i i i i i i i i i i i	Flush threaded PVC schedule 80	
Ň				Other	
J. Filter pack, bottom353.3 ft. (NAV	VD88) or 67.2 ft.	10	0. Screen material:	Schedule 40 PVC	
		7777	a. Screen Type:	Factory cut	\boxtimes
K. Borehole, bottom ft. (NAV	VD88) or 70.7 ft.			Continuous slot	
6.0				Other	
L. Borehole, diameter 6.0 in.					0.010 .
2.28			c. Slot size:		$\frac{0.010}{10.0}$ in.
M. O.D. well casing 2.38 in.			d. Slotted length:1. Backfill material (below filter pack): None	
N. I.D. well casing 2.07 in.		1.	1' of bentonite chip	s, 2.5' of bedrock drill cuttings Other	
N. I.D. well casing 2.07 in.			r		ت
I hereby certify that the information on this form	n is true and correct to the best of n	ny knowledge.		Date Modified: 2/26/2016	
Signature	D '	Resource Tech	nnology	Tel: (414) 837-3607	
Ath Mala			5, Milwaukee, WI 5		

Signature	htmompeld	Firm	Natural Resource Technology 234 W. Florida Street, Floor 5, Milwaukee, WI 53204	Tel: (414) 837-360 Fax: (414) 837-360
	111. 0-1/			




Facility/Project Name	Local Grid Location of Well		Well Name
Baldwin Energy Complex	Local Grid Origin ☐ (estimated: ☐	$ft. \square E.$	
Facility License, Permit or Monitoring No.			
	Lat. <u>38°</u> <u>11'</u> <u>44.170"</u> Long	<u>-89°</u> <u>52'</u> <u>10.808"</u> or	MW-370
Facility ID	St. Plane556,826.50ft. N,2,381	1,936.14 ft. E. E/Ŵ	Date Well Installed
	Section Location of Waste/Source		11/25/2015
Type of Well	1/4 of 1/4 of Sec, 7	Γ ΝΡ ΠΨ	Well Installed By: (Person's Name and Firm)
mw	Location of Well Relative to Waste/Source	e Gov. Lot Number	Mark Baetje
Distance from Waste/ State	u 🗆 Upgradient s 🗆 Sidegra	adient	
ft. Illinois	d 🛛 Downgradient 🛛 n 🗆 Not Kn		
A. Protective pipe, top elevation	ft. (NAVD 88)	1. Cap and lock?	🖾 Yes 🗆 No
B. Well casing, top elevation 42	20.85_ft. (NAVD88)	2. Protective cover p a. Inside diameter:	<u>4.0</u> in.
C. Land surface elevation4	18.67 ft. (NAVD88)	b. Length:	$\frac{5.0}{\text{Steel}} \text{ft.}$
D. Surface seal, bottom ft. (NAV	/D88).or <u>1.0</u> ft.	c. Material:	Other
12. USCS classification of soil near screen:			ection?
		If yes, describe	Three steel bollards
$\begin{array}{ c c c c c c c c c c c c c c c c c c c$		3. Surface seal:	Bentonite □ Concrete ⊠
13. Sieve analysis attached? \Box Ye	es 🛛 No		Other
14. Drilling method used: Rotar			well casing and protective pipe:
Hollow Stem Aug			Bentonite
			Sand Other
		5 Annular space sea	l: a. Granular/Chipped Bentonite
15. Drilling fluid used: Water $\boxtimes 02$ A	ir 🗆 🛛 👹		ud weight Bentonite-sand slurry
Drilling Mud 03 Nor	ıe □ 🛛 👹 👹		ud weight Bentonite slurry
		d. 30 % Benton	ite Bentonite-cement grout 🛛
16. Drilling additives used? \Box Ye	es 🖾 No		volume added for any of the above
		f. How installed:	
Describe			Tremie pumped 🛛
17. Source of water (attach analysis, if required):		Gravity 🗆
Village of Baldwin		6. Bentonite seal:	a. Bentonite granules \Box
L			$3/8$ in. $\Box 1/2$ in. Bentonite chips \boxtimes
E. Bentonite seal, top ft. (NAV	D88).or 29.0 ft.	/ c	Other
F. Fine sand, top ft. (NAV	(D88) or ft >	7. Fine sand material	: Manufacturer, product name & mesh size
			ft ³
G. Filter pack, top ft. (NAV	D88 <u>) or 51.0</u> ft.	8. Filter pack materia	al: Manufacturer, product name & mesh size
H. Screen joint, top365.7 ft. (NAV	D88) or 53.0 ft.	/	nin Corporation, FILTERSIL
		9. Well casing:	Flush threaded PVC schedule 40 \boxtimes
I. Well bottom <u>355.7</u> ft. (NAV	D88).or_63.0_ft. <	y. Wen cashig.	Flush threaded PVC schedule 80 \Box
	D88).or 63.0 ft. D88).or 63.5 ft.		Other
J. Filter pack, bottom ft. (NAV	D88).or 63.5 ft.	10. Screen material:	Schedule 40 PVC
K. Borehole, bottom352.7 ft. (NAV	D88) or 66.0 ft.	a. Screen Type:	Factory cut ⊠ Continuous slot □
			Other
L. Borehole, diameter <u>6.0</u> in.		b. Manufacturer	
		c. Slot size:	
M. O.D. well casing 2.38 in.		d. Slotted length:	<u>10.0</u> ft.
		11. Backfill material (below filter pack): None \Box
N. I.D. well casing <u>2.07</u> in.		2.1' of bentonite chi	ps, 0.4' of bedrock drill cuttings Other
I hereby certify that the information on this form			Date Modified: 2/26/2016
Signature / M /	Firm Notural Descur	a Tashnalagu	Tel: (414) 837-3607


ignature	Brood Ruches	Firm Natural Resource Technology 234 W. Florida Street, Floor 5, Milwaukee, WI 53204	Tel: (414) 837-3607 Fax: (414) 837-3608





Facility/Project Name	Local Grid Location of Well		Well Name
Baldwin Energy Complex		$ft. \square W.$	
Facility License, Permit or Monitoring No.	Local Grid Origin 🔲 (estimated:) or Well Location	
	Lat. <u>38° 11'</u> 40.344" Lor	ng. <u>-89°</u> <u>52'</u> <u>4.958"</u>	
Facility ID	St. Plane <u>556,440.86</u> ft. N,	<u>2,382,404.51</u> ft. E. E/W	Date Well Installed
	Section Location of Waste/Source		11/23/2015
Type of Well	1/4 of 1/4 of Sec	, T N, R	E Well Installed By: (Person's Name and Firm)
mw Distance from Waste/ State	Location of Well Relative to Waste/S	Source Gov. Lot Numbe	r Jim Dittmaier
Source		degradient	Bulldog Drilling
ft. Illinois	0	ot Known 1. Cap and lock?	$\qquad \qquad $
A. Protective pipe, top elevation	ft. (NAVD 88)	2. Protective cove	
B. Well casing, top elevation 43	31.19 ft. (NAVD88)	a. Inside diame	
C. Land surface elevation42	28.67 ft. (NAVD88)	b. Length:	<u>5.0</u> ft.
		c. Material:	Steel 🛛
D. Surface seal, bottom <u>427.7</u> ft. (NA)	/D88) or 1.0 ft.		Other
12. USCS classification of soil near screen:	<u> </u>		rotection? \boxtimes Yes \square No
		If yes, descri	
$\begin{array}{ c c c c c c c c c c c c c c c c c c c$		3. Surface seal:	Bentonite
13. Sieve analysis attached? Image: Yes	es 🖾 No		Concrete
		X N	en well casing and protective pipe:
14. Drilling method used: Rotat Hollow Stem Aug			Bentonite
	er 🗆 🛛 💥 👹	8	Sand Other 🖂
		5 Appular space	seal: a. Granular/Chipped Bentonite
15. Drilling fluid used: Water $\boxtimes 02$ A	ir 🗆 🛛 👹		I mud weight Bentonite-sand slurry
Drilling Mud 0 3 Nor	ie 🗆 🛛 👹		I mud weight Bentonite slurry
		$d_1 = \frac{30}{\%}$ Ben	tonite Bentonite-cement grout 🛛
16. Drilling additives used? \Box Ye	es 🖾 No		Ft^3 volume added for any of the above
		f. How install	
Describe		8	Tremie pumped 🛛
17. Source of water (attach analysis, if required):	8	Gravity 🗆
Village of Baldwin	📓 🖁	6. Bentonite seal:	8
			\boxtimes 3/8 in. \Box 1/2 in. Bentonite chips \boxtimes
E. Bentonite seal, top 392.8 ft. (NAV	D88 <u>) or 35.9</u> ft.	8 /	Other 🗆
	🛛 🔪	⊗ / /	rial: Manufacturer, product name & mesh size
F. Fine sand, top ft. (NAV	D88) or ft.	a	rd ft ³
C Eilter reak ter 375.8 ft (NA)	D88).or 52.9 ft.		ed ft ³ erial: Manufacturer, product name & mesh size
G. Filter pack, top $3/5.8$ ft. (NAV	D8810F 52.5 II.		nimin Corporation, FILTERSIL
H. Screen joint, top ft. (NAV	D88) or 56.0 ft.		2d ft ³
		9. Well casing:	Flush threaded PVC schedule 40 \boxtimes
I. Well bottom <u>362.7</u> ft. (NAV	D88) or 66.0 ft.	e e	Flush threaded PVC schedule 80 \Box
	D88).or 66.0 ft. D88).or 66.4 ft.		Other
J. Filter pack, bottom <u>362.3</u> ft. (NAV	D88).or 66.4 ft.	10. Screen material	: Schedule 40 PVC
		a. Screen Type	: Factory cut
K. Borehole, bottom ft. (NAV	D88 <u>) or 69.0</u> ft.		Continuous slot \Box
			Other
L. Borehole, diameter 6.0 in.	·····		er 0.010_ in.
238		c. Slot size:	10.0
M. O.D. well casing 2.38 in.		d. Slotted leng	al (below filter pack): None \Box
N. I.D. well casing <u>2.07</u> in.			f bedrock drill cuttings \Box Other \boxtimes
1.1. <i>D</i> . wen casing III.			
I hereby certify that the information on this form	n is true and correct to the best of my	knowledge.	Date Modified: 2/26/2016
Signature Brook Ruchs	D '	ource Technology	Tel: (414) 837-3607
Brad Proven		a Street, Floor 5, Milwaukee, W	


ATTACHMENT 4 – MAPS OF THE DIRECTION OF GROUNDWATER FLOW





























CCR MONITORED UNIT




CCR MONITORED UNIT



CCR MONITORED UNIT





CCR RULE MONITORING WELL

- H NON-CCR RULE MONITORING WELL
- GROUNDWATER FLOW DIRECTION CCR MONITORED MULTI-UNIT

CONTOUR INTERVAL, NAVD88)

GROUNDWATER ELEVATION CONTOUR (10-FT

INFERRED GROUNDWATER ELEVATION CONTOUR

- CCR MONITORED UNIT
- NON-CCR UNIT

BALDWIN BOTTOM ASH POND (UNIT ID: 601) AND BALDWIN FLY ASH POND SYSTEM (UNIT ID: 605) GROUNDWATER ELEVATION CONTOUR MAP

MARCH 24, 2020

BALDWIN ENERGY COMPLEX BALDWIN, ILLINOIS RAMBOLL US CORPORATION A RAMBOLL COMPANY



ATTACHMENT 5 – TABLES SUMMARIZING CONSTITUENT CONCENTRATIONS AT EACH MONITORING WELL

Analytical Results - Appendix III Baldwin Bottom Ash Pond

Sample	Date	Boron, total	Calcium, total	Chloride, total	Fluoride, total	рН	Sulfate, total	Total Dissolved Solids	
Location	Sampled	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(s.u.)	(mg/L)	(mg/L)	
Background	Wells								
MW-304	12/29/2015	1.28	9.64	124	1.98	8.0	157	1090	
MW-304	3/21/2016	1.27	9.86	131	1.86	8.2	163	1200	
MW-304	12/27/2016	1.51	15.4	141	1.61	7.9	177	1230	
MW-304	6/21/2016	1.33	14.3	140	1.59	8.1	200	1220	
MW-304	9/19/2016	1.95	16.5	138	1.66	7.9	176	1220	
MW-304	9/26/2018	1.74	13.1	151	1.64	7.9	201	1420	
MW-304	3/16/2017	1.49	6.91	144	1.66	7.9	166	1280	
MW-304	6/21/2017	1.55	17.8	152	1.84	7.9	177	1360	
MW-304	7/28/2017	1.42	13.2	155	1.75	7.8	187	1330	
MW-304	11/28/2017	1.45	11.4	138	1.72	8.0	178	1330	
MW-304	6/27/2018	1.75	12.9	151	1.67	7.4	208	1360	
MW-304	3/20/2019	1.82	13.7	148	1.88	7.7	177	1390	
MW-304	9/25/2019	1.84	18.4	152	1.74	7.9	169	1350	
MW-304	3/26/2020	1.66	17.2	153	1.81	7.9	177	1320	
MW-306	12/27/2016	0.220	30.7	47	0.58	10.8	26	360	
MW-306	6/21/2016	0.478	5.37	33	0.69	10.3	21	408	
MW-306	9/19/2016	0.240	35.3	47	0.55	11.0	28	235	
MW-306	9/26/2018	0.159	36.9	61	0.54	11.1	34	325	
MW-306	3/22/2016	0.634	6.10	34	0.83	9.9	19	482	
MW-306	3/16/2017	0.306	19.7	51	0.61	11.2	27	328	
MW-306	6/21/2017	0.225	26.3	53	0.62	11.1	30	335	
MW-306	8/18/2016	0.322	22.4	41	0.54	10.3	25	314	
MW-306	7/28/2017	0.259	15.3	54	0.60	10.9	31	256	
MW-306	11/28/2017	0.407	3.40	55	0.65	10.7	39	328	
MW-306	6/27/2018	0.139	45.9	64	0.64	10.5	42	376	
MW-306	3/20/2019	0.174	50.4	62	0.65	11.4	32	330	
MW-306	9/25/2019	0.166	46.0	62	0.59	11.0	37	318	
MW-306	3/26/2020	0.180	43.1	63	0.60	11.5	37	288	
Downgradien	t Wells								
MW-356	12/29/2015	1.93	12.7	42	1.91	7.5	47	674	
MW-356	3/28/2016	1.83	11.7	41	1.89	7.8	50	666	
MW-356	6/23/2016	2.04	12.0	40	1.78	7.6	49	670	
MW-356	9/22/2016	2.58	13.7	41	1.78	7.7	51	670	
MW-356	12/27/2016	2.06	11.4	40	1.80	7.7	44	678	
MW-356	3/15/2017	1.99	11.7	34	1.85	7.8	47	696	
MW-356	6/20/2017	1.97	10.6	34	1.88	7.8	45	642	
MW-356	7/26/2017	1.93	11.2	34	1.88	7.9	46	670	
MW-356	11/27/2017	1.98	12.2	33	1.99	7.6	44	744	
MW-356	6/26/2018	2.14	11.4	31	1.96	7.4	46	696	
MW-356	9/26/2018	2.29	12.0	36	1.88	7.8	46	718	
MW-356	3/19/2019	2.12	11.7	31	2.18	7.8	43	678	
MW-356	9/24/2019	2.04	11.6	29	2.00	7.7	38	644	
MW-356	3/25/2020	1.94	12.2	29	2.01	7.9	43	654	

Analytical Results - Appendix III Baldwin Bottom Ash Pond

Sample	Date	Boron, total	Calcium, total	Chloride, total	Fluoride, total	рН	Sulfate, total	Total Dissolved Solids
Location	Sampled	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(s.u.)	(mg/L)	(mg/L)
MW-369	12/29/2015	0.729	4.12	154	3.60	8.8	338	1070
MW-369	3/28/2016	1.42	20.4	126	2.69	8.4	220	1280
MW-369	6/23/2016	1.91	27.9	176	2.90	8.5	234	1230
MW-369	9/22/2016	2.40	80.3	89	1.31	8.3	157	784
MW-369	12/27/2016	1.90	54.6	127	1.75	8.5	170	964
MW-369	6/20/2017	1.92	64.1	117	1.54	7.4	154	836
MW-369	7/26/2017	1.92	68.2	89	1.32	7.4	125	700
MW-369	11/27/2017	2.10	74.8	95	1.46	7.5	104	780
MW-369	6/26/2018	1.55	69.3	70	1.09	7.0	107	720
MW-369	9/26/2018	2.14	77.8	71	1.10	7.3	100	704
MW-369	3/19/2019	1.96	70.7	92	1.48	7.3	98	732
MW-369	9/24/2019	0.948	85.0	101	1.08	6.7	90	788
MW-369	3/14/2017	1.98	68.5	94	1.31	7.8	142	784
MW-369	3/25/2020	0.714	92.3	94	0.95	7.1	92	726
MW-370	12/29/2015	1.77	31.6	1120	2.80	7.7	234	2510
MW-370	3/28/2016	1.56	25.8	1140	2.53	7.9	281	2710
MW-370	6/23/2016	2.43	42.1	1100	2.63	8.0	247	2730
MW-370	9/22/2016	1.81	35.4	1120	2.70	7.7	241	2620
MW-370	12/27/2016	1.82	33.6	1140	2.77	7.3	230	2780
MW-370	6/20/2017	1.82	35.1	1240	2.94	7.6	249	2850
MW-370	11/27/2017	1.81	45.9	1290	2.99	7.9	268	2960
MW-370	6/26/2018	1.75	43.1	1390	2.94	7.4	282	3130
MW-370	9/26/2018	2.05	45.5	1530	3.06	7.7	287	3280
MW-370	7/25/2017	1.84	38.2	1280	3.00	7.6	247	2830
MW-370	3/19/2019	2.01	46.7	1280	3.45	7.7	224	2950
MW-370	9/24/2019	1.95	47.0	1290	3.00	7.5	237	2830
MW-370	3/14/2017	1.81	38.1	1120	2.58	7.9	240	2730
MW-370	3/25/2020	1.79	44.5	1340	3.19	7.7	251	2880
MW-382	12/29/2015	1.61	19.3	46	2.77	7.8	457	1120
MW-382	3/28/2016	1.60	17.9	37	2.87	7.9	509	1250
MW-382	6/23/2016	2.17	24.8	39	2.83	8.0	447	1200
MW-382	9/22/2016	2.57	27.3	35	2.78	7.8	481	1170
MW-382	12/27/2016	1.78	18.4	35	2.76	7.7	428	1200
MW-382	6/20/2017	1.71	19.4	39	2.89	7.8	445	1160
MW-382	11/27/2017	1.86	20.3	35	2.91	7.9	443	1240
MW-382	6/26/2018	2.02	17.7	36	2.79	7.4	482	1240
MW-382	9/26/2018	1.77	16.8	40	2.92	7.8	434	1240
MW-382	7/25/2017	1.75	10.0	38	2.88	7.7	450	1180
MW-382	3/19/2019	1.86	21.5	36	3.30	7.6	426	1180
MW-382	9/24/2019	1.78	20.5	30	2.85	7.0	388	1150
MW-382	3/14/2017	1.76	20.5	34	2.85	8.1	451	1200
MW-382	3/14/2017 3/25/2020	1.74	19.7	34	3.04	7.9	451	1200
10100-302	3/23/2020	1.75	19.7	34	3.0 4	1.9	415	1100

Notes:

1. Abbreviations: mg/L - milligrams per liter; s.u. - standard units.

Analytical Results - Appendix IV Baldwin Bottom Ash Pond

Sample	Date	Antimony , total	Arsenic, total	Barium, total	Beryllium , total	Cadmium ,total	Chromium , total	Cobalt, total	Fluoride, total	Lead, total	Lithium, total	Mercury, total	Molybdenum , total	Radium- 226 + Radium 228, tot	Selenium , total	Thallium, total
Location	Sampled	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(pCi/L)	(mg/L)	(mg/L)
Background Wel	ls															
MW-304	12/29/2015	< 0.001	0.0019	0.0191	< 0.001	< 0.001	< 0.001	<0.001	1.98	<0.001	0.0568	< 0.0002	0.0052	0	< 0.001	< 0.001
MW-304	3/21/2016	<0.001	0.0016	0.0195	<0.001	< 0.001	<0.001	<0.001	1.86	<0.001	0.0541	< 0.0002	0.0076	0	<0.001	<0.001
MW-304	12/27/2016	<0.001	0.0019	0.0199	<0.001	< 0.001	<0.001	<0.001	1.61	< 0.001	0.0646	< 0.0002	0.0053	0.11	<0.001	< 0.001
MW-304	6/21/2016	<0.001	0.0016	0.0199	<0.001	< 0.001	<0.001	<0.001	1.59	<0.001	0.0552	< 0.0002	0.0058	0.49	<0.001	<0.001
MW-304	9/19/2016	<0.001	0.0025	0.0238	<0.001	< 0.001	<0.001	<0.001	1.66	<0.001	0.0693	<0.0002	0.0069	0.49	<0.001	<0.001
MW-304	9/26/2018	<0.001	0.0025	0.0229	NA	NA	<0.0015	NA	1.64	NA	0.0958	NA	0.0019	0.26	<0.001	NA
MW-304	3/16/2017	<0.001	0.0016	0.0171	<0.001	< 0.001	<0.001	<0.001	1.66	<0.001	0.0685	<0.0002	0.0081	1.18	<0.001	<0.001
MW-304	6/21/2017	<0.001	0.0017	0.0206	<0.001	< 0.001	<0.001	<0.001	1.84	<0.001	0.0650	<0.0002	0.0039	1.16	<0.001	<0.001
MW-304	7/28/2017	<0.001	0.0021	0.0193	<0.001	< 0.001	<0.001	<0.001	1.75	<0.001	0.0650	<0.0002	0.0034	0.99	<0.001	<0.001
MW-304	11/28/2017	NA	NA	NA	NA	NA	NA	NA	1.72	NA	NA	NA	NA	NA	NA	NA
MW-304	6/27/2018	<0.001	0.0021	0.021	<0.001	<0.001	<0.0015	<0.001	1.67	<0.001	0.0874	<0.0002	0.0022	1.23	<0.001	<0.002
MW-304	3/20/2019	<0.001	0.0029	0.0214	<0.001	<0.001	<0.0015	<0.001	1.88	<0.001	0.0833	<0.0002	0.0019	0.55	<0.001	<0.002
MW-304	9/25/2019	< 0.001	0.0017	0.0211	<0.001	< 0.001	<0.0015	<0.001	1.74	<0.001	0.0836	< 0.0002	0.0017	0.42	<0.001	< 0.002
MW-304	3/26/2020	<0.001	0.0016	0.0212	<0.001	<0.001	<0.0015	<0.001	1.81	<0.001	0.0782	< 0.0002	0.0015	0.95	<0.001	<0.002
MW-306	12/27/2016	<0.001	0.0044	0.0131	<0.001	<0.001	<0.001	<0.001	0.58	<0.001	0.0160	<0.0002	0.0201	0.21	<0.001	<0.001
MW-306	6/21/2016	<0.001	0.0140	0.0097	<0.001	<0.001	0.0011	<0.001	0.69	<0.001	0.0273	<0.0002	0.0072	1.14	<0.001	<0.001
MW-306	9/19/2016	<0.001	0.0045	0.0157	<0.001	<0.001	<0.001	<0.001	0.55	<0.001	0.0201	<0.0002	0.0198	0.12	<0.001	<0.001
MW-306	9/26/2018	< 0.001	0.0019	0.0155	NA	NA	<0.0015	NA	0.54	NA	0.0132	NA	0.0252	0.49	<0.001	NA
MW-306	3/22/2016	< 0.001	0.0101	0.0113	< 0.001	< 0.001	0.0011	< 0.001	0.83	< 0.001	0.0378	< 0.0002	0.0067	0.35	< 0.001	< 0.001
MW-306	3/16/2017	< 0.001	0.0153	0.0096	< 0.001	< 0.001	< 0.001	< 0.001	0.61	< 0.001	0.0170	< 0.0002	0.0182	0.90	< 0.001	< 0.001
MW-306	6/21/2017	< 0.001	0.0046	0.0127	< 0.001	< 0.001	< 0.001	< 0.001	0.62	< 0.001	0.0157	< 0.0002	0.0224	0.89	< 0.001	< 0.001
MW-306	8/18/2016 7/28/2017	< 0.001	0.0121	0.0125	<0.001 <0.001	<0.001 <0.001	< 0.001	<0.001 <0.001	0.54 0.60	<0.001 <0.001	0.0202	< 0.0002	0.0126	0.49	<0.001 <0.001	<0.001 <0.001
MW-306 MW-306	11/28/2017	<0.001 NA	0.0057 NA	0.0085 NA	<0.001 NA	<0.001 NA	0.0015 NA	<0.001 NA	0.60	<0.001 NA	0.0159 NA	<0.0002 NA	0.0237 NA	0.14 NA	<0.001 NA	<0.001 NA
MW-306	6/27/2018	<0.001	0.0024	0.0205	<0.001	<0.001	<0.0015	<0.001	0.65	<0.001	0.0136	<0.0002	0.0281	0.55	<0.001	<0.002
MW-306	3/20/2019	< 0.001	0.0024	0.0205	<0.001	<0.001	< 0.0015	<0.001	0.65	<0.001	0.0136	<0.0002	0.0201	0.55	<0.001	<0.002
MW-306	9/25/2019	<0.001	0.0030	0.0192	<0.001	<0.001	< 0.0015	<0.001	0.59	<0.001	0.0143	<0.0002	0.0299	0.74	<0.001	<0.002
MW-306	3/26/2020	<0.001	0.0021	0.0150	<0.001	<0.001	< 0.0015	<0.001	0.60	<0.001	0.0133	<0.0002	0.0269	1.08	<0.001	<0.002
Downgradient W		40.001	0.0020	0.0100	40.001	40.001	10.0010	-0.001	0.00	-0.001	0.0102	40.0002	0.0200	1.00	40.001	40.002
MW-356		<0.001	<0.001	0.0297	<0.001	<0.001	<0.001	<0.001	1.91	<0.001	0.0484	<0.0002	0.0023	0.12	<0.001	<0.001
MW-356	12/29/2015 3/28/2016	0.001	0.0012	0.0297	<0.001	<0.001	<0.001	<0.001	1.91	<0.001	0.0404	<0.0002	0.0023	0.12	<0.001	<0.001
MW-356	6/23/2016	<0.0011 <0.001	<0.0012	0.0288	<0.001	<0.001	<0.001	<0.001	1.89	<0.001	0.0408	<0.0002	0.0027	0.146	<0.001	<0.001
MW-356	9/22/2016	< 0.001	<0.001 0.0013	0.0315	<0.001	<0.001	<0.001	<0.001	1.78	<0.001	0.0464	<0.0002	0.0024	0.06	<0.001	<0.001
MW-356	12/27/2016	<0.001	0.0013	0.0334	<0.001	<0.001	<0.001	<0.001	1.70	<0.001	0.0503	<0.0002	0.0024	0.06	<0.001	<0.001
MW-356	3/15/2017	<0.001	0.0012	0.0301	<0.001	<0.001	<0.001	<0.001	1.85	<0.001	0.0523	<0.0002	0.0020	0.04	<0.001	<0.001
MW-356	6/20/2017	<0.001	<0.0010	0.0301	< 0.001	<0.001	<0.001	<0.001	1.88	<0.001	0.0533	<0.0002	0.0018	1.21	<0.001	<0.001
MW-356	7/26/2017	<0.001	<0.001	0.0297	<0.001	<0.001	<0.001	<0.001	1.88	<0.001	0.0533	<0.0002	0.0014	0.83	<0.001	<0.001
MW-356	11/27/2017	NA	NA	0.0233 NA	NA	NA	NA	NA	1.99	NA	NA	NA	NA	NA	NA	NA
MW-356	6/26/2018	<0.001	<0.001	0.0309	< 0.001	< 0.001	< 0.0015	<0.001	1.96	<0.001	0.0580	< 0.0002	< 0.0015	0.56	< 0.001	< 0.002
MW-356	9/26/2018	NA	<0.001	0.0303	NA	NA	NA	NA	1.88	NA	0.0595	NA	<0.0015	0.08	NA	NA
MW-356	3/19/2019	<0.001	0.0011	0.0322	< 0.001	< 0.001	< 0.0015	<0.001	2.18	<0.001	0.0578	< 0.0002	<0.0015	0.00	<0.001	<0.002
MW-356	9/24/2019	NA	<0.001	0.0322	NA	NA	<0.0015	NA	2.00	NA	0.0580	NA	< 0.0015	0.10	NA	NA
MW-356	3/25/2020	< 0.001	<0.001	0.0303	< 0.001	< 0.001	< 0.0015	<0.001	2.00	<0.001	0.0529	< 0.0002	< 0.0015	2.18	<0.001	< 0.002

					1						1			Radium-		
		Antimony	Arsenic,	Barium,	Beryllium	Cadmium	Chromium	Cobalt,	Fluoride,	Lead,	Lithium,	Mercury,	Molybdenum	226 +	Selenium	Thallium,
		, total	total	total	, total	,total	, total	total	total	total	total	total	, total	Radium	, total	total
Sample	Date													228, tot		
Location	Sampled	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(pCi/L)	(mg/L)	(mg/L)
MW-369	12/29/2015	0.0038	0.0139	0.0080	<0.001	<0.001	0.0029	<0.001	3.60	<0.001	0.0260	<0.0002	0.0761	0.01	0.0275	<0.001
MW-369	3/28/2016	0.0021	0.0034	0.0208	<0.001	<0.001	<0.001	<0.001	2.69	<0.001	0.0234	<0.0002	0.0300	0.04	0.0096	<0.001
MW-369	6/23/2016	0.0016	0.0038	0.0228	<0.001	<0.001	<0.001	<0.001	2.90	<0.001	0.0308	<0.0002	0.0264	0.89	0.0064	<0.001
MW-369	9/22/2016	<0.001	0.0020	0.0539	<0.001	<0.001	<0.001	<0.001	1.31	<0.001	0.0379	<0.0002	0.0227	0.027	0.003	<0.001
MW-369	12/27/2016	<0.001	0.0024	0.0395	<0.001	<0.001	<0.001	<0.001	1.75	<0.001	0.0311	<0.0002	0.0256	0.02	0.0023	<0.001
MW-369	6/20/2017	0.0021	0.0022	0.0503	<0.001	<0.001	<0.001	<0.001	1.54	<0.001	0.0349	<0.0002	0.0313	0.84	0.001	<0.001
MW-369	7/26/2017	<0.001	0.0016	0.0480	<0.001	<0.001	0.0012	<0.001	1.32	<0.001	0.0354	<0.0002	0.0235	0.75	<0.001	<0.001
MW-369	11/27/2017	NA	NA	NA	NA	NA	NA	NA	1.46	NA	NA	NA	NA	NA	NA	NA
MW-369	6/26/2018	<0.001	0.0015	0.0567	<0.001	<0.001	<0.0015	<0.001	1.09	<0.001	0.0280	<0.0002	0.0207	0.23	<0.001	<0.002
MW-369	9/26/2018	NA	0.0012	0.0562	NA	NA	NA	NA	1.10	NA	0.0376	NA	0.0213	1.05	NA	NA
MW-369	3/19/2019	<0.001	0.0021	0.0562	<0.001	<0.001	<0.0015	<0.001	1.48	<0.001	0.0382	<0.0002	0.0263	0.34	<0.001	<0.002
MW-369	9/24/2019	NA	0.0059	0.0849	NA	NA	<0.0015	NA	1.08	NA	0.0259	NA	0.0186	0.84	NA	NA
MW-369	3/14/2017	<0.001	0.0015	0.0482	<0.001	<0.001	<0.001	<0.001	1.31	<0.001	0.0321	<0.0002	0.0230	1.01	0.0012	<0.001
MW-369	3/25/2020	<0.001	0.0028	0.0918	<0.001	<0.001	<0.0015	<0.001	0.95	<0.001	0.0182	<0.0002	0.0113	1.72	<0.001	<0.002
MW-370	12/29/2015	0.0031	0.0013	0.0443	<0.001	<0.001	<0.001	<0.001	2.80	<0.001	0.115	<0.0002	0.0075	0.14	0.001	<0.001
MW-370	3/28/2016	0.0022	0.0027	0.0445	<0.001	<0.001	<0.001	0.0014	2.53	<0.001	0.0983	<0.0002	0.0296	0.51	<0.001	<0.001
MW-370	6/23/2016	0.0024	0.0030	0.0582	<0.001	<0.001	<0.001	<0.001	2.63	<0.001	0.154	<0.0002	0.0171	0.73	<0.001	<0.001
MW-370	9/22/2016	0.0023	0.0019	0.0431	<0.001	<0.001	<0.001	<0.001	2.70	<0.001	0.178	<0.0002	0.0181	0.35	<0.001	<0.001
MW-370	12/27/2016	<0.001	0.0023	0.0378	<0.001	<0.001	<0.001	<0.001	2.77	<0.001	0.131	<0.0002	0.0236	0.43	<0.001	<0.001
MW-370	6/20/2017	<0.001	0.0019	0.0379	<0.001	<0.001	<0.001	<0.001	2.94	<0.001	0.134	<0.0002	0.0223	1.41	<0.001	<0.001
MW-370	11/27/2017	NA	NA	NA	NA	NA	NA	NA	2.99	NA	NA	NA	NA	NA	NA	NA
MW-370	6/26/2018	<0.001	0.0012	0.0423	<0.001	<0.001	<0.0015	<0.001	2.94	<0.001	0.125	<0.0002	0.0279	0.23	<0.001	<0.002
MW-370	9/26/2018	NA	0.0010	0.0403	NA	NA	NA	NA	3.06	NA	0.142	NA	0.0214	0.73	NA	NA
MW-370	7/25/2017	<0.001	0.0017	0.0370	<0.001	<0.001	<0.001	<0.001	3.00	<0.001	0.137	<0.0002	0.0207	0.84	<0.001	<0.001
MW-370	3/19/2019	<0.001	0.0015	0.0449	<0.001	<0.001	<0.0015	<0.001	3.45	<0.001	0.147	<0.0002	0.0238	0.61	<0.001	<0.002
MW-370	9/24/2019	NA	<0.001	0.0424	NA	NA	<0.0015	NA	3.00	NA	0.149	NA	0.0188	0.75	NA	NA
MW-370	3/14/2017	0.0015	0.0019	0.0390	<0.001	<0.001	<0.001	<0.001	2.58	<0.001	0.126	<0.0002	0.0151	4.84	<0.001	<0.001
MW-370	3/25/2020	<0.001	<0.001	0.0421	<0.001	<0.001	<0.0015	<0.001	3.19	<0.001	0.132	<0.0002	0.0180	2.01	<0.001	<0.002
MW-382	12/29/2015	<0.001	0.0027	0.0204	<0.001	<0.001	0.003	<0.001	2.77	<0.001	0.0517	<0.0002	0.0034	0.15	<0.001	<0.001
MW-382	3/28/2016	<0.001	0.0030	0.0160	<0.001	<0.001	<0.001	<0.001	2.87	<0.001	0.0522	<0.0002	0.0010	0.06	<0.001	<0.001
MW-382	6/23/2016	<0.001	0.0030	0.0221	<0.001	<0.001	0.003	<0.001	2.83	<0.001	0.0705	<0.0002	0.0013	0.45	<0.001	<0.001
MW-382	9/22/2016	<0.001	0.0023	0.0243	<0.001	<0.001	0.005	<0.001	2.78	0.001	0.0723	<0.0002	0.0016	0.65	<0.001	<0.001
MW-382	12/27/2016	<0.001	0.0012	0.0157	<0.001	<0.001	0.0025	<0.001	2.76	<0.001	0.0603	<0.0002	0.0011	0.23	<0.001	<0.001
MW-382	6/20/2017	< 0.001	<0.001	0.0155	< 0.001	< 0.001	0.0018	< 0.001	2.89	<0.001	0.0647	< 0.0002	< 0.001	2.62	< 0.001	< 0.001
MW-382	11/27/2017	NA	NA	NA	NA	NA	NA	NA	2.91	NA	NA	NA	NA	NA	NA	NA
MW-382	6/26/2018	< 0.001	<0.001	0.0141	< 0.001	< 0.001	<0.0015	<0.001	2.79	<0.001	0.0678	<0.0002	< 0.0015	0.54	< 0.001	< 0.002
MW-382	9/26/2018	NA	< 0.001	0.0140	NA	NA	NA	NA	2.92	NA	0.0588	NA	< 0.0015	0.63	NA	NA
MW-382	7/25/2017	< 0.001	0.0011	0.0155	< 0.001	< 0.001	0.003	< 0.001	2.88	< 0.001	0.0610	< 0.0002	0.0017	0.97	< 0.001	< 0.001
MW-382	3/19/2019	< 0.001	0.0012	0.0170	< 0.001	< 0.001	0.0021	<0.001	3.30	<0.001	0.0625	< 0.0002	0.0019	0.16	<0.001	< 0.002
MW-382	9/24/2019	NA	0.0012	0.0221	NA	NA	0.0044	NA	2.85	NA	0.0623	NA	0.0025	0.51	NA	NA
MW-382	3/14/2017	< 0.001	0.0014	0.0176	< 0.001	< 0.001	0.0021	< 0.001	2.76	0.0013	0.0575	< 0.0002	0.0018	0.43	< 0.001	< 0.001
MW-382	3/25/2020	<0.001	0.0014	0.0196	<0.001	<0.001	0.0028	<0.001	3.04	<0.001	0.0561	<0.0002	0.0021	2.33	<0.001	<0.002

Notes: 1. Abbreviations: mg/L - milligrams per liter; NA - not analyzed; pCi/L - picocurie per liter;

ATTACHMENT 6 – SITE HYDROGEOLOGY AND STRATIGRAPHIC CROSS-SECTIONS OF THE SITE

CONCEPTUAL SITE MODEL AND DESCRIPTION OF SITE HYDROGEOLOGY (BOTTOM ASH POND)

The Baldwin Energy Complex (BEC) conceptual site model (CSM) and Description of Site Hydrogeology for the Bottom Ash Pond (BAP), located near Baldwin, Illinois are described in the following sections.

REGIONAL SETTING

The BEC is located in the Mt. Vernon Hill Country of the Till Plains Section of the Central Lowland Province. The topography of Mt. Vernon Hill Country consists of gently rolling hills and valleys that predominantly follow the surface topography of the underlying bedrock and the surface drainage is primarily toward the Kaskaskia River, located west of the Site. Near the Site, the primary geologic materials encountered from the surficial deposits downward include, lake deposits and fine-grained alluvium of the Equality Formation of the Wisconsinan Glaciation, sand and gravel glacial outwash deposits of the Pearl Formation of the Illinoian Glaciation, till deposits of the Vandalia Till Member of the Glasford Formation of the Illinoian Glaciation, and Pennsylvanian and Mississippian-aged shale and limestone bedrock. Additional regional geologic sequences in the surrounding areas include: the Kaskaskia River bottomlands west of the Site, consisting of alluvium of the Cahokia Formation, glacial outwash of the Henry Formation of the Wisconsinan Glaciation, and Pennsylvanian and Mississippian-aged shale and limestone bedrock; and Upland Areas south and east of the Site, consisting of Peoria Loess and Roxana Silt of the Wisconsinan Glaciation, till deposits of the Vandalia Till Member of the Glasford Formation, and Pennsylvanian and Mississippian-aged shale and limestone bedrock.

SITE GEOLOGY

Geologic units present at the Site include unlithified geologic materials (i.e., Peoria Loess, Equality Formation, and Vandalia Till Member of the Glasford Formation) and Mississippian and Pennsylvanian-aged bedrock as illustrated in the cross-sections attached to this demonstration.

The three principal types of unlithified materials (Upper Groundwater Unit) present above the Bedrock Unit (Uppermost Aquifer), in the vicinity of the BAP, consist of the following, in descending order:

- UNLITHIFIED DEPOSITS (UPPER GROUNDWATER UNIT)
 - Peoria Loess (silt and silty clay). The Peoria Loess occurs in topographically higher areas and bedrock upland areas and is typically underlain by the Vandalia Till Member of the Glasford Formation. The Peoria Loess is present along the northern end of the BAP and was not noted elsewhere around the ponds. It was categorized as silt and silty clay and ranges from 2 to 23 ft in thickness.
 - Equality Formation (clay and sandy clay with occasional sand seams and lenses). The stratigraphic position of the Equality Formation varies across the Site and the general position is dependent on the presence or absence of overlying units. The Equality Formation is present in the western and southern portion of the BAP. It is thickest under the southwestern portion of the BAP and pinches out moving east. The Equality Formation was deposited in a slackwater lake formed as a result of back flooding of the Kaskaskia River during flooding events of the Mississippi River. The Equality Formation ranged in thickness from approximately 5 to 25 ft.
 - Vandalia Till Member (clay and sandy clay diamictons with intermittent and discontinuous sand lenses). The Vandalia Till Member of the Glasford Formation is the lowermost and oldest unlithified geologic material in the vicinity of the Site. The Vandalia Till is a diamicton and occurs beneath the Equality Formation in the central portion of the Site. At the higher topographic elevations



(i.e., bedrock uplands) to the east and southeast of the ash ponds, the Vandalia Till is the principal unlithified geologic material and ranges from approximately 5 to 40 ft thick, but may be mantled in some areas by 4 to 6 ft of the Peoria Loess. The Vandalia Till also exhibits some intermittent and discontinuous sand lenses. The lowermost portion of the Vandalia Till may become shaley within a few feet of the top of bedrock.

- BEDROCK UNIT (UPPERMOST AQUIFER)
 - Bedrock Unit (Uppermost Aquifer) The Bedrock Unit is the Uppermost Aquifer beneath the Site and consists of Pennsylvanian and Mississippian bedrock, mainly limestone and shale. The shallow bedrock transitions from Mississippian-age limestone and shale beneath the western portion of the Site, to Pennsylvanian-age limestone and shale toward the east. The change from Mississippian bedrock to Pennsylvanian bedrock occurs beneath the central portion of the ash ponds (Willman, 1967). The shallow bedrock is composed of interbedded and undifferentiated limestone and shale. Bedrock topography slopes generally to the west and northwest across the BAP. The topographic relief of the bedrock (change in bedrock elevation beneath the BAP) is approximately 35 ft.

SITE HYDROGEOLOGY

The CCR groundwater monitoring system consists of six monitoring wells installed in the uppermost aquifer and adjacent to the BAP (MW-304, MW-306, MW-356, MW-369, MW-370 and MW-382) (see Monitoring Well Location Map, and Well Construction Diagrams and Drilling Logs attached to this demonstration). The unit utilizes two background monitoring wells (MW-304, MW-306) as part of the CCR groundwater monitoring system.

The Site Uppermost Aquifer is the shallow Pennsylvanian and Mississippian-aged bedrock that immediately underlies the unlithified deposits. Within the boundaries of the Site, only thin and intermittent sand lenses are present within predominantly clay deposits, thus, the unlithified materials do not represent a continuous aquifer unit. Off-site shallow bedrock wells are used for a water supply. The shallow bedrock yields water through interconnected secondary porosity features (e.g. cracks, fractures, crevices, joints, bedding planes and other secondary openings). The shallow bedrock is the only water-bearing unit that is continuous across the Site. Groundwater in the Pennsylvanian and Mississippian-aged bedrock mainly occurs under semi-confined to confined conditions with the overlying unlithified unit behaving as the upper confining unit to the Uppermost Aquifer.

Water quality in the Uppermost Aquifer (i.e., Pennsylvanian and Mississippian-aged bedrock) decreases with increasing depth as water becomes increasingly mineralized. Further, the ability of the unit to store and transmit water is dependent on the density of bedrock features that contribute to secondary porosities and whether those features are interconnected enough to yield water. Therefore, the lower limit of the uppermost aquifer is the depth at which either the groundwater is mineralized to a point that it is no longer a useable water source or the secondary porosities do not yield a sufficient volume of groundwater to produce a useable water supply.

Hydraulic Conductivity

Field measurements indicated that the horizontal hydraulic conductivity for the Upper Groundwater Unit ranged from 3.5×10^{-7} to 6.8×10^{-4} centimeters per second (cm/s), with a geometric mean of 3.2×10^{-5} cm/s. Laboratory testing of vertical hydraulic conductivity measurements from the units that comprise the Upper Groundwater Unit have a geometric mean value of 8.6×10^{-7} cm/s. Based on field testing, the geometric mean horizontal hydraulic conductivity for the Uppermost Aquifer (Bedrock Unit) was 5.0×10^{-6} cm/s (NRT, 2014).



Groundwater Elevations, Flow Direction and Velocity

A discussion of typical Site groundwater elevations, flow directions and groundwater velocities is included in this section using data collected in March and September of 2019. Groundwater elevation contour maps, including maps illustrating groundwater elevations and flow directions in March and September 2019, are provided as an attachment to this demonstration. Piezometric heads measured in bedrock monitoring wells on March 19, 2019 ranged from 377.15 to 448.14 feet above North American Vertical Datum of 1988 (ft NAVD88). The piezometric head at location MW-352 was above the ground surface on March 19, 2019, indicating MW-352 is a flowing artesian well. Piezometric heads measured in bedrock monitoring wells on September 24, 2019 ranged from 370.54 to 446.19 ft msl NAVD88.

Groundwater flow in the shallow bedrock is generally to the west and southwest, as indicated by elevation measurements collected on March 19, 2019. Changes in groundwater elevation across the Site typically mimic bedrock surface topography. General groundwater flow direction is west toward the Kaskaskia River (i.e., regional discharge area) with localized flow toward bedrock surface lows. For instance, flow is almost due west on the east area of the Site until groundwater reaches the bedrock valley feature at the Secondary and Tertiary Ponds, at which point the flow direction veers toward the bedrock surface low. As indicated by comparison of the March 19, 2019 and September 24, 2019 groundwater elevation contour maps, there is little to no seasonal variation in groundwater flow direction.

A hydraulic conductivity of 5 x 10⁻⁶ cm/s and a median effective porosity of 30% were used to calculate bedrock groundwater velocities based on data referenced in Groundwater Quality Assessment and Phase II Hydrogeologic Investigation (NRT, 2014). Groundwater flow velocity in the vicinity of the BAP was approximately 0.0017 and 0.0009 feet per day (ft/day) as groundwater flowed from east to west across the BAP on March 19, 2019 and September 24, 2019, respectively. Less than 0.0008 ft/day change in groundwater velocity was observed when comparing March 19, 2019 and September 24, 2019.

REFERENCES

Natural Resource Technology, Inc. (NRT), 2014. Groundwater Quality Assessment and Phase II Hydrogeologic Investigation, Baldwin Ash Pond System, Baldwin, Illinois. Prepared for Dynegy Midwest Generation, LLC by Natural Resource Technology, Inc. June 11, 2014.

Willman, H.B. and others. 1967. Geologic Map of Illinois. Illinois State Geological Survey. Champaign, Illinois.



CCR MONITORED UNIT

700

Feet

NON-CCR UNIT

350

PROPERTY BOUNDARY **CROSS-SECTION TRANSECTS** A to A' A to B'


CROSS SECTION LOCATION MAP

FIGURE 1

RAMBOLL US CORPORATION A RAMBOLL COMPANY



BALDWIN ASH POND SYSTEM BALDWIN ENERGY COMPLEX 10901 BALDWIN RD, BALDWIN, ILLINOIS



LEGEND

* * * * * * COAL COMBUSTION RESIDUALS, CCRs \times FILL


CLAY (CL) CLAY (CH)

SILT (ML) SAND (SP/SM/SW) SHALE



NOTES


- 1. This profile was developed by interpolation between widely spaced boreholes. Only at the borehole location should it be considered as an approximately accurate representation and then only to the degree implied by the notes on the borehole logs. Scale is approximate. 2.
- 3. Vertical scale is exaggerated 60X.





RAMBOLL US CORPORATION A RAMBOLL COMPANY







LEGEND

* * * * * * COAL COMBUSTION RESIDUALS, CCRs \times

> CLAY (CL) CLAY (CH)

SILT (ML) SAND (SP/SM/SW) SHALE

FILL

WELL SCREEN INTERVAL

NOTES

- 1. This profile was developed by interpolation between widely spaced boreholes. Only at the borehole location should it be considered as an approximately accurate representation and then only to the degree implied by the notes on the borehole logs. Scale is approximate. 2.
- 3. Vertical scale is exaggerated 21.25X.



FIGURE 3

RAMBOLL US CORPORATION A RAMBOLL COMPANY



ATTACHMENT 7 – STRUCTURAL STABILITY ASSESSMENT



Submitted toSubmittedDynegy Midwest Generation,AECOMLLC1001 Hig1500 Eastport DriveSuite 300Collinsville, IL 62234St. Louis

Submitted by AECOM 1001 Highlands Plaza Drive West Suite 300 St. Louis, MO 63110

October 2016

CCR Rule Report: Initial Structural Stability Assessment

For

Bottom Ash Pond At Baldwin Energy Complex

1 Introduction

This Coal Combustion Residual (CCR) Rule Report documents that the Bottom Ash Pond at the Dynegy Midwest Generation, LLC Baldwin Energy Complex meets the structural stability assessment requirements specified in 40 Code of Federal Regulations (CFR) §257.73(d). The Bottom Ash Pond is located near Baldwin, Illinois in Randolph County, approximately 0.9 miles southwest of the Baldwin Energy Complex. The Bottom Ash Pond serves as the primary wet impoundment for sluiced bottom ash and other non-CCR wastewaters produced at the Baldwin Energy Complex.

The Bottom Ash Pond is an existing CCR surface impoundment as defined by 40 CFR §257.53. The CCR Rule requires that an initial structural stability assessment for an existing CCR surface impoundment be completed by October 17, 2016. In general, the initial structural stability assessment must document that the design, construction, operation, and maintenance of the CCR unit is consistent with recognized and generally accepted good engineering practices.

The owner or operator of the CCR unit must obtain a certification from a qualified professional engineer stating that the initial structural stability assessment was conducted in accordance with the requirements of 40 CFR § 257.73(d). The owner or operator must prepare a periodic structural stability assessment every five years.

2 Initial Structural Stability Assessment

40 CFR §257.73(d)(1)

The owner or operator of the CCR unit must conduct initial and periodic structural stability assessments and document whether the design, construction, operation, and maintenance of the CCR unit is consistent with recognized and generally accepted good engineering practices for the maximum volume of CCR and CCR wastewater which can be impounded therein. The assessment must, at a minimum, document whether the CCR unit has been designed, constructed, operated, and maintained with [the standards in (d)(1)(i)-(vii)].

An initial structural stability assessment has been performed to document that the design, construction, operation and maintenance of the Bottom Ash Pond is consistent with recognized and generally accepted good engineering practices and meets the standards in 257.73(d)(1)(i)-(vii). The results of the structural stability assessment are discussed in the following sections. Based on the assessment and its results, the design, construction, operation, and maintenance of the Bottom Ash Pond were found to be consistent with recognized and generally accepted good engineering practices.

2.1 Foundations and Abutments (§257.73(d)(1)(i))

CCR unit designed, constructed, operated, and maintained with stable foundations and abutments.

The stability of the foundations was evaluated using soil data from field investigations and reviewing design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM. Additionally, slope stability analyses were performed to evaluate slip surfaces passing through the foundations.

The foundation consists of soft to stiff clay, which indicates stable foundations. Soil conditions at the abutments were found to be similar to the foundation for the remainder of the Bottom Ash Pond. Slope stability analyses exceed the criteria listed in §257.73(e)(1) for slip surfaces passing through the foundation. The slope stability analyses are discussed in the *CCR Rule Report: Initial Safety Factor Assessment for Bottom Ash Pond at Baldwin Energy Complex* (October 2016). A review of operational and maintenance procedures as well as current and past performance of the dikes has determined appropriate processes are in place for continued operational performance. Based on the conditions observed by AECOM, the Bottom Ash Pond was designed and constructed with stable foundations and abutments. Operational and maintenance procedures are in place to address any issues related to the stability of the foundations and abutments. Therefore, the Bottom Ash Pond meets the requirements in §257.73(d)(1)(i).

2.2 Slope Protection (§257.73(d)(1)(ii))

CCR unit designed, constructed, operated, and maintained with adequate slope protection to protect against surface erosion, wave action and adverse effects of sudden drawdown.

The adequacy of slope protection was evaluated by reviewing design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM.

Based on this evaluation, adequate slope protection was designed and constructed at the Bottom Ash Pond. No evidence of significant areas of erosion or wave action were observed. The interior slopes are covered with riprap erosion protection in some areas and vegetation in other areas. The exterior slopes are covered in vegetation. Operational and maintenance procedures to repair the vegetation and riprap as needed are appropriate to protect against surface erosion and wave action. Intentional or unintentional sudden drawdown of the pool in the Bottom Ash Pond is not expected to occur due to the characteristics of the spillway structures. Because sudden

drawdown conditions are not expected to occur, slope protection to protect against the adverse effects of sudden drawdown is not required. Therefore, the Bottom Ash Pond meets the requirements in §257.73(d)(1)(ii).

2.3 Dike Compaction (§257.73(d)(1)(iii))

CCR unit designed, constructed, operated, and maintained with dikes mechanically compacted to a density sufficient to withstand the range of loading conditions in the CCR unit.

The density of the dike materials was evaluated using soil data from field investigations and reviewing design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM. Additionally, slope stability analyses were performed to evaluate slip surfaces passing through the dike over the range of expected loading conditions as defined within §257.73(e)(1).

Based on this evaluation, the dike consists of soft to very stiff material that is stiff on average, which is indicative of mechanically compacted dikes. Slope stability analyses, which are discussed in the *CCR Rule Report: Initial Safety Factor Assessment for Bottom Ash Pond at Baldwin Energy Complex* (October 2016), exceed the criteria listed in §257.73(e)(1) for slip surfaces passing through the dike. Thus, the original design and construction of the Bottom Ash Pond included sufficient dike compaction. Operational and maintenance procedures are in place to identify and mitigate deficiencies in order to maintain sufficient compaction of the dikes to withstand the range of loading conditions. Therefore, the Bottom Ash Pond meets the requirements in §257.73(d)(1)(iii).

2.4 Vegetated Slopes (§257.73(d)(1)(iv))¹

CCR unit designed, constructed, operated, and maintained with vegetated slopes of dikes and surrounding areas, except for slopes which have an alternate form or forms of slope protection.

The adequacy of slope vegetation was evaluated by reviewing design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM.

Based on this evaluation, the vegetation on the exterior and interior slopes is adequate as no substantial bare or overgrown areas were observed. Riprap slope protection is present in some areas on the interior slopes and is used as an alternate form of slope protection, which is adequate as significant areas of erosion or bare soil within or around the riprap were not observed. Therefore, the original design and construction of the Bottom Ash Pond included adequate vegetation of the dikes and surrounding areas. Adequate operational and maintenance procedures are in place to regularly manage vegetation growth, including mowing and seeding any bare areas, as evidenced by the conditions observed by AECOM. Therefore, the Bottom Ash Pond meets the requirements in \$257.73(d)(1)(iv).

¹ As modified by court order issued June 14, 2016, Utility Solid Waste Activities Group v. EPA, D.C. Cir. No. 15-1219 (order granting remand and vacatur of specific regulatory provisions).

2.5 Spillways (§257.73(d)(1)(v))

CCR unit designed, constructed, operated, and maintained with a single spillway or a combination of spillways configured as specified in [paragraph (A) and (B)]:

(A) All spillways must be either:

(1) of non-erodible construction and designed to carry sustained flows; or

(2) earth- or grass-lined and designed to carry short-term, infrequent flows at non-erosive velocities where sustained flows are not expected.

- (B) The combined capacity of all spillways must adequately manage flow during and following the peak discharge from a:
 - (1) Probable maximum flood (PMF) for a high hazard potential CCR surface impoundment; or
 - (2) 1000-year flood for a significant hazard potential CCR surface impoundment; or
 - (3) 100-year flood for a low hazard potential CCR surface impoundment.

The spillways were evaluated using design drawings, operational and maintenance procedures, and conditions observed in the field by AECOM. Additionally, hydrologic and hydraulic analyses were completed to evaluate the capacity of the spillways relative to inflow estimated for the 1,000-year flood event for the significant hazard potential Bottom Ash Pond. The hazard potential classification assessment was performed by Stantec in 2016 in accordance with §257.73(a)(2).

Three separate spillways are present: a high-density polyethylene (HDPE) pipe conduit and riser, a riprap-lined emergency spillway, and a pumping station with HDPE discharge pipes. All of the spillways are constructed with non-erodible materials that are designed to carry sustained flows. The capacity of the spillways, was evaluated using hydrologic and hydraulic analysis performed per §257.82(a). The analysis found that the spillways can adequately manage flow during peak discharge resulting from the 1,000-year storm event without uncontrolled overtopping of the embankments. The hydrologic and hydraulic analyses are discussed in the *CCR Rule Report: Initial Inflow Design Flood Control System Plan for Bottom Ash Pond at Baldwin Energy Complex* (October 2016). Operational and maintenance procedures are in place to repair any issues with the spillways and remove debris or other obstructions from the spillways, as evidenced by the conditions observed by AECOM. As a result, these procedures are appropriate for maintaining the spillway. Therefore, the Bottom Ash Pond meets the requirements in §257.73(d)(1)(v).

2.6 Stability and Structural Integrity of Hydraulic Structures (§257.73(d)(1)(vi))

CCR unit designed, constructed, operated, and maintained with hydraulic structures underlying the base of the CCR unit or passing through the dike of the CCR unit that maintain structural integrity and are free of significant deterioration, deformation, distortion, bedding deficiencies, sedimentation, and debris which may negatively affect the operation of the hydraulic structure.

The stability and structural integrity of the hydraulic structure penetrating the dike of the Bottom Ash Pond, the 30inch HDPE pipe conduit spillway, was evaluated using design drawings, operational and maintenance procedures, closed-circuit televisions (CCTV) pipe inspections, and conditions observed in the field by AECOM. No other hydraulic structures are known to pass through the dike of or underlie the base of the Bottom Ash Pond.

The CCTV inspection of the HDPE outflow pipe found the pipe to be free of significant deterioration, deformation, distortion, bedding deficiencies, sedimentation, and debris that may negatively affect the operation of the hydraulic structure. Operational and maintenance procedures are in place to remove debris or other obstructions from the hydraulic structure, and address any deficiencies, as evidenced by conditions observed by AECOM. As a result, these procedures are appropriate for maintaining the spillway. Therefore, the Bottom Ash Pond meets the requirements in §257.73(d)(1)(vi).

2.7 Downstream Slope Inundation/Stability (§257.73(d)(1)(vii))

CCR unit designed, constructed, operated, and maintained with, for CCR units with downstream slopes which can be inundated by the pool of an adjacent water body, such as a river, stream or lake, downstream slopes that maintain structural stability during low pool of the adjacent water body or sudden drawdown of the adjacent water body.

The structural stability of the downstream slopes of the Bottom Ash Pond was evaluated using hydraulic and hydrologic analyses, as discussed in the *CCR Rule Report: Initial Inflow Design Flood Control System Plan for Bottom Ash Pond at Baldwin Energy Complex* (October, 2016). This analysis, which considered a 100-year flood condition in the downstream Kaskaskia River, found that the peak water surface elevation of the downstream non-CCR Secondary Pond is 0.6 feet below the elevation of the Bottom Ash Pond embankment toe during 1,000-year Inflow Design Flood conditions. During normal conditions, the pool in the Secondary Pond is approximately 1,000 lateral feet beyond the toe of the Bottom Ash Pond embankment.

Based on this evaluation, the requirements in §257.73(d)(1)(vii) are not applicable to the Bottom Ash Pond, as inundation of the downstream slopes is not expected to occur.

3 Certification Statement

CCR Unit: Dynegy Midwest Generation, LLC; Baldwin Energy Complex; Bottom Ash Pond

I, Victor A. Modeer, being a Registered Professional Engineer in good standing in the State of Illinois, do hereby certify, to the best of my knowledge, information, and belief that the information contained in this CCR Rule Report, and the underlying data in the operating record, has been prepared in accordance with the accepted practice of engineering. I certify, for the above-referenced CCR Unit, that the initial structural stability assessment dated October 13, 2016 was conducted in accordance with the requirements of 40 CFR § 257.73(d).

MODER JR. Printed Name

10/13/16 Date



About AECOM

AECOM (NYSE: ACM) is a global provider of professional technical and management support services to a broad range of markets, including transportation, facilities, environmental, energy, water and government. With nearly 100,000 employees around the world, AECOM is a leader in all of the key markets that it serves. AECOM provides a blend of global reach, local knowledge, innovation, and collaborative technical excellence in delivering solutions that enhance and sustain the world's built, natural, and social environments. A Fortune 500 company, AECOM serves clients in more than 100 countries and has annual revenue in excess of \$19 billion.

More information on AECOM and its services can be found at <u>www.aecom.com</u>.

1001 Highlands Plaza Drive Wes Suite 300 St. Louis, MO 63110 1-314-429-0100 **ATTACHMENT 8 – SAFETY FACTOR ASSESSMENT**



Submitted toSubmittedDynegy Midwest Generation,AECOMLLC1001 Hig1500 Eastport DriveSuite 300Collinsville, IL 62234St. Louis

Submitted by AECOM 1001 Highlands Plaza Drive West Suite 300 St. Louis, MO 63110

October 2016

CCR Rule Report: Initial Safety Factor Assessment

For

Bottom Ash Pond At Baldwin Energy Complex

1 Introduction

This Coal Combustion Residual (CCR) Rule Report documents that the Bottom Ash Pond at the Dynegy Midwest Generation, LLC Baldwin Energy Complex meets the safety factor assessment requirements specified in 40 Code of Federal Regulations (CFR) §257.73(e). The Bottom Ash Pond is located near Baldwin, Illinois in Randolph County, approximately 0.9 miles southwest of the Baldwin Energy Complex. The Bottom Ash Pond serves as the primary wet impoundment for sluiced bottom ash and other non-CCR wastewaters produced at the Baldwin Energy Complex.

The Bottom Ash Pond is an existing CCR surface impoundment as defined by 40 CFR §257.53. The CCR Rule requires that the initial safety factor assessment for an existing CCR surface impoundment be completed by October 17, 2016.

The owner or operator of the CCR unit must obtain a certification from a qualified professional engineer stating that the initial safety factor assessment meets the requirements of 40 CFR § 257.73(e). The owner or operator must prepare a safety factor assessment every five years.

2 Initial Safety Factor Assessment

40 CFR §257.73(e)(1)

The owner or operator must conduct initial and periodic safety factor assessments for each CCR unit and document whether the calculated factors of safety for each CCR unit achieve the minimum safety factors specified in (e)(1)(i) through (iv) of this section for the critical cross section of the embankment. The critical cross section is the cross section anticipated to be the most susceptible of all cross sections to structural failure based on appropriate engineering considerations, including loading conditions. The safety factor assessments must be supported by appropriate engineering calculations.

(i) The calculated static factor of safety under the long-term, maximum storage pool loading condition must equal or exceed 1.50.

(ii) The calculated static factor of safety under the maximum surcharge pool loading condition must equal or exceed 1.40.

(iii) The calculated seismic factor of safety must equal or exceed 1.00.

(iv) For dikes constructed of soils that have susceptibility to liquefaction, the calculated liquefaction factor of safety must equal or exceed 1.20.

A geotechnical investigation program and stability analyses were performed to evaluate the design, performance, and condition of the earthen dikes of the Bottom Ash Pond. The exploration consisted of hollow-stem auger borings, solid-stem auger borings, piezometer installation, cone penetration tests, and laboratory program including strength and index testing. Data collected from the geotechnical investigation, available design drawings, construction records, inspection reports, previous engineering investigations, and other pertinent historic documents were utilized to perform the safety factor assessment and geotechnical analyses.

In general, the subsurface conditions at the Bottom Ash Pond consist of soft to very stiff embankment fill (clay) intermittently overlying soft to stiff loess (clay), overlying medium stiff to hard residual soils (clay), which in turn overlies shale and limestone bedrock. Phreatic water is typically several feet above the bottom of the embankment.

A representative cross section was analyzed using limit equilibrium slope stability analysis software to evaluate stability of the perimeter dike system and foundations. The cross section was located at the maximum embankment height for the Bottom Ash Pond. Due to the relatively short height of the Bottom Ash Pond embankments and uniform slope orientations, subsurface stratigraphy, and phreatic conditions, a single cross section at the maximum embankment height is sufficient to represent the critical cross section. The cross section was evaluated for each of the loading conditions stipulated in §257.73(e)(1).

A liquefaction susceptibility evaluation did not find soils susceptible to liquefaction within the Bottom Ash Pond dikes or foundation. As a result, the Soils Susceptible to Liquefaction loading condition (§257.73(e)(1)(iv)) is not applicable to the Bottom Ash Pond at the Baldwin Energy Complex.

Results of the Initial Safety Factor Assessments are listed in Table 1.

Loading Conditions	§257.73(e)(1) Subsection	Minimum Factor of Safety	Calculated Factor of Safety
Maximum Storage Pool Loading	(i)	1.50	2.04
Maximum Surcharge Pool Loading	(ii)	1.40	2.04
Seismic	(iii)	1.00	1.43
Soils Susceptible to Liquefaction	(iv)	1.20	Not Applicable

Table 1 – Summary of Initial Safety Factor Assessments

Based on this evaluation, the Bottom Ash Pond meets the requirements in §257.73(e)(1).

3 **Certification Statement**


CCR Unit: Dynegy Midwest Generation, LLC; Baldwin Energy Complex; Bottom Ash Pond

I, Victor A. Modeer, being a Registered Professional Engineer in good standing in the State of Illinois, do hereby certify, to the best of my knowledge, information, and belief that the information contained in this CCR Rule Report, and the underlying data in the operating record, has been prepared in accordance with the accepted practice of engineering. I certify, for the above-referenced CCR Unit, that the initial safety factor assessment dated October 13, 2016 meets the requirements of 40 CFR §257.73(e).

MODER JR.

Printed Name

Date



About AECOM

AECOM (NYSE: ACM) is a global provider of professional technical and management support services to a broad range of markets, including transportation, facilities, environmental, energy, water and government. With nearly 100,000 employees around the world, AECOM is a leader in all of the key markets that it serves. AECOM provides a blend of global reach, local knowledge, innovation, and collaborative technical excellence in delivering solutions that enhance and sustain the world's built, natural, and social environments. A Fortune 500 company, AECOM serves clients in more than 100 countries and has annual revenue in excess of \$19 billion.

More information on AECOM and its services can be found at <u>www.aecom.com</u>.

1001 Highlands Plaza Drive Wes Suite 300 St. Louis, MO 63110 1-314-429-0100 ATTACHMENT 9 – ADDENDUM TO THE CLOSURE PLAN (SEPTEMBER 2020)



40 C.F.R. § 257.102(B)(3): Closure Plan Addendum Baldwin Bottom Ash Pond September 29, 2020

ADDENDUM NO. 1 BALDWIN BOTTOM ASH POND CLOSURE PLAN

This Addendum No. 1 to the Closure Plan for Existing Coal Combustion Residuals (CCR) Impoundment for the Baldwin Bottom Ash Pond at the Baldwin Energy Complex, Revision 0 - October 17, 2016 has been prepared to meet the requirements of Title 40 of the Code of Federal Regulations (40 C.F.R.) Section 257.103(f)(2)(v)(D) as a component of the demonstration that the Baldwin Bottom Ash Pond gualifies for a site-specific alternative deadline to initiate closure due to permanent cessation of a coal-fired boiler by a certain date.

The Baldwin Bottom Ash Pond will begin construction of closure by April 17, 2025 and cease receipt and placement of CCR and non-CCR wastestreams by no later than July 17, 2027 as indicated in the Baldwin Power Station Alternative Closure Demonstration dated September 29, 2020. Closure will be completed by October 17, 2028 within the 5-year timeframe included in the Closure Schedule identified in the Baldwin Bottom Ash Pond Closure Plan in accordance with 40 C.F.R. § 257.102(f)(ii).

All other aspects of the Closure Plan remain unchanged.

CERTIFICATION

I, Eric J. Tlachac, a Qualified Professional Engineer in good standing in the State of Illinois, certify that the information in this addendum is accurate as of the date of my signature below. The content of this report is not to be used for other than its intended purpose and meaning, or for extrapolations beyond the interpretations contained herein.

04

ERIC J. TLACHAC 062-063091 Eric J. Tlachac **Qualified Professional Engineer** 062-063091 Illinois Ramboll Americas Engineering Solutions, Inc., f/k/a O'Brien & Gere Engineers, Inc. Date: September 29, 2020







CREATE AMAZING.



Burns & McDonnell World Headquarters 9400 Ward Parkway Kansas City, MO 64114 **O** 816-333-9400 **F** 816-333-3690 www.burnsmcd.com