Illinois Power Resources Generating, LLC

EDWARDS POWER STATION BARTONVILLE, PEORIA COUNTY, ILLINOIS

Emergency Action Plan (EAP)

40 CFR § 257.73(a)(3) Coal Combustion Residual (CCR) Impoundment & Related Facilities

• Ash Pond (NID # IL50710)

Revision Date: April 13, 2017

Qualified Professional Engineer Certification; Emergency Action Plan for the Edwards Power Station Ash Pond.

In accordance with 40 CFR 257.73(a)(3)(iv), the owner or operator of a CCR unit that is required to prepare a written Emergency Action Plan under 40 CFR 257.73(a)(3) must obtain a certification from a qualified professional engineer stating that the written Emergency Action Plan meets the requirements of 40 CFR 257.73(a)(3).

I, Matthew Hoy, being a Professional Engineer in good standing in the State of Illinois, do hereby certify, to the best of my knowledge, information, and belief that:

- 1. the information contained in this Emergency Action Plan was prepared in accordance with the accepted practice of engineering; and
- 2. this Emergency Action Plan meets the requirements of 40 CFR 257.73(a)(3).

SIGNATURE

ADDRESS:

Stantec Consulting Services Inc. 1859 Bowles Avenue Suite 250 Fenton MO 63026-1944

TELEPHONE: (636) 343-3880

DATE 4/13/2017

Section

EDWARDS POWER STATION EMERGENCY ACTION PLAN CCR IMPOUNDMENT & RELATED FACILITIES

TABLE OF CONTENTS

PART I – EAP NARRATIVE AND EXHIBITS

1	STATEMENT OF PURPOSE	1
2	COMMUNICATION	4
3	EAP ROLES AND RESPONSIBILITIES	8
4	EAP RESPONSE	9
5	PREPAREDNESS	14
6	FACILITY/IMPOUNDMENT DESCRIPTION	16
7	BREACH INUNDATION MAP AND POTENTIAL IMPACTS	17

List of Tables

Table

Table 2-1.	EAP Emergency Responders	.7
	Summary of EAP Roles	
Table 4-1.	Guidance for Determining the Response Level	.9
Table 4-2.	Impoundment Trigger Elevations	11
	Step 3: Emergency Actions	
	Emergency Supplies and Equipment	
Table 5-2.	Supplier Addresses	15
Table 6-1.	Station Impoundment Characteristics	16

List of Figures

<u>Figure</u>

Page

Page

Page

Figure 1-1. Edwards Power Station Location Map	2
Figure 1-2. Edwards Power Station CCR Impoundment & Related Facilities	3
Figure 2-1. Summary/Sequence of Tasks 4-Step Incident Response Process	4
Figure 2-2. Notification Flowchart	5
Figure 2-3. EAP Response Process Decision Tree	6
Figure 7-1. Ash Pond Inundation Map	18

EDWARDS POWER STATION EMERGENCY ACTION PLAN CCR IMPOUNDMENT & RELATED FACILITIES

PART I – EAP NARRATIVE AND EXHIBITS

1 STATEMENT OF PURPOSE

The Edwards Power Station (Station) is located near Bartonville in Peoria County, Illinois. The location is shown in Figure 1-1. The Station is a coal-fired electricity producing power plant owned and operated by Illinois Power Resources Generating, LLC, a subsidiary of Dynegy. This Emergency Action Plan (EAP) was prepared in accordance with 40 CFR § 257.73(a)(3) and covers the following Coal Combustion Residual (CCR) surface impoundment located at the site:


• Ash Pond


The location of this impoundment is shown in Figure 1-2. Section 6 of this EAP includes a description of the impoundment.


The purpose of this Emergency Action Plan (EAP) is to:

- 1. Safeguard the lives, as well as to reduce property damage, of citizens living within potential downstream flood inundation areas of the CCR impoundment and related facilities at the Edwards Power Station.
- 2. Define the events or circumstances involving the CCR impoundment and related facilities at the Edwards Power Station that represent atypical operating conditions that pose a safety hazard or emergency and how to identify those conditions.
- 3. Define responsible persons, their responsibilities, and notification procedures in the event of a safety emergency.
- 4. Provide contact information of emergency responders.
- 5. Identify emergency actions in the event of a potential or imminent failure of the impoundment.
- 6. Identify the downstream area that would be affected by failure of the impoundment.
- 7. Provide for effective facility surveillance, prompt notification to local Emergency Management Agencies, citizen warning and notification responses, and preparation should an emergency occur.

Information provided by Dynegy was utilized and relied upon in preparation of this report.









Project Location Latitude: 40.595484 Longitude: -89.663301 Peoria County, Illinois

175605019 Prepared by CMB on 2017-03-29 Technical Review by SN on 2017-03-29 Independent Review by WSW on 2017-03-29

Client/Project Edwards Power Station Emergency Action Plan

Figure No ⁻1-2

Title

CCR Impoundment

2 COMMUNICATION

To facilitate understanding among everyone involved in implementing this EAP, four response levels are used to identify the condition of an impoundment. These are:

Response Levels:

- <u>Level 0</u>: Normal conditions and routine operations, including surveillance and initial investigation of unusual conditions and effects of storm events.
- <u>Level 1</u>: Potentially hazardous condition exists, requiring investigation and possible corrective action.
- <u>Level 2</u>: Potential failure situation is developing; possible mode of failure is being assessed; corrective measures are underway.
- Level 3: Failure is occurring or is imminent, public protective actions are required.

The 4-Step Incident Response Process is outlined in Figure 2-1. This should be used in conjunction with the Notification Flowchart (Figure 2-2) and EAP Decision Tree (Figure 2-3). Section 4 provides guidance tables for determining Response Levels and a table providing emergency actions to be taken given various situations. Table 2-1 lists contact information for the emergency responders.

Figure 2-1. Summary/Sequence of Tasks 4-Step Incident Response Process

Step 1: Detection, Evaluation, and Response Level Determination

Sequence of Tasks:

- Notify EAP Coordinator, Station Management (Director and Engineering), and Dynegy Dam Safety Manager of unusual condition detected and confer on next steps needed. Conduct technical evaluation of conditions as needed.
- Determine Response Level based on evaluation. (
- Table 4-1)

Step 2: Notification

Sequence of Tasks:

- Notify authorities, designated personnel, and external response partners of change in Response Level, using the Notification Flowchart. (Figure 2-2)
- *Re-notify authorities, designated personnel, and external response partners as Response Level is changed.*

Step 3: Emergency Actions

Sequence of Tasks:

- Perform emergency actions with goal of saving the impoundment and minimizing impacts to life, property, and environment. (Table 4-3)
- Take continuous actions to include situation assessment, information sharing, remediation, and public safety advisories or warnings, as warranted.
- Revise action plan as changes in conditions warrant.

Step 4: Follow-up

Sequence of Tasks:

- Document conditions and decisions in the Emergency Incident Log.
- Notify authorities, designated personnel, and external response partners that condition is stabilized; limit incident termination declarations to conditions at the site.
- Conduct and document after-action review of incident and response.




Figure 2-2. Notification Flowchart




Figure 2-3. EAP Response Process Decision Tree

Note: At any given below, if failure is imminent or actively occurring CALL 911 IMMEDIATELY to notify emergency responders and then continue with process afterwards.

Position/Entity	Nat	me
Intern	al Contacts	
Edwards Power Station	Contact	Phone #
Managing Director	Ted Lindenbusch	
Environmental Manager (EAP Coordinator)	Mark Davis	(309) 241-4219
Engineering Manager	William Ackerman	
Control Room		(309) 633-2425
Dynegy Corporate Operations		
Dam Safety Manager	Jason Campbell	(618) 792-8488
Construction Manager	Steve Bluemner	
Extern	al Contacts	
Local/County EMA, Police, & Fire	Contact	Phone #
Peoria County – EMA	Mark Molleck	(309) 691-3111
Peoria County – Sheriff Dept.	Michael D. McCoy	(309) 697-8515
Bartonville, IL Police Department	Brian Fengel	(309) 697-2323
Timber-Hollis Fire Protection District	LeAnn Westhafer	(309) 303-3458
Spring Lake State Fish and Wildlife Area	Stan Weimer	(309) 968-7135
Peoria County E-911 Board		
State Emergency Management Agencies & Organizations	Contact	Phone #
Illinois Conservation Police	Troy Lazzell	(309) 573-8434

Table 2-1. EAP Emergency Responders

3 EAP ROLES AND RESPONSIBILITIES

Table 3-1 provides a summary of the EAP roles during an emergency event.

Entity	Role Description
Dynegy Emergency	ERT: Dynegy personnel responsible for EAP implementation, distribution, updates/maintenance, and
Response Team	training activities. The <u>ERT</u> is comprised of the following roles;
(ERT)	1. Dynegy Corporate: Dynegy corporate entity, committee, team, or position with relevant
	responsibility for a given generating station.
	2. Station Management Personnel: Personnel responsible for day-to-day operation and management of
	the Station.
	3. Dam Safety Manager: Personnel that is most knowledgeable about the design and technical
	operation of facilities at a given Station.
	4. EAP Coordinator: Personnel responsible for implementing the EAP and associated activities.
	<u>Emergency Event – EAP Responsibilities</u>
	1. Respond to emergencies at the Station.
	2. Verify and assess emergency conditions.
	3. Notify and coordinate as appropriate with participating emergency services disaster agencies or
	emergency management agencies (ESDA/EMA's), emergency responders, regulatory agencies, and all
	other entities involved or affected by this EAP.
	4. Take corrective action at the Station.
	5. Declare termination of emergencies at the Station.
Peoria County EMA	1. Receive Response Level reports from <u>Dynegy Corporate</u> through <u>EAP Coordinator</u> .
	2. Coordinate emergency response activities with local authorities: police, fire, and rescue, etc.
	3. Coordinate notification of public as necessary through established channels, which may include door-
	to-door contact.
	4. Coordinate notification activities to affected parties within inundation areas.
	5. Evaluate risk to areas beyond the inundation areas, communicate needs to the <u>Dynegy Corporate</u>
	and/or <i>EAP Coordinator</i> , and coordinate aid as appropriate.
	6. Responsible for declaring termination of an emergency condition off-site upon receiving notification
	of an emergency status termination from the <u>Dynegy Corporate</u> .
	7. If necessary, coordinate with <u>State ESDA/EMA</u> .
Local/County Police,	1. Receive alert status reports from the <u>ERT</u> or the Peoria County <u>EMA</u> .
Fire & Rescue	2. If necessary, notify Affected Parties and general public within inundation areas (see Section 7).
	3. Render assistance to Peoria County EMA, as necessary.
	4. Render assistance to <u>Dynegy Corporate</u> and <u>Station Management</u> , as necessary.

4 EAP RESPONSE

The 4-Step Incident Response Process is shown in Figure 2-1. The Decision Tree shown in Figure 2-3 provides a flowchart for the various elements of the response process. Upon reaching Step 4 of the response process (termination and follow-up), the EAP Coordinator is responsible for notifying the ESDA/EMA's that the condition of the dam/impoundment has been stabilized. The purpose of this section is to provide specific information that can be used during a response. This information is provided in the following tables:

- Table 4-1 provides guidance for determining the response level.
- Table 4-2 provides impoundment pool level trigger elevations.
- Table 4-3 lists emergency actions to be taken depending on the situation.

Event	Situation	Response Level
	Primary spillway flow is not causing active erosion and impoundment water surface elevation is below auxiliary spillway crest elevation (if equipped).	Level 0
	Impoundment water surface elevation is at or above auxiliary spillway crest elevation (if equipped). No active erosion caused by spillway flow.	Level 1
Spillway flow	Spillway flow actively causing minor erosion that is not threatening the control section or dam/impoundment stability.	Level 2
Spillway flow (see Table 4-2 for relevant elevations)	Spillway flow that could result in flooding of people downstream if the reservoir level continues to rise.	Level 2
	Abnormal operation of the spillway system due to blockage or damage that could lead to flooding.	Level 2
	Spillway flow actively eroding the soil around the spillway that is threatening the control section (e.g. undermining) or dam/impoundment stability.	Level 3
	Spillway flow that is flooding people downstream.	Level 3
Embankment	Impoundment water surface elevation at or below typical normal pool fluctuation elevation.	Level 0
Overtopping	Impoundment water surface elevation above typical high pool fluctuation elevation.	Level 1
(see Table 4-2 for relevant elevations)	Impoundment water surface elevation within 2 feet of the embankment crest elevation	Level 2
	Impoundment water surface elevation at or above embankment crest elevation.	Level 3
	New seepage areas in or near the dam/impoundment with clear flow.	Level 1
Seepage	New seepage areas with cloudy discharge or increasing flow rate.	Level 2
	Heavy seepage with active erosion, muddy flow, and/or sand boils.	Level 3
0.11.1	Observation of new sinkhole in impoundment area or on embankment.	Level 2
Sinkholes	Rapidly enlarging sinkhole and/or whirlpool in the impoundment.	Level 3

Table 4-1. Guidance for Determining the Response Level

Event	Situation	Response Level
	New cracks in the embankment greater than ¹ / ₄ inch wide without seepage.	Level 1
Embankment cracking	Any crack in the embankment with seepage.	Level 2
	Enlarging cracks with muddy seepage.	Level 3
	Visual signs of movement/slippage of the embankment slope.	Level 1
Embankment movement	Detectable active movement/slippage of the embankment slope or other related effects (tension cracking, bulges/heaves, etc.) that could threaten the integrity of the embankment.	Level 2
	Sudden or rapidly proceeding slides of the embankment slopes.	Level 3
Embankment	Instrumentation readings beyond historic normal.	Level 1
Monitoring Equipment	Instrumentation readings indicate the embankment is susceptible to failure.	Level 2
(piezometers, inclinometers, surface displacement mounts, etc.)	Instrumentation readings indicate embankment is at threshold of failure or is currently failing.	Level 3
	Measurable earthquake felt or reported on or within 100 miles of the impoundment.	Level 1
Earthquake or other event	Earthquake or other event resulting in visible damage to the impoundment or appurtenances.	Level 2
	Earthquake or other event resulting in uncontrolled release of water or materials from the impoundment.	Level 3
Security	Verified bomb threat or other physical threat that, if carried out, could result in damage to the impoundment.	Level 2
threat	Detonated bomb or other physical damage that has resulted in damage to the impoundment or appurtenances.	Level 3
	Damage to impoundment or appurtenance with no impact to the functioning of the impoundment.	Level 1
Sabotage/ vandalism	Modification to the impoundment or appurtenances that could adversely impact the functioning of the impoundment. This would include unauthorized operation of spillway facilities.	Level 2
	Damage to impoundment or appurtenances that has resulted in seepage flow.	Level 2
	Damage to impoundment or appurtenances that has resulted in uncontrolled water release.	Level 3

Table 4-1.	Guidance for Determining the Response Level
------------	---

Impoundment	Embankment Crest	Auxiliary spillway	Normal Pool Fluctuation	
Impoundment	Elevation	Crest Elevation	Typical	High
Ash Pond (north open water area)	461 ft.	Not Applicable	449.8 ft.	452 ft.
Ash Pond (south open water area)	461 ft.	Not Applicable	447.6 ft.	452 ft.

Table 4-2. Impoundment Trigger	[•] Elevations
--------------------------------	-------------------------

Notes: Elevations are in reference to NAVD88

All remaining values are GIS estimated.

Condition	Description of Condition	Action to be Taken	
High Water Level/ Large Spillway Release	See Table 4-1 and Table 4-2 for elevations and triggering water levels associated with the impoundment and spillway covered by this EAP.	 Assess cause of increased reservoir stage, especially during fair weather conditions. Determine Response Level. Make proper notifications as outlined in the Figure 2-2 Notification Flowchart. Perform additional tasks as determined through consultation with the ERT. Make notifications if condition worsens such that downstream flooding is imminent. Response Level 0: require enhanced surveillance 3 times per day Response Level 1: contact internal chain of command and external partners as necessary; inspect impoundment minimum 1 time per hour Response Level 2: contact internal chain of command; notify ESDA/EMA's and notify additional external partners (ESDA/EMA's notify affected parties) Response Level 3: contact internal chain of command; notify ESDA/EMA's and notify additional external partners (ESDA/EMA's notify affected parties) 	
Seepage	Localized new seepage or boil(s) observed along downstream face / toe of earthen embankment with muddy discharge and increasing but controllable discharge of water.	 Measure and record feature dimensions, approximate flow rate, and relative location to existing surface features. Take photos. Document location on a site plan and in inspection notes. Determine Response Level. Make proper notifications as outlined in the notification flowcharts in the Figure 2-2 Notification Flowchart. ERT (with Dam Safety Manager as lead) to determine mitigation actions. The following actions may apply: Place a ring of sand bags with a weir at the top towards the natural drainage path to monitor flow rate. If boil becomes too large to sand bag, place a blanket filter over the area using non-woven filter fabric and pea gravel. Attempt to contain flow in such a manner (without performing any excavations) that flow rates can be measured. Stockpile gravel and sand fill for later use, if necessary. Inspect the embankment and collect piezometer, water level and seepage flow data daily unless otherwise instructed by the Engineer. Record any changes of conditions. Carefully observe embankment for signs of depressions, seepage, sinkholes, cracking or movement. 	

Condition	Description of Condition	Action to be Taken
		 c) Maintain continuous monitoring of feature. Record measured flow rate and any changes of condition, including presence or absence of muddy discharge. 5. Make notifications as outlined in the lower portion of the Figure 2-2 Notification Flowchart if condition worsens such that failure is imminent.
Sabotage and Miscellaneous Other Issues	Criminal action with significant damage to embankment or structures where significant repairs are required and the integrity of the facility is compromised— condition appears stable with time.	 Contact law enforcement authorities and restrict all access (except emergency responders) to impoundment. Restrict traffic on embankment crest to essential emergency operations only. Determine Response Level. Make internal notifications as outlined in the flowcharts in the upper portion of the Figure 2-2 Notification Flowchart. In conjunction with the Dam Safety Manager, assess extent of damage and visually inspect entire embankment and ancillary structures for additional less obvious damage. Based on inspection results, confirm if extent of damage to various components of the impoundment warrants a revised Response Level and additional notifications. Perform additional tasks as directed by the ERT. Make notifications if conditions worsen.
Embankment Deformation	Cracks: New longitudinal (along the embankment) or transverse (across the embankment) cracks more than 6 inches deep or more than 3 inches wide or increasing with time. New concave cracks on or near the embankment crest associated with slope movement.	 Make notifications in conditions worsen. Measure and record feature dimensions, approximate flow rate, and relative location to existing surface features. Take photos. Document location on a site plan and in inspection notes. Restrict traffic on embankment crest to essential emergency operations only. Determine Response Level. Make notifications as outlined in the Figure 2-2 Notification Flowchart ERT (with Dam Safety Manager as lead) to determine mitigation actions. The following actions may apply: Place buttress fill against base of slope immediately below surface feature. Stock pile additional fill. Place sand bags as necessary around crack area to divert any storm water runoff from flowing into crack(s). As directed by the Dam Safety Manager, additional inspection and monitoring of the dam may be required. Items may include; inspect the dam on a schedule determined by the engineers; collect piezometer and water level data; and record any changes of condition. Carefully observe dam for signs of depressions, seepage, sinkholes, cracking or movement. Make notifications as outlined in the Figure 2-2 Notification Flowchart if conditions worsen such that failure is imminent.
Embankment Deformation (cont.)	Slides / Erosion: Deep slide / erosion (greater than 2 feet deep) on the embankment that may also extend beyond the embankment toe but does not encroach onto the embankment crest and appears stable with time.	 Measure and record feature dimensions, approximate flow rate, and relative location to existing surface features. Take photos. Document location on a site plan and in inspection report. Restrict traffic on embankment crest to essential emergency operations only. Determine the Response Level. Make notifications as outlined in the Figure 2-2 Notification Flowchart. ERT (with Dam Safety Manager as lead) to determine mitigation actions. Additional actions may include the following items. a) Place sand bags as necessary around slide area to divert any storm water runoff from flowing into slide(s). b) Increase inspections of the dam; collect piezometer and water level data; and record any changes of condition. During inspections,

Table 4-3. Step 3: Emergency Actions

Condition	Description of Condition	Action to be Taken
	Sinkholes: Small depression observed on the embankment or within 50 feet of the embankment toe that is less than 5 feet deep and 30 feet wide or which is increasing with time.	 carefully observe dam for signs of depressions, seepage, sinkholes, cracking or movement. Make notifications as outlined in the Figure 2-2 Notification Flowchart if conditions worsen such that failure is imminent. Slowly open drain gates to lower pool elevation. Measure and record feature dimensions, approximate flow rate, and relative location to existing surface features. Take photos. Document location on a site plan and in inspection notes. Restrict traffic on embankment crest to essential emergency operations only. Determine Response Level. Make notifications as outlined in the Figure 2-2 Notification Flowchart. ERT (with Dam Safety Manager as lead) to determine mitigation actions. Additional actions may include the following items: a) Backfill the depression with relatively clean earth fill (free of organic materials) generally even with surrounding grade and slightly mounded (6 to 12 inches higher) in the center in order to shed storm water away from the depression. Stock pile additional fill. b) Increase inspections of the dam; collect piezometer and water level data daily unless otherwise instructed by engineer; and record any changes of condition. Carefully observe dam for signs of depressions, seepage, sinkholes, cracking or movement. Make notifications as outlined in the Figure 2-2 Notification Flowchart if conditions worsen such that failure is imminent.
Gate Malfunction or Failure	Sluice gate damaged structurally (sabotage, debris, etc.) with uncontrolled release of water at a constant volume. Condition appears stable.	 Close any other gates, if open. Determine Response Level. Make notifications as outlined in the Figure 2-2 Notification Flowchart. Obtain instructions from the Engineer to determine if there are other methods to stop or slow down the flow of water. If conditions worsen such that failure is imminent, make notifications as outlined in the lower portion of the Figure 2-2 Notification Flowchart.

Table 4-3.	Step 3:	Emergency	Actions
------------	---------	-----------	---------

5 **PREPAREDNESS**

The intent of this section is to provide information that will be utilized during a response. Established emergency supplies and locations, suppliers, and equipment are provided in Table 5-1. Supplier contact information is listed in Table 5-2.

A coordination meeting shall be conducted annually between representatives of the Illinois Power Resources Generating, LLC and local emergency responders. This meeting may be in the form of a face-to-face meeting, tabletop exercise, or additional training regarding the EAP.

Item	On-site (Yes/No/Occasionally)	Remarks	
Flashlights	Yes	Contact Shift Supervisor for location(s).	
Generator	Yes	Contact Shift Supervisor for location(s). Contact National Rental, Inc. for additional emergency generators (see Table 5-2).	
Extension Cords	Yes	Contact Shift Supervisor for location(s).	
Fire extinguishers	Yes	Contact Shift Supervisor for location(s).	
Floodlights	Yes	Contact Shift Supervisor for location(s). Contact JM Industrial Supply for additional emergency lighting (see Table 5-2).	
Backhoe	Yes	Contact Shift Supervisor for location(s).	
Dozer	Yes	Contact Shift Supervisor for location(s).	
Dump Truck	No	Contact Shift Supervisor for resources and availability. Contact: • National Rental, Inc.	
Large Equipment (Rental – including excavating equipment, pumps, lighting)	No	Contact Shift Supervisor for resources and availability. Contact: • National Rental, Inc. • Sunbelt Rentals	
Pump and Hoses	Yes	Contact Shift Supervisor for location(s). Contact National Rental, Inc. and/or JM Industrial Supply for high capacity portable pumps (see Table 5-2).	
Sandbags and Sand	No	Contact: • Pekin Sand & Gravel, L.L.C. (see Table 5-2)	
Fill (Stone, aggregate, sand)	No	Contact: • Pekin Sand & Gravel, L.L.C. (see Table 5-2) • Westside Aggregates (see Table 5-2)	
Concrete/grout	No	Contact: • Roanoke Concrete Products (see Table 5-2) • United Ready-Mix Inc. (see Table 5-2)	
Geotextile Filter Fabric	Yes	Contact Shift Supervisor for location(s).	
Plastic Sheeting	Yes	Contact Shift Supervisor for location(s).	
Rope	Yes	Contact Shift Supervisor for location(s). Should be maintained in close proximity to any features that might require immediate access.	
Personal Flotation Devices	Yes	Contact Shift Supervisor for location(s).	

Table 5-1. Emergency Supplies and Equipment

Supplier	Distance from Site (miles)	Address	
National Rental, Inc.	4.4	706 S. 2 nd , Pekin, IL 61554	
Sunbelt Rentals	18.9	1601 N. Main Street, East Peoria, IL 61611	
JM Industrial Supply	6.7	2323 Lakeshore, Pekin, IL 61554	
Pekin Sand & Gravel, L.L.C.	7.9	13018 Manito Road, Pekin, IL 61554	
Westside Aggregates	8.8	2401 West Rhodora Avenue, West Peoria, IL	
Roanoke Concrete Products	5.5	1675 S. 2 nd Street, Pekin, IL 661544	
United Ready-Mix Inc.	6.0	2101 S. 2 nd Street, Pekin, IL 61544	

 Table 5-2.
 Supplier Addresses

6 FACILITY/IMPOUNDMENT DESCRIPTION

The impoundment included in this EAP is described as follows and illustrated in Figure 1-2. Table 6-1 contains additional geometric details for the impoundment.

The Edwards Power Station is located in Peoria County, Illinois approximately one half mile east of the intersection of U.S. Highway 24 and Illinois Route 9. The plant is located on the west bank of the Illinois River, just over one mile northwest of downtown Pekin, Illinois. The Ash Pond is located west of the power plant and Switch Yard and east of the Toledo Peoria & Western Railroad.

The Ash Pond is located on the west side of the Edwards Power Station. The impoundment is a perched pond with watershed area beyond the extent of the pond limited to small areas of the switchyard and Edwards Power Station. The surrounding areas will contribute an insignificant amount of runoff to the Ash Pond. According to the drainage construction plans for the Ash Pond primary spillway, flow from the Ash Pond discharges east to the Illinois River through a 36-inch diameter Corrugated Metal Pipe (CMP) located parallel to the property boundary, south of the Coal Yard. The primary spillway is equipped with a flapgate and has a sluice gate located at the embankment along the Illinois River. The Ash Pond has wet bottom storage areas on the north and south ends and does not have a dedicated auxiliary spillway. The earthen impoundment also services a railroad line.

Tuble 0 1. Station impoundment characteristics			
Feature/Parameter	Ash Pond		
Maximum Embankment Height	29 ft.		
Length of Dam	6,700 ft.		
Crest Width	14 ft.		
Crest Elevation	461 ft. **		
Reservoir Area at Top of Dam	89 acres		
Storage Capacity at Top of Dam	1,024 acre-ft.		
Primary Spillway Type	36-inch diameter CMP*		
Primary Spillway Crest Elevation	450.1*		
Storage Capacity at Primary Spillway Elevation	580		
Reservoir Area at Normal Water Surface Elevation (south wet bottom storage area)	23 acres		
Reservoir Area at Normal Water Surface Elevation (north wet bottom storage area)	5 acres		
Auxiliary spillway Type	N/A		
Auxiliary spillway Crest Elevation	N/A		

Table 6-1. Station Impoundment Characteristics

Notes:

*Kleinfelder. (May 2011). *Coal Ash Impoundment Site Assessment Final Report*. All remaining values are GIS estimated. **Elevation in reference to NAVD88

7 BREACH INUNDATION MAP AND POTENTIAL IMPACTS

An inundation map for Ash Pond potential breach scenarios is provided in this section. It is the Peoria County EMA's responsibility to keep a current list of affected parties/properties to contact in the case of emergencies that result in Response Level 2 or 3. This list should encompass all properties within and adjacent to the probable inundation extents shown in the provided map.

The methodology used to identify probable inundation extents for potential breach scenarios varied as a function of the impoundment size, location, surrounding topography, and surrounding structures/facilities/waterbodies. Probable Maximum Flood (PMF) and crest volume transfer analyses were completed for potential breach scenarios to the west and east embankments of the Ash Pond. The approximate inundation area is illustrated in Figure 7-1.

