

Prepared for
Dynegy Midwest Generation, LLC

Date
January 31, 2024

Project No.
1940103649-010

**2023 40 C.F.R. § 257 ANNUAL
GROUNDWATER MONITORING AND
CORRECTIVE ACTION REPORT
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS
CCR UNIT 804**

**2023 40 C.F.R. § 257 ANNUAL GROUNDWATER
MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT OLD WEST ASH POND**


Project name **Hennepin Power Plant Old West Ash Pond**
Project no. **1940103649-010**
Recipient **Dynegy Midwest Generation, LLC**
Document type **Annual Groundwater Monitoring and Corrective Action Report**
Version **FINAL**
Date **January 31, 2024**
Prepared by **Jeff R. Kampman**
Checked by **Lauren D. Cook**
Approved by **Eric J. Tlachac**
Description **Annual Report required by 40 C.F.R. § 257.90(e)**

Ramboll
234 W. Florida Street
Fifth Floor
Milwaukee, WI 53204
USA

T 414-837-3607
F 414-837-3608
<https://ramboll.com>



Jeff R. Kampman
Senior Project Scientist



Eric J. Tlachac, PE
Senior Managing Engineer

CONTENTS

EXECUTIVE SUMMARY	3
1. Introduction	4
2. Monitoring and Corrective Action Program Status	6
3. Key Actions Completed in 2023	7
4. Problems Encountered and Actions to Resolve the Problems	9
5. Key Activities Planned for 2024	10
6. References	11

TABLES (IN TEXT)

Table A	2023 Assessment Monitoring Program Summary
---------	--

TABLES (ATTACHED)

Table 1	Groundwater Elevation Data
Table 2	Analytical Results - Appendix III Parameters
Table 3	Analytical Results - Appendix IV Parameters
Table 4	Statistical Background Values
Table 5	Groundwater Protection Standards
Table 6	Determination of Statistically Significant Levels

FIGURES (ATTACHED)

Figure 1	Monitoring Well Location Map
Figure 2	Potentiometric Surface Map, February 28 and March 1, 2023
Figure 3	Potentiometric Surface Map, May 30, 2023
Figure 4	Potentiometric Surface Map, August 21 and 22, 2023
Figure 5	Potentiometric Surface Map, November 13, 2023

APPENDICES

Appendix A	Laboratory Reports and Field Data Sheets
Appendix B	Statistical Methodology for Determination of Background Values
Appendix C	Statistical Methodology for Determination of Statistically Significant Levels
Appendix D	Alternative Source Demonstrations

ACRONYMS AND ABBREVIATIONS

35 I.A.C.	Title 35 of the Illinois Administrative Code
40 C.F.R.	Title 40 of the Code of Federal Regulations
A5D	Quarter 3, 2022 Assessment Monitoring resampling event
A6	Quarter 1, 2023 Assessment Monitoring sampling event
A6R	Quarter 2, 2023 Assessment Monitoring resampling event
A6D	Quarter 3, 2023 Assessment Monitoring sampling event
A6DR	Quarter 4, 2023 Assessment Monitoring resampling event
ASD	Alternative Source Demonstration
CCR	coal combustion residuals
CMA	Corrective Measures Assessment
GWPS	groundwater protection standard
HPP	Hennepin Power Plant
IEPA	Illinois Environmental Protection Agency
NA	not applicable
OBG	OBG, Part of Ramboll
OWAP	Old West Ash Pond
Ramboll	Ramboll Americas Engineering Solutions, Inc.
SAP	Sampling and Analysis Plan
SSI	statistically significant increase
SSL	statistically significant level
TBD	to be determined

EXECUTIVE SUMMARY

This report has been prepared to provide the information required by Title 40 of the Code of Federal Regulations (40 C.F.R.) § 257.90(e) for the Old West Ash Pond (OWAP) located at the Hennepin Power Plant (HPP) near Hennepin, Illinois.

Groundwater is being monitored at the OWAP in accordance with the Assessment Monitoring Program requirements specified in 40 C.F.R. § 257.95. Assessment Monitoring was initiated at the OWAP on April 9, 2018.

As discussed in **Section 3** of this annual report, the monitoring system was updated in 2023 to use the same monitoring system developed for compliance with Title 35 of the Illinois Administrative Code (35 I.A.C.) § 845, which was submitted to the Illinois Environmental Protection Agency (IEPA) via an operating permit application.

The following statistically significant levels (SSLs) of 40 C.F.R. § 257 Appendix IV parameters above groundwater protection standards (GWPSs) were reported in 2023:

- Arsenic at wells 21R and 51
- Cadmium at well 22
- Lithium at well 22

Alternate Source Demonstrations (ASDs) were completed in 2023 for the cadmium SSLs referenced above.

As required by 40 C.F.R. § 257.95(g)(3)(i), a Corrective Measures Assessment (CMA) (OBG, Part of Ramboll [OBG], 2019) following the requirements of 40 C.F.R. § 257.96 was initiated on May 8, 2019 and completed on September 5, 2019 to address SSLs for total arsenic, total lithium, and total molybdenum. The CMA evaluated closure in place with a geomembrane cover system in accordance with the Closure and Post Closure Care Plan submitted to IEPA in January 2018. IEPA approved the Closure and Post Closure Care Plan on June 19, 2018. Closure construction began in August of 2019 and was completed in November of 2020.

The OWAP is also regulated under 35 I.A.C. § 845. Quarterly groundwater sampling for 35 I.A.C. § 845 compliance evaluation was initiated at AP2 during Quarter 2, 2023. Exceedances of GWPSs established under 35 I.A.C. § 845 were determined and require corrective action through a permitting process administered by IEPA. Therefore, remedy selection will take into consideration compliance with both 40 C.F.R. § 257 and 35 I.A.C. § 845.

In accordance with 40 C.F.R. § 257.97, remedy selection is to be completed as soon as feasible following completion of the CMA. As required by 35 I.A.C. § 845.670, a corrective action plan that identifies the selected remedy must be submitted to IEPA within one year after completing the CMA completed in accordance with 35 I.A.C. § 845.660. On December 10, 2023, Ramboll initiated a CMA for the OWAP in accordance with 35 I.A.C. § 845.660. It is anticipated that a corrective action plan will be submitted in 2025 that meets the requirements of both 40 C.F.R. § 257 and 35 I.A.C. § 845.

1. INTRODUCTION

This report has been prepared by Ramboll Americas Engineering Solutions, Inc. (Ramboll) on behalf of Dynegy Midwest Generation, LLC, to provide the information required by 40 C.F.R. § 257.90(e) for the OWAP located at the HPP near Hennepin, Illinois.

In accordance with 40 C.F.R. § 257.90(e), the owner or operator of a coal combustion residuals (CCR) unit must prepare an Annual Groundwater Monitoring and Corrective Action Report for the preceding calendar year that documents the status of the Groundwater Monitoring and Corrective Action Program for the CCR unit (**Section 2**), summarizes key actions completed (**Section 3**), describes any problems encountered and actions to resolve the problems (**Section 4**), and projects key activities for the upcoming year (**Section 5**). At a minimum, the annual report must contain the following information, to the extent available:

1. A map, aerial image, or diagram showing the CCR unit and all background (or upgradient) and downgradient monitoring wells, to include the well identification numbers, that are part of the groundwater monitoring program for the CCR unit (**Figure 1**).
2. Identification of any monitoring wells that were installed or decommissioned during the preceding year, along with a narrative description of why those actions were taken (**Section 3**, paragraph 1).
3. In addition to all the monitoring data obtained under § 257.90 through 257.98, a summary including the number of groundwater samples that were collected for analysis for each background and downgradient well, the dates the samples were collected, and whether the sample was required by the Detection Monitoring or Assessment Monitoring Programs (**Section 3, Table A**).
4. A narrative discussion of any transition between monitoring programs (*e.g.*, the date and circumstances for transitioning from Detection Monitoring to Assessment Monitoring in addition to identifying the constituent(s) detected at a statistically significant increase relative to background levels) (**Section 3**).
5. Other information required to be included in the annual report as specified in § 257.90 through 257.98.
6. A section at the beginning of the annual report that provides an overview of the current status of groundwater monitoring and corrective action programs for the CCR unit (see **Executive Summary**). At a minimum, the summary must specify all of the following:
 - i. At the start of the current annual reporting period, whether the CCR unit was operating under the Detection Monitoring Program in § 257.94 or the Assessment Monitoring Program in § 257.95.
 - ii. At the end of the current annual reporting period, whether the CCR unit was operating under the Detection Monitoring Program in § 257.94 or the Assessment Monitoring Program in § 257.95.
 - iii. If it was determined that there was a statistically significant increase over background for one or more constituents listed in Appendix III of § 257 pursuant to § 257.94(e):
 - A. Identify those constituents listed in Appendix III of § 257 and the names of the monitoring wells associated with such an increase.

- B. Provide the date when the Assessment Monitoring Program was initiated for the CCR unit.
- iv. If it was determined that there was a statistically significant level above the groundwater protection standard for one or more constituents listed in Appendix IV of § 257 pursuant to § 257.95(g) include all of the following:
 - A. Identify those constituents listed in Appendix IV of § 257 and the names of the monitoring wells associated with such an increase.
 - B. Provide the date when the assessment of corrective measures was initiated for the CCR unit.
 - C. Provide the date when the public meeting was held for the assessment of corrective measures for the CCR unit.
 - D. Provide the date when the assessment of corrective measures was completed for the CCR unit.
- v. Whether a remedy was selected pursuant to § 257.97 during the current annual reporting period, and if so, the date of remedy selection.
- vi. Whether remedial activities were initiated or are ongoing pursuant to § 257.98 during the current annual reporting period.

This report provides the required information for the OWAP for calendar year 2023.

2. MONITORING AND CORRECTIVE ACTION PROGRAM STATUS

Groundwater is being monitored at the OWAP in accordance with the Assessment Monitoring Program requirements specified in 40 C.F.R. § 257.95. Assessment monitoring was initiated on April 9, 2018. SSLs of arsenic, lithium, and molybdenum were determined for the OWAP and alternative source evaluations were inconclusive for these SSLs. In accordance with 40 C.F.R. § 257.95(g)(5), a CMA following the requirements of 40 C.F.R. § 257.96 was initiated on May 8, 2019 and completed on September 5, 2019. A public meeting was held on December 17, 2019 at the St. Margaret's Hospital Presentation Room in Spring Valley, Illinois to discuss the results of the CMA in accordance with 40 C.F.R. § 257.96(e). The CMA evaluated closure in place with a geomembrane cover system in accordance with the Closure and Post Closure Care Plan submitted to the IEPA in January 2018. IEPA approved the Closure and Post Closure Care Plan on June 19, 2018. Closure construction began in August of 2019 and was completed in November of 2020.

Cadmium SSLs were subsequently determined for the OWAP in 2022 and ASDs have been completed for these SSLs.

The OWAP is also regulated under 35 I.A.C. § 845. Groundwater sampling for 35 I.A.C. § 845 compliance was initiated at the OWAP during Quarter 2, 2023. Exceedances of GWPSs established under 35 I.A.C. § 845 were determined and require corrective action through a permitting process administered by IEPA. Therefore, remedy selection will take into consideration compliance with both 40 C.F.R. § 257 and 35 I.A.C. § 845.

In accordance with 40 C.F.R. § 257.97, remedy selection is to be completed as soon as feasible following completion of the CMA. As required by 35 I.A.C. § 845.670, a corrective action plan that identifies the selected remedy must be submitted to IEPA within one year after completing the CMA completed in accordance with 35 I.A.C. § 845.660. It is anticipated that a corrective action plan will be submitted in 2025 that meets the requirements of both 40 C.F.R. § 257 and 35 I.A.C. § 845.

The OWAP remains in the Assessment Monitoring Program in accordance with 40 C.F.R. § 257.96(b).

3. KEY ACTIONS COMPLETED IN 2023

A summary of the samples collected from background and compliance monitoring wells in 2023 under the Assessment Monitoring Program is included in **Table A** on the following page. The groundwater monitoring system, including the CCR unit and all background and compliance monitoring wells, is presented in **Figure 1**. Beginning in 2023, the monitoring system was updated to be consistent with that proposed for compliance with 35 I.A.C. § 845, which includes all of the monitoring wells used in the 2022 40 C.F.R. § 257 monitoring system (Ramboll, 2022a). No wells were installed or decommissioned in 2023 (the wells added from the 35 I.A.C. § 845 monitoring system were installed prior to 2023).

One groundwater sample was collected from each background and compliance well during each monitoring event. The OWAP is also regulated under 35 I.A.C. § 845, which requires quarterly monitoring. The groundwater monitoring systems for both programs (35 I.A.C. § 845 and 40 C.F.R. § 257) are identical, so all available data from the four quarterly monitoring events in 2023 are included in this report. All samples were collected and analyzed in accordance with the Multi-Site Sampling and Analysis Plan (SAP) (Ramboll, 2023). Data collected in accordance with 35 I.A.C. § 845 was included for statistical calculations performed in accordance with 40 C.F.R. § 257.95(d)(1); however, SSLs are reported semiannually per 40 C.F.R. § 257.

Potentiometric surfaces for the quarterly sampling events are included in **Figures 2 through 5**. All monitoring data and analytical results obtained under 40 C.F.R. § 257.90 through 257.98 and 35 I.A.C. § 845 in 2023 are presented in **Tables 1 through 3**. All associated laboratory reports and field data sheets are included in **Appendix A**. Analytical data received after December 31, 2023 will be reported in the 2024 Annual Groundwater Monitoring and Corrective Action Report.

Analytical data were evaluated in accordance with the Multi-Site Statistical Analysis Plan (Ramboll, 2022b), the Multi-Site Quality Assurance Project Plan (Ramboll, 2022c), and the Multi-Site Data Management Plan (Ramboll, 2022d) to determine any SSLs of Appendix IV parameters over GWPSs and statistically significant increases (SSIs) of Appendix III parameters greater than background values. SSL notifications were completed in accordance with 40 C.F.R. § 257.95(g). SSIs are highlighted in **Table 2**. Statistical background values are provided in **Table 4** and GWPSs in **Table 5**. A flow chart showing the statistical methodology for determination of background values is included as **Appendix B**. A summary of the determination of SSLs is included in **Table 6**. A flow chart showing the statistical methodology for determination of SSLs is included as **Appendix C**.

Potential alternative sources were evaluated as outlined in the 40 C.F.R. § 257.95(g)(3)(ii). ASDs were completed in 2023 for the cadmium SSLs. The dates the ASDs were completed are provided in **Table A**. The ASDs were certified by a qualified professional engineer and are included in **Appendix D**.

A CMA was completed in 2019 to address arsenic, lithium, and molybdenum SSLs. The OWAP remains in the Assessment Monitoring Program.

Table A. 2023 Assessment Monitoring Program Summary

Event ID	Sampling Dates ^{1, 2, 3}	Analytical Data Receipt Date ^{4,5}	SSL(s) Determination Date	SSL(s)	ASD Completion Date
A5D ⁶	September 13 - 14, 2022	October 31, 2022	January 31, 2023	Arsenic at well 21R and 51; Cadmium and Lithium at well 22	May 1, 2023
A6	February 28 – March 2, 2023	April 14, 2023	July 13, 2023	Arsenic at well 21R and 51; Cadmium at well 22	October 11, 2023
A6R	May 31 – June 1, 2023	July 13, 2023	NA	NA	NA
A6D	August 22 - 28, 2023	November 16, 2023	February 14, 2024	TBD	NA
A6DR	November 14 - 15, 2023	TBD	NA	NA	NA

Notes:

ASD: Alternative Source Demonstration

NA: not applicable

SSL: Statistically Significant Level

TBD: to be determined in 2024

¹ All samples were analyzed for Appendix III parameters listed in 40 C.F.R. § 257.94(e) and Appendix IV parameters listed in 40 C.F.R. § 257.95(g).

² The following background wells were sampled for each event: 32 and 34

³ The following compliance wells were sampled for each event: 21R, 22, 22D, 23, 27, 35, 49, 50, and 51

⁴ Data collected in accordance with 35 I.A.C. § 845 was included for statistical calculations performed in accordance with 40 C.F.R. § 257.95(d)(1); however, SSLs are reported semiannually per 40 C.F.R. § 257.

⁵ Analytical data received after December 31, 2023 will be reported in the 2024 Annual Groundwater Monitoring and Corrective Action Report.

⁶ Laboratory reports and associated analytical data tables were included in the 2022 Annual Groundwater Monitoring and Corrective Action Report.

4. PROBLEMS ENCOUNTERED AND ACTIONS TO RESOLVE THE PROBLEMS

No problems were encountered with the groundwater monitoring program during 2023. Groundwater samples were collected and analyzed in accordance with the SAP and all data were accepted.

5. KEY ACTIVITIES PLANNED FOR 2024

The following key activities are planned for 2024:

- Continuation of the Assessment Monitoring Program with semiannual sampling for reporting purposes scheduled for the first and third quarters of 2024 (and sampling for 35 I.A.C. § 845 scheduled for the second and fourth quarters).
- Complete evaluation of analytical data from the compliance wells to determine whether an SSL of Appendix IV parameters above GWPSs has occurred.
- If an SSL is identified, potential alternative sources (*i.e.*, a source other than the CCR unit caused the SSL or that the SSL resulted from error in sampling, analysis, statistical evaluation, or natural variation in groundwater quality) will be evaluated.
 - If an alternative source is identified to be the cause of the SSL, a written demonstration will be completed within 90 days of SSL determination and included in the 2024 Annual Groundwater Monitoring and Corrective Action Report.
- If an alternative source(s) is not identified to be the cause of the SSL, the applicable requirements of 40 C.F.R. § 257.94 through 257.98 (*e.g.*, assessment of corrective measures) as may apply in 2024 will be met, including associated recordkeeping/notifications required by 40 C.F.R. § 257.105 through 257.108.
- Remedy selection will continue considering compliance with both 40 C.F.R. § 257 and 35 I.A.C. § 845; semiannual progress reports required by 40 C.F.R. § 257.97(a) will be completed and posted to the publicly accessible website as required by 40 C.F.R. § 257.107(h)(9).

6. REFERENCES

Code of Federal Regulations, Title 40, Chapter I, Subchapter I, Part 257, Subpart D, Standards for the Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments, effective April 17, 2015. Accessed from URL <https://www.ecfr.gov/current/title-40/chapter-I/subchapter-I/part-257/subpart-D#page-top>

OBG, Part of Ramboll (OBG), 2019. Corrective Measures Assessment, Old West Ash Pond (Pond No. 1 and Pond No. 3) and Polishing Pond, Hennepin Power Station, 13498 East 800th Street, Hennepin, Illinois, Dynegy Midwest Generation, LLC, September 5, 2019.

Ramboll Americas Engineering Solutions, Inc. (Ramboll), 2022a. 40 C.F.R. § 257 Groundwater Monitoring Plan, Ash Pond No. 2, Hennepin Power Plant, Hennepin, Illinois. December 28, 2022.

Ramboll Americas Engineering Solutions, Inc. (Ramboll), 2022b. Multi-Site Statistical Analysis Plan, 40 C.F.R. § 257. December 28, 2022.

Ramboll Americas Engineering Solutions, Inc. (Ramboll), 2022c. Multi-Site Quality Assurance Project Plan. December 28, 2022.

Ramboll Americas Engineering Solutions, Inc. (Ramboll), 2022d. Multi-Site Data Management Plan. December 28, 2022.

Ramboll Americas Engineering Solutions, Inc. (Ramboll), 2023. Multi-Site Sampling and Analysis Plan, Revision 1. October 10, 2023.

TABLES

TABLE 1
GROUNDWATER ELEVATION DATA
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	Well Type	Monitored Unit	Date	Depth to Groundwater (feet BMP)	Groundwater Elevation (feet NAVD88)
21R	Compliance	UA	02/28/2023	5.25	446.80
21R	Compliance	UA	04/30/2023	5.16	446.88
21R	Compliance	UA	05/30/2023	5.92	446.13
21R	Compliance	UA	06/21/2023	6.36	445.68
21R	Compliance	UA	07/21/2023	6.11	445.93
21R	Compliance	UA	08/21/2023	6.36	445.68
21R	Compliance	UA	09/30/2023	6.52	445.53
21R	Compliance	UA	10/31/2023	5.67	446.38
21R	Compliance	UA	11/13/2023	5.77	446.28
21R	Compliance	UA	12/21/2023	6.18	445.87
22	Compliance	UA	02/28/2023	17.30	447.15
22	Compliance	UA	04/30/2023	17.85	446.59
22	Compliance	UA	05/30/2023	18.45	446.00
22	Compliance	UA	06/21/2023	18.73	445.71
22	Compliance	UA	07/21/2023	18.52	445.92
22	Compliance	UA	08/21/2023	18.68	445.76
22	Compliance	UA	09/30/2023	19.54	444.91
22	Compliance	UA	10/31/2023	18.87	445.58
22	Compliance	UA	11/13/2023	18.43	446.02
22	Compliance	UA	12/21/2023	18.84	445.61
22D	Compliance	UA	02/28/2023	18.45	446.98
22D	Compliance	UA	04/30/2023	18.43	446.99
22D	Compliance	UA	05/30/2023	19.10	446.33
22D	Compliance	UA	06/21/2023	19.42	446.00
22D	Compliance	UA	07/21/2023	19.19	446.23
22D	Compliance	UA	08/21/2023	19.40	446.02
22D	Compliance	UA	10/31/2023	18.90	446.53
22D	Compliance	UA	11/13/2023	22.10	443.33
22D	Compliance	UA	12/21/2023	19.54	445.89
23	Compliance	UA	02/28/2023	17.30	446.09
23	Compliance	UA	04/30/2023	15.90	447.48
23	Compliance	UA	05/30/2023	16.72	446.67
23	Compliance	UA	06/21/2023	17.08	446.30
23	Compliance	UA	07/21/2023	16.83	446.55
23	Compliance	UA	08/21/2023	17.08	446.30
23	Compliance	UA	09/30/2023	17.38	446.01
23	Compliance	UA	10/31/2023	16.45	446.94
23	Compliance	UA	11/13/2023	17.64	445.75
23	Compliance	UA	12/21/2023	17.18	446.21
27	Compliance	UA	02/28/2023	3.90	446.68
27	Compliance	UA	04/30/2023	3.33	447.24
27	Compliance	UA	05/30/2023	4.14	446.44
27	Compliance	UA	06/21/2023	4.53	446.04
27	Compliance	UA	07/21/2023	4.31	446.27
27	Compliance	UA	08/21/2023	4.56	446.02
27	Compliance	UA	10/31/2023	3.72	446.86

TABLE 1
GROUNDWATER ELEVATION DATA
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	Well Type	Monitored Unit	Date	Depth to Groundwater (feet BMP)	Groundwater Elevation (feet NAVD88)
27	Compliance	UA	11/13/2023	3.91	446.67
27	Compliance	UA	12/21/2023	4.38	446.20
32	Background	UA	02/28/2023	4.62	446.76
32	Background	UA	04/30/2023	4.36	447.02
32	Background	UA	05/30/2023	5.22	446.16
32	Background	UA	06/21/2023	5.63	445.75
32	Background	UA	07/21/2023	5.42	445.96
32	Background	UA	08/21/2023	5.60	445.78
32	Background	UA	09/30/2023	5.74	445.64
32	Background	UA	10/31/2023	4.62	446.76
32	Background	UA	11/13/2023	4.79	446.59
32	Background	UA	12/21/2023	5.20	446.18
34	Background	UA	02/28/2023	2.45	447.11
34	Background	UA	04/30/2023	7.69	441.86
34	Background	UA	05/30/2023	8.66	440.90
34	Background	UA	06/21/2023	9.16	440.39
34	Background	UA	08/25/2023	NA	[440.58]
34	Background	UA	08/25/2023	NA	[440.58]
34	Background	UA	10/31/2023	7.74	441.82
34	Background	UA	11/13/2023	8.37	441.19
34	Background	UA	12/21/2023	7.76	441.80
35	Compliance	UA	02/28/2023	8.20	446.63
35	Compliance	UA	04/30/2023	7.69	447.13
35	Compliance	UA	05/30/2023	8.30	446.53
35	Compliance	UA	06/21/2023	8.84	445.98
35	Compliance	UA	07/21/2023	8.58	446.24
35	Compliance	UA	08/21/2023	8.87	445.96
35	Compliance	UA	09/30/2023	9.05	445.78
35	Compliance	UA	10/31/2023	7.97	446.86
35	Compliance	UA	11/13/2023	8.15	446.68
35	Compliance	UA	12/21/2023	8.70	446.13
49	Compliance	UA	02/28/2023	21.30	446.87
49	Compliance	UA	05/30/2023	21.54	446.63
49	Compliance	UA	08/25/2023	[19.65]	[448.52]
49	Compliance	UA	08/25/2023	[19.65]	[448.52]
49	Compliance	UA	09/30/2023	22.16	446.01
49	Compliance	UA	10/31/2023	21.33	446.84
49	Compliance	UA	11/13/2023	21.49	446.68
49	Compliance	UA	12/21/2023	22.02	446.15
50	Compliance	UA	02/28/2023	16.74	447.20
50	Compliance	UA	05/30/2023	18.25	445.69
50	Compliance	UA	10/31/2023	18.06	445.88
50	Compliance	UA	11/13/2023	18.24	445.70
50	Compliance	UA	12/21/2023	18.61	445.33
51	Compliance	UA	02/28/2023	17.91	446.89
51	Compliance	UA	04/30/2023	17.74	447.05

TABLE 1
GROUNDWATER ELEVATION DATA
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	Well Type	Monitored Unit	Date	Depth to Groundwater (feet BMP)	Groundwater Elevation (feet NAVD88)
51	Compliance	UA	05/30/2023	18.50	446.30
51	Compliance	UA	06/21/2023	18.94	445.85
51	Compliance	UA	07/21/2023	18.69	446.10
51	Compliance	UA	08/21/2023	18.92	445.87
51	Compliance	UA	09/30/2023	19.17	445.63
51	Compliance	UA	10/31/2023	18.22	446.58
51	Compliance	UA	11/13/2023	18.59	446.21
51	Compliance	UA	12/21/2023	18.84	445.96

Notes:
Only wells with groundwater elevations measured are included.
BMP = below measuring point
Bracketing [] indicates that the measurement was obtained outside of the episodic depth to groundwater measurements time frame.
NA = not available/not applicable
NAVD88 = North American Vertical Datum of 1988
Monitored Unit Abbreviations:
 UA = uppermost aquifer

TABLE 2
ANALYTICAL RESULTS - APPENDIX III PARAMETERS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Well Type	Date	Event ID	Parameter	Unit	Result	Background	SSI Type
32	UA	Background	02/28/2023	A6	Boron, total	mg/L	0.199	NA	NA
32	UA	Background	05/31/2023	A6R	Boron, total	mg/L	0.143	NA	NA
32	UA	Background	08/22/2023	A6D	Boron, total	mg/L	0.140	NA	NA
32	UA	Background	11/14/2023	A6DR	Boron, total	mg/L	0.180 J+	NA	NA
32	UA	Background	02/28/2023	A6	Calcium, total	mg/L	122	NA	NA
32	UA	Background	05/31/2023	A6R	Calcium, total	mg/L	102	NA	NA
32	UA	Background	08/22/2023	A6D	Calcium, total	mg/L	100	NA	NA
32	UA	Background	11/14/2023	A6DR	Calcium, total	mg/L	110	NA	NA
32	UA	Background	02/28/2023	A6	Chloride, total	mg/L	83.0	NA	NA
32	UA	Background	05/31/2023	A6R	Chloride, total	mg/L	70.0	NA	NA
32	UA	Background	08/22/2023	A6D	Chloride, total	mg/L	68.0	NA	NA
32	UA	Background	11/14/2023	A6DR	Chloride, total	mg/L	67.0	NA	NA
32	UA	Background	02/28/2023	A6	Fluoride, total	mg/L	0.130	NA	NA
32	UA	Background	05/31/2023	A6R	Fluoride, total	mg/L	0.100	NA	NA
32	UA	Background	08/22/2023	A6D	Fluoride, total	mg/L	0.22 J	NA	NA
32	UA	Background	11/14/2023	A6DR	Fluoride, total	mg/L	0.130	NA	NA
32	UA	Background	02/28/2023	A6	pH (field)	SU	7.0	NA	NA
32	UA	Background	05/31/2023	A6R	pH (field)	SU	6.9	NA	NA
32	UA	Background	08/22/2023	A6D	pH (field)	SU	7.1	NA	NA
32	UA	Background	11/14/2023	A6DR	pH (field)	SU	7.2	NA	NA
32	UA	Background	02/28/2023	A6	Sulfate, total	mg/L	82.0	NA	NA
32	UA	Background	05/31/2023	A6R	Sulfate, total	mg/L	63.0	NA	NA
32	UA	Background	08/22/2023	A6D	Sulfate, total	mg/L	66.0	NA	NA
32	UA	Background	11/14/2023	A6DR	Sulfate, total	mg/L	65.0	NA	NA
32	UA	Background	02/28/2023	A6	Total Dissolved Solids	mg/L	564	NA	NA
32	UA	Background	05/31/2023	A6R	Total Dissolved Solids	mg/L	550	NA	NA
32	UA	Background	08/22/2023	A6D	Total Dissolved Solids	mg/L	570	NA	NA
32	UA	Background	11/14/2023	A6DR	Total Dissolved Solids	mg/L	600	NA	NA
34	UA	Background	02/28/2023	A6	Boron, total	mg/L	0.206	NA	NA
34	UA	Background	05/31/2023	A6R	Boron, total	mg/L	0.125	NA	NA
34	UA	Background	08/25/2023	A6D	Boron, total	mg/L	0.0750	NA	NA
34	UA	Background	11/14/2023	A6DR	Boron, total	mg/L	0.110 J+	NA	NA
34	UA	Background	02/28/2023	A6	Calcium, total	mg/L	184	NA	NA
34	UA	Background	05/31/2023	A6R	Calcium, total	mg/L	149	NA	NA
34	UA	Background	08/25/2023	A6D	Calcium, total	mg/L	150	NA	NA
34	UA	Background	11/14/2023	A6DR	Calcium, total	mg/L	150	NA	NA
34	UA	Background	02/28/2023	A6	Chloride, total	mg/L	80.0	NA	NA
34	UA	Background	05/31/2023	A6R	Chloride, total	mg/L	71.0	NA	NA
34	UA	Background	08/25/2023	A6D	Chloride, total	mg/L	69.0	NA	NA
34	UA	Background	11/14/2023	A6DR	Chloride, total	mg/L	67.0	NA	NA
34	UA	Background	02/28/2023	A6	Fluoride, total	mg/L	0.160	NA	NA
34	UA	Background	05/31/2023	A6R	Fluoride, total	mg/L	0.120	NA	NA
34	UA	Background	08/25/2023	A6D	Fluoride, total	mg/L	0.19 J	NA	NA
34	UA	Background	11/14/2023	A6DR	Fluoride, total	mg/L	0.150	NA	NA
34	UA	Background	02/28/2023	A6	pH (field)	SU	6.9	NA	NA
34	UA	Background	05/31/2023	A6R	pH (field)	SU	6.9	NA	NA

TABLE 2
ANALYTICAL RESULTS - APPENDIX III PARAMETERS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Well Type	Date	Event ID	Parameter	Unit	Result	Background	SSI Type
34	UA	Background	08/25/2023	A6D	pH (field)	SU	7.1	NA	NA
34	UA	Background	11/14/2023	A6DR	pH (field)	SU	7.2	NA	NA
34	UA	Background	02/28/2023	A6	Sulfate, total	mg/L	48.0	NA	NA
34	UA	Background	05/31/2023	A6R	Sulfate, total	mg/L	49.0	NA	NA
34	UA	Background	08/25/2023	A6D	Sulfate, total	mg/L	46.0	NA	NA
34	UA	Background	11/14/2023	A6DR	Sulfate, total	mg/L	49.0	NA	NA
34	UA	Background	02/28/2023	A6	Total Dissolved Solids	mg/L	685	NA	NA
34	UA	Background	05/31/2023	A6R	Total Dissolved Solids	mg/L	845	NA	NA
34	UA	Background	08/25/2023	A6D	Total Dissolved Solids	mg/L	760	NA	NA
34	UA	Background	11/14/2023	A6DR	Total Dissolved Solids	mg/L	700	NA	NA
21R	UA	Compliance	02/28/2023	A6	Boron, total	mg/L	3.28	0.199	Confirmed
21R	UA	Compliance	05/31/2023	A6R	Boron, total	mg/L	2.32	0.199	Confirmed
21R	UA	Compliance	08/22/2023	A6D	Boron, total	mg/L	1.70	0.199	TBD
21R	UA	Compliance	11/14/2023	A6DR	Boron, total	mg/L	2.10	0.199	TBD
21R	UA	Compliance	02/28/2023	A6	Calcium, total	mg/L	147	170	No Exceedance
21R	UA	Compliance	05/31/2023	A6R	Calcium, total	mg/L	121	170	No Exceedance
21R	UA	Compliance	08/22/2023	A6D	Calcium, total	mg/L	120	170	TBD
21R	UA	Compliance	11/14/2023	A6DR	Calcium, total	mg/L	120	170	TBD
21R	UA	Compliance	02/28/2023	A6	Chloride, total	mg/L	108	108	No Exceedance
21R	UA	Compliance	05/31/2023	A6R	Chloride, total	mg/L	103	108	No Exceedance
21R	UA	Compliance	08/22/2023	A6D	Chloride, total	mg/L	95.0	108	TBD
21R	UA	Compliance	11/14/2023	A6DR	Chloride, total	mg/L	89.0	108	TBD
21R	UA	Compliance	02/28/2023	A6	Fluoride, total	mg/L	0.150	0.170	No Exceedance
21R	UA	Compliance	05/31/2023	A6R	Fluoride, total	mg/L	0.120	0.170	No Exceedance
21R	UA	Compliance	08/22/2023	A6D	Fluoride, total	mg/L	0.23 J	0.170	TBD
21R	UA	Compliance	11/14/2023	A6DR	Fluoride, total	mg/L	0.140	0.170	TBD
21R	UA	Compliance	02/28/2023	A6	pH (field)	SU	7.3	6.8/7.4	No Exceedance
21R	UA	Compliance	05/31/2023	A6R	pH (field)	SU	7.4	6.8/7.4	No Exceedance
21R	UA	Compliance	08/22/2023	A6D	pH (field)	SU	7.5	6.8/7.4	TBD
21R	UA	Compliance	11/14/2023	A6DR	pH (field)	SU	7.7	6.8/7.4	TBD
21R	UA	Compliance	02/28/2023	A6	Sulfate, total	mg/L	105	117	No Exceedance
21R	UA	Compliance	05/31/2023	A6R	Sulfate, total	mg/L	91.0	117	No Exceedance
21R	UA	Compliance	08/22/2023	A6D	Sulfate, total	mg/L	94.0	117	TBD
21R	UA	Compliance	11/14/2023	A6DR	Sulfate, total	mg/L	81.0	117	TBD
21R	UA	Compliance	02/28/2023	A6	Total Dissolved Solids	mg/L	678	830	No Exceedance
21R	UA	Compliance	05/31/2023	A6R	Total Dissolved Solids	mg/L	695	830	No Exceedance
21R	UA	Compliance	08/22/2023	A6D	Total Dissolved Solids	mg/L	730	830	TBD
21R	UA	Compliance	11/14/2023	A6DR	Total Dissolved Solids	mg/L	700	830	TBD
22	UA	Compliance	02/28/2023	A6	Boron, total	mg/L	4.51	0.199	Confirmed
22	UA	Compliance	05/31/2023	A6R	Boron, total	mg/L	3.44	0.199	Confirmed
22	UA	Compliance	08/25/2023	A6D	Boron, total	mg/L	0.130	0.199	TBD
22	UA	Compliance	11/15/2023	A6DR	Boron, total	mg/L	3.20	0.199	TBD
22	UA	Compliance	02/28/2023	A6	Calcium, total	mg/L	102	170	No Exceedance
22	UA	Compliance	05/31/2023	A6R	Calcium, total	mg/L	87.1	170	No Exceedance
22	UA	Compliance	08/25/2023	A6D	Calcium, total	mg/L	23.0	170	TBD
22	UA	Compliance	11/15/2023	A6DR	Calcium, total	mg/L	87.0	170	TBD

TABLE 2
ANALYTICAL RESULTS - APPENDIX III PARAMETERS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Well Type	Date	Event ID	Parameter	Unit	Result	Background	SSI Type
22	UA	Compliance	02/28/2023	A6	Chloride, total	mg/L	100	108	No Exceedance
22	UA	Compliance	05/31/2023	A6R	Chloride, total	mg/L	97.0	108	No Exceedance
22	UA	Compliance	08/25/2023	A6D	Chloride, total	mg/L	89.0	108	TBD
22	UA	Compliance	11/15/2023	A6DR	Chloride, total	mg/L	92.0	108	TBD
22	UA	Compliance	02/28/2023	A6	Fluoride, total	mg/L	0.160	0.170	No Exceedance
22	UA	Compliance	05/31/2023	A6R	Fluoride, total	mg/L	0.130	0.170	No Exceedance
22	UA	Compliance	08/25/2023	A6D	Fluoride, total	mg/L	0.22 J	0.170	TBD
22	UA	Compliance	11/15/2023	A6DR	Fluoride, total	mg/L	0.150	0.170	TBD
22	UA	Compliance	02/28/2023	A6	pH (field)	SU	7.6	6.8/7.4	Confirmed
22	UA	Compliance	05/31/2023	A6R	pH (field)	SU	7.6	6.8/7.4	Confirmed
22	UA	Compliance	08/25/2023	A6D	pH (field)	SU	7.7	6.8/7.4	TBD
22	UA	Compliance	11/15/2023	A6DR	pH (field)	SU	7.7	6.8/7.4	TBD
22	UA	Compliance	02/28/2023	A6	Sulfate, total	mg/L	145	117	Confirmed
22	UA	Compliance	05/31/2023	A6R	Sulfate, total	mg/L	123	117	Confirmed
22	UA	Compliance	08/25/2023	A6D	Sulfate, total	mg/L	120	117	TBD
22	UA	Compliance	11/15/2023	A6DR	Sulfate, total	mg/L	120	117	TBD
22	UA	Compliance	02/28/2023	A6	Total Dissolved Solids	mg/L	598	830	No Exceedance
22	UA	Compliance	05/31/2023	A6R	Total Dissolved Solids	mg/L	586	830	No Exceedance
22	UA	Compliance	08/25/2023	A6D	Total Dissolved Solids	mg/L	640	830	TBD
22	UA	Compliance	11/15/2023	A6DR	Total Dissolved Solids	mg/L	590	830	TBD
22D	UA	Compliance	02/28/2023	A6	Boron, total	mg/L	2.40	0.199	Confirmed
22D	UA	Compliance	05/31/2023	A6R	Boron, total	mg/L	1.57	0.199	Confirmed
22D	UA	Compliance	08/22/2023	A6D	Boron, total	mg/L	1.30	0.199	TBD
22D	UA	Compliance	11/15/2023	A6DR	Boron, total	mg/L	1.50	0.199	TBD
22D	UA	Compliance	02/28/2023	A6	Calcium, total	mg/L	137	170	No Exceedance
22D	UA	Compliance	05/31/2023	A6R	Calcium, total	mg/L	113	170	No Exceedance
22D	UA	Compliance	08/22/2023	A6D	Calcium, total	mg/L	120	170	TBD
22D	UA	Compliance	11/15/2023	A6DR	Calcium, total	mg/L	120	170	TBD
22D	UA	Compliance	02/28/2023	A6	Chloride, total	mg/L	113	108	Confirmed
22D	UA	Compliance	05/31/2023	A6R	Chloride, total	mg/L	110	108	Confirmed
22D	UA	Compliance	08/22/2023	A6D	Chloride, total	mg/L	97.0	108	TBD
22D	UA	Compliance	11/15/2023	A6DR	Chloride, total	mg/L	93.0	108	TBD
22D	UA	Compliance	02/28/2023	A6	Fluoride, total	mg/L	0.110	0.170	No Exceedance
22D	UA	Compliance	05/31/2023	A6R	Fluoride, total	mg/L	0.09 J	0.170	No Exceedance
22D	UA	Compliance	08/22/2023	A6D	Fluoride, total	mg/L	0.22 J	0.170	TBD
22D	UA	Compliance	11/15/2023	A6DR	Fluoride, total	mg/L	0.110	0.170	TBD
22D	UA	Compliance	02/28/2023	A6	pH (field)	SU	7.2	6.8/7.4	No Exceedance
22D	UA	Compliance	05/31/2023	A6R	pH (field)	SU	7.2	6.8/7.4	No Exceedance
22D	UA	Compliance	08/22/2023	A6D	pH (field)	SU	7.3	6.8/7.4	TBD
22D	UA	Compliance	11/15/2023	A6DR	pH (field)	SU	7.4	6.8/7.4	TBD
22D	UA	Compliance	02/28/2023	A6	Sulfate, total	mg/L	112	117	No Exceedance
22D	UA	Compliance	05/31/2023	A6R	Sulfate, total	mg/L	104	117	No Exceedance
22D	UA	Compliance	08/22/2023	A6D	Sulfate, total	mg/L	96.0	117	TBD
22D	UA	Compliance	11/15/2023	A6DR	Sulfate, total	mg/L	89.0	117	TBD
22D	UA	Compliance	02/28/2023	A6	Total Dissolved Solids	mg/L	680	830	No Exceedance
22D	UA	Compliance	05/31/2023	A6R	Total Dissolved Solids	mg/L	640	830	No Exceedance

TABLE 2
ANALYTICAL RESULTS - APPENDIX III PARAMETERS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Well Type	Date	Event ID	Parameter	Unit	Result	Background	SSI Type
22D	UA	Compliance	08/22/2023	A6D	Total Dissolved Solids	mg/L	690	830	TBD
22D	UA	Compliance	11/15/2023	A6DR	Total Dissolved Solids	mg/L	640	830	TBD
23	UA	Compliance	02/28/2023	A6	Boron, total	mg/L	12.8	0.199	Confirmed
23	UA	Compliance	05/31/2023	A6R	Boron, total	mg/L	8.79	0.199	Confirmed
23	UA	Compliance	08/22/2023	A6D	Boron, total	mg/L	8.10	0.199	TBD
23	UA	Compliance	11/15/2023	A6DR	Boron, total	mg/L	8.70	0.199	TBD
23	UA	Compliance	02/28/2023	A6	Calcium, total	mg/L	122	170	No Exceedance
23	UA	Compliance	05/31/2023	A6R	Calcium, total	mg/L	105	170	No Exceedance
23	UA	Compliance	08/22/2023	A6D	Calcium, total	mg/L	110	170	TBD
23	UA	Compliance	11/15/2023	A6DR	Calcium, total	mg/L	110	170	TBD
23	UA	Compliance	02/28/2023	A6	Chloride, total	mg/L	66.0	108	No Exceedance
23	UA	Compliance	05/31/2023	A6R	Chloride, total	mg/L	55.0	108	No Exceedance
23	UA	Compliance	08/22/2023	A6D	Chloride, total	mg/L	53.0	108	TBD
23	UA	Compliance	11/15/2023	A6DR	Chloride, total	mg/L	56.0	108	TBD
23	UA	Compliance	02/28/2023	A6	Fluoride, total	mg/L	0.170	0.170	No Exceedance
23	UA	Compliance	05/31/2023	A6R	Fluoride, total	mg/L	0.140	0.170	No Exceedance
23	UA	Compliance	08/22/2023	A6D	Fluoride, total	mg/L	0.23 J	0.170	TBD
23	UA	Compliance	11/15/2023	A6DR	Fluoride, total	mg/L	0.150	0.170	TBD
23	UA	Compliance	02/28/2023	A6	pH (field)	SU	7.4	6.8/7.4	No Exceedance
23	UA	Compliance	05/31/2023	A6R	pH (field)	SU	7.4	6.8/7.4	No Exceedance
23	UA	Compliance	08/22/2023	A6D	pH (field)	SU	7.4	6.8/7.4	TBD
23	UA	Compliance	11/15/2023	A6DR	pH (field)	SU	7.5	6.8/7.4	TBD
23	UA	Compliance	02/28/2023	A6	Sulfate, total	mg/L	433	117	Confirmed
23	UA	Compliance	05/31/2023	A6R	Sulfate, total	mg/L	450	117	Confirmed
23	UA	Compliance	08/22/2023	A6D	Sulfate, total	mg/L	460	117	TBD
23	UA	Compliance	11/15/2023	A6DR	Sulfate, total	mg/L	430	117	TBD
23	UA	Compliance	02/28/2023	A6	Total Dissolved Solids	mg/L	856	830	Confirmed
23	UA	Compliance	05/31/2023	A6R	Total Dissolved Solids	mg/L	876	830	Confirmed
23	UA	Compliance	08/22/2023	A6D	Total Dissolved Solids	mg/L	950	830	TBD
23	UA	Compliance	11/15/2023	A6DR	Total Dissolved Solids	mg/L	890	830	TBD
27	UA	Compliance	02/28/2023	A6	Boron, total	mg/L	2.73	0.199	Confirmed
27	UA	Compliance	05/31/2023	A6R	Boron, total	mg/L	2.27	0.199	Confirmed
27	UA	Compliance	08/24/2023	A6D	Boron, total	mg/L	2.00	0.199	TBD
27	UA	Compliance	11/14/2023	A6DR	Boron, total	mg/L	2.40	0.199	TBD
27	UA	Compliance	02/28/2023	A6	Calcium, total	mg/L	141	170	No Exceedance
27	UA	Compliance	05/31/2023	A6R	Calcium, total	mg/L	117	170	No Exceedance
27	UA	Compliance	08/24/2023	A6D	Calcium, total	mg/L	120	170	TBD
27	UA	Compliance	11/14/2023	A6DR	Calcium, total	mg/L	120	170	TBD
27	UA	Compliance	02/28/2023	A6	Chloride, total	mg/L	99.0	108	No Exceedance
27	UA	Compliance	05/31/2023	A6R	Chloride, total	mg/L	107	108	No Exceedance
27	UA	Compliance	08/24/2023	A6D	Chloride, total	mg/L	91.0	108	TBD
27	UA	Compliance	11/14/2023	A6DR	Chloride, total	mg/L	88.0	108	TBD
27	UA	Compliance	02/28/2023	A6	Fluoride, total	mg/L	0.130	0.170	No Exceedance
27	UA	Compliance	05/31/2023	A6R	Fluoride, total	mg/L	0.100	0.170	No Exceedance
27	UA	Compliance	08/24/2023	A6D	Fluoride, total	mg/L	0.22 J	0.170	TBD
27	UA	Compliance	11/14/2023	A6DR	Fluoride, total	mg/L	0.120	0.170	TBD

TABLE 2
ANALYTICAL RESULTS - APPENDIX III PARAMETERS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Well Type	Date	Event ID	Parameter	Unit	Result	Background	SSI Type
27	UA	Compliance	02/28/2023	A6	pH (field)	SU	7.0	6.8/7.4	No Exceedance
27	UA	Compliance	05/31/2023	A6R	pH (field)	SU	7.0	6.8/7.4	No Exceedance
27	UA	Compliance	08/24/2023	A6D	pH (field)	SU	7.3	6.8/7.4	TBD
27	UA	Compliance	11/14/2023	A6DR	pH (field)	SU	7.3	6.8/7.4	TBD
27	UA	Compliance	02/28/2023	A6	Sulfate, total	mg/L	159	117	Confirmed
27	UA	Compliance	05/31/2023	A6R	Sulfate, total	mg/L	118	117	Confirmed
27	UA	Compliance	08/24/2023	A6D	Sulfate, total	mg/L	110	117	TBD
27	UA	Compliance	11/14/2023	A6DR	Sulfate, total	mg/L	120	117	TBD
27	UA	Compliance	02/28/2023	A6	Total Dissolved Solids	mg/L	636	830	No Exceedance
27	UA	Compliance	05/31/2023	A6R	Total Dissolved Solids	mg/L	658	830	No Exceedance
27	UA	Compliance	08/24/2023	A6D	Total Dissolved Solids	mg/L	660	830	TBD
27	UA	Compliance	11/14/2023	A6DR	Total Dissolved Solids	mg/L	660	830	TBD
35	UA	Compliance	02/28/2023	A6	Boron, total	mg/L	9.58	0.199	Confirmed
35	UA	Compliance	05/31/2023	A6R	Boron, total	mg/L	12.6	0.199	Confirmed
35	UA	Compliance	08/24/2023	A6D	Boron, total	mg/L	12.0	0.199	TBD
35	UA	Compliance	11/15/2023	A6DR	Boron, total	mg/L	11.0	0.199	TBD
35	UA	Compliance	02/28/2023	A6	Calcium, total	mg/L	268	170	Confirmed
35	UA	Compliance	05/31/2023	A6R	Calcium, total	mg/L	291	170	Confirmed
35	UA	Compliance	08/24/2023	A6D	Calcium, total	mg/L	320	170	TBD
35	UA	Compliance	11/15/2023	A6DR	Calcium, total	mg/L	320	170	TBD
35	UA	Compliance	02/28/2023	A6	Chloride, total	mg/L	26.0	108	No Exceedance
35	UA	Compliance	05/31/2023	A6R	Chloride, total	mg/L	32.0	108	No Exceedance
35	UA	Compliance	08/24/2023	A6D	Chloride, total	mg/L	37.0	108	TBD
35	UA	Compliance	11/15/2023	A6DR	Chloride, total	mg/L	24.0	108	TBD
35	UA	Compliance	02/28/2023	A6	Fluoride, total	mg/L	0.190	0.170	Exceedance Not Confirmed
35	UA	Compliance	05/31/2023	A6R	Fluoride, total	mg/L	0.110	0.170	No Exceedance
35	UA	Compliance	08/24/2023	A6D	Fluoride, total	mg/L	0.2 J	0.170	TBD
35	UA	Compliance	11/15/2023	A6DR	Fluoride, total	mg/L	0.150	0.170	TBD
35	UA	Compliance	02/28/2023	A6	pH (field)	SU	7.0	6.8/7.4	No Exceedance
35	UA	Compliance	05/31/2023	A6R	pH (field)	SU	6.9	6.8/7.4	No Exceedance
35	UA	Compliance	08/24/2023	A6D	pH (field)	SU	7.0	6.8/7.4	TBD
35	UA	Compliance	11/15/2023	A6DR	pH (field)	SU	6.9	6.8/7.4	TBD
35	UA	Compliance	02/28/2023	A6	Sulfate, total	mg/L	476	117	Confirmed
35	UA	Compliance	05/31/2023	A6R	Sulfate, total	mg/L	670	117	Confirmed
35	UA	Compliance	08/24/2023	A6D	Sulfate, total	mg/L	890	117	TBD
35	UA	Compliance	11/15/2023	A6DR	Sulfate, total	mg/L	730	117	TBD
35	UA	Compliance	02/28/2023	A6	Total Dissolved Solids	mg/L	918	830	Confirmed
35	UA	Compliance	05/31/2023	A6R	Total Dissolved Solids	mg/L	1,300	830	Confirmed
35	UA	Compliance	08/24/2023	A6D	Total Dissolved Solids	mg/L	1,600	830	TBD
35	UA	Compliance	11/15/2023	A6DR	Total Dissolved Solids	mg/L	1,500	830	TBD
49	UA	Compliance	02/28/2023	A6	Boron, total	mg/L	0.703	0.199	Confirmed
49	UA	Compliance	05/31/2023	A6R	Boron, total	mg/L	0.758	0.199	Confirmed
49	UA	Compliance	08/25/2023	A6D	Boron, total	mg/L	0.690	0.199	TBD
49	UA	Compliance	11/15/2023	A6DR	Boron, total	mg/L	0.890	0.199	TBD
49	UA	Compliance	02/28/2023	A6	Calcium, total	mg/L	127	170	No Exceedance
49	UA	Compliance	05/31/2023	A6R	Calcium, total	mg/L	115	170	No Exceedance

TABLE 2
ANALYTICAL RESULTS - APPENDIX III PARAMETERS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Well Type	Date	Event ID	Parameter	Unit	Result	Background	SSI Type
49	UA	Compliance	08/25/2023	A6D	Calcium, total	mg/L	99.0	170	TBD
49	UA	Compliance	11/15/2023	A6DR	Calcium, total	mg/L	100	170	TBD
49	UA	Compliance	02/28/2023	A6	Chloride, total	mg/L	104	108	No Exceedance
49	UA	Compliance	05/31/2023	A6R	Chloride, total	mg/L	102	108	No Exceedance
49	UA	Compliance	08/25/2023	A6D	Chloride, total	mg/L	95.0	108	TBD
49	UA	Compliance	11/15/2023	A6DR	Chloride, total	mg/L	95.0	108	TBD
49	UA	Compliance	02/28/2023	A6	Fluoride, total	mg/L	0.150	0.170	No Exceedance
49	UA	Compliance	05/31/2023	A6R	Fluoride, total	mg/L	0.120	0.170	No Exceedance
49	UA	Compliance	08/25/2023	A6D	Fluoride, total	mg/L	0.24 J	0.170	TBD
49	UA	Compliance	11/15/2023	A6DR	Fluoride, total	mg/L	0.150	0.170	TBD
49	UA	Compliance	02/28/2023	A6	pH (field)	SU	7.0	6.8/7.4	No Exceedance
49	UA	Compliance	05/31/2023	A6R	pH (field)	SU	7.0	6.8/7.4	No Exceedance
49	UA	Compliance	08/25/2023	A6D	pH (field)	SU	7.1	6.8/7.4	TBD
49	UA	Compliance	11/15/2023	A6DR	pH (field)	SU	7.2	6.8/7.4	TBD
49	UA	Compliance	02/28/2023	A6	Sulfate, total	mg/L	108	117	No Exceedance
49	UA	Compliance	05/31/2023	A6R	Sulfate, total	mg/L	84.0	117	No Exceedance
49	UA	Compliance	08/25/2023	A6D	Sulfate, total	mg/L	78.0	117	TBD
49	UA	Compliance	11/15/2023	A6DR	Sulfate, total	mg/L	77.0	117	TBD
49	UA	Compliance	02/28/2023	A6	Total Dissolved Solids	mg/L	618	830	No Exceedance
49	UA	Compliance	05/31/2023	A6R	Total Dissolved Solids	mg/L	602	830	No Exceedance
49	UA	Compliance	08/25/2023	A6D	Total Dissolved Solids	mg/L	620	830	TBD
49	UA	Compliance	11/15/2023	A6DR	Total Dissolved Solids	mg/L	580	830	TBD
50	UA	Compliance	02/28/2023	A6	Boron, total	mg/L	1.43	0.199	Confirmed
50	UA	Compliance	05/31/2023	A6R	Boron, total	mg/L	0.784	0.199	Confirmed
50	UA	Compliance	08/25/2023	A6D	Boron, total	mg/L	0.590	0.199	TBD
50	UA	Compliance	11/14/2023	A6DR	Boron, total	mg/L	1.00	0.199	TBD
50	UA	Compliance	02/28/2023	A6	Calcium, total	mg/L	121	170	No Exceedance
50	UA	Compliance	05/31/2023	A6R	Calcium, total	mg/L	122	170	No Exceedance
50	UA	Compliance	08/25/2023	A6D	Calcium, total	mg/L	100	170	TBD
50	UA	Compliance	11/14/2023	A6DR	Calcium, total	mg/L	110	170	TBD
50	UA	Compliance	02/28/2023	A6	Chloride, total	mg/L	101	108	No Exceedance
50	UA	Compliance	05/31/2023	A6R	Chloride, total	mg/L	90.0	108	No Exceedance
50	UA	Compliance	08/25/2023	A6D	Chloride, total	mg/L	87.0	108	TBD
50	UA	Compliance	11/14/2023	A6DR	Chloride, total	mg/L	83.0	108	TBD
50	UA	Compliance	02/28/2023	A6	Fluoride, total	mg/L	0.140	0.170	No Exceedance
50	UA	Compliance	05/31/2023	A6R	Fluoride, total	mg/L	0.09 J	0.170	No Exceedance
50	UA	Compliance	08/25/2023	A6D	Fluoride, total	mg/L	0.2 J	0.170	TBD
50	UA	Compliance	11/14/2023	A6DR	Fluoride, total	mg/L	0.120	0.170	TBD
50	UA	Compliance	02/28/2023	A6	pH (field)	SU	7.4	6.8/7.4	No Exceedance
50	UA	Compliance	05/31/2023	A6R	pH (field)	SU	7.3	6.8/7.4	No Exceedance
50	UA	Compliance	08/25/2023	A6D	pH (field)	SU	7.5	6.8/7.4	TBD
50	UA	Compliance	11/14/2023	A6DR	pH (field)	SU	7.5	6.8/7.4	TBD
50	UA	Compliance	02/28/2023	A6	Sulfate, total	mg/L	136	117	Exceedance Not Confirmed
50	UA	Compliance	05/31/2023	A6R	Sulfate, total	mg/L	88.0	117	No Exceedance
50	UA	Compliance	08/25/2023	A6D	Sulfate, total	mg/L	93.0	117	TBD
50	UA	Compliance	11/14/2023	A6DR	Sulfate, total	mg/L	91.0	117	TBD

TABLE 2
ANALYTICAL RESULTS - APPENDIX III PARAMETERS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Well Type	Date	Event ID	Parameter	Unit	Result	Background	SSI Type
50	UA	Compliance	02/28/2023	A6	Total Dissolved Solids	mg/L	580	830	No Exceedance
50	UA	Compliance	05/31/2023	A6R	Total Dissolved Solids	mg/L	632	830	No Exceedance
50	UA	Compliance	08/25/2023	A6D	Total Dissolved Solids	mg/L	610	830	TBD
50	UA	Compliance	11/14/2023	A6DR	Total Dissolved Solids	mg/L	610	830	TBD
51	UA	Compliance	02/28/2023	A6	Boron, total	mg/L	1.54	0.199	Confirmed
51	UA	Compliance	05/31/2023	A6R	Boron, total	mg/L	1.63	0.199	Confirmed
51	UA	Compliance	08/22/2023	A6D	Boron, total	mg/L	1.30	0.199	TBD
51	UA	Compliance	11/15/2023	A6DR	Boron, total	mg/L	1.60	0.199	TBD
51	UA	Compliance	02/28/2023	A6	Calcium, total	mg/L	132	170	No Exceedance
51	UA	Compliance	05/31/2023	A6R	Calcium, total	mg/L	127	170	No Exceedance
51	UA	Compliance	08/22/2023	A6D	Calcium, total	mg/L	110	170	TBD
51	UA	Compliance	11/15/2023	A6DR	Calcium, total	mg/L	110	170	TBD
51	UA	Compliance	02/28/2023	A6	Chloride, total	mg/L	110	108	Confirmed
51	UA	Compliance	05/31/2023	A6R	Chloride, total	mg/L	109	108	Confirmed
51	UA	Compliance	08/22/2023	A6D	Chloride, total	mg/L	94.0	108	TBD
51	UA	Compliance	11/15/2023	A6DR	Chloride, total	mg/L	92.0	108	TBD
51	UA	Compliance	02/28/2023	A6	Fluoride, total	mg/L	0.140	0.170	No Exceedance
51	UA	Compliance	05/31/2023	A6R	Fluoride, total	mg/L	0.110	0.170	No Exceedance
51	UA	Compliance	08/22/2023	A6D	Fluoride, total	mg/L	0.23 J	0.170	TBD
51	UA	Compliance	11/15/2023	A6DR	Fluoride, total	mg/L	0.130	0.170	TBD
51	UA	Compliance	02/28/2023	A6	pH (field)	SU	7.2	6.8/7.4	No Exceedance
51	UA	Compliance	05/31/2023	A6R	pH (field)	SU	7.2	6.8/7.4	No Exceedance
51	UA	Compliance	08/22/2023	A6D	pH (field)	SU	7.4	6.8/7.4	TBD
51	UA	Compliance	11/15/2023	A6DR	pH (field)	SU	7.4	6.8/7.4	TBD
51	UA	Compliance	02/28/2023	A6	Sulfate, total	mg/L	105	117	No Exceedance
51	UA	Compliance	05/31/2023	A6R	Sulfate, total	mg/L	97.0	117	No Exceedance
51	UA	Compliance	08/22/2023	A6D	Sulfate, total	mg/L	90.0	117	TBD
51	UA	Compliance	11/15/2023	A6DR	Sulfate, total	mg/L	87.0	117	TBD
51	UA	Compliance	02/28/2023	A6	Total Dissolved Solids	mg/L	630	830	No Exceedance
51	UA	Compliance	05/31/2023	A6R	Total Dissolved Solids	mg/L	630	830	No Exceedance
51	UA	Compliance	08/22/2023	A6D	Total Dissolved Solids	mg/L	680	830	TBD
51	UA	Compliance	11/15/2023	A6DR	Total Dissolved Solids	mg/L	650	830	TBD

Notes:
HSU = hydrostratigraphic unit:
 UA = Uppermost Aquifer
ID = identification
mg/L = milligrams per liter
NA = not applicable
R = resample
Statistically Significant Increase (SSI) Type:
 TBD: To be determined in 2024.
 No Exceedance: No exceedance of the background.
 Exceedance Not Confirmed: An exceedance was determined in the parent event, a resample was collected, and the resample did not confirm the exceedance.
 Confirmed: An exceedance was determined with comparison to a resample. If a determined exceedance is confirmed by resample, both the sample and resample are noted as confirmed.

SU = Standard Units
J = The result is an estimated quantity. The associated numerical value is the approximate concentration of the analyte in the sample.
J+ = The result is an estimated quantity, but the result may be biased high.

TABLE 3
ANALYTICAL RESULTS - APPENDIX IV PARAMETERS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	Well Type	Date	Event ID	Antimony, total (mg/L)	Arsenic, total (mg/L)	Barium, total (mg/L)	Beryllium, total (mg/L)	Cadmium, total (mg/L)	Chromium, total (mg/L)	Cobalt, total (mg/L)	Fluoride, total (mg/L)	Lead, total (mg/L)	Lithium, total (mg/L)	Mercury, total (mg/L)	Molybdenum, total (mg/L)	Radium 226 + 228 (pCi/L)	Selenium, total (mg/L)	Thallium, total (mg/L)
32	B	02/28/2023	A6	0.0004 U	0.0004 U	0.0590	0.0002 U	0.0002 J	0.0014 J	0.00290	0.130	0.0006 U	0.00310	0.00007 U	0.0007 J	0.886	0.0006 U	0.001 U
32	B	05/31/2023	A6R	0.0004 U	0.0087 U	0.0410	0.0002 U	0.0005 U	0.0028 U	0.00180	0.100	0.004 U	0.0029 J	0.00006 U	0.0037 U	0.312	0.0006 U	0.001 U
32	B	08/22/2023	A6D	0.0013 U	0.00049 J	0.0390	0.00053 U	0.00021 J	0.0011 U	0.00140	0.22 J	0.00019 U	0.0048 J	0.000079 U	0.0025 U	0.636	0.00098 U	0.00057 U
34	B	02/28/2023	A6	0.0004 U	0.0007 J	0.139	0.0002 U	0.0002 U	0.0007 U	0.0003 J	0.160	0.0006 J	0.0111	0.00007 U	0.00170	1.55	0.0006 U	0.001 U
34	B	05/31/2023	A6R	0.0004 U	0.0087 U	0.0995	0.0002 U	0.0005 U	0.0028 U	0.0007 J	0.120	0.004 U	0.0032 J	0.00006 U	0.0037 U	0.492	0.0006 U	0.001 U
34	B	08/25/2023	A6D	0.0013 U	0.001 UJ	0.110	0.00053 U	0.00017 U	0.0011 U	0.0004 U	0.19 J	0.00019 U	0.0130	0.0002 UJ	0.0025 U	0.823	0.00098 U	0.00057 U
21R	C	02/28/2023	A6	0.0004 U	0.0345	0.398	0.0002 U	0.0002 J	0.00240	0.00170	0.150	0.00540	0.0199	0.00006 U	0.0109	1.75	0.0006 U	0.001 U
21R	C	05/31/2023	A6R	0.0004 U	0.0274	0.296	0.0002 U	0.0005 U	0.0028 U	0.00130	0.120	0.004 U	0.0167 J+	0.00006 U	0.008 J	2.44	0.0006 U	0.001 U
21R	C	08/22/2023	A6D	0.0013 U	0.0230	0.300	0.00053 U	0.00017 U	0.0026 J	0.00140	0.23 J	0.00280	0.0260 J	0.000079 U	0.00970	0.855	0.00098 U	0.00057 U
22	C	02/28/2023	A6	0.00100 J	0.00140	0.0900	0.0002 U	0.00960	0.0007 U	0.00380	0.160	0.0007 J	0.0419	0.00007 U	0.156	0.324	0.0322	0.001 U
22	C	05/31/2023	A6R	0.0008 J	0.0087 U	0.0585	0.0002 U	0.00520	0.0028 U	0.00240	0.130	0.004 U	0.0500 J+	0.00006 U	0.0829	0.781	0.0157	0.001 U
22	C	08/25/2023	A6D	0.0013 U	0.00023 U	0.0130	0.00053 U	0.0005 UJ	0.0011 U	0.00076 J	0.22 J	0.00019 U	0.0490	0.000079 U	0.00500	0.492	0.0150	0.00057 U
22D	C	02/28/2023	A6	0.0004 U	0.00160	0.0783	0.0002 U	0.0002 U	0.0014 U	0.0005 J	0.110	0.0006 J	0.0129	0.00006 U	0.00820	1.25	0.0006 U	0.001 U
22D	C	05/31/2023	A6R	0.0004 U	0.0087 U	0.0669	0.0002 U	0.0005 U	0.0028 U	0.0004 J	0.09 J	0.004 U	0.0150 J+	0.00006 U	0.0054 J	0.104	0.0006 U	0.001 U
22D	C	08/22/2023	A6D	0.0013 U	0.00130	0.0660	0.00053 U	0.00017 U	0.0011 U	0.0004 U	0.22 J	0.00019 U	0.0170	0.000079 U	0.00670	1.26	0.00098 U	0.00057 U
23	C	02/28/2023	A6	0.0004 U	0.00130	0.0685	0.0002 U	0.0002 U	0.0007 U	0.0004 J	0.170	0.0006 U	0.00420	0.00007 U	0.0213	0.727	0.0006 U	0.001 U
23	C	05/31/2023	A6R	0.0004 U	0.0087 U	0.0481	0.0003 J	0.0005 U	0.0028 U	0.0004 J	0.140	0.004 U	0.0019 U	0.00006 U	0.0146	0.392	0.0006 U	0.001 U
23	C	08/22/2023	A6D	0.0013 U	0.00089 J	0.0420	0.00053 U	0.00017 U	0.0011 U	0.00047 J	0.23 J	0.00019 U	0.00630	0.000079 U	0.0150	0.658	0.00098 U	0.00057 U
27	C	02/28/2023	A6	0.0004 U	0.00130	0.0971	0.0002 U	0.0003 J	0.00160	0.00210	0.130	0.00100 J	0.0174	0.00007 U	0.00520	0.671	0.0006 U	0.001 U
27	C	05/31/2023	A6R	0.0004 U	0.0087 U	0.0837	0.0002 U	0.0005 U	0.0028 U	0.00330	0.100	0.004 U	0.0225 J+	0.00006 U	0.0037 U	0.219	0.0006 U	0.001 U
27	C	08/24/2023	A6D	0.0013 U	0.00100	0.0840	0.00053 U	0.00025 J	0.0011 U	0.00260	0.22 J	0.0002 J+	0.0240	0.0002 UJ	0.0047 J	0.589	0.00098 U	0.00057 U
35	C	02/28/2023	A6	0.0004 U	0.0008 J	0.0591	0.0002 U	0.0005 J	0.0007 U	0.00140	0.190	0.0006 U	0.0128	0.00007 U	0.0711	1.99	0.0006 U	0.001 U
35	C	05/31/2023	A6R	0.0004 U	0.0087 U	0.0381	0.0002 U	0.0005 U	0.0028 U	0.00140	0.110	0.004 U	0.0210 J+	0.00006 U	0.0798	0.353	0.0006 U	0.001 U
35	C	08/24/2023	A6D	0.0013 U	0.001 UJ	0.0470	0.00053 U	0.0005 UJ	0.0011 U	0.00120	0.2 J	0.00019 U	0.0340	0.000079 U	0.0760	0.626	0.00098 U	0.00057 U
49	C	02/28/2023	A6	0.0004 U	0.0006 J	0.0827	0.0002 U	0.00250	0.0013 J	0.00370	0.150	0.0008 J	0.0207	0.00006 U	0.0355	0.231	0.0006 U	0.001 U
49	C	05/31/2023	A6R	0.0004 U	0.0087 U	0.0711	0.0002 U	0.0011 J	0.0028 U	0.00670	0.120	0.004 U	0.0202 J+	0.00006 U	0.0243	0.583	0.0006 U	0.001 U
49	C	08/25/2023	A6D	0.0013 U	0.00049 J	0.0620	0.00053 U	0.00130	0.0011 U	0.00330	0.24 J	0.0005 UJ	0.0230	0.000079 U	0.0230	0.793	0.00098 U	0.00057 U

TABLE 3
ANALYTICAL RESULTS - APPENDIX IV PARAMETERS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	Well Type	Date	Event ID	Antimony, total (mg/L)	Arsenic, total (mg/L)	Barium, total (mg/L)	Beryllium, total (mg/L)	Cadmium, total (mg/L)	Chromium, total (mg/L)	Cobalt, total (mg/L)	Fluoride, total (mg/L)	Lead, total (mg/L)	Lithium, total (mg/L)	Mercury, total (mg/L)	Molybdenum, total (mg/L)	Radium 226 + 228 (pCi/L)	Selenium, total (mg/L)	Thallium, total (mg/L)
50	C	02/28/2023	A6	0.0004 U	0.00100	0.103	0.0002 U	0.00370	0.0007 U	0.00990	0.140	0.0006 U	0.0242	0.00006 U	0.0971	0.608	0.0007 J	0.001 U
50	C	05/31/2023	A6R	0.0004 U	0.0087 U	0.0888	0.0002 U	0.0005 U	0.0028 U	0.00510	0.09 J	0.004 U	0.00710 J+	0.00006 U	0.0411	0.580	0.0008 J	0.001 U
50	C	08/25/2023	A6D	0.0013 U	0.001 UJ	0.0640	0.00053 U	0.00140 J+	0.0011 U	0.00350	0.2 J	0.0005 UJ	0.0250	0.000079 U	0.0250	0.752	0.00098 U	0.00057 U
51	C	02/28/2023	A6	0.0004 U	0.0308	0.134	0.0002 U	0.0002 U	0.0007 J	0.0009 J	0.140	0.0009 J	0.0210	0.00006 U	0.0135	1.35	0.0006 U	0.001 U
51	C	05/31/2023	A6R	0.0004 U	0.0182	0.109	0.0002 U	0.0005 U	0.0028 U	0.0008 J	0.110	0.004 U	0.0714 J+	0.00006 U	0.0067 J	2.43	0.0006 U	0.001 U
51	C	08/22/2023	A6D	0.0013 U	0.0190	0.100	0.00053 U	0.00017 U	0.0011 J	0.00086 J	0.23 J	0.00120 J+	0.0250	0.000079 U	0.00890	1.03	0.00098 U	0.00057 U

Notes:
ID = identification
mg/L = milligrams per liter
pCi/L = picoCuries per liter
J = The result is an estimated quantity. The associated numerical value is the approximate concentration of the analyte in the sample.
J+ = The result is an estimated quantity, but the result may be biased high.
U = The analyte was analyzed for, but was not detected above the level of the adjusted detection limit or quantitation limit, as appropriate.
UJ = The analyte was analyzed for, but was not detected. The reported quantitation limit is approximate and may be inaccurate or imprecise.
Well Type:
B = Background
C = Compliance

TABLE 4
STATISTICAL BACKGROUND VALUES
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Parameter	Date Range	Sample Count	Percent Non-Detects	Statistical Calculation	Statistical Background Value (LPL/UPL)
Boron (mg/L)	12/09/2015 - 06/08/2017	16	0	Parametric UPL	0.199
Calcium (mg/L)	12/09/2015 - 06/08/2017	16	0	Non-parametric UPL	170
Chloride (mg/L)	12/09/2015 - 06/08/2017	16	0	Non-parametric UPL	108
Fluoride (mg/L)	12/09/2015 - 06/08/2017	16	0	Parametric UPL	0.170
pH (field) (SU)	12/09/2015 - 06/08/2017	16	0	Parametric LPL/UPL	6.8/7.4
Sulfate (mg/L)	12/09/2015 - 06/08/2017	16	0	Non-parametric UPL	117
Total Dissolved Solids (mg/L)	12/09/2015 - 06/08/2017	16	0	Non-parametric UPL	830

Notes:
LPL = lower prediction limit (applicable for pH only)
mg/L = milligrams per liter
SU = standard units
UPL = upper prediction limit

Generated 2024-01-14 01:43:33.370151 by banoffra

TABLE 5
GROUNDWATER PROTECTION STANDARDS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Parameter	Background					MCL/HBL	Groundwater Protection Standard*	Groundwater Protection Standard Source
	Date Range	Sample Count	Percent Non-Detects	Statistical Calculation	Value			
Antimony (mg/L)	12/09/2015 - 06/08/2017	16	100	All ND - Last Reporting Limit	0.001	0.006	0.006	MCL/HBL
Arsenic (mg/L)	12/09/2015 - 06/08/2017	16	100	All ND - Last Reporting Limit	0.001	0.010	0.010	MCL/HBL
Barium (mg/L)	12/09/2015 - 06/08/2017	16	0	Non-parametric UTL	0.156	2.0	2.0	MCL/HBL
Beryllium (mg/L)	12/09/2015 - 06/08/2017	16	100	All ND - Last Reporting Limit	0.001	0.004	0.004	MCL/HBL
Cadmium (mg/L)	12/09/2015 - 06/08/2017	16	100	All ND - Last Reporting Limit	0.001	0.005	0.005	MCL/HBL
Chromium (mg/L)	12/09/2015 - 06/08/2017	16	94	Non-parametric UTL	0.00130	0.1	0.1	MCL/HBL
Cobalt (mg/L)	12/09/2015 - 06/08/2017	16	75	Non-parametric UTL	0.00170	0.006	0.006	MCL/HBL
Fluoride (mg/L)	12/09/2015 - 06/08/2017	16	0	Parametric UTL	0.172	4.0	4.0	MCL/HBL
Lead (mg/L)	12/09/2015 - 06/08/2017	16	100	All ND - Last Reporting Limit	0.001	0.015	0.015	MCL/HBL
Lithium (mg/L)	12/09/2015 - 06/08/2017	16	0	Non-parametric UTL	0.0135	0.04	0.04	MCL/HBL
Mercury (mg/L)	12/09/2015 - 06/08/2017	16	100	All ND - Last Reporting Limit	0.0002	0.002	0.002	MCL/HBL
Molybdenum (mg/L)	12/09/2015 - 06/08/2017	16	50	Non-parametric UTL	0.00200	0.1	0.1	MCL/HBL
Radium 226 + Radium 228 (pCi/L)	12/09/2015 - 06/08/2017	16	0	Parametric UTL	2.64	5	5	MCL/HBL
Selenium (mg/L)	12/09/2015 - 06/08/2017	16	81	Non-parametric UTL	0.00110	0.05	0.05	MCL/HBL
Thallium (mg/L)	12/09/2015 - 06/08/2017	16	100	All ND - Last Reporting Limit	0.001	0.002	0.002	MCL/HBL

Notes:
* Groundwater Protection Standard is the higher of the MCL/HBL or background.
MCL/HBL = maximum contaminant level/health-based level
mg/L = milligrams per liter
ND = non-detect
pCi/L = picoCuries per liter
UTL = upper tolerance limit

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
 2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT
 OLD WEST ASH POND
 HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
21/21R	UA	A6	Antimony, total	mg/L	12/10/2015 - 02/28/2023	26	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
21/21R	UA	A6R	Antimony, total	mg/L	12/10/2015 - 05/31/2023	27	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
21/21R	UA	A6	Arsenic, total	mg/L	12/10/2015 - 02/28/2023	26	0	CB around T-S line	0.0208	0.010	MCL/HBL	Confirmed
21/21R	UA	A6R	Arsenic, total	mg/L	12/10/2015 - 05/31/2023	27	0	CB around T-S line	0.0198	0.010	MCL/HBL	Confirmed
21/21R	UA	A6	Barium, total	mg/L	12/10/2015 - 02/28/2023	26	0	CB around linear reg	0.322	2.0	MCL/HBL	No Exceedance
21/21R	UA	A6R	Barium, total	mg/L	12/10/2015 - 05/31/2023	27	0	CB around linear reg	0.32	2.0	MCL/HBL	No Exceedance
21/21R	UA	A6	Beryllium, total	mg/L	12/10/2015 - 02/28/2023	26	100	All ND - Last	0.001	0.004	MCL/HBL	No Exceedance
21/21R	UA	A6R	Beryllium, total	mg/L	12/10/2015 - 05/31/2023	27	100	All ND - Last	0.0005	0.004	MCL/HBL	No Exceedance
21/21R	UA	A6	Cadmium, total	mg/L	12/10/2015 - 02/28/2023	26	100	All ND - Last	0.001	0.005	MCL/HBL	No Exceedance
21/21R	UA	A6R	Cadmium, total	mg/L	12/10/2015 - 05/31/2023	27	100	All ND - Last	0.002	0.005	MCL/HBL	No Exceedance
21/21R	UA	A6	Chromium, total	mg/L	12/10/2015 - 02/28/2023	26	54	CB around T-S line	0.0015	0.1	MCL/HBL	No Exceedance
21/21R	UA	A6R	Chromium, total	mg/L	12/10/2015 - 05/31/2023	27	56	CB around T-S line	0.0015	0.1	MCL/HBL	No Exceedance
21/21R	UA	A6	Cobalt, total	mg/L	12/10/2015 - 02/28/2023	26	77	CI around median	0.001	0.006	MCL/HBL	No Exceedance
21/21R	UA	A6R	Cobalt, total	mg/L	12/10/2015 - 05/31/2023	27	74	CB around T-S line	0.001	0.006	MCL/HBL	No Exceedance
21/21R	UA	A6	Fluoride, total	mg/L	12/10/2015 - 02/28/2023	27	7.4	CI around median	0.14	4.0	MCL/HBL	No Exceedance
21/21R	UA	A6R	Fluoride, total	mg/L	12/10/2015 - 05/31/2023	28	7.1	CI around median	0.14	4.0	MCL/HBL	No Exceedance
21/21R	UA	A6	Lead, total	mg/L	12/10/2015 - 02/28/2023	26	50	CB around T-S line	0.001	0.015	MCL/HBL	No Exceedance
21/21R	UA	A6R	Lead, total	mg/L	12/10/2015 - 05/31/2023	27	52	CB around T-S line	0.001	0.015	MCL/HBL	No Exceedance
21/21R	UA	A6	Lithium, total	mg/L	12/10/2015 - 02/28/2023	26	0	CB around linear reg	0.0201	0.04	MCL/HBL	No Exceedance
21/21R	UA	A6R	Lithium, total	mg/L	12/10/2015 - 05/31/2023	27	0	CB around linear reg	0.0195	0.04	MCL/HBL	No Exceedance
21/21R	UA	A6	Mercury, total	mg/L	12/10/2015 - 02/28/2023	26	96	CI around median	0.0002	0.002	MCL/HBL	No Exceedance
21/21R	UA	A6R	Mercury, total	mg/L	12/10/2015 - 05/31/2023	27	96	CI around median	0.0002	0.002	MCL/HBL	No Exceedance
21/21R	UA	A6	Molybdenum, total	mg/L	12/10/2015 - 02/28/2023	26	0	CB around linear reg	0.00766	0.1	MCL/HBL	No Exceedance
21/21R	UA	A6R	Molybdenum, total	mg/L	12/10/2015 - 05/31/2023	27	3.7	CI around mean	0.00656	0.1	MCL/HBL	No Exceedance
21/21R	UA	A6	Radium 226 + Radium 228, total	pCi/L	12/10/2015 - 02/28/2023	19	0	CI around mean	0.752	5	MCL/HBL	No Exceedance
21/21R	UA	A6R	Radium 226 + Radium 228, total	pCi/L	12/10/2015 - 05/31/2023	20	0	CI around mean	0.805	5	MCL/HBL	No Exceedance
21/21R	UA	A6	Selenium, total	mg/L	12/10/2015 - 02/28/2023	26	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
 2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT
 OLD WEST ASH POND
 HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
21/21R	UA	A6R	Selenium, total	mg/L	12/10/2015 - 05/31/2023	27	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
21/21R	UA	A6	Thallium, total	mg/L	12/10/2015 - 02/28/2023	26	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
21/21R	UA	A6R	Thallium, total	mg/L	12/10/2015 - 05/31/2023	27	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
22	UA	A6	Antimony, total	mg/L	12/10/2015 - 02/28/2023	29	90	CI around median	0.001	0.006	MCL/HBL	No Exceedance
22	UA	A6R	Antimony, total	mg/L	12/10/2015 - 05/31/2023	30	90	CI around median	0.001	0.006	MCL/HBL	No Exceedance
22	UA	A6	Arsenic, total	mg/L	12/10/2015 - 02/28/2023	33	70	CI around median	0.001	0.010	MCL/HBL	No Exceedance
22	UA	A6R	Arsenic, total	mg/L	12/10/2015 - 05/31/2023	34	71	CI around median	0.001	0.010	MCL/HBL	No Exceedance
22	UA	A6	Barium, total	mg/L	12/10/2015 - 02/28/2023	29	0	CI around median	0.0652	2.0	MCL/HBL	No Exceedance
22	UA	A6R	Barium, total	mg/L	12/10/2015 - 05/31/2023	30	0	CI around median	0.0635	2.0	MCL/HBL	No Exceedance
22	UA	A6	Beryllium, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.001	0.004	MCL/HBL	No Exceedance
22	UA	A6R	Beryllium, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.0005	0.004	MCL/HBL	No Exceedance
22	UA	A6	Cadmium, total	mg/L	12/10/2015 - 02/28/2023	29	0	CB around T-S line	0.00614	0.005	MCL/HBL	Confirmed
22	UA	A6R	Cadmium, total	mg/L	12/10/2015 - 05/31/2023	30	0	CB around T-S line	0.00587	0.005	MCL/HBL	Confirmed
22	UA	A6	Chromium, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.0015	0.1	MCL/HBL	No Exceedance
22	UA	A6R	Chromium, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.005	0.1	MCL/HBL	No Exceedance
22	UA	A6	Cobalt, total	mg/L	12/10/2015 - 02/28/2023	29	0	CB around T-S line	0.0021	0.006	MCL/HBL	No Exceedance
22	UA	A6R	Cobalt, total	mg/L	12/10/2015 - 05/31/2023	30	0	CB around T-S line	0.00215	0.006	MCL/HBL	No Exceedance
22	UA	A6	Fluoride, total	mg/L	12/10/2015 - 02/28/2023	29	3.4	CB around T-S line	0.15	4.0	MCL/HBL	No Exceedance
22	UA	A6R	Fluoride, total	mg/L	12/10/2015 - 05/31/2023	30	3.3	CI around median	0.15	4.0	MCL/HBL	No Exceedance
22	UA	A6	Lead, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.001	0.015	MCL/HBL	No Exceedance
22	UA	A6R	Lead, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.0075	0.015	MCL/HBL	No Exceedance
22	UA	A6	Lithium, total	mg/L	12/10/2015 - 02/28/2023	33	0	CB around T-S line	0.0407	0.04	MCL/HBL	Exceedance Not Confirmed
22	UA	A6R	Lithium, total	mg/L	12/10/2015 - 05/31/2023	34	0	CB around T-S line	0.0395	0.04	MCL/HBL	No Exceedance
22	UA	A6	Mercury, total	mg/L	12/10/2015 - 02/28/2023	27	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
22	UA	A6R	Mercury, total	mg/L	12/10/2015 - 05/31/2023	28	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
22	UA	A6	Molybdenum, total	mg/L	12/10/2015 - 02/28/2023	33	0	CB around T-S line	0.087	0.1	MCL/HBL	No Exceedance

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
22	UA	A6R	Molybdenum, total	mg/L	12/10/2015 - 05/31/2023	34	0	CB around T-S line	0.082	0.1	MCL/HBL	No Exceedance
22	UA	A6	Radium 226 + Radium 228, total	pCi/L	12/10/2015 - 02/28/2023	20	0	CI around mean	0.323	5	MCL/HBL	No Exceedance
22	UA	A6R	Radium 226 + Radium 228, total	pCi/L	12/10/2015 - 05/31/2023	21	0	CI around mean	0.344	5	MCL/HBL	No Exceedance
22	UA	A6	Selenium, total	mg/L	12/10/2015 - 02/28/2023	29	0	CB around linear reg	0.0163	0.05	MCL/HBL	No Exceedance
22	UA	A6R	Selenium, total	mg/L	12/10/2015 - 05/31/2023	30	0	CB around linear reg	0.0161	0.05	MCL/HBL	No Exceedance
22	UA	A6	Thallium, total	mg/L	12/10/2015 - 02/28/2023	29	93	CB around T-S line	0.002	0.002	MCL/HBL	No Exceedance
22	UA	A6R	Thallium, total	mg/L	12/10/2015 - 05/31/2023	30	93	CB around T-S line	0.002	0.002	MCL/HBL	No Exceedance
22D	UA	A6	Antimony, total	mg/L	09/17/2019 - 02/28/2023	13	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
22D	UA	A6R	Antimony, total	mg/L	09/17/2019 - 05/31/2023	14	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
22D	UA	A6	Arsenic, total	mg/L	09/17/2019 - 02/28/2023	13	0	CI around mean	0.00122	0.010	MCL/HBL	No Exceedance
22D	UA	A6R	Arsenic, total	mg/L	09/17/2019 - 05/31/2023	14	7.1	CI around median	0.0012	0.010	MCL/HBL	No Exceedance
22D	UA	A6	Barium, total	mg/L	09/17/2019 - 02/28/2023	13	0	CB around T-S line	0.0636	2.0	MCL/HBL	No Exceedance
22D	UA	A6R	Barium, total	mg/L	09/17/2019 - 05/31/2023	14	0	CB around T-S line	0.0606	2.0	MCL/HBL	No Exceedance
22D	UA	A6	Beryllium, total	mg/L	09/17/2019 - 02/28/2023	12	100	All ND - Last	0.001	0.004	MCL/HBL	No Exceedance
22D	UA	A6R	Beryllium, total	mg/L	09/17/2019 - 05/31/2023	13	100	All ND - Last	0.0005	0.004	MCL/HBL	No Exceedance
22D	UA	A6	Cadmium, total	mg/L	09/17/2019 - 02/28/2023	13	100	All ND - Last	0.001	0.005	MCL/HBL	No Exceedance
22D	UA	A6R	Cadmium, total	mg/L	09/17/2019 - 05/31/2023	14	100	All ND - Last	0.002	0.005	MCL/HBL	No Exceedance
22D	UA	A6	Chromium, total	mg/L	09/17/2019 - 02/28/2023	13	85	CI around median	0.0015	0.1	MCL/HBL	No Exceedance
22D	UA	A6R	Chromium, total	mg/L	09/17/2019 - 05/31/2023	14	86	CI around median	0.0015	0.1	MCL/HBL	No Exceedance
22D	UA	A6	Cobalt, total	mg/L	09/17/2019 - 02/28/2023	13	92	CI around median	0.001	0.006	MCL/HBL	No Exceedance
22D	UA	A6R	Cobalt, total	mg/L	09/17/2019 - 05/31/2023	14	93	CI around median	0.001	0.006	MCL/HBL	No Exceedance
22D	UA	A6	Fluoride, total	mg/L	09/17/2019 - 02/28/2023	13	0	CI around mean	0.114	4.0	MCL/HBL	No Exceedance
22D	UA	A6R	Fluoride, total	mg/L	09/17/2019 - 05/31/2023	14	7.1	CI around median	0.11	4.0	MCL/HBL	No Exceedance
22D	UA	A6	Lead, total	mg/L	09/17/2019 - 02/28/2023	13	92	CI around median	0.001	0.015	MCL/HBL	No Exceedance
22D	UA	A6R	Lead, total	mg/L	09/17/2019 - 05/31/2023	14	93	CI around median	0.001	0.015	MCL/HBL	No Exceedance
22D	UA	A6	Lithium, total	mg/L	09/17/2019 - 02/28/2023	13	0	CI around mean	0.0143	0.04	MCL/HBL	No Exceedance
22D	UA	A6R	Lithium, total	mg/L	09/17/2019 - 05/31/2023	14	0	CI around mean	0.0144	0.04	MCL/HBL	No Exceedance

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
 2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT
 OLD WEST ASH POND
 HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
22D	UA	A6	Mercury, total	mg/L	12/11/2019 - 02/28/2023	12	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
22D	UA	A6R	Mercury, total	mg/L	12/11/2019 - 05/31/2023	13	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
22D	UA	A6	Molybdenum, total	mg/L	09/17/2019 - 02/28/2023	13	0	CI around median	0.0068	0.1	MCL/HBL	No Exceedance
22D	UA	A6R	Molybdenum, total	mg/L	09/17/2019 - 05/31/2023	14	7.1	CI around mean	0.00654	0.1	MCL/HBL	No Exceedance
22D	UA	A6	Radium 226 + Radium 228, total	pCi/L	09/17/2019 - 02/28/2023	10	0	CI around mean	0.621	5	MCL/HBL	No Exceedance
22D	UA	A6R	Radium 226 + Radium 228, total	pCi/L	09/17/2019 - 05/31/2023	11	0	CI around mean	0.518	5	MCL/HBL	No Exceedance
22D	UA	A6	Selenium, total	mg/L	09/17/2019 - 02/28/2023	13	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
22D	UA	A6R	Selenium, total	mg/L	09/17/2019 - 05/31/2023	14	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
22D	UA	A6	Thallium, total	mg/L	09/17/2019 - 02/28/2023	13	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
22D	UA	A6R	Thallium, total	mg/L	09/17/2019 - 05/31/2023	14	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
23	UA	A6	Antimony, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
23	UA	A6R	Antimony, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
23	UA	A6	Arsenic, total	mg/L	12/10/2015 - 02/28/2023	33	94	CB around T-S line	0.001	0.010	MCL/HBL	No Exceedance
23	UA	A6R	Arsenic, total	mg/L	12/10/2015 - 05/31/2023	34	94	CB around T-S line	0.001	0.010	MCL/HBL	No Exceedance
23	UA	A6	Barium, total	mg/L	12/10/2015 - 02/28/2023	29	0	CB around T-S line	0.0336	2.0	MCL/HBL	No Exceedance
23	UA	A6R	Barium, total	mg/L	12/10/2015 - 05/31/2023	30	0	CB around T-S line	0.0365	2.0	MCL/HBL	No Exceedance
23	UA	A6	Beryllium, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.001	0.004	MCL/HBL	No Exceedance
23	UA	A6R	Beryllium, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.0005	0.004	MCL/HBL	No Exceedance
23	UA	A6	Cadmium, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.001	0.005	MCL/HBL	No Exceedance
23	UA	A6R	Cadmium, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.002	0.005	MCL/HBL	No Exceedance
23	UA	A6	Chromium, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.0015	0.1	MCL/HBL	No Exceedance
23	UA	A6R	Chromium, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.005	0.1	MCL/HBL	No Exceedance
23	UA	A6	Cobalt, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
23	UA	A6R	Cobalt, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
23	UA	A6	Fluoride, total	mg/L	12/10/2015 - 02/28/2023	29	3.4	CI around median	0.15	4.0	MCL/HBL	No Exceedance
23	UA	A6R	Fluoride, total	mg/L	12/10/2015 - 05/31/2023	30	3.3	CI around median	0.15	4.0	MCL/HBL	No Exceedance
23	UA	A6	Lead, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.001	0.015	MCL/HBL	No Exceedance

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
23	UA	A6R	Lead, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.0075	0.015	MCL/HBL	No Exceedance
23	UA	A6	Lithium, total	mg/L	12/10/2015 - 02/28/2023	33	3.0	CI around mean	0.00465	0.04	MCL/HBL	No Exceedance
23	UA	A6R	Lithium, total	mg/L	12/10/2015 - 05/31/2023	34	5.9	CI around median	0.0048	0.04	MCL/HBL	No Exceedance
23	UA	A6	Mercury, total	mg/L	12/10/2015 - 02/28/2023	27	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
23	UA	A6R	Mercury, total	mg/L	12/10/2015 - 05/31/2023	28	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
23	UA	A6	Molybdenum, total	mg/L	12/10/2015 - 02/28/2023	33	0	CI around median	0.0141	0.1	MCL/HBL	No Exceedance
23	UA	A6R	Molybdenum, total	mg/L	12/10/2015 - 05/31/2023	34	0	CI around median	0.0146	0.1	MCL/HBL	No Exceedance
23	UA	A6	Radium 226 + Radium 228, total	pCi/L	12/10/2015 - 02/28/2023	20	0	CI around mean	0.245	5	MCL/HBL	No Exceedance
23	UA	A6R	Radium 226 + Radium 228, total	pCi/L	12/10/2015 - 05/31/2023	21	0	CI around mean	0.253	5	MCL/HBL	No Exceedance
23	UA	A6	Selenium, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
23	UA	A6R	Selenium, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
23	UA	A6	Thallium, total	mg/L	12/10/2015 - 02/28/2023	29	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
23	UA	A6R	Thallium, total	mg/L	12/10/2015 - 05/31/2023	30	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
24/51	UA	A6	Antimony, total	mg/L	12/10/2015 - 02/28/2023	27	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
24/51	UA	A6R	Antimony, total	mg/L	12/10/2015 - 05/31/2023	28	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
24/51	UA	A6	Arsenic, total	mg/L	12/10/2015 - 02/28/2023	31	0	CI around mean	0.0205	0.010	MCL/HBL	Confirmed
24/51	UA	A6R	Arsenic, total	mg/L	12/10/2015 - 05/31/2023	32	0	CI around mean	0.0204	0.010	MCL/HBL	Confirmed
24/51	UA	A6	Barium, total	mg/L	12/10/2015 - 02/28/2023	27	0	CB around linear reg	0.111	2.0	MCL/HBL	No Exceedance
24/51	UA	A6R	Barium, total	mg/L	12/10/2015 - 05/31/2023	28	0	CB around linear reg	0.112	2.0	MCL/HBL	No Exceedance
24/51	UA	A6	Beryllium, total	mg/L	12/10/2015 - 02/28/2023	27	100	All ND - Last	0.001	0.004	MCL/HBL	No Exceedance
24/51	UA	A6R	Beryllium, total	mg/L	12/10/2015 - 05/31/2023	28	100	All ND - Last	0.0005	0.004	MCL/HBL	No Exceedance
24/51	UA	A6	Cadmium, total	mg/L	12/10/2015 - 02/28/2023	27	100	All ND - Last	0.001	0.005	MCL/HBL	No Exceedance
24/51	UA	A6R	Cadmium, total	mg/L	12/10/2015 - 05/31/2023	28	100	All ND - Last	0.002	0.005	MCL/HBL	No Exceedance
24/51	UA	A6	Chromium, total	mg/L	12/10/2015 - 02/28/2023	27	74	CB around T-S line	0.00148	0.1	MCL/HBL	No Exceedance
24/51	UA	A6R	Chromium, total	mg/L	12/10/2015 - 05/31/2023	28	75	CB around T-S line	0.0015	0.1	MCL/HBL	No Exceedance
24/51	UA	A6	Cobalt, total	mg/L	12/10/2015 - 02/28/2023	27	70	CI around median	0.001	0.006	MCL/HBL	No Exceedance
24/51	UA	A6R	Cobalt, total	mg/L	12/10/2015 - 05/31/2023	28	71	CI around median	0.001	0.006	MCL/HBL	No Exceedance

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
 2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT
 OLD WEST ASH POND
 HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
24/51	UA	A6	Fluoride, total	mg/L	12/10/2015 - 02/28/2023	27	3.7	CI around median	0.14	4.0	MCL/HBL	No Exceedance
24/51	UA	A6R	Fluoride, total	mg/L	12/10/2015 - 05/31/2023	28	3.6	CB around T-S line	0.114	4.0	MCL/HBL	No Exceedance
24/51	UA	A6	Lead, total	mg/L	12/10/2015 - 02/28/2023	27	67	CI around median	0.001	0.015	MCL/HBL	No Exceedance
24/51	UA	A6R	Lead, total	mg/L	12/10/2015 - 05/31/2023	28	68	CI around median	0.001	0.015	MCL/HBL	No Exceedance
24/51	UA	A6	Lithium, total	mg/L	12/10/2015 - 02/28/2023	31	0	CI around mean	0.0223	0.04	MCL/HBL	No Exceedance
24/51	UA	A6R	Lithium, total	mg/L	12/10/2015 - 05/31/2023	32	0	CB around T-S line	0.0224	0.04	MCL/HBL	No Exceedance
24/51	UA	A6	Mercury, total	mg/L	12/10/2015 - 02/28/2023	26	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
24/51	UA	A6R	Mercury, total	mg/L	12/10/2015 - 05/31/2023	27	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
24/51	UA	A6	Molybdenum, total	mg/L	12/10/2015 - 02/28/2023	31	0	CI around mean	0.0102	0.1	MCL/HBL	No Exceedance
24/51	UA	A6R	Molybdenum, total	mg/L	12/10/2015 - 05/31/2023	32	3.1	CI around mean	0.00992	0.1	MCL/HBL	No Exceedance
24/51	UA	A6	Radium 226 + Radium 228, total	pCi/L	12/10/2015 - 02/28/2023	19	0	CB around linear reg	0.939	5	MCL/HBL	No Exceedance
24/51	UA	A6R	Radium 226 + Radium 228, total	pCi/L	12/10/2015 - 05/31/2023	20	0	CB around linear reg	1.12	5	MCL/HBL	No Exceedance
24/51	UA	A6	Selenium, total	mg/L	12/10/2015 - 02/28/2023	27	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
24/51	UA	A6R	Selenium, total	mg/L	12/10/2015 - 05/31/2023	28	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
24/51	UA	A6	Thallium, total	mg/L	12/10/2015 - 02/28/2023	27	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
24/51	UA	A6R	Thallium, total	mg/L	12/10/2015 - 05/31/2023	28	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
27	UA	A6	Antimony, total	mg/L	09/12/2018 - 02/28/2023	16	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
27	UA	A6R	Antimony, total	mg/L	09/12/2018 - 05/31/2023	17	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
27	UA	A6	Arsenic, total	mg/L	09/12/2018 - 02/28/2023	16	62	CI around median	0.001	0.010	MCL/HBL	No Exceedance
27	UA	A6R	Arsenic, total	mg/L	09/12/2018 - 05/31/2023	17	65	CI around median	0.001	0.010	MCL/HBL	No Exceedance
27	UA	A6	Barium, total	mg/L	09/12/2018 - 02/28/2023	16	0	CI around mean	0.0836	2.0	MCL/HBL	No Exceedance
27	UA	A6R	Barium, total	mg/L	09/12/2018 - 05/31/2023	17	0	CI around mean	0.0835	2.0	MCL/HBL	No Exceedance
27	UA	A6	Beryllium, total	mg/L	09/12/2018 - 02/28/2023	16	100	All ND - Last	0.001	0.004	MCL/HBL	No Exceedance
27	UA	A6R	Beryllium, total	mg/L	09/12/2018 - 05/31/2023	17	100	All ND - Last	0.0005	0.004	MCL/HBL	No Exceedance
27	UA	A6	Cadmium, total	mg/L	09/12/2018 - 02/28/2023	16	100	All ND - Last	0.001	0.005	MCL/HBL	No Exceedance
27	UA	A6R	Cadmium, total	mg/L	09/12/2018 - 05/31/2023	17	100	All ND - Last	0.002	0.005	MCL/HBL	No Exceedance
27	UA	A6	Chromium, total	mg/L	09/12/2018 - 02/28/2023	16	75	CI around median	0.0015	0.1	MCL/HBL	No Exceedance

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
 2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT
 OLD WEST ASH POND
 HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
27	UA	A6R	Chromium, total	mg/L	09/12/2018 - 05/31/2023	17	76	CI around median	0.0015	0.1	MCL/HBL	No Exceedance
27	UA	A6	Cobalt, total	mg/L	09/12/2018 - 02/28/2023	16	0	CI around mean	0.00179	0.006	MCL/HBL	No Exceedance
27	UA	A6R	Cobalt, total	mg/L	09/12/2018 - 05/31/2023	17	0	CI around mean	0.00185	0.006	MCL/HBL	No Exceedance
27	UA	A6	Fluoride, total	mg/L	09/12/2018 - 02/28/2023	16	0	CB around linear reg	0.13	4.0	MCL/HBL	No Exceedance
27	UA	A6R	Fluoride, total	mg/L	09/12/2018 - 05/31/2023	17	0	CI around median	0.12	4.0	MCL/HBL	No Exceedance
27	UA	A6	Lead, total	mg/L	09/12/2018 - 02/28/2023	16	50	CI around median	0.001	0.015	MCL/HBL	No Exceedance
27	UA	A6R	Lead, total	mg/L	09/12/2018 - 05/31/2023	17	53	CI around median	0.001	0.015	MCL/HBL	No Exceedance
27	UA	A6	Lithium, total	mg/L	09/12/2018 - 02/28/2023	16	0	CI around mean	0.0211	0.04	MCL/HBL	No Exceedance
27	UA	A6R	Lithium, total	mg/L	09/12/2018 - 05/31/2023	17	0	CI around mean	0.0212	0.04	MCL/HBL	No Exceedance
27	UA	A6	Mercury, total	mg/L	09/12/2018 - 02/28/2023	16	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
27	UA	A6R	Mercury, total	mg/L	09/12/2018 - 05/31/2023	17	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
27	UA	A6	Molybdenum, total	mg/L	09/12/2018 - 02/28/2023	16	0	CI around mean	0.0043	0.1	MCL/HBL	No Exceedance
27	UA	A6R	Molybdenum, total	mg/L	09/12/2018 - 05/31/2023	17	5.9	CI around mean	0.00434	0.1	MCL/HBL	No Exceedance
27	UA	A6	Radium 226 + Radium 228, total	pCi/L	09/12/2018 - 02/28/2023	10	0	CI around geomean	0.187	5	MCL/HBL	No Exceedance
27	UA	A6R	Radium 226 + Radium 228, total	pCi/L	09/12/2018 - 05/31/2023	11	0	CI around geomean	0.189	5	MCL/HBL	No Exceedance
27	UA	A6	Selenium, total	mg/L	09/12/2018 - 02/28/2023	16	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
27	UA	A6R	Selenium, total	mg/L	09/12/2018 - 05/31/2023	17	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
27	UA	A6	Thallium, total	mg/L	09/12/2018 - 02/28/2023	16	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
27	UA	A6R	Thallium, total	mg/L	09/12/2018 - 05/31/2023	17	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
35	UA	A6	Antimony, total	mg/L	12/09/2015 - 02/28/2023	28	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
35	UA	A6R	Antimony, total	mg/L	12/09/2015 - 05/31/2023	29	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
35	UA	A6	Arsenic, total	mg/L	12/09/2015 - 02/28/2023	28	79	CI around median	0.001	0.010	MCL/HBL	No Exceedance
35	UA	A6R	Arsenic, total	mg/L	12/09/2015 - 05/31/2023	29	79	CI around median	0.001	0.010	MCL/HBL	No Exceedance
35	UA	A6	Barium, total	mg/L	12/09/2015 - 02/28/2023	28	0	CI around geomean	0.0394	2.0	MCL/HBL	No Exceedance
35	UA	A6R	Barium, total	mg/L	12/09/2015 - 05/31/2023	29	0	CI around geomean	0.0394	2.0	MCL/HBL	No Exceedance
35	UA	A6	Beryllium, total	mg/L	12/09/2015 - 02/28/2023	28	100	All ND - Last	0.001	0.004	MCL/HBL	No Exceedance
35	UA	A6R	Beryllium, total	mg/L	12/09/2015 - 05/31/2023	29	100	All ND - Last	0.0005	0.004	MCL/HBL	No Exceedance

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
 2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT
 OLD WEST ASH POND
 HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
35	UA	A6	Cadmium, total	mg/L	12/09/2015 - 02/28/2023	28	100	All ND - Last	0.001	0.005	MCL/HBL	No Exceedance
35	UA	A6R	Cadmium, total	mg/L	12/09/2015 - 05/31/2023	29	100	All ND - Last	0.002	0.005	MCL/HBL	No Exceedance
35	UA	A6	Chromium, total	mg/L	12/09/2015 - 02/28/2023	28	96	CB around T-S line	0.0015	0.1	MCL/HBL	No Exceedance
35	UA	A6R	Chromium, total	mg/L	12/09/2015 - 05/31/2023	29	97	CB around T-S line	0.0015	0.1	MCL/HBL	No Exceedance
35	UA	A6	Cobalt, total	mg/L	12/09/2015 - 02/28/2023	28	46	CI around median	0.001	0.006	MCL/HBL	No Exceedance
35	UA	A6R	Cobalt, total	mg/L	12/09/2015 - 05/31/2023	29	45	CB around T-S line	0.001	0.006	MCL/HBL	No Exceedance
35	UA	A6	Fluoride, total	mg/L	12/09/2015 - 02/28/2023	29	0	CI around mean	0.179	4.0	MCL/HBL	No Exceedance
35	UA	A6R	Fluoride, total	mg/L	12/09/2015 - 05/31/2023	30	0	CI around mean	0.175	4.0	MCL/HBL	No Exceedance
35	UA	A6	Lead, total	mg/L	12/09/2015 - 02/28/2023	28	89	CI around median	0.001	0.015	MCL/HBL	No Exceedance
35	UA	A6R	Lead, total	mg/L	12/09/2015 - 05/31/2023	29	90	CI around median	0.001	0.015	MCL/HBL	No Exceedance
35	UA	A6	Lithium, total	mg/L	12/09/2015 - 02/28/2023	28	0	CI around mean	0.0247	0.04	MCL/HBL	No Exceedance
35	UA	A6R	Lithium, total	mg/L	12/09/2015 - 05/31/2023	29	0	CI around mean	0.0245	0.04	MCL/HBL	No Exceedance
35	UA	A6	Mercury, total	mg/L	12/09/2015 - 02/28/2023	27	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
35	UA	A6R	Mercury, total	mg/L	12/09/2015 - 05/31/2023	28	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
35	UA	A6	Molybdenum, total	mg/L	12/09/2015 - 02/28/2023	28	0	CI around mean	0.066	0.1	MCL/HBL	No Exceedance
35	UA	A6R	Molybdenum, total	mg/L	12/09/2015 - 05/31/2023	29	0	CI around mean	0.0664	0.1	MCL/HBL	No Exceedance
35	UA	A6	Radium 226 + Radium 228, total	pCi/L	12/09/2015 - 02/28/2023	21	0	CI around mean	0.34	5	MCL/HBL	No Exceedance
35	UA	A6R	Radium 226 + Radium 228, total	pCi/L	12/09/2015 - 05/31/2023	22	0	CI around median	0.25	5	MCL/HBL	No Exceedance
35	UA	A6	Selenium, total	mg/L	12/09/2015 - 02/28/2023	28	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
35	UA	A6R	Selenium, total	mg/L	12/09/2015 - 05/31/2023	29	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
35	UA	A6	Thallium, total	mg/L	12/09/2015 - 02/28/2023	28	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
35	UA	A6R	Thallium, total	mg/L	12/09/2015 - 05/31/2023	29	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
49	UA	A6	Antimony, total	mg/L	12/10/2015 - 02/28/2023	28	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
49	UA	A6R	Antimony, total	mg/L	12/10/2015 - 05/31/2023	29	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
49	UA	A6	Arsenic, total	mg/L	12/10/2015 - 02/28/2023	28	96	CI around median	0.001	0.010	MCL/HBL	No Exceedance
49	UA	A6R	Arsenic, total	mg/L	12/10/2015 - 05/31/2023	29	97	CI around median	0.001	0.010	MCL/HBL	No Exceedance
49	UA	A6	Barium, total	mg/L	12/10/2015 - 02/28/2023	28	0	CB around T-S line	0.0596	2.0	MCL/HBL	No Exceedance

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
49	UA	A6R	Barium, total	mg/L	12/10/2015 - 05/31/2023	29	0	CB around linear reg	0.0617	2.0	MCL/HBL	No Exceedance
49	UA	A6	Beryllium, total	mg/L	12/10/2015 - 02/28/2023	28	100	All ND - Last	0.001	0.004	MCL/HBL	No Exceedance
49	UA	A6R	Beryllium, total	mg/L	12/10/2015 - 05/31/2023	29	100	All ND - Last	0.0005	0.004	MCL/HBL	No Exceedance
49	UA	A6	Cadmium, total	mg/L	12/10/2015 - 02/28/2023	28	29	CB around linear reg	0.0016	0.005	MCL/HBL	No Exceedance
49	UA	A6R	Cadmium, total	mg/L	12/10/2015 - 05/31/2023	29	31	CB around linear reg	0.00165	0.005	MCL/HBL	No Exceedance
49	UA	A6	Chromium, total	mg/L	12/10/2015 - 02/28/2023	28	96	CB around T-S line	0.0015	0.1	MCL/HBL	No Exceedance
49	UA	A6R	Chromium, total	mg/L	12/10/2015 - 05/31/2023	29	97	CB around T-S line	0.0015	0.1	MCL/HBL	No Exceedance
49	UA	A6	Cobalt, total	mg/L	12/10/2015 - 02/28/2023	28	0	CI around mean	0.0045	0.006	MCL/HBL	No Exceedance
49	UA	A6R	Cobalt, total	mg/L	12/10/2015 - 05/31/2023	29	0	CI around mean	0.00456	0.006	MCL/HBL	No Exceedance
49	UA	A6	Fluoride, total	mg/L	12/10/2015 - 02/28/2023	29	0	CI around mean	0.15	4.0	MCL/HBL	No Exceedance
49	UA	A6R	Fluoride, total	mg/L	12/10/2015 - 05/31/2023	30	0	CI around mean	0.148	4.0	MCL/HBL	No Exceedance
49	UA	A6	Lead, total	mg/L	12/10/2015 - 02/28/2023	28	93	CI around median	0.001	0.015	MCL/HBL	No Exceedance
49	UA	A6R	Lead, total	mg/L	12/10/2015 - 05/31/2023	29	93	CB around T-S line	0.001	0.015	MCL/HBL	No Exceedance
49	UA	A6	Lithium, total	mg/L	12/10/2015 - 02/28/2023	28	0	CI around mean	0.0242	0.04	MCL/HBL	No Exceedance
49	UA	A6R	Lithium, total	mg/L	12/10/2015 - 05/31/2023	29	0	CI around mean	0.024	0.04	MCL/HBL	No Exceedance
49	UA	A6	Mercury, total	mg/L	12/10/2015 - 02/28/2023	27	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
49	UA	A6R	Mercury, total	mg/L	12/10/2015 - 05/31/2023	28	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
49	UA	A6	Molybdenum, total	mg/L	12/10/2015 - 02/28/2023	28	0	CB around linear reg	0.0244	0.1	MCL/HBL	No Exceedance
49	UA	A6R	Molybdenum, total	mg/L	12/10/2015 - 05/31/2023	29	0	CB around linear reg	0.0233	0.1	MCL/HBL	No Exceedance
49	UA	A6	Radium 226 + Radium 228, total	pCi/L	12/10/2015 - 02/28/2023	21	0	CI around mean	0.275	5	MCL/HBL	No Exceedance
49	UA	A6R	Radium 226 + Radium 228, total	pCi/L	12/10/2015 - 05/31/2023	22	0	CI around mean	0.29	5	MCL/HBL	No Exceedance
49	UA	A6	Selenium, total	mg/L	12/10/2015 - 02/28/2023	28	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
49	UA	A6R	Selenium, total	mg/L	12/10/2015 - 05/31/2023	29	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
49	UA	A6	Thallium, total	mg/L	12/10/2015 - 02/28/2023	28	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
49	UA	A6R	Thallium, total	mg/L	12/10/2015 - 05/31/2023	29	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance
50	UA	A6	Antimony, total	mg/L	09/17/2019 - 02/28/2023	13	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance
50	UA	A6R	Antimony, total	mg/L	09/17/2019 - 05/31/2023	14	100	All ND - Last	0.001	0.006	MCL/HBL	No Exceedance

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
 2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT
 OLD WEST ASH POND
 HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
50	UA	A6	Arsenic, total	mg/L	09/17/2019 - 02/28/2023	13	92	Most recent sample	0.001	0.010	MCL/HBL	No Exceedance
50	UA	A6R	Arsenic, total	mg/L	09/17/2019 - 05/31/2023	14	93	CI around median	0.001	0.010	MCL/HBL	No Exceedance
50	UA	A6	Barium, total	mg/L	09/17/2019 - 02/28/2023	13	0	CI around mean	0.0901	2.0	MCL/HBL	No Exceedance
50	UA	A6R	Barium, total	mg/L	09/17/2019 - 05/31/2023	14	0	CI around mean	0.0899	2.0	MCL/HBL	No Exceedance
50	UA	A6	Beryllium, total	mg/L	09/17/2019 - 02/28/2023	12	100	All ND - Last	0.001	0.004	MCL/HBL	No Exceedance
50	UA	A6R	Beryllium, total	mg/L	09/17/2019 - 05/31/2023	13	100	All ND - Last	0.0005	0.004	MCL/HBL	No Exceedance
50	UA	A6	Cadmium, total	mg/L	09/17/2019 - 02/28/2023	13	0	CI around median	0.0012	0.005	MCL/HBL	No Exceedance
50	UA	A6R	Cadmium, total	mg/L	09/17/2019 - 05/31/2023	14	7.1	CI around median	0.0011	0.005	MCL/HBL	No Exceedance
50	UA	A6	Chromium, total	mg/L	09/17/2019 - 02/28/2023	13	100	All ND - Last	0.0015	0.1	MCL/HBL	No Exceedance
50	UA	A6R	Chromium, total	mg/L	09/17/2019 - 05/31/2023	14	100	All ND - Last	0.005	0.1	MCL/HBL	No Exceedance
50	UA	A6	Cobalt, total	mg/L	09/17/2019 - 02/28/2023	13	0	CI around mean	0.00434	0.006	MCL/HBL	No Exceedance
50	UA	A6R	Cobalt, total	mg/L	09/17/2019 - 05/31/2023	14	0	CI around mean	0.00441	0.006	MCL/HBL	No Exceedance
50	UA	A6	Fluoride, total	mg/L	09/17/2019 - 02/28/2023	13	15	CB around linear reg	0.123	4.0	MCL/HBL	No Exceedance
50	UA	A6R	Fluoride, total	mg/L	09/17/2019 - 05/31/2023	14	21	CI around mean	0.0987	4.0	MCL/HBL	No Exceedance
50	UA	A6	Lead, total	mg/L	09/17/2019 - 02/28/2023	13	100	All ND - Last	0.001	0.015	MCL/HBL	No Exceedance
50	UA	A6R	Lead, total	mg/L	09/17/2019 - 05/31/2023	14	100	All ND - Last	0.0075	0.015	MCL/HBL	No Exceedance
50	UA	A6	Lithium, total	mg/L	09/17/2019 - 02/28/2023	13	0	CI around mean	0.0207	0.04	MCL/HBL	No Exceedance
50	UA	A6R	Lithium, total	mg/L	09/17/2019 - 05/31/2023	14	0	CI around median	0.0197	0.04	MCL/HBL	No Exceedance
50	UA	A6	Mercury, total	mg/L	12/11/2019 - 02/28/2023	12	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
50	UA	A6R	Mercury, total	mg/L	12/11/2019 - 05/31/2023	13	100	All ND - Last	0.0002	0.002	MCL/HBL	No Exceedance
50	UA	A6	Molybdenum, total	mg/L	09/17/2019 - 02/28/2023	13	0	CB around linear reg	0.0356	0.1	MCL/HBL	No Exceedance
50	UA	A6R	Molybdenum, total	mg/L	09/17/2019 - 05/31/2023	14	0	CB around T-S line	0.0301	0.1	MCL/HBL	No Exceedance
50	UA	A6	Radium 226 + Radium 228, total	pCi/L	09/17/2019 - 02/28/2023	9	0	CI around mean	0.487	5	MCL/HBL	No Exceedance
50	UA	A6R	Radium 226 + Radium 228, total	pCi/L	09/17/2019 - 05/31/2023	10	0	CI around mean	0.498	5	MCL/HBL	No Exceedance
50	UA	A6	Selenium, total	mg/L	09/17/2019 - 02/28/2023	13	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
50	UA	A6R	Selenium, total	mg/L	09/17/2019 - 05/31/2023	14	100	All ND - Last	0.001	0.05	MCL/HBL	No Exceedance
50	UA	A6	Thallium, total	mg/L	09/17/2019 - 02/28/2023	13	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance

TABLE 6
DETERMINATION OF STATISTICALLY SIGNIFICANT LEVELS
2023 40 C.F.R. § 257 ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	HSU	Event ID	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	SSL Type
50	UA	A6R	Thallium, total	mg/L	09/17/2019 - 05/31/2023	14	100	All ND - Last	0.002	0.002	MCL/HBL	No Exceedance

Notes:
Only SSLs determined in 2023 (see Table A) for 40 C.F.R. § 257 are included
Statistically Significant Level (SSL) Type:
No Exceedance: No exceedance of the GWPS and no resample was collected.
Exceedance Not Confirmed: An exceedance was determined in the parent event, a resample was collected, and the resample did not confirm the exceedance
Confirmed: An exceedance was determined with comparison to a resample. If a determined exceedance is confirmed by resample, both the sample and resample are noted as confirmed.

GWPS = Groundwater Protection Standard
GWPS Source:
MCL/HBL = maximum contaminant level/health-based level

HSU = hydrostratigraphic unit:
UA = Uppermost Aquifer

ID = identification
mg/L = milligrams per liter
ND = non-detect
pCi/L = picocuries per liter
R = resample
Sample Count = number of samples from Sampled Date Range used to calculate the Statistical Result
Statistical Calculation = method used to calculate the statistical result:
All ND - Last = All results were below the reporting limit, and the last determined reporting limit is shown
CB around T-S line = Confidence band around Thiel-Sen line
CB around linear reg = Confidence band around linear regression
CI around geomean = Confidence interval around the geometric mean
CI around mean = Confidence interval around the mean
CI around median = Confidence interval around the median
Most recent sample = Result for the most recently collected sample used due to insufficient data

Statistical Result = calculated in accordance with Statistical Analysis Plan using constituent concentrations observed at monitoring well during all sampling events within the specified date range

Generated 2024-01-22 10:51:49.061639 by banoffra

FIGURES



- BACKGROUND WELL
- COMPLIANCE WELL
- MONITORING WELL
- REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- SITE FEATURE
- PROPERTY BOUNDARY

0 200 400
Feet

MONITORING WELL LOCATION MAP

2023 ANNUAL GROUNDWATER MONITORING
AND CORRECTIVE ACTION REPORT
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

FIGURE 1

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.





- COMPLIANCE MONITORING WELL
- BACKGROUND MONITORING WELL
- MONITORING WELL
- GROUNDWATER ELEVATION CONTOUR (1 FT CONTOUR INTERVAL, NAVD88)
- INFERRED GROUNDWATER ELEVATION CONTOUR
- GROUNDWATER FLOW DIRECTION
- REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- PROPERTY BOUNDARY

NOTES:

1.ELEVATIONS IN PARENTHESES WERE NOT USED FOR CONTOURING.

2. ELEVATION CONTOURS SHOWN IN FEET, NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)

*ILLINOIS RIVER ELEVATION OBTAINED FROM STAFF GAGE SG02, LOCATED AT THE HENNEPIN POWER PLANT

0 200 400 Feet

POTENTIOMETRIC SURFACE MAP FEBRUARY 28 AND MARCH 1, 2023

2023 ANNUAL GROUNDWATER MONITORING
AND CORRECTIVE ACTION REPORT
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

FIGURE 2

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.





- COMPLIANCE MONITORING WELL
- BACKGROUND MONITORING WELL
- MONITORING WELL
- GROUNDWATER ELEVATION CONTOUR (1 FT CONTOUR INTERVAL, NAVD88)
- INFERRED GROUNDWATER ELEVATION CONTOUR
- GROUNDWATER FLOW DIRECTION
- REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- PROPERTY BOUNDARY

NOTES:

- ELEVATIONS IN PARENTHESES WERE NOT USED FOR CONTOURING.
- ELEVATION CONTOURS SHOWN IN FEET, NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)

*ILLINOIS RIVER ELEVATION OBTAINED FROM STAFF GAGE SG02, LOCATED AT THE HENNEPIN POWER PLANT

0 200 400 Feet


**POTENTIOMETRIC SURFACE MAP
MAY 30, 2023**

**2023 ANNUAL GROUNDWATER MONITORING
AND CORRECTIVE ACTION REPORT
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS**

FIGURE 3

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.





Service Layer Credits: Source: Esri, Maxar, Earthstar Geographics, and the GIS User Community

- COMPLIANCE MONITORING WELL
- BACKGROUND MONITORING WELL
- MONITORING WELL
- GROUNDWATER ELEVATION CONTOUR (1 FT CONTOUR INTERVAL, NAVD88)
- INFERRED GROUNDWATER ELEVATION CONTOUR
- GROUNDWATER FLOW DIRECTION
- REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- PROPERTY BOUNDARY

NOTES:

1. ELEVATIONS IN PARENTHESES WERE NOT USED FOR CONTOURING.

2. ELEVATIONS IN BRACKETS WERE OBTAINED OUTSIDE OF THE 24 HOUR PERIOD FROM INITIATION OF DEPTH TO GROUNDWATER MEASUREMENTS BUT WITHIN THE SAME SAMPLING EVENT.

3. ELEVATION CONTOURS SHOWN IN FEET, NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)

*ILLINOIS RIVER ELEVATION OBTAINED FROM STAFF GAGE SG02, LOCATED AT THE HENNEPIN POWER PLANT



POTENTIOMETRIC SURFACE MAP
AUGUST 21 AND 22, 2023


2023 ANNUAL GROUNDWATER MONITORING
AND CORRECTIVE ACTION REPORT
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

FIGURE 4

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.



PROJECT: 169000XXX | DATED: 12/18/2023 | DESIGNER: GALARNMC
Y:\Mapping\Projects\22\2285\MXD\GW_Contours\Round_2023\Hennepin\OWAP_804\HEN 804 OWAP Pot Surface 20231113.mxd



- COMPLIANCE MONITORING WELL
- BACKGROUND MONITORING WELL
- MONITORING WELL
- GROUNDWATER ELEVATION CONTOUR (1 FT CONTOUR INTERVAL, NAVD88)
- INFERRED GROUNDWATER ELEVATION CONTOUR
- GROUNDWATER FLOW DIRECTION
- REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- PROPERTY BOUNDARY

NOTES:

1.ELEVATIONS IN PARENTHESES WERE NOT USED FOR CONTOURING.

2. ELEVATION CONTOURS SHOWN IN FEET, NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)

*ILLINOIS RIVER ELEVATION OBTAINED FROM STAFF GAGE SG02, LOCATED AT THE HENNEPIN POWER PLANT

0 200 400 Feet

POTENTIOMETRIC SURFACE MAP
NOVEMBER 13, 2023

2023 ANNUAL GROUNDWATER MONITORING
AND CORRECTIVE ACTION REPORT
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

FIGURE 5

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.



APPENDICES

APPENDIX A

LABORATORY REPORTS AND FIELD DATA SHEETS

April 14, 2023

Eric Bauer
Ramboll
234 W. Florida St.
Milwaukee, WI 53204
TEL: (414) 837-3614
FAX: (414) 837-3608



Illinois	100226
Kansas	E-10374
Louisiana	05002
Louisiana	05003
Oklahoma	9978

RE: HEN-23Q1

WorkOrder: 23020845

Dear Eric Bauer:

TEKLAB, INC received 51 samples on 3/2/2023 8:00:00 AM for the analysis presented in the following report.

Samples are analyzed on an as received basis unless otherwise requested and documented. The sample results contained in this report relate only to the requested analytes of interest as directed on the chain of custody. NELAP accredited fields of testing are indicated by the letters NELAP under the Certification column. Unless otherwise documented within this report, Teklab Inc. analyzes samples utilizing the most current methods in compliance with 40CFR. All tests are performed in the Collinsville, IL laboratory unless otherwise noted in the Case Narrative.

All quality control criteria applicable to the test methods employed for this project have been satisfactorily met and are in accordance with NELAP except where noted. The following report shall not be reproduced, except in full, without the written approval of Teklab, Inc.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,



Elizabeth A. Hurley
Director of Customer Service
(618)344-1004 ex 33
ehurley@teklabinc.com



Report Contents

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

This reporting package includes the following:

Cover Letter	1
Report Contents	2
Definitions	3
Case Narrative	5
Accreditations	7
Laboratory Results	8
Sample Summary	38
Dates Report	39
Quality Control Results	48
Receiving Check List	85
Chain of Custody	Appended



Definitions

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Abbr Definition

* Analytes on report marked with an asterisk are not NELAP accredited

CCV Continuing calibration verification is a check of a standard to determine the state of calibration of an instrument between recalibration.

CRQL A Client Requested Quantitation Limit is a reporting limit that varies according to customer request. The CRQL may not be less than the MDL.

DF Dilution factor is the dilution performed during analysis only and does not take into account any dilutions made during sample preparation. The reported result is final and includes all dilution factors.

DNI Did not ignite

DUP Laboratory duplicate is a replicate aliquot prepared under the same laboratory conditions and independently analyzed to obtain a measure of precision.

ICV Initial calibration verification is a check of a standard to determine the state of calibration of an instrument before sample analysis is initiated.

IDPH IL Dept. of Public Health

LCS Laboratory control sample is a sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes and analyzed exactly like a sample to establish intra-laboratory or analyst specific precision and bias or to assess the performance of all or a portion of the measurement system.

LCSD Laboratory control sample duplicate is a replicate laboratory control sample that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).

MBLK Method blank is a sample of a matrix similar to the batch of associated sample (when available) that is free from the analytes of interest and is processed simultaneously with and under the same conditions as samples through all steps of the analytical procedures, and in which no target analytes or interferences should present at concentrations that impact the analytical results for sample analyses.

MDL "The method detection limit is defined as the minimum measured concentration of a substance that can be reported with 99% confidence that the measured concentration is distinguishable from method blank results."

MS Matrix spike is an aliquot of matrix fortified (spiked) with known quantities of specific analytes that is subjected to the entire analytical procedures in order to determine the effect of the matrix on an approved test method's recovery system. The acceptable recovery range is listed in the QC Package (provided upon request).

MSD Matrix spike duplicate means a replicate matrix spike that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).

MW Molecular weight

NC Data is not acceptable for compliance purposes

ND Not Detected at the Reporting Limit

NELAP NELAP Accredited

PQL Practical quantitation limit means the lowest level that can be reliably achieved within specified limits of precision and accuracy during routine laboratory operation conditions.

RL The reporting limit the lowest level that the data is displayed in the final report. The reporting limit may vary according to customer request or sample dilution. The reporting limit may not be less than the MDL.

RPD Relative percent difference is a calculated difference between two recoveries (ie. MS/MSD). The acceptable recovery limit is listed in the QC Package (provided upon request).

SPK The spike is a known mass of target analyte added to a blank sample or sub-sample; used to determine recovery deficiency or for other quality control purposes.

Surr Surrogates are compounds which are similar to the analytes of interest in chemical composition and behavior in the analytical process, but which are not normally found in environmental samples.

TIC Tentatively identified compound: Analytes tentatively identified in the sample by using a library search. Only results not in the calibration standard will be reported as tentatively identified compounds. Results for tentatively identified compounds that are not present in the calibration standard, but are assigned a specific chemical name based upon the library search, are calculated using total peak areas from reconstructed ion chromatograms and a response factor of one. The nearest Internal Standard is used for the calculation. The results of any TICs must be considered estimated, and are flagged with a "T". If the estimated result is above the calibration range it is flagged "ET"

TNTC Too numerous to count (> 200 CFU)



Definitions

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Qualifiers

- | | |
|---|--|
| # - Unknown hydrocarbon | B - Analyte detected in associated Method Blank |
| C - RL shown is a Client Requested Quantitation Limit | E - Value above quantitation range |
| H - Holding times exceeded | I - Associated internal standard was outside method criteria |
| J - Analyte detected below quantitation limits | M - Manual Integration used to determine area response |
| ND - Not Detected at the Reporting Limit | R - RPD outside accepted recovery limits |
| S - Spike Recovery outside recovery limits | T - TIC(Tentatively identified compound) |
| X - Value exceeds Maximum Contaminant Level | |



Case Narrative

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Cooler Receipt Temp: 3.2 °C

An employee of Teklab, Inc. collected the sample(s).

55 was measured on 3/1/23 at 1008 per field file. 05DR was collected at 1237 rather than 1257 per field file. EAH 3/21/23

HEN_257_804 data is included in this report. EAH 4/14/23

Locations

Collinsville

Address 5445 Horseshoe Lake Road
Collinsville, IL 62234-7425
Phone (618) 344-1004
Fax (618) 344-1005
Email jhriley@teklabinc.com

Collinsville Air

Address 5445 Horseshoe Lake Road
Collinsville, IL 62234-7425
Phone (618) 344-1004
Fax (618) 344-1005
Email EHurley@teklabinc.com

Springfield

Address 3920 Pintail Dr
Springfield, IL 62711-9415
Phone (217) 698-1004
Fax (217) 698-1005
Email KKlostermann@teklabinc.com

Chicago

Address 1319 Butterfield Rd.
Downers Grove, IL 60515
Phone (630) 324-6855
Fax
Email arenner@teklabinc.com

Kansas City

Address 8421 Nieman Road
Lenexa, KS 66214
Phone (913) 541-1998
Fax (913) 541-1998
Email jhriley@teklabinc.com



Accreditations

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

State	Dept	Cert #	NELAP	Exp Date	Lab
Illinois	IEPA	100226	NELAP	1/31/2024	Collinsville
Kansas	KDHE	E-10374	NELAP	4/30/2023	Collinsville
Louisiana	LDEQ	05002	NELAP	6/30/2023	Collinsville
Louisiana	LDEQ	05003	NELAP	6/30/2023	Collinsville
Oklahoma	ODEQ	9978	NELAP	8/31/2023	Collinsville
Arkansas	ADEQ	88-0966		3/14/2024	Collinsville
Illinois	IDPH	17584		5/31/2023	Collinsville
Iowa	IDNR	430		6/1/2024	Collinsville
Kentucky	UST	0073		1/31/2024	Collinsville
Missouri	MDNR	00930		5/31/2023	Collinsville
Missouri	MDNR	930		1/31/2025	Collinsville



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804
Laboratory Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-009

Client Sample ID: 22

Matrix: GROUNDWATER

Collection Date: 02/28/2023 11:28

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		17.30	ft	1	02/28/2023 11:28	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		7.58		1	02/28/2023 11:28	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		< 1.0	NTU	1	02/28/2023 11:28	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		51.9	mV	1	02/28/2023 11:28	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1295	µS/cm	1	02/28/2023 11:28	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		14.8	°C	1	02/28/2023 11:28	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		0.30	mg/L	1	02/28/2023 11:28	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		237	mg/L	1	03/06/2023 10:05	R325659
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/06/2023 10:05	R325659
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		598	mg/L	1	03/02/2023 11:25	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	50		145	mg/L	5	03/07/2023 16:45	R325693
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.16	mg/L	1	03/02/2023 13:00	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		100	mg/L	5	03/07/2023 16:45	R325696
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		102	mg/L	1	03/03/2023 17:17	203466
Magnesium	NELAP	0.050		34.0	mg/L	1	03/03/2023 17:17	203466
Potassium	NELAP	0.500		11.5	mg/L	5	03/06/2023 15:04	203466
Sodium	NELAP	0.050		57.4	mg/L	1	03/03/2023 17:17	203466
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0	J	1.0	µg/L	5	03/03/2023 14:48	203466
Arsenic	NELAP	1.0		1.4	µg/L	5	03/03/2023 14:48	203466
Barium	NELAP	1.0		90.0	µg/L	5	03/03/2023 14:48	203466
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 11:44	203466
Boron	NELAP	25.0		4510	µg/L	5	03/16/2023 13:57	203466
Cadmium	NELAP	1.0		9.6	µg/L	5	03/03/2023 14:48	203466
Chromium	NELAP	1.5		< 1.5	µg/L	5	03/06/2023 11:44	203466
Cobalt	NELAP	1.0		3.8	µg/L	5	03/03/2023 14:48	203466
Lead	NELAP	1.0	J	0.7	µg/L	5	03/03/2023 14:48	203466
Lithium	*	3.0		41.9	µg/L	5	03/06/2023 11:44	203466
Molybdenum	NELAP	1.5		156	µg/L	5	03/03/2023 14:48	203466
Selenium	NELAP	1.0		32.2	µg/L	5	03/03/2023 14:48	203466
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 14:48	203466



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-009
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 22
Collection Date: 02/28/2023 11:28

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/06/2023 20:37	203469



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-010

Client Sample ID: 23

Matrix: GROUNDWATER

Collection Date: 02/28/2023 10:35

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		16.70	ft	1	02/28/2023 10:35	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		7.38		1	02/28/2023 10:35	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		< 1.0	NTU	1	02/28/2023 10:35	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		-124.9	mV	1	02/28/2023 10:35	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1657	µS/cm	1	02/28/2023 10:35	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		12.5	°C	1	02/28/2023 10:35	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		0.30	mg/L	1	02/28/2023 10:35	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		171	mg/L	1	03/06/2023 10:12	R325659
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/06/2023 10:12	R325659
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		856	mg/L	1	03/02/2023 11:26	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	100		433	mg/L	10	03/07/2023 16:58	R325693
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.17	mg/L	1	03/02/2023 13:05	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		66	mg/L	5	03/07/2023 16:53	R325696
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		122	mg/L	1	03/03/2023 17:21	203466
Magnesium	NELAP	0.050		80.5	mg/L	1	03/03/2023 17:21	203466
Potassium	NELAP	0.100		2.99	mg/L	1	03/06/2023 13:48	203466
Sodium	NELAP	0.050		46.3	mg/L	1	03/03/2023 17:21	203466
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 14:54	203466
Arsenic	NELAP	1.0		1.3	µg/L	5	03/03/2023 14:54	203466
Barium	NELAP	1.0		68.5	µg/L	5	03/03/2023 14:54	203466
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 11:50	203466
Boron	NELAP	25.0		12800	µg/L	5	03/22/2023 2:23	204109
Cadmium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 14:54	203466
Chromium	NELAP	1.5		< 1.5	µg/L	5	03/06/2023 11:50	203466
Cobalt	NELAP	1.0	J	0.4	µg/L	5	03/03/2023 14:54	203466
Lead	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 14:54	203466
Lithium	*	3.0		4.2	µg/L	5	03/06/2023 11:50	203466
Molybdenum	NELAP	1.5		21.3	µg/L	5	03/03/2023 14:54	203466
Selenium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 14:54	203466
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 14:54	203466



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-010
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 23
Collection Date: 02/28/2023 10:35

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/06/2023 20:40	203469



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-011

Client Sample ID: 25

Matrix: GROUNDWATER

Collection Date: 02/28/2023 14:35

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		15.87	ft	1	02/28/2023 14:35	R325999



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-012

Client Sample ID: 26

Matrix: GROUNDWATER

Collection Date: 02/28/2023 14:36

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		15.95	ft	1	02/28/2023 14:36	R325999



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-013

Client Sample ID: 27

Matrix: GROUNDWATER

Collection Date: 02/28/2023 13:47

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		3.90	ft	1	02/28/2023 13:47	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		7.05		1	02/28/2023 13:47	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		8.96	NTU	1	02/28/2023 13:47	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		-49.1	mV	1	02/28/2023 13:47	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1475	µS/cm	1	02/28/2023 13:47	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		11.6	°C	1	02/28/2023 13:47	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		0.22	mg/L	1	02/28/2023 13:47	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		323	mg/L	1	03/03/2023 15:28	R325591
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/03/2023 15:28	R325591
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		636	mg/L	1	03/02/2023 12:08	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	50		159	mg/L	5	03/07/2023 17:01	R325693
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.13	mg/L	1	03/02/2023 12:01	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		99	mg/L	5	03/07/2023 17:00	R325696
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		141	mg/L	1	03/03/2023 17:39	203466
Magnesium	NELAP	0.050		39.6	mg/L	1	03/03/2023 17:39	203466
Potassium	NELAP	0.100		3.08	mg/L	1	03/06/2023 13:52	203466
Sodium	NELAP	0.050		51.1	mg/L	1	03/03/2023 17:39	203466
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 15:00	203466
Arsenic	NELAP	1.0		1.3	µg/L	5	03/03/2023 15:00	203466
Barium	NELAP	1.0		97.1	µg/L	5	03/03/2023 15:00	203466
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 11:56	203466
Boron	NELAP	25.0		2730	µg/L	5	03/06/2023 11:56	203466
Cadmium	NELAP	1.0	J	0.3	µg/L	5	03/03/2023 15:00	203466
Chromium	NELAP	1.5		1.6	µg/L	5	03/06/2023 11:56	203466
Cobalt	NELAP	1.0		2.1	µg/L	5	03/03/2023 15:00	203466
Lead	NELAP	1.0	J	1.0	µg/L	5	03/06/2023 11:56	203466
Lithium	*	3.0		17.4	µg/L	5	03/06/2023 11:56	203466
Molybdenum	NELAP	1.5		5.2	µg/L	5	03/03/2023 15:00	203466
Selenium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 15:00	203466
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 15:00	203466



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-013
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 27
Collection Date: 02/28/2023 13:47

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/06/2023 20:42	203469



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-014
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 30
Collection Date: 02/28/2023 12:49

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		6.48	ft	1	02/28/2023 12:49	R325999



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-015
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 31
Collection Date: 02/28/2023 12:50

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		6.42	ft	1	02/28/2023 12:50	R325999



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-016

Client Sample ID: 32

Matrix: GROUNDWATER

Collection Date: 02/28/2023 13:06

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		4.62	ft	1	02/28/2023 13:06	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		7.02		1	02/28/2023 13:06	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		9.62	NTU	1	02/28/2023 13:06	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		116.1	mV	1	02/28/2023 13:06	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1317	µS/cm	1	02/28/2023 13:06	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		10.2	°C	1	02/28/2023 13:06	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		0.39	mg/L	1	02/28/2023 13:06	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		341	mg/L	1	03/03/2023 15:35	R325591
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/03/2023 15:35	R325591
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		564	mg/L	1	03/02/2023 12:08	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	50		82	mg/L	5	03/07/2023 17:14	R325693
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.13	mg/L	1	03/02/2023 13:13	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		83	mg/L	5	03/07/2023 17:14	R325696
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		122	mg/L	1	03/03/2023 17:43	203466
Magnesium	NELAP	0.050		42.4	mg/L	1	03/03/2023 17:43	203466
Potassium	NELAP	0.100		1.95	mg/L	1	03/06/2023 15:15	203466
Sodium	NELAP	0.050		39.7	mg/L	1	03/03/2023 17:43	203466
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 15:50	203466
Arsenic	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 15:50	203466
Barium	NELAP	1.0		59.0	µg/L	5	03/03/2023 15:50	203466
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 13:20	203466
Boron	NELAP	25.0		199	µg/L	5	03/22/2023 2:54	204109
Cadmium	NELAP	1.0	J	0.2	µg/L	5	03/03/2023 15:50	203466
Chromium	NELAP	1.5	J	1.4	µg/L	5	03/06/2023 13:20	203466
Cobalt	NELAP	1.0		2.9	µg/L	5	03/03/2023 15:50	203466
Lead	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 15:50	203466
Lithium	*	3.0		3.1	µg/L	5	03/06/2023 13:20	203466
Molybdenum	NELAP	1.5	J	0.7	µg/L	5	03/03/2023 15:50	203466
Selenium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 15:50	203466
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 15:50	203466

CCV recovered outside the upper control limits for Pb. Sample results are below the reporting limit. Data is reportable per the TNI standard.



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-016
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 32
Collection Date: 02/28/2023 13:06

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/06/2023 20:49	203469



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-017
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 33
Collection Date: 02/28/2023 13:15

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		3.50	ft	1	02/28/2023 13:15	R325999



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-018

Client Sample ID: 34

Matrix: GROUNDWATER

Collection Date: 02/28/2023 14:21

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		2.45	ft	1	02/28/2023 14:21	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		6.92		1	02/28/2023 14:21	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		8.83	NTU	1	02/28/2023 14:21	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		-84.5	mV	1	02/28/2023 14:21	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1703	µS/cm	1	02/28/2023 14:21	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		11.2	°C	1	02/28/2023 14:21	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		0.43	mg/L	1	02/28/2023 14:21	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		575	mg/L	1	03/03/2023 15:43	R325591
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/03/2023 15:43	R325591
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	50		685	mg/L	2.5	03/02/2023 12:09	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	10		48	mg/L	1	03/07/2023 17:17	R325693
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.16	mg/L	1	03/02/2023 13:15	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		80	mg/L	5	03/07/2023 17:35	R325696
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		184	mg/L	1	03/03/2023 17:47	203466
Magnesium	NELAP	0.050		47.7	mg/L	1	03/03/2023 17:47	203466
Potassium	NELAP	0.100		0.423	mg/L	1	03/06/2023 15:18	203466
Sodium	NELAP	0.050		54.7	mg/L	1	03/03/2023 17:47	203466
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 15:57	203466
Arsenic	NELAP	1.0	J	0.7	µg/L	5	03/03/2023 15:57	203466
Barium	NELAP	1.0		139	µg/L	5	03/03/2023 15:57	203466
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 13:26	203466
Boron	NELAP	25.0		206	µg/L	5	03/22/2023 2:36	204109
Cadmium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 15:57	203466
Chromium	NELAP	1.5		< 1.5	µg/L	5	03/06/2023 13:26	203466
Cobalt	NELAP	1.0	J	0.3	µg/L	5	03/03/2023 15:57	203466
Lead	NELAP	1.0	J	0.6	µg/L	5	03/03/2023 15:57	203466
Lithium	*	3.0		11.1	µg/L	5	03/06/2023 13:26	203466
Molybdenum	NELAP	1.5		1.7	µg/L	5	03/03/2023 15:57	203466
Selenium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 15:57	203466
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 15:57	203466

CCV recovered outside the upper control limits for Pb. Sample results are below the reporting limit. Data is reportable per the TNI standard.



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-018
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 34
Collection Date: 02/28/2023 14:21

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/06/2023 20:56	203469



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-019

Client Sample ID: 35

Matrix: GROUNDWATER

Collection Date: 02/28/2023 12:33

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		8.20	ft	1	02/28/2023 12:33	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		6.98		1	02/28/2023 12:33	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		3.83	NTU	1	02/28/2023 12:33	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		108.2	mV	1	02/28/2023 12:33	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1732	µS/cm	1	02/28/2023 12:33	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		11.1	°C	1	02/28/2023 12:33	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		0.95	mg/L	1	02/28/2023 12:33	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		269	mg/L	1	03/06/2023 10:18	R325659
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/06/2023 10:18	R325659
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		918	mg/L	1	03/02/2023 12:09	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	200		476	mg/L	20	03/07/2023 17:43	R325693
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.19	mg/L	1	03/02/2023 13:17	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	1		26	mg/L	1	03/07/2023 17:38	R325696
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		268	mg/L	1	03/03/2023 17:50	203466
Magnesium	NELAP	0.050		30.6	mg/L	1	03/03/2023 17:50	203466
Potassium	NELAP	0.500		10.2	mg/L	5	03/06/2023 15:07	203466
Sodium	NELAP	0.050		25.6	mg/L	1	03/03/2023 17:50	203466
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 16:03	203466
Arsenic	NELAP	1.0	J	0.8	µg/L	5	03/03/2023 16:03	203466
Barium	NELAP	1.0		59.1	µg/L	5	03/03/2023 16:03	203466
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 13:33	203466
Boron	NELAP	25.0		9580	µg/L	5	03/22/2023 2:42	204109
Cadmium	NELAP	1.0	J	0.5	µg/L	5	03/03/2023 16:03	203466
Chromium	NELAP	1.5		< 1.5	µg/L	5	03/06/2023 13:33	203466
Cobalt	NELAP	1.0		1.4	µg/L	5	03/03/2023 16:03	203466
Lead	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 16:03	203466
Lithium	*	3.0		12.8	µg/L	5	03/06/2023 13:33	203466
Molybdenum	NELAP	1.5		71.1	µg/L	5	03/03/2023 16:03	203466
Selenium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 16:03	203466
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 16:03	203466

CCV recovered outside the upper control limits for Pb. Sample results are below the reporting limit. Data is reportable per the TNI standard.



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-019
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 35
Collection Date: 02/28/2023 12:33

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/06/2023 20:58	203469



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-020
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 36
Collection Date: 02/28/2023 12:20

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		15.28	ft	1	02/28/2023 12:20	R325999



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-024
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 49
Collection Date: 02/28/2023 11:01

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		21.30	ft	1	02/28/2023 11:01	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		6.98		1	02/28/2023 11:01	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		42.02	NTU	1	02/28/2023 11:01	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		33.4	mV	1	02/28/2023 11:01	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1449	µS/cm	1	02/28/2023 11:01	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		13.9	°C	1	02/28/2023 11:01	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		0.35	mg/L	1	02/28/2023 11:01	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		347	mg/L	1	03/03/2023 15:58	R325591
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/03/2023 15:58	R325591
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		618	mg/L	1	03/02/2023 12:10	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	50		108	mg/L	5	03/07/2023 18:12	R325693
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.15	mg/L	1	03/02/2023 13:23	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		104	mg/L	5	03/07/2023 18:12	R325696
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		127	mg/L	1	03/03/2023 18:27	203466
Magnesium	NELAP	0.050		36.3	mg/L	1	03/03/2023 18:27	203466
Potassium	NELAP	0.500		14.7	mg/L	5	03/06/2023 15:11	203466
Sodium	NELAP	0.050		62.8	mg/L	1	03/03/2023 18:27	203466
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 16:22	203466
Arsenic	NELAP	1.0	J	0.6	µg/L	5	03/03/2023 16:22	203466
Barium	NELAP	1.0		82.7	µg/L	5	03/03/2023 16:22	203466
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 13:52	203466
Boron	NELAP	25.0		703	µg/L	5	03/22/2023 2:48	204109
Cadmium	NELAP	1.0		2.5	µg/L	5	03/03/2023 16:22	203466
Chromium	NELAP	1.5	J	1.3	µg/L	5	03/06/2023 13:52	203466
Cobalt	NELAP	1.0		3.7	µg/L	5	03/06/2023 13:52	203466
Lead	NELAP	1.0	J	0.8	µg/L	5	03/03/2023 16:22	203466
Lithium	*	3.0		20.7	µg/L	5	03/06/2023 13:52	203466
Molybdenum	NELAP	1.5		35.5	µg/L	5	03/03/2023 16:22	203466
Selenium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 16:22	203466
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 16:22	203466

CCV recovered outside the upper control limits for Pb. Sample results are below the reporting limit. Data is reportable per the TNI standard.



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-024
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23

Client Sample ID: 49

Collection Date: 02/28/2023 11:01

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/06/2023 21:09	203470



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-025

Client Sample ID: 50

Matrix: GROUNDWATER

Collection Date: 02/28/2023 12:10

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		16.74	ft	1	02/28/2023 12:10	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		7.41		1	02/28/2023 12:10	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		9.41	NTU	1	02/28/2023 12:10	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		24.1	mV	1	02/28/2023 12:10	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1287	µS/cm	1	02/28/2023 12:10	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		14.7	°C	1	02/28/2023 12:10	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		0.33	mg/L	1	02/28/2023 12:10	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		251	mg/L	1	03/03/2023 16:05	R325591
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/03/2023 16:05	R325591
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		580	mg/L	1	03/02/2023 12:54	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	50		136	mg/L	5	03/07/2023 18:55	R325693
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.14	mg/L	1	03/02/2023 13:25	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		101	mg/L	5	03/07/2023 18:55	R325696
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		121	mg/L	1	03/03/2023 18:31	203466
Magnesium	NELAP	0.050		27.4	mg/L	1	03/03/2023 18:31	203466
Potassium	NELAP	0.100		9.20	mg/L	1	03/06/2023 16:30	203466
Sodium	NELAP	0.050		56.5	mg/L	1	03/03/2023 18:31	203466
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 16:28	203466
Arsenic	NELAP	1.0		1.0	µg/L	5	03/03/2023 16:28	203466
Barium	NELAP	1.0		103	µg/L	5	03/03/2023 16:28	203466
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 13:58	203466
Boron	NELAP	25.0		1430	µg/L	5	03/06/2023 13:58	203466
Cadmium	NELAP	1.0		3.7	µg/L	5	03/03/2023 16:28	203466
Chromium	NELAP	1.5		< 1.5	µg/L	5	03/06/2023 13:58	203466
Cobalt	NELAP	1.0		9.9	µg/L	5	03/03/2023 16:28	203466
Lead	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 13:58	203466
Lithium	*	3.0		24.2	µg/L	5	03/06/2023 13:58	203466
Molybdenum	NELAP	1.5		97.1	µg/L	5	03/03/2023 16:28	203466
Selenium	NELAP	1.0	J	0.7	µg/L	5	03/03/2023 16:28	203466
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 16:28	203466



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-025
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 50
Collection Date: 02/28/2023 12:10

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/06/2023 21:16	203470



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-026

Client Sample ID: 51

Matrix: GROUNDWATER

Collection Date: 02/28/2023 10:03

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		17.91	ft	1	02/28/2023 10:03	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		7.23		1	02/28/2023 10:03	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		21.13	NTU	1	02/28/2023 10:03	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		-119.3	mV	1	02/28/2023 10:03	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1477	µS/cm	1	02/28/2023 10:03	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		11.2	°C	1	02/28/2023 10:03	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		1.08	mg/L	1	02/28/2023 10:03	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		357	mg/L	1	03/06/2023 10:39	R325659
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/06/2023 10:39	R325659
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		630	mg/L	1	03/02/2023 12:55	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	50		105	mg/L	5	03/07/2023 18:58	R325693
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.14	mg/L	1	03/02/2023 13:37	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		110	mg/L	5	03/07/2023 18:57	R325696
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		132	mg/L	1	03/03/2023 18:35	203466
Magnesium	NELAP	0.050		39.8	mg/L	1	03/03/2023 18:35	203466
Potassium	NELAP	0.100		6.55	mg/L	1	03/06/2023 16:33	203466
Sodium	NELAP	0.050		59.3	mg/L	1	03/03/2023 18:35	203466
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 17:36	203466
Arsenic	NELAP	1.0		30.8	µg/L	5	03/03/2023 17:36	203466
Barium	NELAP	1.0		134	µg/L	5	03/03/2023 17:36	203466
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 14:04	203466
Boron	NELAP	25.0		1540	µg/L	5	03/06/2023 14:04	203466
Cadmium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 17:36	203466
Chromium	NELAP	1.5	J	0.7	µg/L	5	03/06/2023 14:04	203466
Cobalt	NELAP	1.0	J	0.9	µg/L	5	03/03/2023 17:36	203466
Lead	NELAP	1.0	J	0.9	µg/L	5	03/06/2023 14:04	203466
Lithium	*	3.0		21.0	µg/L	5	03/06/2023 14:04	203466
Molybdenum	NELAP	1.5		13.5	µg/L	5	03/03/2023 17:36	203466
Selenium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 17:36	203466
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 17:36	203466



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-026
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 51
Collection Date: 02/28/2023 10:03

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/07/2023 5:12	203470



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab ID: 23020845-036

Client Sample ID: 21R

Matrix: GROUNDWATER

Collection Date: 02/28/2023 9:18

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		5.25	ft	1	02/28/2023 9:18	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		7.33		1	02/28/2023 9:18	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		121.3	NTU	1	02/28/2023 9:18	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		-143.2	mV	1	02/28/2023 9:18	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1517	µS/cm	1	02/28/2023 9:18	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		10.9	°C	1	02/28/2023 9:18	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		1.21	mg/L	1	02/28/2023 9:18	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		378	mg/L	1	03/03/2023 16:46	R325591
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/03/2023 16:46	R325591
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		678	mg/L	1	03/02/2023 13:36	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	50		105	mg/L	5	03/08/2023 11:49	R325765
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.15	mg/L	1	03/02/2023 14:03	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		108	mg/L	5	03/08/2023 11:49	R325771
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		147	mg/L	1	03/03/2023 19:42	203468
Magnesium	NELAP	0.050		44.7	mg/L	1	03/03/2023 19:42	203468
Potassium	NELAP	0.100		2.91	mg/L	1	03/06/2023 18:02	203468
Sodium	NELAP	0.050		52.5	mg/L	1	03/03/2023 19:42	203468
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:07	203468
Arsenic	NELAP	1.0		34.5	µg/L	5	03/03/2023 13:07	203468
Barium	NELAP	1.0		398	µg/L	5	03/03/2023 13:07	203468
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 16:25	203468
Boron	NELAP	25.0		3280	µg/L	5	03/22/2023 4:13	204109
Cadmium	NELAP	1.0	J	0.2	µg/L	5	03/03/2023 13:07	203468
Chromium	NELAP	1.5		2.4	µg/L	5	03/06/2023 16:25	203468
Cobalt	NELAP	1.0		1.7	µg/L	5	03/03/2023 13:07	203468
Lead	NELAP	1.0		5.4	µg/L	5	03/03/2023 13:07	203468
Lithium	*	3.0		19.9	µg/L	5	03/06/2023 16:25	203468
Molybdenum	NELAP	1.5		10.9	µg/L	5	03/03/2023 13:07	203468
Selenium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:07	203468
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 13:07	203468



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-036
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 21R
Collection Date: 02/28/2023 9:18

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/07/2023 5:46	203470



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-037
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 22D
Collection Date: 02/28/2023 11:44

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		18.45	ft	1	02/28/2023 11:44	R325999
STANDARD METHOD 4500-H B 2001 FIELD								
pH	*	1.00		7.19		1	02/28/2023 11:44	R325999
STANDARD METHODS 2130 B FIELD								
Turbidity	*	1.0		9.36	NTU	1	02/28/2023 11:44	R325999
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential	*	-300		-107.2	mV	1	02/28/2023 11:44	R325999
STANDARD METHODS 2510 B FIELD								
Spec. Conductance, Field	*	0		1459	µS/cm	1	02/28/2023 11:44	R325999
STANDARD METHODS 2550 B FIELD								
Temperature	*	0		14.8	°C	1	02/28/2023 11:44	R325999
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved	*	0		0.40	mg/L	1	02/28/2023 11:44	R325999
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		341	mg/L	1	03/03/2023 16:54	R325591
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/03/2023 16:54	R325591
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		680	mg/L	1	03/02/2023 13:36	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	50		112	mg/L	5	03/08/2023 11:55	R325765
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.11	mg/L	1	03/02/2023 14:05	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		113	mg/L	5	03/08/2023 11:55	R325771
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		137	mg/L	1	03/03/2023 19:45	203468
Magnesium	NELAP	0.050		42.2	mg/L	1	03/03/2023 19:45	203468
Potassium	NELAP	0.100		3.30	mg/L	1	03/06/2023 18:06	203468
Sodium	NELAP	0.050		48.9	mg/L	1	03/03/2023 19:45	203468
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:14	203468
Arsenic	NELAP	1.0		1.6	µg/L	5	03/03/2023 13:14	203468
Barium	NELAP	1.0		78.3	µg/L	5	03/03/2023 13:14	203468
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 16:32	203468
Boron	NELAP	25.0		2400	µg/L	5	03/22/2023 4:20	204109
Cadmium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:14	203468
Chromium	NELAP	1.5		< 1.5	µg/L	5	03/06/2023 16:32	203468
Cobalt	NELAP	1.0	J	0.5	µg/L	5	03/03/2023 13:14	203468
Lead	NELAP	1.0	J	0.6	µg/L	5	03/03/2023 13:14	203468
Lithium	*	3.0		12.9	µg/L	5	03/06/2023 16:32	203468
Molybdenum	NELAP	1.5		8.2	µg/L	5	03/03/2023 13:14	203468
Selenium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:14	203468
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 13:14	203468



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-037
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: 22D
Collection Date: 02/28/2023 11:44

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/07/2023 5:53	203470



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-040
Matrix: GROUNDWATER

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: SG02
Collection Date: 03/02/2023 7:30

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to water from measuring point	*	0		449.50	ft	1	03/02/2023 7:30	R325999



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020845-051
Matrix: AQUEOUS

Work Order: 23020845
Report Date: 14-Apr-23
Client Sample ID: Field Blank
Collection Date: 03/01/2023 17:01

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
STANDARD METHODS 2320 B (TOTAL) 1997, 2011								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		1	mg/L	1	03/07/2023 8:46	R325659
STANDARD METHODS 2320 B 1997, 2011								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	03/07/2023 8:46	R325659
STANDARD METHODS 2540 C (TOTAL) 1997, 2011								
Total Dissolved Solids	NELAP	20		< 20	mg/L	1	03/02/2023 14:09	R325574
SW-846 9036 (TOTAL)								
Sulfate	NELAP	10		< 10	mg/L	1	03/08/2023 13:33	R325765
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		< 0.10	mg/L	1	03/02/2023 14:29	R325510
SW-846 9251 (TOTAL)								
Chloride	NELAP	1		< 1	mg/L	1	03/08/2023 13:33	R325771
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.100		< 0.100	mg/L	1	03/03/2023 20:34	203468
Magnesium	NELAP	0.050		< 0.050	mg/L	1	03/03/2023 20:34	203468
Potassium	NELAP	0.100		< 0.100	mg/L	1	03/06/2023 18:21	203468
Sodium	NELAP	0.050		< 0.050	mg/L	1	03/03/2023 20:34	203468
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:45	203468
Arsenic	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:45	203468
Barium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:45	203468
Beryllium	NELAP	1.0		< 1.0	µg/L	5	03/06/2023 18:08	203468
Boron	NELAP	25.0		< 25.0	µg/L	5	03/07/2023 9:57	203468
Cadmium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:45	203468
Chromium	NELAP	1.5		< 1.5	µg/L	5	03/06/2023 18:08	203468
Cobalt	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:45	203468
Lead	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:45	203468
Lithium	*	3.0		< 3.0	µg/L	5	03/07/2023 9:57	203468
Molybdenum	NELAP	1.5		< 1.5	µg/L	5	03/03/2023 13:45	203468
Selenium	NELAP	1.0		< 1.0	µg/L	5	03/03/2023 13:45	203468
Thallium	NELAP	2.0		< 2.0	µg/L	5	03/03/2023 13:45	203468
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	03/06/2023 19:27	203471



Sample Summary

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

Lab Sample ID	Client Sample ID	Matrix	Fractions	Collection Date
23020845-009	22	Groundwater	4	02/28/2023 11:28
23020845-010	23	Groundwater	4	02/28/2023 10:35
23020845-011	25	Groundwater	1	02/28/2023 14:35
23020845-012	26	Groundwater	1	02/28/2023 14:36
23020845-013	27	Groundwater	4	02/28/2023 13:47
23020845-014	30	Groundwater	1	02/28/2023 12:49
23020845-015	31	Groundwater	1	02/28/2023 12:50
23020845-016	32	Groundwater	4	02/28/2023 13:06
23020845-017	33	Groundwater	1	02/28/2023 13:15
23020845-018	34	Groundwater	4	02/28/2023 14:21
23020845-019	35	Groundwater	4	02/28/2023 12:33
23020845-020	36	Groundwater	1	02/28/2023 12:20
23020845-024	49	Groundwater	4	02/28/2023 11:01
23020845-025	50	Groundwater	4	02/28/2023 12:10
23020845-026	51	Groundwater	4	02/28/2023 10:03
23020845-036	21R	Groundwater	4	02/28/2023 9:18
23020845-037	22D	Groundwater	4	02/28/2023 11:44
23020845-040	SG02	Groundwater	1	03/02/2023 7:30
23020845-051	Field Blank	Aqueous	9	03/01/2023 17:01



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
23020845-009A	22	02/28/2023 11:28	03/02/2023 8:00		
	Field Elevation Measurements				02/28/2023 11:28
	Standard Method 4500-H B 2001 Field				02/28/2023 11:28
	Standard Methods 2130 B Field				02/28/2023 11:28
	Standard Methods 18th Ed. 2580 B Field				02/28/2023 11:28
	Standard Methods 2320 B (Total) 1997, 2011				03/06/2023 10:05
	Standard Methods 2320 B 1997, 2011				03/06/2023 10:05
	Standard Methods 2510 B Field				02/28/2023 11:28
	Standard Methods 2540 C (Total) 1997, 2011				03/02/2023 11:25
	Standard Methods 2550 B Field				02/28/2023 11:28
	Standard Methods 4500-O G Field				02/28/2023 11:28
	SW-846 9036 (Total)				03/07/2023 16:45
	SW-846 9214 (Total)				03/02/2023 13:00
	SW-846 9251 (Total)				03/07/2023 16:45
23020845-009B	22	02/28/2023 11:28	03/02/2023 8:00		
	SW-846 9251 (Dissolved)				03/07/2023 12:45
23020845-009C	22	02/28/2023 11:28	03/02/2023 8:00		
	SW-846 3005A, 6010B, Metals by ICP (Total)			03/02/2023 9:03	03/03/2023 17:17
	SW-846 3005A, 6010B, Metals by ICP (Total)			03/02/2023 9:03	03/06/2023 15:04
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/02/2023 9:03	03/03/2023 14:48
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/02/2023 9:03	03/06/2023 11:44
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/02/2023 9:03	03/16/2023 13:57
	SW-846 7470A (Total)			03/02/2023 9:08	03/06/2023 20:37
23020845-009D	22	02/28/2023 11:28	03/02/2023 8:00		
	SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)			03/02/2023 9:16	03/02/2023 19:02
23020845-010A	23	02/28/2023 10:35	03/02/2023 8:00		
	Field Elevation Measurements				02/28/2023 10:35
	Standard Method 4500-H B 2001 Field				02/28/2023 10:35
	Standard Methods 2130 B Field				02/28/2023 10:35
	Standard Methods 18th Ed. 2580 B Field				02/28/2023 10:35
	Standard Methods 2320 B (Total) 1997, 2011				03/06/2023 10:12
	Standard Methods 2320 B 1997, 2011				03/06/2023 10:12
	Standard Methods 2510 B Field				02/28/2023 10:35
	Standard Methods 2540 C (Total) 1997, 2011				03/02/2023 11:26
	Standard Methods 2550 B Field				02/28/2023 10:35
	Standard Methods 4500-O G Field				02/28/2023 10:35
	SW-846 9036 (Total)				03/07/2023 16:58



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
Test Name				Prep Date/Time	Analysis Date/Time
SW-846 9214 (Total)					03/02/2023 13:05
SW-846 9251 (Total)					03/07/2023 16:53
23020845-010B	23	02/28/2023 10:35	03/02/2023 8:00		
SW-846 9251 (Dissolved)					03/07/2023 12:47
23020845-010C	23	02/28/2023 10:35	03/02/2023 8:00		
SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:03	03/03/2023 17:21
SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:03	03/06/2023 13:48
SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:03	03/03/2023 14:54
SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:03	03/06/2023 11:50
SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/20/2023 19:16	03/22/2023 2:23
SW-846 7470A (Total)				03/02/2023 9:08	03/06/2023 20:40
23020845-010D	23	02/28/2023 10:35	03/02/2023 8:00		
SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)				03/02/2023 9:16	03/02/2023 19:08
23020845-011A	25	02/28/2023 14:35	03/02/2023 8:00		
Field Elevation Measurements					02/28/2023 14:35
23020845-012A	26	02/28/2023 14:36	03/02/2023 8:00		
Field Elevation Measurements					02/28/2023 14:36
23020845-013A	27	02/28/2023 13:47	03/02/2023 8:00		
Field Elevation Measurements					02/28/2023 13:47
Standard Method 4500-H B 2001 Field					02/28/2023 13:47
Standard Methods 2130 B Field					02/28/2023 13:47
Standard Methods 18th Ed. 2580 B Field					02/28/2023 13:47
Standard Methods 2320 B (Total) 1997, 2011					03/03/2023 15:28
Standard Methods 2320 B 1997, 2011					03/03/2023 15:28
Standard Methods 2510 B Field					02/28/2023 13:47
Standard Methods 2540 C (Total) 1997, 2011					03/02/2023 12:08
Standard Methods 2550 B Field					02/28/2023 13:47
Standard Methods 4500-O G Field					02/28/2023 13:47
SW-846 9036 (Total)					03/07/2023 17:01
SW-846 9214 (Total)					03/02/2023 12:01
SW-846 9251 (Total)					03/07/2023 17:00
23020845-013B	27	02/28/2023 13:47	03/02/2023 8:00		
SW-846 9251 (Dissolved)					03/07/2023 13:11
23020845-013C	27	02/28/2023 13:47	03/02/2023 8:00		
SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:03	03/03/2023 17:39
SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:03	03/06/2023 13:52
SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:03	03/03/2023 15:00



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Sample ID	Client Sample ID	Collection Date	Received Date	Test Name	Prep Date/Time	Analysis Date/Time
				SW-846 3005A, 6020A, Metals by ICPMS (Total)	03/02/2023 9:03	03/06/2023 11:56
				SW-846 7470A (Total)	03/02/2023 9:08	03/06/2023 20:42
23020845-013D	27	02/28/2023 13:47	03/02/2023 8:00			
				SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)	03/20/2023 21:00	03/22/2023 5:39
23020845-014A	30	02/28/2023 12:49	03/02/2023 8:00			
				Field Elevation Measurements		02/28/2023 12:49
23020845-015A	31	02/28/2023 12:50	03/02/2023 8:00			
				Field Elevation Measurements		02/28/2023 12:50
23020845-016A	32	02/28/2023 13:06	03/02/2023 8:00			
				Field Elevation Measurements		02/28/2023 13:06
				Standard Method 4500-H B 2001 Field		02/28/2023 13:06
				Standard Methods 2130 B Field		02/28/2023 13:06
				Standard Methods 18th Ed. 2580 B Field		02/28/2023 13:06
				Standard Methods 2320 B (Total) 1997, 2011		03/03/2023 15:35
				Standard Methods 2320 B 1997, 2011		03/03/2023 15:35
				Standard Methods 2510 B Field		02/28/2023 13:06
				Standard Methods 2540 C (Total) 1997, 2011		03/02/2023 12:08
				Standard Methods 2550 B Field		02/28/2023 13:06
				Standard Methods 4500-O G Field		02/28/2023 13:06
				SW-846 9036 (Total)		03/07/2023 17:14
				SW-846 9214 (Total)		03/02/2023 13:13
				SW-846 9251 (Total)		03/07/2023 17:14
23020845-016B	32	02/28/2023 13:06	03/02/2023 8:00			
				SW-846 9251 (Dissolved)		03/07/2023 13:38
23020845-016C	32	02/28/2023 13:06	03/02/2023 8:00			
				SW-846 3005A, 6010B, Metals by ICP (Total)	03/02/2023 9:03	03/03/2023 17:43
				SW-846 3005A, 6010B, Metals by ICP (Total)	03/02/2023 9:03	03/06/2023 15:15
				SW-846 3005A, 6020A, Metals by ICPMS (Total)	03/02/2023 9:03	03/03/2023 15:50
				SW-846 3005A, 6020A, Metals by ICPMS (Total)	03/02/2023 9:03	03/06/2023 13:20
				SW-846 3005A, 6020A, Metals by ICPMS (Total)	03/20/2023 19:16	03/22/2023 2:54
				SW-846 7470A (Total)	03/02/2023 9:08	03/06/2023 20:49
23020845-016D	32	02/28/2023 13:06	03/02/2023 8:00			
				SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)	03/02/2023 9:16	03/02/2023 19:21
23020845-017A	33	02/28/2023 13:15	03/02/2023 8:00			
				Field Elevation Measurements		02/28/2023 13:15
23020845-018A	34	02/28/2023 14:21	03/02/2023 8:00			



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Sample ID	Client Sample ID	Collection Date	Received Date	Test Name	Prep Date/Time	Analysis Date/Time
				Field Elevation Measurements		02/28/2023 14:21
				Standard Method 4500-H B 2001 Field		02/28/2023 14:21
				Standard Methods 2130 B Field		02/28/2023 14:21
				Standard Methods 18th Ed. 2580 B Field		02/28/2023 14:21
				Standard Methods 2320 B (Total) 1997, 2011		03/03/2023 15:43
				Standard Methods 2320 B 1997, 2011		03/03/2023 15:43
				Standard Methods 2510 B Field		02/28/2023 14:21
				Standard Methods 2540 C (Total) 1997, 2011		03/02/2023 12:09
				Standard Methods 2550 B Field		02/28/2023 14:21
				Standard Methods 4500-O G Field		02/28/2023 14:21
				SW-846 9036 (Total)		03/07/2023 17:17
				SW-846 9214 (Total)		03/02/2023 13:15
				SW-846 9251 (Total)		03/07/2023 17:35
23020845-018B	34	02/28/2023 14:21	03/02/2023 8:00	SW-846 9251 (Dissolved)		03/07/2023 13:59
23020845-018C	34	02/28/2023 14:21	03/02/2023 8:00	SW-846 3005A, 6010B, Metals by ICP (Total)	03/02/2023 9:03	03/03/2023 17:47
				SW-846 3005A, 6010B, Metals by ICP (Total)	03/02/2023 9:03	03/06/2023 15:18
				SW-846 3005A, 6020A, Metals by ICPMS (Total)	03/02/2023 9:03	03/03/2023 15:57
				SW-846 3005A, 6020A, Metals by ICPMS (Total)	03/02/2023 9:03	03/06/2023 13:26
				SW-846 3005A, 6020A, Metals by ICPMS (Total)	03/20/2023 19:16	03/22/2023 2:36
				SW-846 7470A (Total)	03/02/2023 9:08	03/06/2023 20:56
23020845-018D	34	02/28/2023 14:21	03/02/2023 8:00	SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)	03/02/2023 9:16	03/02/2023 19:27
23020845-019A	35	02/28/2023 12:33	03/02/2023 8:00	Field Elevation Measurements		02/28/2023 12:33
				Standard Method 4500-H B 2001 Field		02/28/2023 12:33
				Standard Methods 2130 B Field		02/28/2023 12:33
				Standard Methods 18th Ed. 2580 B Field		02/28/2023 12:33
				Standard Methods 2320 B (Total) 1997, 2011		03/06/2023 10:18
				Standard Methods 2320 B 1997, 2011		03/06/2023 10:18
				Standard Methods 2510 B Field		02/28/2023 12:33
				Standard Methods 2540 C (Total) 1997, 2011		03/02/2023 12:09
				Standard Methods 2550 B Field		02/28/2023 12:33
				Standard Methods 4500-O G Field		02/28/2023 12:33
				SW-846 9036 (Total)		03/07/2023 17:43
				SW-846 9214 (Total)		03/02/2023 13:17



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
Test Name					
SW-846 9251 (Total)					03/07/2023 17:38
23020845-019B	35	02/28/2023 12:33	03/02/2023 8:00		
SW-846 9251 (Dissolved)					03/07/2023 14:02
23020845-019C	35	02/28/2023 12:33	03/02/2023 8:00		
SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:03	03/03/2023 17:50
SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:03	03/06/2023 15:07
SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:03	03/03/2023 16:03
SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:03	03/06/2023 13:33
SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/20/2023 19:16	03/22/2023 2:42
SW-846 7470A (Total)				03/02/2023 9:08	03/06/2023 20:58
23020845-019D	35	02/28/2023 12:33	03/02/2023 8:00		
SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)				03/20/2023 21:00	03/22/2023 6:04
23020845-020A	36	02/28/2023 12:20	03/02/2023 8:00		
Field Elevation Measurements					02/28/2023 12:20
23020845-024A	49	02/28/2023 11:01	03/02/2023 8:00		
Field Elevation Measurements					02/28/2023 11:01
Standard Method 4500-H B 2001 Field					02/28/2023 11:01
Standard Methods 2130 B Field					02/28/2023 11:01
Standard Methods 18th Ed. 2580 B Field					02/28/2023 11:01
Standard Methods 2320 B (Total) 1997, 2011					03/03/2023 15:58
Standard Methods 2320 B 1997, 2011					03/03/2023 15:58
Standard Methods 2510 B Field					02/28/2023 11:01
Standard Methods 2540 C (Total) 1997, 2011					03/02/2023 12:10
Standard Methods 2550 B Field					02/28/2023 11:01
Standard Methods 4500-O G Field					02/28/2023 11:01
SW-846 9036 (Total)					03/07/2023 18:12
SW-846 9214 (Total)					03/02/2023 13:23
SW-846 9251 (Total)					03/07/2023 18:12
23020845-024B	49	02/28/2023 11:01	03/02/2023 8:00		
SW-846 9251 (Dissolved)					03/07/2023 14:10
23020845-024C	49	02/28/2023 11:01	03/02/2023 8:00		
SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:03	03/03/2023 18:27
SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:03	03/06/2023 15:11
SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:03	03/03/2023 16:22
SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:03	03/06/2023 13:52
SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/20/2023 19:16	03/22/2023 2:48
SW-846 7470A (Total)				03/02/2023 9:11	03/06/2023 21:09



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
23020845-024D	49	02/28/2023 11:01	03/02/2023 8:00		
	SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)			03/20/2023 21:00	03/22/2023 5:57
23020845-025A	50	02/28/2023 12:10	03/02/2023 8:00		
	Field Elevation Measurements				02/28/2023 12:10
	Standard Method 4500-H B 2001 Field				02/28/2023 12:10
	Standard Methods 2130 B Field				02/28/2023 12:10
	Standard Methods 18th Ed. 2580 B Field				02/28/2023 12:10
	Standard Methods 2320 B (Total) 1997, 2011				03/03/2023 16:05
	Standard Methods 2320 B 1997, 2011				03/03/2023 16:05
	Standard Methods 2510 B Field				02/28/2023 12:10
	Standard Methods 2540 C (Total) 1997, 2011				03/02/2023 12:54
	Standard Methods 2550 B Field				02/28/2023 12:10
	Standard Methods 4500-O G Field				02/28/2023 12:10
	SW-846 9036 (Total)				03/07/2023 18:55
	SW-846 9214 (Total)				03/02/2023 13:25
	SW-846 9251 (Total)				03/07/2023 18:55
23020845-025B	50	02/28/2023 12:10	03/02/2023 8:00		
	SW-846 9251 (Dissolved)				03/07/2023 14:18
23020845-025C	50	02/28/2023 12:10	03/02/2023 8:00		
	SW-846 3005A, 6010B, Metals by ICP (Total)			03/02/2023 9:03	03/03/2023 18:31
	SW-846 3005A, 6010B, Metals by ICP (Total)			03/02/2023 9:03	03/06/2023 16:30
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/02/2023 9:03	03/03/2023 16:28
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/02/2023 9:03	03/06/2023 13:58
	SW-846 7470A (Total)			03/02/2023 9:11	03/06/2023 21:16
23020845-025D	50	02/28/2023 12:10	03/02/2023 8:00		
	SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)			03/02/2023 9:16	03/07/2023 13:15
23020845-026A	51	02/28/2023 10:03	03/02/2023 8:00		
	Field Elevation Measurements				02/28/2023 10:03
	Standard Method 4500-H B 2001 Field				02/28/2023 10:03
	Standard Methods 2130 B Field				02/28/2023 10:03
	Standard Methods 18th Ed. 2580 B Field				02/28/2023 10:03
	Standard Methods 2320 B (Total) 1997, 2011				03/06/2023 10:39
	Standard Methods 2320 B 1997, 2011				03/06/2023 10:39
	Standard Methods 2510 B Field				02/28/2023 10:03
	Standard Methods 2540 C (Total) 1997, 2011				03/02/2023 12:55
	Standard Methods 2550 B Field				02/28/2023 10:03
	Standard Methods 4500-O G Field				02/28/2023 10:03



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
Test Name				Prep Date/Time	Analysis Date/Time
	SW-846 9036 (Total)				03/07/2023 18:58
	SW-846 9214 (Total)				03/02/2023 13:37
	SW-846 9251 (Total)				03/07/2023 18:57
23020845-026B	51	02/28/2023 10:03	03/02/2023 8:00		
	SW-846 9251 (Dissolved)				03/07/2023 14:26
23020845-026C	51	02/28/2023 10:03	03/02/2023 8:00		
	SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:03 03/03/2023 18:35
	SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:03 03/06/2023 16:33
	SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:03 03/03/2023 17:36
	SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:03 03/06/2023 14:04
	SW-846 7470A (Total)				03/02/2023 9:11 03/07/2023 5:12
23020845-026D	51	02/28/2023 10:03	03/02/2023 8:00		
	SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)				03/02/2023 9:16 03/02/2023 20:12
23020845-036A	21R	02/28/2023 9:18	03/02/2023 8:00		
	Field Elevation Measurements				02/28/2023 9:18
	Standard Method 4500-H B 2001 Field				02/28/2023 9:18
	Standard Methods 2130 B Field				02/28/2023 9:18
	Standard Methods 18th Ed. 2580 B Field				02/28/2023 9:18
	Standard Methods 2320 B (Total) 1997, 2011				03/03/2023 16:46
	Standard Methods 2320 B 1997, 2011				03/03/2023 16:46
	Standard Methods 2510 B Field				02/28/2023 9:18
	Standard Methods 2540 C (Total) 1997, 2011				03/02/2023 13:36
	Standard Methods 2550 B Field				02/28/2023 9:18
	Standard Methods 4500-O G Field				02/28/2023 9:18
	SW-846 9036 (Total)				03/08/2023 11:49
	SW-846 9214 (Total)				03/02/2023 14:03
	SW-846 9251 (Total)				03/08/2023 11:49
23020845-036B	21R	02/28/2023 9:18	03/02/2023 8:00		
	SW-846 9251 (Dissolved)				03/07/2023 14:53
23020845-036C	21R	02/28/2023 9:18	03/02/2023 8:00		
	SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:06 03/03/2023 19:42
	SW-846 3005A, 6010B, Metals by ICP (Total)				03/02/2023 9:06 03/06/2023 18:02
	SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:06 03/03/2023 13:07
	SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/02/2023 9:06 03/06/2023 16:25
	SW-846 3005A, 6020A, Metals by ICPMS (Total)				03/20/2023 19:16 03/22/2023 4:13
	SW-846 7470A (Total)				03/02/2023 9:11 03/07/2023 5:46
23020845-036D	21R	02/28/2023 9:18	03/02/2023 8:00		



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)			03/20/2023 21:00	03/22/2023 7:17
23020845-037A	22D	02/28/2023 11:44	03/02/2023 8:00		
	Field Elevation Measurements				02/28/2023 11:44
	Standard Method 4500-H B 2001 Field				02/28/2023 11:44
	Standard Methods 2130 B Field				02/28/2023 11:44
	Standard Methods 18th Ed. 2580 B Field				02/28/2023 11:44
	Standard Methods 2320 B (Total) 1997, 2011				03/03/2023 16:54
	Standard Methods 2320 B 1997, 2011				03/03/2023 16:54
	Standard Methods 2510 B Field				02/28/2023 11:44
	Standard Methods 2540 C (Total) 1997, 2011				03/02/2023 13:36
	Standard Methods 2550 B Field				02/28/2023 11:44
	Standard Methods 4500-O G Field				02/28/2023 11:44
	SW-846 9036 (Total)				03/08/2023 11:55
	SW-846 9214 (Total)				03/02/2023 14:05
	SW-846 9251 (Total)				03/08/2023 11:55
23020845-037B	22D	02/28/2023 11:44	03/02/2023 8:00		
	SW-846 9251 (Dissolved)				03/07/2023 14:55
23020845-037C	22D	02/28/2023 11:44	03/02/2023 8:00		
	SW-846 3005A, 6010B, Metals by ICP (Total)			03/02/2023 9:06	03/03/2023 19:45
	SW-846 3005A, 6010B, Metals by ICP (Total)			03/02/2023 9:06	03/06/2023 18:06
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/02/2023 9:06	03/03/2023 13:14
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/02/2023 9:06	03/06/2023 16:32
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/20/2023 19:16	03/22/2023 4:20
	SW-846 7470A (Total)			03/02/2023 9:11	03/07/2023 5:53
23020845-037D	22D	02/28/2023 11:44	03/02/2023 8:00		
	SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)			03/20/2023 21:00	03/22/2023 7:23
23020845-040A	SG02	03/02/2023 7:30	03/02/2023 8:00		
	Field Elevation Measurements				03/02/2023 7:30
23020845-051A	Field Blank	03/01/2023 17:01	03/02/2023 8:00		
	Standard Methods 2320 B 1997, 2011				03/07/2023 8:46
	Standard Methods 2320 B (Total) 1997, 2011				03/07/2023 8:46
	Standard Methods 2320 B 1997, 2011				03/07/2023 8:46
	Standard Methods 2540 C (Total) 1997, 2011				03/02/2023 14:09
	Standard Methods 4500-NO2 B (Total) 2000, 2011				03/02/2023 15:28
	Standard Methods 4500-NO3 F (Total) 2000, 2011				03/02/2023 15:23
	Standard Methods 4500-NO3 F (Total) 2000, 2011				03/02/2023 15:23
	SW-846 9036 (Total)				03/08/2023 13:33



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	SW-846 9214 (Total)				03/02/2023 14:29
	SW-846 9251 (Total)				03/08/2023 13:33
23020845-051B	Field Blank	03/01/2023 17:01	03/02/2023 8:00		
	EPA 314.0				03/09/2023 0:00
23020845-051C	Field Blank	03/01/2023 17:01	03/02/2023 8:00		
	SW-846 9036 (Dissolved)				03/06/2023 13:56
	SW-846 9214 (Dissolved)				03/02/2023 11:58
	SW-846 9251 (Dissolved)				03/06/2023 13:55
23020845-051D	Field Blank	03/01/2023 17:01	03/02/2023 8:00		
	SW-846 3005A, 6010B, Metals by ICP (Total)			03/02/2023 9:06	03/03/2023 20:34
	SW-846 3005A, 6010B, Metals by ICP (Total)			03/02/2023 9:06	03/06/2023 18:21
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/02/2023 9:06	03/03/2023 13:45
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/02/2023 9:06	03/06/2023 18:08
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			03/02/2023 9:06	03/07/2023 9:57
	SW-846 7470A (Total)			03/02/2023 9:14	03/06/2023 19:27
23020845-051E	Field Blank	03/01/2023 17:01	03/02/2023 8:00		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			03/02/2023 9:19	03/03/2023 15:23
	SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)			03/02/2023 9:19	03/02/2023 23:24
	SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)			03/02/2023 9:19	03/03/2023 20:14
	SW-846 7470A (Dissolved)			03/02/2023 9:14	03/06/2023 19:38
23020845-051F	Field Blank	03/01/2023 17:01	03/02/2023 8:00		
	SW-846 9012A (Total)			03/03/2023 16:10	03/06/2023 14:50
23020845-051G	Field Blank	03/01/2023 17:01	03/02/2023 8:00		
	SW-846 9066 (Total)				03/06/2023 12:09
23020845-051H	Field Blank	03/01/2023 17:01	03/02/2023 8:00		
	Standard Methods 4500-NH3 G (Total) 1997, 2011				03/03/2023 12:57
23020845-051I	Field Blank	03/01/2023 17:01	03/02/2023 8:00		
	SW-846 5030, 8260B, Volatile Organic Compounds by GC/MS				03/02/2023 15:05



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

STANDARD METHOD 4500-H B 2001 FIELD

Batch R325999		SampType: LCS		Units							
SampID: LCS-R325999											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
pH	*	1.00		7.02	7.000	0	100.3	98.57	101.4	02/28/2023	
pH	*	1.00		7.09	7.000	0	101.3	98.57	101.4	03/01/2023	

STANDARD METHODS 2510 B FIELD

Batch R325999		SampType: LCS		Units µS/cm							
SampID: LCS-R325999											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Spec. Conductance, Field	*	0		1460	1409	0	103.6	90	110	03/01/2023	
Spec. Conductance, Field	*	0		1481	1409	0	105.1	90	110	02/28/2023	

STANDARD METHODS 2320 B 1997, 2011

Batch R325591		SampType: MBLK		Units mg/L							
SampID: MBLK											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Alkalinity, Total (as CaCO3)			0		0						03/03/2023

Batch R325591		SampType: LCS		Units mg/L							
SampID: LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Alkalinity, Total (as CaCO3)		0		243	236.0	0	103.0	90	110	03/03/2023	

Batch R325591		SampType: LCSD		Units mg/L				RPD Limit:			
SampID: LCSDUP											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Alkalinity, Total (as CaCO3)			0		235	236.0	0	99.6	90	110	03/03/2023

Batch R325659		SampType: MBLK		Units mg/L							
SampID: MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Alkalinity, Total (as CaCO3)		0		0						03/06/2023	

Batch R325659		SampType: LCS		Units mg/L							
SampID: LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Alkalinity, Total (as CaCO3)		0		237	236.0	0	100.4	90	110	03/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

STANDARD METHODS 2320 B 1997, 2011

Batch	R325659	SampType:	LCSD	Units	mg/L	RPD Limit:						Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		Analyzed
Alkalinity, Total (as CaCO ₃)			0		236	236.0	0	100.0	90	110		03/06/2023
Alkalinity, Total (as CaCO ₃)			0		240	236.0	0	101.7	90	110		03/06/2023

Batch	R325659	SampType:	DUP	Units	mg/L	RPD Limit: 10						Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		Analyzed
Alkalinity, Total (as CaCO ₃)			0		249				243.0	2.44		03/06/2023

Batch	R325659	SampType:	DUP	Units	mg/L	RPD Limit: 10						Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		Analyzed
Alkalinity, Total (as CaCO ₃)			0		1				1.000	0.00		03/07/2023

STANDARD METHODS 2540 C (TOTAL) 1997, 2011

Batch	R325574	SampType:	MBLK	Units	mg/L						Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Total Dissolved Solids			20		< 20	16.00	0	0	-100	100	03/02/2023
Total Dissolved Solids			20		< 20	16.00	0	0	-100	100	03/02/2023
Total Dissolved Solids			20		< 20	16.00	0	0	-100	100	03/02/2023

Batch	R325574	SampType:	LCS	Units	mg/L						Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Total Dissolved Solids			20		920	1000	0	92.0	90	110	03/02/2023
Total Dissolved Solids			20		908	1000	0	90.8	90	110	03/02/2023
Total Dissolved Solids			20		910	1000	0	91.0	90	110	03/02/2023

Batch	R325574	SampType:	DUP	Units	mg/L	RPD Limit: 5						Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		Analyzed
Total Dissolved Solids			20		488				488.0	0.00		03/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

STANDARD METHODS 2540 C (TOTAL) 1997, 2011

Batch R325574		SampType: DUP		Units mg/L				RPD Limit: 5			Date Analyzed
SampID: 23020845-021ADUP											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Total Dissolved Solids		20		492				496.0	0.81	03/02/2023	

Batch R325574		SampType: DUP		Units mg/L				RPD Limit: 5			
SampID: 23020845-030ADUP											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Total Dissolved Solids			20		540				534.0	1.12	03/02/2023

Batch R325574		SampType:	DUP		Units mg/L			RPD Limit: 5			
SampID: 23020845-041ADUP											Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Analyzed
Total Dissolved Solids			20		544				558.0	2.54	03/02/2023

Batch R325574		SampType: DUP		Units mg/L				RPD Limit: 5			
SampID: 23020845-050ADUP											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Total Dissolved Solids			20		1090				1080	0.74	03/02/2023

STANDARD METHODS 4500-NH3 G (TOTAL) 1997, 2011

Batch R325556		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Nitrogen, Ammonia (as N)		0.10		< 0.10	0.0270	0	0	-100	100	03/03/2023	

Batch R325556		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Ammonia (as N)			0.10		1.01	1.000	0	101.3	90	110	03/03/2023

Batch R325556		SampType: MS		Units mg/L							
SampID: 23020845-005GMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Nitrogen, Ammonia (as N)		0.10	S	1.70	2.000	0	85.2	90	110	03/03/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020845
Report Date: 14-Apr-23

STANDARD METHODS 4500-NH3 G (TOTAL) 1997, 2011

Batch R325556		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed	
SampID: 23020845-005GMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Nitrogen, Ammonia (as N)			0.10	S	1.72	2.000	0	85.8	1.705	0.58	03/03/2023	

STANDARD METHODS 4500-NO2 B (TOTAL) 2000, 2011

Batch R325452		SampType: MBLK		Units mg/L							
SampID: MBLK											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrite (as N)		0.05		< 0.05	0.0250	0	0	-100	100	03/01/2023	

Batch R325452		SampType: LCS		Units mg/L							
SampID: LCS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrite (as N)		0.25		0.65	0.6510	0	99.8	90	110	03/01/2023	

Batch R325452		SampType: MS		Units mg/L							
SampID: 23020845-002AMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrite (as N)		0.05		0.49	0.5000	0	97.6	85	115	03/02/2023	

Batch R325452		SampType: MSD		Units mg/L					RPD Limit: 10		
SampID: 23020845-002AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrite (as N)			0.05		0.50	0.5000	0	99.0	0.4880	1.42	03/02/2023

Batch R325452		SampType: MS		Units mg/L						
SampID: 23020845-003AMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Nitrite (as N)		0.05		0.49	0.5000	0.006000	96.8	85	115	03/02/2023

Batch R325452		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23020845-003AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrite (as N)			0.05		0.49	0.5000	0.006000	97.6	0.4900	0.81	03/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

STANDARD METHODS 4500-NO2 B (TOTAL) 2000, 2011

Batch R325452		SampType: MS		Units mg/L						
SampID: 23020845-005AMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Nitrite (as N)		0.05		0.49	0.5000	0	98.8	85	115	03/02/2023

Batch R325452		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23020845-005AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrite (as N)			0.05		0.50	0.5000	0	99.8	0.4940	1.01	03/02/2023

STANDARD METHODS 4500-NO3 F (TOTAL) 2000, 2011

Batch R325529		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											Date Analyzed
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Nitrogen, Nitrate (as N)			0.050		< 0.050						03/02/2023
Nitrogen, Nitrate-Nitrite (as N)			0.050		< 0.050	0.0090	0	0	-100	100	03/02/2023

Batch R325529		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Nitrogen, Nitrate-Nitrite (as N)		0.050		0.522	0.5000	0	104.4	90	110	03/02/2023	

Batch R325529		SampType: MS		Units mg/L							
SampID: 23020845-039AMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrate-Nitrite (as N)		0.250		4.38	1.250	3.190	95.0	85	115	03/02/2023	

Batch R325529		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed
SampID: 23020845-039AMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Nitrogen, Nitrate-Nitrite (as N)		0.250		4.41	1.250	3.190	97.9	4.378	0.82	03/02/2023	

Batch R325529		SampType: MS		Units mg/L							
SampID: 23020845-049AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Nitrogen, Nitrate-Nitrite (as N)		0.250		3.01	1.250	1.734	102.2	85	115	03/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

STANDARD METHODS 4500-NO3 F (TOTAL) 2000, 2011

Batch R325529		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23020845-049AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrate-Nitrite (as N)			0.250		3.02	1.250	1.734	103.0	3.011	0.36	03/02/2023

SW-846 9012A (TOTAL)

Batch 203485		SampType: MBLK		Units mg/L							
SampleID: MBLK 230302 TCN1											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Cyanide		0.005		< 0.005	0.0015	0	0	-100	100	03/03/2023	

Batch 203485		SampType: LCS		Units mg/L							
SampleID: LCS 230302 TCN1											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Cyanide		0.005		0.024	0.0250	0	97.5	90	110	03/03/2023	

Batch 203485		SampType: MS		Units mg/L							
SampleID: 23020845-007EMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Cyanide		0.005		0.025	0.0250	0	99.5	75	125	03/03/2023	

Batch	203485	SampType:	MSD	Units					mg/L			RPD Limit: 15		Date Analyzed
SampID: 23020845-007EMSD														
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD				
Cyanide			0.005	R	0.020	0.0250	0	81.8	0.02488	19.53	03/03/2023			

Batch 203538		SampType: MBLK		Units mg/L							
SampID: MBLK 230303 TCN1											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Cyanide		0.005		< 0.005	0.0015	0	0	-100	100	03/06/2023	

Batch 203538		SampType: LCS		Units mg/L							
SampleID: LCS 230303 TCN1											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Cyanide		0.005		0.023	0.0250	0	92.9	90	110	03/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 9012A (TOTAL)

Batch 203538		SampType: MS		Units mg/L							
SampID: 23020845-035FMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Cyanide		0.005		0.025	0.0250	0	98.2	75	125	03/06/2023	

Batch 203538		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23020845-035FMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Cyanide		0.005		0.022	0.0250	0	89.5	0.02454	9.21	03/06/2023	

Batch 203538		SampType: MS		Units mg/L							
SampID: 23020845-049DMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Cyanide		0.005	S	0.016	0.0250	0	62.8	75	125	03/06/2023	

Batch 203538		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed
SampID: 23020845-049DMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Cyanide		0.005	R	0.023	0.0250	0	93.6	0.01570	39.42		

SW-846 9036 (DISSOLVED)

Batch R325628		SampType: MS		Units mg/L							
SampID: 23020845-002CMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		50		168	100.0	75.21	93.1	85	115	03/06/2023	

Batch R325628		SampType: MSD		Units mg/L		RPD Limit: 10					Date Analyzed	
SampID: 23020845-002CMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Sulfate			50		172	100.0	75.21	97.2	168.4	2.36		

Batch R325628		SampType: MS		Units mg/L							
SampID: 23020845-030CMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		50		180	100.0	88.46	91.8	85	115	03/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 9036 (DISSOLVED)

Batch R325628		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23020845-030CMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Sulfate			50		185	100.0	88.46	96.3	180.3	2.47	03/06/2023

Batch R325628		SampType: MS		Units mg/L							
SampID: 23020845-034CMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		50		205	100.0	108.2	96.7	85	115	03/06/2023	

Batch R325628		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed	
SampID: 23020845-034CMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Sulfate			50		207	100.0	108.2	98.4	204.9	0.83	03/06/2023	

SW-846 9036 (TOTAL)

Batch R325628		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		10		< 10	6.140	0	0	-100	100	03/06/2023	

Batch R325628		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		10		21	20.00	0	104.6	90	110	03/06/2023	

Batch R325693		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Sulfate			10		< 10	6.140	0	0	-100	100	03/07/2023

Batch R325693		SampType: LCS		Units mg/L							
SampID: ICB/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		10		20	20.00	0	100.5	90	110	03/07/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 9036 (TOTAL)

Batch R325693		SampType: MS		Units mg/L							Date
SampID: 23020845-003AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		50		215	100.0	129.4	85.6	85	115	03/07/2023	

Batch R325693		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23020845-003AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Sulfate			50		220	100.0	129.4	90.6	215.0	2.29	03/07/2023

Batch R325693		SampType: MS		Units mg/L							Date
SampID: 23020845-024AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		50		208	100.0	108.0	100.4	85	115	03/07/2023	

Batch R325693		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed
SampID: 23020845-024AMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Sulfate		50		209	100.0	108.0	101.3	208.4	0.45	03/07/2023	

Batch R325693		SampType: MS		Units mg/L							Date
SampID: 23020845-030AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		50		179	100.0	82.42	96.2	85	115	03/07/2023	

Batch R325693		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23020845-030AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Sulfate			50		182	100.0	82.42	99.3	178.7	1.71	03/07/2023

Batch R325765		SampType: MBLK		Units mg/L							Date
SampID: ICB/MBLK											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		10		< 10	6.140	0	0	-100	100	03/08/2023	

Batch R325765		SampType: LCS		Units mg/L							Date
SampID: ICV/LCS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		10		20	20.00	0	101.2	90	110	03/08/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 9036 (TOTAL)

Batch R325765		SampType: MS		Units mg/L							
SampID: 23020845-037AMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		50		212	100.0	111.8	99.9	85	115	03/08/2023	

Batch R325765		SampType: MSD		Units mg/L				RPD Limit: 10			
SampleID: 23020845-037AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Sulfate			50		209	100.0	111.8	97.3	211.7	1.21	03/08/2023

SW-846 9066 (TOTAL)

Batch R325651		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Phenols		0.005		< 0.005	0.0028	0	0	-100	100	03/06/2023	

Batch R325651		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Phenols		0.005		0.055	0.0500	0	109.8	90	110	03/06/2023	

Batch R325651		SampType: MS		Units µg/L							
SampID: 23020845-051GMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Phenols		5		55	50.00	3.190	104.0	85	115	03/06/2023	

Batch R325651		SampType: MSD		Units µg/L		RPD Limit: 15					
SampleID: 23020845-051GMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Phenols			5		56	50.00	3.190	104.7	55.20	0.65	03/06/2023

SW-846 9214 (DISSOLVED)

Batch R325510		SampType: MS		Units mg/L							
SampleID: 23020845-008BMS											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Fluoride			0.10		2.24	2.000	0.1350	105.4	75	125	03/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 9214 (DISSOLVED)

Batch R325510		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed
SampID: 23020845-008BMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Fluoride		0.10		2.24	2.000	0.1350	105.5	2.242	0.13		

Batch R325510		SampType: MS		Units mg/L							
SampID: 23020845-039CMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		2.37	2.000	0.2680	105.0	75	125	03/02/2023	

Batch R325510		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23020845-039CMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Fluoride			0.10		2.43	2.000	0.2680	108.0	2.368	2.50	03/02/2023

SW-846 9214 (TOTAL)

Batch R325510		SampType: MBLK		Units mg/L							
SampID: MBLK										Date Analyzed	
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		< 0.10	0.0370	0	0	-100	100	03/02/2023	

Batch R325510		SampType: LCS		Units mg/L							
SampID: LCS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		1.05	1.000	0	105.3	90	110	03/02/2023	

Batch R325510		SampType: MS		Units mg/L							
SampID: 23020845-009AMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		2.22	2.000	0.1560	103.4	75	125	03/02/2023	

Batch R325510		SampType: MSD		Units mg/L				RPD Limit: 15				Date Analyzed
SampID: 23020845-009AMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Fluoride			0.10		2.13	2.000	0.1560	98.8	2.224	4.18		



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 9214 (TOTAL)

Batch R325510		SampType: MS		Units mg/L							Date
SampID: 23020845-013AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		2.17	2.000	0.1270	102.0	75	125	03/02/2023	

Batch R325510		SampType: MSD		Units mg/L							RPD Limit: 15	Date
SampID: 23020845-013AMSD												Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Fluoride		0.10		2.24	2.000	0.1270	105.4	2.168	3.04	03/02/2023		

Batch R325510		SampType: MS		Units mg/L							Date
SampID: 23020845-025AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		2.15	2.000	0.1410	100.2	75	125	03/02/2023	

Batch R325510		SampType: MSD		Units mg/L							RPD Limit: 15	Date
SampID: 23020845-025AMSD												Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Fluoride		0.10		2.14	2.000	0.1410	100.0	2.146	0.23	03/02/2023		

Batch R325510		SampType: MS		Units mg/L							Date
SampID: 23020845-034AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		2.28	2.000	0.1490	106.8	75	125	03/02/2023	

Batch R325510		SampType: MSD		Units mg/L							RPD Limit: 15	Date
SampID: 23020845-034AMSD												Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Fluoride		0.10		2.24	2.000	0.1490	104.6	2.284	1.95	03/02/2023		

Batch R325510		SampType: MS		Units mg/L							Date
SampID: 23020845-043AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		1.97	2.000	0.1400	91.6	75	125	03/02/2023	

Batch R325510		SampType: MSD		Units mg/L							RPD Limit: 15	Date
SampID: 23020845-043AMSD												Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Fluoride		0.10		2.05	2.000	0.1400	95.5	1.971	3.93	03/02/2023		



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 9214 (TOTAL)

Batch R325510		SampType: MS		Units mg/L							
SampID: 23020845-051AMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		2.00	2.000	0	100.0	75	125	03/02/2023	

Batch R325510		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23020845-051AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Fluoride			0.10		2.05	2.000	0	102.7	2.000	2.66	03/02/2023

SW-846 9251 (DISSOLVED)

Batch R325629		SampType: MS		Units mg/L							
SampID: 23020845-002CMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		20		179	100.0	88.87	89.7	85	115	03/06/2023	

Batch R325629		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23020845-002CMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Chloride			20		178	100.0	88.87	89.5	178.5	0.10	03/06/2023

Batch R325629		SampType: MS		Units mg/L							
SampID: 23020845-030CMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		20		195	100.0	102.4	92.6	85	115	03/06/2023	

Batch R325629		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23020845-030CMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Chloride			20		192	100.0	102.4	89.2	195.1	1.78	03/06/2023

Batch R325629		SampType: MS		Units mg/L							
SampID: 23020845-034CMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		20		181	100.0	86.13	94.7	85	115	03/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 9251 (DISSOLVED)

Batch R325629		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed
SampID: 23020845-034CMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Chloride		20		179	100.0	86.13	92.9	180.8	0.97		

Batch R325696		SampType: MS		Units mg/L							
SampID: 23020845-013BMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		5		190	100.0	98.15	91.5	85	115	03/07/2023	

Batch R325696		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed	
SampID: 23020845-013BMSD												
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Chloride		5		190	100.0	98.15	92.0	189.6	0.26			

SW-846 9251 (TOTAL)

Batch R325629		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		4		< 4	0.5000	0	0	-100	100	03/06/2023	

Batch R325629		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		4		21	20.00	0	103.1	90	110	03/06/2023	

Batch R325696		SampType: MBLK		Units mg/L								Date Analyzed
SampID: ICB/MBLK												
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			
Chloride		1		< 1	0.5000	0	0	-100	100			

Batch R325696		SampType: LCS		Units mg/L							
SampID: ICB/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		1		20	20.00	0	99.8	90	110	03/07/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 9251 (TOTAL)

Batch R325696		SampType: MS		Units mg/L							Date
SampID: 23020845-024AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		5		195	100.0	104.4	90.6	85	115	03/07/2023	

Batch R325696		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23020845-024AMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Chloride		5		195	100.0	104.4	90.6	195.0	0.03	03/07/2023	

Batch R325696		SampType: MS		Units mg/L							Date
SampID: 23020845-030AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		5		219	100.0	130.4	89.0	85	115	03/07/2023	

Batch R325696		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23020845-030AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Chloride			5		218	100.0	130.4	87.2	219.4	0.82	03/07/2023

Batch R325771		SampType: MBLK		Units mg/L							Date
SampID: ICB/MBLK											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		1		< 1	0.5000	0	0	-100	100	03/08/2023	

Batch R325771		SampType: LCS		Units mg/L							Date
SampID: ICB/LCS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		1		20	20.00	0	99.0	90	110	03/08/2023	

Batch R325771		SampType: MS		Units mg/L							Date
SampID: 23020845-003AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		20		590	400.0	226.8	90.7	85	115	03/08/2023	

Batch R325771		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23020845-003AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Chloride			20		593	400.0	226.8	91.5	589.7	0.54	03/08/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 9251 (TOTAL)

Batch R325771		SampType: MS		Units mg/L						
SampID: 23020845-037AMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Chloride		5		204	100.0	113.2	90.4	85	115	03/08/2023

Batch R325771		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23020845-037AMSD											Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Analyzed
Chloride			5		200	100.0	113.2	87.0	203.5	1.68	03/08/2023

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 203472		SampType: MBLK		Units mg/L							
SampID: MBLK-203472											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	03/09/2023	
Magnesium		0.050		< 0.050	0.0055	0	0	-100	100	03/09/2023	

Batch 203472		SampType: LCS		Units mg/L							
SampID: LCS-203472											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Calcium		0.100		2.54	2.500	0	101.5	85	115	03/09/2023	
Magnesium		0.050		2.31	2.500	0	92.2	85	115	03/09/2023	

Batch 203472		SampType: MS		Units mg/L							
SampID: 23020845-005DMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Calcium		0.100	S	74.3	2.500	73.42	35.6	75	125	03/09/2023	
Magnesium		0.050	S	29.1	2.500	27.39	69.3	75	125	03/09/2023	

Batch 203472		SampType: MSD		Units mg/L				RPD Limit: 20			
SampID: 23020845-005DMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Calcium			0.100		75.4	2.500	73.42	80.4	74.31	1.50	03/09/2023
Magnesium			0.050		29.7	2.500	27.39	92.5	29.12	1.97	03/09/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 203473 SampType: MBLK Units mg/L

SampleID: MBLK-203473

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	03/03/2023
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	03/03/2023

Batch 203473 SampType: LCS Units mg/L

SampleID: LCS-203473

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100		2.45	2.500	0	97.9	85	115	03/03/2023
Magnesium		0.0500		2.41	2.500	0	96.6	85	115	03/03/2023

Batch 203473 SampType: MS Units mg/L

SampleID: 23020845-051EMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100		2.44	2.500	0	97.6	75	125	03/03/2023
Magnesium		0.050		2.40	2.500	0	96.1	75	125	03/03/2023

Batch 203473 SampType: MSD Units mg/L

SampleID: 23020845-051EMSD

RPD Limit: 20

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Calcium		0.100		2.45	2.500	0	97.8	2.439	0.29	03/03/2023
Magnesium		0.050		2.43	2.500	0	97.1	2.403	1.03	03/03/2023

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 203466 SampType: MBLK Units mg/L

SampleID: MBLK-203466

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	03/03/2023
Magnesium		0.050		< 0.050	0.0055	0	0	-100	100	03/03/2023
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	03/03/2023
Sodium		0.050		< 0.050	0.0180	0	0	-100	100	03/03/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 203466 SampType: LCS Units mg/L

SampleID: LCS-203466

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100		2.65	2.500	0	106.1	85	115	03/03/2023
Magnesium		0.050		2.63	2.500	0	105.2	85	115	03/03/2023
Potassium		0.100		2.52	2.500	0	101.0	85	115	03/03/2023
Sodium		0.050		2.50	2.500	0	100.1	85	115	03/03/2023

Batch 203466 SampType: MS Units mg/L

SampleID: 23020845-007CMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100		102	2.500	99.38	120.8	75	125	03/03/2023
Magnesium		0.050		36.2	2.500	33.39	114.4	75	125	03/03/2023
Potassium		0.100		7.73	2.500	4.797	117.4	75	125	03/06/2023
Sodium		0.050		60.0	2.500	57.31	107.2	75	125	03/03/2023

Batch 203466 SampType: MSD Units mg/L

RPD Limit: 20

SampleID: 23020845-007CMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Calcium		0.100	S	103	2.500	99.38	136.8	102.4	0.39	03/03/2023
Magnesium		0.050		36.2	2.500	33.39	114.4	36.25	0.00	03/03/2023
Potassium		0.100		7.42	2.500	4.797	105.1	7.731	4.05	03/06/2023
Sodium		0.050		60.2	2.500	57.31	116.0	59.99	0.37	03/03/2023

Batch 203466 SampType: MS Units mg/L

SampleID: 23020845-023BMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100	S	90.9	2.500	87.61	130.8	75	125	03/03/2023
Magnesium		0.050		32.2	2.500	29.43	110.0	75	125	03/03/2023
Potassium		0.100		8.52	2.500	5.864	106.4	75	125	03/06/2023
Sodium		0.050		54.1	2.500	51.50	104.8	75	125	03/03/2023

Batch 203466 SampType: MSD Units mg/L

RPD Limit: 20

SampleID: 23020845-023BMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Calcium		0.100		90.2	2.500	87.61	101.6	90.88	0.81	03/03/2023
Magnesium		0.050		31.9	2.500	29.43	98.4	32.18	0.91	03/03/2023
Potassium		0.100		8.42	2.500	5.864	102.4	8.523	1.16	03/06/2023
Sodium		0.050		53.5	2.500	51.50	79.6	54.12	1.17	03/03/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 203468 SampType: MBLK Units mg/L

SampleID: MBLK-203468

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	03/03/2023
Magnesium		0.050		< 0.050	0.0055	0	0	-100	100	03/03/2023
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	03/06/2023
Sodium		0.050		< 0.050	0.0180	0	0	-100	100	03/03/2023

Batch 203468 SampType: LCS Units mg/L

SampleID: LCS-203468

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100		2.66	2.500	0	106.5	85	115	03/03/2023
Magnesium		0.050		2.62	2.500	0	104.6	85	115	03/03/2023
Potassium		0.100		2.56	2.500	0	102.4	85	115	03/06/2023
Sodium		0.050		2.50	2.500	0	100.1	85	115	03/03/2023

Batch 203468 SampType: MS Units mg/L

SampleID: 23020845-032CMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100	S	96.7	2.500	89.90	270.4	75	125	03/03/2023
Magnesium		0.050	S	35.0	2.500	31.33	146.4	75	125	03/03/2023
Potassium		0.500		11.4	2.500	8.785	105.6	75	125	03/06/2023
Sodium		0.050	S	50.2	2.500	45.92	173.2	75	125	03/03/2023

Batch 203468 SampType: MSD Units mg/L

RPD Limit: 20

SampleID: 23020845-032CMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Calcium		0.100	S	97.7	2.500	89.90	312.4	96.66	1.08	03/03/2023
Magnesium		0.050	S	35.4	2.500	31.33	164.0	34.99	1.25	03/03/2023
Potassium		0.500		11.1	2.500	8.785	91.6	11.42	3.11	03/06/2023
Sodium		0.050	S	51.0	2.500	45.92	204.4	50.25	1.54	03/03/2023

Batch 203468 SampType: MS Units mg/L

SampleID: 23020845-043BMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100	S	110	2.500	105.8	168.0	75	125	03/03/2023
Magnesium		0.050		2.90	2.500	0.2942	104.3	75	125	03/03/2023
Potassium		1.00		28.0	2.500	25.07	117.6	75	125	03/06/2023
Sodium		0.050	S	123	2.500	118.6	188.0	75	125	03/03/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 203468		SampType: MSD		Units mg/L				RPD Limit: 20		
SampID: 23020845-043BMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Calcium		0.100	S	110	2.500	105.8	180.0	110.0	0.27	03/03/2023
Magnesium		0.050		2.88	2.500	0.2942	103.4	2.901	0.80	03/03/2023
Potassium		1.00		27.0	2.500	25.07	79.2	28.01	3.49	03/06/2023
Sodium		0.050	S	124	2.500	118.6	208.0	123.3	0.40	03/03/2023

Batch 203617		SampType: MBLK		Units mg/L						
SampleID: MBLK-203617										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	03/08/2023
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	03/08/2023
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	03/08/2023
Sodium		0.0500		< 0.0500	0.0180	0	0	-100	100	03/08/2023

Batch 203617		SampType: LCS		Units mg/L						
SampleID: LCS-203617										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100		2.59	2.500	0	103.6	85	115	03/08/2023
Magnesium		0.0500		2.59	2.500	0	103.7	85	115	03/08/2023
Potassium		0.100		2.55	2.500	0	102.0	85	115	03/08/2023
Sodium		0.0500		2.42	2.500	0	96.7	85	115	03/08/2023

Batch 203617		SampType: MS		Units mg/L						
SampID: 23020845-023BMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium		0.100	S	92.6	2.500	87.27	215.2	75	125	03/08/2023
Magnesium		0.050	S	35.0	2.500	29.46	220.0	75	125	03/08/2023
Sodium		0.050	S	55.6	2.500	50.52	204.4	75	125	03/08/2023

Batch 203617		SampType: MSD		Units mg/L				RPD Limit: 20		
SampleID: 23020845-023BMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Calcium		0.100	S	92.6	2.500	87.27	215.2	92.65	0.00	03/08/2023
Magnesium		0.050	S	34.9	2.500	29.46	216.0	34.96	0.29	03/08/2023
Sodium		0.050	S	55.9	2.500	50.52	216.0	55.63	0.52	03/08/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch	203472	SampType:	MBLK	Units µg/L							
SampleID: MBLK-203472											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Aluminum		25.0		< 25.0	12.50	0	0	-100	100	03/02/2023	
Antimony		1.0		< 1.0	0.4500	0	0	-100	100	03/02/2023	
Arsenic		1.0		< 1.0	0.3750	0	0	-100	100	03/02/2023	
Barium		1.0		< 1.0	0.7000	0	0	-100	100	03/02/2023	
Beryllium		1.0		< 1.0	0.2500	0	0	-100	100	03/02/2023	
Boron		25.0		< 25.0	9.250	0	0	-100	100	03/02/2023	
Cadmium		1.0		< 1.0	0.1340	0	0	-100	100	03/02/2023	
Chromium		1.5		< 1.5	0.7000	0	0	-100	100	03/02/2023	
Cobalt		1.0		< 1.0	0.1150	0	0	-100	100	03/02/2023	
Copper		1.0		< 1.0	0.3000	0	0	-100	100	03/02/2023	
Iron		25.0		< 25.0	11.50	0	0	-100	100	03/02/2023	
Lead		1.0		< 1.0	0.6000	0	0	-100	100	03/02/2023	
Manganese		2.0		< 2.0	0.7500	0	0	-100	100	03/02/2023	
Molybdenum		1.5		< 1.5	0.6000	0	0	-100	100	03/02/2023	
Nickel		1.0		< 1.0	0.4300	0	0	-100	100	03/02/2023	
Selenium		1.0		< 1.0	0.6000	0	0	-100	100	03/02/2023	
Silver		1.0		< 1.0	0.1000	0	0	-100	100	03/02/2023	
Thallium		2.0		< 2.0	0.9500	0	0	-100	100	03/02/2023	
Vanadium		5.0		< 5.0	5.000	0	0	-100	100	03/02/2023	
Zinc		15.0		< 15.0	5.900	0	0	-100	100	03/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch 203472		SampType: LCS		Units µg/L							Date Analyzed	
SampleID: LCS-203472												
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			
Aluminum		25.0		1750	2000	0	87.7	80	120	03/03/2023		
Antimony		1.0		542	500.0	0	108.4	80	120	03/02/2023		
Arsenic		1.0		555	500.0	0	111.1	80	120	03/02/2023		
Barium		1.0		2270	2000	0	113.3	80	120	03/02/2023		
Beryllium		1.0		53.8	50.00	0	107.7	80	120	03/02/2023		
Boron		25.0		550	500.0	0	109.9	80	120	03/02/2023		
Cadmium		1.0		54.4	50.00	0	108.7	80	120	03/02/2023		
Chromium		1.5		223	200.0	0	111.6	80	120	03/02/2023		
Cobalt		1.0		572	500.0	0	114.3	80	120	03/02/2023		
Copper		1.0		292	250.0	0	116.8	80	120	03/02/2023		
Iron		25.0		2260	2000	0	113.0	80	120	03/02/2023		
Lead		1.0		559	500.0	0	111.8	80	120	03/02/2023		
Manganese		2.0		559	500.0	0	111.8	80	120	03/02/2023		
Molybdenum		1.5		538	500.0	0	107.5	80	120	03/02/2023		
Nickel		1.0		572	500.0	0	114.4	80	120	03/02/2023		
Selenium		1.0		515	500.0	0	103.1	80	120	03/02/2023		
Silver		1.0		58.9	50.00	0	117.9	80	120	03/02/2023		
Thallium		2.0		276	250.0	0	110.6	80	120	03/02/2023		
Vanadium		5.0		544	500.0	0	108.8	80	120	03/02/2023		
Zinc		15.0		531	500.0	0	106.2	80	120	03/02/2023		



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch 203472 SampType: MS

Units µg/L

SampleID: 23020845-005DMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		25.0		1710	2000	0	85.7	75	125	03/03/2023
Antimony		1.0		590	500.0	0.5607	117.9	75	125	03/02/2023
Arsenic		1.0		600	500.0	0	119.9	75	125	03/02/2023
Barium		1.0		1840	2000	49.50	89.5	75	125	03/03/2023
Beryllium		1.0		45.4	50.00	0	90.8	75	125	03/03/2023
Boron		25.0		646	500.0	175.6	94.0	75	125	03/06/2023
Cadmium		1.0		58.9	50.00	0	117.7	75	125	03/02/2023
Chromium		1.5		177	200.0	0	88.5	75	125	03/03/2023
Cobalt		1.0		572	500.0	0	114.4	75	125	03/02/2023
Copper		1.0		286	250.0	0.7983	114.1	75	125	03/02/2023
Iron		25.0		1790	2000	0	89.7	75	125	03/03/2023
Lead		1.0		592	500.0	0	118.4	75	125	03/02/2023
Manganese		2.0		579	500.0	0	115.9	75	125	03/02/2023
Molybdenum		1.5		611	500.0	19.68	118.3	75	125	03/02/2023
Nickel		1.0		573	500.0	0.7214	114.4	75	125	03/02/2023
Selenium		1.0		560	500.0	0.7404	111.9	75	125	03/02/2023
Silver		1.0		59.8	50.00	0	119.5	75	125	03/02/2023
Thallium		2.0		224	250.0	0	89.5	75	125	03/03/2023
Zinc		15.0		561	500.0	0	112.1	75	125	03/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch 203472		SampType: MSD		Units µg/L			RPD Limit: 20			
SampleID: 23020845-005DMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Aluminum		25.0		1830	2000	0	91.6	1714	6.73	03/03/2023
Antimony		1.0		490	500.0	0.5607	97.8	590.1	18.57	03/02/2023
Arsenic		1.0		505	500.0	0	101.0	599.6	17.11	03/02/2023
Barium		1.0		1920	2000	49.50	93.8	1839	4.59	03/03/2023
Beryllium		1.0		48.5	50.00	0	97.0	45.41	6.61	03/03/2023
Boron		25.0		698	500.0	175.6	104.4	645.7	7.76	03/06/2023
Cadmium		1.0		48.4	50.00	0	96.7	58.87	19.62	03/02/2023
Chromium		1.5		189	200.0	0	94.6	177.0	6.60	03/03/2023
Cobalt		1.0		478	500.0	0	95.6	571.9	17.89	03/02/2023
Copper		1.0		240	250.0	0.7983	95.6	286.1	17.60	03/02/2023
Iron		25.0		1900	2000	0	94.9	1794	5.66	03/03/2023
Lead		1.0		490	500.0	0	98.0	592.1	18.87	03/02/2023
Manganese		2.0		481	500.0	0	96.1	579.4	18.64	03/02/2023
Molybdenum		1.5		505	500.0	19.68	97.1	611.1	18.95	03/02/2023
Nickel		1.0		473	500.0	0.7214	94.5	572.8	19.08	03/02/2023
Selenium		1.0		466	500.0	0.7404	93.1	560.2	18.29	03/02/2023
Silver		1.0		50.4	50.00	0	100.8	59.77	17.03	03/02/2023
Thallium		2.0		243	250.0	0	97.0	223.7	8.08	03/03/2023
Zinc		15.0		466	500.0	0	93.1	560.6	18.50	03/02/2023

Batch 203472		SampType: MS		Units µg/L							
SampleID: 23020845-025DMS											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Boron			25.0		1930	500.0	1517	82.5	75	125	03/07/2023

Batch 203472		SampType: MSD		Units µg/L				RPD Limit: 20			
SampleID: 23020845-025DMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Boron			25.0		1900	500.0	1517	76.1	1929	1.67	03/07/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch	203473	SampType:	MBLK	Units µg/L							
SampleID:		MBLK-203473									Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Aluminum		25.0		< 25.0	12.50	0	0	-100	100	03/02/2023	
Antimony		1.0		< 1.0	0.4500	0	0	-100	100	03/02/2023	
Arsenic		1.0		< 1.0	0.3750	0	0	-100	100	03/02/2023	
Barium		1.0		< 1.0	0.7000	0	0	-100	100	03/02/2023	
Beryllium		1.0		< 1.0	0.2500	0	0	-100	100	03/02/2023	
Boron		25.0		< 25.0	9.250	0	0	-100	100	03/02/2023	
Cadmium		1.0		< 1.0	0.1340	0	0	-100	100	03/02/2023	
Chromium		1.5		< 1.5	0.7000	0	0	-100	100	03/02/2023	
Cobalt		1.0		< 1.0	0.1150	0	0	-100	100	03/02/2023	
Copper		1.0		< 1.0	0.3000	0	0	-100	100	03/02/2023	
Iron		25.0		< 25.0	11.50	0	0	-100	100	03/02/2023	
Lead		1.0		< 1.0	0.6000	0	0	-100	100	03/02/2023	
Manganese		2.0		< 2.0	0.7500	0	0	-100	100	03/02/2023	
Molybdenum		1.5		< 1.5	0.6000	0	0	-100	100	03/02/2023	
Nickel		1.0		< 1.0	0.4300	0	0	-100	100	03/02/2023	
Selenium		1.0		< 1.0	0.6000	0	0	-100	100	03/02/2023	
Silver		1.0		< 1.0	0.1000	0	0	-100	100	03/02/2023	
Thallium		2.0		< 2.0	0.9500	0	0	-100	100	03/02/2023	
Vanadium		5.0		< 5.0	5.000	0	0	-100	100	03/02/2023	
Zinc		15.0		< 15.0	5.900	0	0	-100	100	03/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch	203473	SampType:	LCS	Units µg/L							
SampleID:		LCS-203473									Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Aluminum			25.0		2060	2000	0	103.0	80	120	03/03/2023
Antimony			1.0		502	500.0	0	100.5	80	120	03/03/2023
Arsenic			1.0		488	500.0	0	97.6	80	120	03/03/2023
Barium			1.0		2130	2000	0	106.4	80	120	03/03/2023
Beryllium			1.0		52.1	50.00	0	104.2	80	120	03/03/2023
Boron			25.0		501	500.0	0	100.3	80	120	03/03/2023
Cadmium			1.0		52.0	50.00	0	104.0	80	120	03/03/2023
Chromium			1.5		214	200.0	0	107.0	80	120	03/03/2023
Cobalt			1.0		543	500.0	0	108.6	80	120	03/03/2023
Copper			1.0		275	250.0	0	110.0	80	120	03/03/2023
Iron			25.0		2160	2000	0	108.0	80	120	03/03/2023
Lead			1.0		529	500.0	0	105.7	80	120	03/03/2023
Manganese			2.0		533	500.0	0	106.7	80	120	03/03/2023
Molybdenum			1.5		517	500.0	0	103.4	80	120	03/03/2023
Nickel			1.0		538	500.0	0	107.7	80	120	03/03/2023
Selenium			1.0		473	500.0	0	94.6	80	120	03/03/2023
Silver			1.0		52.3	50.00	0	104.5	80	120	03/03/2023
Thallium			2.0		244	250.0	0	97.4	80	120	03/03/2023
Vanadium			5.0		523	500.0	0	104.7	80	120	03/03/2023
Zinc			15.0		462	500.0	0	92.3	80	120	03/03/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch	203473	SampType:	MS	Units µg/L							
SampID: 23020845-035EMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Antimony		1.0		407	500.0	0	81.3	75	125	03/03/2023	
Arsenic		1.0		442	500.0	0.5053	88.2	75	125	03/03/2023	
Barium		1.0		1740	2000	46.25	84.8	75	125	03/03/2023	
Beryllium		1.0		42.5	50.00	0	85.0	75	125	03/03/2023	
Boron		25.0		3200	500.0	2627	114.2	75	125	03/02/2023	
Cadmium		1.0		41.9	50.00	0	83.8	75	125	03/03/2023	
Chromium		1.5		168	200.0	0.8898	83.5	75	125	03/03/2023	
Cobalt		1.0		423	500.0	0.1224	84.5	75	125	03/03/2023	
Copper		1.0		211	250.0	0.8759	84.1	75	125	03/03/2023	
Iron		25.0		1720	2000	0	86.0	75	125	03/03/2023	
Lead		1.0		439	500.0	0	87.7	75	125	03/03/2023	
Manganese		2.0		427	500.0	2.474	85.0	75	125	03/03/2023	
Nickel		1.0		415	500.0	0.9686	82.7	75	125	03/03/2023	
Selenium		1.0		635	500.0	18.35	123.4	75	125	03/02/2023	
Silver		1.0		42.8	50.00	0	85.7	75	125	03/03/2023	
Thallium		2.0		219	250.0	0	87.4	75	125	03/03/2023	
Vanadium		5.0		428	500.0	6.704	84.2	75	125	03/03/2023	
Zinc		15.0		619	500.0	0	123.8	75	125	03/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch 203473		SampType: MSD		Units µg/L				RPD Limit: 20		
SampleID: 23020845-035EMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Antimony		1.0		421	500.0	0	84.1	406.6	3.38	03/03/2023
Arsenic		1.0		441	500.0	0.5053	88.2	441.6	0.05	03/03/2023
Barium		1.0		1770	2000	46.25	86.1	1743	1.51	03/03/2023
Beryllium		1.0		42.1	50.00	0	84.1	42.49	1.00	03/03/2023
Boron		25.0		3180	500.0	2627	110.8	3198	0.53	03/02/2023
Cadmium		1.0		42.1	50.00	0	84.1	41.89	0.39	03/03/2023
Chromium		1.5		169	200.0	0.8898	83.9	167.8	0.54	03/03/2023
Cobalt		1.0		419	500.0	0.1224	83.9	422.8	0.81	03/03/2023
Copper		1.0		210	250.0	0.8759	83.8	211.0	0.32	03/03/2023
Iron		25.0		1710	2000	0	85.6	1720	0.49	03/03/2023
Lead		1.0		437	500.0	0	87.3	438.6	0.47	03/03/2023
Manganese		2.0		425	500.0	2.474	84.5	427.3	0.59	03/03/2023
Nickel		1.0		413	500.0	0.9686	82.3	414.7	0.49	03/03/2023
Selenium		1.0		634	500.0	18.35	123.2	635.4	0.17	03/02/2023
Silver		1.0		43.2	50.00	0	86.5	42.84	0.94	03/03/2023
Thallium		2.0		215	250.0	0	86.0	218.6	1.61	03/03/2023
Vanadium		5.0		425	500.0	6.704	83.7	427.7	0.56	03/03/2023
Zinc		15.0	S	626	500.0	0	125.1	618.9	1.08	03/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch 203473		SampType: MS		Units µg/L							Date Analyzed	
SampleID: 23020845-051EMS												
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			
Aluminum		25.0		1820	2000	0	90.9	75	125		03/03/2023	
Antimony		1.0		462	500.0	0	92.4	75	125		03/03/2023	
Arsenic		1.0		490	500.0	0	98.1	75	125		03/02/2023	
Barium		1.0		1930	2000	0	96.3	75	125		03/03/2023	
Beryllium		1.0		48.6	50.00	0	97.2	75	125		03/02/2023	
Boron		25.0		504	500.0	0	100.9	75	125		03/02/2023	
Cadmium		1.0		46.6	50.00	0	93.1	75	125		03/03/2023	
Chromium		1.5		202	200.0	1.653	100.0	75	125		03/02/2023	
Cobalt		1.0		478	500.0	0	95.6	75	125		03/03/2023	
Copper		1.0		255	250.0	1.672	101.4	75	125		03/02/2023	
Iron		25.0		1930	2000	17.63	95.5	75	125		03/03/2023	
Lead		1.0		500	500.0	0	100.1	75	125		03/02/2023	
Manganese		2.0		496	500.0	0	99.2	75	125		03/02/2023	
Molybdenum		1.5		464	500.0	0	92.8	75	125		03/03/2023	
Nickel		1.0		494	500.0	0	98.8	75	125		03/02/2023	
Selenium		1.0		464	500.0	0	92.7	75	125		03/02/2023	
Silver		1.0		48.1	50.00	0	96.2	75	125		03/03/2023	
Thallium		2.0		246	250.0	0	98.3	75	125		03/02/2023	
Vanadium		5.0		477	500.0	0	95.3	75	125		03/02/2023	
Zinc		15.0		484	500.0	0	96.9	75	125		03/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch 203473		SampType: MSD		Units µg/L			RPD Limit: 20			
SampleID: 23020845-051EMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Aluminum		25.0		1760	2000	0	88.1	1818	3.10	03/03/2023
Antimony		1.0		456	500.0	0	91.2	462.1	1.29	03/03/2023
Arsenic		1.0		589	500.0	0	117.8	490.3	18.30	03/02/2023
Barium		1.0		1910	2000	0	95.4	1926	0.99	03/03/2023
Beryllium		1.0		59.3	50.00	0	118.7	48.59	19.92	03/02/2023
Boron		25.0		594	500.0	0	118.8	504.4	16.28	03/02/2023
Cadmium		1.0		46.0	50.00	0	92.1	46.56	1.13	03/03/2023
Chromium		1.5		239	200.0	1.653	118.6	201.7	16.83	03/02/2023
Cobalt		1.0		464	500.0	0	92.9	478.1	2.92	03/03/2023
Copper		1.0		308	250.0	1.672	122.6	255.2	18.83	03/02/2023
Iron		25.0		1880	2000	17.63	93.3	1928	2.33	03/03/2023
Lead		1.0		604	500.0	0	120.8	500.4	18.76	03/02/2023
Manganese		2.0		599	500.0	0	119.9	496.2	18.82	03/02/2023
Molybdenum		1.5		458	500.0	0	91.6	463.8	1.22	03/03/2023
Nickel		1.0		598	500.0	0	119.6	494.0	19.06	03/02/2023
Selenium		1.0		551	500.0	0	110.2	463.7	17.20	03/02/2023
Silver		1.0		48.2	50.00	0	96.4	48.12	0.20	03/03/2023
Thallium		2.0		292	250.0	0	116.6	245.7	17.06	03/02/2023
Vanadium		5.0		578	500.0	0	115.5	476.7	19.16	03/02/2023
Zinc		15.0		584	500.0	0	116.8	484.3	18.67	03/02/2023

Batch 204110		SampType: MBLK		Units µg/L							
SampID: MBLK-204110											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Boron		25.0		< 25.0	9.250	0	0	-100	100	03/22/2023	
Cobalt		1.0		< 1.0	0.1150	0	0	-100	100	03/22/2023	

Batch	204110	SampType:	LCS	Units µg/L						
SampID: LCS-204110										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Boron		25.0		481	500.0	0	96.2	80	120	03/22/2023
Cobalt		1.0		485	500.0	0	97.1	80	120	03/22/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch 204110		SampType: MS		Units µg/L							
SampID: 23020845-019DMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Boron		25.0	S	8520	500.0	8393	25.9	75	125	03/22/2023	

Batch 204110		SampType: MSD		Units µg/L				RPD Limit: 20			
SampID: 23020845-019DMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Boron			25.0	S	8570	500.0	8393	35.3	8522	0.55	03/22/2023

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 203466		SampType: MBLK		Units µg/L							
SampID: MBLK-203466											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Antimony		1.0		< 1.0	0.4500	0	0	-100	100	03/03/2023	
Arsenic		1.0		< 1.0	0.3750	0	0	-100	100	03/03/2023	
Barium		1.0		< 1.0	0.7000	0	0	-100	100	03/03/2023	
Beryllium		1.0		< 1.0	0.2500	0	0	-100	100	03/06/2023	
Boron		25.0		< 25.0	9.250	0	0	-100	100	03/06/2023	
Cadmium		1.0		< 1.0	0.1340	0	0	-100	100	03/03/2023	
Chromium		1.5		< 1.5	0.7000	0	0	-100	100	03/06/2023	
Cobalt		1.0		< 1.0	0.1150	0	0	-100	100	03/03/2023	
Lead		1.0		< 1.0	0.6000	0	0	-100	100	03/03/2023	
Lithium	*	3.0		< 3.0	1.450	0	0	-100	100	03/06/2023	
Molybdenum		1.5		< 1.5	0.6000	0	0	-100	100	03/03/2023	
Selenium		1.0		< 1.0	0.6000	0	0	-100	100	03/03/2023	
Thallium		2.0		< 2.0	0.9500	0	0	-100	100	03/03/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 203466		SampType: LCS		Units µg/L							
SampID: LCS-203466											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Antimony		1.0		494	500.0	0	98.9	80	120	03/03/2023	
Arsenic		1.0		480	500.0	0	96.0	80	120	03/03/2023	
Barium		1.0		2100	2000	0	104.8	80	120	03/03/2023	
Beryllium		1.0		51.2	50.00	0	102.3	80	120	03/06/2023	
Boron		25.0		518	500.0	0	103.6	80	120	03/06/2023	
Cadmium		1.0		56.3	50.00	0	112.5	80	120	03/03/2023	
Chromium		1.5		206	200.0	0	103.2	80	120	03/06/2023	
Cobalt		1.0		494	500.0	0	98.8	80	120	03/03/2023	
Lead		1.0		489	500.0	0	97.7	80	120	03/03/2023	
Lithium	*	3.0		574	500.0	0	114.7	80	120	03/06/2023	
Molybdenum		1.5		505	500.0	0	101.1	80	120	03/03/2023	
Selenium		1.0		448	500.0	0	89.5	80	120	03/03/2023	
Thallium		2.0		243	250.0	0	97.0	80	120	03/03/2023	

Batch 203466		SampType: MS		Units µg/L							
SampID: 23020845-007CMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Antimony		1.0		505	500.0	0	101.1	75	125	03/03/2023	
Arsenic		1.0		498	500.0	0	99.7	75	125	03/03/2023	
Barium		1.0		2240	2000	116.6	106.3	75	125	03/03/2023	
Beryllium		1.0		52.7	50.00	0	105.5	75	125	03/06/2023	
Boron		25.0		738	500.0	207.3	106.2	75	125	03/06/2023	
Cadmium		1.0		55.5	50.00	0	111.0	75	125	03/03/2023	
Chromium		1.5		203	200.0	0	101.4	75	125	03/06/2023	
Cobalt		1.0		487	500.0	0.1439	97.3	75	125	03/03/2023	
Lead		1.0		505	500.0	0	101.0	75	125	03/03/2023	
Lithium	*	3.0		607	500.0	7.654	119.8	75	125	03/06/2023	
Molybdenum		1.5		505	500.0	9.996	99.1	75	125	03/03/2023	
Selenium		1.0		461	500.0	0	92.2	75	125	03/03/2023	
Thallium		2.0		248	250.0	0	99.2	75	125	03/03/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 203466		SampType: MSD		Units µg/L				RPD Limit: 20		
SampleID: 23020845-007CMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Antimony		1.0		508	500.0	0	101.7	505.4	0.60	03/03/2023
Arsenic		1.0		503	500.0	0	100.6	498.4	0.93	03/03/2023
Barium		1.0		2250	2000	116.6	106.7	2242	0.40	03/03/2023
Beryllium		1.0		53.0	50.00	0	105.9	52.73	0.46	03/06/2023
Boron		25.0		752	500.0	207.3	108.8	738.3	1.78	03/06/2023
Cadmium		1.0		56.6	50.00	0	113.2	55.51	1.96	03/03/2023
Chromium		1.5		202	200.0	0	100.9	202.8	0.51	03/06/2023
Cobalt		1.0		505	500.0	0.1439	101.0	486.7	3.76	03/03/2023
Lead		1.0		514	500.0	0	102.7	504.9	1.72	03/03/2023
Lithium	*	3.0		605	500.0	7.654	119.5	606.8	0.30	03/06/2023
Molybdenum		1.5		528	500.0	9.996	103.7	505.5	4.42	03/03/2023
Selenium		1.0		466	500.0	0	93.1	461.0	0.98	03/03/2023
Thallium		2.0		250	250.0	0	99.9	247.9	0.72	03/03/2023

Batch 203468		SampType: MBLK		Units µg/L							
SampleID: MBLK-203468											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Antimony		1.0		< 1.0	0.4500	0	0	-100	100	03/03/2023	
Arsenic		1.0		< 1.0	0.3750	0	0	-100	100	03/03/2023	
Barium		1.0		< 1.0	0.7000	0	0	-100	100	03/03/2023	
Beryllium		1.0		< 1.0	0.2500	0	0	-100	100	03/06/2023	
Boron		25.0		< 25.0	9.250	0	0	-100	100	03/06/2023	
Cadmium		1.0		< 1.0	0.1340	0	0	-100	100	03/03/2023	
Chromium		1.5		< 1.5	0.7000	0	0	-100	100	03/06/2023	
Cobalt		1.0		< 1.0	0.1150	0	0	-100	100	03/03/2023	
Lead		1.0		< 1.0	0.6000	0	0	-100	100	03/03/2023	
Lithium	*	3.0		< 3.0	1.450	0	0	-100	100	03/06/2023	
Molybdenum		1.5		< 1.5	0.6000	0	0	-100	100	03/03/2023	
Selenium		1.0		< 1.0	0.6000	0	0	-100	100	03/03/2023	
Thallium		2.0		< 2.0	0.9500	0	0	-100	100	03/03/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 203468 SampType: LCS Units µg/L

SampleID: LCS-203468

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		1.0		498	500.0	0	99.6	80	120	03/03/2023
Arsenic		1.0		497	500.0	0	99.4	80	120	03/03/2023
Barium		1.0		2160	2000	0	108.0	80	120	03/03/2023
Beryllium		1.0		55.0	50.00	0	109.9	80	120	03/06/2023
Boron		25.0		561	500.0	0	112.2	80	120	03/06/2023
Cadmium		1.0		56.0	50.00	0	111.9	80	120	03/03/2023
Chromium		1.5		218	200.0	0	109.2	80	120	03/06/2023
Cobalt		1.0		516	500.0	0	103.2	80	120	03/03/2023
Lead		1.0		491	500.0	0	98.2	80	120	03/03/2023
Lithium	*	3.0		496	500.0	0	99.2	80	120	03/07/2023
Molybdenum		1.5		508	500.0	0	101.7	80	120	03/03/2023
Selenium		1.0		460	500.0	0	91.9	80	120	03/03/2023
Thallium		2.0		235	250.0	0	93.8	80	120	03/03/2023

Batch 203617 SampType: MBLK Units µg/L

SampleID: MBLK-203617

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Boron		25.0		< 25.0	9.250	0	0	-100	100	03/08/2023

Batch 203617 SampType: LCS Units µg/L

SampleID: LCS-203617

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Boron		25.0		516	500.0	0	103.1	80	120	03/08/2023

Batch 203617 SampType: MS Units µg/L

SampleID: 23020845-023BMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Boron		25.0		2450	1000	1407	104.3	75	125	03/08/2023

Batch 203617 SampType: MSD Units µg/L

RPD Limit: 20

SampleID: 23020845-023BMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Boron		25.0		2370	1000	1407	96.3	2450	3.29	03/08/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 204109 SampType: MBLK Units µg/L

SampleID: MBLK-204109

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Boron		25.0		< 25.0	9.250	0	0	-100	100	03/22/2023
Cobalt		1.0		< 1.0	0.1150	0	0	-100	100	03/22/2023

Batch 204109 SampType: LCS Units µg/L

SampleID: LCS-204109

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Boron		25.0		503	500.0	0	100.5	80	120	03/22/2023
Cobalt		1.0		528	500.0	0	105.7	80	120	03/22/2023

Batch 204109 SampType: MS Units µg/L

SampleID: 23020845-016CMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Boron		25.0		671	500.0	198.9	94.4	75	125	03/22/2023

Batch 204109 SampType: MSD Units µg/L

SampleID: 23020845-016CMSD

RPD Limit: 20

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Boron		25.0		661	500.0	198.9	92.4	671.0	1.50	03/22/2023

SW-846 7470A (DISSOLVED)

Batch 203471 SampType: MBLK Units µg/L

SampleID: MBLK-203471

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Mercury		0.20		< 0.20	0.0550	0	0	-100	100	03/03/2023

Batch 203471 SampType: LCS Units µg/L

SampleID: LCS-203471

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Mercury		0.20		4.84	5.000	0	96.9	85	115	03/03/2023

Batch 203471 SampType: MS Units µg/L

SampleID: 23020845-039EMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Mercury		0.20		5.04	5.000	0	100.7	75	125	03/06/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 7470A (DISSOLVED)

Batch 203471		SampType: MSD		Units µg/L					RPD Limit: 15		
SampID: 23020845-039EMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Mercury			0.20		5.08	5.000	0	101.6	5.036	0.84	03/06/2023

SW-846 7470A (TOTAL)

Batch 203469		SampType: MBLK		Units µg/L							
SampleID: MBLK-203469											Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Mercury			0.20		< 0.20	0.0550	0	0	-100	100	03/06/2023

Batch 203469		SampType: LCS		Units µg/L							
SampleID: LCS-203469											Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Mercury			0.20		4.85	5.000	0	97.0	85	115	03/06/2023

Batch 203469		SampType: MS		Units µg/L							
SampleID: 23020845-002DMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.20		5.24	5.000	0	104.8	75	125	03/06/2023	

Batch	203469	SampType:	MSD	Units µg/L							RPD Limit: 15	
SampleID: 23020845-002DMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Mercury			0.20		4.90	5.000	0	98.1	5.239	6.62	03/06/2023	

Batch 203469		SampType: MS		Units µg/L							
SampleID: 23020845-013CMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.20		5.35	5.000	0	106.9	75	125	03/06/2023	

Batch 203469		SampType: MSD		Units µg/L					RPD Limit: 15		
SampleID: 23020845-013CMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Mercury			0.20		5.42	5.000	0	108.3	5.346	1.30	03/06/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

SW-846 7470A (TOTAL)

Batch 203470		SampType: MBLK		Units µg/L							
SampID: MBLK-203470											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.20		< 0.20	0.0550	0	0	-100	100	03/06/2023	

Batch 203470		SampType: LCS		Units µg/L							
SampID: LCS-203470											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Mercury		0.20		5.06	5.000	0	101.2	85	115	03/06/2023	

Batch 203470		SampType: MS		Units µg/L							
SampID: 23020845-024CMS											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Mercury		0.20		5.46	5.000	0	109.2	75	125	03/06/2023	

Batch 203470		SampType: MSD		Units µg/L				RPD Limit: 15			
SampID: 23020845-024CMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Mercury			0.20		5.46	5.000	0	109.2	5.460	0.05	03/06/2023

Batch 203470		SampType: MS		Units µg/L							
SampID: 23020845-036CMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.20		5.30	5.000	0	106.0	75	125	03/07/2023	

Batch 203470		SampType: MSD		Units µg/L				RPD Limit: 15			
SampID: 23020845-036CMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Mercury		0.20		5.30	5.000	0	106.0	5.300	0.05	03/07/2023	

Batch 203471		SampType: MS		Units µg/L							
SampID: 23020845-051DMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.20		5.02	5.000	0	100.4	75	125	03/06/2023	

Batch 203471		SampType: MSD		Units µg/L				RPD Limit: 15			
SampID: 23020845-051DMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Mercury			0.20		4.90	5.000	0	98.0	5.022	2.45	03/06/2023



Receiving Check List

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020845

Client Project: HEN-23Q1

Report Date: 14-Apr-23

Carrier: Joe Riley

Received By: ANC

Completed by:

On:

02-Mar-23

Lindsey Maddox

Reviewed by:

On:

02-Mar-23

Elizabeth A. Hurley

Pages to follow: Chain of custody

4

Extra pages included

0

Shipping container/cooler in good condition?

Yes ☒

No ☐

Not Present ☐

Temp °C 3.2

Type of thermal preservation?

None ☐

Ice ☒

Blue Ice ☐

Dry Ice ☐

Chain of custody present?

Yes ☒

No ☐

Chain of custody signed when relinquished and received?

Yes ☒

No ☐

Chain of custody agrees with sample labels?

Yes ☒

No ☐

Samples in proper container/bottle?

Yes ☒

No ☐

Sample containers intact?

Yes ☒

No ☐

Sufficient sample volume for indicated test?

Yes ☒

No ☐

All samples received within holding time?

Yes ☒

No ☐

Reported field parameters measured:

Field ☒

Lab ☐

NA ☐

Container/Temp Blank temperature in compliance?

Yes ☒

No ☐

When thermal preservation is required, samples are compliant with a temperature between 0.1°C - 6.0°C, or when samples are received on ice the same day as collected.

Water – at least one vial per sample has zero headspace?

Yes ☒

No ☐

No VOA vials ☐

Water - TOX containers have zero headspace?

Yes ☐

No ☐

No TOX containers ☒

Water - pH acceptable upon receipt?

Yes ☐

No ☒

NA ☐

NPDES/CWA TCN interferences checked/treated in the field?

Yes ☐

No ☐

NA ☒

Any No responses must be detailed below or on the COC.

pH strip #87147/79929. - TSM/Imaddox - 3/2/2023 8:53:12 AM

Additional Sodium Hydroxide (81662) was needed in 02, 07, 08, 10, 12, 13, 16, 17, 05R, 08D, 18D, 06, 15, and 08 Duplicate upon arrival at the laboratory. - Imaddox - 3/2/2023 10:13:57 AM

Additional Nitric Acid (87873) was needed in 08D and 08 Duplicate upon arrival at the laboratory. - Imaddox - 3/2/2023 10:15:51 AM

Additional Sulfuric Acid (86787) was needed in 08 upon arrival at the laboratory. - Imaddox - 3/2/2023 10:22:00 AM

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST WASH POND
HEN-257-804

APPENDIX A

Section A

Required Client Information:

Section B

Required Project Information:

Section C

Invoice Information:

Page: 1 of 4

Company: Vistra Corp	Report To: Brian Voelker	Attention: Jason Stuckey	REGULATORY AGENCY		
Address: 13498 E. 900th St	Copy To: Jason Stuckey	Company Name: Vistra Corp			
		Address: see Section A			
Email To: Brian.Voelker@VistraCorp.com	Purchase Order No.:	Quote Reference:			
Phone: (217) 753-8911 Fax:	Project Name:	Project Manager:	NPDES	GROUND WATER	DRINKING WATER
Requested Due Date/TAT: 10 day	Project Number: 2285	Profile #:	UST	RCRA	OTHER
			Site Location	IL	
			STATE:		

ITEM #	Section D Required Client Information	Valid Matrix Codes MATRIX CODE ORINKING WATER OW WATER WT WASTE WATER WW PRODUCT P SOIL/SOLID SL OIL OL WIPE WP AIR AP OTHER OT TISSUE TS	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives										Analysis Test ↓	Requested Analysis Filtered (Y/N)										Residual Chlorine (Y/N)	Project No./ Lab I.D.
					DATE	TIME			Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other	HEN_257_801	HEN_257_802		HEN_257_803	HEN_257_804	HEN_811_801	HEN_CLOSURE_802-805	HEN_CLOSURE_804	HEN_WPCP_East	HEN_WPCP_West	East Group 1	East Group 2			
1	*	- 02			03/01/23	1423																				23020845-001					
2	*	- 07			03/01/23	1616																				002					
3	* X	- 08			03/01/23	1501																				003					
4	* * TE	- 10			03/01/23	0417																				004					
5	* * TE	- 12			03/01/23	1046																				005					
6	* * TE	- 13			03/01/23	1028																				006					
7	*	- 16			02/28/23	1557																				007					
8	*	- 17			02/28/23	1614																				008					
9		- 22			03/28/23	1745																				009					
10		- 23			02/28/23	1035																				010					
11		- 25			02/28/23	1435																				011					
12		- 26			02/28/23	1436																				012					
13		- 27			02/28/23	1347																				013					
14		- 30			02/28/23	1249																				014					
15		- 31			02/28/23	1250																				015					
16		- 32			02/28/23	1306																				016					
ADDITIONAL COMMENTS					RELINQUISHED BY / AFFILIATION		DATE	TIME	ACCEPTED BY / AFFILIATION		DATE	TIME	SAMPLE CONDITIONS																		
HEN-23Q1 Rev 0					J/M Tel/ab		03/01/23	1506	Aurism Colon		3/2/23	800																			

SAMPLER NAME AND SIGNATURE			
PRINT Name of SAMPLER: Joe R. R. R.		DATE Signed (MM/DD/YY): 03/02/23	
SIGNATURE of SAMPLER: [Signature]		Temp in °C	
		Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)
		Samples Intact (Y/N)	

HS present in FB(213)

* Added HNO₃(87873)

* Added NaOH(81662)

X Added H₂SO₄(86787)3.2 #5
PH: 87147/79929 UM
TSM 312TE
EAH
3/23/23

Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page: 2 of 4

Section C

Required Client Information:

Required Project Information:

Invoice Information:

Company: Vistra Corp		Report To: Brian Voelker		Attention: Jason Stuckey				
Address: 13498 E. 900th St		Copy To: Jason Stuckey		Company Name: Vistra Corp		REGULATORY AGENCY		
				Address: see Section A		NPDES GROUND WATER DRINKING WATER UST RCRA OTHER		
Email To: <u>Brian.Voelker@VistraCorp.com</u>		Purchase Order No.:		Quote Reference:				
Phone: (217) 753-8911	Fax:	Project Name:		Project Manager:		Site Location		
Requested Due Date/TAT: 10 day		Project Number: 2285		Profile #:		STATE:		IL

[illegible]

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER: Joe Rife					
SIGNATURE of SAMPLER: [Signature]	DATE Signed (MM/DD/YY): 03/09/23				

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

HENNEPIN POWER PLANT, OLD WEST ASHLAND

HEN-257-804

APPENDIX A.

Section A

Required Client Information:

Company: **Vistra Corp**
 Address: **13498 E. 900th St**
 Email To: **Brian.Voelker@VistraCorp.com**
 Phone: **(217) 753-8911** Fax:
 Requested Due Date/TAT: **10 day**

Section B

Required Project Information:

Report To: **Brian Voelker**
 Copy To: **Jason Stuckey**
 Purchase Order No.:
 Project Name:
 Project Number: **2285**

Section C

Invoice Information:

Attention: **Jason Stuckey**
 Company Name: **Vistra Corp**
 Address: **see Section A**
 Quote Reference:
 Project Manager:
 Profile #:

Page: **3** of **4**

REGULATORY AGENCY

NPDES GROUND WATER DRINKING WATER
 UST RCRA OTHER

Site Location

IL

STATE:

Requested Analysis Filtered (Y/N)

ITEM #	Section D Required Client Information		Valid Matrix Codes		MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives								Analysis Test ↓	Requested Analysis Filtered (Y/N)																Residual Chlorine (Y/N)	Project No./ Lab I.D.
			MATRIX	CODE			DATE	TIME			Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other		HEN_257_801	HEN_257_802	HEN_257_803	HEN_257_804	HEN_811_801	HEN_CLOSURE_802-805	HEN_CLOSURE_804	HEN_WPCP_East	HEN_WPCP_West	East Group 1	East Group 2							
			DRINKING WATER	DW																											WATER	WT	WASTE WATER	WW	PRODUCT		
SAMPLE ID (A-Z, 0-9 / , -) Sample IDs MUST BE UNIQUE																																					
1	***	08D					03/01/23	1442												✓	✓	✓		✓	✓	✓	✓	✓	✓				23020845-033				
2	***	18D					03/01/23	1309												✓	✓			✓	✓	✓	✓	✓	✓				034				
3		18S					03/01/23	1255													✓			✓	✓	✓	✓	✓	✓				035				
4		21R					02/25/23	0915															✓		✓	✓	✓	✓	✓				036				
5		22D					02/25/23	1144															✓		✓	✓	✓	✓					037				
6		40S					03/01/23	1200												✓				✓		✓	✓	✓	✓				038				
7		45S					03/01/23	1350													✓			✓	✓	✓	✓	✓					039				
8		SG02					03/02/23	0730	0											✓	✓	✓	✓	✓	✓	✓	✓	✓					040				
9		XPW01					02/28/23	1519													✓	✓	✓	✓	✓	✓	✓	✓					041				
10		XPW02	03/01/23				03/01/23	0813													✓	✓	✓	✓	✓	✓	✓	✓					042				
11		XPW03					03/01/23	1537																									043				
12		XSG01					02/25/23	1630	0												✓			✓	✓	✓	✓	✓					044				
13		04R					03/01/23	1120																				✓					045				
14	***	06					03/01/23	1408																				✓	✓				046				
15	***	15					03/01/23	1107																				✓	✓				047				
16		19D					03/01/23	1148																				✓	✓				048				

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS			
HEN-23Q1 Rev 0	4/m Teklab	03/01/23	0805	Allen Coler	3/2/23	800				

SAMPLER NAME AND SIGNATURE

PRINT Name of SAMPLER: Joe Rile-

SIGNATURE of SAMPLER: [Signature]

DATE Signed (MM/DD/YY): 03/02/23

Temp in °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples intact (Y/N)

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
Request Document HENNEPIN POWER PLANT, OLD WEST ASH POND

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

APPENDIX A

ACTION REPORT

EST ASH POND

HFN-257-804

Section C

Invoice Information:

Page: 4 of 4

Company: Vistra Corp		Report To: Brian Voelker	Attention: Jason Stuckey			
Address: 13498 E. 900th St		Copy To: Jason Stuckey	Company Name: Vistra Corp	REGULATORY AGENCY		
			Address: see Section A	NPDES	GROUND WATER	DRINKING WATER
Email To: <u>Brian.Voelker@VistraCorp.com</u>		Purchase Order No.:	Quote Reference:	UST	RCRA	OTHER
Phone: (217) 753-8911	Fax:	Project Name:	Project Manager:	Site Location		
Requested Due Date/TAT: 10 day		Project Number: 2285	Profile #:	STATE:	IL	

[illegible]

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER: Joe Riley					
SIGNATURE of SAMPLER: [Signature]	DATE Signed (MM/DD/YY): 03/22/23				

March 27, 2023

Eric Bauer
Ramboll
234 W. Florida St.
5th Floor
Milwaukee, WI 61704
TEL: (414) 837-3607
FAX:



Illinois	100226
Kansas	E-10374
Louisiana	05002
Louisiana	05003
Oklahoma	9978

RE: HEN-23Q1

WorkOrder: 23020844

Dear Eric Bauer:

TEKLAB, INC received 28 samples on 3/2/2023 8:00:00 AM for the analysis presented in the following report.

Samples are analyzed on an as received basis unless otherwise requested and documented. The sample results contained in this report relate only to the requested analytes of interest as directed on the chain of custody. NELAP accredited fields of testing are indicated by the letters NELAP under the Certification column. Unless otherwise documented within this report, Teklab Inc. analyzes samples utilizing the most current methods in compliance with 40CFR. All tests are performed in the Collinsville, IL laboratory unless otherwise noted in the Case Narrative.

All quality control criteria applicable to the test methods employed for this project have been satisfactorily met and are in accordance with NELAP except where noted. The following report shall not be reproduced, except in full, without the written approval of Teklab, Inc.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,



Elizabeth A. Hurley
Director of Customer Service
(618)344-1004 ex 33
ehurley@teklabinc.com



Report Contents

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020844

Client Project: HEN-23Q1

Report Date: 27-Mar-23

This reporting package includes the following:

Cover Letter	1
Report Contents	2
Definitions	3
Case Narrative	5
Accreditations	6
Laboratory Results	7
Sample Summary	35
Dates Report	36
Receiving Check List	38
Chain of Custody	Appended



Definitions

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020844

Client Project: HEN-23Q1

Report Date: 27-Mar-23

Abbr Definition

* Analytes on report marked with an asterisk are not NELAP accredited

CCV Continuing calibration verification is a check of a standard to determine the state of calibration of an instrument between recalibration.

CRQL A Client Requested Quantitation Limit is a reporting limit that varies according to customer request. The CRQL may not be less than the MDL.

DF Dilution factor is the dilution performed during analysis only and does not take into account any dilutions made during sample preparation. The reported result is final and includes all dilution factors.

DNI Did not ignite

DUP Laboratory duplicate is a replicate aliquot prepared under the same laboratory conditions and independently analyzed to obtain a measure of precision.

ICV Initial calibration verification is a check of a standard to determine the state of calibration of an instrument before sample analysis is initiated.

IDPH IL Dept. of Public Health

LCS Laboratory control sample is a sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes and analyzed exactly like a sample to establish intra-laboratory or analyst specific precision and bias or to assess the performance of all or a portion of the measurement system.

LCSD Laboratory control sample duplicate is a replicate laboratory control sample that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).

MBLK Method blank is a sample of a matrix similar to the batch of associated sample (when available) that is free from the analytes of interest and is processed simultaneously with and under the same conditions as samples through all steps of the analytical procedures, and in which no target analytes or interferences should present at concentrations that impact the analytical results for sample analyses.

MDL "The method detection limit is defined as the minimum measured concentration of a substance that can be reported with 99% confidence that the measured concentration is distinguishable from method blank results."

MS Matrix spike is an aliquot of matrix fortified (spiked) with known quantities of specific analytes that is subjected to the entire analytical procedures in order to determine the effect of the matrix on an approved test method's recovery system. The acceptable recovery range is listed in the QC Package (provided upon request).

MSD Matrix spike duplicate means a replicate matrix spike that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).

MW Molecular weight

NC Data is not acceptable for compliance purposes

ND Not Detected at the Reporting Limit

NELAP NELAP Accredited

PQL Practical quantitation limit means the lowest level that can be reliably achieved within specified limits of precision and accuracy during routine laboratory operation conditions.

RL The reporting limit the lowest level that the data is displayed in the final report. The reporting limit may vary according to customer request or sample dilution. The reporting limit may not be less than the MDL.

RPD Relative percent difference is a calculated difference between two recoveries (ie. MS/MSD). The acceptable recovery limit is listed in the QC Package (provided upon request).

SPK The spike is a known mass of target analyte added to a blank sample or sub-sample; used to determine recovery deficiency or for other quality control purposes.

Surr Surrogates are compounds which are similar to the analytes of interest in chemical composition and behavior in the analytical process, but which are not normally found in environmental samples.

TIC Tentatively identified compound: Analytes tentatively identified in the sample by using a library search. Only results not in the calibration standard will be reported as tentatively identified compounds. Results for tentatively identified compounds that are not present in the calibration standard, but are assigned a specific chemical name based upon the library search, are calculated using total peak areas from reconstructed ion chromatograms and a response factor of one. The nearest Internal Standard is used for the calculation. The results of any TICs must be considered estimated, and are flagged with a "T". If the estimated result is above the calibration range it is flagged "ET"

TNTC Too numerous to count (> 200 CFU)



Definitions

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020844

Client Project: HEN-23Q1

Report Date: 27-Mar-23

Qualifiers

- | | |
|---|--|
| # - Unknown hydrocarbon | B - Analyte detected in associated Method Blank |
| C - RL shown is a Client Requested Quantitation Limit | E - Value above quantitation range |
| H - Holding times exceeded | I - Associated internal standard was outside method criteria |
| J - Analyte detected below quantitation limits | M - Manual Integration used to determine area response |
| ND - Not Detected at the Reporting Limit | R - RPD outside accepted recovery limits |
| S - Spike Recovery outside recovery limits | T - TIC(Tentatively identified compound) |
| X - Value exceeds Maximum Contaminant Level | |



Case Narrative

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020844
Report Date: 27-Mar-23

Cooler Receipt Temp: 3.2 °C

An employee of Teklab, Inc. collected the sample(s).

Radium-226 and Radium-228 analysis was performed by Pace Analytical Services, LLC. See attached report for results.

Locations

Collinsville

Address 5445 Horseshoe Lake Road
Collinsville, IL 62234-7425
Phone (618) 344-1004
Fax (618) 344-1005
Email jhriley@teklabinc.com

Collinsville Air

Address 5445 Horseshoe Lake Road
Collinsville, IL 62234-7425
Phone (618) 344-1004
Fax (618) 344-1005
Email EHurley@teklabinc.com

Springfield

Address 3920 Pintail Dr
Springfield, IL 62711-9415
Phone (217) 698-1004
Fax (217) 698-1005
Email KKlostermann@teklabinc.com

Chicago

Address 1319 Butterfield Rd.
Downers Grove, IL 60515
Phone (630) 324-6855
Fax
Email arenner@teklabinc.com

Kansas City

Address 8421 Nieman Road
Lenexa, KS 66214
Phone (913) 541-1998
Fax (913) 541-1998
Email jhriley@teklabinc.com



Accreditations

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020844

Client Project: HEN-23Q1

Report Date: 27-Mar-23

State	Dept	Cert #	NELAP	Exp Date	Lab
Illinois	IEPA	100226	NELAP	1/31/2024	Collinsville
Kansas	KDHE	E-10374	NELAP	4/30/2023	Collinsville
Louisiana	LDEQ	05002	NELAP	6/30/2023	Collinsville
Louisiana	LDEQ	05003	NELAP	6/30/2023	Collinsville
Oklahoma	ODEQ	9978	NELAP	8/31/2023	Collinsville
Arkansas	ADEQ	88-0966		3/14/2024	Collinsville
Illinois	IDPH	17584		5/31/2023	Collinsville
Iowa	IDNR	430		6/1/2024	Collinsville
Kentucky	UST	0073		1/31/2024	Collinsville
Missouri	MDNR	00930		5/31/2023	Collinsville
Missouri	MDNR	930		1/31/2025	Collinsville



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020844
Report Date: 27-Mar-23

Lab ID: 23020844-001

Client Sample ID: 03R

Matrix: GROUNDWATER

Collection Date: 03/01/2023 13:26

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-002
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 07
Collection Date: 03/01/2023 16:16

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-003
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 08
Collection Date: 03/01/2023 15:01

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-004
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 08D
Collection Date: 03/01/2023 14:42

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-005
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 12
Collection Date: 03/01/2023 10:46

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-006
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 13
Collection Date: 03/01/2023 10:28

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020844
Report Date: 27-Mar-23

Lab ID: 23020844-007

Client Sample ID: 16

Matrix: GROUNDWATER

Collection Date: 02/28/2023 15:57

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020844
Report Date: 27-Mar-23

Lab ID: 23020844-008

Client Sample ID: 17

Matrix: GROUNDWATER

Collection Date: 02/28/2023 16:14

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-009
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 18S
Collection Date: 03/01/2023 12:53

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-010
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 18D
Collection Date: 03/01/2023 13:08

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-011
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 21R
Collection Date: 02/28/2023 9:18

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020844
Report Date: 27-Mar-23

Lab ID: 23020844-012

Client Sample ID: 22

Matrix: GROUNDWATER

Collection Date: 02/28/2023 11:28

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-013
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 22D
Collection Date: 02/28/2023 11:44

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-014
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 23
Collection Date: 02/28/2023 10:35

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-015
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 27
Collection Date: 02/28/2023 13:47

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-016
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 32
Collection Date: 02/28/2023 13:06

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-017
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 34
Collection Date: 02/28/2023 14:21

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-018
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 35
Collection Date: 02/28/2023 12:33

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/14/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-019
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 45S
Collection Date: 03/01/2023 13:50

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-020
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 46
Collection Date: 02/28/2023 16:34

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-021
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 47
Collection Date: 03/01/2023 9:37

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020844
Report Date: 27-Mar-23

Lab ID: 23020844-022

Client Sample ID: 49

Matrix: GROUNDWATER

Collection Date: 02/28/2023 11:01

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-023
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 50
Collection Date: 02/28/2023 12:10

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-024
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 51
Collection Date: 02/28/2023 10:03

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-025
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 52
Collection Date: 02/28/2023 16:57

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-026
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 54
Collection Date: 03/01/2023 9:59

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-027
Matrix: GROUNDWATER

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: 08 Duplicate
Collection Date: 03/01/2023 15:01

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520



Client: Ramboll
Client Project: HEN-23Q1
Lab ID: 23020844-028
Matrix: AQUEOUS

Work Order: 23020844
Report Date: 27-Mar-23
Client Sample ID: Field Blank
Collection Date: 03/01/2023 17:01

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
EPA 903.0/904.0, RADIUM 226/228								
Radium-226	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520
Radium-228	*	0		See Attached	pci/L	1	03/16/2023 0:00	R326520



Sample Summary

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q1

Work Order: 23020844
Report Date: 27-Mar-23

Lab Sample ID	Client Sample ID	Matrix	Fractions	Collection Date
23020844-001	03R	Groundwater	1	03/01/2023 13:26
23020844-002	07	Groundwater	1	03/01/2023 16:16
23020844-003	08	Groundwater	1	03/01/2023 15:01
23020844-004	08D	Groundwater	1	03/01/2023 14:42
23020844-005	12	Groundwater	1	03/01/2023 10:46
23020844-006	13	Groundwater	1	03/01/2023 10:28
23020844-007	16	Groundwater	1	02/28/2023 15:57
23020844-008	17	Groundwater	1	02/28/2023 16:14
23020844-009	18S	Groundwater	1	03/01/2023 12:53
23020844-010	18D	Groundwater	1	03/01/2023 13:08
23020844-011	21R	Groundwater	1	02/28/2023 9:18
23020844-012	22	Groundwater	1	02/28/2023 11:28
23020844-013	22D	Groundwater	1	02/28/2023 11:44
23020844-014	23	Groundwater	1	02/28/2023 10:35
23020844-015	27	Groundwater	1	02/28/2023 13:47
23020844-016	32	Groundwater	1	02/28/2023 13:06
23020844-017	34	Groundwater	1	02/28/2023 14:21
23020844-018	35	Groundwater	1	02/28/2023 12:33
23020844-019	45S	Groundwater	1	03/01/2023 13:50
23020844-020	46	Groundwater	1	02/28/2023 16:34
23020844-021	47	Groundwater	1	03/01/2023 9:37
23020844-022	49	Groundwater	1	02/28/2023 11:01
23020844-023	50	Groundwater	1	02/28/2023 12:10
23020844-024	51	Groundwater	1	02/28/2023 10:03
23020844-025	52	Groundwater	1	02/28/2023 16:57
23020844-026	54	Groundwater	1	03/01/2023 9:59
23020844-027	08 Duplicate	Groundwater	1	03/01/2023 15:01
23020844-028	Field Blank	Aqueous	1	03/01/2023 17:01



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020844

Client Project: HEN-23Q1

Report Date: 27-Mar-23

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
Test Name					
23020844-001A	03R	03/01/2023 13:26	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-002A	07	03/01/2023 16:16	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-003A	08	03/01/2023 15:01	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-004A	08D	03/01/2023 14:42	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-005A	12	03/01/2023 10:46	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-006A	13	03/01/2023 10:28	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-007A	16	02/28/2023 15:57	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-008A	17	02/28/2023 16:14	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-009A	18S	03/01/2023 12:53	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-010A	18D	03/01/2023 13:08	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-011A	21R	02/28/2023 9:18	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-012A	22	02/28/2023 11:28	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-013A	22D	02/28/2023 11:44	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-014A	23	02/28/2023 10:35	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-015A	27	02/28/2023 13:47	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-016A	32	02/28/2023 13:06	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-017A	34	02/28/2023 14:21	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-018A	35	02/28/2023 12:33	03/02/2023 8:00		



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020844

Client Project: HEN-23Q1

Report Date: 27-Mar-23

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
	Test Name				
	EPA 903.0/904.0, Radium 226/228				03/14/2023 0:00
23020844-019A	45S	03/01/2023 13:50	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/16/2023 0:00
23020844-020A	46	02/28/2023 16:34	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/16/2023 0:00
23020844-021A	47	03/01/2023 9:37	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/16/2023 0:00
23020844-022A	49	02/28/2023 11:01	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/16/2023 0:00
23020844-023A	50	02/28/2023 12:10	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/16/2023 0:00
23020844-024A	51	02/28/2023 10:03	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/16/2023 0:00
23020844-025A	52	02/28/2023 16:57	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/16/2023 0:00
23020844-026A	54	03/01/2023 9:59	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/16/2023 0:00
23020844-027A	08 Duplicate	03/01/2023 15:01	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/16/2023 0:00
23020844-028A	Field Blank	03/01/2023 17:01	03/02/2023 8:00		
	EPA 903.0/904.0, Radium 226/228				03/16/2023 0:00



Receiving Check List

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23020844

Client Project: HEN-23Q1

Report Date: 27-Mar-23

Carrier: Joe Riley

Received By: ANC

Completed by:

On:

02-Mar-23

Lindsey Maddox

Reviewed by:

On:

02-Mar-23

Elizabeth A. Hurley

Elizabeth A. Hurley

Pages to follow: Chain of custody

2

Extra pages included

48

Shipping container/cooler in good condition?

Yes ☒

No ☐

Not Present ☐

Temp °C 3.2

Type of thermal preservation?

None ☐

Ice ☒

Blue Ice ☐

Dry Ice ☐

Chain of custody present?

Yes ☒

No ☐

Chain of custody signed when relinquished and received?

Yes ☒

No ☐

Chain of custody agrees with sample labels?

Yes ☒

No ☐

Samples in proper container/bottle?

Yes ☒

No ☐

Sample containers intact?

Yes ☒

No ☐

Sufficient sample volume for indicated test?

Yes ☒

No ☐

All samples received within holding time?

Yes ☒

No ☐

Reported field parameters measured:

Field ☐

Lab ☐

NA ☒

Container/Temp Blank temperature in compliance?

Yes ☒

No ☐

When thermal preservation is required, samples are compliant with a temperature between 0.1°C - 6.0°C, or when samples are received on ice the same day as collected.

Water – at least one vial per sample has zero headspace?

Yes ☐

No ☐

No VOA vials ☒

Water - TOX containers have zero headspace?

Yes ☐

No ☐

No TOX containers ☒

Water - pH acceptable upon receipt?

Yes ☐

No ☒

NA ☐

NPDES/CWA TCN interferences checked/treated in the field?

Yes ☐

No ☐

NA ☒

Any No responses must be detailed below or on the COC.

Additional Nitric Acid (87873) was needed in 08, 08D, 12, 27, 34, 35, 47, 49, 50, and 51 upon arrival at the laboratory. - Imaddox - 3/2/2023 10:35:49 AM

pH strip #87147. - Imaddox - 3/2/2023 10:36:49 AM

HEN-257-804

Page: 1 of 2

Invoice Information:

[illegible]

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS
HEN-23Q1 Rev 0	J. L. Teldas	03/20/23	800	Allison Coln	3/2/23	800	32 Y N Y
Ra226/228, only.							

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER: Joe Rylex					
SIGNATURE of SAMPLER: [Signature]	DATE Signed (MM/DD/YY): 03/02/23				

* Additional HNO_3 needed 3.2°
 (8787) TE #5 WY
 8787 3/2

TE
EAH
3/23/23

Page: 2 of 2

REGULATORY AGENCY

Invoice Information:

Company: Vistra Corp		Report To: Brian Voelker		Attention: Jason Stuckey				
Address: 13498 E. 900th St		Copy To: Jason Stuckey		Company Name: Vistra Corp		REGULATORY AGENCY		
				Address: see Section A		NPDES GROUND WATER DRINKING WATER UST RCRA OTHER		
Email To: Brian.Voelker@VistraCorp.com		Purchase Order No.:		Quote Reference:				
Phone: (217) 753-8911	Fax:	Project Name:		Project Manager:		Site Location STATE:	IL	
Requested Due Date/TAT: 10 day		Project Number: 2285		Profile #:				

[illegible]

SAMPLER NAME AND SIGNATURE PRINT Name of SAMPLER: <u>Joe Rile</u> SIGNATURE of SAMPLER: <u>[Signature]</u>		DATE Signed (MM/DD/YY): <u>03/02/03</u>	Temp in °C Received on ice (Y/N) Custody Sealed Cooler (Y/N) Samples Intact (Y/N)



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

ANALYTICAL REPORT

March 22, 2023

TEKLAB, Inc.


Sample Delivery Group: L1591962
Samples Received: 03/06/2023
Project Number: 23020844
Description:

Report To: Elizabeth Hurley
5445 Horseshoe Lake Road
Collinsville, IL 62234

Entire Report Reviewed By:

Mark W. Beasley
Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.



Pace Analytical National

12065 Lebanon Rd Mount Juliet, TN 37122 615-758-5858 800-767-5859 www.pacenational.com

TABLE OF CONTENTS

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Cp: Cover Page	1
Tc: Table of Contents	2
Ss: Sample Summary	3
Cn: Case Narrative	8
Sr: Sample Results	9
23020844-001 L1591962-01	9
23020844-002 L1591962-02	10
23020844-003 L1591962-03	11
23020844-004 L1591962-04	12
23020844-005 L1591962-05	13
23020844-006 L1591962-06	14
23020844-007 L1591962-07	15
23020844-008 L1591962-08	16
23020844-009 L1591962-09	17
23020844-010 L1591962-10	18
23020844-011 L1591962-11	19
23020844-012 L1591962-12	20
23020844-013 L1591962-13	21
23020844-014 L1591962-14	22
23020844-015 L1591962-15	23
23020844-016 L1591962-16	24
23020844-017 L1591962-17	25
23020844-018 L1591962-18	26
23020844-019 L1591962-19	27
23020844-020 L1591962-20	28
23020844-021 L1591962-21	29
23020844-022 L1591962-22	30
23020844-023 L1591962-23	31
23020844-024 L1591962-24	32
23020844-025 L1591962-25	33
23020844-026 L1591962-26	34
23020844-027 L1591962-27	35
23020844-028 L1591962-28	36
Qc: Quality Control Summary	37
Radiochemistry by Method 904/9320	37
Radiochemistry by Method SM7500Ra B M	40
Gl: Glossary of Terms	42
Al: Accreditations & Locations	43
Sc: Sample Chain of Custody	44

¹ Cp
² Tc
³ Ss
⁴ Cn
⁵ Sr
⁶ Qc
⁷ Gl
⁸ Al
⁹ Sc

SAMPLE SUMMARY

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

CHENEPIN POWER PLANT OLD WEST ASH POND

APPENDIX A.

23020844-001 L1591962-01 Non-Potable Water

03/01/23 13:26

03/06/23 08:45

HEN-257-804

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2023907	1	03/15/23 19:33	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:19	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

03/01/23 16:16

03/06/23 08:45

23020844-002 L1591962-02 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2023907	1	03/15/23 19:33	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:19	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

03/01/23 15:01

03/06/23 08:45

23020844-003 L1591962-03 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2023907	1	03/15/23 19:33	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:19	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

03/01/23 14:42

03/06/23 08:45

23020844-004 L1591962-04 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2023907	1	03/15/23 19:33	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:19	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

03/01/23 10:46

03/06/23 08:45

23020844-005 L1591962-05 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2023907	1	03/15/23 19:33	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:19	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

03/01/23 10:28

03/06/23 08:45

23020844-006 L1591962-06 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2023907	1	03/15/23 19:33	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:19	RGT	Mt. Juliet, TN



SAMPLE SUMMARY

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

APPENDIX A.

CHENEPIN POWER PLANT OLD WEST ASH POND

23020844-007 L1591962-07 Non-Potable Water

02/28/23 15:57

03/06/23 08:45

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2023907	1	03/15/23 19:33	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:19	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

02/28/23 16:14

03/06/23 08:45

23020844-008 L1591962-08 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2023907	1	03/15/23 19:33	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:19	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

03/01/23 12:53

03/06/23 08:45

23020844-009 L1591962-09 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2023907	1	03/15/23 19:33	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 17:45	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:19	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

03/01/23 13:08

03/06/23 08:45

23020844-010 L1591962-10 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:20	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

02/28/23 09:18

03/06/23 08:45

23020844-011 L1591962-11 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:20	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

02/28/23 11:28

03/06/23 08:45

23020844-012 L1591962-12 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:20	RGT	Mt. Juliet, TN



SAMPLE SUMMARY

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

CHENEPIN POWER PLANT/OLD WEST ASH POND

APPENDIX A.

02/28/23 11:44 03/06/23 08:45 HEN-257-804

23020844-013 L1591962-13 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:20	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
02/28/23 10:35 03/06/23 08:45

23020844-014 L1591962-14 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:20	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
02/28/23 13:47 03/06/23 08:45

23020844-015 L1591962-15 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:20	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
02/28/23 13:06 03/06/23 08:45

23020844-016 L1591962-16 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:20	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
02/28/23 14:21 03/06/23 08:45


23020844-017 L1591962-17 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:20	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
02/28/23 12:33 03/06/23 08:45

23020844-018 L1591962-18 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019012	1	03/08/23 17:16	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019012	1	03/08/23 17:16	03/14/23 11:20	RGT	Mt. Juliet, TN



SAMPLE SUMMARY

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

APPENDIX A.

CHENEPIN POWER PLANT OLD WEST ASH POND

23020844-019 L1591962-19 Non-Potable Water

03/01/23 13:50

03/06/23 08:45

HEN-257-804

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019014	1	03/13/23 16:35	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019014	1	03/13/23 16:35	03/16/23 22:33	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

23020844-020 L1591962-20 Non-Potable Water

02/28/23 16:34

03/06/23 08:45

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019014	1	03/13/23 16:35	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019014	1	03/13/23 16:35	03/16/23 22:32	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

23020844-021 L1591962-21 Non-Potable Water

03/01/23 09:37

03/06/23 08:45

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019014	1	03/13/23 16:35	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019014	1	03/13/23 16:35	03/16/23 22:32	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

23020844-022 L1591962-22 Non-Potable Water

02/28/23 11:01

03/06/23 08:45

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019014	1	03/13/23 16:35	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019014	1	03/13/23 16:35	03/16/23 22:32	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

23020844-023 L1591962-23 Non-Potable Water

02/28/23 12:10

03/06/23 08:45

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2024709	1	03/16/23 19:18	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019014	1	03/13/23 16:35	03/20/23 10:52	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019014	1	03/13/23 16:35	03/16/23 22:32	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

23020844-024 L1591962-24 Non-Potable Water

02/28/23 10:03

03/06/23 08:45

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2025460	1	03/17/23 17:43	03/22/23 10:40	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019014	1	03/13/23 16:35	03/22/23 10:40	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019014	1	03/13/23 16:35	03/16/23 22:32	RGT	Mt. Juliet, TN



SAMPLE SUMMARY

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

CHENNEPIN POWER PLANT OLD WEST ASH POND

APPENDIX A.

02/28/23 16:57

03/06/23 08:45

HEN-257-804

23020844-025 L1591962-25 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2025460	1	03/17/23 17:43	03/22/23 10:40	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019014	1	03/13/23 16:35	03/22/23 10:40	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019014	1	03/13/23 16:35	03/16/23 22:32	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

03/01/23 09:59

03/06/23 08:45

23020844-026 L1591962-26 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2025460	1	03/17/23 17:43	03/22/23 10:40	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019014	1	03/13/23 16:35	03/22/23 10:40	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019014	1	03/13/23 16:35	03/16/23 22:32	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

03/01/23 15:01

03/06/23 08:45

23020844-027 L1591962-27 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2025460	1	03/17/23 17:43	03/22/23 10:40	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019014	1	03/13/23 16:35	03/22/23 10:40	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019014	1	03/13/23 16:35	03/16/23 22:32	RGT	Mt. Juliet, TN

Collected by

Collected date/time


Received date/time

03/01/23 17:01

03/06/23 08:45

23020844-028 L1591962-28 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2025460	1	03/17/23 17:43	03/22/23 10:40	SWM	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2019014	1	03/13/23 16:35	03/22/23 10:40	SWM	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2019014	1	03/13/23 16:35	03/16/23 22:32	RGT	Mt. Juliet, TN



CASE NARRATIVE

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All radiochemical sample results for solids are reported on a dry weight basis with the exception of tritium, carbon-14 and radon, unless wet weight was requested by the client. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.



Mark W. Beasley
Project Manager



Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	1.64		0.391	0.655	03/20/2023 17:45	WG2023907
(T) Barium	78.7			30.0-143	03/20/2023 17:45	WG2023907
(T) Yttrium	85.7			30.0-136	03/20/2023 17:45	WG2023907

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.93		0.474	0.735	03/20/2023 17:45	WG2019012

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.289	J	0.268	0.334	03/14/2023 11:19	WG2019012
(T) Barium-133	91.4			30.0-143	03/14/2023 11:19	WG2019012

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	1.62		0.307	0.502	03/20/2023 17:45	WG2023907
(T) Barium	90.5			30.0-143	03/20/2023 17:45	WG2023907
(T) Yttrium	90.1			30.0-136	03/20/2023 17:45	WG2023907

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	2.00		0.448	0.643	03/20/2023 17:45	WG2019012

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.384	J	0.326	0.402	03/14/2023 11:19	WG2019012
(T) Barium-133	80.6			30.0-143	03/14/2023 11:19	WG2019012

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.688		0.282	0.487	03/20/2023 17:45	WG2023907
(T) Barium	83.3			30.0-143	03/20/2023 17:45	WG2023907
(T) Yttrium	95.7			30.0-136	03/20/2023 17:45	WG2023907

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.871		0.349	0.558	03/20/2023 17:45	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.183	J	0.206	0.272	03/14/2023 11:19	WG2019012
(T) Barium-133	83.5			30.0-143	03/14/2023 11:19	WG2019012

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	1.21		0.275	0.456	03/20/2023 17:45	WG2023907
(T) Barium	78.0			30.0-143	03/20/2023 17:45	WG2023907
(T) Yttrium	103			30.0-136	03/20/2023 17:45	WG2023907

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.37		0.333	0.519	03/20/2023 17:45	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.167	J	0.188	0.248	03/14/2023 11:19	WG2019012
(T) Barium-133	78.8			30.0-143	03/14/2023 11:19	WG2019012

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.143	U	0.315	0.581	03/20/2023 17:45	WG2023907
(T) Barium	80.4			30.0-143	03/20/2023 17:45	WG2023907
(T) Yttrium	94.6			30.0-136	03/20/2023 17:45	WG2023907

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.370	J	0.419	0.650	03/20/2023 17:45	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.370		0.276	0.292	03/14/2023 11:19	WG2019012
(T) Barium-133	82.5			30.0-143	03/14/2023 11:19	WG2019012

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-1.02	U	0.298	0.576	03/20/2023 17:45	WG2023907
(T) Barium	82.1			30.0-143	03/20/2023 17:45	WG2023907
(T) Yttrium	91.4			30.0-136	03/20/2023 17:45	WG2023907

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.129	U	0.333	0.607	03/20/2023 17:45	WG2019012

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.129	J	0.148	0.190	03/14/2023 11:19	WG2019012
(T) Barium-133	85.3			30.0-143	03/14/2023 11:19	WG2019012

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.570	U	0.335	0.587	03/20/2023 17:45	WG2023907
(T) Barium	78.4			30.0-143	03/20/2023 17:45	WG2023907
(T) Yttrium	101			30.0-136	03/20/2023 17:45	WG2023907

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.956		0.425	0.640	03/20/2023 17:45	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.385		0.262	0.254	03/14/2023 11:19	WG2019012
(T) Barium-133	89.5			30.0-143	03/14/2023 11:19	WG2019012

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.0392	U	0.354	0.644	03/20/2023 17:45	WG2023907
(T) Barium	76.6			30.0-143	03/20/2023 17:45	WG2023907
(T) Yttrium	82.7			30.0-136	03/20/2023 17:45	WG2023907

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.0457	U	0.396	0.722	03/20/2023 17:45	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.00652	U	0.178	0.327	03/14/2023 11:19	WG2019012
(T) Barium-133	88.1			30.0-143	03/14/2023 11:19	WG2019012

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.183	U	0.306	0.561	03/20/2023 17:45	WG2023907
(T) Barium	79.3			30.0-143	03/20/2023 17:45	WG2023907
(T) Yttrium	99.5			30.0-136	03/20/2023 17:45	WG2023907

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.0783	U	0.349	0.627	03/20/2023 17:45	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.0783	U	0.168	0.279	03/14/2023 11:19	WG2019012
(T) Barium-133	89.1			30.0-143	03/14/2023 11:19	WG2019012

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	1.04		0.366	0.658	03/20/2023 10:52	WG2024709
(T) Barium	84.1			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	91.1			30.0-136	03/20/2023 10:52	WG2024709

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.28		0.438	0.729	03/20/2023 10:52	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.240	J	0.241	0.313	03/14/2023 11:20	WG2019012
(T) Barium-133	89.9			30.0-143	03/14/2023 11:20	WG2019012

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.950		0.245	0.430	03/20/2023 10:52	WG2024709
(T) Barium	80.3			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	104			30.0-136	03/20/2023 10:52	WG2024709

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.75		0.472	0.552	03/20/2023 10:52	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.803		0.404	0.346	03/14/2023 11:20	WG2019012
(T) Barium-133	84.6			30.0-143	03/14/2023 11:20	WG2019012

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.247	J	0.277	0.515	03/20/2023 10:52	WG2024709
(T) Barium	90.0			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	107			30.0-136	03/20/2023 10:52	WG2024709

¹Cp

²Tc

³Ss

⁴Cn

⁵Sr

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.324	J	0.326	0.595	03/20/2023 10:52	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.0769	U	0.172	0.297	03/14/2023 11:20	WG2019012
(T) Barium-133	86.5			30.0-143	03/14/2023 11:20	WG2019012

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.263	J	0.245	0.456	03/20/2023 10:52	WG2024709
(T) Barium	94.8			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	93.3			30.0-136	03/20/2023 10:52	WG2024709

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.25		0.495	0.555	03/20/2023 10:52	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.984		0.430	0.316	03/14/2023 11:20	WG2019012
(T) Barium-133	86.0			30.0-143	03/14/2023 11:20	WG2019012

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.635	J	0.357	0.655	03/20/2023 10:52	WG2024709
(T) Barium	77.7			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	78.8			30.0-136	03/20/2023 10:52	WG2024709

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.727		0.392	0.705	03/20/2023 10:52	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.0929	U	0.163	0.260	03/14/2023 11:20	WG2019012
(T) Barium-133	93.8			30.0-143	03/14/2023 11:20	WG2019012

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.473	J	0.264	0.484	03/20/2023 10:52	WG2024709
(T) Barium	90.4			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	111			30.0-136	03/20/2023 10:52	WG2024709

¹Cp

²Tc

³Ss

⁴Cn

⁵Sr

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.671		0.328	0.539	03/20/2023 10:52	WG2019012

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.198	J	0.194	0.237	03/14/2023 11:20	WG2019012
(T) Barium-133	94.7			30.0-143	03/14/2023 11:20	WG2019012

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.781		0.248	0.443	03/20/2023 10:52	WG2024709
(T) Barium	91.6			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	103			30.0-136	03/20/2023 10:52	WG2024709

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.886		0.314	0.534	03/20/2023 10:52	WG2019012

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.106	U	0.192	0.298	03/14/2023 11:20	WG2019012
(T) Barium-133	95.3			30.0-143	03/14/2023 11:20	WG2019012

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	1.00		0.272	0.480	03/20/2023 10:52	WG2024709
(T) Barium	87.1			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	93.0			30.0-136	03/20/2023 10:52	WG2024709



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.55		0.383	0.519	03/20/2023 10:52	WG2019012



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.544		0.269	0.197	03/14/2023 11:20	WG2019012
(T) Barium-133	89.9			30.0-143	03/14/2023 11:20	WG2019012



Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.551		0.254	0.464	03/20/2023 10:52	WG2024709
(T) Barium	78.2			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	98.0			30.0-136	03/20/2023 10:52	WG2024709

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.99		0.536	0.560	03/20/2023 10:52	WG2019012

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	1.44		0.472	0.314	03/14/2023 11:20	WG2019012
(T) Barium-133	88.6			30.0-143	03/14/2023 11:20	WG2019012

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.598		0.318	0.584	03/20/2023 10:52	WG2024709
(T) Barium	75.6			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	103			30.0-136	03/20/2023 10:52	WG2024709

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.748		0.373	0.647	03/20/2023 10:52	WG2019014

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.149	J	0.194	0.278	03/16/2023 22:33	WG2019014
(T) Barium-133	89.3			30.0-143	03/16/2023 22:33	WG2019014

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.612	U	0.252	0.501	03/20/2023 10:52	WG2024709
(T) Barium	85.9			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	104			30.0-136	03/20/2023 10:52	WG2024709

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.187	U	0.351	0.611	03/20/2023 10:52	WG2019014

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.187	J	0.244	0.349	03/16/2023 22:32	WG2019014
(T) Barium-133	80.6			30.0-143	03/16/2023 22:32	WG2019014

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.556		0.291	0.532	03/20/2023 10:52	WG2024709
(T) Barium	94.8			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	91.3			30.0-136	03/20/2023 10:52	WG2024709

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.671		0.381	0.670	03/20/2023 10:52	WG2019014

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.115	U	0.246	0.408	03/16/2023 22:32	WG2019014
(T) Barium-133	71.7			30.0-143	03/16/2023 22:32	WG2019014

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.208	U	0.216	0.421	03/20/2023 10:52	WG2024709
(T) Barium	95.7			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	100			30.0-136	03/20/2023 10:52	WG2024709

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.231	J	0.310	0.503	03/20/2023 10:52	WG2019014

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.231	J	0.223	0.276	03/16/2023 22:32	WG2019014
(T) Barium-133	93.0			30.0-143	03/16/2023 22:32	WG2019014

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.201	U	0.258	0.483	03/20/2023 10:52	WG2024709
(T) Barium	91.5			30.0-143	03/20/2023 10:52	WG2024709
(T) Yttrium	101			30.0-136	03/20/2023 10:52	WG2024709

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.608		0.390	0.573	03/20/2023 10:52	WG2019014

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.408		0.293	0.309	03/16/2023 22:32	WG2019014
(T) Barium-133	88.2			30.0-143	03/16/2023 22:32	WG2019014

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.387	J	0.306	0.564	03/22/2023 10:40	WG2025460
(T) Barium	81.0			30.0-143	03/22/2023 10:40	WG2025460
(T) Yttrium	110			30.0-136	03/22/2023 10:40	WG2025460

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.35		0.493	0.623	03/22/2023 10:40	WG2019014

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.966		0.386	0.264	03/16/2023 22:32	WG2019014
(T) Barium-133	92.4			30.0-143	03/16/2023 22:32	WG2019014

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-1.69	U	0.254	0.529	03/22/2023 10:40	WG2025460
(T) Barium	93.9			30.0-143	03/22/2023 10:40	WG2025460
(T) Yttrium	114			30.0-136	03/22/2023 10:40	WG2025460

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.259	J	0.359	0.613	03/22/2023 10:40	WG2019014

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.259	J	0.254	0.310	03/16/2023 22:32	WG2019014
(T) Barium-133	72.3			30.0-143	03/16/2023 22:32	WG2019014

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.626	U	0.278	0.539	03/22/2023 10:40	WG2025460
(T) Barium	94.3			30.0-143	03/22/2023 10:40	WG2025460
(T) Yttrium	108			30.0-136	03/22/2023 10:40	WG2025460

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.00730	U	0.327	0.631	03/22/2023 10:40	WG2019014

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.00730	U	0.172	0.329	03/16/2023 22:32	WG2019014
(T) Barium-133	86.1			30.0-143	03/16/2023 22:32	WG2019014

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.104	U	0.265	0.506	03/22/2023 10:40	WG2025460
(T) Barium	78.7			30.0-143	03/22/2023 10:40	WG2025460
(T) Yttrium	117			30.0-136	03/22/2023 10:40	WG2025460

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.277	J	0.336	0.548	03/22/2023 10:40	WG2019014

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.277		0.207	0.210	03/16/2023 22:32	WG2019014
(T) Barium-133	84.2			30.0-143	03/16/2023 22:32	WG2019014

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.000	<u>U</u>	0.272	0.512	03/22/2023 10:40	WG2025460
(T) Barium	95.0			30.0-143	03/22/2023 10:40	WG2025460
(T) Yttrium	94.6			30.0-136	03/22/2023 10:40	WG2025460

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.0150	<u>U</u>	0.323	0.610	03/22/2023 10:40	WG2019014

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.0150	<u>U</u>	0.174	0.331	03/16/2023 22:32	WG2019014
(T) Barium-133	84.2			30.0-143	03/16/2023 22:32	WG2019014

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Method Blank (MB)

(MB) R3903513-1 03/20/23 17:45

Analyte	MB Result pCi/l	MB Qualifier	MB Uncertainty + / -	MB MDA pCi/l
Radium-228	-0.137	<u>U</u>	0.165	0.302
(T) Barium	92.2		92.2	
(T) Yttrium	100		100	

L1587256-01 Original Sample (OS) • Duplicate (DUP)

(OS) L1587256-01 03/20/23 17:45 • (DUP) R3903513-5 03/20/23 17:45

Analyte	Original Result pCi/l	Original Uncertainty + / -	Original MDA pCi/l	DUP Result pCi/l	DUP Uncertainty + / -	DUP MDA pCi/l	Dilution	DUP RPD %	DUP RER	DUP Qualifier	DUP RPD Limits %	DUP RER Limit
Radium-228	1.61	0.441	0.748	1.75	0.370	0.748	1	7.98	0.233		20	3
(T) Barium	94.4			89.5	89.5							
(T) Yttrium	94.9			100	100							

Laboratory Control Sample (LCS)

(LCS) R3903513-2 03/20/23 17:45

Analyte	Spike Amount pCi/l	LCS Result pCi/l	LCS Rec. %	Rec. Limits %	LCS Qualifier
Radium-228	5.00	5.92	118	80.0-120	
(T) Barium			94.6		
(T) Yttrium			92.9		

L1585977-06 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1585977-06 03/20/23 17:45 • (MS) R3903513-3 03/20/23 17:45 • (MSD) R3903513-4 03/20/23 17:45

Analyte	Spike Amount pCi/l	Original Result pCi/l	MS Result pCi/l	MSD Result pCi/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	MS Qualifier	MSD Qualifier	RPD %	MS RER	RPD Limits %
Radium-228	10.0	1.90	11.5	11.5	96.2	96.3	1	70.0-130			0.0868		20
(T) Barium		80.7			90.2	83.9							
(T) Yttrium		77.7			95.6	94.8							

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Method Blank (MB)

(MB) R3903198-1 03/20/23 10:52

Analyte	MB Result pCi/l	MB Qualifier	MB Uncertainty + / -	MB MDA pCi/l
Radium-228	-0.570	U	0.143	0.289
(T) Barium	96.3		96.3	
(T) Yttrium	105		105	

L1591962-10 Original Sample (OS) • Duplicate (DUP)

(OS) L1591962-10 03/20/23 10:52 • (DUP) R3903198-5 03/20/23 10:52

Analyte	Original Result pCi/l	Original Uncertainty + / -	Original MDA pCi/l	DUP Result pCi/l	DUP Uncertainty + / -	DUP MDA pCi/l	Dilution	DUP RPD %	DUP RER	DUP Qualifier	DUP RPD Limits %	DUP RER Limit
Radium-228	1.04	0.366	0.658	1.59	0.338	0.658	1	42.4	1.12		20	3
(T) Barium	84.1			98.6	98.6							
(T) Yttrium	91.1			108	108							

Laboratory Control Sample (LCS)

(LCS) R3903198-2 03/20/23 10:52

Analyte	Spike Amount pCi/l	LCS Result pCi/l	LCS Rec. %	Rec. Limits %	LCS Qualifier
Radium-228	5.00	5.67	113	80.0-120	
(T) Barium			94.5		
(T) Yttrium			94.9		

L1587304-03 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1587304-03 03/20/23 10:52 • (MS) R3903198-3 03/20/23 10:52 • (MSD) R3903198-4 03/20/23 10:52

Analyte	Spike Amount pCi/l	Original Result pCi/l	MS Result pCi/l	MSD Result pCi/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	MS Qualifier	MSD Qualifier	RPD %	MS RER	RPD Limits %
Radium-228	10.0	1.19	13.6	12.7	124	115	1	70.0-130			6.71		20
(T) Barium		91.4			97.2	98.6							
(T) Yttrium		96.2			93.8	114							

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Method Blank (MB)

(MB) R3904214-1 03/22/23 10:40

Analyte	MB Result pCi/l	MB Qualifier	MB Uncertainty + / -	MB MDA pCi/l
Radium-228	0.393		0.146	0.261
(T) Barium	84.2		84.2	
(T) Yttrium	102		102	

L1591962-24 Original Sample (OS) • Duplicate (DUP)

(OS) L1591962-24 03/22/23 10:40 • (DUP) R3904214-5 03/22/23 10:40

Analyte	Original Result pCi/l	Original Uncertainty + / -	Original MDA pCi/l	DUP Result pCi/l	DUP Uncertainty + / -	DUP MDA pCi/l	Dilution	DUP RPD %	DUP RER	DUP Qualifier	DUP RPD Limits %	DUP RER Limit
Radium-228	0.387	0.306	0.564	0.850	0.431	0.564	1	74.9	0.876		20	3
(T) Barium	81.0			77.8	77.8							
(T) Yttrium	110			98.3	98.3							

Laboratory Control Sample (LCS)

(LCS) R3904214-2 03/22/23 10:40

Analyte	Spike Amount pCi/l	LCS Result pCi/l	LCS Rec. %	Rec. Limits %	LCS Qualifier
Radium-228	5.00	5.66	113	80.0-120	
(T) Barium			82.6		
(T) Yttrium			114		

L1587251-03 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1587251-03 03/22/23 10:40 • (MS) R3904214-3 03/22/23 10:40 • (MSD) R3904214-4 03/22/23 10:40

Analyte	Spike Amount pCi/l	Original Result pCi/l	MS Result pCi/l	MSD Result pCi/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	MS Qualifier	MSD Qualifier	RPD %	MS RER	RPD Limits %
Radium-228	10.0	1.41	13.4	11.0	119	95.4	1	70.0-130			19.8		20
(T) Barium		78.8			84.4	87.3							
(T) Yttrium		98.3			107	111							



^1Cp ${}^2\text{Tc}$ 3S_s
$$^4\text{Cn}$$
 ${}^5\text{Sr}$ ⁶Qc⁷Gd ${}^8\text{Al}$ ⁹Sc

Method Blank (MB)

(MB) R3902467-1 03/15/23 10:22

Analyte	MB Result pCi/l	MB Qualifier	MB Uncertainty + / -	MB MDA pCi/l
Radium-226	-0.0100	<u>U</u>	0.0639	0.125
(T) Barium-133	67.0		67.0	

L1590063-07 Original Sample (OS) • Duplicate (DUP)

(OS) L1590063-07 03/16/23 22:32 • (DUP) R3902467-5 03/15/23 10:22

Analyte	Original Result pCi/l	Original Uncertainty + / -	Original MDA pCi/l	DUP Result pCi/l	DUP Uncertainty + / -	DUP MDA pCi/l	Dilution	DUP RPD %	DUP RER	DUP Qualifier	DUP RPD Limits %	DUP RER Limit
Radium-226	0.226	0.234	0.298	-0.0426	0.277	0.298	1	200	0.740	<u>U</u>	20	3
(T) Barium-133	76.4			69.4	69.4							

Laboratory Control Sample (LCS)

(LCS) R3902467-2 03/15/23 10:22

Analyte	Spike Amount pCi/l	LCS Result pCi/l	LCS Rec. %	Rec. Limits %	LCS Qualifier
Radium-226	5.01	4.94	98.6	80.0-120	
(T) Barium-133			77.4		

L1591962-28 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1591962-28 03/16/23 22:32 • (MS) R3902467-3 03/15/23 10:22 • (MSD) R3902467-4 03/15/23 10:22

Analyte	Spike Amount pCi/l	Original Result pCi/l	MS Result pCi/l	MSD Result pCi/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	MS Qualifier	MSD Qualifier	RPD %	MS RER	RPD Limits %
Radium-226	20.0	0.0150	19.8	22.1	99.1	111	1	75.0-125			11.0		20
(T) Barium-133		84.2			87.8	82.4							

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

GLOSSARY OF TERMS

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Guide to Reading and Understanding Your Laboratory Report

HEN-257-804

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.


Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

Abbreviations and Definitions

MDA	Minimum Detectable Activity.
Rec.	Recovery.
RER	Replicate Error Ratio.
RPD	Relative Percent Difference.
SDG	Sample Delivery Group.
(T)	Tracer - A radioisotope of known concentration added to a solution of chemically equivalent radioisotopes at a known concentration to assist in monitoring the yield of the chemical separation.
Analyte	The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported.
Dilution	If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor.
Limits	These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges.
Original Sample	The non-spiked sample in the prep batch used to determine the Relative Percent Difference (RPD) from a quality control sample. The Original Sample may not be included within the reported SDG.
Qualifier	This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable.
Result	The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state "ND" (Not Detected) or "BDL" (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte.
Uncertainty (Radiochemistry)	Confidence level of 2 sigma.
Case Narrative (Cn)	A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report.
Quality Control Summary (Qc)	This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material.
Sample Chain of Custody (Sc)	This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis.
Sample Results (Sr)	This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported.
Sample Summary (Ss)	This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis.

Qualifier Description

J	The identification of the analyte is acceptable; the reported value is an estimate.
U	Below Detectable Limits: Indicates that the analyte was not detected.



ACCREDITATIONS & LOCATIONS

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804


Pace Analytical National 12065 Lebanon Rd Mount Juliet, TN 37122

Alabama	40660	Nebraska	NE-OS-15-05
Alaska	17-026	Nevada	TN000032021-1
Arizona	AZ0612	New Hampshire	2975
Arkansas	88-0469	New Jersey--NELAP	TN002
California	2932	New Mexico ¹	TN00003
Colorado	TN00003	New York	11742
Connecticut	PH-0197	North Carolina	Env375
Florida	E87487	North Carolina ¹	DW21704
Georgia	NELAP	North Carolina ³	41
Georgia ¹	923	North Dakota	R-140
Idaho	TN00003	Ohio--VAP	CL0069
Illinois	200008	Oklahoma	9915
Indiana	C-TN-01	Oregon	TN200002
Iowa	364	Pennsylvania	68-02979
Kansas	E-10277	Rhode Island	LA000356
Kentucky ^{1,6}	KY90010	South Carolina	84004002
Kentucky ²	16	South Dakota	n/a
Louisiana	AI30792	Tennessee ^{1,4}	2006
Louisiana	LA018	Texas	T104704245-20-18
Maine	TN00003	Texas ⁵	LAB0152
Maryland	324	Utah	TN000032021-11
Massachusetts	M-TN003	Vermont	VT2006
Michigan	9958	Virginia	110033
Minnesota	047-999-395	Washington	C847
Mississippi	TN00003	West Virginia	233
Missouri	340	Wisconsin	998093910
Montana	CERT0086	Wyoming	A2LA
A2LA -- ISO 17025	1461.01	AIHA-LAP,LLC EMLAP	100789
A2LA -- ISO 17025 ⁵	1461.02	DOD	1461.01
Canada	1461.01	USDA	P330-15-00234
EPA--Crypto	TN00003		

¹ Drinking Water ² Underground Storage Tanks ³ Aquatic Toxicity ⁴ Chemical/Microbiological ⁵ Mold ⁶ Wastewater n/a Accreditation not applicable

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.

* Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace Analytical.



ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

TEKLAB, INC. Chain of Custody

5445 Horseshoe Lake Road, Collinsville, IL 62234 Phone (618) 344-1004 Fax (618) 344-1005

Are the samples chilled? YES ☐ NO ☒ With: ☐ Ice ☐ Blue Ice Preserved in: ☐ Lab ☐ Field

Teklab Inc
5445 Horseshoe Lake Road
Collinsville, IL 62234

Cooler Temp: Sampler: Joseph Riley/Adam Bridges

QC Level:

Project#

Contact: Elizabeth Hurley

Email: EHurley@TekLabInc.com

Requested Due Date: Standard TAT

Billing/PO: 34061

Phone: (618) 344-1004

Comments: **Please Issue reports and invoices via email only**

Please analyze for Radium 226/228 on your standard turn around time.

Samples collected from an IL site.

Batch QC is required for all analyses requested. EDD requested..

11591902

PLEASE NOTE:

NELAP accreditation is required on the requested analytes and must be documented as such on the final report. If your laboratory does not currently hold a NELAP accreditation for the requested method and/or analytes, please contact Teklab immediately. If your laboratory loses accreditation or is suspended for any analyte/method during the life of the contract, you must contact Teklab immediately.

Any changes to analysis/methods must be approved by Teklab, Inc.

Lab Use	Sample ID	Sample Date/Time	Preservative	Matrix	Ra226/228															
-01	23020844-001	3/1/23 1326	HNO3	Groundwater	✓															
-02	23020844-002	3/1/23 1616	HNO3	Groundwater	✓															
-03	23020844-003	3/1/23 1501	HNO3	Groundwater	✓															
-04	23020844-004	3/1/23 1442	HNO3	Groundwater	✓															
-05	23020844-005	3/1/23 1046	HNO3	Groundwater	✓															
-06	23020844-006	3/1/23 1028	HNO3	Groundwater	✓															
-07	23020844-007	3/1/23 1557	HNO3	Groundwater	✓															
-08	23020844-008	3/1/23 1614	HNO3	Groundwater	✓															
-09	23020844-009	3/1/23 1253	HNO3	Groundwater	✓															
-10	23020844-010	3/1/23 1308	HNO3	Groundwater	✓															
-11	23020844-011	2/28/23 0918	HNO3	Groundwater	✓															

*Relinquished By	Date/Time	Received By	Date/Time
<i>[Signature]</i>	3/2/23	<i>[Signature]</i>	3/6/23

631936159223

Teklab maintains a strict policy of client confidentiality and as such does not provide client/sam
Teklab, Inc. protects clients' confidential information as directed by local, state or federal

Sample Receipt Checklist

COC Seal Present/Intact: ☒ Y ☐ N If Applicable

COC Signed/Accurate: ☒ Y ☐ N VOA Zero Headspace: ☒ Y ☐ N

Bottles arrive intact: ☒ Y ☐ N Pres. Correct/Check: ☒ Y ☐ N

Correct bottles used: ☒ Y ☐ N

Sufficient volume sent: ☒ Y ☐ N

RAD Screen <0.5 mR/hr: ☒ Y ☐ N

Amb+0 = Amb

TEKLAB, INC. Chain of Custody

5445 Horseshoe Lake Road, Collinsville, IL 62234 Phone (618) 344-1004 Fax (618) 344-1005

Are the samples chilled? YES ☐ NO ☒ With: ☐ Ice ☐ Blue Ice Preserved in: ☐ Lab ☐ Field

Teklab Inc
5445 Horseshoe Lake Road
Collinsville, IL 62234

Cooler Temp: Sampler: Joseph Riley/Adam Bridges

QC Level: 3

Project# 23020844

Contact: Elizabeth Hurley

Email: EHurley@TekLabInc.com

Requested Due Date: Standard TAT

Billing/PO: 34061

Phone: (618) 344-1004

Comments: Please Issue reports and invoices via email only

Please analyze for Radium 226/228 on your standard turn around time.

Samples collected from an IL site.

Batch QC is required for all analyses requested. EDD requested..

PLEASE NOTE:

NELAP accreditation is required on the requested analytes and must be documented as such on the final report. If your laboratory does not currently hold a NELAP accreditation for the requested method and/or analytes, please contact Teklab immediately. If your laboratory loses accreditation or is suspended for any analyte/method during the life of the contract, you must contact Teklab immediately.

Any changes to analysis/methods must be approved by Teklab, Inc.

Lab Use	Sample ID	Sample Date/Time	Preservative	Matrix	Ra226/228															
-01	23020844-001	3/1/23 1326	HNO3	Groundwater	✓															
-02	23020844-002	3/1/23 1616	HNO3	Groundwater	✓															
-03	23020844-003	3/1/23 1501	HNO3	Groundwater	✓															
-04	23020844-004	3/1/23 1442	HNO3	Groundwater	✓															
-05	23020844-005	3/1/23 1046	HNO3	Groundwater	✓															
-06	23020844-006	3/1/23 1028	HNO3	Groundwater	✓															
-07	23020844-007	3/1/23 1557	HNO3	Groundwater	✓															
-08	23020844-008	3/1/23 1614	HNO3	Groundwater	✓															
-09	23020844-009	3/1/23 1253	HNO3	Groundwater	✓															
-10	23020844-010	3/1/23 1308	HNO3	Groundwater	✓															
-11	23020844-011	2/28/23 0918	HNO3	Groundwater	✓															

*Relinquished By	Date/Time	Received By	Date/Time
<i>[Signature]</i>	3/2/23	<i>[Signature]</i>	3/6/23

631936159223

Sample Receipt Checklist

COC Seal Present/Intact: ☒ Y ☐ N If Applicable
COC Signed/Accurate: ☒ Y ☐ N VOA Zero Headspace: ☒ Y ☐ N
Bottles arrive intact: ☒ Y ☐ N Pres. Correct/Check: ☒ Y ☐ N
Correct bottles used: ☒ Y ☐ N
Sufficient volume sent: ☒ Y ☐ N
RAD Screen <0.5 mR/hr: ☒ Y ☐ N

Amb+0=Amb

Teklab maintains a strict policy of client confidentiality and as such does not provide client/sam
Teklab, Inc. protects clients' confidential information as directed by local, state or federal

SubCocRevA
3/2/2016

TEKLAB, INC. Chain of Custody

5445 Horseshoe Lake Road, Collinsville, IL 62234 Phone (618) 344-1004 Fax (618) 344-1005

Are the samples chilled? YES ☐ NO ☒ With: ☐ Ice ☐ Blue Ice Preserved in: ☐ Lab ☐ Field

Teklab Inc
5445 Horseshoe Lake Road
Collinsville, IL 62234

Cooler Temp: Sampler: Joseph Riley/Adam Bridges

QC Level:

Project# 23020844

Comments: Please Issue reports and invoices via email only

Please analyze for Radium 226/228 on your standard turn around time.

Samples collected from an IL site.

Batch QC is required for all analyses requested. EDD requested..

Contact: Elizabeth Hurley

Email: EHurley@TekLabInc.com

Requested Due Date: Standard TAT

Billing/PO: 34061

Phone: (618) 344-1004

LF591962

PLEASE NOTE:

NELAP accreditation is required on the requested analytes and must be documented as such on the final report. If your laboratory does not currently hold a NELAP accreditation for the requested method and/or analytes, please contact Teklab immediately. If your laboratory loses accreditation or is suspended for any analyte/method during the life of the contract, you must contact Teklab immediately.

Any changes to analysis/methods must be approved by Teklab, Inc.

Lab Use	Sample ID	Sample Date/Time	Preservative	Matrix	Ra226/228														
-12	23020844-012	2/28/23 1128	HNO3	Groundwater	✓														
-13	23020844-013	2/28/23 1144	HNO3	Groundwater	✓														
-14	23020844-014	2/28/23 1035	HNO3	Groundwater	✓														
-15	23020844-015	2/28/23 1347	HNO3	Groundwater	✓														
-16	23020844-016	2/28/23 1306	HNO3	Groundwater	✓														
-17	23020844-017	2/28/23 1421	HNO3	Groundwater	✓														
-18	23020844-018	2/28/23 1233	HNO3	Groundwater	✓														
-19	23020844-019	3/1/23 1350	HNO3	Groundwater	✓														
-20	23020844-020	2/28/23 1634	HNO3	Groundwater	✓														
-21	23020844-021	3/1/23 0937	HNO3	Groundwater	✓														
-22	23020844-022	2/28/23 1101	HNO3	Groundwater	✓														

*Relinquished By	Date/Time	Received By	Date/Time
<i>[Signature]</i>	3/2/23	<i>[Signature]</i>	3/6/23

Teklab maintains a strict policy of client confidentiality and as such does not provide client/sampler info
Teklab, Inc. protects clients' confidential information as directed by local, state or federal laws.

631936159212
Sample Receipt Checklist
COC Seal Present/Intact: ☒ Y ☐ N If Applicable
COC Signed/Accurate: ☒ Y ☐ N VOA Zero Headspace: ☐ Y ☐ N
Bottles arrive intact: ☒ Y ☐ N Pres. Correct/Check: ☐ Y ☐ N
Correct bottles used: ☒ Y ☐ N
Sufficient volume sent: ☒ Y ☐ N
Amb+0=Amb

TEKLAB, INC. Chain of Custody

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

5445 Horseshoe Lake Road, Collinsville, IL 62234 Phone (618) 344-1004 Fax (618) 344-1005

Are the samples chilled? YES ☐ NO ☒ With: ☐ Ice ☐ Blue Ice Preserved in: ☐ Lab ☐ Field

Teklab Inc
5445 Horseshoe Lake Road
Collinsville, IL 62234

Cooler Temp: Sampler: Joseph Riley/Adam Bridges

QC Level:

Project# 23020844

Comments: Please issue reports and invoices via email only

Please analyze for Radium 226/228 on your standard turn around time.

Samples collected from an IL site.

Batch QC is required for all analyses requested. EDD requested..

Contact: Elizabeth Hurley

Email: EHurley@TekLabInc.com

Requested Due Date: Standard TAT

Billing/PO: 34061

Phone: (618) 344-1004

11591962

PLEASE NOTE:

NELAP accreditation is required on the requested analytes and must be documented as such on the final report. If your laboratory does not currently hold a NELAP accreditation for the requested method and/or analytes, please contact Teklab immediately. If your laboratory loses accreditation or is suspended for any analyte/method during the life of the contract, you must contact Teklab immediately.

Any changes to analysis/methods must be approved by Teklab, Inc.

Lab Use	Sample ID	Sample Date/Time	Preservative	Matrix	Ra226/228														
-23	23020844-023	2/28/23 23 1210	HNO3	Groundwater	✓														
-24	23020844-024	2/28/23 1003	HNO3	Groundwater	✓														
-25	23020844-025	2/28/23 1057	HNO3	Groundwater	✓														
-26	23020844-026	3/1/23 0959	HNO3	Groundwater	✓														
-27	23020844-027	3/1/23 1501	HNO3	Groundwater	✓														
-28	23020844-028	3/1/23 1701	HNO3	Groundwater	✓														
			HNO3	Groundwater															
			HNO3	Groundwater															
			HNO3	Groundwater															
			HNO3	Groundwater															
			HNO3	Groundwater															
			HNO3	Groundwater															

*Relinquished By	Date/Time	Received By	Date/Time
DMP	3/2/23	Adam Bridges	3/6/23

Teklab maintains a strict policy of client confidentiality and as such does not provide client/sampler
Teklab, Inc. protects clients' confidential information as directed by local, state or federal law

631936159201

Sample Receipt Checklist

COC Seal Present/Intact: ☒ Y ☐ N If Applicable
COC Signed/Accurate: ☒ Y ☐ N
Bottles arrive intact: ☒ Y ☐ N
Correct bottles used: ☒ Y ☐ N
Sufficient volume sent: ☒ Y ☐ N
RAD Screen <0.5 mR/hr: ☒ Y ☐ N

AMB+0=AMB

ubCocRevA
12/2016

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

45519102

Tracking Numbers		Temperature
631936159223		Amb+0-Amb
631936159212		Amb+0-Amb
631936159201		Amb+0-Amb

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION											
Site: <u>Hennepin</u>			Client: <u>Vistra</u>								
Project Number: 23010001			Task #:		Start Date: 1/11/2023		Time: 11:00				
Field Personnel: <u>J. Riley / J. Colp</u>			Finish Date: <u>2/28/2023</u>			Time: <u>1306</u>					
WELL INFORMATION				EVENT TYPE							
Well ID: <u>32</u>				Well Development				Low-Flow / Low Stress Sampling Other			
Casing ID: _____ inches				Well Volume Approach Sampling				(Specify): Low Flow			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mv)	Visual Clarity
	12:54		4.62								
	12:57	0.13	4.62	0	10.1	7.2	1321	0.76	32.07	122.2	
	13:00	0.26	4.62	0	10	7.1	1321	0.56	26.93	120.4	
	13:03	0.39	4.62	0	10.1	7.04	1318	0.44	16.64	118	
	13:06	0.52	4.62	0	10.2	7.02	1317	0.39	9.62	116.1	Clear
NOTES (continued)								ABBREVIATIONS			
Bladder Pump / Clear / No Color / No odor								Cond. - Actual Conductivity ORP - Oxidation-Reduction Potential SEC - Specific Electrical FT BTQC - Feet Below Top of Casing na - Conductance SU - Standard Units			

Low-Flow Sampling Form

Page 2 of 2

□	□
□	□

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION											
Site: <u>Hennepin</u>			Client: <u>Vistra</u>								
Project Number: <u>23010001</u>			Task #: _____			Start Date: <u>1/11/2023</u>			Time: <u>11:00</u>		
Field Personnel: <u>J. Riley / J. Colp</u>			Finish Date: <u>2/28/2023</u>			Time: _____			<u>1421</u>		
WELL INFORMATION				EVENT TYPE							
Well ID: <u>34</u> Casing ID: _____ inches				Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	14:12		2.45								
	14:15	0.13	2.45	0	11.2	6.98	1691	0.6	64.24	-71.4	
	14:18	0.26	2.45	0	11.2	6.93	1698	0.5	27.88	-80.3	
	14:21	0.39	2.45	0	11.2	6.92	1703	0.43	8.83	-84.5	Clear
NOTES (continued)								ABBREVIATIONS			
Bladder Pump / Clear / No Color / Slight odor								Cond. - Actual Conductivity ORP - Oxidation-Reduction Potential SEC - Specific Electrical FT BTQC - Feet Below Top of Casing na - Conductance SU - Standard Units			

Low-Flow Sampling Form

Page 2 of 2

☐	☐
☐	☐

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION											
Site: Hennepin		Client: Vistra									
Project Number: 23010001		Task #:		Start Date: 1/11/2023		Time: 11:00					
Field Personnel: J. Riley / J. Colp				Finish Date: 2/28/2023				Time: 0918			
WELL INFORMATION				EVENT TYPE							
Well ID: 21R				Well Development				Low-Flow / Low Stress Sampling Other			
Casing ID: inches				Well Volume Approach Sampling				(Specify): Low Flow			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	8:42		5.25								
	9:09	1.17	5.25	0	10.8	7.38	1522	1.84	125.37	-141.5	
	9:12	1.3	5.25	0	10.8	7.34	1519	1.41	116.76	-143.4	
	9:15	1.43	5.25	0	10.9	7.33	1518	1.29	120.4	-143	Clear
	9:18	1.56	5.25	0	10.9	7.33	1517	1.21	121.3	-143.2	
NOTES (continued)								ABBREVIATIONS			
Bladder Pump / Cloudy / Lt Brown / Slight odor								Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units			

Low-Flow Sampling Form

Page 2 of 2

☐	☐
☐	☐

HEN-257-804

Bladder Pump / Clear /No Color / No odor

HEN-257-804

Bladder Pump / Clear /No Color / No odor

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION											
Site: <u>Hennepin</u>			Client: <u>Vistra</u>								
Project Number: <u>23010001</u>			Task #: _____			Start Date: <u>1/11/2023</u>			Time: <u>11:00</u>		
Field Personnel: <u>J. Riley / J. Colp</u>			Finish Date: <u>2/28/2023</u>			Time: _____			<u>1035</u>		
WELL INFORMATION				EVENT TYPE							
Well ID: <u>23</u>				Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow			
Casing ID: _____ inches											
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µS/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	10:23		16.7								
	10:29	0.26	16.7	0	12.4	7.42	1664	0.44	0.18	-108.7	
	10:32	0.39	16.7	0	12.5	7.39	1662	0.35	0	-121.3	
	10:35	0.52	16.7	0	12.5	7.38	1657	0.3	0	-124.9	Clear
NOTES (continued)								ABBREVIATIONS			
Bladder Pump / Clear / No Color / No odor								Cond. - Actual Conductivity			
								FT BTOC - Feet Below Top of Casing na -			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units			

Low-Flow Sampling Form

Page 2 of 2

☐	☐
☐	☐

HEN-257-804

Bladder Pump / Clear /No Color / Slight odor

Page 2 of 2

	☐	☐
	☐	☐

Page 2 of 2

Page 2 of 2

HEN-257-804

Bladder Pump / Clear /No Color / No odor

Page 2 of 2

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION															
Site: <u>Hennepin</u>			Client: <u>Vistra</u>												
Project Number: 23010001			Task #:		Start Date: 1/11/2023		Time: 11:00								
Field Personnel: <u>J. Riley / J. Colp</u>			Finish Date: <u>2/28/2023</u>			Time: <u>1003</u>									
WELL INFORMATION				EVENT TYPE											
Well ID: <u>51</u> Casing ID: _____ inches				Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow							
WATER QUALITY INDICATOR PARAMETERS (continued)															
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity				
	9:45		17.91												
	9:54	0.39	17.91	0	11.4	7.24	1465	2.19	36.33	-97.9					
	9:57	0.52	17.91	0	11.8	7.22	1471	1.38	26.29	-111.7					
	10:00	0.65	17.91	0	11.8	7.23	1476	1	20.87	-118.9					
	10:03	0.78	17.91	0	11.2	7.23	1477	1.08	21.13	-119.3	Clear				
NOTES (continued)								ABBREVIATIONS							
Bladder Pump / Clear / No Color / Slight odor								Cond. - Actual Conductivity				ORP - Oxidation-Reduction Potential SEC - Specific Electrical			
								FT BTOC - Feet Below Top of Casing na -				Conductance SU - Standard Units			

Low-Flow Sampling Form

Page 2 of 2

□	□
□	□

June 21, 2023

Eric Bauer
Ramboll
300 S. Wacker Drive
Suite 130
Chicago, IL 60606
TEL: (414) 837-3607
FAX: (414) 837-3608



Illinois	100226
Kansas	E-10374
Louisiana	05002
Louisiana	05003
Oklahoma	9978

RE: HEN-23Q2

WorkOrder: 23051600

Dear Eric Bauer:

TEKLAB, INC received 45 samples on 6/1/2023 4:00:00 PM for the analysis presented in the following report.

Samples are analyzed on an as received basis unless otherwise requested and documented. The sample results contained in this report relate only to the requested analytes of interest as directed on the chain of custody. NELAP accredited fields of testing are indicated by the letters NELAP under the Certification column. Unless otherwise documented within this report, Teklab Inc. analyzes samples utilizing the most current methods in compliance with 40CFR. All tests are performed in the Collinsville, IL laboratory unless otherwise noted in the Case Narrative.

All quality control criteria applicable to the test methods employed for this project have been satisfactorily met and are in accordance with NELAP except where noted. The following report shall not be reproduced, except in full, without the written approval of Teklab, Inc.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,



Elizabeth A. Hurley
Director of Customer Service
(618)344-1004 ex 33
ehurley@teklabinc.com



Report Contents

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

This reporting package includes the following:

Cover Letter	1
Report Contents	2
Definitions	3
Case Narrative	5
Accreditations	6
Laboratory Results	7
Sample Summary	37
Dates Report	38
Quality Control Results	55
Receiving Check List	125
Chain of Custody	Appended



Definitions

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Abbr Definition

* Analytes on report marked with an asterisk are not NELAP accredited

CCV Continuing calibration verification is a check of a standard to determine the state of calibration of an instrument between recalibration.

CRQL A Client Requested Quantitation Limit is a reporting limit that varies according to customer request. The CRQL may not be less than the MDL.

DF Dilution factor is the dilution performed during analysis only and does not take into account any dilutions made during sample preparation. The reported result is final and includes all dilution factors.

DNI Did not ignite

DUP Laboratory duplicate is a replicate aliquot prepared under the same laboratory conditions and independently analyzed to obtain a measure of precision.

ICV Initial calibration verification is a check of a standard to determine the state of calibration of an instrument before sample analysis is initiated.

IDPH IL Dept. of Public Health

LCS Laboratory control sample is a sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes and analyzed exactly like a sample to establish intra-laboratory or analyst specific precision and bias or to assess the performance of all or a portion of the measurement system.

LCSD Laboratory control sample duplicate is a replicate laboratory control sample that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).

MBLK Method blank is a sample of a matrix similar to the batch of associated sample (when available) that is free from the analytes of interest and is processed simultaneously with and under the same conditions as samples through all steps of the analytical procedures, and in which no target analytes or interferences should present at concentrations that impact the analytical results for sample analyses.

MDL "The method detection limit is defined as the minimum measured concentration of a substance that can be reported with 99% confidence that the measured concentration is distinguishable from method blank results."

MS Matrix spike is an aliquot of matrix fortified (spiked) with known quantities of specific analytes that is subjected to the entire analytical procedures in order to determine the effect of the matrix on an approved test method's recovery system. The acceptable recovery range is listed in the QC Package (provided upon request).

MSD Matrix spike duplicate means a replicate matrix spike that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).

MW Molecular weight

NC Data is not acceptable for compliance purposes

ND Not Detected at the Reporting Limit

NELAP NELAP Accredited

PQL Practical quantitation limit means the lowest level that can be reliably achieved within specified limits of precision and accuracy during routine laboratory operation conditions.

RL The reporting limit the lowest level that the data is displayed in the final report. The reporting limit may vary according to customer request or sample dilution. The reporting limit may not be less than the MDL.

RPD Relative percent difference is a calculated difference between two recoveries (ie. MS/MSD). The acceptable recovery limit is listed in the QC Package (provided upon request).

SPK The spike is a known mass of target analyte added to a blank sample or sub-sample; used to determine recovery deficiency or for other quality control purposes.

Surr Surrogates are compounds which are similar to the analytes of interest in chemical composition and behavior in the analytical process, but which are not normally found in environmental samples.

TIC Tentatively identified compound: Analytes tentatively identified in the sample by using a library search. Only results not in the calibration standard will be reported as tentatively identified compounds. Results for tentatively identified compounds that are not present in the calibration standard, but are assigned a specific chemical name based upon the library search, are calculated using total peak areas from reconstructed ion chromatograms and a response factor of one. The nearest Internal Standard is used for the calculation. The results of any TICs must be considered estimated, and are flagged with a "T". If the estimated result is above the calibration range it is flagged "ET"

TNTC Too numerous to count (> 200 CFU)



Definitions

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Qualifiers

- | | |
|---|--|
| # - Unknown hydrocarbon | B - Analyte detected in associated Method Blank |
| C - RL shown is a Client Requested Quantitation Limit | E - Value above quantitation range |
| H - Holding times exceeded | I - Associated internal standard was outside method criteria |
| J - Analyte detected below quantitation limits | M - Manual Integration used to determine area response |
| ND - Not Detected at the Reporting Limit | R - RPD outside accepted recovery limits |
| S - Spike Recovery outside recovery limits | T - TIC(Tentatively identified compound) |
| X - Value exceeds Maximum Contaminant Level | |



Case Narrative

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

Cooler Receipt Temp: 5.4 °C

An employee of Teklab, Inc. collected the sample(s).

HEN_257_804 data is included in this report. EAH 6/21/23

Locations

Collinsville

Address 5445 Horseshoe Lake Road
Collinsville, IL 62234-7425
Phone (618) 344-1004
Fax (618) 344-1005
Email jhriley@teklabinc.com

Collinsville Air

Address 5445 Horseshoe Lake Road
Collinsville, IL 62234-7425
Phone (618) 344-1004
Fax (618) 344-1005
Email EHurley@teklabinc.com

Springfield

Address 3920 Pintail Dr
Springfield, IL 62711-9415
Phone (217) 698-1004
Fax (217) 698-1005
Email KKlostermann@teklabinc.com

Chicago

Address 1319 Butterfield Rd.
Downers Grove, IL 60515
Phone (630) 324-6855
Fax
Email arenner@teklabinc.com

Kansas City

Address 8421 Nieman Road
Lenexa, KS 66214
Phone (913) 541-1998
Fax (913) 541-1998
Email jhriley@teklabinc.com



Accreditations

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

State	Dept	Cert #	NELAP	Exp Date	Lab
Illinois	IEPA	100226	NELAP	1/31/2024	Collinsville
Kansas	KDHE	E-10374	NELAP	4/30/2024	Collinsville
Louisiana	LDEQ	05002	NELAP	6/30/2023	Collinsville
Louisiana	LDEQ	05003	NELAP	6/30/2023	Collinsville
Oklahoma	ODEQ	9978	NELAP	8/31/2023	Collinsville
Arkansas	ADEQ	88-0966		3/14/2024	Collinsville
Illinois	IDPH	17584		5/31/2025	Collinsville
Iowa	IDNR	430		6/1/2024	Collinsville
Kentucky	UST	0073		1/31/2024	Collinsville
Missouri	MDNR	00930		5/31/2023	Collinsville
Missouri	MDNR	930		1/31/2025	Collinsville



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804
Laboratory Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-015
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-21R
Collection Date: 05/31/2023 11:09

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		5.92	ft	1	05/31/2023 11:09	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		42	NTU	1	05/31/2023 11:09	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		-178	mV	1	05/31/2023 11:09	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		1150	µS/cm	1	05/31/2023 11:09	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		13.2	°C	1	05/31/2023 11:09	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.12	mg/L	1	05/31/2023 11:09	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		7.37		1	05/31/2023 11:09	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		388	mg/L	1	06/05/2023 15:36	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 15:36	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	40	50		695	mg/L	2.5	06/05/2023 11:19	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	31	50		91	mg/L	5	06/02/2023 19:29	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10		0.12	mg/L	1	06/05/2023 11:38	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	2	20		103	mg/L	5	06/02/2023 19:30	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		0.0274	mg/L	1	06/05/2023 17:46	206856
Barium	NELAP	0.0007	0.0025		0.296	mg/L	1	06/05/2023 17:46	206856
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 17:46	206856
Boron	NELAP	0.0090	0.0200		2.32	mg/L	1	06/05/2023 17:46	206856
Cadmium	NELAP	0.0005	0.0020		< 0.0020	mg/L	1	06/05/2023 17:46	206856
Calcium	NELAP	0.0350	0.100		121	mg/L	1	06/05/2023 17:46	206856
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 17:46	206856
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 17:46	206856
Lithium	NELAP	0.0019	0.0050		0.0167	mg/L	1	06/15/2023 10:59	206856
Magnesium	NELAP	0.0055	0.0500		41.7	mg/L	1	06/05/2023 17:46	206856
Molybdenum	NELAP	0.0037	0.010	J	0.0080	mg/L	1	06/05/2023 17:46	206856
Potassium	NELAP	0.0400	0.100		3.01	mg/L	1	06/05/2023 17:46	206856
Sodium	NELAP	0.0180	0.0500		49.4	mg/L	1	06/05/2023 17:46	206856
<i>Sample result exceeds 10 times the method blank contamination for Si. Data is reportable per the TNI Standard.</i>									
<i>Allowable Marginal Exceedance of Si in the laboratory control sample is verified per the TNI Standard.</i>									
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 19:00	206856
Cobalt	NELAP	0.0001	0.0010		0.0013	mg/L	5	06/05/2023 19:00	206856
Selenium	NELAP	0.0006	0.0010		< 0.0010	mg/L	5	06/05/2023 19:00	206856
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 19:00	206856



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-015
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-21R
Collection Date: 05/31/2023 11:09

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 10:52	206867



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-016
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-22
Collection Date: 05/31/2023 14:01

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		18.45	ft	1	05/31/2023 14:01	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		< 1.0	NTU	1	05/31/2023 14:01	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		49	mV	1	05/31/2023 14:01	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		999	µS/cm	1	05/31/2023 14:01	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		15.7	°C	1	05/31/2023 14:01	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.43	mg/L	1	05/31/2023 14:01	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		7.58		1	05/31/2023 14:01	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		243	mg/L	1	06/05/2023 15:42	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 15:42	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	16	20		586	mg/L	1	06/05/2023 11:19	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	31	50		123	mg/L	5	06/02/2023 19:36	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10		0.13	mg/L	1	06/05/2023 11:41	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	2	20		97	mg/L	5	06/02/2023 19:38	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		< 0.0100	mg/L	1	06/05/2023 17:47	206856
Barium	NELAP	0.0007	0.0025		0.0585	mg/L	1	06/05/2023 17:47	206856
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 17:47	206856
Boron	NELAP	0.0090	0.0200		3.44	mg/L	1	06/05/2023 17:47	206856
Cadmium	NELAP	0.0005	0.0020		0.0052	mg/L	1	06/05/2023 17:47	206856
Calcium	NELAP	0.0350	0.100		87.1	mg/L	1	06/05/2023 17:47	206856
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 17:47	206856
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 17:47	206856
Lithium	NELAP	0.0019	0.0050		0.0500	mg/L	1	06/15/2023 11:02	206856
Magnesium	NELAP	0.0055	0.0500		32.0	mg/L	1	06/05/2023 17:47	206856
Molybdenum	NELAP	0.0037	0.0100		0.0829	mg/L	1	06/05/2023 17:47	206856
Potassium	NELAP	0.400	1.00		11.4	mg/L	10	06/08/2023 12:26	206856
Sodium	NELAP	0.0180	0.0500		55.8	mg/L	1	06/05/2023 17:47	206856
<i>Sample result exceeds 10 times the method blank contamination for Si. Data is reportable per the TNI Standard.</i>									
<i>Allowable Marginal Exceedance of Si in the laboratory control sample is verified per the TNI Standard.</i>									
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010	J	0.0008	mg/L	5	06/05/2023 19:05	206856
Cobalt	NELAP	0.0001	0.0010		0.0024	mg/L	5	06/05/2023 19:05	206856
Selenium	NELAP	0.0006	0.0010		0.0157	mg/L	5	06/05/2023 19:05	206856
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 19:05	206856



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-016
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-22
Collection Date: 05/31/2023 14:01

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 10:54	206867



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804
Laboratory Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-017
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-22&D
Collection Date: 05/31/2023 14:19

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		19.10	ft	1	05/31/2023 14:19	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		1.8	NTU	1	05/31/2023 14:19	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		-121	mV	1	05/31/2023 14:19	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		1120	µS/cm	1	05/31/2023 14:19	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		15.9	°C	1	05/31/2023 14:19	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.41	mg/L	1	05/31/2023 14:19	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		7.24		1	05/31/2023 14:19	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		345	mg/L	1	06/05/2023 16:00	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 16:00	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	40	50		640	mg/L	2.5	06/05/2023 11:20	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	31	50		104	mg/L	5	06/02/2023 19:45	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10	J	0.09	mg/L	1	06/05/2023 11:42	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	2	20		110	mg/L	5	06/02/2023 19:46	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		< 0.0100	mg/L	1	06/05/2023 17:47	206856
Barium	NELAP	0.0007	0.0025		0.0669	mg/L	1	06/05/2023 17:47	206856
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 17:47	206856
Boron	NELAP	0.0090	0.0200		1.57	mg/L	1	06/05/2023 17:47	206856
Cadmium	NELAP	0.0005	0.0020		< 0.0020	mg/L	1	06/05/2023 17:47	206856
Calcium	NELAP	0.0350	0.100		113	mg/L	1	06/05/2023 17:47	206856
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 17:47	206856
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 17:47	206856
Lithium	NELAP	0.0019	0.0050		0.0150	mg/L	1	06/15/2023 11:06	206856
Magnesium	NELAP	0.0055	0.0500		39.4	mg/L	1	06/05/2023 17:47	206856
Molybdenum	NELAP	0.0037	0.010	J	0.0054	mg/L	1	06/05/2023 17:47	206856
Potassium	NELAP	0.0400	0.100		3.32	mg/L	1	06/05/2023 17:47	206856
Sodium	NELAP	0.0180	0.0500		47.2	mg/L	1	06/05/2023 17:47	206856
<i>Sample result exceeds 10 times the method blank contamination for Si. Data is reportable per the TNI Standard.</i>									
<i>Allowable Marginal Exceedance of Si in the laboratory control sample is verified per the TNI Standard.</i>									
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 19:11	206856
Cobalt	NELAP	0.0001	0.0010	J	0.0004	mg/L	5	06/05/2023 19:11	206856
Selenium	NELAP	0.0006	0.0010		< 0.0010	mg/L	5	06/05/2023 19:11	206856
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 19:11	206856



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-017
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-22&D
Collection Date: 05/31/2023 14:19

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 12:29	206869



Laboratory Results

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

Lab ID: 23051600-018

Client Sample ID: HEN-23

Matrix: GROUNDWATER

Collection Date: 05/31/2023 12:00

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		16.72	ft	1	05/31/2023 12:00	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		< 1.0	NTU	1	05/31/2023 12:00	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		-127	mV	1	05/31/2023 12:00	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		1280	µS/cm	1	05/31/2023 12:00	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		13.0	°C	1	05/31/2023 12:00	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.55	mg/L	1	05/31/2023 12:00	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		7.41		1	05/31/2023 12:00	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		169	mg/L	1	06/05/2023 16:08	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 16:08	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	16	20		876	mg/L	1	06/05/2023 11:20	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	123	200		450	mg/L	20	06/02/2023 20:15	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10		0.14	mg/L	1	06/05/2023 11:53	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	1	8		55	mg/L	2	06/02/2023 20:10	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		< 0.0100	mg/L	1	06/05/2023 17:52	206856
Barium	NELAP	0.0007	0.0025		0.0481	mg/L	1	06/05/2023 17:52	206856
Beryllium	NELAP	0.0002	0.0005	J	0.0003	mg/L	1	06/05/2023 17:52	206856
Boron	NELAP	0.0090	0.0200		8.79	mg/L	1	06/05/2023 17:52	206856
Cadmium	NELAP	0.0005	0.0020		< 0.0020	mg/L	1	06/05/2023 17:52	206856
Calcium	NELAP	0.0350	0.100		105	mg/L	1	06/05/2023 17:52	206856
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 17:52	206856
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 17:52	206856
Lithium	NELAP	0.0019	0.0050		< 0.0050	mg/L	1	06/14/2023 20:27	206856
Magnesium	NELAP	0.0055	0.0500		77.5	mg/L	1	06/05/2023 17:52	206856
Molybdenum	NELAP	0.0037	0.0100		0.0146	mg/L	1	06/05/2023 17:52	206856
Potassium	NELAP	0.0400	0.100		3.16	mg/L	1	06/05/2023 17:52	206856
Sodium	NELAP	0.0180	0.0500		46.0	mg/L	1	06/05/2023 17:52	206856
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 19:53	206856
Cobalt	NELAP	0.0001	0.0010	J	0.0004	mg/L	5	06/05/2023 19:53	206856

Contamination present in the CCB for Li. Sample results below the reporting limit are reportable per the TNI Standard.

CCV recovered outside the upper control limits. Sample results are below the reporting limit. Data is reportable per the TNI standard.

Sample result exceeds 10 times the method blank contamination for Si. Data is reportable per the TNI Standard.

Allowable Marginal Exceedance of Si in the laboratory control sample is verified per the TNI Standard.



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-018
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23

Client Sample ID: HEN-23
Collection Date: 05/31/2023 12:00

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Selenium	NELAP	0.0006	0.0010		< 0.0010	mg/L	5	06/05/2023 19:53	206856
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 19:53	206856
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 12:31	206869



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-019
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-25
Collection Date: 05/31/2023 12:59

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		15.94	ft	1	05/31/2023 12:59	R329806



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-020
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-26
Collection Date: 05/31/2023 12:41

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		16.00	ft	1	05/31/2023 12:41	R329806



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804
Laboratory Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-021
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-27
Collection Date: 05/31/2023 9:15

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		4.14	ft	1	05/31/2023 9:15	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		8.2	NTU	1	05/31/2023 9:15	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		-16	mV	1	05/31/2023 9:15	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		1130	µS/cm	1	05/31/2023 9:15	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		12.0	°C	1	05/31/2023 9:15	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.05	mg/L	1	05/31/2023 9:15	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		6.98		1	05/31/2023 9:15	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		334	mg/L	1	06/05/2023 17:17	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 17:17	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	16	20		658	mg/L	1	06/05/2023 11:21	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	31	50		118	mg/L	5	06/02/2023 20:36	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10		0.10	mg/L	1	06/05/2023 12:00	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	2	20		107	mg/L	5	06/02/2023 20:36	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		< 0.0100	mg/L	1	06/05/2023 17:54	206856
Barium	NELAP	0.0007	0.0025		0.0837	mg/L	1	06/05/2023 17:54	206856
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 17:54	206856
Boron	NELAP	0.0090	0.0200		2.27	mg/L	1	06/05/2023 17:54	206856
Cadmium	NELAP	0.0005	0.0020		< 0.0020	mg/L	1	06/05/2023 17:54	206856
Calcium	NELAP	0.0350	0.100		117	mg/L	1	06/05/2023 17:54	206856
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 17:54	206856
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 17:54	206856
Lithium	NELAP	0.0019	0.0050		0.0225	mg/L	1	06/15/2023 11:53	206856
Magnesium	NELAP	0.0055	0.0500		35.4	mg/L	1	06/05/2023 17:54	206856
Molybdenum	NELAP	0.0037	0.0100		< 0.0100	mg/L	1	06/05/2023 17:54	206856
Potassium	NELAP	0.0400	0.100		3.60	mg/L	1	06/05/2023 17:54	206856
Sodium	NELAP	0.0180	0.0500		54.8	mg/L	1	06/05/2023 17:54	206856
<i>Sample result exceeds 10 times the method blank contamination for Si. Data is reportable per the TNI Standard.</i>									
<i>Allowable Marginal Exceedance of Si in the laboratory control sample is verified per the TNI Standard.</i>									
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 20:09	206856
Cobalt	NELAP	0.0001	0.0010		0.0033	mg/L	5	06/05/2023 20:09	206856
Selenium	NELAP	0.0006	0.0010		< 0.0010	mg/L	5	06/05/2023 20:09	206856
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 20:09	206856



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-021
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-27
Collection Date: 05/31/2023 9:15

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 12:43	206869



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-022
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-30
Collection Date: 05/30/2023 15:09

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		6.62	ft	1	05/30/2023 15:09	R329806



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-023
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-31
Collection Date: 05/30/2023 15:09

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		6.56	ft	1	05/30/2023 15:09	R329806



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804
Laboratory Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-024
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-32
Collection Date: 05/31/2023 9:46

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		5.22	ft	1	05/31/2023 9:46	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		6.2	NTU	1	05/31/2023 9:46	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		86	mV	1	05/31/2023 9:46	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		997	µS/cm	1	05/31/2023 9:46	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		11.0	°C	1	05/31/2023 9:46	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.24	mg/L	1	05/31/2023 9:46	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		6.92		1	05/31/2023 9:46	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		329	mg/L	1	06/05/2023 17:24	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 17:24	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	16	20		550	mg/L	1	06/05/2023 11:22	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	12	20		63	mg/L	2	06/02/2023 21:13	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10		0.10	mg/L	1	06/05/2023 12:02	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	1	8		70	mg/L	2	06/02/2023 21:14	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		< 0.0100	mg/L	1	06/05/2023 17:55	206856
Barium	NELAP	0.0007	0.0025		0.0410	mg/L	1	06/05/2023 17:55	206856
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 17:55	206856
Boron	NELAP	0.0090	0.0200		0.143	mg/L	1	06/05/2023 17:55	206856
Cadmium	NELAP	0.0005	0.0020		< 0.0020	mg/L	1	06/05/2023 17:55	206856
Calcium	NELAP	0.0350	0.100	S	102	mg/L	1	06/05/2023 17:55	206856
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 17:55	206856
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 17:55	206856
Lithium	NELAP	0.0019	0.0050	JS	0.0029	mg/L	1	06/14/2023 20:41	206856
Magnesium	NELAP	0.0055	0.0500		39.5	mg/L	1	06/05/2023 17:55	206856
Molybdenum	NELAP	0.0037	0.0100		< 0.0100	mg/L	1	06/05/2023 17:55	206856
Potassium	NELAP	0.0400	0.100		2.22	mg/L	1	06/05/2023 17:55	206856
Sodium	NELAP	0.0180	0.0500		40.1	mg/L	1	06/05/2023 17:55	206856

Matrix spike recovered outside upper control limits. Sample results are below the reporting limit. Data is reportable.

Contamination present in the CCB for Li. Sample results below the reporting limit are reportable per the TNI Standard.

CCV recovered outside the upper control limits. Sample results are below the reporting limit. Data is reportable per the TNI standard.

Sample result exceeds 10 times the method blank contamination for Si. Data is reportable per the TNI Standard.

Allowable Marginal Exceedance of Si in the laboratory control sample is verified per the TNI Standard.

Matrix spike control limits are not applicable due to high sample/spike ratio.



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-024
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23

Client Sample ID: HEN-32
Collection Date: 05/31/2023 9:46

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 20:30	206856
Cobalt	NELAP	0.0001	0.0010		0.0018	mg/L	5	06/05/2023 20:30	206856
Selenium	NELAP	0.0006	0.0010		< 0.0010	mg/L	5	06/05/2023 20:30	206856
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 20:30	206856
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 12:45	206869



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-025
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-33
Collection Date: 05/30/2023 15:15

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		4.03	ft	1	05/30/2023 15:15	R329806



Laboratory Results

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

Lab ID: 23051600-026

Client Sample ID: HEN-34

Matrix: GROUNDWATER

Collection Date: 05/31/2023 10:39

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		8.66	ft	1	05/31/2023 10:39	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		1.8	NTU	1	05/31/2023 10:39	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		-83	mV	1	05/31/2023 10:39	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		1250	µS/cm	1	05/31/2023 10:39	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		12.3	°C	1	05/31/2023 10:39	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.60	mg/L	1	05/31/2023 10:39	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		6.92		1	05/31/2023 10:39	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		521	mg/L	1	06/05/2023 16:19	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 16:19	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	40	50		845	mg/L	2.5	06/05/2023 12:07	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	12	20		49	mg/L	2	06/02/2023 21:21	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10		0.12	mg/L	1	06/05/2023 12:04	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	1	8		71	mg/L	2	06/02/2023 21:22	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		< 0.0100	mg/L	1	06/05/2023 17:57	206856
Barium	NELAP	0.0007	0.0025		0.0995	mg/L	1	06/05/2023 17:57	206856
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 17:57	206856
Boron	NELAP	0.0090	0.0200		0.125	mg/L	1	06/05/2023 17:57	206856
Cadmium	NELAP	0.0005	0.0020		< 0.0020	mg/L	1	06/05/2023 17:57	206856
Calcium	NELAP	0.0350	0.100		149	mg/L	1	06/05/2023 17:57	206856
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 17:57	206856
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 17:57	206856
Lithium	NELAP	0.0019	0.0050	J	0.0032	mg/L	1	06/14/2023 20:52	206856
Magnesium	NELAP	0.0055	0.0500		41.8	mg/L	1	06/05/2023 17:57	206856
Molybdenum	NELAP	0.0037	0.0100		< 0.0100	mg/L	1	06/05/2023 17:57	206856
Potassium	NELAP	0.0400	0.100		0.450	mg/L	1	06/05/2023 17:57	206856
Sodium	NELAP	0.0180	0.0500		53.5	mg/L	1	06/05/2023 17:57	206856
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 20:14	206856
Cobalt	NELAP	0.0001	0.0010	J	0.0007	mg/L	5	06/05/2023 20:14	206856

Contamination present in the CCB for Li. Sample results below the reporting limit are reportable per the TNI Standard.

CCV recovered outside the upper control limits. Sample results are below the reporting limit. Data is reportable per the TNI standard.

Sample result exceeds 10 times the method blank contamination for Si. Data is reportable per the TNI Standard.

Allowable Marginal Exceedance of Si in the laboratory control sample is verified per the TNI Standard.



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-026
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23

Client Sample ID: HEN-34
Collection Date: 05/31/2023 10:39

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Selenium	NELAP	0.0006	0.0010		< 0.0010	mg/L	5	06/05/2023 20:14	206856
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 20:14	206856
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 12:47	206869



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804
Laboratory Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-027
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-35
Collection Date: 05/31/2023 10:09

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		8.30	ft	1	05/31/2023 10:09	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		2.2	NTU	1	05/31/2023 10:09	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		105	mV	1	05/31/2023 10:09	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		1650	µS/cm	1	05/31/2023 10:09	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		12.9	°C	1	05/31/2023 10:09	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.60	mg/L	1	05/31/2023 10:09	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		6.88		1	05/31/2023 10:09	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		249	mg/L	1	06/05/2023 16:26	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 16:26	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	16	20		1300	mg/L	1	06/05/2023 12:08	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	123	200		670	mg/L	20	06/02/2023 21:34	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10		0.11	mg/L	1	06/05/2023 12:06	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	1	4		32	mg/L	1	06/02/2023 21:30	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		< 0.0100	mg/L	1	06/05/2023 17:58	206856
Barium	NELAP	0.0007	0.0025		0.0381	mg/L	1	06/05/2023 17:58	206856
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 17:58	206856
Boron	NELAP	0.0090	0.0200		12.6	mg/L	1	06/05/2023 17:58	206856
Cadmium	NELAP	0.0005	0.0020		< 0.0020	mg/L	1	06/05/2023 17:58	206856
Calcium	NELAP	0.0350	0.100		291	mg/L	1	06/05/2023 17:58	206856
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 17:58	206856
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 17:58	206856
Lithium	NELAP	0.0019	0.0050		0.0210	mg/L	1	06/15/2023 11:56	206856
Magnesium	NELAP	0.0055	0.0500		31.7	mg/L	1	06/05/2023 17:58	206856
Molybdenum	NELAP	0.0037	0.0100		0.0798	mg/L	1	06/05/2023 17:58	206856
Potassium	NELAP	0.400	1.00		14.0	mg/L	10	06/08/2023 12:26	206856
Sodium	NELAP	0.0180	0.0500		30.8	mg/L	1	06/05/2023 17:58	206856
<i>Sample result exceeds 10 times the method blank contamination for Si. Data is reportable per the TNI Standard.</i>									
<i>Allowable Marginal Exceedance of Si in the laboratory control sample is verified per the TNI Standard.</i>									
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 20:19	206856
Cobalt	NELAP	0.0001	0.0010		0.0014	mg/L	5	06/05/2023 20:19	206856
Selenium	NELAP	0.0006	0.0010		< 0.0010	mg/L	5	06/05/2023 20:19	206856
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 20:19	206856



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-027
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-35
Collection Date: 05/31/2023 10:09

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 12:54	206869



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-028
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-36
Collection Date: 05/30/2023 15:28

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		15.32	ft	1	05/30/2023 15:28	R329806



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804
Laboratory Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-033
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-49
Collection Date: 05/31/2023 12:19

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		21.54	ft	1	05/31/2023 12:19	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		21	NTU	1	05/31/2023 12:19	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		-19	mV	1	05/31/2023 12:19	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		1080	µS/cm	1	05/31/2023 12:19	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		14.9	°C	1	05/31/2023 12:19	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.36	mg/L	1	05/31/2023 12:19	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		7.04		1	05/31/2023 12:19	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		339	mg/L	1	06/05/2023 16:44	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 16:44	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	16	20		602	mg/L	1	06/05/2023 12:10	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	31	50		84	mg/L	5	06/02/2023 22:09	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10		0.12	mg/L	1	06/05/2023 12:19	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	2	20		102	mg/L	5	06/02/2023 22:10	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		< 0.0100	mg/L	1	06/05/2023 16:58	206857
Barium	NELAP	0.0007	0.0025		0.0711	mg/L	1	06/05/2023 16:58	206857
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 16:58	206857
Boron	NELAP	0.0090	0.0200		0.758	mg/L	1	06/05/2023 16:58	206857
Cadmium	NELAP	0.0005	0.0020	J	0.0011	mg/L	1	06/05/2023 16:58	206857
Calcium	NELAP	0.0350	0.100		115	mg/L	1	06/05/2023 16:58	206857
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 16:58	206857
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 16:58	206857
Lithium	NELAP	0.0019	0.0050		0.0202	mg/L	1	06/15/2023 14:17	206857
Magnesium	NELAP	0.0055	0.0500		35.9	mg/L	1	06/05/2023 16:58	206857
Molybdenum	NELAP	0.0037	0.0100		0.0243	mg/L	1	06/05/2023 16:58	206857
Potassium	NELAP	0.400	1.00		12.3	mg/L	10	06/09/2023 11:08	206857
Sodium	NELAP	0.0180	0.0500		57.9	mg/L	1	06/05/2023 16:58	206857
<i>Sample result(s) for Si exceed 10 times the method blank contamination. Data is reportable per the TNI Standard.</i>									
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 14:53	206857
Cobalt	NELAP	0.0001	0.0010		0.0067	mg/L	5	06/05/2023 14:53	206857
Selenium	NELAP	0.0006	0.0010		< 0.0010	mg/L	5	06/05/2023 14:53	206857
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 14:53	206857



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-033
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-49
Collection Date: 05/31/2023 12:19

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 13:01	206869



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804
Laboratory Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-034
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-50
Collection Date: 05/31/2023 13:37

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		18.25	ft	1	05/31/2023 13:37	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		1.8	NTU	1	05/31/2023 13:37	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		34	mV	1	05/31/2023 13:37	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		1050	µS/cm	1	05/31/2023 13:37	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		15.5	°C	1	05/31/2023 13:37	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.17	mg/L	1	05/31/2023 13:37	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		7.35		1	05/31/2023 13:37	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		324	mg/L	1	06/05/2023 16:51	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 16:51	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	16	20		632	mg/L	1	06/05/2023 12:10	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	31	50		88	mg/L	5	06/02/2023 22:20	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10	J	0.09	mg/L	1	06/05/2023 12:22	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	2	20		90	mg/L	5	06/02/2023 22:20	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		< 0.0100	mg/L	1	06/05/2023 16:59	206857
Barium	NELAP	0.0007	0.0025		0.0888	mg/L	1	06/05/2023 16:59	206857
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 16:59	206857
Boron	NELAP	0.0090	0.0200		0.784	mg/L	1	06/05/2023 16:59	206857
Cadmium	NELAP	0.0005	0.0020		< 0.0020	mg/L	1	06/05/2023 16:59	206857
Calcium	NELAP	0.0350	0.100		122	mg/L	1	06/05/2023 16:59	206857
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 16:59	206857
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 16:59	206857
Lithium	NELAP	0.0019	0.0050		0.0071	mg/L	1	06/15/2023 14:21	206857
Magnesium	NELAP	0.0055	0.0500		30.1	mg/L	1	06/05/2023 16:59	206857
Molybdenum	NELAP	0.0037	0.0100		0.0411	mg/L	1	06/05/2023 16:59	206857
Potassium	NELAP	0.0400	0.100		9.45	mg/L	1	06/05/2023 16:59	206857
Sodium	NELAP	0.0180	0.0500		59.7	mg/L	1	06/05/2023 16:59	206857
<i>Sample result(s) for Si exceed 10 times the method blank contamination. Data is reportable per the TNI Standard.</i>									
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 16:12	206857
Cobalt	NELAP	0.0001	0.0010		0.0051	mg/L	5	06/05/2023 16:12	206857
Selenium	NELAP	0.0006	0.0010	J	0.0008	mg/L	5	06/05/2023 16:12	206857
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 16:12	206857



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-034
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-50
Collection Date: 05/31/2023 13:37

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 13:03	206869



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-035
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23

Client Sample ID: HEN-51

Collection Date: 05/31/2023 11:37

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		18.50	ft	1	05/31/2023 11:37	R329806
STANDARD METHODS 2130 B FIELD									
Turbidity	*	1.0	1.0		6.1	NTU	1	05/31/2023 11:37	R329806
STANDARD METHODS 18TH ED. 2580 B FIELD									
Oxidation-Reduction Potential	*	-300	-300		-135	mV	1	05/31/2023 11:37	R329806
STANDARD METHODS 2510 B FIELD									
Spec. Conductance, Field	*	0	0		1130	µS/cm	1	05/31/2023 11:37	R329806
STANDARD METHODS 2550 B FIELD									
Temperature	*	0	0		12.9	°C	1	05/31/2023 11:37	R329806
STANDARD METHODS 4500-O G FIELD									
Oxygen, Dissolved	*	0	0		1.50	mg/L	1	05/31/2023 11:37	R329806
SW-846 9040B FIELD									
pH	*	0	1.00		7.24		1	05/31/2023 11:37	R329806
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		356	mg/L	1	06/05/2023 16:57	R329791
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/05/2023 16:57	R329791
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	40	50		630	mg/L	2.5	06/05/2023 12:11	R329833
SW-846 9036 (TOTAL)									
Sulfate	NELAP	31	50		97	mg/L	5	06/02/2023 22:55	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10		0.11	mg/L	1	06/05/2023 12:24	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	2	20		109	mg/L	5	06/02/2023 22:55	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		0.0182	mg/L	1	06/05/2023 17:01	206857
Barium	NELAP	0.0007	0.0025		0.109	mg/L	1	06/05/2023 17:01	206857
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 17:01	206857
Boron	NELAP	0.0090	0.0200		1.63	mg/L	1	06/05/2023 17:01	206857
Cadmium	NELAP	0.0005	0.0020		< 0.0020	mg/L	1	06/05/2023 17:01	206857
Calcium	NELAP	0.0350	0.100		127	mg/L	1	06/05/2023 17:01	206857
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 17:01	206857
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 17:01	206857
Lithium	NELAP	0.0019	0.0050		0.0714	mg/L	1	06/15/2023 14:25	206857
Magnesium	NELAP	0.0055	0.0500		40.2	mg/L	1	06/05/2023 17:01	206857
Molybdenum	NELAP	0.0037	0.010	J	0.0067	mg/L	1	06/05/2023 17:01	206857
Potassium	NELAP	0.0400	0.100		6.65	mg/L	1	06/05/2023 17:01	206857
Sodium	NELAP	0.0180	0.0500		58.9	mg/L	1	06/05/2023 17:01	206857
<i>Sample result(s) for Si exceed 10 times the method blank contamination. Data is reportable per the TNI Standard.</i>									
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 16:17	206857
Cobalt	NELAP	0.0001	0.0010	J	0.0008	mg/L	5	06/05/2023 16:17	206857
Selenium	NELAP	0.0006	0.0010		< 0.0010	mg/L	5	06/05/2023 16:17	206857
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 16:17	206857



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-035
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-51
Collection Date: 05/31/2023 11:37

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 13:05	206869



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-043
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: HEN-YSG-ILRIVER
Collection Date: 05/30/2023 13:21

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS									
Depth to water from measuring point	*	0	0		440.50	ft	1	05/30/2023 13:21	R329806



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051600-044
Matrix: GROUNDWATER

Work Order: 23051600
Report Date: 21-Jun-23
Client Sample ID: Field Blank
Collection Date: 06/01/2023 8:22

Analyses	Certification	MDL	RL	Qual	Result	Units	DF	Date Analyzed	Batch
STANDARD METHODS 2320 B (TOTAL) 1997, 2011									
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0	0		1	mg/L	1	06/06/2023 10:50	R329835
STANDARD METHODS 2320 B 1997, 2011									
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0	0		0	mg/L	1	06/06/2023 10:50	R329835
STANDARD METHODS 2540 C (TOTAL) 1997, 2011									
Total Dissolved Solids	NELAP	16	20	J	18	mg/L	1	06/06/2023 11:43	R329904
SW-846 9036 (TOTAL)									
Sulfate	NELAP	6	10		< 10	mg/L	1	06/02/2023 23:09	R329716
SW-846 9214 (TOTAL)									
Fluoride	NELAP	0.04	0.10		< 0.10	mg/L	1	06/05/2023 11:01	R329756
SW-846 9251 (TOTAL)									
Chloride	NELAP	1	4		< 4	mg/L	1	06/02/2023 23:11	R329717
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)									
Arsenic	NELAP	0.0087	0.0100		< 0.0100	mg/L	1	06/05/2023 17:02	206857
Barium	NELAP	0.0007	0.0025		< 0.0025	mg/L	1	06/05/2023 17:02	206857
Beryllium	NELAP	0.0002	0.0005		< 0.0005	mg/L	1	06/05/2023 17:02	206857
Boron	NELAP	0.0090	0.0200		< 0.0200	mg/L	1	06/05/2023 17:02	206857
Cadmium	NELAP	0.0005	0.0020		< 0.0020	mg/L	1	06/05/2023 17:02	206857
Calcium	NELAP	0.035	0.10	J	0.044	mg/L	1	06/05/2023 17:02	206857
Chromium	NELAP	0.0028	0.0050		< 0.0050	mg/L	1	06/05/2023 17:02	206857
Lead	NELAP	0.0040	0.0075		< 0.0075	mg/L	1	06/05/2023 17:02	206857
Lithium	NELAP	0.0019	0.0050		< 0.0050	mg/L	1	06/15/2023 15:05	206857
Magnesium	NELAP	0.0055	0.050	J	0.025	mg/L	1	06/05/2023 17:02	206857
Molybdenum	NELAP	0.0037	0.0100		< 0.0100	mg/L	1	06/05/2023 17:02	206857
Potassium	NELAP	0.0400	0.100		< 0.100	mg/L	1	06/05/2023 17:02	206857
Sodium	NELAP	0.018	0.050	J	0.025	mg/L	1	06/05/2023 17:02	206857
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)									
Antimony	NELAP	0.0004	0.0010		< 0.0010	mg/L	5	06/05/2023 17:20	206857
Cobalt	NELAP	0.0001	0.0010		< 0.0010	mg/L	5	06/05/2023 17:20	206857
Selenium	NELAP	0.0006	0.0010		< 0.0010	mg/L	5	06/05/2023 17:20	206857
Thallium	NELAP	0.0010	0.0020		< 0.0020	mg/L	5	06/05/2023 17:20	206857
SW-846 7470A (TOTAL)									
Mercury	NELAP	0.00006	0.00020		< 0.00020	mg/L	1	06/05/2023 13:10	206869



Sample Summary

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

Lab Sample ID	Client Sample ID	Matrix	Fractions	Collection Date
23051600-015	HEN-21R	Groundwater	6	05/31/2023 11:09
23051600-016	HEN-22	Groundwater	6	05/31/2023 14:01
23051600-017	HEN-22&D	Groundwater	6	05/31/2023 14:19
23051600-018	HEN-23	Groundwater	6	05/31/2023 12:00
23051600-019	HEN-25	Groundwater	6	05/31/2023 12:59
23051600-020	HEN-26	Groundwater	6	05/31/2023 12:41
23051600-021	HEN-27	Groundwater	6	05/31/2023 9:15
23051600-022	HEN-30	Groundwater	1	05/30/2023 15:09
23051600-023	HEN-31	Groundwater	1	05/30/2023 15:09
23051600-024	HEN-32	Groundwater	6	05/31/2023 9:46
23051600-025	HEN-33	Groundwater	1	05/30/2023 15:15
23051600-026	HEN-34	Groundwater	6	05/31/2023 10:39
23051600-027	HEN-35	Groundwater	6	05/31/2023 10:09
23051600-028	HEN-36	Groundwater	1	05/30/2023 15:28
23051600-033	HEN-49	Groundwater	6	05/31/2023 12:19
23051600-034	HEN-50	Groundwater	6	05/31/2023 13:37
23051600-035	HEN-51	Groundwater	6	05/31/2023 11:37
23051600-043	HEN-YSG-ILRIVER	Groundwater	1	05/30/2023 13:21
23051600-044	Field Blank	Groundwater	10	06/01/2023 8:22



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
23051600-015A	HEN-21R	05/31/2023 11:09	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 11:09
	Field Elevation Measurements				05/31/2023 11:09
	Standard Methods 2130 B Field				05/31/2023 11:09
	Standard Methods 18th Ed. 2580 B Field				05/31/2023 11:09
	Standard Methods 2320 B (Total) 1997, 2011				06/05/2023 15:36
	Standard Methods 2320 B 1997, 2011				06/05/2023 15:36
	Standard Methods 2510 B Field				05/31/2023 11:09
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 11:19
	Standard Methods 2550 B Field				05/31/2023 11:09
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/01/2023 19:58
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 9:27
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 9:27
	Standard Methods 4500-O G Field				05/31/2023 11:09
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 16:55
	SW-846 9036 (Total)				06/02/2023 19:29
	SW-846 9040B Field				05/31/2023 11:09
	SW-846 9214 (Total)				06/05/2023 11:38
	SW-846 9251 (Total)				06/02/2023 19:30
23051600-015B	HEN-21R	05/31/2023 11:09	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:14
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:14
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/01/2023 19:50
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 9:18
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 9:18
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 17:56
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 13:08
	SW-846 9251 (Dissolved)				06/02/2023 13:09
23051600-015C	HEN-21R	05/31/2023 11:09	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/05/2023 17:46
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/07/2023 9:21
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/15/2023 10:59
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:35	06/05/2023 19:00
	SW-846 7470A (Total)			06/02/2023 8:28	06/05/2023 10:52
23051600-015D	HEN-21R	05/31/2023 11:09	06/01/2023 12:08		



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:34	06/07/2023 11:51
23051600-015E	HEN-21R	05/31/2023 11:09	06/01/2023 12:08		
	SW-846 9060				06/08/2023 22:19
23051600-015F	HEN-21R	05/31/2023 11:09	06/01/2023 12:08		
	SW-846 9060				06/08/2023 15:21
23051600-016A	HEN-22	05/31/2023 14:01	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 14:01
	Field Elevation Measurements				05/31/2023 14:01
	Standard Methods 2130 B Field				05/31/2023 14:01
	Standard Methods 18th Ed. 2580 B Field				05/31/2023 14:01
	Standard Methods 2320 B (Total) 1997, 2011				06/05/2023 15:42
	Standard Methods 2320 B 1997, 2011				06/05/2023 15:42
	Standard Methods 2510 B Field				05/31/2023 14:01
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 11:19
	Standard Methods 2550 B Field				05/31/2023 14:01
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/02/2023 11:41
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 10:18
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 10:18
	Standard Methods 4500-O G Field				05/31/2023 14:01
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 16:55
	SW-846 9036 (Total)				06/02/2023 19:36
	SW-846 9040B Field				05/31/2023 14:01
	SW-846 9214 (Total)				06/05/2023 11:41
	SW-846 9251 (Total)				06/02/2023 19:38
23051600-016B	HEN-22	05/31/2023 14:01	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:20
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:20
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/02/2023 11:42
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:15
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:15
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 18:45
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 13:15
	SW-846 9251 (Dissolved)				06/02/2023 13:17
23051600-016C	HEN-22	05/31/2023 14:01	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/05/2023 17:47



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Dates Report

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date	Test Name	Prep Date/Time	Analysis Date/Time
				SW-846 3005A, 6010B, Metals by ICP (Total)	06/01/2023 18:35	06/07/2023 9:22
				SW-846 3005A, 6010B, Metals by ICP (Total)	06/01/2023 18:35	06/08/2023 12:26
				SW-846 3005A, 6010B, Metals by ICP (Total)	06/01/2023 18:35	06/15/2023 11:02
				SW-846 3005A, 6020A, Metals by ICPMS (Total)	06/01/2023 18:35	06/05/2023 19:05
				SW-846 7470A (Total)	06/02/2023 8:28	06/05/2023 10:54
23051600-016D	HEN-22	05/31/2023 14:01	06/01/2023 12:08			
				SW-846 3005A, 6010B, Metals by ICP (Dissolved)	06/02/2023 8:34	06/07/2023 11:52
				SW-846 3005A, 6010B, Metals by ICP (Dissolved)	06/02/2023 8:34	06/08/2023 12:27
23051600-016E	HEN-22	05/31/2023 14:01	06/01/2023 12:08			
				SW-846 9060		06/08/2023 22:26
23051600-016F	HEN-22	05/31/2023 14:01	06/01/2023 12:08			
				SW-846 9060		06/08/2023 15:27
23051600-017A	HEN-22&D	05/31/2023 14:19	06/01/2023 12:08			
				Ferrous Iron by CHEMets Kit		05/31/2023 14:19
				Field Elevation Measurements		05/31/2023 14:19
				Standard Methods 2130 B Field		05/31/2023 14:19
				Standard Methods 18th Ed. 2580 B Field		05/31/2023 14:19
				Standard Methods 2320 B (Total) 1997, 2011		06/05/2023 16:00
				Standard Methods 2320 B 1997, 2011		06/05/2023 16:00
				Standard Methods 2510 B Field		05/31/2023 14:19
				Standard Methods 2540 C (Total) 1997, 2011		06/05/2023 11:20
				Standard Methods 2550 B Field		05/31/2023 14:19
				Standard Methods 4500-NO2 B (Total) 2000, 2011		06/02/2023 11:43
				Standard Methods 4500-NO3 F (Total) 2000, 2011		06/02/2023 10:33
				Standard Methods 4500-NO3 F (Total) 2000, 2011		06/02/2023 10:33
				Standard Methods 4500-O G Field		05/31/2023 14:19
				Standard Methods 4500-P E 1999		06/01/2023 16:00
				Standard Methods 4500-P E 1999, 2011		06/01/2023 16:57
				SW-846 9036 (Total)		06/02/2023 19:45
				SW-846 9040B Field		05/31/2023 14:19
				SW-846 9214 (Total)		06/05/2023 11:42
				SW-846 9251 (Total)		06/02/2023 19:46
23051600-017B	HEN-22&D	05/31/2023 14:19	06/01/2023 12:08			
				Standard Methods 2320 B (Dissolved) 1997, 2011		06/05/2023 11:38
				Standard Methods 2320 B (Dissolved) 1997, 2011		06/05/2023 11:38
				Standard Methods 4500-NO2 B (Dissolved) 2000, 2011		06/02/2023 11:43
				Standard Methods 4500-NO3 F (Dissolved) 2000, 2011		06/02/2023 11:17



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:17
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 18:45
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 13:40
	SW-846 9251 (Dissolved)				06/02/2023 13:41
23051600-017C	HEN-22&D	05/31/2023 14:19	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/05/2023 17:47
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/07/2023 9:23
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/15/2023 11:06
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:35	06/05/2023 19:11
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 12:29
23051600-017D	HEN-22&D	05/31/2023 14:19	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:34	06/07/2023 11:53
23051600-017E	HEN-22&D	05/31/2023 14:19	06/01/2023 12:08		
	SW-846 9060				06/08/2023 22:32
23051600-017F	HEN-22&D	05/31/2023 14:19	06/01/2023 12:08		
	SW-846 9060				06/08/2023 15:34
23051600-018A	HEN-23	05/31/2023 12:00	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 12:00
	Field Elevation Measurements				05/31/2023 12:00
	Standard Methods 2130 B Field				05/31/2023 12:00
	Standard Methods 18th Ed. 2580 B Field				05/31/2023 12:00
	Standard Methods 2320 B (Total) 1997, 2011				06/05/2023 16:08
	Standard Methods 2320 B 1997, 2011				06/05/2023 16:08
	Standard Methods 2510 B Field				05/31/2023 12:00
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 11:20
	Standard Methods 2550 B Field				05/31/2023 12:00
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/01/2023 19:58
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 9:56
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 9:56
	Standard Methods 4500-O G Field				05/31/2023 12:00
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 16:57
	SW-846 9036 (Total)				06/02/2023 20:15
	SW-846 9040B Field				05/31/2023 12:00
	SW-846 9214 (Total)				06/05/2023 11:53
	SW-846 9251 (Total)				06/02/2023 20:10



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
23051600-018B	HEN-23	05/31/2023 12:00	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:44
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:44
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/01/2023 19:51
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:26
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:26
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 18:24
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 14:07
	SW-846 9251 (Dissolved)				06/02/2023 14:02
23051600-018C	HEN-23	05/31/2023 12:00	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/05/2023 17:52
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/07/2023 9:23
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/14/2023 20:27
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:35	06/05/2023 19:53
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 12:31
23051600-018D	HEN-23	05/31/2023 12:00	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:34	06/07/2023 11:53
23051600-018E	HEN-23	05/31/2023 12:00	06/01/2023 12:08		
	SW-846 9060				06/08/2023 22:38
23051600-018F	HEN-23	05/31/2023 12:00	06/01/2023 12:08		
	SW-846 9060				06/08/2023 17:02
23051600-019A	HEN-25	05/31/2023 12:59	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 12:59
	Field Elevation Measurements				05/31/2023 12:59
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 11:21
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/02/2023 11:44
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 12:01
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 12:01
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 16:58
	SW-846 9036 (Total)				06/06/2023 23:22
	SW-846 9040B Field				05/31/2023 12:59
	SW-846 9214 (Total)				06/05/2023 11:56
	SW-846 9251 (Total)				06/02/2023 20:23
23051600-019B	HEN-25	05/31/2023 12:59	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:49



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:49
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/02/2023 11:45
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:19
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:19
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 18:46
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/04/2023 1:59
	SW-846 9251 (Dissolved)				06/02/2023 14:15
23051600-019C	HEN-25	05/31/2023 12:59	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/05/2023 17:52
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/07/2023 9:24
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/15/2023 11:45
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:35	06/05/2023 19:58
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 12:34
23051600-019D	HEN-25	05/31/2023 12:59	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:34	06/07/2023 11:54
23051600-019E	HEN-25	05/31/2023 12:59	06/01/2023 12:08		
	SW-846 9060				06/08/2023 23:29
23051600-019F	HEN-25	05/31/2023 12:59	06/01/2023 12:08		
	SW-846 9060				06/08/2023 17:09
23051600-020A	HEN-26	05/31/2023 12:41	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 12:41
	Field Elevation Measurements				05/31/2023 12:41
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 11:21
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/02/2023 11:47
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 10:38
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 10:38
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 16:58
	SW-846 9036 (Total)				06/02/2023 20:31
	SW-846 9040B Field				05/31/2023 12:41
	SW-846 9214 (Total)				06/05/2023 11:58
	SW-846 9251 (Total)				06/02/2023 20:31
23051600-020B	HEN-26	05/31/2023 12:41	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:54
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:54
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/02/2023 11:48



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:22
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:22
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 18:46
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 14:39
	SW-846 9251 (Dissolved)				06/02/2023 14:39
23051600-020C	HEN-26	05/31/2023 12:41	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/05/2023 17:53
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/07/2023 9:35
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/15/2023 11:49
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:35	06/05/2023 20:03
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 12:40
23051600-020D	HEN-26	05/31/2023 12:41	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:34	06/07/2023 11:55
23051600-020E	HEN-26	05/31/2023 12:41	06/01/2023 12:08		
	SW-846 9060				06/08/2023 23:35
23051600-020F	HEN-26	05/31/2023 12:41	06/01/2023 12:08		
	SW-846 9060				06/08/2023 17:15
23051600-021A	HEN-27	05/31/2023 9:15	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 9:15
	Field Elevation Measurements				05/31/2023 9:15
	Standard Methods 2130 B Field				05/31/2023 9:15
	Standard Methods 18th Ed. 2580 B Field				05/31/2023 9:15
	Standard Methods 2320 B (Total) 1997, 2011				06/05/2023 17:17
	Standard Methods 2320 B 1997, 2011				06/05/2023 17:17
	Standard Methods 2510 B Field				05/31/2023 9:15
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 11:21
	Standard Methods 2550 B Field				05/31/2023 9:15
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/01/2023 19:59
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 8:21
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 8:21
	Standard Methods 4500-O G Field				05/31/2023 9:15
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 16:59
	SW-846 9036 (Total)				06/02/2023 20:36
	SW-846 9040B Field				05/31/2023 9:15
	SW-846 9214 (Total)				06/05/2023 12:00



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
Test Name					
	SW-846 9251 (Total)				06/02/2023 20:36
23051600-021B	HEN-27	05/31/2023 9:15	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 12:00
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 12:00
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/01/2023 19:52
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 8:06
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 8:06
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 17:58
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 14:41
	SW-846 9251 (Dissolved)				06/02/2023 14:42
23051600-021C	HEN-27	05/31/2023 9:15	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/05/2023 17:54
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/07/2023 9:36
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/15/2023 11:53
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:35	06/05/2023 20:09
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 12:43
23051600-021D	HEN-27	05/31/2023 9:15	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:34	06/07/2023 11:55
23051600-021E	HEN-27	05/31/2023 9:15	06/01/2023 12:08		
	SW-846 9060				06/08/2023 23:41
23051600-021F	HEN-27	05/31/2023 9:15	06/01/2023 12:08		
	SW-846 9060				06/08/2023 17:21
23051600-022A	HEN-30	05/30/2023 15:09	06/01/2023 12:08		
	Field Elevation Measurements				05/30/2023 15:09
23051600-023A	HEN-31	05/30/2023 15:09	06/01/2023 12:08		
	Field Elevation Measurements				05/30/2023 15:09
23051600-024A	HEN-32	05/31/2023 9:46	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 9:46
	Field Elevation Measurements				05/31/2023 9:46
	Standard Methods 2130 B Field				05/31/2023 9:46
	Standard Methods 18th Ed. 2580 B Field				05/31/2023 9:46
	Standard Methods 2320 B (Total) 1997, 2011				06/05/2023 17:24
	Standard Methods 2320 B 1997, 2011				06/05/2023 17:24
	Standard Methods 2510 B Field				05/31/2023 9:46
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 11:22
	Standard Methods 2550 B Field				05/31/2023 9:46



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/01/2023 19:59
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 8:24
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 8:24
	Standard Methods 4500-O G Field				05/31/2023 9:46
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 16:59
	SW-846 9036 (Total)				06/02/2023 21:13
	SW-846 9040B Field				05/31/2023 9:46
	SW-846 9214 (Total)				06/05/2023 12:02
	SW-846 9251 (Total)				06/02/2023 21:14
23051600-024B	HEN-32	05/31/2023 9:46	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:27
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 11:27
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/01/2023 19:52
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 8:08
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 8:08
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 17:58
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 14:50
	SW-846 9251 (Dissolved)				06/02/2023 14:50
23051600-024C	HEN-32	05/31/2023 9:46	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/05/2023 17:55
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/07/2023 9:37
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/14/2023 20:41
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:35	06/05/2023 20:30
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 12:45
23051600-024D	HEN-32	05/31/2023 9:46	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:34	06/07/2023 12:08
23051600-024E	HEN-32	05/31/2023 9:46	06/01/2023 12:08		
	SW-846 9060				06/08/2023 23:48
23051600-024F	HEN-32	05/31/2023 9:46	06/01/2023 12:08		
	SW-846 9060				06/08/2023 17:28
23051600-025A	HEN-33	05/30/2023 15:15	06/01/2023 12:08		
	Field Elevation Measurements				05/30/2023 15:15
23051600-026A	HEN-34	05/31/2023 10:39	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 10:39
	Field Elevation Measurements				05/31/2023 10:39



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	Standard Methods 2130 B Field				05/31/2023 10:39
	Standard Methods 18th Ed. 2580 B Field				05/31/2023 10:39
	Standard Methods 2320 B (Total) 1997, 2011				06/05/2023 16:19
	Standard Methods 2320 B 1997, 2011				06/05/2023 16:19
	Standard Methods 2510 B Field				05/31/2023 10:39
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 12:07
	Standard Methods 2550 B Field				05/31/2023 10:39
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/01/2023 19:59
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 8:48
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 8:48
	Standard Methods 4500-O G Field				05/31/2023 10:39
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 17:24
	SW-846 9036 (Total)				06/02/2023 21:21
	SW-846 9040B Field				05/31/2023 10:39
	SW-846 9214 (Total)				06/05/2023 12:04
	SW-846 9251 (Total)				06/02/2023 21:22
23051600-026B	HEN-34	05/31/2023 10:39	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 12:06
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 12:06
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/01/2023 19:53
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 8:41
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 8:41
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 17:59
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 14:58
	SW-846 9251 (Dissolved)				06/02/2023 14:58
23051600-026C	HEN-34	05/31/2023 10:39	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/05/2023 17:57
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/07/2023 9:39
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/14/2023 20:52
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:35	06/05/2023 20:14
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 12:47
23051600-026D	HEN-34	05/31/2023 10:39	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:34	06/07/2023 12:08
23051600-026E	HEN-34	05/31/2023 10:39	06/01/2023 12:08		
	SW-846 9060				06/09/2023 0:07



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
23051600-026F	HEN-34	05/31/2023 10:39	06/01/2023 12:08		
	SW-846 9060				06/08/2023 17:47
23051600-027A	HEN-35	05/31/2023 10:09	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 10:09
	Field Elevation Measurements				05/31/2023 10:09
	Standard Methods 2130 B Field				05/31/2023 10:09
	Standard Methods 18th Ed. 2580 B Field				05/31/2023 10:09
	Standard Methods 2320 B (Total) 1997, 2011				06/05/2023 16:26
	Standard Methods 2320 B 1997, 2011				06/05/2023 16:26
	Standard Methods 2510 B Field				05/31/2023 10:09
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 12:08
	Standard Methods 2550 B Field				05/31/2023 10:09
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/01/2023 20:00
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 8:50
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 8:50
	Standard Methods 4500-O G Field				05/31/2023 10:09
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 17:25
	SW-846 9036 (Total)				06/02/2023 21:34
	SW-846 9040B Field				05/31/2023 10:09
	SW-846 9214 (Total)				06/05/2023 12:06
	SW-846 9251 (Total)				06/02/2023 21:30
23051600-027B	HEN-35	05/31/2023 10:09	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 12:14
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 12:14
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/01/2023 19:53
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 8:43
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 8:43
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 18:00
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/04/2023 2:01
	SW-846 9251 (Dissolved)				06/02/2023 15:06
23051600-027C	HEN-35	05/31/2023 10:09	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/05/2023 17:58
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/07/2023 9:40
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/08/2023 12:26
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:35	06/15/2023 11:56



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Dates Report

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:35	06/05/2023 20:19
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 12:54
23051600-027D	HEN-35	05/31/2023 10:09	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:34	06/07/2023 12:09
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:34	06/08/2023 12:28
23051600-027E	HEN-35	05/31/2023 10:09	06/01/2023 12:08		
	SW-846 9060				06/12/2023 13:24
23051600-027F	HEN-35	05/31/2023 10:09	06/01/2023 12:08		
	SW-846 9060				06/08/2023 17:53
23051600-028A	HEN-36	05/30/2023 15:28	06/01/2023 12:08		
	Field Elevation Measurements				05/30/2023 15:28
23051600-033A	HEN-49	05/31/2023 12:19	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 12:19
	Field Elevation Measurements				05/31/2023 12:19
	Standard Methods 2130 B Field				05/31/2023 12:19
	Standard Methods 18th Ed. 2580 B Field				05/31/2023 12:19
	Standard Methods 2320 B (Total) 1997, 2011				06/05/2023 16:44
	Standard Methods 2320 B 1997, 2011				06/05/2023 16:44
	Standard Methods 2510 B Field				05/31/2023 12:19
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 12:10
	Standard Methods 2550 B Field				05/31/2023 12:19
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/02/2023 11:49
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 10:40
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 10:40
	Standard Methods 4500-O G Field				05/31/2023 12:19
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 17:27
	SW-846 9036 (Total)				06/02/2023 22:09
	SW-846 9040B Field				05/31/2023 12:19
	SW-846 9214 (Total)				06/05/2023 12:19
	SW-846 9251 (Total)				06/02/2023 22:10
23051600-033B	HEN-49	05/31/2023 12:19	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 12:31
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 12:31
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/01/2023 19:54
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:28
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 11:28



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 18:24
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 15:46
	SW-846 9251 (Dissolved)				06/02/2023 15:46
23051600-033C	HEN-49	05/31/2023 12:19	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:36	06/05/2023 16:58
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:36	06/09/2023 11:08
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:36	06/09/2023 11:50
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:36	06/15/2023 14:17
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:36	06/05/2023 14:53
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 13:01
23051600-033D	HEN-49	05/31/2023 12:19	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:42	06/06/2023 16:14
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:42	06/07/2023 9:48
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:42	06/08/2023 11:52
23051600-033E	HEN-49	05/31/2023 12:19	06/01/2023 12:08		
	SW-846 9060				06/09/2023 1:23
23051600-033F	HEN-49	05/31/2023 12:19	06/01/2023 12:08		
	SW-846 9060				06/08/2023 18:50
23051600-034A	HEN-50	05/31/2023 13:37	06/01/2023 12:08		
	Ferrous Iron by CHEMets Kit				05/31/2023 13:37
	Field Elevation Measurements				05/31/2023 13:37
	Standard Methods 2130 B Field				05/31/2023 13:37
	Standard Methods 18th Ed. 2580 B Field				05/31/2023 13:37
	Standard Methods 2320 B (Total) 1997, 2011				06/05/2023 16:51
	Standard Methods 2320 B 1997, 2011				06/05/2023 16:51
	Standard Methods 2510 B Field				05/31/2023 13:37
	Standard Methods 2540 C (Total) 1997, 2011				06/05/2023 12:10
	Standard Methods 2550 B Field				05/31/2023 13:37
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/02/2023 11:50
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 12:03
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 12:03
	Standard Methods 4500-O G Field				05/31/2023 13:37
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 17:28
	SW-846 9036 (Total)				06/02/2023 22:20
	SW-846 9040B Field				05/31/2023 13:37



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date	Test Name	Prep Date/Time	Analysis Date/Time
				SW-846 9214 (Total)		06/05/2023 12:22
				SW-846 9251 (Total)		06/02/2023 22:20
23051600-034B	HEN-50	05/31/2023 13:37	06/01/2023 12:08	Standard Methods 2320 B (Dissolved) 1997, 2011		06/05/2023 12:37
				Standard Methods 2320 B (Dissolved) 1997, 2011		06/05/2023 12:37
				Standard Methods 4500-NO2 B (Dissolved) 2000, 2011		06/02/2023 11:51
				Standard Methods 4500-NO3 F (Dissolved) 2000, 2011		06/02/2023 11:24
				Standard Methods 4500-NO3 F (Dissolved) 2000, 2011		06/02/2023 11:24
				Standard Methods 4500-P E (Dissolved) 1999, 2011		06/01/2023 18:25
				Standard Methods 4500-P E (Dissolved) 1999		06/01/2023 16:00
				SW-846 9036 (Dissolved)		06/02/2023 15:56
				SW-846 9251 (Dissolved)		06/02/2023 15:57
23051600-034C	HEN-50	05/31/2023 13:37	06/01/2023 12:08	SW-846 3005A, 6010B, Metals by ICP (Total)	06/01/2023 18:36	06/05/2023 16:59
				SW-846 3005A, 6010B, Metals by ICP (Total)	06/01/2023 18:36	06/09/2023 11:51
				SW-846 3005A, 6010B, Metals by ICP (Total)	06/01/2023 18:36	06/15/2023 14:21
				SW-846 3005A, 6020A, Metals by ICPMS (Total)	06/01/2023 18:36	06/05/2023 16:12
				SW-846 7470A (Total)	06/02/2023 8:31	06/05/2023 13:03
23051600-034D	HEN-50	05/31/2023 13:37	06/01/2023 12:08	SW-846 3005A, 6010B, Metals by ICP (Dissolved)	06/02/2023 8:42	06/06/2023 16:15
				SW-846 3005A, 6010B, Metals by ICP (Dissolved)	06/02/2023 8:42	06/07/2023 9:49
23051600-034E	HEN-50	05/31/2023 13:37	06/01/2023 12:08	SW-846 9060		06/09/2023 1:29
23051600-034F	HEN-50	05/31/2023 13:37	06/01/2023 12:08	SW-846 9060		06/08/2023 18:56
23051600-035A	HEN-51	05/31/2023 11:37	06/01/2023 12:08	Ferrous Iron by CHEMets Kit		05/31/2023 11:37
				Field Elevation Measurements		05/31/2023 11:37
				Standard Methods 2130 B Field		05/31/2023 11:37
				Standard Methods 18th Ed. 2580 B Field		05/31/2023 11:37
				Standard Methods 2320 B (Total) 1997, 2011		06/05/2023 16:57
				Standard Methods 2320 B 1997, 2011		06/05/2023 16:57
				Standard Methods 2510 B Field		05/31/2023 11:37
				Standard Methods 2540 C (Total) 1997, 2011		06/05/2023 12:11
				Standard Methods 2550 B Field		05/31/2023 11:37
				Standard Methods 4500-NO2 B (Total) 2000, 2011		06/01/2023 20:02
				Standard Methods 4500-NO3 F (Total) 2000, 2011		06/02/2023 9:32



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 9:32
	Standard Methods 4500-O G Field				05/31/2023 11:37
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 17:29
	SW-846 9036 (Total)				06/02/2023 22:55
	SW-846 9040B Field				05/31/2023 11:37
	SW-846 9214 (Total)				06/05/2023 12:24
	SW-846 9251 (Total)				06/02/2023 22:55
23051600-035B	HEN-51	05/31/2023 11:37	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 12:43
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/05/2023 12:43
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/01/2023 19:55
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 9:22
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 9:22
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 18:25
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 16:34
	SW-846 9251 (Dissolved)				06/02/2023 16:34
23051600-035C	HEN-51	05/31/2023 11:37	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:36	06/05/2023 17:01
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:36	06/09/2023 11:53
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:36	06/15/2023 14:25
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:36	06/05/2023 16:17
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 13:05
23051600-035D	HEN-51	05/31/2023 11:37	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:42	06/06/2023 16:16
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:42	06/07/2023 9:49
23051600-035E	HEN-51	05/31/2023 11:37	06/01/2023 12:08		
	SW-846 9060				06/09/2023 1:35
23051600-035F	HEN-51	05/31/2023 11:37	06/01/2023 12:08		
	SW-846 9060				06/08/2023 19:03
23051600-043A	HEN-YSG-ILRIVER	05/30/2023 13:21	06/01/2023 12:08		
	Field Elevation Measurements				05/30/2023 13:21
23051600-044A	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	Standard Methods 2320 B 1997, 2011				06/06/2023 10:50
	Standard Methods 2320 B (Total) 1997, 2011				06/06/2023 10:50
	Standard Methods 2320 B 1997, 2011				06/06/2023 10:50



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	Standard Methods 2540 C (Total) 1997, 2011				06/06/2023 11:43
	Standard Methods 4500-NO2 B (Total) 2000, 2011				06/02/2023 11:52
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 10:44
	Standard Methods 4500-NO3 F (Total) 2000, 2011				06/02/2023 10:44
	Standard Methods 4500-P E 1999				06/01/2023 16:00
	Standard Methods 4500-P E 1999, 2011				06/01/2023 17:30
	SW-846 9036 (Total)				06/02/2023 23:09
	SW-846 9214 (Total)				06/05/2023 11:01
	SW-846 9251 (Total)				06/02/2023 23:11
23051600-044B	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	EPA 314.0				06/14/2023 17:15
23051600-044C	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/06/2023 10:53
	Standard Methods 2320 B (Dissolved) 1997, 2011				06/06/2023 10:53
	Standard Methods 4500-NO2 B (Dissolved) 2000, 2011				06/02/2023 11:52
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 10:46
	Standard Methods 4500-NO3 F (Dissolved) 2000, 2011				06/02/2023 10:46
	Standard Methods 4500-P E (Dissolved) 1999, 2011				06/01/2023 18:26
	Standard Methods 4500-P E (Dissolved) 1999				06/01/2023 16:00
	SW-846 9036 (Dissolved)				06/02/2023 16:49
	SW-846 9214 (Dissolved)				06/05/2023 11:04
	SW-846 9251 (Dissolved)				06/02/2023 16:50
23051600-044D	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:36	06/05/2023 17:02
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/12/2023 17:15	06/14/2023 17:41
	SW-846 3005A, 6010B, Metals by ICP (Total)			06/01/2023 18:36	06/15/2023 15:05
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			06/01/2023 18:36	06/05/2023 17:20
	SW-846 7470A (Total)			06/02/2023 8:31	06/05/2023 13:10
23051600-044E	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:42	06/06/2023 16:20
	SW-846 3005A, 6010B, Metals by ICP (Dissolved)			06/02/2023 8:42	06/07/2023 9:55
	SW-846 3005A, 6020A, Metals by ICPMS (Dissolved)			06/02/2023 8:42	06/05/2023 16:22
	SW-846 7470A (Dissolved)			06/02/2023 8:31	06/05/2023 13:12
23051600-044F	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	SW-846 9012A (Total)			06/02/2023 17:45	06/05/2023 15:08
23051600-044G	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	SW-846 9060				06/12/2023 13:31



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
	Test Name				
	SW-846 9066 (Total)				06/06/2023 10:52
23051600-044H	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	SW-846 9060				06/08/2023 20:25
23051600-044I	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	Standard Methods 4500-NH3 G (Total) 1997, 2011				06/05/2023 10:33
23051600-044J	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	SW-846 5030, 8260B, Volatile Organic Compounds by GC/MS				06/01/2023 20:52



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

STANDARD METHODS 2510 B FIELD

Batch R329806		SampType: LCS		Units $\mu\text{S/cm}$							
SampID: LCS-R329806											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Spec. Conductance, Field	*	0		1430	1412	0	101.2	90	110	05/31/2023	
Spec. Conductance, Field	*	0		1410	1412	0	100.1	90	110	05/31/2023	
Spec. Conductance, Field	*	0		1410	1412	0	100.1	90	110	06/01/2023	
Spec. Conductance, Field	*	0		1410	1412	0	100.1	90	110	06/01/2023	

SW-846 9040B FIELD

Batch R329806		SampType: LCS		Units						
SampID: LCS-R329806										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
pH	*	1.00		7.09	7.000	0	101.3	98.57	101.4	05/31/2023
pH	*	1.00		7.08	7.000	0	101.1	98.57	101.4	05/31/2023
pH	*	1.00		7.10	7.000	0	101.4	98.57	101.4	06/01/2023
pH	*	1.00		7.07	7.000	0	101.0	98.57	101.4	06/01/2023

STANDARD METHODS 2320 B 1997, 2011

Batch R329791		SampType: MBLK		Units mg/L							
SampID: MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Alkalinity, Total (as CaCO3)		0		0						06/05/2023	

Batch R329791		SampType: LCS		Units mg/L							
SampID: LCS											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Alkalinity, Total (as CaCO3)		0		232	233.0	0	99.6	90	110	06/05/2023	

Batch R329835		SampType: MBLK		Units mg/L							
SampID: MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Alkalinity, Total (as CaCO3)		0		0						06/06/2023	

Batch R329835		SampType: LCS		Units mg/L							
SampID: LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Alkalinity, Total (as CaCO3)		0		235	233.0	0	100.9	90	110	06/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

STANDARD METHODS 2540 C (TOTAL) 1997, 2011

Batch R329833		SampType: MBLK		Units mg/L							
SampID: MBLK											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Total Dissolved Solids		20		< 20	16.00	0	0	-100	100	06/05/2023	
Total Dissolved Solids		20		< 20	16.00	0	0	-100	100	06/05/2023	

Batch R329833		SampType: LCS		Units mg/L							Date Analyzed	
SampID: LCS												
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			
Total Dissolved Solids		20		906	1000	0	90.6	90	110			
Total Dissolved Solids		20		926	1000	0	92.6	90	110			

Batch R329833		SampType: DUP		Units mg/L							RPD Limit: 10		Date Analyzed
SampID: 23051600-017ADUP													
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Total Dissolved Solids			50		615				640.0	3.98			
												06/05/2023	

Batch R329833		SampType: DUP		Units mg/L					RPD Limit: 10		
SampID: 23051600-031ADUP											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Total Dissolved Solids			20		492				464.0	5.86	06/05/2023

Batch R329904		SampType: MBLK		Units mg/L							
SampID: MBLK		Date Analyzed									
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Total Dissolved Solids			20		< 20	16.00	0	0	-100	100	
06/06/2023											

Batch R329904		SampType: LCS		Units mg/L							
SampID: LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Total Dissolved Solids		20		948	1000	0	94.8	90	110	06/06/2023	

Batch R329904		SampType: DUP		Units mg/L							RPD Limit: 10		Date Analyzed
SampID: 23051600-039ADUP													
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Total Dissolved Solids			20		588				538.0	8.88			



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

STANDARD METHODS 4500-NH3 G (TOTAL) 1997, 2011

Batch R329804 SampType: MBLK Units mg/L

SampID: ICB/MBLK

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Ammonia (as N)		0.10		< 0.10	0.0270	0	0	-100	100	06/05/2023

Batch R329804 SampType: LCS Units mg/L

SampID: ICB/LCS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Ammonia (as N)		0.10		1.05	1.000	0	104.7	90	110	06/05/2023

Batch R329804 SampType: MS Units mg/L

SampID: 23051600-009HMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Ammonia (as N)		0.10		1.83	2.000	0	91.6	90	110	06/05/2023

Batch R329804 SampType: MSD Units mg/L

RPD Limit: 10

SampID: 23051600-009HMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Ammonia (as N)		0.10		1.83	2.000	0	91.4	1.832	0.16	06/05/2023

STANDARD METHODS 4500-NO2 B (DISSOLVED) 2000, 2011

Batch R329648 SampType: MS Units mg/L

SampID: 23051600-009BMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Nitrite (as N)		0.05		0.53	0.5000	0	105.8	85	115	06/01/2023

Batch R329648 SampType: MSD Units mg/L

RPD Limit: 10

SampID: 23051600-009BMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrite (as N)		0.05		0.53	0.5000	0	106.0	0.5290	0.19	06/01/2023

Batch R329648 SampType: MS Units mg/L

SampID: 23051600-010BMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Nitrite (as N)		0.05		0.53	0.5000	0	105.6	85	115	06/01/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

STANDARD METHODS 4500-NO2 B (DISSOLVED) 2000, 2011

Batch R329648		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed	
SampID: 23051600-010BMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Nitrogen, Nitrite (as N)			0.05		0.53	0.5000	0	105.8	0.5280	0.19	06/01/2023	

Batch R329648		SampType: MS		Units mg/L							
SampID: 23051600-014CMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrite (as N)		0.05		0.45	0.5000	0	89.8	85	115	06/02/2023	

Batch R329648		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed	
SampID: 23051600-014CMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Nitrogen, Nitrite (as N)			0.05		0.46	0.5000	0	92.2	0.4490	2.64	06/02/2023	

Batch R329648		SampType: MS		Units mg/L							
SampID: 23051600-015BMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Nitrogen, Nitrite (as N)		0.05		0.53	0.5000	0	105.2	85	115	06/01/2023	

Batch R329648		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed	
SampID: 23051600-015BMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Nitrogen, Nitrite (as N)			0.05		0.53	0.5000	0	105.2	0.5260	0.00	06/01/2023	

Batch R329713		SampType: MS		Units mg/L							Date Analyzed
SampID: 23051600-005CMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrite (as N)		0.05		0.52	0.5000	0	104.4	85	115	06/02/2023	

Batch R329713		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-005CMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrite (as N)			0.05		0.53	0.5000	0	105.8	0.5220	1.33	06/02/2023

Batch R329713		SampType: MS		Units mg/L							
SampID: 23051600-006CMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Nitrogen, Nitrite (as N)		0.05		0.70	0.5000	0.1790	103.8	85	115	06/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

STANDARD METHODS 4500-NO2 B (DISSOLVED) 2000, 2011

Batch R329713		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed
SampID: 23051600-006CMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Nitrogen, Nitrite (as N)			0.05		0.70	0.5000	0.1790	104.4	0.6980	0.43	06/02/2023

Batch R329713		SampType: MS		Units mg/L							
SampID: 23051600-011BMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrite (as N)		0.05		0.52	0.5000	0	105.0	85	115	06/02/2023	

Batch R329713		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed
SampID: 23051600-011BMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Nitrogen, Nitrite (as N)			0.05		0.52	0.5000	0	105.0	0.5250	0.00	06/02/2023

STANDARD METHODS 4500-NO2 B (TOTAL) 2000, 2011

Batch R329648		SampType: MBLK		Units mg/L							
SampID: MBLK											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Nitrite (as N)			0.05		< 0.05	0.0250	0	0	-100	100	06/01/2023

Batch R329648		SampType: LCS		Units mg/L							
SampID: LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Nitrogen, Nitrite (as N)		0.25		0.66	0.6510	0	102.2	90	110	06/01/2023	

Batch R329648		SampType: MS		Units mg/L							
SampID: 23051600-004AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Nitrogen, Nitrite (as N)		0.05		0.48	0.5000	0	95.4	85	115	06/02/2023	

Batch R329648		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-004AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrite (as N)			0.05	SR	0.42	0.5000	0	84.6	0.4770	12.00	06/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

STANDARD METHODS 4500-NO2 B (TOTAL) 2000, 2011

Batch R329648 SampType: MS Units mg/L

SampID: 23051600-033AMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Nitrite (as N)		0.05		0.49	0.5000	0	97.6	85	115	06/02/2023

Batch R329648 SampType: MSD Units mg/L

RPD Limit: 10

SampID: 23051600-033AMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrite (as N)		0.05		0.46	0.5000	0	92.8	0.4880	5.04	06/02/2023

Batch R329713 SampType: MBLK Units mg/L

SampID: MBLK

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Nitrite (as N)		0.05		< 0.05	0.0250	0	0	-100	100	06/02/2023

Batch R329713 SampType: LCS Units mg/L

SampID: LCS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Nitrite (as N)		0.25		0.68	0.6510	0	105.2	90	110	06/02/2023

STANDARD METHODS 4500-NO3 F (DISSOLVED) 2000, 2011

Batch R329727 SampType: MS Units mg/L

SampID: 23051600-002CMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Nitrate-Nitrite (as N)		0.500		4.98	2.500	2.705	90.9	85	115	06/02/2023

Batch R329727 SampType: MSD Units mg/L

RPD Limit: 10

SampID: 23051600-002CMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrate-Nitrite (as N)		0.500		5.03	2.500	2.705	92.9	4.977	1.02	06/02/2023

Batch R329727 SampType: MS Units mg/L

SampID: 23051600-032BMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Nitrogen, Nitrate-Nitrite (as N)		0.500		6.14	2.500	3.849	91.6	85	115	06/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

STANDARD METHODS 4500-NO3 F (DISSOLVED) 2000, 2011

Batch R329727		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-032BMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrate-Nitrite (as N)			0.500		6.11	2.500	3.849	90.5	6.140	0.46	06/02/2023

Batch R329727		SampType: MS		Units mg/L							
SampID: 23051600-036BMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Nitrogen, Nitrate-Nitrite (as N)		0.500		6.15	2.500	3.884	90.6	85	115	06/02/2023	

Batch R329727		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed
SampID: 23051600-036BMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Nitrogen, Nitrate-Nitrite (as N)			0.500		6.08	2.500	3.884	87.9	6.148	1.10	06/02/2023

Batch R329727		SampType: MS		Units mg/L							
SampleID: 23051600-040BMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Nitrogen, Nitrate-Nitrite (as N)		0.100		0.763	0.5000	0.2830	96.0	85	115	06/02/2023	

Batch R329727		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed
SampID: 23051600-040BMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Nitrogen, Nitrate-Nitrite (as N)			0.100		0.744	0.5000	0.2830	92.2	0.7630	2.52	06/02/2023

STANDARD METHODS 4500-NO3 F (TOTAL) 2000, 2011

Batch	R329727	SampType:	MBLK	Units mg/L								
SampID: ICB/MBLK												
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed		
Nitrogen, Nitrate (as N)		0.050		< 0.050						06/02/2023		
Nitrogen, Nitrate-Nitrite (as N)		0.050		< 0.050	0.0090	0	0	-100	100	06/02/2023		

Batch R329727		SampType: LCS		Units mg/L							
SampID: ICB/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Nitrogen, Nitrate-Nitrite (as N)		0.050		0.469	0.5000	0	93.8	90	110	06/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

STANDARD METHODS 4500-NO3 F (TOTAL) 2000, 2011

Batch R329727		SampType: MS		Units mg/L							Date
SampID: 23051600-007AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrate-Nitrite (as N)		1.00		13.8	5.000	9.093	94.9	85	115	06/02/2023	

Batch R329727		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-007AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrate-Nitrite (as N)			1.00		13.7	5.000	9.093	92.4	13.84	0.94	06/02/2023

Batch R329727		SampType: MS		Units mg/L							Date
SampID: 23051600-011AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrate-Nitrite (as N)		1.00		10.6	5.000	6.001	91.2	85	115	06/02/2023	

Batch R329727		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-011AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrate-Nitrite (as N)			1.00		10.4	5.000	6.001	88.0	10.56	1.52	06/02/2023

Batch R329727		SampType: MS		Units mg/L							Date
SampID: 23051600-027AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrate-Nitrite (as N)		0.250		4.14	1.250	2.934	96.4	85	115	06/02/2023	

Batch R329727		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-027AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrate-Nitrite (as N)			0.250	S	3.99	1.250	2.934	84.6	4.139	3.64	06/02/2023

Batch R329727		SampType: MS		Units mg/L							Date
SampID: 23051600-035AMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Nitrogen, Nitrate-Nitrite (as N)		0.050		0.245	0.2500	0.01700	91.2	85	115	06/02/2023	

Batch R329727		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-035AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Nitrogen, Nitrate-Nitrite (as N)			0.050		0.250	0.2500	0.01700	93.2	0.2450	2.02	06/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

STANDARD METHODS 4500-P E 1999, 2011

Batch	R329742	SampType:	MBLK	Units mg/L							
SampID: MBLK											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Phosphorus, Orthophosphate (as P)	*	0.010		< 0.010	0.0020	0	0	-100	100	06/01/2023	

Batch R329742		SampType: LCS		Units mg/L							
SampID: LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Phosphorus, Orthophosphate (as P)	*	0.010		0.107	0.1000	0	107.0	90	110	06/01/2023	

Batch R329742		SampType: MS		Units mg/L							
SampID: 23051600-002AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Phosphorus, Orthophosphate (as P)	*	0.010		0.061	0.0500	0.009000	104.0	85	115	06/01/2023	

Batch	R329742	SampType:	MSD	Units mg/L							RPD Limit: 10	
SampID: 23051600-002AMSD												
Analyses			Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Phosphorus, Orthophosphate (as P)			*	0.010		0.056	0.0500	0.009000	94.0	0.06100	8.55	06/01/2023

Batch R329742		SampType: MS		Units mg/L							
SampID: 23051600-007AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Phosphorus, Orthophosphate (as P)	*	0.010		0.080	0.0500	0.03000	100.0	85	115	06/01/2023	

Batch R329742		SampType: MSD	Units mg/L					RPD Limit: 10			
SampID: 23051600-007AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Phosphorus, Orthophosphate (as P)		*	0.010		0.083	0.0500	0.03000	106.0	0.08000	3.68	06/01/2023

Batch R329742		SampType: MS		Units mg/L							
SampID: 23051600-009AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Phosphorus, Orthophosphate (as P)	*	0.010		0.062	0.0500	0.01600	92.0	85	115	06/01/2023	

Batch R329742		SampType:	MSD		Units mg/L				RPD Limit: 10		
SampID: 23051600-009AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Phosphorus, Orthophosphate (as P)		*	0.010		0.061	0.0500	0.01600	90.0	0.06200	1.63	06/01/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

STANDARD METHODS 4500-P E 1999, 2011

Batch R329742		SampType: MS		Units mg/L							
SampID: 23051600-010AMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Phosphorus, Orthophosphate (as P)	*	0.010		0.049	0.0500	0	98.0	85	115	06/01/2023	

Batch R329742		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-010AMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Phosphorus, Orthophosphate (as P)	*	0.010		0.054	0.0500	0	108.0	0.04900	9.71	06/01/2023	

Batch R329742		SampType: MS		Units mg/L							
SampID: 23051600-013AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Phosphorus, Orthophosphate (as P)	*	0.010		0.067	0.0500	0.01600	102.0	85	115	06/01/2023	

Batch R329742		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-013AMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Phosphorus, Orthophosphate (as P)	*	0.010		0.062	0.0500	0.01600	92.0	0.06700	7.75	06/01/2023	

Batch R329742		SampType: MS		Units mg/L							
SampID: 23051600-014AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Phosphorus, Orthophosphate (as P)	*	0.010		0.113	0.0500	0.05900	108.0	85	115	06/01/2023	

Batch R329742		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-014AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Phosphorus, Orthophosphate (as P)		*	0.010		0.116	0.0500	0.05900	114.0	0.1130	2.62	06/01/2023

Batch R329746		SampType: MBLK		Units mg/L							
SampID: MBLK											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Phosphorus, Orthophosphate (as P)		*	0.010		< 0.010	0.0020	0	0	-100	100	06/02/2023

Batch R329746		SampType: LCS		Units mg/L							
SampID: LCS											Date Analyzed
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Phosphorus, Orthophosphate (as P)		*	0.010		0.103	0.1000	0	103.0	90	110	06/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

STANDARD METHODS 4500-P E 1999, 2011

Batch R329746 SampType: MS Units mg/L

SampleID: 23051600-005AMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Phosphorus, Orthophosphate (as P)	*	0.010	S	0.047	0.0500	0.02000	54.0	85	115	06/02/2023

Batch R329746 SampType: MSD Units mg/L

RPD Limit: 10

SampleID: 23051600-005AMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Phosphorus, Orthophosphate (as P)	*	0.010	SR	0.052	0.0500	0.02000	64.0	0.04700	10.10	06/02/2023

Batch R329746 SampType: MS Units mg/L

SampleID: 23051600-006AMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Phosphorus, Orthophosphate (as P)	*	0.010		0.044	0.0500	0	88.0	85	115	06/02/2023

Batch R329746 SampType: MSD Units mg/L

RPD Limit: 10

SampleID: 23051600-006AMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Phosphorus, Orthophosphate (as P)	*	0.010		0.048	0.0500	0	96.0	0.04400	8.70	06/02/2023

SW-846 9012A (TOTAL)

Batch 206887 SampType: MBLK Units mg/L

SampleID: MBLK 230602 TCN1

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Cyanide		0.005		< 0.005	0.0015	0	0	-100	100	06/05/2023

Batch 206887 SampType: LCS Units mg/L

SampleID: LCS 230602 TCN1

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Cyanide		0.005		0.027	0.0250	0	106.7	90	110	06/05/2023

Batch 206887 SampType: MS Units mg/L

SampleID: 23051600-001EMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Cyanide		0.005		0.033	0.0250	0.006700	104.9	75	125	06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9012A (TOTAL)

Batch 206887		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23051600-001EMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Cyanide		0.005		0.031	0.0250	0.006700	97.2	0.03292	6.04	06/05/2023	

Batch 206887		SampType: MS		Units mg/L							
SampID: 23051600-010EMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Cyanide		0.005		0.027	0.0250	0	107.9	75	125	06/05/2023	

Batch 206887		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed
SampID: 23051600-010EMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Cyanide		0.005		0.027	0.0250	0	108.6	0.02696	0.70	06/05/2023	

SW-846 9036 (DISSOLVED)

Batch R329716		SampType: MS		Units mg/L							
SampID: 23051600-004BMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		50		164	100.0	77.76	86.1	85	115		
											06/02/2023

Batch R329716		SampType: MSD		Units mg/L				RPD Limit: 10			Date Analyzed	
SampID: 23051600-004BMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Sulfate			50		169	100.0	77.76	91.4	163.9	3.16	06/02/2023	

Batch R329716		SampType: MS		Units mg/L							
SampID: 23051600-017BMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		50		194	100.0	101.8	92.1	85	115	06/02/2023	

Batch R329716		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-017BMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Sulfate			50		198	100.0	101.8	96.5	193.9	2.24	06/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9036 (DISSOLVED)

Batch R329716		SampType: MS		Units mg/L							Date
SampID: 23051600-034BMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		50	S	172	100.0	89.14	83.0	85	115	06/02/2023	

Batch R329716		SampType: MSD		Units mg/L							RPD Limit: 10	Date
SampID: 23051600-034BMSD												Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Sulfate		50		182	100.0	89.14	92.8	172.2	5.54	06/02/2023		

Batch R329893		SampType: MS		Units mg/L							Date
SampID: 23051600-005CMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		20	E	130	40.00	94.54	88.4	85	115	06/06/2023	

Batch R329893		SampType: MSD		Units mg/L							RPD Limit: 10	Date
SampID: 23051600-005CMSD												Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Sulfate		20	E	132	40.00	94.54	94.5	129.9	1.85	06/06/2023		

Batch R329893		SampType: MS		Units mg/L							Date
SampID: 23051600-030CMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		50		186	100.0	87.30	98.4	85	115	06/07/2023	

Batch R329893		SampType: MSD		Units mg/L							RPD Limit: 10	Date
SampID: 23051600-030CMSD												Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Sulfate		50		184	100.0	87.30	96.4	185.7	1.07	06/07/2023		

SW-846 9036 (TOTAL)

Batch R329716		SampType: MBLK		Units mg/L							Date
SampID: ICB/MBLK											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		10		< 10	6.140	0	0	-100	100	06/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9036 (TOTAL)

Batch R329716		SampType: LCS		Units mg/L							
SampID: ICV/LCS											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Sulfate		10		20	20.00	0	100.8	90	110	06/02/2023	

Batch R329716		SampType: MS		Units mg/L						
SampID: 23051600-008AMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Sulfate		50		165	100.0	79.56	85.2	85	115	06/02/2023

Batch R329716		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-008AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Sulfate			50		165	100.0	79.56	85.5	164.8	0.18	06/02/2023

Batch R329716		SampType: MS		Units mg/L						
SampID: 23051600-013AMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Sulfate		100		313	200.0	142.9	85.1	85	115	06/02/2023

Batch R329716		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-013AMSD											Date Analyzed
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Sulfate			100		320	200.0	142.9	88.5	313.2	2.15	06/02/2023

Batch R329716		SampType: MS		Units mg/L							
SampID: 23051600-021AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		50		211	100.0	117.8	93.3	85	115	06/02/2023	

Batch R329716		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-021AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Sulfate			50		206	100.0	117.8	87.9	211.1	2.61	06/02/2023

Batch R329716		SampType: MS		Units mg/L							
SampID: 23051600-034AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		50		180	100.0	88.17	92.3	85	115	06/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9036 (TOTAL)

Batch R329716		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-034AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Sulfate			50		184	100.0	88.17	95.7	180.5	1.84	06/02/2023

Batch R329763		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Sulfate			10		< 10	6.140	0	0	-100	100	06/03/2023

Batch R329763		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		10		18	20.00	0	91.2	90	110	06/03/2023	

Batch R329780		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		10		< 10	6.140	0	0	-100	100	06/05/2023	

Batch R329780		SampType: LCS		Units mg/L							
SampID: ICV/LCS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		10		19	20.00	0	93.0	90	110	06/05/2023	

Batch R329893		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Sulfate			10		< 10	6.140	0	0	-100	100	06/06/2023

Batch R329893		SampType: LCS		Units mg/L							
SampID: ICB/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		10		19	20.00	0	93.8	90	110	06/06/2023	

Batch R329893		SampType: MS		Units mg/L							
SampID: 23051600-030AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		50		180	100.0	86.98	92.6	85	115	06/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9036 (TOTAL)

Batch R329893		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-030AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Sulfate			50		183	100.0	86.98	95.9	179.6	1.84	06/06/2023

Batch R329925		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Sulfate			10		< 10	6.140	0	0	-100	100	06/07/2023

Batch R329925		SampType: MBLK		Units mg/L							
SampID: MBLK 230531											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Sulfate		10		< 10	7.620	0	0	-100	100	06/07/2023	

Batch R329925		SampType: LCS		Units mg/L							
SampID: ICV/LCS											Date
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Sulfate			10		18	20.00	0	91.0	90	110	06/07/2023

Batch R329925		SampType: MS		Units mg/L							
SampID: 23051600-006AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Sulfate		50		224	100.0	134.2	90.0	85	115	06/08/2023	

Batch R329925		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-006AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Sulfate			50		233	100.0	134.2	98.4	224.2	3.65	06/08/2023

SW-846 9060

Batch R329995		SampType: MBLK		Units mg/L							
SampID: Filter Blank											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Total Organic Carbon (TOC)			1.0		< 1.0	0.4500	0	0	-100	100	06/08/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9060

Batch R329995		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Total Organic Carbon (TOC)		1.0		< 1.0	0.4500	0	0	-100	100	06/08/2023	

Batch R329995		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Total Organic Carbon (TOC)		1.0		5.1	5.000	0	102.0	90	110	06/08/2023	

Batch R329995		SampType: MS		Units mg/L							
SampID: 23051600-002GMS											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Total Organic Carbon (TOC)		1.0		6.8	5.000	2.020	95.8	85	115	06/08/2023	

Batch R329995		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-002GMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Total Organic Carbon (TOC)			1.0		6.8	5.000	2.020	95.0	6.810	0.59	06/08/2023

Batch R329995		SampType: MS		Units mg/L							
SampID: 23051600-002HMS											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Dissolved Organic Carbon		1.0		7.5	5.000	2.750	95.4	85	115	06/08/2023	

Batch R329995		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-002HMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Dissolved Organic Carbon			1.0		7.5	5.000	2.750	95.4	7.520	0.00	06/08/2023

Batch R329995		SampType: MS		Units mg/L							
SampID: 23051600-010GMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Dissolved Organic Carbon		1.0		9.2	5.000	4.140	101.0	85	115	06/08/2023	

Batch R329995		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-010GMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Dissolved Organic Carbon			1.0		9.0	5.000	4.140	98.2	9.190	1.54	06/08/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9060

Batch R329995		SampType: MS		Units mg/L							
SampID: 23051600-011EMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Total Organic Carbon (TOC)		1.0		7.3	5.000	2.370	98.2	85	115	06/08/2023	

Batch R329995		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-011EMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Total Organic Carbon (TOC)			1.0		7.3	5.000	2.370	98.0	7.280	0.14	06/08/2023

Batch R329995		SampType: MS		Units mg/L							
SampID: 23051600-018EMS											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Total Organic Carbon (TOC)			1.0		7.8	5.000	3.200	92.0	85	115	06/08/2023

Batch R329995		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-018EMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Total Organic Carbon (TOC)			1.0		8.1	5.000	3.200	98.6	7.800	4.14	06/08/2023

Batch R329995		SampType: MS		Units mg/L							
SampID: 23051600-024EMS											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Total Organic Carbon (TOC)			1.0		5.9	5.000	0.9700	98.0	85	115	06/08/2023

Batch R329995		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-024EMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Total Organic Carbon (TOC)			1.0		5.8	5.000	0.9700	96.2	5.870	1.55	06/09/2023

Batch R329995		SampType: MS		Units mg/L							
SampID: 23051600-024FMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Dissolved Organic Carbon		1.0		5.6	5.000	0.9100	94.4	85	115	06/08/2023	

Batch R329995		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-024FMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Dissolved Organic Carbon			1.0		5.7	5.000	0.9100	95.8	5.630	1.24	06/08/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9060

Batch R329995		SampType: MS		Units mg/L						
SampID: 23051600-031EMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Total Organic Carbon (TOC)		1.0		6.2	5.000	1.240	99.8	85	115	06/09/2023

Batch R329995		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-031EMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Total Organic Carbon (TOC)			1.0		6.1	5.000	1.240	97.8	6.230	1.62	06/09/2023

Batch R329995		SampType: MS		Units mg/L							
SampID: 23051600-036FMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Dissolved Organic Carbon		1.0		6.7	5.000	1.670	101.4	85	115	06/09/2023	

Batch R329995		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-036FMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Dissolved Organic Carbon			1.0		6.7	5.000	1.670	99.8	6.740	1.19	06/09/2023

Batch R329995		SampType: MS		Units mg/L							
SampID: 23051600-040EMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Total Organic Carbon (TOC)		1.0		8.2	5.000	2.990	104.4	85	115	06/09/2023	

Batch R329995		SampType: MSD		Units mg/L				RPD Limit: 10			
SampID: 23051600-040EMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Total Organic Carbon (TOC)			1.0		8.1	5.000	2.990	101.8	8.210	1.60	06/09/2023

Batch R329995		SampType: MS		Units mg/L							
SampID: 23051600-040FMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Dissolved Organic Carbon		1.0		8.1	5.000	2.700	107.2	85	115	06/08/2023	

Batch R329995		SampType: MSD		Units mg/L		RPD Limit: 10					
SampID: 23051600-040FMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Dissolved Organic Carbon			1.0		7.8	5.000	2.700	103.0	8.060	2.64	06/08/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9060

Batch R330146		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Total Organic Carbon (TOC)		1.0		< 1.0	0.4500	0	0	-100	100	06/12/2023	

Batch R330146		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Total Organic Carbon (TOC)		1.0		4.8	5.000	0	95.8	90	110	06/12/2023	

Batch R330486		SampType: MBLK		Units mg/L							
SampID: Filter Blank											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Total Organic Carbon (TOC)			1.0		< 1.0	0.4500	0	0	-100	100	06/20/2023

Batch R330486		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Total Organic Carbon (TOC)		1.0		< 1.0	0.4500	0	0	-100	100	06/19/2023	

Batch R330486		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Total Organic Carbon (TOC)		1.0		4.9	5.000	0	97.6	90	110	06/19/2023	

SW-846 9066 (TOTAL)

Batch R329815		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Phenols		0.005		< 0.005	0.0028	0	0	-100	100	06/06/2023	

Batch R329815		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Phenols		0.005		0.052	0.0500	0	103.3	90	110	06/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9066 (TOTAL)

Batch R329815		SampType: MS		Units µg/L						
SampID: 23051600-007GMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Phenols		5	S	27	50.00	8.780	37.3	85	115	06/06/2023

Batch R329815		SampType: MSD		Units µg/L				RPD Limit: 15			
SampID: 23051600-007GMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Phenols			5	SR	9	50.00	8.780	0.7	27.45	100.33	06/06/2023

SW-846 9214 (DISSOLVED)

Batch R329756		SampType: MS		Units mg/L						
SampID: 23051600-006CMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Fluoride		0.10		1.96	2.000	0.08500	93.8	75	125	06/05/2023

Batch R329756		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23051600-006CMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Fluoride			0.10		1.85	2.000	0.08500	88.2	1.961	5.93	06/05/2023

SW-846 9214 (TOTAL)

Batch R329756		SampType: MBLK		Units mg/L							
SampID: MBLK											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		< 0.10	0.0500	0	0	-100	100	06/05/2023	

Batch R329756		SampType: LCS		Units mg/L							
SampID: LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Fluoride		0.10		0.93	1.000	0	92.8	90	110	06/05/2023	

Batch R329756		SampType: MS		Units mg/L							
SampID: 23051600-007AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Fluoride		0.10		1.81	2.000	0.08200	86.4	75	125	06/05/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

SW-846 9214 (TOTAL)

Batch R329756		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed
SampID: 23051600-007AMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Fluoride		0.10		1.83	2.000	0.08200	87.4	1.809	1.15	06/05/2023	

Batch R329756		SampType: MS		Units mg/L							
SampID: 23051600-011AMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		2.08	2.000	0.2260	92.6	75	125	06/05/2023	

Batch R329756		SampType: MSD		Units mg/L				RPD Limit: 15				Date Analyzed
SampID: 23051600-011AMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Fluoride			0.10		2.02	2.000	0.2260	89.6	2.077	2.93	06/05/2023	

Batch R329756		SampType: MS		Units mg/L							
SampID: 23051600-017AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Fluoride		0.10		1.76	2.000	0.09300	83.3	75	125	06/05/2023	

Batch R329756		SampType: MSD		Units mg/L				RPD Limit: 15				Date Analyzed
SampID: 23051600-017AMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Fluoride			0.10		1.86	2.000	0.09300	88.4	1.759	5.69	06/05/2023	

Batch R329756		SampType: MS		Units mg/L							
SampID: 23051600-031AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Fluoride		0.10		1.89	2.000	0.1720	85.9	75	125	06/05/2023	

Batch R329756		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23051600-031AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Fluoride			0.10		1.93	2.000	0.1720	88.0	1.890	2.25	06/05/2023

Batch R329756		SampType: MS		Units mg/L							Date Analyzed
SampID: 23051600-036AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		2.03	2.000	0.2520	88.8	75	125	06/05/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9214 (TOTAL)

Batch R329756		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed
SampID: 23051600-036AMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Fluoride		0.10		2.12	2.000	0.2520	93.2	2.027	4.30		

Batch R329756		SampType: MS		Units mg/L							
SampID: 23051600-037AMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		1.96	2.000	0.2020	87.7	75	125	06/05/2023	

Batch R329756		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed	
SampID: 23051600-037AMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Fluoride			0.10		1.94	2.000	0.2020	86.7	1.956	1.03		

SW-846 9251 (DISSOLVED)

Batch R329717		SampType: MS		Units mg/L							
SampID: 23051600-004BMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		40		270	200.0	87.26	91.3	85	115		
										06/02/2023	

Batch R329717		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed	
SampID: 23051600-004BMSD												
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Chloride		40		272	200.0	87.26	92.4	269.9	0.77			

Batch R329717		SampType: MS		Units mg/L							
SampID: 23051600-017BMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		20		198	100.0	104.2	94.2	85	115	06/02/2023	

Batch R329717		SampType: MSD		Units mg/L		RPD Limit: 15					Date Analyzed	
SampID: 23051600-017BMSD												
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Chloride			20		201	100.0	104.2	97.2	198.4	1.50		



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9251 (DISSOLVED)

Batch R329717		SampType: MS		Units mg/L							Date
SampID: 23051600-034BMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		20		177	100.0	90.22	86.4	85	115	06/02/2023	

Batch R329717		SampType: MSD		Units mg/L							RPD Limit: 15	Date
SampID: 23051600-034BMSD												Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Chloride		20		184	100.0	90.22	94.0	176.6	4.19	06/02/2023		

Batch R329817		SampType: MS		Units mg/L							Date
SampID: 23051600-005CMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		8	E	104	40.00	64.10	98.9	85	115	06/06/2023	

Batch R329817		SampType: MSD		Units mg/L							RPD Limit: 15	Date
SampID: 23051600-005CMSD												Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Chloride		8	E	101	40.00	64.10	91.6	103.7	2.87	06/06/2023		

Batch R329848		SampType: MS		Units mg/L							Date
SampID: 23051600-030CMS											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		20		225	100.0	125.0	100.4	85	115	06/07/2023	

Batch R329848		SampType: MSD		Units mg/L							RPD Limit: 15	Date
SampID: 23051600-030CMSD												Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD			
Chloride		20		224	100.0	125.0	98.9	225.5	0.67	06/07/2023		

SW-846 9251 (TOTAL)

Batch R329717		SampType: MBLK		Units mg/L							Date
SampID: ICB/MBLK											Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		4		< 4	0.5000	0	0	-100	100	06/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

SW-846 9251 (TOTAL)

Batch R329717		SampType: LCS		Units mg/L							
SampID: ICV/LCS											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Chloride		4		21	20.00	0	104.2	90	110	06/02/2023	

Batch R329717		SampType: MS		Units mg/L						
SampID: 23051600-008AMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Chloride		20		184	100.0	91.20	93.1	85	115	06/02/2023

Batch R329717		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23051600-008AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Chloride			20		179	100.0	91.20	88.2	184.3	2.70	06/02/2023

Batch R329717		SampType: MS		Units mg/L						
SampID: 23051600-013AMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Chloride		20		183	100.0	88.78	94.4	85	115	06/02/2023

Batch R329717		SampType: MSD		Units mg/L				RPD Limit: 15		
SampID: 23051600-013AMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Chloride		20		180	100.0	88.78	90.9	183.2	1.96	06/02/2023

Batch R329717		SampType: MS		Units mg/L							
SampID: 23051600-021AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		20		198	100.0	106.7	91.5	85	115	06/02/2023	

Batch R329717		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23051600-021AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Chloride			20		193	100.0	106.7	86.5	198.2	2.56	06/02/2023

Batch R329717		SampType: MS		Units mg/L							
SampID: 23051600-034AMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		20		187	100.0	90.31	96.3	85	115	06/02/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9251 (TOTAL)

Batch R329717		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23051600-034AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Chloride			20		185	100.0	90.31	95.0	186.6	0.70	06/02/2023

Batch R329720		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		4		< 4	0.5000	0	0	-100	100	06/03/2023	

Batch R329720		SampType: LCS		Units mg/L							
SampID: ICV/LCS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		4		20	20.00	0	101.7	90	110	06/03/2023	

Batch R329817		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		4		< 4	0.5000	0	0	-100	100	06/05/2023	

Batch R329817		SampType: LCS		Units mg/L							
SampID: ICV/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		4		20	20.00	0	100.6	90	110	06/05/2023	

Batch R329848		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		4		< 4	0.5000	0	0	-100	100	06/06/2023	

Batch R329848		SampType: LCS		Units mg/L							
SampID: ICB/LCS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		4		19	20.00	0	94.4	90	110	06/06/2023	

Batch R329848		SampType: MS		Units mg/L							
SampID: 23051600-006AMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		20		249	100.0	148.5	100.6	85	115	06/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 9251 (TOTAL)

Batch R329848		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed
SampID: 23051600-006AMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Chloride		20	E	253	100.0	148.5	104.0	249.1	1.38		

Batch R329848		SampType: MS		Units mg/L							
SampID: 23051600-030AMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		20		221	100.0	123.3	97.9	85	115	06/06/2023	

Batch R329848		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed
SampID: 23051600-030AMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Chloride			20		220	100.0	123.3	96.7	221.2	0.57	

Batch R329955		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride		4		< 4	0.5000	0	0	-100	100	06/07/2023	

Batch R329955		SampType: LCS		Units mg/L							
SampID: ICV/LCS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride		4		19	20.00	0	96.2	90	110	06/07/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206871 SampType: MBLK Units mg/L

SampleID: MBLK-206871

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		< 0.0250	0.0127	0	0	-100	100	06/07/2023
Antimony		0.0500		< 0.0500	0.0068	0	0	-100	100	06/07/2023
Arsenic		0.0250		< 0.0250	0.0087	0	0	-100	100	06/07/2023
Barium		0.0025		< 0.0025	0.0007	0	0	-100	100	06/07/2023
Beryllium		0.0005		< 0.0005	0.0002	0	0	-100	100	06/07/2023
Boron		0.0200		< 0.0200	0.0090	0	0	-100	100	06/07/2023
Cadmium		0.0020		< 0.0020	0.0005	0	0	-100	100	06/07/2023
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	06/07/2023
Chromium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/07/2023
Cobalt		0.0050		< 0.0050	0.0020	0	0	-100	100	06/07/2023
Copper		0.0050		< 0.0050	0.0013	0	0	-100	100	06/07/2023
Iron		0.0400		< 0.0400	0.0200	0	0	-100	100	06/07/2023
Lead		0.0150		< 0.0150	0.0014	0	0	-100	100	06/07/2023
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	06/07/2023
Manganese		0.0070		< 0.0070	0.0025	0	0	-100	100	06/07/2023
Molybdenum		0.0100		< 0.0100	0.0037	0	0	-100	100	06/07/2023
Nickel		0.0050		< 0.0050	0.0016	0	0	-100	100	06/08/2023
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	06/07/2023
Selenium		0.0400		< 0.0400	0.0170	0	0	-100	100	06/07/2023
Silicon	*	0.0500		< 0.0500	0.0400	0	0	-100	100	06/07/2023
Silver		0.0070		< 0.0070	0.0027	0	0	-100	100	06/07/2023
Sodium		0.0500		< 0.0500	0.0180	0	0	-100	100	06/07/2023
Thallium		0.0500		< 0.0500	0.0111	0	0	-100	100	06/07/2023
Vanadium		0.0100		< 0.0100	0.0009	0	0	-100	100	06/07/2023
Zinc		0.0100		< 0.0100	0.0050	0	0	-100	100	06/07/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206871		SampType: LCS		Units mg/L							
SampID: LCS-206871											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Aluminum		0.0250		1.71	2.000	0	85.4	85	115	06/07/2023	
Antimony		0.0500		0.433	0.5000	0	86.5	85	115	06/07/2023	
Arsenic		0.0250		0.450	0.5000	0	89.9	85	115	06/07/2023	
Barium		0.0025		1.80	2.000	0	90.0	85	115	06/07/2023	
Beryllium		0.0005		0.0437	0.0500	0	87.4	85	115	06/07/2023	
Boron		0.0200		0.439	0.5000	0	87.8	85	115	06/07/2023	
Cadmium		0.0020		0.0455	0.0500	0	91.0	85	115	06/07/2023	
Calcium		0.100		2.30	2.500	0	91.9	85	115	06/07/2023	
Chromium		0.0050		0.181	0.2000	0	90.7	85	115	06/07/2023	
Cobalt		0.0050		0.446	0.5000	0	89.2	85	115	06/07/2023	
Copper		0.0050		0.224	0.2500	0	89.5	85	115	06/07/2023	
Iron		0.0400		1.80	2.000	0	90.1	85	115	06/07/2023	
Lead		0.0150		0.442	0.5000	0	88.5	85	115	06/07/2023	
Magnesium		0.0500		2.13	2.500	0	85.2	85	115	06/07/2023	
Manganese		0.0070		0.446	0.5000	0	89.2	85	115	06/07/2023	
Molybdenum		0.0100		0.426	0.5000	0	85.2	85	115	06/07/2023	
Nickel		0.0050		0.460	0.5000	0	92.0	85	115	06/08/2023	
Potassium		0.100		2.39	2.500	0	95.7	85	115	06/07/2023	
Selenium		0.0400		0.430	0.5000	0	86.0	85	115	06/07/2023	
Silicon	*	0.0500		0.511	0.5000	0	102.1	85	115	06/07/2023	
Silver		0.0070		0.0456	0.0500	0	91.2	85	115	06/07/2023	
Sodium		0.0500		2.25	2.500	0	90.1	85	115	06/07/2023	
Thallium		0.0500		0.218	0.2500	0	87.0	85	115	06/07/2023	
Vanadium		0.0100		0.440	0.5000	0	88.0	85	115	06/07/2023	
Zinc		0.0100		0.446	0.5000	0	89.2	85	115	06/07/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206871		SampType: MS		Units mg/L							
SampID: 23051600-003DMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Aluminum		0.0250		1.72	2.000	0	85.9	75	125	06/07/2023	
Arsenic		0.0250		0.470	0.5000	0	94.0	75	125	06/07/2023	
Barium		0.0025		1.85	2.000	0.04570	90.0	75	125	06/07/2023	
Boron		0.0200		1.02	0.5000	0.5821	86.9	75	125	06/07/2023	
Cadmium		0.0020		0.0451	0.0500	0	90.2	75	125	06/07/2023	
Calcium		0.100	S	76.3	2.500	75.16	46.8	75	125	06/07/2023	
Chromium		0.0050		0.180	0.2000	0	90.2	75	125	06/07/2023	
Copper		0.0050		0.227	0.2500	0	91.0	75	125	06/07/2023	
Iron		0.0400		1.80	2.000	0	89.9	75	125	06/07/2023	
Lead		0.0150		0.438	0.5000	0	87.6	75	125	06/07/2023	
Magnesium		0.0500	S	29.5	2.500	27.75	70.2	75	125	06/07/2023	
Molybdenum		0.0100		0.452	0.5000	0.02060	86.3	75	125	06/07/2023	
Potassium		1.00		10.9	2.500	8.544	93.0	75	125	06/08/2023	
Sodium		0.0500	S	43.2	2.500	41.68	60.4	75	125	06/07/2023	
Zinc		0.0100		0.453	0.5000	0	90.6	75	125	06/07/2023	

Batch 206871		SampType: MSD		Units mg/L				RPD Limit: 20			
SampID: 23051600-003DMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Aluminum		0.0250		1.74	2.000	0	86.9	1.717	1.18	06/07/2023	
Arsenic		0.0250		0.467	0.5000	0	93.4	0.4702	0.70	06/07/2023	
Barium		0.0025		1.85	2.000	0.04570	90.4	1.847	0.42	06/07/2023	
Boron		0.0200		1.02	0.5000	0.5821	87.1	1.017	0.09	06/07/2023	
Cadmium		0.0020		0.0452	0.0500	0	90.4	0.04510	0.22	06/07/2023	
Calcium		0.100	S	76.6	2.500	75.16	59.2	76.33	0.41	06/07/2023	
Chromium		0.0050		0.182	0.2000	0	91.2	0.1804	1.10	06/07/2023	
Copper		0.0050		0.230	0.2500	0	91.8	0.2274	0.92	06/07/2023	
Iron		0.0400		1.82	2.000	0	90.8	1.797	0.99	06/07/2023	
Lead		0.0150		0.442	0.5000	0	88.4	0.4378	1.00	06/07/2023	
Magnesium		0.0500	S	29.4	2.500	27.75	67.5	29.50	0.23	06/07/2023	
Molybdenum		0.0100		0.454	0.5000	0.02060	86.7	0.4520	0.49	06/07/2023	
Potassium		1.00		10.9	2.500	8.544	92.9	10.87	0.04	06/08/2023	
Sodium		0.0500	S	43.1	2.500	41.68	56.4	43.19	0.23	06/07/2023	
Zinc		0.0100		0.456	0.5000	0	91.2	0.4529	0.64	06/07/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206871 SampType: MS Units mg/L

SampleID: 23051600-008EMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		1.73	2.000	0	86.3	75	125	06/07/2023
Arsenic		0.0250		0.466	0.5000	0	93.1	75	125	06/07/2023
Barium		0.0025		1.88	2.000	0.07000	90.4	75	125	06/07/2023
Beryllium		0.0005		0.0446	0.0500	0	89.2	75	125	06/07/2023
Boron		0.0200		0.673	0.5000	0.2354	87.5	75	125	06/07/2023
Cadmium		0.0020		0.0451	0.0500	0	90.2	75	125	06/07/2023
Calcium		0.100	S	75.9	2.500	75.15	31.2	75	125	06/07/2023
Chromium		0.0050		0.182	0.2000	0	91.1	75	125	06/07/2023
Copper		0.0050		0.230	0.2500	0.004900	90.0	75	125	06/07/2023
Iron		0.0400		1.83	2.000	0	91.5	75	125	06/07/2023
Lead		0.0150		0.442	0.5000	0	88.4	75	125	06/07/2023
Magnesium		0.0500	S	25.3	2.500	23.57	69.3	75	125	06/07/2023
Manganese		0.0070		0.456	0.5000	0	91.2	75	125	06/07/2023
Molybdenum		0.0100		0.449	0.5000	0.01250	87.4	75	125	06/07/2023
Nickel		0.0050		0.452	0.5000	0	90.3	75	125	06/08/2023
Potassium		0.100		6.61	2.500	4.328	91.2	75	125	06/07/2023
Silver		0.0070		0.0471	0.0500	0.001100	92.0	75	125	06/07/2023
Sodium		0.0500	S	49.8	2.500	48.46	52.4	75	125	06/07/2023
Zinc		0.0100		0.457	0.5000	0	91.4	75	125	06/07/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch	206871	SampType:	MSD	Units mg/L				RPD Limit: 20		
SampID: 23051600-008EMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Aluminum		0.0250		1.71	2.000	0	85.6	1.726	0.80	06/07/2023
Arsenic		0.0250		0.462	0.5000	0	92.4	0.4655	0.71	06/07/2023
Barium		0.0025		1.86	2.000	0.07000	89.4	1.878	1.07	06/07/2023
Beryllium		0.0005		0.0447	0.0500	0	89.4	0.04460	0.22	06/07/2023
Boron		0.0200		0.668	0.5000	0.2354	86.5	0.6728	0.76	06/07/2023
Cadmium		0.0020		0.0443	0.0500	0	88.6	0.04510	1.79	06/07/2023
Calcium		0.100	S	75.2	2.500	75.15	3.2	75.93	0.93	06/07/2023
Chromium		0.0050		0.181	0.2000	0	90.7	0.1822	0.50	06/07/2023
Copper		0.0050		0.238	0.2500	0.004900	93.1	0.2299	3.34	06/07/2023
Iron		0.0400		1.80	2.000	0	90.0	1.829	1.59	06/07/2023
Lead		0.0150		0.436	0.5000	0	87.2	0.4419	1.32	06/07/2023
Magnesium		0.0500	S	25.3	2.500	23.57	67.1	25.30	0.21	06/07/2023
Manganese		0.0070		0.448	0.5000	0	89.7	0.4562	1.70	06/07/2023
Molybdenum		0.0100		0.444	0.5000	0.01250	86.2	0.4494	1.32	06/07/2023
Nickel		0.0050		0.457	0.5000	0	91.4	0.4516	1.21	06/08/2023
Potassium		0.100		6.53	2.500	4.328	88.0	6.608	1.21	06/07/2023
Silver		0.0070		0.0471	0.0500	0.001100	92.0	0.04710	0.00	06/07/2023
Sodium		0.0500	S	49.4	2.500	48.46	35.6	49.77	0.85	06/07/2023
Zinc		0.0100		0.456	0.5000	0	91.2	0.4568	0.22	06/07/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206873 SampType: MBLK Units mg/L

SampleID: MBLK-206873

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		< 0.0250	0.0127	0	0	-100	100	06/06/2023
Antimony		0.0500		< 0.0500	0.0068	0	0	-100	100	06/06/2023
Arsenic		0.0250		< 0.0250	0.0087	0	0	-100	100	06/06/2023
Barium		0.0025		< 0.0025	0.0007	0	0	-100	100	06/06/2023
Beryllium		0.0005	J	0.0002	0.0002	0	100.0	-100	100	06/06/2023
Boron		0.0200		< 0.0200	0.0090	0	0	-100	100	06/06/2023
Cadmium		0.0020		< 0.0020	0.0005	0	0	-100	100	06/06/2023
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	06/06/2023
Chromium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/06/2023
Cobalt		0.0050		< 0.0050	0.0020	0	0	-100	100	06/06/2023
Copper		0.0050		< 0.0050	0.0013	0	0	-100	100	06/06/2023
Iron		0.0400		< 0.0400	0.0200	0	0	-100	100	06/06/2023
Lead		0.0150		< 0.0150	0.0014	0	0	-100	100	06/06/2023
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	06/06/2023
Manganese		0.0070		< 0.0070	0.0025	0	0	-100	100	06/06/2023
Molybdenum		0.0100		< 0.0100	0.0037	0	0	-100	100	06/06/2023
Nickel		0.0050		< 0.0050	0.0016	0	0	-100	100	06/06/2023
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	06/06/2023
Selenium		0.0400		< 0.0400	0.0170	0	0	-100	100	06/06/2023
Silicon	*	0.0500		< 0.0500	0.0122	0	0	-100	100	06/07/2023
Silver		0.0070		< 0.0070	0.0027	0	0	-100	100	06/06/2023
Sodium		0.0500		< 0.0500	0.0180	0	0	-100	100	06/07/2023
Thallium		0.0500		< 0.0500	0.0111	0	0	-100	100	06/06/2023
Vanadium		0.0100		< 0.0100	0.0009	0	0	-100	100	06/06/2023
Zinc		0.0100		< 0.0100	0.0050	0	0	-100	100	06/06/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206873		SampType: LCS		Units mg/L							
SampID: LCS-206873											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Aluminum		0.0250		1.79	2.000	0	89.3	85	115	06/06/2023	
Antimony		0.0500		0.439	0.5000	0	87.8	85	115	06/06/2023	
Arsenic		0.0250		0.466	0.5000	0	93.2	85	115	06/06/2023	
Barium		0.0025		1.81	2.000	0	90.3	85	115	06/06/2023	
Beryllium		0.0005		0.0460	0.0500	0	92.0	85	115	06/06/2023	
Boron		0.0200		0.454	0.5000	0	90.7	85	115	06/06/2023	
Cadmium		0.0020		0.0445	0.0500	0	89.0	85	115	06/06/2023	
Calcium		0.100		2.35	2.500	0	94.2	85	115	06/06/2023	
Chromium		0.0050		0.189	0.2000	0	94.7	85	115	06/06/2023	
Cobalt		0.0050		0.478	0.5000	0	95.5	85	115	06/06/2023	
Copper		0.0050		0.232	0.2500	0	93.0	85	115	06/06/2023	
Iron		0.0400		1.87	2.000	0	93.3	85	115	06/06/2023	
Lead		0.0150		0.461	0.5000	0	92.3	85	115	06/06/2023	
Magnesium		0.0500		2.23	2.500	0	89.2	85	115	06/06/2023	
Manganese		0.0070		0.485	0.5000	0	97.0	85	115	06/06/2023	
Molybdenum		0.0100		0.449	0.5000	0	89.8	85	115	06/06/2023	
Nickel		0.0050		0.464	0.5000	0	92.9	85	115	06/06/2023	
Potassium		0.100		2.32	2.500	0	92.9	85	115	06/06/2023	
Selenium		0.0400		0.449	0.5000	0	89.7	85	115	06/06/2023	
Silicon	*	0.0500		0.506	0.5000	0	101.2	85	115	06/07/2023	
Silver		0.0070		0.0440	0.0500	0	88.0	85	115	06/06/2023	
Sodium		0.0500		2.25	2.500	0	89.8	85	115	06/07/2023	
Thallium		0.0500		0.233	0.2500	0	93.1	85	115	06/06/2023	
Vanadium		0.0100		0.450	0.5000	0	89.9	85	115	06/06/2023	
Zinc		0.0100		0.452	0.5000	0	90.3	85	115	06/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206873 SampType: MS Units mg/L

SampleID: 23051600-044EMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		3.15	4.000	0	78.8	75	125	06/06/2023
Arsenic		0.0250		0.852	1.000	0	85.2	75	125	06/06/2023
Barium		0.0025		3.27	4.000	0	81.8	75	125	06/06/2023
Beryllium		0.0005		0.0838	0.1000	0.0008000	83.0	75	125	06/06/2023
Boron		0.0200		0.817	1.000	0	81.7	75	125	06/06/2023
Cadmium		0.0020		0.0805	0.1000	0	80.5	75	125	06/06/2023
Calcium		0.100		4.26	5.000	0	85.2	75	125	06/06/2023
Chromium		0.0050		0.344	0.4000	0	86.1	75	125	06/06/2023
Copper		0.0050		0.428	0.5000	0	85.5	75	125	06/06/2023
Iron		0.0400		3.55	4.000	0	88.8	75	125	06/06/2023
Lead		0.0150		0.830	1.000	0	83.0	75	125	06/06/2023
Magnesium		0.0500		4.03	5.000	0	80.7	75	125	06/06/2023
Manganese		0.0070		0.888	1.000	0	88.8	75	125	06/06/2023
Molybdenum		0.0100		0.812	1.000	0	81.2	75	125	06/06/2023
Nickel		0.0050		0.837	1.000	0	83.7	75	125	06/06/2023
Potassium		0.100		4.10	5.000	0	82.0	75	125	06/06/2023
Silicon	*	0.0500		0.948	1.000	0	94.8	75	125	06/07/2023
Silver		0.0070		0.0811	0.1000	0	81.1	75	125	06/06/2023
Sodium		0.0500		4.30	5.000	0.03250	85.3	75	125	06/07/2023
Zinc		0.0100		0.810	1.000	0	81.0	75	125	06/06/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206873		SampType: MSD		Units mg/L			RPD Limit: 20			
SampleID: 23051600-044EMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Aluminum		0.0250		3.17	4.000	0	79.2	3.150	0.63	06/06/2023
Arsenic		0.0250		0.844	1.000	0	84.4	0.8525	1.03	06/06/2023
Barium		0.0025		3.27	4.000	0	81.8	3.270	0.00	06/06/2023
Beryllium		0.0005		0.0839	0.1000	0.0008000	83.1	0.08380	0.12	06/06/2023
Boron		0.0200		0.819	1.000	0	81.9	0.8172	0.17	06/06/2023
Cadmium		0.0020		0.0806	0.1000	0	80.6	0.08050	0.12	06/06/2023
Calcium		0.100		4.26	5.000	0	85.2	4.261	0.01	06/06/2023
Chromium		0.0050		0.345	0.4000	0	86.2	0.3444	0.17	06/06/2023
Copper		0.0050		0.427	0.5000	0	85.4	0.4275	0.16	06/06/2023
Iron		0.0400		3.55	4.000	0	88.8	3.550	0.00	06/06/2023
Lead		0.0150		0.833	1.000	0	83.3	0.8298	0.36	06/06/2023
Magnesium		0.0500		4.05	5.000	0	81.1	4.035	0.45	06/06/2023
Manganese		0.0070		0.875	1.000	0	87.5	0.8881	1.53	06/06/2023
Molybdenum		0.0100		0.814	1.000	0	81.4	0.8125	0.18	06/06/2023
Nickel		0.0050		0.839	1.000	0	83.9	0.8367	0.30	06/06/2023
Potassium		0.100		4.09	5.000	0	81.9	4.099	0.14	06/06/2023
Silicon	*	0.0500		0.945	1.000	0	94.5	0.9484	0.39	06/07/2023
Silver		0.0070		0.0812	0.1000	0	81.2	0.08110	0.12	06/06/2023
Sodium		0.0500		4.29	5.000	0.03250	85.2	4.299	0.20	06/07/2023
Zinc		0.0100		0.811	1.000	0	81.1	0.8098	0.15	06/06/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206891 SampType: MBLK Units mg/L

SampleID: MBLK-206891

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		< 0.0250	0.0127	0	0	-100	100	06/06/2023
Antimony		0.0500		< 0.0500	0.0068	0	0	-100	100	06/06/2023
Arsenic		0.0250		< 0.0250	0.0087	0	0	-100	100	06/06/2023
Barium		0.0025		< 0.0025	0.0007	0	0	-100	100	06/06/2023
Beryllium		0.0005		< 0.0005	0.0002	0	0	-100	100	06/06/2023
Boron		0.0200		< 0.0200	0.0090	0	0	-100	100	06/06/2023
Cadmium		0.0020		< 0.0020	0.0005	0	0	-100	100	06/06/2023
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	06/06/2023
Chromium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/06/2023
Cobalt		0.0050		< 0.0050	0.0020	0	0	-100	100	06/06/2023
Copper		0.0050		< 0.0050	0.0013	0	0	-100	100	06/06/2023
Iron		0.0400		< 0.0400	0.0200	0	0	-100	100	06/06/2023
Lead		0.0150		< 0.0150	0.0014	0	0	-100	100	06/06/2023
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	06/06/2023
Manganese		0.0070		< 0.0070	0.0025	0	0	-100	100	06/06/2023
Molybdenum		0.0100		< 0.0100	0.0037	0	0	-100	100	06/06/2023
Nickel		0.0050		< 0.0050	0.0016	0	0	-100	100	06/06/2023
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	06/06/2023
Selenium		0.0400		< 0.0400	0.0170	0	0	-100	100	06/06/2023
Silicon	*	0.0500		< 0.0500	0.0500	0	0	-100	100	06/07/2023
Silver		0.0070		< 0.0070	0.0027	0	0	-100	100	06/06/2023
Sodium		0.0500		< 0.0500	0.0180	0	0	-100	100	06/06/2023
Thallium		0.0500		< 0.0500	0.0111	0	0	-100	100	06/06/2023
Vanadium		0.0100		< 0.0100	0.0009	0	0	-100	100	06/06/2023
Zinc		0.0100		< 0.0100	0.0050	0	0	-100	100	06/06/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206891		SampType: LCS		Units mg/L							
SampleID: LCS-206891											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Aluminum		0.0250		1.79	2.000	0	89.4	85	115	06/06/2023	
Antimony		0.0500		0.439	0.5000	0	87.8	85	115	06/06/2023	
Arsenic		0.0250		0.468	0.5000	0	93.7	85	115	06/06/2023	
Barium		0.0025		1.81	2.000	0	90.4	85	115	06/06/2023	
Beryllium		0.0005		0.0455	0.0500	0	91.0	85	115	06/06/2023	
Boron		0.0200		0.455	0.5000	0	90.9	85	115	06/06/2023	
Cadmium		0.0020		0.0445	0.0500	0	89.0	85	115	06/06/2023	
Calcium		0.100		2.35	2.500	0	94.0	85	115	06/06/2023	
Chromium		0.0050		0.185	0.2000	0	92.6	85	115	06/06/2023	
Cobalt		0.0050		0.475	0.5000	0	95.0	85	115	06/06/2023	
Copper		0.0050		0.234	0.2500	0	93.4	85	115	06/06/2023	
Iron		0.0400		1.84	2.000	0	91.8	85	115	06/06/2023	
Lead		0.0150		0.458	0.5000	0	91.6	85	115	06/06/2023	
Magnesium		0.0500		2.22	2.500	0	89.0	85	115	06/06/2023	
Manganese		0.0070		0.475	0.5000	0	95.1	85	115	06/06/2023	
Molybdenum		0.0100		0.447	0.5000	0	89.4	85	115	06/06/2023	
Nickel		0.0050		0.456	0.5000	0	91.2	85	115	06/06/2023	
Potassium		0.100		2.32	2.500	0	92.8	85	115	06/06/2023	
Selenium		0.0400		0.441	0.5000	0	88.3	85	115	06/06/2023	
Silicon	*	0.0500		0.522	0.5000	0	104.5	85	115	06/07/2023	
Silver		0.0070		0.0436	0.0500	0	87.2	85	115	06/06/2023	
Sodium		0.0500		2.23	2.500	0	89.4	85	115	06/06/2023	
Thallium		0.0500		0.232	0.2500	0	93.0	85	115	06/06/2023	
Vanadium		0.0100		0.449	0.5000	0	89.7	85	115	06/06/2023	
Zinc		0.0100		0.451	0.5000	0	90.3	85	115	06/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206891 SampType: MS Units mg/L

SampleID: 23051600-012DMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		1.83	2.000	0	91.6	75	125	06/06/2023
Calcium		0.100	S	86.4	2.500	85.59	34.0	75	125	06/06/2023
Iron		0.0400		1.85	2.000	0	92.7	75	125	06/06/2023
Magnesium		0.0500	S	28.8	2.500	26.91	74.8	75	125	06/06/2023
Manganese		0.0070		0.480	0.5000	0	96.0	75	125	06/06/2023
Potassium		0.100		5.46	2.500	3.178	91.2	75	125	06/06/2023
Silicon	*	0.0500		5.06	0.5000	4.550	101.7	75	125	06/07/2023
Sodium		0.0500	S	38.9	2.500	37.10	71.2	75	125	06/06/2023

Batch 206891 SampType: MSD Units mg/L

RPD Limit: 20

SampleID: 23051600-012DMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Aluminum		0.0250		1.80	2.000	0	90.1	1.832	1.65	06/06/2023
Calcium		0.100	S	85.6	2.500	85.59	-0.8	86.44	1.01	06/06/2023
Iron		0.0400		1.83	2.000	0	91.7	1.854	1.02	06/06/2023
Magnesium		0.0500	S	28.6	2.500	26.91	68.5	28.78	0.55	06/06/2023
Manganese		0.0070		0.476	0.5000	0	95.2	0.4798	0.82	06/06/2023
Potassium		0.100		5.34	2.500	3.178	86.6	5.459	2.14	06/06/2023
Silicon	*	0.0500		5.07	0.5000	4.550	104.7	5.059	0.30	06/07/2023
Sodium		0.0500	S	38.3	2.500	37.10	47.2	38.88	1.56	06/06/2023

Batch 206891 SampType: MS Units mg/L

SampleID: 23051600-041DMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		4.28	2.000	2.550	86.5	75	125	06/06/2023
Calcium		0.100	S	92.2	2.500	91.26	36.8	75	125	06/06/2023
Iron		0.0400		1.87	2.000	0	93.3	75	125	06/06/2023
Magnesium		0.0500		2.19	2.500	0	87.7	75	125	06/06/2023
Manganese		0.0070		0.484	0.5000	0	96.7	75	125	06/06/2023
Potassium		0.500	S	26.8	2.500	24.93	74.9	75	125	06/08/2023
Silicon	*	0.0500	S	11.2	0.5000	10.80	74.7	75	125	06/07/2023
Sodium		0.0500	S	105	2.500	104.0	28.8	75	125	06/06/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (DISSOLVED)

Batch 206891		SampType: MSD		Units mg/L				RPD Limit: 20		
SampleID: 23051600-041DMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Aluminum		0.0250		4.25	2.000	2.550	85.0	4.280	0.70	06/06/2023
Calcium		0.100	S	91.8	2.500	91.26	23.2	92.18	0.37	06/06/2023
Iron		0.0400		1.87	2.000	0	93.3	1.866	0.07	06/06/2023
Magnesium		0.0500		2.19	2.500	0	87.7	2.192	0.02	06/06/2023
Manganese		0.0070		0.483	0.5000	0	96.6	0.4835	0.06	06/06/2023
Potassium		0.500		26.8	2.500	24.93	76.3	26.80	0.13	06/08/2023
Silicon	*	0.0500		11.3	0.5000	10.80	98.2	11.18	1.05	06/07/2023
Sodium		0.0500	S	103	2.500	104.0	-25.2	104.7	1.30	06/06/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206856		SampType: MBLK		Units mg/L							Date Analyzed	
SampID: MBLK-206856												
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			
Aluminum		0.0250		< 0.0250	0.0127	0	0	-100	100	06/05/2023		
Antimony		0.0500		< 0.0500	0.0068	0	0	-100	100	06/05/2023		
Arsenic		0.0250		< 0.0250	0.0087	0	0	-100	100	06/05/2023		
Barium		0.0025		< 0.0025	0.0007	0	0	-100	100	06/05/2023		
Beryllium		0.0005		< 0.0005	0.0002	0	0	-100	100	06/05/2023		
Boron		0.0200		< 0.0200	0.0090	0	0	-100	100	06/05/2023		
Cadmium		0.0020		< 0.0020	0.0005	0	0	-100	100	06/05/2023		
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	06/05/2023		
Chromium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/05/2023		
Cobalt		0.0050		< 0.0050	0.0020	0	0	-100	100	06/05/2023		
Copper		0.0050		< 0.0050	0.0013	0	0	-100	100	06/05/2023		
Iron		0.0400		< 0.0400	0.0200	0	0	-100	100	06/05/2023		
Lead		0.0150		< 0.0150	0.0014	0	0	-100	100	06/05/2023		
Lithium		0.0050		< 0.0050	0.0019	0	0	-100	100	06/14/2023		
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	06/05/2023		
Manganese		0.0070		< 0.0070	0.0025	0	0	-100	100	06/05/2023		
Molybdenum		0.0100		< 0.0100	0.0037	0	0	-100	100	06/05/2023		
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	06/05/2023		
Selenium		0.0400		< 0.0400	0.0170	0	0	-100	100	06/05/2023		
Silicon	*	0.0500	S	0.0599	0.0122	0	491.0	-100	100	06/07/2023		
Sodium		0.0500		< 0.0500	0.0180	0	0	-100	100	06/05/2023		
Thallium		0.0500		< 0.0500	0.0111	0	0	-100	100	06/05/2023		
Vanadium		0.0100		< 0.0100	0.0009	0	0	-100	100	06/05/2023		
Zinc		0.0100		< 0.0100	0.0050	0	0	-100	100	06/05/2023		



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206856		SampType: LCS		Units mg/L							Date Analyzed
SampID: LCS-206856											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Aluminum		0.0250		1.92	2.000	0	96.0	85	115	06/05/2023	
Antimony		0.0500		0.490	0.5000	0	97.9	85	115	06/05/2023	
Arsenic		0.0250		0.516	0.5000	0	103.3	85	115	06/05/2023	
Barium		0.0025		2.02	2.000	0	101.0	85	115	06/05/2023	
Beryllium		0.0005		0.0503	0.0500	0	100.6	85	115	06/05/2023	
Boron		0.0200		0.491	0.5000	0	98.2	85	115	06/05/2023	
Cadmium		0.0020		0.0528	0.0500	0	105.6	85	115	06/05/2023	
Calcium		0.100		2.59	2.500	0	103.7	85	115	06/05/2023	
Chromium		0.0050		0.194	0.2000	0	97.2	85	115	06/05/2023	
Cobalt		0.0050		0.490	0.5000	0	97.9	85	115	06/05/2023	
Copper		0.0050		0.247	0.2500	0	99.0	85	115	06/05/2023	
Iron		0.0400		2.00	2.000	0	100.0	85	115	06/05/2023	
Lead		0.0150		0.493	0.5000	0	98.7	85	115	06/05/2023	
Lithium		0.0050		0.548	0.5000	0	109.6	85	115	06/15/2023	
Lithium		0.0050	S	0.623	0.5000	0	124.6	85	115	06/15/2023	
Magnesium		0.0500		2.36	2.500	0	94.2	85	115	06/05/2023	
Manganese		0.0070		0.488	0.5000	0	97.6	85	115	06/05/2023	
Molybdenum		0.0100		0.476	0.5000	0	95.2	85	115	06/05/2023	
Potassium		0.100		2.62	2.500	0	104.7	85	115	06/05/2023	
Selenium		0.0400		0.496	0.5000	0	99.1	85	115	06/05/2023	
Silicon	*	0.0500	BS	0.602	0.5000	0	120.5	85	115	06/07/2023	
Sodium		0.0500		2.50	2.500	0	100.2	85	115	06/05/2023	
Thallium		0.0500		0.242	0.2500	0	96.7	85	115	06/05/2023	
Vanadium		0.0100		0.490	0.5000	0	98.0	85	115	06/05/2023	
Zinc		0.0100		0.499	0.5000	0	99.7	85	115	06/05/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206856		SampType: MS		Units mg/L							Date Analyzed	
SampleID: 23051600-007DMS												
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			
Aluminum		0.0250		2.07	2.000	0.05820	100.6	75	125	06/05/2023		
Arsenic		0.0250		0.524	0.5000	0	104.9	75	125	06/05/2023		
Barium		0.0025		2.11	2.000	0.1075	100.1	75	125	06/05/2023		
Beryllium		0.0005		0.0505	0.0500	0.0003000	100.4	75	125	06/05/2023		
Boron		0.0200		0.591	0.5000	0.08420	101.4	75	125	06/05/2023		
Cadmium		0.0020		0.0515	0.0500	0	103.0	75	125	06/05/2023		
Calcium		0.100	S	201	2.500	200.2	42.8	75	125	06/05/2023		
Chromium		0.0050		0.195	0.2000	0	97.3	75	125	06/05/2023		
Copper		0.0050		0.263	0.2500	0.007200	102.3	75	125	06/05/2023		
Iron		0.0400		2.20	2.000	0.1000	105.0	75	125	06/05/2023		
Lead		0.0150		0.484	0.5000	0	96.7	75	125	06/05/2023		
Lithium		0.0050		0.568	0.5000	0.01140	111.3	75	125	06/15/2023		
Magnesium		0.0500		64.1	2.500	61.99	86.0	75	125	06/05/2023		
Manganese		0.0070		0.508	0.5000	0.01790	97.9	75	125	06/05/2023		
Molybdenum		0.0100		0.484	0.5000	0	96.9	75	125	06/05/2023		
Potassium		0.100		6.61	2.500	3.973	105.3	75	125	06/05/2023		
Silicon	*	0.0500	B	9.42	0.5000	8.822	118.8	75	125	06/07/2023		
Sodium		0.0500		181	2.500	178.4	96.8	75	125	06/05/2023		
Zinc		0.0100		0.514	0.5000	0.01010	100.8	75	125	06/05/2023		



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206856		SampType: MSD		Units mg/L			RPD Limit: 20			
SampID: 23051600-007DMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Aluminum		0.0250		2.08	2.000	0.05820	101.1	2.070	0.48	06/05/2023
Arsenic		0.0250		0.525	0.5000	0	105.0	0.5243	0.15	06/05/2023
Barium		0.0025		2.13	2.000	0.1075	101.1	2.110	0.94	06/05/2023
Beryllium		0.0005		0.0507	0.0500	0.0003000	100.8	0.05050	0.40	06/05/2023
Boron		0.0200		0.592	0.5000	0.08420	101.5	0.5912	0.08	06/05/2023
Cadmium		0.0020		0.0519	0.0500	0	103.8	0.05150	0.77	06/05/2023
Calcium		0.100		203	2.500	200.2	96.0	201.3	0.66	06/05/2023
Chromium		0.0050		0.196	0.2000	0	98.0	0.1946	0.72	06/05/2023
Copper		0.0050		0.262	0.2500	0.007200	102.0	0.2629	0.30	06/05/2023
Iron		0.0400		2.17	2.000	0.1000	103.5	2.200	1.37	06/05/2023
Lead		0.0150		0.488	0.5000	0	97.7	0.4837	0.99	06/05/2023
Lithium		0.0050		0.569	0.5000	0.01140	111.5	0.5681	0.16	06/15/2023
Magnesium		0.0500		64.4	2.500	61.99	95.8	64.14	0.38	06/05/2023
Manganese		0.0070		0.513	0.5000	0.01790	98.9	0.5076	0.98	06/05/2023
Molybdenum		0.0100		0.485	0.5000	0	96.9	0.4843	0.08	06/05/2023
Potassium		0.100		6.54	2.500	3.973	102.6	6.606	1.04	06/05/2023
Silicon	*	0.0500	BS	9.51	0.5000	8.822	136.9	9.416	0.96	06/07/2023
Sodium		0.0500	S	180	2.500	178.4	53.2	180.8	0.60	06/05/2023
Zinc		0.0100		0.516	0.5000	0.01010	101.1	0.5142	0.29	06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206856		SampType: MS		Units mg/L							Date Analyzed	
SampID: 23051600-024CMS												
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			
Aluminum		0.0250		2.22	2.000	0.2164	100.2	75	125	06/05/2023		
Arsenic		0.0250		0.521	0.5000	0	104.2	75	125	06/05/2023		
Barium		0.0025		2.06	2.000	0.04100	101.0	75	125	06/05/2023		
Beryllium		0.0005		0.0512	0.0500	0	102.4	75	125	06/05/2023		
Boron		0.0200		0.645	0.5000	0.1428	100.4	75	125	06/05/2023		
Cadmium		0.0020		0.0522	0.0500	0	104.4	75	125	06/05/2023		
Calcium		0.100	S	103	2.500	102.2	47.6	75	125	06/05/2023		
Chromium		0.0050		0.197	0.2000	0	98.6	75	125	06/05/2023		
Iron		0.0400		2.40	2.000	0.2952	105.2	75	125	06/05/2023		
Lead		0.0150		0.494	0.5000	0	98.8	75	125	06/05/2023		
Lithium		0.0050	S	0.644	0.5000	0.002900	128.2	75	125	06/14/2023		
Magnesium		0.0500		41.7	2.500	39.45	89.6	75	125	06/05/2023		
Manganese		0.0070		0.598	0.5000	0.1040	98.9	75	125	06/05/2023		
Molybdenum		0.0100		0.486	0.5000	0	97.2	75	125	06/05/2023		
Potassium		0.100		4.76	2.500	2.222	101.7	75	125	06/05/2023		
Silicon	*	0.0500	B	7.18	0.5000	6.601	115.5	75	125	06/07/2023		
Sodium		0.0500		42.1	2.500	40.12	78.4	75	125	06/05/2023		



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch	206856	SampType:	MSD	Units mg/L				RPD Limit: 20		
SampleID: 23051600-024CMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Aluminum		0.0250		2.23	2.000	0.2164	100.7	2.220	0.45	06/05/2023
Arsenic		0.0250		0.525	0.5000	0	105.0	0.5212	0.73	06/05/2023
Barium		0.0025		2.05	2.000	0.04100	100.5	2.060	0.49	06/05/2023
Beryllium		0.0005		0.0508	0.0500	0	101.6	0.05120	0.78	06/05/2023
Boron		0.0200		0.645	0.5000	0.1428	100.5	0.6447	0.06	06/05/2023
Cadmium		0.0020		0.0516	0.0500	0	103.2	0.05220	1.16	06/05/2023
Calcium		0.100	S	104	2.500	102.2	66.8	103.4	0.46	06/05/2023
Chromium		0.0050		0.196	0.2000	0	98.2	0.1972	0.36	06/05/2023
Iron		0.0400		2.41	2.000	0.2952	105.7	2.400	0.42	06/05/2023
Lead		0.0150		0.487	0.5000	0	97.4	0.4939	1.37	06/05/2023
Lithium		0.0050		0.617	0.5000	0.002900	122.9	0.6439	4.20	06/14/2023
Magnesium		0.0500		41.8	2.500	39.45	93.3	41.69	0.22	06/05/2023
Manganese		0.0070		0.596	0.5000	0.1040	98.5	0.5984	0.32	06/05/2023
Molybdenum		0.0100		0.481	0.5000	0	96.3	0.4859	0.93	06/05/2023
Potassium		0.100		4.80	2.500	2.222	102.9	4.764	0.65	06/05/2023
Silicon	*	0.0500	B	7.20	0.5000	6.601	118.9	7.178	0.24	06/07/2023
Sodium		0.0500		42.3	2.500	40.12	88.0	42.08	0.57	06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206857 SampType: MBLK Units mg/L

SampleID: MBLK-206857

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		< 0.0250	0.0127	0	0	-100	100	06/05/2023
Aluminum		0.0250		< 0.0250	0.0127	0	0	-100	100	06/02/2023
Arsenic		0.0250		< 0.0250	0.0087	0	0	-100	100	06/05/2023
Arsenic		0.0250		< 0.0250	0.0087	0	0	-100	100	06/02/2023
Barium		0.0025		< 0.0025	0.0007	0	0	-100	100	06/02/2023
Barium		0.0025		< 0.0025	0.0007	0	0	-100	100	06/05/2023
Beryllium		0.0005		< 0.0005	0.0002	0	0	-100	100	06/02/2023
Beryllium		0.0005		< 0.0005	0.0002	0	0	-100	100	06/05/2023
Boron		0.0200		< 0.0200	0.0090	0	0	-100	100	06/02/2023
Boron		0.0200		< 0.0200	0.0090	0	0	-100	100	06/05/2023
Cadmium		0.0020		< 0.0020	0.0005	0	0	-100	100	06/05/2023
Cadmium		0.0020		< 0.0020	0.0005	0	0	-100	100	06/02/2023
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	06/05/2023
Chromium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/05/2023
Chromium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/02/2023
Copper		0.0050		< 0.0050	0.0013	0	0	-100	100	06/05/2023
Copper		0.0050		< 0.0050	0.0013	0	0	-100	100	06/02/2023
Iron		0.0400		< 0.0400	0.0200	0	0	-100	100	06/05/2023
Iron		0.0400		< 0.0400	0.0200	0	0	-100	100	06/02/2023
Lead		0.0150		< 0.0150	0.0040	0	0	-100	100	06/05/2023
Lead		0.0150		< 0.0150	0.0040	0	0	-100	100	06/02/2023
Lithium	*	0.0050		< 0.0050	0.0019	0	0	-100	100	06/14/2023
Lithium	*	0.0050		< 0.0050	0.0019	0	0	-100	100	06/02/2023
Lithium	*	0.0050		< 0.0050	0.0019	0	0	-100	100	06/05/2023
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	06/02/2023
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	06/05/2023
Manganese		0.0070		< 0.0070	0.0025	0	0	-100	100	06/05/2023
Manganese		0.0070		< 0.0070	0.0025	0	0	-100	100	06/02/2023
Molybdenum		0.0100		< 0.0100	0.0037	0	0	-100	100	06/02/2023
Molybdenum		0.0100		< 0.0100	0.0037	0	0	-100	100	06/05/2023
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	06/05/2023
Silicon	*	0.0500	S	0.0543	0.0122	0	445.1	-100	100	06/09/2023
Sodium		0.0500		< 0.0500	0.0180	0	0	-100	100	06/05/2023
Sodium		0.0500	JS	0.023	0.0180	0	128.3	-100	100	06/02/2023
Zinc		0.0100		< 0.0100	0.0050	0	0	-100	100	06/05/2023
Zinc		0.0100		< 0.0100	0.0050	0	0	-100	100	06/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206857 SampType: MBLK Units mg/L

SampleID: MBLK-206857

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
----------	------	----	------	--------	-------	-------------	------	-----------	------------	---------------



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206857 SampType: LCS Units mg/L

SampleID: LCS-206857

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		2.03	2.000	0	101.5	85	115	06/05/2023
Aluminum		0.0250		1.95	2.000	0	97.5	85	115	06/02/2023
Arsenic		0.0250		0.528	0.5000	0	105.5	85	115	06/02/2023
Arsenic		0.0250		0.566	0.5000	0	113.3	85	115	06/05/2023
Barium		0.0025		2.18	2.000	0	109.0	85	115	06/05/2023
Barium		0.0025		2.05	2.000	0	102.5	85	115	06/02/2023
Beryllium		0.0005		0.0507	0.0500	0	101.4	85	115	06/02/2023
Beryllium		0.0005		0.0543	0.0500	0	108.6	85	115	06/05/2023
Boron		0.0200		0.507	0.5000	0	101.3	85	115	06/02/2023
Boron		0.0200		0.531	0.5000	0	106.1	85	115	06/05/2023
Cadmium		0.0020		0.0568	0.0500	0	113.6	85	115	06/05/2023
Cadmium		0.0020		0.0511	0.0500	0	102.2	85	115	06/02/2023
Calcium		0.100		2.78	2.500	0	111.0	85	115	06/05/2023
Chromium		0.0050		0.205	0.2000	0	102.4	85	115	06/02/2023
Chromium		0.0050		0.216	0.2000	0	108.2	85	115	06/05/2023
Copper		0.0050		0.257	0.2500	0	102.9	85	115	06/02/2023
Copper		0.0050		0.261	0.2500	0	104.3	85	115	06/05/2023
Iron		0.0400		2.18	2.000	0	109.0	85	115	06/05/2023
Iron		0.0400		2.07	2.000	0	103.5	85	115	06/02/2023
Lead		0.0150		0.508	0.5000	0	101.6	85	115	06/02/2023
Lead		0.0150		0.550	0.5000	0	110.1	85	115	06/05/2023
Lithium	*	0.0050		0.533	0.5000	0	106.7	85	115	06/02/2023
Lithium	*	0.0050		0.546	0.5000	0	109.1	85	115	06/05/2023
Lithium	*	0.0050		0.550	0.5000	0	110.0	85	115	06/15/2023
Magnesium		0.0500		2.57	2.500	0	102.7	85	115	06/05/2023
Magnesium		0.0500		2.39	2.500	0	95.5	85	115	06/02/2023
Manganese		0.0070		0.513	0.5000	0	102.7	85	115	06/02/2023
Manganese		0.0070		0.544	0.5000	0	108.8	85	115	06/05/2023
Molybdenum		0.0100		0.524	0.5000	0	104.9	85	115	06/05/2023
Molybdenum		0.0100		0.495	0.5000	0	99.0	85	115	06/02/2023
Potassium		0.100		2.62	2.500	0	105.0	85	115	06/05/2023
Silicon	*	0.0500	B	0.521	0.5000	0	104.1	85	115	06/09/2023
Sodium		0.0500		2.55	2.500	0	101.9	85	115	06/05/2023
Sodium		0.0500	B	2.46	2.500	0	98.5	85	115	06/02/2023
Zinc		0.0100		0.538	0.5000	0	107.6	85	115	06/05/2023
Zinc		0.0100		0.507	0.5000	0	101.4	85	115	06/02/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206857 SampType: LCS Units mg/L

SampleID: LCS-206857

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
----------	------	----	------	--------	-------	-------------	------	-----------	------------	---------------

Batch 206857 SampType: MS Units mg/L

SampleID: 23051600-032CMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		2.12	2.000	0	106.0	75	125	06/05/2023
Arsenic		0.0250		0.596	0.5000	0	119.2	75	125	06/05/2023
Barium		0.0025		2.30	2.000	0.08020	111.0	75	125	06/05/2023
Beryllium		0.0005		0.0562	0.0500	0	112.4	75	125	06/05/2023
Boron		0.0200		0.949	0.5000	0.3785	114.2	75	125	06/05/2023
Cadmium		0.0020		0.0567	0.0500	0	113.4	75	125	06/05/2023
Calcium		0.100	S	95.9	2.500	88.19	308.4	75	125	06/05/2023
Chromium		0.0050		0.223	0.2000	0	111.3	75	125	06/05/2023
Iron		0.0400		2.23	2.000	0	111.5	75	125	06/05/2023
Lead		0.0150		0.556	0.5000	0	111.3	75	125	06/05/2023
Lithium		0.0050		0.584	0.5000	0.01010	114.7	75	125	06/15/2023
Magnesium		0.0500	S	33.2	2.500	29.12	164.0	75	125	06/05/2023
Manganese		0.0070		0.562	0.5000	0	112.4	75	125	06/05/2023
Molybdenum		0.0100		0.577	0.5000	0.03020	109.4	75	125	06/05/2023
Potassium		0.100		7.79	2.500	4.870	116.8	75	125	06/05/2023
Silicon	*	0.0500	BS	7.09	0.5000	6.449	128.7	75	125	06/09/2023
Sodium		0.0500	S	58.9	2.500	53.10	232.0	75	125	06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch	206857	SampType:	MSD	Units	mg/L	RPD Limit: 20					Date
SampleID:	23051600-032CMSD										Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Aluminum		0.0250		2.02	2.000	0	101.0	2.120	4.83		06/05/2023
Arsenic		0.0250		0.562	0.5000	0	112.4	0.5958	5.82		06/05/2023
Barium		0.0025		2.19	2.000	0.08020	105.5	2.300	4.90		06/05/2023
Beryllium		0.0005		0.0535	0.0500	0	107.0	0.05620	4.92		06/05/2023
Boron		0.0200		0.903	0.5000	0.3785	105.0	0.9494	4.98		06/05/2023
Cadmium		0.0020		0.0546	0.0500	0	109.2	0.05670	3.77		06/05/2023
Calcium		0.100		90.8	2.500	88.19	102.8	95.90	5.51		06/05/2023
Chromium		0.0050		0.213	0.2000	0	106.4	0.2226	4.45		06/05/2023
Iron		0.0400		2.12	2.000	0	106.0	2.230	5.06		06/05/2023
Lead		0.0150		0.534	0.5000	0	106.8	0.5565	4.15		06/05/2023
Lithium		0.0050		0.582	0.5000	0.01010	114.3	0.5838	0.39		06/15/2023
Magnesium		0.0500		31.6	2.500	29.12	99.2	33.22	5.00		06/05/2023
Manganese		0.0070		0.534	0.5000	0	106.9	0.5621	5.03		06/05/2023
Molybdenum		0.0100		0.547	0.5000	0.03020	103.3	0.5771	5.41		06/05/2023
Potassium		0.100		7.43	2.500	4.870	102.3	7.790	4.77		06/05/2023
Silicon	*	0.0500	B	7.02	0.5000	6.449	114.4	7.092	1.01		06/09/2023
Sodium		0.0500		55.9	2.500	53.10	112.4	58.90	5.21		06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206857 SampType: MS Units mg/L

SampleID: 23051600-037CMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		2.06	2.000	0	103.0	75	125	06/05/2023
Arsenic		0.0250		0.576	0.5000	0	115.2	75	125	06/05/2023
Barium		0.0025		2.21	2.000	0.05370	107.8	75	125	06/05/2023
Beryllium		0.0005		0.0548	0.0500	0	109.6	75	125	06/05/2023
Boron		0.0200		0.825	0.5000	0.2937	106.2	75	125	06/05/2023
Cadmium		0.0020		0.0558	0.0500	0	111.6	75	125	06/05/2023
Calcium		0.100	S	87.7	2.500	85.94	70.4	75	125	06/05/2023
Chromium		0.0050		0.217	0.2000	0	108.7	75	125	06/05/2023
Iron		0.0400		2.19	2.000	0.02510	108.2	75	125	06/05/2023
Lead		0.0150		0.542	0.5000	0	108.5	75	125	06/05/2023
Lithium		0.0050		0.579	0.5000	0.01080	113.7	75	125	06/15/2023
Magnesium		0.0500		33.8	2.500	31.65	86.8	75	125	06/05/2023
Manganese		0.0070		0.547	0.5000	0	109.4	75	125	06/05/2023
Molybdenum		0.0100		0.554	0.5000	0.02230	106.3	75	125	06/05/2023
Potassium		0.100		7.63	2.500	5.112	100.7	75	125	06/05/2023
Silicon	*	0.0500	BS	8.97	0.5000	8.193	156.0	75	125	06/09/2023
Sodium		0.0500		46.8	2.500	44.50	93.2	75	125	06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch	206857	SampType:	MSD	Units				mg/L	RPD Limit: 20		
SampleID: 23051600-037CMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Aluminum		0.0250		1.97	2.000	0	98.5	2.060	4.43	06/05/2023	
Arsenic		0.0250		0.562	0.5000	0	112.4	0.5760	2.46	06/05/2023	
Barium		0.0025		2.14	2.000	0.05370	104.3	2.210	3.22	06/05/2023	
Beryllium		0.0005		0.0529	0.0500	0	105.8	0.05480	3.53	06/05/2023	
Boron		0.0200		0.803	0.5000	0.2937	101.9	0.8249	2.69	06/05/2023	
Cadmium		0.0020		0.0536	0.0500	0	107.2	0.05580	4.02	06/05/2023	
Calcium		0.100	S	84.8	2.500	85.94	-46.0	87.70	3.37	06/05/2023	
Chromium		0.0050		0.210	0.2000	0	105.0	0.2173	3.37	06/05/2023	
Iron		0.0400		2.12	2.000	0.02510	104.7	2.190	3.25	06/05/2023	
Lead		0.0150		0.528	0.5000	0	105.6	0.5423	2.67	06/05/2023	
Lithium		0.0050		0.578	0.5000	0.01080	113.4	0.5972	3.30	06/15/2023	
Magnesium		0.0500	S	32.8	2.500	31.65	46.2	33.82	3.05	06/05/2023	
Manganese		0.0070		0.530	0.5000	0	106.1	0.5469	3.04	06/05/2023	
Molybdenum		0.0100		0.534	0.5000	0.02230	102.3	0.5540	3.75	06/05/2023	
Potassium		0.100		7.46	2.500	5.112	94.1	7.630	2.19	06/05/2023	
Silicon	*	0.0500	BS	9.03	0.5000	8.193	167.7	8.973	0.65	06/09/2023	
Sodium		0.0500	S	45.8	2.500	44.50	50.4	46.83	2.31	06/05/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206885		SampType: MBLK		Units mg/L							Date
SampID: MBLK-206885											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Aluminum		0.0250		< 0.0250	0.0127	0	0	-100	100	06/06/2023	
Aluminum		0.0250		< 0.0250	0.0127	0	0	-100	100	06/07/2023	
Arsenic		0.0250		< 0.0250	0.0087	0	0	-100	100	06/06/2023	
Arsenic		0.0250		< 0.0250	0.0087	0	0	-100	100	06/07/2023	
Barium		0.0025		< 0.0025	0.0007	0	0	-100	100	06/07/2023	
Barium		0.0025		< 0.0025	0.0007	0	0	-100	100	06/06/2023	
Beryllium		0.0005		< 0.0005	0.0002	0	0	-100	100	06/07/2023	
Beryllium		0.0005		< 0.0005	0.0002	0	0	-100	100	06/06/2023	
Boron		0.0200		< 0.0200	0.0090	0	0	-100	100	06/07/2023	
Boron		0.0200		< 0.0200	0.0090	0	0	-100	100	06/06/2023	
Cadmium		0.0020		< 0.0020	0.0005	0	0	-100	100	06/07/2023	
Cadmium		0.0020		< 0.0020	0.0005	0	0	-100	100	06/06/2023	
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	06/06/2023	
Chromium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/07/2023	
Chromium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/06/2023	
Copper		0.0050		< 0.0050	0.0013	0	0	-100	100	06/07/2023	
Copper		0.0050	J	0.0013	0.0013	0	100.0	-100	100	06/06/2023	
Iron		0.0400		< 0.0400	0.0200	0	0	-100	100	06/06/2023	
Iron		0.0400		< 0.0400	0.0200	0	0	-100	100	06/07/2023	
Lead		0.0150		< 0.0150	0.0040	0	0	-100	100	06/06/2023	
Lead		0.0150		< 0.0150	0.0040	0	0	-100	100	06/07/2023	
Lithium	*	0.0050		< 0.0050	0.0019	0	0	-100	100	06/07/2023	
Lithium	*	0.0050		< 0.0050	0.0019	0	0	-100	100	06/14/2023	
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	06/07/2023	
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	06/06/2023	
Manganese		0.0070		< 0.0070	0.0025	0	0	-100	100	06/06/2023	
Manganese		0.0070		< 0.0070	0.0025	0	0	-100	100	06/07/2023	
Molybdenum		0.0100		< 0.0100	0.0037	0	0	-100	100	06/06/2023	
Molybdenum		0.0100		< 0.0100	0.0037	0	0	-100	100	06/07/2023	
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	06/06/2023	
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	06/07/2023	
Silicon	*	0.0500	JS	0.049	0.0122	0	404.1	-100	100	06/07/2023	
Sodium		0.0500		< 0.0500	0.0180	0	0	-100	100	06/07/2023	
Sodium		0.0500		< 0.0500	0.0180	0	0	-100	100	06/06/2023	
Zinc		0.0100		< 0.0100	0.0050	0	0	-100	100	06/07/2023	
Zinc		0.0100		< 0.0100	0.0050	0	0	-100	100	06/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206885 SampType: MBLK Units mg/L

SampleID: MBLK-206885

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
----------	------	----	------	--------	-------	-------------	------	-----------	------------	---------------



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206885		SampType: LCS		Units mg/L							
SampID: LCS-206885											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Aluminum		0.0250		1.88	2.000	0	94.1	85	115	06/07/2023	
Aluminum		0.0250		1.90	2.000	0	95.0	85	115	06/06/2023	
Arsenic		0.0250		0.529	0.5000	0	105.7	85	115	06/06/2023	
Arsenic		0.0250		0.511	0.5000	0	102.2	85	115	06/07/2023	
Barium		0.0025		1.98	2.000	0	99.2	85	115	06/06/2023	
Barium		0.0025		1.97	2.000	0	98.4	85	115	06/07/2023	
Beryllium		0.0005		0.0512	0.0500	0	102.4	85	115	06/06/2023	
Beryllium		0.0005		0.0489	0.0500	0	97.8	85	115	06/07/2023	
Boron		0.0200		0.505	0.5000	0	101.0	85	115	06/06/2023	
Boron		0.0200		0.488	0.5000	0	97.6	85	115	06/07/2023	
Cadmium		0.0020		0.0550	0.0500	0	110.0	85	115	06/06/2023	
Cadmium		0.0020		0.0490	0.0500	0	98.0	85	115	06/07/2023	
Calcium		0.100		2.60	2.500	0	104.1	85	115	06/06/2023	
Chromium		0.0050		0.205	0.2000	0	102.4	85	115	06/06/2023	
Chromium		0.0050		0.197	0.2000	0	98.5	85	115	06/07/2023	
Copper		0.0050		0.246	0.2500	0	98.4	85	115	06/06/2023	
Copper		0.0050		0.248	0.2500	0	99.2	85	115	06/07/2023	
Iron		0.0400		2.06	2.000	0	103.0	85	115	06/06/2023	
Iron		0.0400		1.96	2.000	0	98.1	85	115	06/07/2023	
Lead		0.0150		0.490	0.5000	0	98.0	85	115	06/07/2023	
Lead		0.0150		0.518	0.5000	0	103.7	85	115	06/06/2023	
Lithium	*	0.0050		0.513	0.5000	0	102.6	85	115	06/07/2023	
Lithium	*	0.0050	S	0.613	0.5000	0	122.6	85	115	06/14/2023	
Lithium	*	0.0050		0.568	0.5000	0	113.5	85	115	06/15/2023	
Magnesium		0.0500		2.47	2.500	0	98.7	85	115	06/06/2023	
Magnesium		0.0500		2.45	2.500	0	98.1	85	115	06/07/2023	
Manganese		0.0070		0.498	0.5000	0	99.6	85	115	06/07/2023	
Manganese		0.0070		0.512	0.5000	0	102.3	85	115	06/06/2023	
Molybdenum		0.0100		0.492	0.5000	0	98.3	85	115	06/06/2023	
Molybdenum		0.0100		0.475	0.5000	0	95.0	85	115	06/07/2023	
Potassium		0.100		2.50	2.500	0	100.1	85	115	06/06/2023	
Potassium		0.100		2.75	2.500	0	109.9	85	115	06/07/2023	
Silicon	*	0.0500	B	0.557	0.5000	0	111.5	85	115	06/07/2023	
Sodium		0.0500		2.49	2.500	0	99.6	85	115	06/06/2023	
Sodium		0.0500		2.51	2.500	0	100.5	85	115	06/07/2023	
Zinc		0.0100		0.492	0.5000	0	98.3	85	115	06/07/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206885 SampType: LCS Units mg/L

SampleID: LCS-206885

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Zinc		0.0100		0.506	0.5000	0	101.2	85	115	06/06/2023

Batch 206885 SampType: MS Units mg/L

SampleID: 23051600-029CMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		2.03	2.000	0	101.5	75	125	06/06/2023
Arsenic		0.0250		0.553	0.5000	0	110.6	75	125	06/06/2023
Barium		0.0025		2.14	2.000	0.03980	105.0	75	125	06/06/2023
Boron		0.0200		2.51	0.5000	1.928	116.2	75	125	06/06/2023
Cadmium		0.0020		0.0532	0.0500	0	106.4	75	125	06/06/2023
Calcium		0.100	S	71.0	2.500	65.93	201.2	75	125	06/06/2023
Chromium		0.0050		0.208	0.2000	0	104.2	75	125	06/06/2023
Copper		0.0050		0.262	0.2500	0.002000	104.2	75	125	06/06/2023
Iron		0.0400		2.08	2.000	0	104.0	75	125	06/06/2023
Lead		0.0150		0.522	0.5000	0	104.5	75	125	06/06/2023
Magnesium		0.0500	S	31.9	2.500	28.49	138.1	75	125	06/06/2023
Molybdenum		0.0100		0.565	0.5000	0.04800	103.4	75	125	06/06/2023
Potassium		0.100		9.25	2.500	6.688	102.6	75	125	06/06/2023
Sodium		0.0500	S	47.4	2.500	43.95	137.2	75	125	06/06/2023
Zinc		0.0100		0.530	0.5000	0	106.1	75	125	06/06/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 206885		SampType: MSD		Units mg/L				RPD Limit: 20		
SampleID: 23051600-029CMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Aluminum		0.0250		2.03	2.000	0	101.5	2.030	0.00	06/06/2023
Arsenic		0.0250		0.561	0.5000	0	112.3	0.5532	1.47	06/06/2023
Barium		0.0025		2.14	2.000	0.03980	105.0	2.140	0.00	06/06/2023
Boron		0.0200		2.52	0.5000	1.928	119.3	2.510	0.60	06/06/2023
Cadmium		0.0020		0.0534	0.0500	0	106.8	0.05320	0.38	06/06/2023
Calcium		0.100	S	71.6	2.500	65.93	225.2	70.96	0.84	06/06/2023
Chromium		0.0050		0.208	0.2000	0	104.2	0.2083	0.00	06/06/2023
Copper		0.0050		0.261	0.2500	0.002000	103.7	0.2625	0.46	06/06/2023
Iron		0.0400		2.08	2.000	0	104.0	2.080	0.00	06/06/2023
Lead		0.0150		0.525	0.5000	0	105.0	0.5223	0.50	06/06/2023
Magnesium		0.0500	S	32.1	2.500	28.49	145.7	31.94	0.59	06/06/2023
Molybdenum		0.0100		0.565	0.5000	0.04800	103.3	0.5649	0.05	06/06/2023
Potassium		0.100		9.26	2.500	6.688	103.0	9.252	0.13	06/06/2023
Sodium		0.0500	S	47.5	2.500	43.95	140.8	47.38	0.19	06/06/2023
Zinc		0.0100		0.530	0.5000	0	106.0	0.5304	0.04	06/06/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 207204 SampType: MBLK Units mg/L

SampID: MBLK-207204

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		< 0.0250	0.0127	0	0	-100	100	06/14/2023
Aluminum		0.0250		< 0.0250	0.0127	0	0	-100	100	06/13/2023
Arsenic		0.0250		< 0.0250	0.0087	0	0	-100	100	06/14/2023
Arsenic		0.0250		< 0.0250	0.0087	0	0	-100	100	06/13/2023
Barium		0.0025		< 0.0025	0.0007	0	0	-100	100	06/13/2023
Barium		0.0025		< 0.0025	0.0007	0	0	-100	100	06/14/2023
Beryllium		0.0005		< 0.0005	0.0002	0	0	-100	100	06/14/2023
Beryllium		0.0005		< 0.0005	0.0002	0	0	-100	100	06/13/2023
Boron		0.0200		< 0.0200	0.0090	0	0	-100	100	06/14/2023
Boron		0.0200		< 0.0200	0.0090	0	0	-100	100	06/13/2023
Cadmium		0.0020		< 0.0020	0.0005	0	0	-100	100	06/13/2023
Cadmium		0.0020		< 0.0020	0.0005	0	0	-100	100	06/14/2023
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	06/13/2023
Calcium		0.100		< 0.100	0.0350	0	0	-100	100	06/14/2023
Chromium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/13/2023
Chromium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/14/2023
Copper		0.0050		< 0.0050	0.0013	0	0	-100	100	06/14/2023
Copper		0.0050		< 0.0050	0.0013	0	0	-100	100	06/13/2023
Iron		0.0400		< 0.0400	0.0200	0	0	-100	100	06/14/2023
Iron		0.0400		< 0.0400	0.0200	0	0	-100	100	06/13/2023
Lead		0.0150		< 0.0150	0.0040	0	0	-100	100	06/14/2023
Lead		0.0150		< 0.0150	0.0014	0	0	-100	100	06/13/2023
Lithium	*	0.0050	S	0.0864	0.0019	0	4547	-100	100	06/16/2023
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	06/13/2023
Magnesium		0.0500		< 0.0500	0.0055	0	0	-100	100	06/14/2023
Manganese		0.0070		< 0.0070	0.0025	0	0	-100	100	06/14/2023
Manganese		0.0070		< 0.0070	0.0025	0	0	-100	100	06/13/2023
Molybdenum		0.0100		< 0.0100	0.0037	0	0	-100	100	06/13/2023
Molybdenum		0.0100		< 0.0100	0.0037	0	0	-100	100	06/14/2023
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	06/13/2023
Potassium		0.100		< 0.100	0.0400	0	0	-100	100	06/14/2023
Silicon	*	0.0500		< 0.0500	0.0122	0	0	-100	100	06/14/2023
Sodium		0.0500		< 0.0500	0.0180	0	0	-100	100	06/14/2023
Sodium		0.0500		< 0.0500	0.0180	0	0	-100	100	06/13/2023
Zinc		0.0100		< 0.0100	0.0050	0	0	-100	100	06/13/2023
Zinc		0.0100		< 0.0100	0.0050	0	0	-100	100	06/14/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 207204 SampType: MBLK Units mg/L

SampleID: MBLK-207204

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
----------	------	----	------	--------	-------	-------------	------	-----------	------------	---------------



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 207204 SampType: LCS Units mg/L

SampleID: LCS-207204

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Aluminum		0.0250		1.96	2.000	0	98.1	85	115	06/13/2023
Aluminum		0.0250		1.92	2.000	0	96.1	85	115	06/14/2023
Arsenic		0.0250		0.521	0.5000	0	104.2	85	115	06/13/2023
Arsenic		0.0250		0.516	0.5000	0	103.1	85	115	06/14/2023
Barium		0.0025		2.10	2.000	0	105.0	85	115	06/13/2023
Barium		0.0025		1.95	2.000	0	97.3	85	115	06/14/2023
Beryllium		0.0005		0.0512	0.0500	0	102.4	85	115	06/13/2023
Beryllium		0.0005		0.0494	0.0500	0	98.8	85	115	06/14/2023
Boron		0.0200		0.517	0.5000	0	103.5	85	115	06/13/2023
Boron		0.0200		0.495	0.5000	0	99.0	85	115	06/14/2023
Cadmium		0.0020		0.0520	0.0500	0	104.0	85	115	06/13/2023
Cadmium		0.0020		0.0501	0.0500	0	100.2	85	115	06/14/2023
Calcium		0.100		2.59	2.500	0	103.6	85	115	06/14/2023
Calcium		0.100		2.67	2.500	0	106.7	85	115	06/13/2023
Chromium		0.0050		0.207	0.2000	0	103.7	85	115	06/13/2023
Chromium		0.0050		0.197	0.2000	0	98.7	85	115	06/14/2023
Copper		0.0050		0.254	0.2500	0	101.6	85	115	06/14/2023
Copper		0.0050		0.256	0.2500	0	102.6	85	115	06/13/2023
Iron		0.0400		2.15	2.000	0	107.5	85	115	06/13/2023
Iron		0.0400		1.97	2.000	0	98.6	85	115	06/14/2023
Lead		0.0150		0.515	0.5000	0	103.1	85	115	06/13/2023
Lead		0.0150		0.494	0.5000	0	98.8	85	115	06/14/2023
Lithium	*	0.0050	B	0.544	0.5000	0	108.8	85	115	06/16/2023
Magnesium		0.0500		2.42	2.500	0	96.9	85	115	06/13/2023
Magnesium		0.0500		2.45	2.500	0	97.8	85	115	06/14/2023
Manganese		0.0070		0.494	0.5000	0	98.8	85	115	06/14/2023
Manganese		0.0070		0.529	0.5000	0	105.8	85	115	06/13/2023
Molybdenum		0.0100		0.481	0.5000	0	96.3	85	115	06/14/2023
Molybdenum		0.0100		0.504	0.5000	0	100.8	85	115	06/13/2023
Potassium		0.100		2.60	2.500	0	104.0	85	115	06/13/2023
Potassium		0.100		2.43	2.500	0	97.3	85	115	06/14/2023
Silicon	*	0.0500		0.501	0.5000	0	100.3	85	115	06/14/2023
Sodium		0.0500		2.45	2.500	0	98.1	85	115	06/13/2023
Sodium		0.0500		2.41	2.500	0	96.5	85	115	06/14/2023
Zinc		0.0100		0.498	0.5000	0	99.6	85	115	06/14/2023
Zinc		0.0100		0.507	0.5000	0	101.4	85	115	06/13/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051600
Report Date: 21-Jun-23

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 207204 SampType: LCS Units mg/L
SampleID: LCS-207204

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
----------	------	----	------	--------	-------	-------------	------	-----------	------------	---------------

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch 206871 SampType: MBLK Units mg/L
SampleID: MBLK-206871

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		< 0.0010	0.0004	0	0	-100	100	06/05/2023
Cobalt		0.0010		< 0.0010	0.0001	0	0	-100	100	06/05/2023
Selenium		0.0010		< 0.0010	0.0006	0	0	-100	100	06/05/2023
Thallium		0.0020		< 0.0020	0.0010	0	0	-100	100	06/05/2023
Vanadium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/05/2023

Batch 206871 SampType: LCS Units mg/L
SampleID: LCS-206871

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		0.447	0.5000	0	89.5	80	120	06/05/2023
Cobalt		0.0010		0.461	0.5000	0	92.3	80	120	06/05/2023
Selenium		0.0010		0.451	0.5000	0	90.2	80	120	06/05/2023
Thallium		0.0020		0.218	0.2500	0	87.2	80	120	06/05/2023
Vanadium		0.0050		0.456	0.5000	0	91.2	80	120	06/05/2023

Batch 206871 SampType: MS Units mg/L
SampleID: 23051600-003DMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Selenium		0.0010		0.473	0.5000	0.002202	94.2	75	125	06/05/2023
Vanadium		0.0050		0.456	0.5000	0	91.1	75	125	06/05/2023

Batch 206871 SampType: MSD Units mg/L
SampleID: 23051600-003DMSD

RPD Limit: 20

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Selenium		0.0010		0.456	0.5000	0.002202	90.8	0.4734	3.68	06/05/2023
Vanadium		0.0050		0.451	0.5000	0	90.1	0.4557	1.12	06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch 206871		SampType: MS		Units mg/L						
SampID: 23051600-008EMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		0.449	0.5000	0	89.8	75	125	06/05/2023
Cobalt		0.0010		0.435	0.5000	0.0006618	87.0	75	125	06/05/2023
Selenium		0.0010		0.459	0.5000	0.001402	91.5	75	125	06/05/2023
Thallium		0.0020		0.219	0.2500	0	87.6	75	125	06/05/2023
Vanadium		0.0050		0.446	0.5000	0	89.1	75	125	06/05/2023

Batch 206871		SampType: MSD		Units mg/L					RPD Limit: 20		
SampID: 23051600-008EMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Antimony		0.0010		0.453	0.5000	0	90.6	0.4491	0.89	06/05/2023	
Cobalt		0.0010		0.423	0.5000	0.0006618	84.5	0.4354	2.89	06/05/2023	
Selenium		0.0010		0.442	0.5000	0.001402	88.0	0.4590	3.85	06/05/2023	
Thallium		0.0020		0.215	0.2500	0	86.2	0.2190	1.63	06/05/2023	
Vanadium		0.0050		0.431	0.5000	0	86.2	0.4457	3.38	06/05/2023	

Batch 206873		SampType: MBLK		Units mg/L							
SampID: MBLK-206873											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Antimony		0.0010		< 0.0010	0.0004	0	0	-100	100	06/05/2023	
Cobalt		0.0010		< 0.0010	0.0001	0	0	-100	100	06/05/2023	
Selenium		0.0010		< 0.0010	0.0006	0	0	-100	100	06/05/2023	
Thallium		0.0020		< 0.0020	0.0010	0	0	-100	100	06/05/2023	
Vanadium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/05/2023	

Batch	206873	SampType:	LCS	Units mg/L							
SampID:		LCS-206873									
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Antimony		0.0010		0.447	0.5000	0	89.4	80	120	06/05/2023	
Cobalt		0.0010		0.463	0.5000	0	92.6	80	120	06/05/2023	
Selenium		0.0010		0.442	0.5000	0	88.4	80	120	06/05/2023	
Thallium		0.0020		0.220	0.2500	0	87.9	80	120	06/05/2023	
Vanadium		0.0050		0.450	0.5000	0	89.9	80	120	06/05/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6020A, METALS BY ICPMS (DISSOLVED)

Batch 206873		SampType: MS		Units mg/L						
SampID: 23051600-044EMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		0.905	1.000	0	90.5	75	125	06/05/2023
Cobalt		0.0010		0.812	1.000	0	81.2	75	125	06/05/2023
Selenium		0.0010		0.807	1.000	0	80.7	75	125	06/05/2023
Thallium		0.0020		0.406	0.5000	0	81.2	75	125	06/05/2023
Vanadium		0.0050		0.813	1.000	0	81.3	75	125	06/05/2023

Batch 206873		SampType: MSD		Units mg/L					RPD Limit: 20		Date Analyzed
SampID: 23051600-044EMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Antimony			0.0010		0.922	1.000	0	92.2	0.9050	1.85	06/05/2023
Cobalt			0.0010		0.814	1.000	0	81.4	0.8117	0.24	06/05/2023
Selenium			0.0010		0.790	1.000	0	79.0	0.8065	2.08	06/05/2023
Thallium			0.0020		0.403	0.5000	0	80.6	0.4060	0.74	06/05/2023
Vanadium			0.0050		0.814	1.000	0	81.4	0.8126	0.16	06/05/2023

Batch 206891		SampType: MBLK		Units mg/L						
SampID: MBLK-206891										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		< 0.0010	0.0004	0	0	-100	100	06/06/2023
Cobalt		0.0010		< 0.0010	0.0001	0	0	-100	100	06/06/2023
Selenium		0.0010		< 0.0010	0.0006	0	0	-100	100	06/06/2023
Thallium		0.0020		< 0.0020	0.0010	0	0	-100	100	06/07/2023
Vanadium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/06/2023

Batch 206891		SampType: LCS		Units mg/L							
SampID: LCS-206891											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Antimony		0.0010		0.433	0.5000	0	86.5	80	120	06/06/2023	
Cobalt		0.0010		0.449	0.5000	0	89.8	80	120	06/06/2023	
Selenium		0.0010		0.447	0.5000	0	89.4	80	120	06/06/2023	
Thallium		0.0020		0.211	0.2500	0	84.5	80	120	06/07/2023	
Vanadium		0.0050		0.434	0.5000	0	86.8	80	120	06/06/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 206856 SampType: MBLK Units mg/L
SampID: MBLK-206856

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		< 0.0010	0.0004	0	0	-100	100	06/05/2023
Cobalt		0.0010		< 0.0010	0.0001	0	0	-100	100	06/05/2023
Selenium		0.0010		< 0.0010	0.0006	0	0	-100	100	06/05/2023
Thallium		0.0020		< 0.0020	0.0010	0	0	-100	100	06/05/2023
Vanadium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/05/2023

Batch 206856 SampType: LCS Units mg/L
SampID: LCS-206856

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		0.493	0.5000	0	98.5	80	120	06/05/2023
Cobalt		0.0010		0.469	0.5000	0	93.8	80	120	06/05/2023
Selenium		0.0010		0.494	0.5000	0	98.8	80	120	06/05/2023
Thallium		0.0020		0.229	0.2500	0	91.6	80	120	06/05/2023
Vanadium		0.0050		0.468	0.5000	0	93.6	80	120	06/05/2023

Batch 206856 SampType: MS Units mg/L
SampID: 23051600-007DMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		0.497	0.5000	0	99.5	75	125	06/05/2023
Cobalt		0.0010		0.461	0.5000	0.004599	91.2	75	125	06/05/2023
Selenium		0.0010		0.491	0.5000	0	98.1	75	125	06/05/2023
Thallium		0.0020		0.237	0.2500	0	94.7	75	125	06/05/2023
Vanadium		0.0050		0.475	0.5000	0	95.0	75	125	06/05/2023

Batch 206856 SampType: MSD Units mg/L
SampID: 23051600-007DMSD

RPD Limit: 20

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Antimony		0.0010		0.489	0.5000	0	97.8	0.4974	1.66	06/05/2023
Cobalt		0.0010		0.461	0.5000	0.004599	91.3	0.4607	0.07	06/05/2023
Selenium		0.0010		0.503	0.5000	0	100.5	0.4905	2.45	06/05/2023
Thallium		0.0020		0.235	0.2500	0	94.1	0.2368	0.69	06/05/2023
Vanadium		0.0050		0.472	0.5000	0	94.4	0.4752	0.64	06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 206856 SampType: MS Units mg/L

SampleID: 23051600-024CMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		0.491	0.5000	0	98.2	75	125	06/05/2023
Cobalt		0.0010		0.479	0.5000	0.001809	95.4	75	125	06/05/2023
Selenium		0.0010		0.522	0.5000	0	104.5	75	125	06/05/2023
Thallium		0.0020		0.240	0.2500	0	95.9	75	125	06/05/2023

Batch 206856 SampType: MSD Units mg/L

RPD Limit: 20

SampleID: 23051600-024CMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Antimony		0.0010		0.503	0.5000	0	100.5	0.4909	2.36	06/05/2023
Cobalt		0.0010		0.492	0.5000	0.001809	98.1	0.4789	2.74	06/05/2023
Selenium		0.0010		0.542	0.5000	0	108.5	0.5223	3.75	06/05/2023
Thallium		0.0020		0.251	0.2500	0	100.5	0.2397	4.75	06/05/2023

Batch 206857 SampType: MBLK Units mg/L

SampleID: MBLK-206857

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		< 0.0010	0.0004	0	0	-100	100	06/05/2023
Cobalt		0.0010		< 0.0010	0.0001	0	0	-100	100	06/05/2023
Selenium		0.0010		< 0.0010	0.0006	0	0	-100	100	06/05/2023
Thallium		0.0020		< 0.0020	0.0010	0	0	-100	100	06/05/2023
Vanadium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/05/2023

Batch 206857 SampType: LCS Units mg/L

SampleID: LCS-206857

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		0.512	0.5000	0	102.4	80	120	06/05/2023
Cobalt		0.0010		0.473	0.5000	0	94.7	80	120	06/05/2023
Selenium		0.0010		0.482	0.5000	0	96.4	80	120	06/05/2023
Thallium		0.0020		0.235	0.2500	0	94.2	80	120	06/05/2023
Vanadium		0.0050		0.471	0.5000	0	94.2	80	120	06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 206857		SampType: MS		Units mg/L							
SampID: 23051600-032CMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Antimony		0.0010		0.505	0.5000	0.0008773	100.8	75	125	06/05/2023	
Cobalt		0.0010		0.462	0.5000	0.0005179	92.3	75	125	06/05/2023	
Selenium		0.0010		0.505	0.5000	0.001397	100.7	75	125	06/05/2023	
Thallium		0.0020		0.238	0.2500	0	95.2	75	125	06/05/2023	

Batch 206857		SampType: MSD		Units mg/L				RPD Limit: 20		
SampID: 23051600-032CMSD										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Antimony		0.0010		0.513	0.5000	0.0008773	102.4	0.5047	1.60	06/05/2023
Cobalt		0.0010		0.466	0.5000	0.0005179	93.1	0.4621	0.85	06/05/2023
Selenium		0.0010		0.516	0.5000	0.001397	103.0	0.5048	2.29	06/05/2023
Thallium		0.0020		0.242	0.2500	0	96.9	0.2379	1.80	06/05/2023

Batch 206857		SampType: MS		Units mg/L						
SampID: 23051600-037CMS										
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		0.514	0.5000	0	102.9	75	125	06/05/2023
Cobalt		0.0010		0.469	0.5000	0.0001901	93.8	75	125	06/05/2023
Selenium		0.0010		0.505	0.5000	0.001439	100.8	75	125	06/05/2023
Thallium		0.0020		0.243	0.2500	0	97.0	75	125	06/05/2023

Batch	206857	SampType:	MSD	Units mg/L					RPD Limit: 20		
SampID: 23051600-037CMSD											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Antimony		0.0010		0.504	0.5000	0	100.8	0.5144	2.00	06/05/2023	
Cobalt		0.0010		0.454	0.5000	0.0001901	90.7	0.4694	3.43	06/05/2023	
Selenium		0.0010		0.478	0.5000	0.001439	95.4	0.5054	5.52	06/05/2023	
Thallium		0.0020		0.237	0.2500	0	94.7	0.2426	2.43	06/05/2023	



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 206885 SampType: MBLK Units mg/L
SampleID: MBLK-206885

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		< 0.0010	0.0004	0	0	-100	100	06/06/2023
Cobalt		0.0010		< 0.0010	0.0001	0	0	-100	100	06/06/2023
Selenium		0.0010		< 0.0010	0.0006	0	0	-100	100	06/06/2023
Thallium		0.0020		< 0.0020	0.0010	0	0	-100	100	06/07/2023
Vanadium		0.0050		< 0.0050	0.0028	0	0	-100	100	06/06/2023

Batch 206885 SampType: LCS Units mg/L
SampleID: LCS-206885

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony		0.0010		0.525	0.5000	0	104.9	80	120	06/06/2023
Cobalt		0.0010		0.512	0.5000	0	102.5	80	120	06/06/2023
Selenium		0.0010		0.547	0.5000	0	109.3	80	120	06/06/2023
Thallium		0.0020		0.232	0.2500	0	92.6	80	120	06/07/2023
Vanadium		0.0050		0.503	0.5000	0	100.7	80	120	06/06/2023

Batch 206885 SampType: MS Units mg/L
SampleID: 23051600-029CMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Selenium		0.0010		0.538	0.5000	0.003991	106.9	75	125	06/06/2023
Vanadium		0.0050		0.494	0.5000	0.005282	97.7	75	125	06/06/2023

Batch 206885 SampType: MSD Units mg/L
SampleID: 23051600-029CMSD

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Selenium		0.0010		0.499	0.5000	0.003991	99.0	0.5384	7.56	06/06/2023
Vanadium		0.0050		0.466	0.5000	0.005282	92.1	0.4935	5.84	06/06/2023

SW-846 7470A (DISSOLVED)

Batch 206867 SampType: MS Units mg/L
SampleID: 23051600-003DMS

Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Mercury		0.00020		0.00497	0.0050	0	99.4	75	125	06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 7470A (DISSOLVED)

Batch 206867		SampType: MSD		Units mg/L				RPD Limit: 15			
SampID: 23051600-003DMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Mercury			0.00020		0.00493	0.0050	0	98.5	0.004970	0.89	06/05/2023

Batch 206893		SampType: MS		Units mg/L							
SampID: 23051600-029DMS											Date Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Mercury		0.00020		0.00513	0.0050	0	102.6	75	125	06/05/2023	

Batch 206893		SampType: MSD		Units mg/L				RPD Limit: 15			Date Analyzed
SampID: 23051600-029DMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Mercury			0.00020		0.00523	0.0050	0	104.5	0.005132	1.85	

SW-846 7470A (TOTAL)

Batch 206867		SampType: MBLK		Units mg/L							
SampID: MBLK-206867											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.00020		< 0.00020	0.0001	0	0	-100	100	06/05/2023	

Batch 206867		SampType: LCS		Units mg/L							
SampID: LCS-206867											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.00020		0.00486	0.0050	0	97.2	85	115	06/05/2023	

Batch 206867		SampType: MS		Units mg/L							
SampID: 23051600-014DMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.00020		0.00502	0.0050	0	100.5	75	125	06/05/2023	

Batch 206867		SampType: MSD		Units mg/L		RPD Limit: 15					
SampID: 23051600-014DMSD											
Analyses		Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Mercury			0.00020		0.00521	0.0050	0	104.1	0.005023	3.59	06/05/2023



Quality Control Results

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

SW-846 7470A (TOTAL)

Batch 206869		SampType: MBLK		Units mg/L							
SampID: MBLK-206869											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.00020		< 0.00020	0.0001	0	0	-100	100	06/05/2023	

Batch 206869		SampType: LCS		Units mg/L							
SampID: LCS-206869											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.00020		0.00490	0.0050	0	98.1	85	115	06/05/2023	

Batch 206869		SampType: MS		Units mg/L							
SampID: 23051600-019CMS											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Mercury		0.00020		0.00521	0.0050	0	104.3	75	125	06/05/2023	

Batch 206869		SampType: MSD		Units mg/L								RPD Limit: 15	Date
SampID: 23051600-019CMSD													Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD				
Mercury		0.00020		0.00501	0.0050	0	100.1	0.005215	4.10				06/05/2023

Batch 206893		SampType: MBLK		Units mg/L							
SampID: MBLK-206893											Date
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Mercury		0.00020		< 0.00020	0.0001	0	0	-100	100	06/05/2023	

Batch 206893		SampType: LCS		Units mg/L							
SampID: LCS-206893											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.00020		0.00511	0.0050	0	102.2	85	115	06/05/2023	

Batch 206893		SampType: MS		Units mg/L							
SampID: 23051600-005DMS											
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Mercury		0.00020		0.00501	0.0050	0	100.2	75	125	06/05/2023	

Batch 206893		SampType: MSD		Units mg/L								RPD Limit: 15	Date
SampID: 23051600-005DMSD													Analyzed
Analyses	Cert	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD				
Mercury		0.00020		0.00476	0.0050	0	95.3	0.005009	5.04				06/05/2023



Receiving Check List

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051600

Client Project: HEN-23Q2

Report Date: 21-Jun-23

Carrier: Joe Riley

Received By: ANC

Completed by:

On:

02-Jun-23

Allison Colin

Reviewed by:

On:

02-Jun-23

Ellie Hopkins

Pages to follow:

Chain of custody

6

Extra pages included

0

Shipping container/cooler in good condition?

Yes ☒

No ☐

Not Present ☐

Temp °C 5.4

Type of thermal preservation?

None ☐

Ice ☒

Blue Ice ☐

Dry Ice ☐

Chain of custody present?

Yes ☒

No ☐

Chain of custody signed when relinquished and received?

Yes ☒

No ☐

Chain of custody agrees with sample labels?

Yes ☒

No ☐

Samples in proper container/bottle?

Yes ☒

No ☐

Sample containers intact?

Yes ☒

No ☐

Sufficient sample volume for indicated test?

Yes ☒

No ☐

All samples received within holding time?

Yes ☒

No ☐

Reported field parameters measured:

Field ☒

Lab ☐

NA ☐

Container/Temp Blank temperature in compliance?

Yes ☒

No ☐

When thermal preservation is required, samples are compliant with a temperature between 0.1°C - 6.0°C, or when samples are received on ice the same day as collected.

Water – at least one vial per sample has zero headspace?

Yes ☒

No ☐

No VOA vials ☐

Water - TOX containers have zero headspace?

Yes ☐

No ☐

No TOX containers ☒

Water - pH acceptable upon receipt?

Yes ☐

No ☒

NA ☐

NPDES/CWA TCN interferences checked/treated in the field?

Yes ☐

No ☒

NA ☐

Any No responses must be detailed below or on the COC.

pH strip #88374/79929. - TWM/acolin - 6/1/2023 3:15:29 PM

Additional HNO₃ (89071) was needed in Field Blank and additional NaOH (81662) was needed in HEN-18&D upon arrival at the laboratory. - TWM/acolin - 6/1/2023 3:15:51 PM

Per Joe Riley, 22 and 22D bottles were switched in the field. - EAH 6/1/23

Samples collected on 6/1/23 were delivered same-day at 14.4C (on ice - LTG 5). - ehurley - 6/5/2023 3:49:12 PM

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page: 1 of 3

ITEM #	Section D Required Client Information	SAMPLE ID (A-Z, 0-9 / .) Sample IDs MUST BE UNIQUE	Valid Matrix Codes MATRIX CODE DRINKING WATER DW WATER WT WASTE WATER WW PRODUCT P SOIL/SOLID SL OIL OL WPPE WP AIR AR OTHER OT TISSUE TS	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives								Analysis Test Y/N ↓ ↑	Requested Analysis Filtered (Y/N)														
						DATE	TIME			Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₅	Methanol	Other		HEN-257-802	HEN-257-803	HEN-257-804	HEN-811-801	HEN-845-802-805	HEN-845-803	HEN-845-804	HEN-CLOSURE-802-805	HEN-CLOSURE-804	HEN-SUP-000	HEN-WPCP-East	HEN-WPCP-West	Residual Chlorine (Y/N)	ADDED HNO ₃ TO DISS. FB ADDED NaOH TO HEX BATH Tax \$8374/99029 Project No./ Lab I.D.	
1	HEN-02								7	3																	23051100 - 001						
2	HEN-03R			5-24-23	1312			10	3	2	2	1														002							
3	HEN-05IR			5-31-23	1517			9	2	2	2	1														003							
4	HEN-05&DR			5-31-23	1458			9	2	2	2	1														004							
5	HEN-07							10	3	2	2	1														005							
6	HEN-08			5-31-23	1510			11	3	3	2	1														006							
7	HEN-08&D			5-31-23	1510			11	3	3	2	1														007							
8	HEN-10			5-31-23	922			10	3	2	2	1														008							
9	HEN-12			5-31-23	1137			10	2	3	2	1														009							
10	HEN-13			5-31-23	1204			10	2	3	2	1														010							
11	HEN-16							6	2	2	2															011							
12	HEN-17							6	2	2	2															012							
13	HEN-18#S			5-31-23	1415			10	3	2	2	1														013							
14	HEN-18&D			5-31-23	1349			10	3	2	2	1														014							
15	HEN-21R			5-31-23	1109			6	2	2	2															015							
16	HEN-22			5-31-23	1401			6	2	2	2															016							
ADDITIONAL COMMENTS		RELINQUISHED BY / AFFILIATION		DATE		TIME		ACCEPTED BY / AFFILIATION		DATE		TIME		SAMPLE CONDITIONS																			
HEN-23Q2 Rev 1		Kb/a3		6/1/23		1201		Ammonia		6/1/23		1201		Y N																			

④ 22 and 22D bottles were switched
in the field per Joe Riley. 204 6/1/83

HENNEPIN POWER PLANT, OLD WESTASH POND

25051600

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:		Page: 2 of 3																					
Company: Vistra Corp		Report To: Brian Voelker		Attention: Jason Stuckey		<table border="1"> <tr> <th colspan="3">REGULATORY AGENCY</th> </tr> <tr> <td>NPDES</td> <td>GROUND WATER</td> <td>DRINKING WATER</td> </tr> <tr> <td>UST</td> <td>RCRA</td> <td>OTHER</td> </tr> <tr> <td>Site Location</td> <td>IL</td> <td></td> </tr> <tr> <td colspan="2">Requested Due Date/TAT: 10 day</td> <td colspan="2">Project Number: 2285</td> <td colspan="2">Profile #:</td> <td colspan="2">STATE:</td> </tr> </table>		REGULATORY AGENCY			NPDES	GROUND WATER	DRINKING WATER	UST	RCRA	OTHER	Site Location	IL		Requested Due Date/TAT: 10 day		Project Number: 2285		Profile #:		STATE:	
REGULATORY AGENCY																											
NPDES	GROUND WATER	DRINKING WATER																									
UST	RCRA	OTHER																									
Site Location	IL																										
Requested Due Date/TAT: 10 day		Project Number: 2285		Profile #:		STATE:																					
Address: 13498 E. 900th St		Copy To: Jason Stuckey		Company Name: Vistra Corp																							
				Address: see Section A																							
Email To: Brian.Voelker@VistraCorp.com		Purchase Order No.:		Quote Reference:																							
Phone: (217) 753-8911 Fax:		Project Name:		Project Manager:																							

ITEM #	Section D Required Client Information		Valid Matrix Codes <u>MATRIX</u> <u>CODE</u>		MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives								$\downarrow$ Analysis Test $\uparrow$ Y/N	Requested Analysis Filtered (Y/N)													
	SAMPLE ID (A-Z, 0-9 / . -) Sample IDs MUST BE UNIQUE		DRINKING WATER DW WATER WT WASTE WATER WW PRODUCT P SOIL/SOLID SL OIL OL WIPE WP AIR AR OTHER OT TISSUE TS	DATE			TIME	Unpreserved			H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other	HEN-257-802		HEN-257-803	HEN-257-804	HEN-811-801	HEN-845-802-805	HEN-845-803	HEN-845-804	HEN-CLOSURE-802-805	HEN-CLOSURE-804	HEN-SUP-000	HEN-WPCP-East	HEN-WPCP-West	Residual Chlorine (Y/N)	Project No./ Lab I.D.	
1	HEN-22&D			5-9-23	1419	6	2	2	2																			23051600-017					
2	HEN-23				1200	6	2	2	2																			018					
3	HEN-25				1259	6	2	2	2																			019					
4	HEN-26				1241	6	2	2	2																			020					
5	HEN-27				0915	6	2	2	2																			021					
6	HEN-30			5-30-23	1509	0																						022					
7	HEN-31			5-30-23	1504	0																						023					
8	HEN-32			5-9-23	0946	6	2	2	2																			024					
9	HEN-33			5-30-23	1515	0																						025					
10	HEN-34			5-31-23	1039	6	2	2	2																			026					
11	HEN-35			5-31-23	1009	6	2	2	2																			027					
12	HEN-36			5-30-23	1528	0																						028					
13	HEN-40#S					9	2	2	2	2	1																	029					
14	HEN-45#S					10	3	2	2	2	1																	030					
15	HEN-46			5-31-23	1100	6	2	2	2																			031					
16	HEN-47			5-31-23	956	6	2	2	2																			032					
ADDITIONAL COMMENTS			RELINQUISHED BY / AFFILIATION			DATE			TIME			ACCEPTED BY / AFFILIATION			DATE			TIME			SAMPLE CONDITIONS												
HEN-23Q2 Rev 1			Teklab			6/1/23			1201			Allison Cole			6/1			1201															
SAMPLER NAME AND SIGNATURE																Temp in °C				Received on ice (Y/N)				Custody Sealed Cooler (Y/N)				Samples Intact (Y/N)					
PRINT Name or SAMPLER: Joe Riley																																	
SIGNATURE of SAMPLER: [Signature]																DATE Signed (MM/DD/YYYY): 6/1/23																	

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

HENNEPIN POWER PLANT, OLD WEST LASH POND

APPENDIX A.

HEN-257-804

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:		Page: 3 of 3	
Company: Vistra Corp		Report To: Brian Voelker		Attention: Jason Stuckey			
Address: 13498 E. 900th St		Copy To: Jason Stuckey		Company Name: Vistra Corp		REGULATORY AGENCY	
Email To: Brian.Voelker@VistraCorp.com		Purchase Order No.:		Address: see Section A		NPDES GROUND WATER DRINKING WATER	
Phone: (217) 753-8911 Fax:		Project Name:		Quote Reference:		UST RCRA OTHER	
Requested Due Date/TAT: 10 day		Project Number: 2285		Project Manager:		Site Location	
				Profile #:		STATE: IL	

ITEM #	Section D Required Client Information	Valid Matrix Codes MATRIX CODE	COLLECTED	DATE	TIME	SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives	Analysis Test	Requested Analysis Filtered (Y/N)												Project No./ Lab I.D.
1	HEN-49			5-31-23	1219		6	2 2 2														23051600-033
2	HEN-50				1357		6	2 2 2														034
3	HEN-51				1137		6	2 2 2														035
4	HEN-52						6	2 2 2														036
5	HEN-54			5-31-23	1027		6	2 2 2														037
6	HEN-55			5-30-23	1438		0															038
7	HEN-XPW01-pore						6	2 2 2														039
8	HEN-XPW02-pore						6	2 2 2														040
9	HEN-XPW03-pore						6	2 2 2														041
10	HEN-XSG01			5-30-23	1403		0															042
11	HEN-YSG-ILRIVER			5-30-23	1327		0															043
12	Field Blank			6/1/23	0822		11	3 3 2 2 1														044
13	HEN-08 Duplicate						11	3 3 2 2 1														045
14																						
15																						
16																						

ADDITIONAL COMMENTS	REMOVED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS
HEN-23Q2 Rev 1		6/1/23	1201	Allen Cole	6/1	12:01	

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER: Joe Ritey					
SIGNATURE of SAMPLER: [Signature]					
DATE Signed (MM/DD/YY): 6/1/23					

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page: 1 of 3

Pres ✓ 88374 TC -
79929

Ø HEADSPACE
TW

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples placed (Y/N)
PRINT Name of SAMPLER:	T. Connell B. Gullivan J. Polp				
SIGNATURE of SAMPLER:	DATE Signed (MM/DD/YY):				

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page: 2 of 3

[illegible]

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples intact (Y/N)
PRINT Name of SAMPLER: Carroll B.G., Lohan J. Colp					
SIGNATURE of SAMPLER: [Signature]	DATE Signed (MM/DD/Yr): 6/1/23				

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately

Page: 3 of 3[illegible]

July 13, 2023

Eric Bauer
Ramboll
300 S. Wacker Drive
Suite 130
Chicago, IL 60606
TEL: (414) 837-3607
FAX: (414) 837-3608



Illinois	100226
Kansas	E-10374
Louisiana	05002
Louisiana	05003
Oklahoma	9978

RE: HEN-23Q2

WorkOrder: 23051601

Dear Eric Bauer:

TEKLAB, INC received 30 samples on 6/1/2023 4:00:00 PM for the analysis presented in the following report.

Samples are analyzed on an as received basis unless otherwise requested and documented. The sample results contained in this report relate only to the requested analytes of interest as directed on the chain of custody. NELAP accredited fields of testing are indicated by the letters NELAP under the Certification column. Unless otherwise documented within this report, Teklab Inc. analyzes samples utilizing the most current methods in compliance with 40CFR. All tests are performed in the Collinsville, IL laboratory unless otherwise noted in the Case Narrative.

All quality control criteria applicable to the test methods employed for this project have been satisfactorily met and are in accordance with NELAP except where noted. The following report shall not be reproduced, except in full, without the written approval of Teklab, Inc.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,



Elizabeth A. Hurley
Director of Customer Service
(618)344-1004 ex 33
ehurley@teklabinc.com



Report Contents

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051601

Client Project: HEN-23Q2

Report Date: 13-Jul-23

This reporting package includes the following:

Cover Letter	1
Report Contents	2
Definitions	3
Case Narrative	5
Accreditations	6
Laboratory Results	7
Sample Summary	37
Dates Report	38
Receiving Check List	40
Chain of Custody	Appended

Definitions

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051601

Client Project: HEN-23Q2

Report Date: 13-Jul-23

Abbr Definition

* Analytes on report marked with an asterisk are not NELAP accredited

CCV Continuing calibration verification is a check of a standard to determine the state of calibration of an instrument between recalibration.

CRQL A Client Requested Quantitation Limit is a reporting limit that varies according to customer request. The CRQL may not be less than the MDL.

DF Dilution factor is the dilution performed during analysis only and does not take into account any dilutions made during sample preparation. The reported result is final and includes all dilution factors.

DNI Did not ignite

DUP Laboratory duplicate is a replicate aliquot prepared under the same laboratory conditions and independently analyzed to obtain a measure of precision.

ICV Initial calibration verification is a check of a standard to determine the state of calibration of an instrument before sample analysis is initiated.

IDPH IL Dept. of Public Health

LCS Laboratory control sample is a sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes and analyzed exactly like a sample to establish intra-laboratory or analyst specific precision and bias or to assess the performance of all or a portion of the measurement system.

LCSD Laboratory control sample duplicate is a replicate laboratory control sample that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).

MBLK Method blank is a sample of a matrix similar to the batch of associated sample (when available) that is free from the analytes of interest and is processed simultaneously with and under the same conditions as samples through all steps of the analytical procedures, and in which no target analytes or interferences should present at concentrations that impact the analytical results for sample analyses.

MDL "The method detection limit is defined as the minimum measured concentration of a substance that can be reported with 99% confidence that the measured concentration is distinguishable from method blank results."

MS Matrix spike is an aliquot of matrix fortified (spiked) with known quantities of specific analytes that is subjected to the entire analytical procedures in order to determine the effect of the matrix on an approved test method's recovery system. The acceptable recovery range is listed in the QC Package (provided upon request).

MSD Matrix spike duplicate means a replicate matrix spike that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).

MW Molecular weight

NC Data is not acceptable for compliance purposes

ND Not Detected at the Reporting Limit

NELAP NELAP Accredited

PQL Practical quantitation limit means the lowest level that can be reliably achieved within specified limits of precision and accuracy during routine laboratory operation conditions.

RL The reporting limit the lowest level that the data is displayed in the final report. The reporting limit may vary according to customer request or sample dilution. The reporting limit may not be less than the MDL.

RPD Relative percent difference is a calculated difference between two recoveries (ie. MS/MSD). The acceptable recovery limit is listed in the QC Package (provided upon request).

SPK The spike is a known mass of target analyte added to a blank sample or sub-sample; used to determine recovery deficiency or for other quality control purposes.

Surr Surrogates are compounds which are similar to the analytes of interest in chemical composition and behavior in the analytical process, but which are not normally found in environmental samples.

TIC Tentatively identified compound: Analytes tentatively identified in the sample by using a library search. Only results not in the calibration standard will be reported as tentatively identified compounds. Results for tentatively identified compounds that are not present in the calibration standard, but are assigned a specific chemical name based upon the library search, are calculated using total peak areas from reconstructed ion chromatograms and a response factor of one. The nearest Internal Standard is used for the calculation. The results of any TICs must be considered estimated, and are flagged with a "T". If the estimated result is above the calibration range it is flagged "ET"

TNTC Too numerous to count (> 200 CFU)



Definitions

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051601

Client Project: HEN-23Q2

Report Date: 13-Jul-23

Qualifiers

- | | |
|---|--|
| # - Unknown hydrocarbon | B - Analyte detected in associated Method Blank |
| C - RL shown is a Client Requested Quantitation Limit | E - Value above quantitation range |
| H - Holding times exceeded | I - Associated internal standard was outside method criteria |
| J - Analyte detected below quantitation limits | M - Manual Integration used to determine area response |
| ND - Not Detected at the Reporting Limit | R - RPD outside accepted recovery limits |
| S - Spike Recovery outside recovery limits | T - TIC(Tentatively identified compound) |
| X - Value exceeds Maximum Contaminant Level | |



Case Narrative

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051601
Report Date: 13-Jul-23

Cooler Receipt Temp: 5.4 °C

An employee of Teklab, Inc. collected the sample(s).

HEN-18&D will be reported as collected at 1349 rather than 1359 per raw field file. EAH 7/13/23

Analyses were performed by Pace Analytical National. See attached report for results and QC.

Locations

Collinsville

Address 5445 Horseshoe Lake Road
Collinsville, IL 62234-7425
Phone (618) 344-1004
Fax (618) 344-1005
Email jhriley@teklabinc.com

Collinsville Air

Address 5445 Horseshoe Lake Road
Collinsville, IL 62234-7425
Phone (618) 344-1004
Fax (618) 344-1005
Email EHurley@teklabinc.com

Springfield

Address 3920 Pintail Dr
Springfield, IL 62711-9415
Phone (217) 698-1004
Fax (217) 698-1005
Email KKlostermann@teklabinc.com

Chicago

Address 1319 Butterfield Rd.
Downers Grove, IL 60515
Phone (630) 324-6855
Fax
Email arenner@teklabinc.com

Kansas City

Address 8421 Nieman Road
Lenexa, KS 66214
Phone (913) 541-1998
Fax (913) 541-1998
Email jhriley@teklabinc.com



Accreditations

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051601

Client Project: HEN-23Q2

Report Date: 13-Jul-23

State	Dept	Cert #	NELAP	Exp Date	Lab
Illinois	IEPA	100226	NELAP	1/31/2024	Collinsville
Kansas	KDHE	E-10374	NELAP	4/30/2024	Collinsville
Louisiana	LDEQ	05002	NELAP	6/30/2024	Collinsville
Louisiana	LDEQ	05003	NELAP	6/30/2024	Collinsville
Oklahoma	ODEQ	9978	NELAP	8/31/2023	Collinsville
Arkansas	ADEQ	88-0966		3/14/2024	Collinsville
Illinois	IDPH	17584		5/31/2025	Collinsville
Iowa	IDNR	430		6/1/2024	Collinsville
Kentucky	UST	0073		1/31/2024	Collinsville
Missouri	MDNR	00930		5/31/2023	Collinsville
Missouri	MDNR	930		1/31/2025	Collinsville



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-001
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-03R
Collection Date: 05/31/2023 13:12

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/03/2023 16:14	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-002
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-07
Collection Date: 06/01/2023 11:45

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/03/2023 16:14	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-003
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-08
Collection Date: 06/01/2023 8:54

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/03/2023 16:14	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-004
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-08D
Collection Date: 05/31/2023 15:10

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/03/2023 16:14	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-005
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-12
Collection Date: 05/31/2023 11:37

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/03/2023 16:14	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-006
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-13
Collection Date: 05/31/2023 12:04

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/03/2023 16:14	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-007
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-16
Collection Date: 06/01/2023 9:40

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/03/2023 16:14	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-008
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-17
Collection Date: 06/01/2023 10:08

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/03/2023 16:14	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-009
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-18#S
Collection Date: 05/31/2023 14:15

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/03/2023 16:14	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-010
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-18&D
Collection Date: 05/31/2023 13:49

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-011
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-21R
Collection Date: 05/31/2023 11:09

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-012
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-22
Collection Date: 05/31/2023 14:01

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-013
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-22&D
Collection Date: 05/31/2023 14:19

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-014
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-23
Collection Date: 05/31/2023 12:00

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-015
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-25
Collection Date: 05/31/2023 12:59

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-016
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-26
Collection Date: 05/31/2023 12:41

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-017
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-27
Collection Date: 05/31/2023 9:15

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-018
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-32
Collection Date: 05/31/2023 9:46

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-019
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-34
Collection Date: 05/31/2023 10:39

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-020
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-35
Collection Date: 05/31/2023 10:09

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-021
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-45#S
Collection Date: 06/01/2023 11:06

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-022
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-46
Collection Date: 05/31/2023 11:00

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-023
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-47
Collection Date: 05/31/2023 9:56

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-024
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-49
Collection Date: 05/31/2023 12:19

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-025
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-50
Collection Date: 05/31/2023 13:37

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-026
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-51
Collection Date: 05/31/2023 11:37

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-027
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-52
Collection Date: 06/01/2023 10:29

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-028
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-54
Collection Date: 05/31/2023 10:27

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-029
Matrix: AQUEOUS

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: Field Blank
Collection Date: 06/01/2023 8:22

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 16:26	R331495



Client: Ramboll
Client Project: HEN-23Q2
Lab ID: 23051601-030
Matrix: GROUNDWATER

Work Order: 23051601
Report Date: 13-Jul-23
Client Sample ID: HEN-08 Duplicate
Collection Date: 06/01/2023 8:54

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SEE ATTACHED FOR SUBCONTRACTING ANALYSIS								
Subcontracted Analysis	*	0		See Attached		1	07/05/2023 21:27	R331495



Sample Summary

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051601
Report Date: 13-Jul-23

Lab Sample ID	Client Sample ID	Matrix	Fractions	Collection Date
23051601-001	HEN-03R	Groundwater	1	05/31/2023 13:12
23051601-002	HEN-07	Groundwater	1	06/01/2023 11:45
23051601-003	HEN-08	Groundwater	1	06/01/2023 8:54
23051601-004	HEN-08D	Groundwater	1	05/31/2023 15:10
23051601-005	HEN-12	Groundwater	1	05/31/2023 11:37
23051601-006	HEN-13	Groundwater	1	05/31/2023 12:04
23051601-007	HEN-16	Groundwater	1	06/01/2023 9:40
23051601-008	HEN-17	Groundwater	1	06/01/2023 10:08
23051601-009	HEN-18#S	Groundwater	1	05/31/2023 14:15
23051601-010	HEN-18&D	Groundwater	1	05/31/2023 13:49
23051601-011	HEN-21R	Groundwater	1	05/31/2023 11:09
23051601-012	HEN-22	Groundwater	1	05/31/2023 14:01
23051601-013	HEN-22&D	Groundwater	1	05/31/2023 14:19
23051601-014	HEN-23	Groundwater	1	05/31/2023 12:00
23051601-015	HEN-25	Groundwater	1	05/31/2023 12:59
23051601-016	HEN-26	Groundwater	1	05/31/2023 12:41
23051601-017	HEN-27	Groundwater	1	05/31/2023 9:15
23051601-018	HEN-32	Groundwater	1	05/31/2023 9:46
23051601-019	HEN-34	Groundwater	1	05/31/2023 10:39
23051601-020	HEN-35	Groundwater	1	05/31/2023 10:09
23051601-021	HEN-45#S	Groundwater	1	06/01/2023 11:06
23051601-022	HEN-46	Groundwater	1	05/31/2023 11:00
23051601-023	HEN-47	Groundwater	1	05/31/2023 9:56
23051601-024	HEN-49	Groundwater	1	05/31/2023 12:19
23051601-025	HEN-50	Groundwater	1	05/31/2023 13:37
23051601-026	HEN-51	Groundwater	1	05/31/2023 11:37
23051601-027	HEN-52	Groundwater	1	06/01/2023 10:29
23051601-028	HEN-54	Groundwater	1	05/31/2023 10:27
23051601-029	Field Blank	Aqueous	1	06/01/2023 8:22
23051601-030	HEN-08 Duplicate	Groundwater	1	06/01/2023 8:54



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll
Client Project: HEN-23Q2

Work Order: 23051601
Report Date: 13-Jul-23

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
Test Name					
23051601-001A	HEN-03R	05/31/2023 13:12	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/03/2023 16:14
23051601-002A	HEN-07	06/01/2023 11:45	06/01/2023 16:00		
See Attached for Subcontracting Analysis					
					07/03/2023 16:14
23051601-003A	HEN-08	06/01/2023 8:54	06/01/2023 16:00		
See Attached for Subcontracting Analysis					
					07/03/2023 16:14
23051601-004A	HEN-08D	05/31/2023 15:10	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/03/2023 16:14
23051601-005A	HEN-12	05/31/2023 11:37	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/03/2023 16:14
23051601-006A	HEN-13	05/31/2023 12:04	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/03/2023 16:14
23051601-007A	HEN-16	06/01/2023 9:40	06/01/2023 16:00		
See Attached for Subcontracting Analysis					
					07/03/2023 16:14
23051601-008A	HEN-17	06/01/2023 10:08	06/01/2023 16:00		
See Attached for Subcontracting Analysis					
					07/03/2023 16:14
23051601-009A	HEN-18#S	05/31/2023 14:15	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/03/2023 16:14
23051601-010A	HEN-18&D	05/31/2023 13:49	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/05/2023 16:26
23051601-011A	HEN-21R	05/31/2023 11:09	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/05/2023 16:26
23051601-012A	HEN-22	05/31/2023 14:01	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/05/2023 16:26
23051601-013A	HEN-22&D	05/31/2023 14:19	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/05/2023 16:26
23051601-014A	HEN-23	05/31/2023 12:00	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/05/2023 16:26
23051601-015A	HEN-25	05/31/2023 12:59	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/05/2023 16:26
23051601-016A	HEN-26	05/31/2023 12:41	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/05/2023 16:26
23051601-017A	HEN-27	05/31/2023 9:15	06/01/2023 12:08		
See Attached for Subcontracting Analysis					
					07/05/2023 16:26
23051601-018A	HEN-32	05/31/2023 9:46	06/01/2023 12:08		



Dates Report

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051601

Client Project: HEN-23Q2

Report Date: 13-Jul-23

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
	Test Name				
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-019A	HEN-34	05/31/2023 10:39	06/01/2023 12:08		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-020A	HEN-35	05/31/2023 10:09	06/01/2023 12:08		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-021A	HEN-45#S	06/01/2023 11:06	06/01/2023 16:00		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-022A	HEN-46	05/31/2023 11:00	06/01/2023 12:08		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-023A	HEN-47	05/31/2023 9:56	06/01/2023 12:08		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-024A	HEN-49	05/31/2023 12:19	06/01/2023 12:08		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-025A	HEN-50	05/31/2023 13:37	06/01/2023 12:08		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-026A	HEN-51	05/31/2023 11:37	06/01/2023 12:08		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-027A	HEN-52	06/01/2023 10:29	06/01/2023 16:00		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-028A	HEN-54	05/31/2023 10:27	06/01/2023 12:08		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-029A	Field Blank	06/01/2023 8:22	06/01/2023 12:08		
	See Attached for Subcontracting Analysis				07/05/2023 16:26
23051601-030A	HEN-08 Duplicate	06/01/2023 8:54	06/01/2023 16:00		
	See Attached for Subcontracting Analysis				07/05/2023 21:27



Receiving Check List

<http://www.teklabinc.com/>

Client: Ramboll

Work Order: 23051601

Client Project: HEN-23Q2

Report Date: 13-Jul-23

Carrier: Joe Riley

Received By: ANC

Completed by:

On:

02-Jun-23

Allison Colin

Reviewed by:

On:

02-Jun-23

Ellie Hopkins

Pages to follow:

Chain of custody

6

Extra pages included

51

Shipping container/cooler in good condition?

Yes ☒

No ☐

Not Present ☐

Temp °C 5.4

Type of thermal preservation?

None ☐

Ice ☒

Blue Ice ☐

Dry Ice ☐

Chain of custody present?

Yes ☒

No ☐

Chain of custody signed when relinquished and received?

Yes ☒

No ☐

Chain of custody agrees with sample labels?

Yes ☒

No ☐

Samples in proper container/bottle?

Yes ☒

No ☐

Sample containers intact?

Yes ☒

No ☐

Sufficient sample volume for indicated test?

Yes ☒

No ☐

All samples received within holding time?

Yes ☒

No ☐

Reported field parameters measured:

Field ☐

Lab ☐

NA ☒

Container/Temp Blank temperature in compliance?

Yes ☒

No ☐

When thermal preservation is required, samples are compliant with a temperature between 0.1°C - 6.0°C, or when samples are received on ice the same day as collected.

Water – at least one vial per sample has zero headspace?

Yes ☐

No ☐

No VOA vials ☒

Water - TOX containers have zero headspace?

Yes ☐

No ☐

No TOX containers ☒

Water - pH acceptable upon receipt?

Yes ☒

No ☐

NA ☐

NPDES/CWA TCN interferences checked/treated in the field?

Yes ☐

No ☐

NA ☒

Any No responses must be detailed below or on the COC.

pH strip #88374. - TWM/acolin - 6/1/2023 3:23:50 PM

Per Joe Riley, 22 and 22D bottles were switched in the field. - EAH 6/1/23

Samples collected on 6/1/23 were delivered same-day at 14.4C (on ice - LTG 5). - ehurley - 6/5/2023 3:57:25 PM

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page: 1 of 3

Invoice Information:

Company: Vistra Corp		Report To: Brian Voelker	Attention: Jason Stuckey	REGULATORY AGENCY		
Address: 13498 E. 900th St		Copy To: Jason Stuckey	Company Name: Vistra Corp			
			Address: see Section A	NPDES	GROUND WATER	DRINKING WATER
Email To: Brian.Voelker@VistraCorp.com		Purchase Order No.:	Quote Reference:	UST	RCRA	OTHER
Phone: (217) 753-8911	Fax:	Project Name:	Project Manager:	Site Location	IL	
Requested Due Date/TAT: 10 day		Project Number: 2285	Profile #:	STATE:		

[illegible]

⊕ 22 and 22D bottles were switched in the field. 5/11/83
(per Joe Raley)

HENNEPIN POWER PLANT, OLD WEST ASH POND

HEN-257-804

Page: 2 of 3

	Requested Analysis Filtered (Y/N)	
--	-----------------------------------	--

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER: <i>Jay Riley</i>					
SIGNATURE of SAMPLER: <i>[Signature]</i>	DATE Signed (MM/DD/YY): <i>6/1/23</i>				

HENNEPIN POWER PLANT, OLD WEST POND

PHEN-257-804

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:		Page: 3 of 3		
Company: Vistra Corp		Report To: Brian Voelker		Attention: Jason Stuckey		REGULATORY AGENCY		
Address: 13498 E. 900th St		Copy To: Jason Stuckey		Company Name: Vistra Corp				
				Address: see Section A				
Email To: Brian.Voelker@VistraCorp.com		Purchase Order No.:		Quote Reference:		NPDES	GROUND WATER	DRINKING WATER
Phone: (217) 753-8911		Project Name:		Project Manager:		UST	RCRA	OTHER
Fax:		Project Number: 2285		Profile #:		Site Location	IL	
Requested Due Date/TAT: 10 day						STATE:		

[illegible]

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples intact (Y/N)
PRINT Name of SAMPLER: Joe R. V. V.					
SIGNATURE of SAMPLER: [Signature]	DATE Signed (MM/DD/YY): 6/1/23				

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page: 1 of 3

[illegible]

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page: 2 of 3

ITEM #	Section D Required Client Information	Valid Matrix Codes MATRIX CODE DRINKING WATER DW WATER WT WASTE WATER WW PRODUCT P SOIL/SOLID SL OIL OL WIPE WP AIR AR OTHER OT TISSUE TS	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives								Analysis Test Y/N	Requested Analysis Filtered (Y/N)										Project No./ Lab I.D.			
					DATE	TIME			Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other		HEN-257-802	HEN-257-803	HEN-257-804	HEN-811-801	HEN-845-802-805	HEN-845-803	HEN-845-804	HEN-CLOSURE-802-805	HEN-CLOSURE-804	HEN-SUP-000		HEN-WPCP-East	HEN-WPCP-West	Residual Chlorine (Y/N)
1	HEN-22&D							2		2																23051601-013					
2	HEN-23							2		2																014					
3	HEN-25							2		2																015					
4	HEN-26							2		2																016					
5	HEN-27							2		2																017					
6	HEN-30																														
7	HEN-31																														
8	HEN-32							2		2																018					
9	HEN-33																														
10	HEN-34							2		2																019					
11	HEN-35							2		2																020					
12	HEN-36																														
13	HEN-40#S																														
14	HEN-45#S				6-1-23	1106		2		2																021					
15	HEN-46							2		2																022					
16	HEN-47							2		2																023					
ADDITIONAL COMMENTS		RELINQUISHED BY / AFFILIATION		DATE		TIME		ACCEPTED BY / AFFILIATION		DATE		TIME		SAMPLE CONDITIONS																	
HEN-23Q2 Rev 1		Turney Control		20/1/23		1000		Shayla A. Harty		4/1/23		1600																			
SAMPLER NAME AND SIGNATURE														Temp in °C		Received on Ice (Y/N)		Custody Sealed Cooler (Y/N)		Samples Intact (Y/N)											
PRINT Name of SAMPLER:																															
SIGNATURE of SAMPLER:																															
DATE Signed (MM/DD/YY):																															

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

HEN-257-1601

Section A

Required Client Information:

Company: **Vistra Corp**
Address: **13498 E. 900th St**
Email To: **Brian.Voelker@VistraCorp.com**
Phone: **(217) 753-8911** Fax:
Requested Due Date/TAT: **10 day**

Section B

Required Project Information:

Report To: **Brian Voelker**
Copy To: **Jason Stuckey**
Purchase Order No.:
Project Name:
Project Number: **2285**

Section C

Invoice Information:

Attention: **Jason Stuckey**
Company Name: **Vistra Corp**
Address: **see Section A**
Quote Reference:
Project Manager:
Profile #:

Page: **3** of **3**

Section D Required Client Information		Valid Matrix Codes MATRIX CODE		COLLECTED		PRESERVATIVES		Requested Analysis Filtered (Y/N)												Project No./ Lab I.D.										
ITEM #	SAMPLE ID (A-Z, 0-9 / -) Sample IDs MUST BE UNIQUE	MATRIX	CODE	DATE	TIME	# OF CONTAINERS	UNPRESERVED	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other	Analysis Test	HEN-257-802	HEN-257-803	HEN-257-804	HEN-811-801	HEN-845-802-805	HEN-845-803	HEN-845-804	HEN-CLOSURE-802-805	HEN-CLOSURE-804	HEN-SUP-000	HEN-WPCP-East	HEN-WPCP-West	Residual Chlorine (Y/N)	Project No./ Lab I.D.	
1	HEN-49					2		2																					23051601-024	
2	HEN-50					2		2																					025	
3	HEN-51					2		2																					026	
4	HEN-52			10/1/23	1029	2		2																					027	
5	HEN-54					2		2																					028	
6	HEN-55																													
7	HEN-XPW01-pore																													
8	HEN-XPW02-pore																													
9	HEN-XPW03-pore																													
10	HEN-XSG01																													
11	HEN-YSG-ILRIVER																													
12	Field Blank					2		2																						029
13	HEN-08 Duplicate			6-1-23	0854	2		2																						030
14																														
15																														
16																														

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS			
HEN-23Q2 Rev 1	Jason Stuckey	4/1/23	1600	Elizaveta G. Harty	4/1/23	1600				

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER:	JAE. BO. JO				
SIGNATURE of SAMPLER:	Jason Stuckey	DATE Signed (MM/DD/YY):	10/1/23		



APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804
ANALYTICAL REPORT
July 12, 2023

TEKLAB, Inc.


Sample Delivery Group: L1623471
Samples Received: 06/07/2023
Project Number: 23051601
Description:

Report To: Elizabeth Hurley
5445 Horseshoe Lake Road
Collinsville, IL 62234

Entire Report Reviewed By:

Mark W. Beasley
Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.



Pace Analytical National

12065 Lebanon Rd Mount Juliet, TN 37122 615-758-5858 800-767-5859 www.pacenational.com

TABLE OF CONTENTS

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Cp: Cover Page	1
Tc: Table of Contents	2
Ss: Sample Summary	4
Cn: Case Narrative	9
Sr: Sample Results	10
23051601-001 L1623471-01	10
23051601-002 L1623471-02	11
23051601-003 L1623471-03	12
23051601-004 L1623471-04	13
23051601-005 L1623471-05	14
23051601-006 L1623471-06	15
23051601-007 L1623471-07	16
23051601-008 L1623471-08	17
23051601-009 L1623471-09	18
23051601-010 L1623471-10	19
23051601-011 L1623471-11	20
23051601-012 L1623471-12	21
23051601-013 L1623471-13	22
23051601-014 L1623471-14	23
23051601-015 L1623471-15	24
23051601-016 L1623471-16	25
23051601-017 L1623471-17	26
23051601-018 L1623471-18	27
23051601-019 L1623471-19	28
23051601-020 L1623471-20	29
23051601-021 L1623471-21	30
23051601-022 L1623471-22	31
23051601-023 L1623471-23	32
23051601-024 L1623471-24	33
23051601-025 L1623471-25	34
23051601-026 L1623471-26	35
23051601-027 L1623471-27	36
23051601-028 L1623471-28	37
23051601-029 L1623471-29	38
23051601-030 L1623471-30	39
Qc: Quality Control Summary	40
Radiochemistry by Method 904/9320	40
Radiochemistry by Method SM7500Ra B M	43
Gl: Glossary of Terms	46
Al: Accreditations & Locations	47

¹ Cp
² Tc
³ Ss
⁴ Cn
⁵ Sr
⁶ Qc
⁷ Gl
⁸ Al
⁹ Sc

Sc: Sample Chain of Custody

- ¹Cp
- ²Tc
- ³Ss
- ⁴Cn
- ⁵Sr
- ⁶Qc
- ⁷Gl
- ⁸Al
- ⁹Sc

SAMPLE SUMMARY

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

CHENEPIN POWER PLANT, OLD WEST ASH POND

APPENDIX A.

05/31/23 13:12 06/07/23 10:30 HEN-257-804

23051601-001 L1623471-01 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084727	1	06/26/23 18:37	07/03/23 16:14	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087358	1	06/30/23 15:34	07/06/23 00:10	SNR	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087358	1	06/30/23 15:34	07/06/23 00:10	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
06/01/23 11:45 06/07/23 10:30

23051601-002 L1623471-02 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084727	1	06/26/23 18:37	07/03/23 16:14	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087358	1	06/30/23 15:34	07/06/23 00:10	SNR	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087358	1	06/30/23 15:34	07/06/23 00:10	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
06/01/23 08:54 06/07/23 10:30

23051601-003 L1623471-03 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084727	1	06/26/23 18:37	07/03/23 16:14	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
05/31/23 15:10 06/07/23 10:30

23051601-004 L1623471-04 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084727	1	06/26/23 18:37	07/03/23 16:14	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
05/31/23 11:37 06/07/23 10:30


23051601-005 L1623471-05 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084727	1	06/26/23 18:37	07/03/23 16:14	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
05/31/23 12:04 06/07/23 10:30

23051601-006 L1623471-06 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084727	1	06/26/23 18:37	07/03/23 16:14	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN



SAMPLE SUMMARY

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

CHENNEPIN POWER PLANT, OLD WEST ASH POND

APPENDIX A.

06/01/23 09:40

06/07/23 10:30

HEN-257-804

23051601-007 L1623471-07 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084727	1	06/26/23 18:37	07/03/23 16:14	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

06/01/23 10:08

06/07/23 10:30

23051601-008 L1623471-08 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084727	1	06/26/23 18:37	07/03/23 16:14	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

05/31/23 14:15

06/07/23 10:30

23051601-009 L1623471-09 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084727	1	06/26/23 18:37	07/03/23 16:14	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

05/31/23 13:49

06/07/23 10:30

23051601-010 L1623471-10 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

05/31/23 11:09

06/07/23 10:30

23051601-011 L1623471-11 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

05/31/23 14:01

06/07/23 10:30

23051601-012 L1623471-12 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN



SAMPLE SUMMARY

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

CHENEPIN POWER PLANT OLD WEST ASH POND

APPENDIX A.

05/31/23 14:19 06/07/23 10:30 HEN-257-804

23051601-013 L1623471-13 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by
05/31/23 12:00
Received date/time
06/07/23 10:30

23051601-014 L1623471-14 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by
05/31/23 12:59
Received date/time
06/07/23 10:30

23051601-015 L1623471-15 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by
05/31/23 12:41
Received date/time
06/07/23 10:30

23051601-016 L1623471-16 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by
05/31/23 09:15
Received date/time
06/07/23 10:30


23051601-017 L1623471-17 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by
05/31/23 09:46
Received date/time
06/07/23 10:30

23051601-018 L1623471-18 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN



SAMPLE SUMMARY

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

CHENEPIN POWER PLANT OLD WEST ASH POND

APPENDIX A.

23051601-019 L1623471-19 Non-Potable Water

05/31/23 10:39 06/07/23 10:39

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2087644	1	07/05/23 11:52	07/06/23 17:45	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
05/31/23 10:09 06/07/23 10:30

23051601-020 L1623471-20 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
06/01/23 11:06 06/07/23 10:30

23051601-021 L1623471-21 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
05/31/23 11:00 06/07/23 10:30

23051601-022 L1623471-22 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
05/31/23 09:56 06/07/23 10:30


23051601-023 L1623471-23 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN

Collected by Collected date/time Received date/time
05/31/23 12:19 06/07/23 10:30

23051601-024 L1623471-24 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN



SAMPLE SUMMARY

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

CHENEPIN POWER PLANT, OLD WEST ASH POND

APPENDIX A.

HEN-257-804

23051601-025 L1623471-25 Non-Potable Water

05/31/23 13:37

06/07/23 10:30

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

05/31/23 11:37

06/07/23 10:30

23051601-026 L1623471-26 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

06/01/23 10:29

06/07/23 10:30

23051601-027 L1623471-27 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

05/31/23 10:27

06/07/23 10:30

23051601-028 L1623471-28 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

06/01/23 08:22

06/07/23 10:30

23051601-029 L1623471-29 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2084950	1	06/27/23 11:11	07/05/23 16:26	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN

Collected by

Collected date/time

Received date/time

06/01/23 08:54

06/07/23 10:30

23051601-030 L1623471-30 Non-Potable Water

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Radiochemistry by Method 904/9320	WG2085377	1	06/29/23 16:49	07/05/23 21:27	SNR	Mt. Juliet, TN
Radiochemistry by Method Calculation	WG2089290	1	07/05/23 13:39	07/06/23 21:21	SNR	Mt. Juliet, TN
Radiochemistry by Method SM7500Ra B M	WG2089290	1	07/05/23 13:39	07/06/23 21:21	RGT	Mt. Juliet, TN



CASE NARRATIVE

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All radiochemical sample results for solids are reported on a dry weight basis with the exception of tritium, carbon-14 and radon, unless wet weight was requested by the client. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.



Mark W. Beasley
Project Manager



Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.558	J	0.405	0.724	07/03/2023 16:14	WG2084727
(T) Barium	110			30.0-143	07/03/2023 16:14	WG2084727
(T) Yttrium	86.7			30.0-136	07/03/2023 16:14	WG2084727

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.807		0.483	0.806	07/06/2023 00:10	WG2087358

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.249	J	0.264	0.354	07/06/2023 00:10	WG2087358
(T) Barium-133	99.0			30.0-143	07/06/2023 00:10	WG2087358

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.465	U	0.256	0.480	07/03/2023 16:14	WG2084727
(T) Barium	105			30.0-143	07/03/2023 16:14	WG2084727
(T) Yttrium	108			30.0-136	07/03/2023 16:14	WG2084727

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.203	U	0.337	0.562	07/06/2023 00:10	WG2087358

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.203	J	0.219	0.292	07/06/2023 00:10	WG2087358
(T) Barium-133	95.3			30.0-143	07/06/2023 00:10	WG2087358

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.479		0.220	0.387	07/03/2023 16:14	WG2084727
(T) Barium	100			30.0-143	07/03/2023 16:14	WG2084727
(T) Yttrium	115			30.0-136	07/03/2023 16:14	WG2084727

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.598		0.259	0.424	07/06/2023 17:45	WG2087644

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.119	J	0.136	0.174	07/06/2023 17:45	WG2087644
(T) Barium-133	94.2			30.0-143	07/06/2023 17:45	WG2087644

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.625		0.216	0.375	07/03/2023 16:14	WG2084727
(T) Barium	94.3			30.0-143	07/03/2023 16:14	WG2084727
(T) Yttrium	111			30.0-136	07/03/2023 16:14	WG2084727

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	2.10		0.525	0.459	07/06/2023 17:45	WG2087644

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	1.47		0.478	0.264	07/06/2023 17:45	WG2087644
(T) Barium-133	92.7			30.0-143	07/06/2023 17:45	WG2087644

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.104	U	0.267	0.487	07/03/2023 16:14	WG2084727
(T) Barium	104			30.0-143	07/03/2023 16:14	WG2084727
(T) Yttrium	111			30.0-136	07/03/2023 16:14	WG2084727

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	2.36		0.569	0.510	07/06/2023 17:45	WG2087644

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	2.26		0.502	0.152	07/06/2023 17:45	WG2087644
(T) Barium-133	100			30.0-143	07/06/2023 17:45	WG2087644

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.0670	U	0.254	0.466	07/03/2023 16:14	WG2084727
(T) Barium	101			30.0-143	07/03/2023 16:14	WG2084727
(T) Yttrium	114			30.0-136	07/03/2023 16:14	WG2084727

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.60		0.530	0.529	07/06/2023 17:45	WG2087644

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	1.54		0.465	0.250	07/06/2023 17:45	WG2087644
(T) Barium-133	93.6			30.0-143	07/06/2023 17:45	WG2087644

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.232	U	0.221	0.414	07/03/2023 16:14	WG2084727
(T) Barium	100			30.0-143	07/03/2023 16:14	WG2084727
(T) Yttrium	113			30.0-136	07/03/2023 16:14	WG2084727

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.0656	U	0.265	0.485	07/06/2023 17:45	WG2087644

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.0656	U	0.146	0.253	07/06/2023 17:45	WG2087644
(T) Barium-133	91.9			30.0-143	07/06/2023 17:45	WG2087644

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.530		0.260	0.459	07/03/2023 16:14	WG2084727
(T) Barium	107			30.0-143	07/03/2023 16:14	WG2084727
(T) Yttrium	106			30.0-136	07/03/2023 16:14	WG2084727

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.597		0.332	0.581	07/06/2023 17:45	WG2087644

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.0666	U	0.206	0.357	07/06/2023 17:45	WG2087644
(T) Barium-133	91.0			30.0-143	07/06/2023 17:45	WG2087644

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.292	J	0.226	0.405	07/03/2023 16:14	WG2084727
(T) Barium	107			30.0-143	07/03/2023 16:14	WG2084727
(T) Yttrium	104			30.0-136	07/03/2023 16:14	WG2084727



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.745		0.357	0.466	07/06/2023 17:45	WG2087644



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.453		0.276	0.230	07/06/2023 17:45	WG2087644
(T) Barium-133	94.4			30.0-143	07/06/2023 17:45	WG2087644



Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.558	U	0.372	0.686	07/05/2023 16:26	WG2084950
(T) Barium	115			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	110			30.0-136	07/05/2023 16:26	WG2084950

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.06		0.551	0.730	07/06/2023 17:45	WG2087644

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	1.06		0.407	0.250	07/06/2023 17:45	WG2087644
(T) Barium-133	106			30.0-143	07/06/2023 17:45	WG2087644

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	1.20		0.314	0.532	07/05/2023 16:26	WG2084950
(T) Barium	112			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	122			30.0-136	07/05/2023 16:26	WG2084950

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	2.44		0.528	0.600	07/06/2023 17:45	WG2087644

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	1.23		0.424	0.277	07/06/2023 17:45	WG2087644
(T) Barium-133	102			30.0-143	07/06/2023 17:45	WG2087644

¹Cp

²Tc

³Ss

⁴Cn

⁵Sr

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.211	U	0.310	0.551	07/05/2023 16:26	WG2084950
(T) Barium	108			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	99.4			30.0-136	07/05/2023 16:26	WG2084950

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.781		0.453	0.638	07/06/2023 17:45	WG2087644

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.570		0.331	0.322	07/06/2023 17:45	WG2087644
(T) Barium-133	96.4			30.0-143	07/06/2023 17:45	WG2087644

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.111	U	0.311	0.561	07/05/2023 16:26	WG2084950
(T) Barium	107			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	95.1			30.0-136	07/05/2023 16:26	WG2084950

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.104	U	0.364	0.633	07/06/2023 17:45	WG2087644

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.104	U	0.189	0.294	07/06/2023 17:45	WG2087644
(T) Barium-133	104			30.0-143	07/06/2023 17:45	WG2087644

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.0354	U	0.270	0.486	07/05/2023 16:26	WG2084950
(T) Barium	107			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	117			30.0-136	07/05/2023 16:26	WG2084950

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.392	J	0.347	0.519	07/06/2023 17:45	WG2087644

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.357		0.218	0.181	07/06/2023 17:45	WG2087644
(T) Barium-133	92.9			30.0-143	07/06/2023 17:45	WG2087644

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.846		0.257	0.437	07/05/2023 16:26	WG2084950
(T) Barium	119			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	106			30.0-136	07/05/2023 16:26	WG2084950

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.70		0.417	0.469	07/06/2023 17:45	WG2087644

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.850		0.328	0.169	07/06/2023 17:45	WG2087644
(T) Barium-133	108			30.0-143	07/06/2023 17:45	WG2087644

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.646		0.248	0.427	07/05/2023 16:26	WG2084950
(T) Barium	126			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	110			30.0-136	07/05/2023 16:26	WG2084950



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.38		0.431	0.530	07/06/2023 17:45	WG2087644



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.738		0.353	0.314	07/06/2023 17:45	WG2087644
(T) Barium-133	104			30.0-143	07/06/2023 17:45	WG2087644



Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.202	U	0.231	0.430	07/05/2023 16:26	WG2084950
(T) Barium	122			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	83.5			30.0-136	07/05/2023 16:26	WG2084950

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.219	J	0.332	0.537	07/06/2023 17:45	WG2087644

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.219	J	0.239	0.321	07/06/2023 17:45	WG2087644
(T) Barium-133	108			30.0-143	07/06/2023 17:45	WG2087644

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.173	U	0.325	0.579	07/05/2023 16:26	WG2084950
(T) Barium	116			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	91.5			30.0-136	07/05/2023 16:26	WG2084950

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.312	J	0.361	0.614	07/06/2023 17:45	WG2087644

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.139	J	0.156	0.205	07/06/2023 17:45	WG2087644
(T) Barium-133	104			30.0-143	07/06/2023 17:45	WG2087644

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.0723	U	0.226	0.409	07/05/2023 16:26	WG2084950
(T) Barium	119			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	95.0			30.0-136	07/05/2023 16:26	WG2084950



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.492	J	0.357	0.495	07/06/2023 17:45	WG2087644



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.420		0.276	0.278	07/06/2023 17:45	WG2087644
(T) Barium-133	104			30.0-143	07/06/2023 17:45	WG2087644



Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.246	J	0.257	0.457	07/05/2023 16:26	WG2084950
(T) Barium	108			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	101			30.0-136	07/05/2023 16:26	WG2084950



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.353	J	0.309	0.529	07/06/2023 21:21	WG2089290



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.107	J	0.171	0.266	07/06/2023 21:21	WG2089290
(T) Barium-133	91.8			30.0-143	07/06/2023 21:21	WG2089290



Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.427	J	0.278	0.487	07/05/2023 16:26	WG2084950
(T) Barium	112			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	98.5			30.0-136	07/05/2023 16:26	WG2084950



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	3.90		0.720	0.540	07/06/2023 21:21	WG2089290



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	3.47		0.664	0.234	07/06/2023 21:21	WG2089290
(T) Barium-133	108			30.0-143	07/06/2023 21:21	WG2089290



Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.0999	U	0.284	0.513	07/05/2023 16:26	WG2084950
(T) Barium	115			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	91.2			30.0-136	07/05/2023 16:26	WG2084950

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	2.20		0.571	0.535	07/06/2023 21:21	WG2089290

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	2.20		0.495	0.152	07/06/2023 21:21	WG2089290
(T) Barium-133	102			30.0-143	07/06/2023 21:21	WG2089290

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	-0.0655	U	0.332	0.603	07/05/2023 16:26	WG2084950
(T) Barium	126			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	103			30.0-136	07/05/2023 16:26	WG2084950

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.73		0.622	0.662	07/06/2023 21:21	WG2089290

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	1.73	J3	0.526	0.274	07/06/2023 21:21	WG2089290
(T) Barium-133	84.8			30.0-143	07/06/2023 21:21	WG2089290

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.446		0.219	0.382	07/05/2023 16:26	WG2084950
(T) Barium	114			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	102			30.0-136	07/05/2023 16:26	WG2084950



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.583		0.307	0.502	07/06/2023 21:21	WG2089290



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.136	J	0.215	0.325	07/06/2023 21:21	WG2089290
(T) Barium-133	118			30.0-143	07/06/2023 21:21	WG2089290



Radiochemistry by Method 904/9320

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.265	J	0.260	0.461	07/05/2023 16:26	WG2084950
(T) Barium	111			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	111			30.0-136	07/05/2023 16:26	WG2084950



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.580		0.346	0.510	07/06/2023 21:21	WG2089290



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.315		0.228	0.217	07/06/2023 21:21	WG2089290
(T) Barium-133	104			30.0-143	07/06/2023 21:21	WG2089290



Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.878		0.250	0.421	07/05/2023 16:26	WG2084950
(T) Barium	116			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	103			30.0-136	07/05/2023 16:26	WG2084950



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	2.43		0.547	0.490	07/06/2023 21:21	WG2089290



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	1.55		0.487	0.250	07/06/2023 21:21	WG2089290
(T) Barium-133	113			30.0-143	07/06/2023 21:21	WG2089290



Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.650		0.211	0.359	07/05/2023 16:26	WG2084950
(T) Barium	116			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	107			30.0-136	07/05/2023 16:26	WG2084950



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	1.37		0.396	0.453	07/06/2023 21:21	WG2089290



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.719		0.335	0.277	07/06/2023 21:21	WG2089290
(T) Barium-133	113			30.0-143	07/06/2023 21:21	WG2089290



Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.0354	U	0.286	0.512	07/05/2023 16:26	WG2084950
(T) Barium	108			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	97.7			30.0-136	07/05/2023 16:26	WG2084950

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.504	J	0.424	0.610	07/06/2023 21:21	WG2089290

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.469		0.313	0.332	07/06/2023 21:21	WG2089290
(T) Barium-133	93.5			30.0-143	07/06/2023 21:21	WG2089290

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	0.396		0.223	0.391	07/05/2023 16:26	WG2084950
(T) Barium	122			30.0-143	07/05/2023 16:26	WG2084950
(T) Yttrium	102			30.0-136	07/05/2023 16:26	WG2084950

¹Cp

²Tc

³Ss

Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	0.403	J	0.278	0.504	07/06/2023 21:21	WG2089290

⁴Cn

⁵Sr

Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.00705	U	0.166	0.318	07/06/2023 21:21	WG2089290
(T) Barium-133	92.3			30.0-143	07/06/2023 21:21	WG2089290

⁶Qc

⁷Gl

⁸Al

⁹Sc

Radiochemistry by Method 904/9320

HEN-257-804

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-228	3.42		0.359	0.561	07/05/2023 21:27	WG2085377
(T) Barium	87.3			30.0-143	07/05/2023 21:27	WG2085377
(T) Yttrium	108			30.0-136	07/05/2023 21:27	WG2085377



Radiochemistry by Method Calculation

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
Combined Radium	3.60		0.392	0.586	07/06/2023 21:21	WG2089290



Radiochemistry by Method SM7500Ra B M

Analyte	Result	Qualifier	Uncertainty	MDA	Analysis Date	Batch
	pCi/l		+ / -	pCi/l	date / time	
RADIUM-226	0.186		0.157	0.168	07/06/2023 21:21	WG2089290
(T) Barium-133	113			30.0-143	07/06/2023 21:21	WG2089290



Method Blank (MB)

(MB) R3946607-1 07/03/23 16:14

Analyte	MB Result pCi/l	MB Qualifier	MB Uncertainty + / -	MB MDA pCi/l
Radium-228	0.106	<u>U</u>	0.159	0.289
(T) Barium	119		119	
(T) Yttrium	98.9		98.9	

L1623471-01 Original Sample (OS) • Duplicate (DUP)

(OS) L1623471-01 07/03/23 16:14 • (DUP) R3946607-5 07/03/23 16:14

Analyte	Original Result pCi/l	Original Uncertainty + / -	Original MDA pCi/l	DUP Result pCi/l	DUP Uncertainty + / -	DUP MDA pCi/l	Dilution	DUP RPD %	DUP RER	DUP Qualifier	DUP RPD Limits %	DUP RER Limit
Radium-228	0.558	0.405	0.724	-0.454	0.392	0.724	1	200	1.80	<u>U</u>	20	3
(T) Barium	110			110	110							
(T) Yttrium	86.7			111	111							

Laboratory Control Sample (LCS)

(LCS) R3946607-2 07/03/23 16:14

Analyte	Spike Amount pCi/l	LCS Result pCi/l	LCS Rec. %	Rec. Limits %	LCS Qualifier
Radium-228	5.00	5.14	103	80.0-120	
(T) Barium			110		
(T) Yttrium			112		

L1622211-01 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1622211-01 07/03/23 16:14 • (MS) R3946607-3 07/03/23 16:14 • (MSD) R3946607-4 07/03/23 16:14

Analyte	Spike Amount pCi/l	Original Result pCi/l	MS Result pCi/l	MSD Result pCi/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	MS Qualifier	MSD Qualifier	RPD %	MS RER	RPD Limits %
Radium-228	10.0	0.191	9.44	9.96	92.5	97.7	1	70.0-130			5.32		20
(T) Barium		111			116	110							
(T) Yttrium		103			110	111							

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Radiochemistry by Method 904/9320

L1623471-10,11,12,13,14,15,16,17,18,19,20,21,22,23,24,25,26,27,28,29,30,31,32,33,34,35,36,37,38,39,40,41,42,43,44,45,46,47,48,49,50,51,52,53,54,55,56,57,58,59,60,61,62,63,64,65,66,67,68,69,70,71,72,73,74,75,76,77,78,79,80,81,82,83,84,85,86,87,88,89,90,91,92,93,94,95,96,97,98,99,100,101,102,103,104,105,106,107,108,109,110,111,112,113,114,115,116,117,118,119,120,121,122,123,124,125,126,127,128,129,130,131,132,133,134,135,136,137,138,139,140,141,142,143,144,145,146,147,148,149,150,151,152,153,154,155,156,157,158,159,160,161,162,163,164,165,166,167,168,169,170,171,172,173,174,175,176,177,178,179,180,181,182,183,184,185,186,187,188,189,190,191,192,193,194,195,196,197,198,199,200,201,202,203,204,205,206,207,208,209,210,211,212,213,214,215,216,217,218,219,220,221,222,223,224,225,226,227,228,229,230,231,232,233,234,235,236,237,238,239,240,241,242,243,244,245,246,247,248,249,250,251,252,253,254,255,256,257,258,259,260,261,262,263,264,265,266,267,268,269,270,271,272,273,274,275,276,277,278,279,280,281,282,283,284,285,286,287,288,289,290,291,292,293,294,295,296,297,298,299,300,301,302,303,304,305,306,307,308,309,310,311,312,313,314,315,316,317,318,319,320,321,322,323,324,325,326,327,328,329,330,331,332,333,334,335,336,337,338,339,340,341,342,343,344,345,346,347,348,349,350,351,352,353,354,355,356,357,358,359,360,361,362,363,364,365,366,367,368,369,370,371,372,373,374,375,376,377,378,379,380,381,382,383,384,385,386,387,388,389,390,391,392,393,394,395,396,397,398,399,400,401,402,403,404,405,406,407,408,409,410,411,412,413,414,415,416,417,418,419,420,421,422,423,424,425,426,427,428,429,430,431,432,433,434,435,436,437,438,439,440,441,442,443,444,445,446,447,448,449,450,451,452,453,454,455,456,457,458,459,460,461,462,463,464,465,466,467,468,469,470,471,472,473,474,475,476,477,478,479,480,481,482,483,484,485,486,487,488,489,490,491,492,493,494,495,496,497,498,499,500,501,502,503,504,505,506,507,508,509,510,511,512,513,514,515,516,517,518,519,520,521,522,523,524,525,526,527,528,529,530,531,532,533,534,535,536,537,538,539,540,541,542,543,544,545,546,547,548,549,550,551,552,553,554,555,556,557,558,559,560,561,562,563,564,565,566,567,568,569,570,571,572,573,574,575,576,577,578,579,580,581,582,583,584,585,586,587,588,589,590,591,592,593,594,595,596,597,598,599,600,601,602,603,604,605,606,607,608,609,610,611,612,613,614,615,616,617,618,619,620,621,622,623,624,625,626,627,628,629,630,631,632,633,634,635,636,637,638,639,640,641,642,643,644,645,646,647,648,649,650,651,652,653,654,655,656,657,658,659,660,661,662,663,664,665,666,667,668,669,670,671,672,673,674,675,676,677,678,679,680,681,682,683,684,685,686,687,688,689,690,691,692,693,694,695,696,697,698,699,700,701,702,703,704,705,706,707,708,709,710,711,712,713,714,715,716,717,718,719,720,721,722,723,724,725,726,727,728,729,730,731,732,733,734,735,736,737,738,739,740,741,742,743,744,745,746,747,748,749,750,751,752,753,754,755,756,757,758,759,760,761,762,763,764,765,766,767,768,769,770,771,772,773,774,775,776,777,778,779,780,781,782,783,784,785,786,787,788,789,790,791,792,793,794,795,796,797,798,799,800,801,802,803,804,805,806,807,808,809,810,811,812,813,814,815,816,817,818,819,820,821,822,823,824,825,826,827,828,829,830,831,832,833,834,835,836,837,838,839,840,841,842,843,844,845,846,847,848,849,850,851,852,853,854,855,856,857,858,859,860,861,862,863,864,865,866,867,868,869,870,871,872,873,874,875,876,877,878,879,880,881,882,883,884,885,886,887,888,889,890,891,892,893,894,895,896,897,898,899,900,901,902,903,904,905,906,907,908,909,910,911,912,913,914,915,916,917,918,919,920,921,922,923,924,925,926,927,928,929,930,931,932,933,934,935,936,937,938,939,940,941,942,943,944,945,946,947,948,949,950,951,952,953,954,955,956,957,958,959,960,961,962,963,964,965,966,967,968,969,970,971,972,973,974,975,976,977,978,979,980,981,982,983,984,985,986,987,988,989,990,991,992,993,994,995,996,997,998,999,1000,1001,1002,1003,1004,1005,1006,1007,1008,1009,1010,1011,1012,1013,1014,1015,1016,1017,1018,1019,1020,1021,1022,1023,1024,1025,1026,1027,1028,1029,1030,1031,1032,1033,1034,1035,1036,1037,1038,1039,1040,1041,1042,1

21. ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT

HEN-257-804

¹Cp ${}^2\text{Tc}$ ${}^3\text{Ss}$ ${}^4\text{Cn}$ ${}^5\text{Sr}$ ⁶Qc ${}^7\text{Gf}$ ${}^8\text{Al}$ ${}^9\text{Sc}$

Method Blank (MB)

(MB) R3946996-1 07/05/23 21:27

Analyte	MB Result pCi/l	MB Qualifier	MB Uncertainty + / -	MB MDA pCi/l
Radium-228	0.202	⬇	0.186	0.335
(T) Barium	84.2		84.2	
(T) Yttrium	106		106	

L1623496-03 Original Sample (OS) • Duplicate (DUP)

(OS) L1623496-03 07/05/23 21:27 • (DUP) R3946996-5 07/05/23 21:27

Analyte	Original Result pCi/l	Original Uncertainty + / -	Original MDA pCi/l	DUP Result pCi/l	DUP Uncertainty + / -	DUP MDA pCi/l	Dilution	DUP RPD %	DUP RER	DUP Qualifier	DUP RPD Limits %	DUP RER Limit
Radium-228	1.09	0.320	0.550	1.05	0.420	0.550	1	4.30	0.0871		20	3
(T) Barium	77.6			93.1	93.1							
(T) Yttrium	108			107	107							

Laboratory Control Sample (LCS)

(LCS) R3946996-2 07/05/23 21:27

Analyte	Spike Amount pCi/l	LCS Result pCi/l	LCS Rec. %	Rec. Limits %	LCS Qualifier
Radium-228	5.00	5.08	102	80.0-120	
(T) Barium			92.3		
(T) Yttrium			117		

L1623493-01 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1623493-01 07/05/23 21:27 • (MS) R3946996-3 07/05/23 21:27 • (MSD) R3946996-4 07/05/23 21:27

Analyte	Spike Amount pCi/l	Original Result pCi/l	MS Result pCi/l	MSD Result pCi/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	MS Qualifier	MSD Qualifier	RPD %	MS RER	RPD Limits %
Radium-228	10.0	0.153	10.4	11.1	102	109	1	70.0-130			6.34		20
(T) Barium		75.2			90.8	87.9							
(T) Yttrium		109			109	110							

1Cp

2Tc

3Ss

4Cn

5Sr

6Qc

7Gl

8Al

9Sc

Method Blank (MB)

(MB) R3945585-5 07/06/23 00:18

Analyte	MB Result pCi/l	MB Qualifier	MB Uncertainty + / -	MB MDA pCi/l
Radium-226	0.00365	<u>U</u>	0.0189	0.0365
(T) Barium-133	96.3		96.3	

L1623344-01 Original Sample (OS) • Duplicate (DUP)

(OS) L1623344-01 07/06/23 00:18 • (DUP) R3945585-4 07/06/23 00:10

Analyte	Original Result pCi/l	Original Uncertainty + / -	Original MDA pCi/l	DUP Result pCi/l	DUP Uncertainty + / -	DUP MDA pCi/l	Dilution	DUP RPD %	DUP RER	DUP Qualifier	DUP RPD Limits %	DUP RER Limit
Radium-226	7.21	1.02	0.218	6.41	0.904	0.218	1	11.7	0.583		20	3
(T) Barium-133	99.5			97.6	97.6							

Laboratory Control Sample (LCS)

(LCS) R3945585-1 07/06/23 00:10

Analyte	Spike Amount pCi/l	LCS Result pCi/l	LCS Rec. %	Rec. Limits %	LCS Qualifier
Radium-226	5.01	5.26	105	80.0-120	
(T) Barium-133			99.6		

L1623471-01 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1623471-01 07/06/23 00:10 • (MS) R3945585-2 07/06/23 00:10 • (MSD) R3945585-3 07/06/23 00:10

Analyte	Spike Amount pCi/l	Original Result pCi/l	MS Result pCi/l	MSD Result pCi/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	MS Qualifier	MSD Qualifier	RPD %	MS RER	RPD Limits %
Radium-226	20.0	0.249	18.6	19.0	91.8	93.8	1	75.0-125			2.13		20
(T) Barium-133		99.0			86.4	87.8							



Method Blank (MB)

(MB) R3946754-1 07/06/23 17:45

Analyte	MB Result pCi/l	MB Qualifier	MB Uncertainty + / -	MB MDA pCi/l
Radium-226	0.00425	U	0.0395	0.0803
(T) Barium-133	92.2		92.2	

L1628140-23 Original Sample (OS) • Duplicate (DUP)

(OS) L1628140-23 07/06/23 17:45 • (DUP) R3946754-5 07/06/23 17:45

	Original Result	Original Uncertainty	Original MDA	DUP Result	DUP Uncertainty	DUP MDA	Dilution	DUP RPD	DUP RER	DUP Qualifier	DUP RPD Limits	DUP RER Limit
Analyte	pCi/l	+ / -	pCi/l	pCi/l	+ / -	pCi/l		%			%	
Radium-226	0.0812	0.183	0.298	-0.0667	0.0975	0.298	1	200	0.714	U	20	3
(T) Barium-133	105			94.2	94.2							

Laboratory Control Sample (LCS)

(LCS) R3946754-2 07/06/23 17:45

Analyte	Spike Amount pCi/l	LCS Result pCi/l	LCS Rec. %	Rec. Limits %	<u>LCS Qualifier</u>
Radium-226	5.01	4.01	80.0	80.0-120	
(T) Barium-133			91.2		

L1623471-05 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1623471-05 07/06/23 17:45 • (MS) R3946754-6 07/07/23 23:34 • (MSD) R3946754-4 07/06/23 17:45

Analyte	Spike Amount pCi/l	Original Result pCi/l	MS Result pCi/l	MSD Result pCi/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	MS Qualifier	MSD Qualifier	RPD %	MS RER	RPD Limits %
Radium-226	20.0	2.26	17.4	19.1	75.8	84.4	1	75.0-125			9.41		20
(T) Barium-133		100			90.1	86.9							



Method Blank (MB)

(MB) R3946774-1 07/06/23 21:21

Analyte	MB Result pCi/l	MB Qualifier	MB Uncertainty + / -	MB MDA pCi/l
Radium-226	-0.00437	<u>U</u>	0.0542	0.105
(T) Barium-133	77.4		77.4	

L1623471-23 Original Sample (OS) • Duplicate (DUP)

(OS) L1623471-23 07/06/23 21:21 • (DUP) R3946774-5 07/06/23 21:21

Analyte	Original Result pCi/l	Original Uncertainty + / -	Original MDA pCi/l	DUP Result pCi/l	DUP Uncertainty + / -	DUP MDA pCi/l	Dilution	DUP RPD %	DUP RER	DUP Qualifier	DUP RPD Limits %	DUP RER Limit
Radium-226	1.73	0.526	0.274	0.0499	0.0948	0.274	1	189	3.14	<u>J3 U</u>	20	3
(T) Barium-133	84.8			99.6	99.6							

L1623471-23 Original Sample (OS) • Duplicate (DUP)

(OS) L1623471-23 07/06/23 21:21 • (DUP) R3946774-6 07/07/23 23:34

Analyte	Original Result pCi/l	Original Uncertainty + / -	Original MDA pCi/l	DUP Result pCi/l	DUP Uncertainty + / -	DUP MDA pCi/l	Dilution	DUP RPD %	DUP RER	DUP Qualifier	DUP RPD Limits %	DUP RER Limit
Radium-226	1.73	0.526	0.274	0.0460	0.165	0.274	1	190	3.05	<u>J3 U</u>	20	3
(T) Barium-133	84.8			99.6	99.6							

Laboratory Control Sample (LCS)

(LCS) R3946774-2 07/06/23 21:21

Analyte	Spike Amount pCi/l	LCS Result pCi/l	LCS Rec. %	Rec. Limits %	LCS Qualifier
Radium-226	5.01	4.08	81.5	80.0-120	
(T) Barium-133			88.5		

L1623471-28 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1623471-28 07/06/23 21:21 • (MS) R3946774-3 07/06/23 21:21 • (MSD) R3946774-4 07/06/23 21:21

Analyte	Spike Amount pCi/l	Original Result pCi/l	MS Result pCi/l	MSD Result pCi/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	MS Qualifier	MSD Qualifier	RPD %	MS RER	RPD Limits %
Radium-226	20.0	0.469	16.8	17.9	81.6	87.0	1	75.0-125			6.23		20
(T) Barium-133		93.5			84.3	89.3							



GLOSSARY OF TERMS

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Guide to Reading and Understanding Your Laboratory Report

HEN-257-804

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.


Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

Abbreviations and Definitions

MDA	Minimum Detectable Activity.
Rec.	Recovery.
RER	Replicate Error Ratio.
RPD	Relative Percent Difference.
SDG	Sample Delivery Group.
(T)	Tracer - A radioisotope of known concentration added to a solution of chemically equivalent radioisotopes at a known concentration to assist in monitoring the yield of the chemical separation.
Analyte	The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported.
Dilution	If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor.
Limits	These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges.
Original Sample	The non-spiked sample in the prep batch used to determine the Relative Percent Difference (RPD) from a quality control sample. The Original Sample may not be included within the reported SDG.
Qualifier	This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable.
Result	The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state "ND" (Not Detected) or "BDL" (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte.
Uncertainty (Radiochemistry)	Confidence level of 2 sigma.
Case Narrative (Cn)	A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report.
Quality Control Summary (Qc)	This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material.
Sample Chain of Custody (Sc)	This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis.
Sample Results (Sr)	This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported.
Sample Summary (Ss)	This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis.

Qualifier Description

J	The identification of the analyte is acceptable; the reported value is an estimate.
J3	The associated batch QC was outside the established quality control range for precision.
U	Below Detectable Limits: Indicates that the analyte was not detected.



ACCREDITATIONS & LOCATIONS

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804


Pace Analytical National 12065 Lebanon Rd Mount Juliet, TN 37122

Alabama	40660	Nebraska	NE-OS-15-05
Alaska	17-026	Nevada	TN000032021-1
Arizona	AZ0612	New Hampshire	2975
Arkansas	88-0469	New Jersey--NELAP	TN002
California	2932	New Mexico ¹	TN00003
Colorado	TN00003	New York	11742
Connecticut	PH-0197	North Carolina	Env375
Florida	E87487	North Carolina ¹	DW21704
Georgia	NELAP	North Carolina ³	41
Georgia ¹	923	North Dakota	R-140
Idaho	TN00003	Ohio--VAP	CL0069
Illinois	200008	Oklahoma	9915
Indiana	C-TN-01	Oregon	TN200002
Iowa	364	Pennsylvania	68-02979
Kansas	E-10277	Rhode Island	LA000356
Kentucky ^{1 6}	KY90010	South Carolina	84004002
Kentucky ²	16	South Dakota	n/a
Louisiana	AI30792	Tennessee ^{1 4}	2006
Louisiana	LA018	Texas	T104704245-20-18
Maine	TN00003	Texas ⁵	LAB0152
Maryland	324	Utah	TN000032021-11
Massachusetts	M-TN003	Vermont	VT2006
Michigan	9958	Virginia	110033
Minnesota	047-999-395	Washington	C847
Mississippi	TN00003	West Virginia	233
Missouri	340	Wisconsin	998093910
Montana	CERT0086	Wyoming	A2LA
A2LA -- ISO 17025	1461.01	AIHA-LAP, LLC EMLAP	100789
A2LA -- ISO 17025 ⁵	1461.02	DOD	1461.01
Canada	1461.01	USDA	P330-15-00234
EPA--Crypto	TN00003		

¹ Drinking Water ² Underground Storage Tanks ³ Aquatic Toxicity ⁴ Chemical/Microbiological ⁵ Mold ⁶ Wastewater n/a Accreditation not applicable

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.

* Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace Analytical.



TEKLAB, INC. Chain of Custody

5445 Horseshoe Lake Road, Collinsville, IL 62234 Phone (618) 344-1004 Fax (618) 344-1005

Are the samples chilled? YES ☐ NO ☒ With: ☐ Ice ☐ Blue Ice Preserved in: ☐ Lab ☐ Field

Teklab Inc
5445 Horseshoe Lake Road
Collinsville, IL 62234

Cooler Temp: Sampler: Tracy Carroll/TEKLAB QC Level: 3

Comments: Please Issue reports and invoices via email only

Please analyze for Radium 226/228 on your standard turn around time.

Samples collected from an IL site.

Batch QC is required for all analyses requested. EDD requested..

Project# 23051601

Contact: Elizabeth Hurley

Email: EHurley@TekLabInc.com

Requested Due Date: Standard TAT

Billing/PO: 34507

Phone: (618) 344-1004

4623471

PLEASE NOTE:

NELAP accreditation is required on the requested analytes and must be documented as such on the final report. If your laboratory does not currently hold a NELAP accreditation for the requested method and/or analytes, please contact Teklab immediately. If your laboratory loses accreditation or is suspended for any analyte/method during the life of the contract, you must contact Teklab immediately.

Any changes to analysis/methods must be approved by Teklab, Inc.

Lab Use	Sample ID	Sample Date/Time	Preservative	Matrix	Ra226/228															
-01	23051601-001	5/31/23 1312	HNO3	Groundwater	✓															
-02	23051601-002	6/1/23 1145	HNO3	Groundwater	✓															
-03	23051601-003	6/1/23 0854	HNO3	Groundwater	✓															
-04	23051601-004	5/31/23 1510	HNO3	Groundwater	✓															
-05	23051601-005	5/31/23 1137	HNO3	Groundwater	✓															
-06	23051601-006	5/31/23 1204	HNO3	Groundwater	✓															
-07	23051601-007	6/1/23 0940	HNO3	Groundwater	✓															
-08	23051601-008	6/1/23 1008	HNO3	Groundwater	✓															
-09	23051601-009	5/31/23 1415	HNO3	Groundwater	✓															
-10	23051601-010	5/31/23 1359	HNO3	Groundwater	✓															
-11	23051601-011	5/31/23 1109	HNO3	Groundwater	✓															

*Relinquished By	Date/Time	Received By	Date/Time
AMS	6/5/23	Haily Rotman	6/7/23 1030

TEKLAB, INC. Chain of Custody

5445 Horseshoe Lake Road, Collinsville, IL 62234 Phone (618) 344-1004 Fax (618) 344-1005

Are the samples chilled? YES ☐ NO ☒ With: ☐ Ice ☐ Blue Ice Preserved in: ☐ Lab ☐ Field

Teklab Inc
5445 Horseshoe Lake Road
Collinsville, IL 62234

Cooler Temp: Sampler: Tracy Carroll/TEKLAB QC Level:

Comments: Please issue reports and invoices via email only

Please analyze for Radium 226/228 on your standard turn around time.

Samples collected from an IL site.

Batch QC is required for all analyses requested. EDD requested..

Project# 23051601

Contact: Elizabeth Hurley

Email: EHurley@TekLabInc.com

Requested Due Date: Standard TAT

Billing/PO: 34507

Phone: (618) 344-1004

416023471

PLEASE NOTE:

NELAP accreditation is required on the requested analytes and must be documented as such on the final report. If your laboratory does not currently hold a NELAP accreditation for the requested method and/or analytes, please contact Teklab immediately. If your laboratory loses accreditation or is suspended for any analyte/method during the life of the contract, you must contact Teklab immediately.

Any changes to analysis/methods must be approved by Teklab, Inc.

Lab Use	Sample ID	Sample Date/Time	Preservative	Matrix	Ra226/228															
-12	23051601-012	5/31/23 1401	HNO3	Groundwater	✓															
-13	23051601-013	5/31/23 1419	HNO3	Groundwater	✓															
-14	23051601-014	5/31/23 1200	HNO3	Groundwater	✓															
-15	23051601-015	5/31/23 1259	HNO3	Groundwater	✓															
-16	23051601-016	5/31/23 1241	HNO3	Groundwater	✓															
-17	23051601-017	5/31/23 0915	HNO3	Groundwater	✓															
-18	23051601-018	5/31/23 0946	HNO3	Groundwater	✓															
-19	23051601-019	5/31/23 1039	HNO3	Groundwater	✓															
-20	23051601-020	5/31/23 1009	HNO3	Groundwater	✓															
-21	23051601-021	6/1/23 1106	HNO3	Groundwater	✓															
-22	23051601-022	5/31/23 1100	HNO3	Groundwater	✓															

*Relinquished By	Date/Time	Received By	Date/Time
Emp	6/5/23	Healy Roberts	6/7/23 1030

TEKLAB, INC. Chain of Custody

5445 Horseshoe Lake Road, Collinsville, IL 62234 Phone (618) 344-1004 Fax (618) 344-1005

Are the samples chilled? YES ☐ NO ☒ With: ☐ Ice ☐ Blue Ice Preserved in: ☐ Lab ☐ Field

Teklab Inc
5445 Horseshoe Lake Road
Collinsville, IL 62234

Cooler Temp: Sampler: Tracy Carroll/TEKLAB QC Level: 3

Comments: Please issue reports and invoices via email only

Please analyze for Radium 226/228 on your standard turn around time.

Samples collected from an IL site.

Batch QC is required for all analyses requested. EDD requested..

Project# 23051601

Contact: Elizabeth Hurley

Email: EHurley@TekLabInc.com

Requested Due Date: Standard TAT

Billing/PO: 34507

Phone: (618) 344-1004

41623471

PLEASE NOTE:

NELAP accreditation is required on the requested analytes and must be documented as such on the final report. If your laboratory does not currently hold a NELAP accreditation for the requested method and/or analytes, please contact Teklab immediately. If your laboratory loses accreditation or is suspended for any analyte/method during the life of the contract, you must contact Teklab immediately.

Any changes to analysis/methods must be approved by Teklab, Inc.

Lab Use	Sample ID	Sample Date/Time	Preservative	Matrix	Ra226/228															
-23	23051601-023	5/31/23 0956	HNO3	Groundwater	☒	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐
-24	23051601-024	5/31/23 1219	HNO3	Groundwater	☒	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐
-25	23051601-025	5/31/23 1337	HNO3	Groundwater	☒	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐
-26	23051601-026	5/31/23 1137	HNO3	Groundwater	☒	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐
-27	23051601-027	6/1/23 1029	HNO3	Groundwater	☒	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐
-28	23051601-028	5/31/23 1027	HNO3	Groundwater	☒	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐
-29	23051601-029	6/1/23 0822	HNO3	Groundwater	☒	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐
-30	23051601-030	6/1/23 0854	HNO3	Groundwater	☒	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐
			HNO3	Groundwater	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐
			HNO3	Groundwater	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐
			HNO3	Groundwater	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐

*Relinquished By: Same Date/Time: 6/5/23 Received By: Hailey Robertson Date/Time: 6/7/23 1030

Sample Receipt Checklist

COC Seal Present/Intact: ☒ Y ☐ N If Applicable
COC Signed/Accurate: ☒ Y ☐ N VOA Zero Headspace: ☒ Y ☐ N
Bottles arrive intact: ☒ Y ☐ N Pres. Correct/Check: ☒ Y ☐ N
Correct bottles used: ☒ Y ☐ N
Sufficient volume sent: ☒ Y ☐ N
RAD Screen <0.5 mR/hr: ☒ Y ☐ N

es not provide client/sampler information without proper authorization, and proprietary rights,
d by local, state or federal laws. (Teklab QAM Section 9.1, TNI V1 M2 Section 4.1.5 c)

SubCocRevA
3/2/2016

11023471

Tracking Numbers		N5 A7. Temperature	
0319	3616	3004	22.2 ± 0.22.2
0319	3616	3705	21.0 ± 0.21.0
0319	3616	3053	22.7 ± 0.22.7

Site Sampling Event	HEN-Q2-2023	APPENDIX A. ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT HENNEPIN POWER PLANT, OLD WEST ASH POND HEN-257-804								
LIMS Workorder	23051600									
Technician	JR,JC/TAC,BG									
WO Sample	Well ID	Date	Time	Time (adj)	DTB (ft)	DTW (ft)	MP Elev (ft)	GW Elev (ft)	Well Condition	Sampling Device
001A	HEN02	06/01/2023	1102	1102		44.96			Good	Bladder Pump
002A	HEN03R	05/31/2023	1312	1312		35.04			Good	Bladder Pump
003A	HEN05R	05/31/2023	1517	1517		41.35			Good	Bladder Pump
004A	HEN05DR	05/31/2023	1458	1458		41.32			Good	Bladder Pump
005A	HEN07	06/01/2023	1145	1145		67.8			Good	Bladder Pump
006A	HEN08	06/01/2023	854	0854		53.84			Good	Bladder Pump
007A	HEN08D	05/31/2023	1510	1510		54.12			Good	Bladder Pump
008A	HEN10	05/31/2023	922	0922		50.78			Good	Bladder Pump
009A	HEN12	05/31/2023	1137	1137		51.21			Good	Bladder Pump
010A	HEN13	05/31/2023	1204	1204		51.21			Good	Bladder Pump
011A	HEN16	06/01/2023	940	0940		54.57			Good	Bladder Pump
012A	HEN17	06/01/2023	1008	1008		55.96			Good	Bladder Pump
013A	HEN18S	05/31/2023	1415	1415		40.86			Good	Bladder Pump
014A	HEN18D	05/31/2023	1349	1349		40.91			Good	Bladder Pump
015A	HEN21R	05/31/2023	1109	1109		5.92			Good	Bladder Pump
016A	HEN22	05/31/2023	1401	1401		18.45			Good	Bladder Pump
017A	HEN22D	05/31/2023	1419	1419		19.1			Good	Bladder Pump
018A	HEN23	05/31/2023	1200	1200		16.72			Good	Bladder Pump
019A	HEN25	05/31/2023	1259	1259		15.94			Good	Bladder Pump
020A	HEN26	05/31/2023	1241	1241		16			Good	Bladder Pump
021A	HEN27	05/31/2023	915	0915		4.14			Good	Bladder Pump
022A	HEN30	05/30/2023	1509	1509		6.62				
023A	HEN31	05/30/2023	1509	1509		6.56				
024A	HEN32	05/31/2023	946	0946		5.22			Good	Bladder Pump
025A	HEN33	05/30/2023	1515	1515		4.03				
026A	HEN34	05/31/2023	1039	1039		8.66			Good	Bladder Pump
027A	HEN35	05/31/2023	1009	1009		8.3			Good	Bladder Pump
028A	HEN36	05/30/2023	1528	1528		15.32				
029A	HEN40S	06/01/2023	1034	1034		40.54			Good	Bladder Pump
030A	HEN45S	06/01/2023	1106	1106		20.42			Good	Bladder Pump
031A	HEN46	05/31/2023	1100	1100		51.4			Good	Bladder Pump
032A	HEN47	05/31/2023	956	0956		55.66			Good	Bladder Pump
033A	HEN49	05/31/2023	1219	1219		21.54			Good	Bladder Pump
034A	HEN50	05/31/2023	1337	1337		18.25			Good	Bladder Pump
035A	HEN51	05/31/2023	1137	1137		18.5			Good	Bladder Pump
036A	HEN52	06/01/2023	1029	1029		53.89			Good	Bladder Pump
037A	HEN54	05/31/2023	1027	1027		53.23			Good	Bladder Pump

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	JR,JC/TAC,BG

WO Sample	Well ID	Date	Time	Time (adj)	DTB (ft)	DTW (ft)	MP Elev (ft)	GW Elev (ft)	Well Condition	Sampling Device
038A	HEN55	05/30/2023	1438	1438		50.55				
039A	HENXPW01	06/01/2023	858	0858		10.25			Good	Peristaltic Pump
040A	HENXPW02	06/01/2023	925	0925		15.37			Good	Peristaltic Pump
041A	HENXPW03	06/01/2023	952	0952		6.41			Good	Peristaltic Pump
042A	HENXSG01	05/30/2023	1403	1403		7.17				
043A	HENYSGILRIVER	05/30/2023	1321	1321		440.5				
044A	FIELD Blank	06/01/2023	822	0822						
045A	HEN08 Dup	06/01/2023	854	0854		53.84			Good	Bladder Pump
				0						

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	JR,JC/TAC,BG

WO Sample	Well ID	Samling Method	Field Filtered	Appearance	Odor	Color	Turbidity (visible)	Ferrous Iron	Transducer SN
001A	HEN02	Low Flow	Yes	Clear	None	None	None	3.598	NA
002A	HEN03R	Low Flow	Yes	Clear	None	None	None	3.23	21615140
003A	HEN05R	Low Flow	Yes	Clear	None	None	None	3.317	NA
004A	HEN05DR	Low Flow	Yes	Clear	None	None	None	3.839	NA
005A	HEN07	Low Flow	Yes	Clear	None	None	None	0.511	21615139
006A	HEN08	Low Flow	Yes	Clear	None	None	None	1.751	21615138
007A	HEN08D	Low Flow	Yes	Clear	None	None	None	1.526	21615598
008A	HEN10	Low Flow	Yes	Clear	None	None	None	3.38	NA
009A	HEN12	Low Flow	Yes	Clear	None	None	None	3.602	21615520
010A	HEN13	Low Flow	Yes	Clear	None	None	None	3.597	21615515
011A	HEN16	Low Flow	Yes	Clear	None	None	None	1.094	21615137
012A	HEN17	Low Flow	Yes	Clear	None	None	None	0.887	21615500
013A	HEN18S	Low Flow	Yes	Clear	None	None	None	3.813	21615482
014A	HEN18D	Low Flow	Yes	Clear	None	None	Slight	4.136	21615609
015A	HEN21R	Low Flow	Yes	Clear	Moder	None	None	6.598	21615613
016A	HEN22	Low Flow	Yes	Clear	None	None	None	0.608	21615497
017A	HEN22D	Low Flow	Yes	Clear	Slight	None	None	2.585	21564134
018A	HEN23	Low Flow	Yes	Clear	Moder	None	None	1.207	21615600
019A	HEN25	Low Flow	Yes	Clear	None	None	None	1.25	
020A	HEN26	Low Flow	Yes	Clear	Slight	None	None	0.884	
021A	HEN27	Low Flow	Yes	Clear	Slight	None	None	over	21615576
022A	HEN30								
023A	HEN31								
024A	HEN32	Low Flow	Yes	Clear	Slight	None	None	2.916	21615487
025A	HEN33								
026A	HEN34	Low Flow	Yes	Clear	None	None	None	over	21615509
027A	HEN35	Low Flow	Yes	Clear	None	None	None	4.586	21615510
028A	HEN36								
029A	HEN40S	Low Flow	Yes	Clear	None	None	None	1.052	
030A	HEN45S	Low Flow	Yes	Clear	None	None	None	1.017	
031A	HEN46	Low Flow	Yes	Clear	None	None	None	3.258	21615491
032A	HEN47	Low Flow	Yes	Clear	None	None	None	3.336	21615505
033A	HEN49	Low Flow	Yes	Clear	None	None	None	0.72	21615490
034A	HEN50	Low Flow	Yes	Clear	None	None	None	0.977	21615489
035A	HEN51	Low Flow	Yes	Clear	Slight	None	None	over	21615608
036A	HEN52	Low Flow	Yes	Clear	None	None	None	3.4	21615145
037A	HEN54	Low Flow	Yes	Clear	None	None	None	3.597	21615143

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	JR,JC/TAC,BG

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

[illegible]

Site Sampling Event	HEN-Q2-2023	
LIMS Workorder	23051600	
Technician	JR,JC/TAC,BG	
WO Sample	Well ID	Trans Reads
001A	HEN02	
002A	HEN03R	447.0424
003A	HEN05R	
004A	HEN05DR	
005A	HEN07	137.3366
006A	HEN08	136.4609
007A	HEN08D	448.15
008A	HEN10	NA
009A	HEN12	447.3286
010A	HEN13	447.4906
011A	HEN16	136.388
012A	HEN17	137.7737
013A	HEN18S	447.0615
014A	HEN18D	447.3612
015A	HEN21R	447.75
016A	HEN22	447.26
017A	HEN22D	447.58
018A	HEN23	447.9
019A	HEN25	
020A	HEN26	
021A	HEN27	447.76
022A	HEN30	
023A	HEN31	
024A	HEN32	447.65
025A	HEN33	
026A	HEN34	446.53
027A	HEN35	447.75
028A	HEN36	
029A	HEN40S	
030A	HEN45S	
031A	HEN46	447.5016
032A	HEN47	447.2565
033A	HEN49	447.82
034A	HEN50	447.15
035A	HEN51	447.8
036A	HEN52	447.4773
037A	HEN54	447.2757

Site Sampling Event	HEN-Q2-2023	
LIMS Workorder	23051600	
Technician	JR,JC/TAC,BG	
WO Sample	Well ID	Trans Reads
038A	HEN55	
039A	HENXPW01	
040A	HENXPW02	
041A	HENXPW03	
042A	HENXSG01	
043A	HENYSGILRIVER	
044A	FIELD Blank	
045A	HEN08 Dup	136.4609

FILE CREATED: 6/2/2023 16:55

DATE	TIME	SITE	DATA ID	Barometer	Temp (°C)	Cond (µS/c	Sp Cond (µS/cm	Sal (psu)	nLFC	Cond (µ	TDS (mg/L)	Resistivity (	Sigma-T (s
5/31/2023	9:16:16 AM	Hennepin	HEN10	747.6	17.5	727.7	848.9	0.42	859.4	552	1374.2	-1	
5/31/2023	9:19:16 AM	Hennepin	HEN10	747.5	17.5	724.5	846.3	0.42	856.9	550	1380.3	-1	
5/31/2023	9:22:16 AM	Hennepin	HEN10	747.5	17.5	724.3	845.7	0.42	856.2	550	1380.6	-1	
5/31/2023	9:50:05 AM	Hennepin	HEN47	747.6	18.1	754.3	868.4	0.43	878.4	564	1325.8	-1.1	
5/31/2023	9:53:05 AM	Hennepin	HEN47	747.5	18.1	753.3	867.3	0.43	877.4	564	1327.5	-1.1	
5/31/2023	9:56:05 AM	Hennepin	HEN47	747.6	18.1	754	868.3	0.43	878.4	564	1326.3	-1.1	
5/31/2023	10:21:41 AM	Hennepin	HEN54	747.6	17.2	728.3	855.8	0.42	866.7	556	1373	-0.9	
5/31/2023	10:24:41 AM	Hennepin	HEN54	747.5	17.2	704.7	828.3	0.41	839	538	1419.1	-0.9	
5/31/2023	10:27:41 AM	Hennepin	HEN54	747.6	17.1	703.5	827.9	0.41	838.5	538	1421.4	-0.9	
5/31/2023	10:54:26 AM	Hennepin	HEN46	747.6	16.4	683.4	818.5	0.4	829.8	532	1463.2	-0.8	
5/31/2023	10:57:26 AM	Hennepin	HEN46	747.6	16.2	679.3	815.9	0.4	827.3	530	1472.1	-0.8	
5/31/2023	11:00:26 AM	Hennepin	HEN46	747.6	16.1	677.1	815.3	0.4	826.8	530	1476.9	-0.8	
5/31/2023	11:31:34 AM	Hennepin	HEN12	747.6	16.3	689.5	827.5	0.41	839	538	1450.3	-0.8	
5/31/2023	11:34:34 AM	Hennepin	HEN12	747.6	15.7	672.3	816.9	0.4	828.7	531	1487.5	-0.7	
5/31/2023	11:37:34 AM	Hennepin	HEN12	747.6	15.7	672	817.4	0.4	829.3	531	1488.1	-0.7	
5/31/2023	11:58:05 AM	Hennepin	HEN13	747.3	16.1	676.8	815.2	0.4	826.7	530	1477.6	-0.8	
5/31/2023	12:01:05 PM	Hennepin	HEN13	747.3	16.2	677.8	814.4	0.4	825.7	529	1475.3	-0.8	
5/31/2023	12:04:05 PM	Hennepin	HEN13	747.1	16.2	677.5	813.7	0.4	825.1	529	1475.9	-0.8	
5/31/2023	1:06:38 PM	Hennepin	HEN03R	747.2	18.5	813.8	928.9	0.46	939.2	604	1228.7	-1.1	
5/31/2023	1:09:38 PM	Hennepin	HEN03R	747.3	18.4	811.2	927.4	0.46	937.7	603	1232.7	-1.1	
5/31/2023	1:12:38 PM	Hennepin	HEN03R	747.2	18.4	809.8	926.7	0.46	937.1	602	1234.8	-1.1	
5/31/2023	1:43:10 PM	Hennepin	HEN18D	746.9	17.5	789.8	920.9	0.46	932.3	599	1266.1	-1	
5/31/2023	1:46:10 PM	Hennepin	HEN18D	747	17.5	790.9	923.1	0.46	934.6	600	1264.4	-1	
5/31/2023	1:49:10 PM	Hennepin	HEN18D	746.8	17.5	789.6	921.7	0.46	933.1	599	1266.5	-1	
5/31/2023	2:09:37 PM	Hennepin	HEN18S	746.7	17.2	782.4	919.8	0.46	931.6	598	1278.2	-0.9	
5/31/2023	2:12:37 PM	Hennepin	HEN18S	746.7	17.2	783.5	920.3	0.46	932.1	598	1276.4	-0.9	
5/31/2023	2:15:37 PM	Hennepin	HEN18S	746.8	17.2	783.4	921	0.46	932.8	599	1276.6	-0.9	
5/31/2023	2:52:51 PM	Hennepin	HEN05DR	746.8	17.3	735.2	861.5	0.43	872.4	560	1360.2	-0.9	
5/31/2023	2:55:50 PM	Hennepin	HEN05DR	747	17.4	739.7	864.8	0.43	875.6	562	1352	-1	
5/31/2023	2:58:50 PM	Hennepin	HEN05DR	747	17.5	739.8	864.3	0.43	875	562	1351.7	-1	
5/31/2023	3:11:19 PM	Hennepin	HEN05R	747.2	17.1	730	858.7	0.42	869.8	558	1370	-0.9	
5/31/2023	3:14:19 PM	Hennepin	HEN05R	747.2	17.2	729.5	858	0.42	869	558	1370.8	-0.9	
5/31/2023	3:17:19 PM	Hennepin	HEN05R	747.2	17.1	728.2	857.7	0.42	868.7	557	1373.3	-0.9	
6/1/2023	8:49:06 AM	Hennepin	HENXPW01	748.7	16.7	934.1	1109.1	0.55	1123.9	721	1070.5	-0.8	

FILE CREATED: 6/2/2023 16:55

DATE	TIME	SITE	DATA ID	Barometer	Temp (°C)	Cond (µS/c	Sp Cond (µS/cm	Sal (psu)	nLFC	Cond (µ	TDS (mg/L)	Resistivity (Sigma-T (s
6/1/2023	8:52:06 AM	Hennepin	HENXPW01	748.7	16.7	933.5	1109.8	0.55	1124.6	721	1071.3	-0.7
6/1/2023	8:55:06 AM	Hennepin	HENXPW01	748.8	16.6	935.6	1114.3	0.56	1129.3	724	1068.8	-0.7
6/1/2023	8:58:06 AM	Hennepin	HENXPW01	748.7	16.5	935.8	1116.4	0.56	1131.6	726	1068.6	-0.7
6/1/2023	9:19:17 AM	Hennepin	HENXPW02	748.8	16.6	3096.9	3687.5	1.95	3737.2	2397	322.9	0.3
6/1/2023	9:22:17 AM	Hennepin	HENXPW02	748.7	16.3	3075.7	3686.2	1.95	3737.1	2396	325.1	0.4
6/1/2023	9:25:17 AM	Hennepin	HENXPW02	748.8	16.3	3074.1	3688	1.96	3739.1	2397	325.3	0.4
6/1/2023	9:46:56 AM	Hennepin	HENXPW03	749.1	15.3	1283	1574.7	0.8	1598.2	1024	779.4	-0.3
6/1/2023	9:49:56 AM	Hennepin	HENXPW03	749	15.4	1277.1	1564.2	0.79	1587.3	1017	783	-0.3
6/1/2023	9:52:56 AM	Hennepin	HENXPW03	749	15.5	1286.8	1573.1	0.8	1596.3	1023	777.2	-0.3
6/1/2023	10:23:49 AM	Hennepin	HEN52	748.8	18.1	758.7	874.4	0.43	884.6	568	1318	-1.1
6/1/2023	10:26:49 AM	Hennepin	HEN52	748.8	17.4	700.9	820.1	0.4	830.4	533	1426.7	-1
6/1/2023	10:29:49 AM	Hennepin	HEN52	748.8	17.3	697.1	816.8	0.4	827.2	531	1434.4	-1
6/1/2023	10:56:37 AM	Hennepin	HEN02	749.2	12.9	658.3	855.3	0.42	869.7	556	1519.1	-0.3
6/1/2023	10:59:37 AM	Hennepin	HEN02	749.1	12.2	754.2	997.9	0.5	1015.1	649	1325.9	-0.1
6/1/2023	11:02:37 AM	Hennepin	HEN02	749.1	12.2	765.1	1012.2	0.5	1029.5	658	1307	-0.1

DATE	TIME	SITE	DATA ID	Barometer	ODO (mg/L	TSS (mg/L)	Turbidity (NTU)	pH	pH (mV)	ORP (mV)	Temp (°C)	Cond (µS/c
5/31/2023	9:06:03 AM	Hennepin	HEN27	758.5	1.22	0	11.64	6.97	-21.1	3.1	12	847
5/31/2023	9:09:03 AM	Hennepin	HEN27	758.5	1.15	0	9.39	6.98	-21.3	-4.6	11.9	846.5
5/31/2023	9:12:03 AM	Hennepin	HEN27	758.6	1.09	0	5.47	6.98	-21.4	-10.3	11.9	846.1
5/31/2023	9:15:03 AM	Hennepin	HEN27	758.6	1.05	0	8.18	6.98	-21.4	-15.7	12	849
5/31/2023	9:33:46 AM	Hennepin	HEN32	758.6	2.69	0	31.45	6.98	-21.6	83.2	11.1	734.6
5/31/2023	9:36:46 AM	Hennepin	HEN32	758.6	1.9	0	19.9	6.95	-19.8	84	11	732.9
5/31/2023	9:39:46 AM	Hennepin	HEN32	758.7	1.56	0	14.63	6.93	-18.5	84.9	11	732.3
5/31/2023	9:42:46 AM	Hennepin	HEN32	758.7	1.37	0	9.91	6.92	-18.1	85.3	11.1	732.4
5/31/2023	9:45:46 AM	Hennepin	HEN32	758.7	1.24	0	6.19	6.92	-17.9	85.7	11	730.9
5/31/2023	10:03:07 AM	Hennepin	HEN35	758.7	3.18	0	8.32	6.89	-16.4	107.4	13	1281.4
5/31/2023	10:06:07 AM	Hennepin	HEN35	758.6	2.04	0	3.93	6.88	-16	106.1	12.9	1269.5
5/31/2023	10:09:07 AM	Hennepin	HEN35	758.6	1.6	0	2.18	6.88	-16	104.8	12.9	1267.7
5/31/2023	10:33:00 AM	Hennepin	HEN34	758.7	2.92	0	10.71	7.02	-23.5	-13	12.2	907.6
5/31/2023	10:36:00 AM	Hennepin	HEN34	758.7	1.98	0	4.75	6.94	-19.3	-64.2	12.2	926.4
5/31/2023	10:39:00 AM	Hennepin	HEN34	758.7	1.6	0	1.79	6.92	-18.2	-82.7	12.3	944.6
5/31/2023	10:57:16 AM	Hennepin	HEN21R	758.7	1.91	0	69.19	7.34	-41.3	-157.6	13.1	887.7
5/31/2023	11:00:16 AM	Hennepin	HEN21R	758.6	1.53	0	50.27	7.35	-41.9	-167.6	13.1	888.4

FILE CREATED: 6/2/2023 16:55

DATE	TIME	SITE	DATA ID	Barometer Temp (°C)		Cond (µS/cm)	Sp Cond (µS/cm)	Sal (psu)	nLFC	Cond (µS/cm)	TDS (mg/L)	Resistivity (Ω·cm)	Sigma-T (S/cm)
5/31/2023	11:03:16 AM	Hennepin	HEN21R	758.7	1.33	0	54.99	7.36	-42.5	-173.5	13	889	
5/31/2023	11:06:16 AM	Hennepin	HEN21R	758.7	1.21	0	46.74	7.36	-42.8	-177	13.1	889.6	
5/31/2023	11:09:16 AM	Hennepin	HEN21R	758.7	1.12	0	42.19	7.37	-43.1	-178.5	13.2	891.8	
5/31/2023	11:28:07 AM	Hennepin	HEN51	758.2	2.56	0	9.63	7.2	-33.5	-121.3	13	867.5	
5/31/2023	11:31:07 AM	Hennepin	HEN51	758.1	1.96	0	8.84	7.22	-34.8	-128.8	13	867.9	
5/31/2023	11:34:07 AM	Hennepin	HEN51	758.2	1.66	0	6.89	7.23	-35.4	-133	12.9	866.9	
5/31/2023	11:37:07 AM	Hennepin	HEN51	758.1	1.5	0	6.08	7.24	-35.6	-135.3	12.9	867.2	
5/31/2023	11:54:11 AM	Hennepin	HEN23	758	3.09	0	-0.46	7.4	-44.9	-128.2	12.9	996.3	
5/31/2023	11:57:11 AM	Hennepin	HEN23	758	1.96	0	-1.38	7.41	-45.1	-132.4	12.9	991.7	
5/31/2023	12:00:11 PM	Hennepin	HEN23	758	1.55	0	-1.79	7.41	-45.5	-127.1	13	988.6	
5/31/2023	12:10:43 PM	Hennepin	HEN49	757.9	5.26	0	6.14	7.16	-31.7	-68.4	14.8	870.9	
5/31/2023	12:13:43 PM	Hennepin	HEN49	757.9	2.34	0	20.09	7.07	-26.7	-39.8	14.8	869.8	
5/31/2023	12:16:43 PM	Hennepin	HEN49	757.9	1.65	0	23.12	7.05	-25.4	-27.3	14.7	867.8	
5/31/2023	12:19:43 PM	Hennepin	HEN49	757.9	1.36	0	21.09	7.04	-24.8	-19	14.9	869.7	
5/31/2023	12:35:31 PM	Hennepin	HEN26	757.9	2.58	0	-1.65	7.1	-28.4	19.6	15	857	
5/31/2023	12:38:31 PM	Hennepin	HEN26	757.9	1.75	0	-2.66	7.07	-26.6	18.3	14.9	854.4	
5/31/2023	12:41:31 PM	Hennepin	HEN26	757.9	1.42	0	-2.77	7.06	-25.8	18.3	15	855.5	
5/31/2023	12:53:20 PM	Hennepin	HEN25	757.7	2.94	0	9.17	7.17	-32	34.3	13.5	696.9	
5/31/2023	12:56:20 PM	Hennepin	HEN25	757.8	2.49	0	0.38	7.15	-30.9	34.8	13.4	689.5	
5/31/2023	12:59:20 PM	Hennepin	HEN25	757.7	2.45	0	-1.34	7.15	-30.7	36.3	13.4	685.8	
5/31/2023	1:31:49 PM	Hennepin	HEN50	757.5	1.48	0	10.75	7.34	-41.7	37.6	15.5	864.1	
5/31/2023	1:34:49 PM	Hennepin	HEN50	757.4	1.29	0	5.59	7.35	-41.9	35.2	15.6	865.3	
5/31/2023	1:37:49 PM	Hennepin	HEN50	757.3	1.17	0	1.85	7.35	-42	33.5	15.5	863.8	
5/31/2023	1:55:01 PM	Hennepin	HEN22	757.3	2.78	0	-0.9	7.58	-55	56.8	15.9	826.3	
5/31/2023	1:58:01 PM	Hennepin	HEN22	757.3	1.8	0	-2.23	7.58	-55	52.4	15.8	825.1	
5/31/2023	2:01:01 PM	Hennepin	HEN22	757.3	1.43	0	-2.68	7.58	-55	48.8	15.7	822.1	
5/31/2023	2:13:23 PM	Hennepin	HEN22D	757.1	2.87	0	4.8	7.24	-35.9	-108	15.9	930.6	
5/31/2023	2:16:23 PM	Hennepin	HEN22D	757.2	1.74	0	3.75	7.24	-35.8	-118.3	15.9	927.2	
5/31/2023	2:19:23 PM	Hennepin	HEN22D	757.1	1.41	0	1.83	7.24	-35.9	-121	15.9	925.4	
5/31/2023	3:04:48 PM	Hennepin	HEN08D	756.7	2.5	0	-0.62	6.65	-2.9	68.5	13.9	1782.4	
5/31/2023	3:07:48 PM	Hennepin	HEN08D	756.7	1.85	0	-1.36	6.64	-2.3	73.3	13.9	1772.6	
5/31/2023	3:10:48 PM	Hennepin	HEN08D	756.7	1.55	0	-2.01	6.63	-2.2	77.1	13.8	1767.2	
6/1/2023	8:48:28 AM	Hennepin	HEN08	758.6	2.95	0	-2.93	6.52	1.3	169.5	13.4	1256.7	
6/1/2023	8:51:28 AM	Hennepin	HEN08	758.7	2.73	0	-2.96	6.53	1	168.6	13.3	1256.1	

FILE CREATED: 6/2/2023 16:55

DATE	TIME	SITE	DATA ID	Barometer Temp (°C)		Cond (µS/cm)	Sp Cond (µS/cm)	Sal (psu)	nLFC	Cond (µS/cm)	TDS (mg/L)	Resistivity (Ω·cm)	Sigma-T (S/cm)
6/1/2023	8:54:28 AM	Hennepin	HEN08	758.6	2.59	0	-3.01	6.53	0.8	167.7	13.3	1255.5	
6/1/2023	9:34:53 AM	Hennepin	HEN16	758.6	3.09	0	-2.75	7.22	-37.3	137.7	18.8	710.6	
6/1/2023	9:37:53 AM	Hennepin	HEN16	758.6	2.92	0	-2.85	7.21	-36.9	138.1	18.7	710.6	
6/1/2023	9:40:53 AM	Hennepin	HEN16	758.5	2.82	0	-2.83	7.21	-36.7	138.1	18.8	710.8	
6/1/2023	10:02:08 AM	Hennepin	HEN17	758.4	8.14	0	-0.9	6.99	-24.4	148.6	15.9	721.9	
6/1/2023	10:05:08 AM	Hennepin	HEN17	758.4	8.09	0	-1.64	6.97	-23.1	150.4	15.9	721	
6/1/2023	10:08:08 AM	Hennepin	HEN17	758.5	8.01	0	-0.91	6.96	-22.8	151.1	15.9	720.5	
6/1/2023	10:28:24 AM	Hennepin	HEN40S	759.1	1.94	0	-2.52	7.67	-62	126.4	17	681.8	
6/1/2023	10:31:24 AM	Hennepin	HEN40S	759	1.55	0	-2.72	7.67	-62.3	125.1	16.9	680.4	
6/1/2023	10:34:24 AM	Hennepin	HEN40S	759.1	1.34	0	-2.71	7.68	-62.4	124.2	16.9	681.2	
6/1/2023	11:00:10 AM	Hennepin	HEN45S	759.7	1.53	0	4.52	6.94	-21.7	136.5	19.9	1006.2	
6/1/2023	11:03:10 AM	Hennepin	HEN45S	759.6	1.26	0	2.67	6.94	-21.5	137.5	19.9	1005	
6/1/2023	11:06:10 AM	Hennepin	HEN45S	759.6	1.11	0	2.52	6.94	-21.4	137.8	19.9	1005.4	
6/1/2023	11:39:31 AM	Hennepin	HEN07	758.3	3.3	0	-2.91	6.7	-8.4	152.9	11.8	897.4	
6/1/2023	11:42:31 AM	Hennepin	HEN07	758.3	2.88	0	-2.95	6.68	-7.3	154	11.8	901.6	
6/1/2023	11:45:31 AM	Hennepin	HEN07	758.3	2.6	0	-3.05	6.66	-6.6	154.7	11.8	903.9	

FILE CREATED: 6/2/2023 16:55

DATE	TIME	SITE	DATA ID	Sigma (s)	TSS (mg/L)	Turbidity (NTU)	ODO (mg/L)	pH	pH (mV)	ORP (mV)
5/31/2023	9:16:16 AM	Hennepin	HEN10	-1	0	-0.43	3.43	6.72	-5.8	145.1
5/31/2023	9:19:16 AM	Hennepin	HEN10	-1	0	-0.86	3.71	6.76	-8.1	145.2
5/31/2023	9:22:16 AM	Hennepin	HEN10	-1	0	-0.87	3.81	6.79	-9.9	145.3
5/31/2023	9:50:05 AM	Hennepin	HEN47	-1.1	0	-0.04	3.73	6.94	-17.6	141.7
5/31/2023	9:53:05 AM	Hennepin	HEN47	-1.1	0	0.03	3.63	6.9	-15.8	143.4
5/31/2023	9:56:05 AM	Hennepin	HEN47	-1.1	0	-0.83	3.6	6.89	-15	144.7
5/31/2023	10:21:41 AM	Hennepin	HEN54	-0.9	0	1.43	5.9	7.23	-33.6	140.7
5/31/2023	10:24:41 AM	Hennepin	HEN54	-0.9	0	0.45	5.73	7.11	-26.9	145.4
5/31/2023	10:27:41 AM	Hennepin	HEN54	-0.9	0	-0.33	5.71	7.07	-24.7	148.6
5/31/2023	10:54:26 AM	Hennepin	HEN46	-0.8	0	0.24	5.15	7.25	-34.6	131.4
5/31/2023	10:57:26 AM	Hennepin	HEN46	-0.8	0	-0.06	4.91	7.14	-28.5	136.5
5/31/2023	11:00:26 AM	Hennepin	HEN46	-0.8	0	-0.46	4.84	7.1	-26.7	139.6
5/31/2023	11:31:34 AM	Hennepin	HEN12	-0.8	0	-0.14	6.12	7.56	-51.7	139.8
5/31/2023	11:34:34 AM	Hennepin	HEN12	-0.7	0	-0.7	5.16	7.25	-34.5	144.7
5/31/2023	11:37:34 AM	Hennepin	HEN12	-0.7	0	-0.77	5.17	7.17	-30.1	147.9
5/31/2023	11:58:05 AM	Hennepin	HEN13	-0.8	0	-0.34	5.24	7.21	-32.3	151.1
5/31/2023	12:01:05 PM	Hennepin	HEN13	-0.8	0	-0.77	5.21	7.2	-31.8	151.7
5/31/2023	12:04:05 PM	Hennepin	HEN13	-0.8	0	-0.78	5.2	7.2	-31.7	152.2
5/31/2023	1:06:38 PM	Hennepin	HEN03R	-1.1	0	3.21	0.95	7.47	-46.9	116
5/31/2023	1:09:38 PM	Hennepin	HEN03R	-1.1	0	1.17	0.82	7.31	-38.1	116
5/31/2023	1:12:38 PM	Hennepin	HEN03R	-1.1	0	0.61	0.78	7.27	-35.7	116
5/31/2023	1:43:10 PM	Hennepin	HEN18D	-1	0	5.27	1.16	7.24	-34.3	139.7
5/31/2023	1:46:10 PM	Hennepin	HEN18D	-1	0	12.32	1	7.2	-32.1	140.2
5/31/2023	1:49:10 PM	Hennepin	HEN18D	-1	0	16.77	0.86	7.19	-31.7	140.1
5/31/2023	2:09:37 PM	Hennepin	HEN18S	-0.9	0	-0.5	0.87	7.37	-41.4	136
5/31/2023	2:12:37 PM	Hennepin	HEN18S	-0.9	0	-0.74	0.84	7.36	-40.8	135.3
5/31/2023	2:15:37 PM	Hennepin	HEN18S	-0.9	0	-0.81	0.85	7.36	-40.7	134.9
5/31/2023	2:52:51 PM	Hennepin	HEN05DR	-0.9	0	-0.34	3.51	7.53	-49.9	146.5
5/31/2023	2:55:50 PM	Hennepin	HEN05DR	-1	0	-0.35	1.22	7.44	-45	146.6
5/31/2023	2:58:50 PM	Hennepin	HEN05DR	-1	0	-0.78	1.1	7.43	-44.3	145.8
5/31/2023	3:11:19 PM	Hennepin	HEN05R	-0.9	0	1.09	1.4	7.65	-56.3	145.1
5/31/2023	3:14:19 PM	Hennepin	HEN05R	-0.9	0	-0.05	1.07	7.61	-54.3	144.8
5/31/2023	3:17:19 PM	Hennepin	HEN05R	-0.9	0	-0.52	1.03	7.6	-53.8	144.2
6/1/2023	8:49:06 AM	Hennepin	HENXPW01	-0.8	0	7.68	1.54	11.01	-246.7	-123.4

FILE CREATED: 6/2/2023 16:55

DATE	TIME	SITE	DATA ID	Sigma (s)	TSS (mg/L)	Turbidity (NTU)	ODO (mg/L)	pH	pH (mV)	ORP (mV)
6/1/2023	8:52:06 AM	Hennepin	HENXPW01	-0.7	0	2.59	1.29	10.98	-245.5	-147.2
6/1/2023	8:55:06 AM	Hennepin	HENXPW01	-0.7	0	2.15	1.18	10.98	-245.4	-161.9
6/1/2023	8:58:06 AM	Hennepin	HENXPW01	-0.7	0	1.99	1.1	10.99	-245.5	-172.4
6/1/2023	9:19:17 AM	Hennepin	HENXPW02	0.3	0	4.88	2.1	11.76	-288.7	-53.1
6/1/2023	9:22:17 AM	Hennepin	HENXPW02	0.4	0	3.53	1.88	11.8	-290.5	-66.7
6/1/2023	9:25:17 AM	Hennepin	HENXPW02	0.4	0	1.35	1.57	11.82	-291.5	-74.7
6/1/2023	9:46:56 AM	Hennepin	HENXPW03	-0.3	0	0.56	1.95	11.52	-273.9	-30.6
6/1/2023	9:49:56 AM	Hennepin	HENXPW03	-0.3	0	0	1.5	11.42	-268.7	-33.5
6/1/2023	9:52:56 AM	Hennepin	HENXPW03	-0.3	0	-0.23	1.35	11.4	-267.4	-35.9
6/1/2023	10:23:49 AM	Hennepin	HEN52	-1.1	0	3.09	6.13	8.37	-100.7	64.1
6/1/2023	10:26:49 AM	Hennepin	HEN52	-1	0	6.07	3.85	7.77	-67.3	80.1
6/1/2023	10:29:49 AM	Hennepin	HEN52	-1	0	2.82	3.71	7.49	-51.4	92.2
6/1/2023	10:56:37 AM	Hennepin	HEN02	-0.3	0	0.45	8.69	7.68	-61.4	114.6
6/1/2023	10:59:37 AM	Hennepin	HEN02	-0.1	0	-0.11	2.31	7.03	-26.2	127.1
6/1/2023	11:02:37 AM	Hennepin	HEN02	-0.1	0	-0.24	2.31	6.89	-18.1	132.4

DATE	TIME	SITE	DATA ID	Sp Cond (µS/cm)	Sal (psu)	nLFCond (µS/cm)	TDS (mg/L)	Resistivity (Sigma-T (s/cm))	Sigma (s)
5/31/2023	9:06:03 AM	Hennepin	HEN27	1128	0.56	1147.5	733	1180.6	-0.1
5/31/2023	9:09:03 AM	Hennepin	HEN27	1128.4	0.56	1147.9	733	1181.3	-0.1
5/31/2023	9:12:03 AM	Hennepin	HEN27	1128	0.56	1147.5	733	1181.9	-0.1
5/31/2023	9:15:03 AM	Hennepin	HEN27	1128.8	0.56	1148.3	734	1177.9	-0.1
5/31/2023	9:33:46 AM	Hennepin	HEN32	1001.2	0.5	1018.8	651	1361.2	0
5/31/2023	9:36:46 AM	Hennepin	HEN32	999.6	0.5	1017.1	650	1364.4	0
5/31/2023	9:39:46 AM	Hennepin	HEN32	999	0.5	1016.6	649	1365.6	0
5/31/2023	9:42:46 AM	Hennepin	HEN32	997.5	0.5	1015	648	1365.4	0
5/31/2023	9:45:46 AM	Hennepin	HEN32	997.2	0.5	1014.8	648	1368.1	0
5/31/2023	10:03:07 AM	Hennepin	HEN35	1663.9	0.85	1691.7	1082	780.4	0
5/31/2023	10:06:07 AM	Hennepin	HEN35	1652.8	0.84	1680.6	1074	787.7	0.1
5/31/2023	10:09:07 AM	Hennepin	HEN35	1647.1	0.84	1674.7	1071	788.8	0
5/31/2023	10:33:00 AM	Hennepin	HEN34	1201.8	0.6	1222.5	781	1101.8	-0.1
5/31/2023	10:36:00 AM	Hennepin	HEN34	1225.3	0.61	1246.3	796	1079.4	0
5/31/2023	10:39:00 AM	Hennepin	HEN34	1247.9	0.63	1269.2	811	1058.6	0
5/31/2023	10:57:16 AM	Hennepin	HEN21R	1149.1	0.58	1168.3	747	1126.5	-0.2
5/31/2023	11:00:16 AM	Hennepin	HEN21R	1150.9	0.58	1170.1	748	1125.6	-0.2

FILE CREATED: 6/2/2023 16:55

DATE	TIME	SITE	DATA ID	Sigma (s)	TSS (mg/L)	Turbidity (NTU)	ODO (mg/L)	pH	pH (mV)	ORP (mV)
5/31/2023	11:03:16 AM	Hennepin	HEN21R	1152.8	0.58	1172	749	1124.8	-0.2	-0.2
5/31/2023	11:06:16 AM	Hennepin	HEN21R	1150.1	0.58	1169.2	748	1124.1	-0.2	-0.2
5/31/2023	11:09:16 AM	Hennepin	HEN21R	1152.6	0.58	1171.8	749	1121.3	-0.2	-0.2
5/31/2023	11:28:07 AM	Hennepin	HEN51	1126.5	0.56	1145.3	732	1152.8	-0.2	-0.2
5/31/2023	11:31:07 AM	Hennepin	HEN51	1126.6	0.56	1145.5	732	1152.2	-0.2	-0.2
5/31/2023	11:34:07 AM	Hennepin	HEN51	1127	0.56	1145.9	733	1153.6	-0.2	-0.2
5/31/2023	11:37:07 AM	Hennepin	HEN51	1128.8	0.56	1147.8	734	1153.1	-0.2	-0.2
5/31/2023	11:54:11 AM	Hennepin	HEN23	1295.7	0.65	1317.4	842	1003.7	-0.1	-0.1
5/31/2023	11:57:11 AM	Hennepin	HEN23	1289.1	0.65	1310.7	838	1008.4	-0.1	-0.1
5/31/2023	12:00:11 PM	Hennepin	HEN23	1282	0.64	1303.5	833	1011.5	-0.1	-0.1
5/31/2023	12:10:43 PM	Hennepin	HEN49	1082.6	0.54	1099.3	704	1148.2	-0.4	-0.4
5/31/2023	12:13:43 PM	Hennepin	HEN49	1080.4	0.54	1097	702	1149.7	-0.4	-0.4
5/31/2023	12:16:43 PM	Hennepin	HEN49	1079.3	0.54	1095.9	702	1152.4	-0.4	-0.4
5/31/2023	12:19:43 PM	Hennepin	HEN49	1078.8	0.54	1095.3	701	1149.8	-0.5	-0.5
5/31/2023	12:35:31 PM	Hennepin	HEN26	1059.8	0.53	1075.9	689	1166.9	-0.5	-0.5
5/31/2023	12:38:31 PM	Hennepin	HEN26	1058	0.53	1074.1	688	1170.4	-0.5	-0.5
5/31/2023	12:41:31 PM	Hennepin	HEN26	1058.7	0.53	1074.8	688	1168.9	-0.5	-0.5
5/31/2023	12:53:20 PM	Hennepin	HEN25	893.9	0.44	908.6	581	1435	-0.3	-0.3
5/31/2023	12:56:20 PM	Hennepin	HEN25	885.4	0.44	900	576	1450.3	-0.3	-0.3
5/31/2023	12:59:20 PM	Hennepin	HEN25	881.5	0.44	896.1	573	1458.3	-0.3	-0.3
5/31/2023	1:31:49 PM	Hennepin	HEN50	1055.5	0.53	1071	686	1157.3	-0.6	-0.6
5/31/2023	1:34:49 PM	Hennepin	HEN50	1054.7	0.53	1070.1	686	1155.6	-0.6	-0.6
5/31/2023	1:37:49 PM	Hennepin	HEN50	1054.6	0.53	1070.1	686	1157.6	-0.6	-0.6
5/31/2023	1:55:01 PM	Hennepin	HEN22	1000.6	0.5	1014.9	650	1210.2	-0.6	-0.6
5/31/2023	1:58:01 PM	Hennepin	HEN22	1000.3	0.5	1014.7	650	1211.9	-0.6	-0.6
5/31/2023	2:01:01 PM	Hennepin	HEN22	998.8	0.5	1013.2	649	1216.4	-0.6	-0.6
5/31/2023	2:13:23 PM	Hennepin	HEN22D	1126.4	0.56	1142.5	732	1074.5	-0.6	-0.6
5/31/2023	2:16:23 PM	Hennepin	HEN22D	1122.3	0.56	1138.4	730	1078.5	-0.6	-0.6
5/31/2023	2:19:23 PM	Hennepin	HEN22D	1119	0.56	1134.9	727	1080.6	-0.6	-0.6
5/31/2023	3:04:48 PM	Hennepin	HEN08D	2259.7	1.17	2296.1	1469	561	0.2	0.2
5/31/2023	3:07:48 PM	Hennepin	HEN08D	2251.9	1.16	2288.3	1464	564.1	0.2	0.2
5/31/2023	3:10:48 PM	Hennepin	HEN08D	2246.5	1.16	2282.8	1460	565.9	0.2	0.2
6/1/2023	8:48:28 AM	Hennepin	HEN08	1615.4	0.82	1642	1050	795.8	0	0
6/1/2023	8:51:28 AM	Hennepin	HEN08	1615.8	0.82	1642.4	1050	796.1	0	0

FILE CREATED: 6/2/2023 16:55

DATE	TIME	SITE	DATA ID	Sigma (s)	TSS (mg/L)	Turbidity (NTU)	ODO (mg/L)	pH	pH (mV)	ORP (mV)
6/1/2023	8:54:28 AM	Hennepin	HEN08	1616.9	0.82	1643.6	1051	796.5	0	0
6/1/2023	9:34:53 AM	Hennepin	HEN16	806.9	0.4	815.5	524	1407.3	-1.2	-1.2
6/1/2023	9:37:53 AM	Hennepin	HEN16	807	0.4	815.7	525	1407.3	-1.2	-1.2
6/1/2023	9:40:53 AM	Hennepin	HEN16	807	0.4	815.6	525	1406.8	-1.2	-1.2
6/1/2023	10:02:08 AM	Hennepin	HEN17	874.7	0.43	887.2	569	1385.3	-0.7	-0.7
6/1/2023	10:05:08 AM	Hennepin	HEN17	873	0.43	885.5	567	1387	-0.7	-0.7
6/1/2023	10:08:08 AM	Hennepin	HEN17	872.1	0.43	884.6	567	1388	-0.7	-0.7
6/1/2023	10:28:24 AM	Hennepin	HEN40S	805.5	0.4	816	524	1466.6	-0.9	-0.9
6/1/2023	10:31:24 AM	Hennepin	HEN40S	804.2	0.4	814.8	523	1469.8	-0.9	-0.9
6/1/2023	10:34:24 AM	Hennepin	HEN40S	805.7	0.4	816.3	524	1467.9	-0.9	-0.9
6/1/2023	11:00:10 AM	Hennepin	HEN45S	1114.4	0.55	1124.4	724	993.8	-1.4	-1.4
6/1/2023	11:03:10 AM	Hennepin	HEN45S	1113.9	0.55	1123.9	724	995.1	-1.3	-1.3
6/1/2023	11:06:10 AM	Hennepin	HEN45S	1114.4	0.55	1124.5	724	994.6	-1.3	-1.3
6/1/2023	11:39:31 AM	Hennepin	HEN07	1199.7	0.6	1220.5	780	1114.3	0	0
6/1/2023	11:42:31 AM	Hennepin	HEN07	1206.5	0.6	1227.5	784	1109.2	0	0
6/1/2023	11:45:31 AM	Hennepin	HEN07	1209.8	0.61	1230.8	786	1106.3	0	0

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	JR,JC/TAC,BG

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)
HEN02	6/1/2023	11:02	1102	12.2	53.96	6.89	1012.2	1012.2	2.31
HEN03R	5/31/2023	13:12	1312	18.4	65.12	7.27	926.7	926.7	0.78
HEN05R	5/31/2023	15:17	1517	17.1	62.78	7.6	857.7	857.7	1.03
HEN05DR	5/31/2023	14:58	1458	17.5	63.5	7.43	864.3	864.3	1.1
HEN07	6/1/2023	11:45	1145	11.8	53.24	6.66	1209.8	1209.8	2.6
HEN08	6/1/2023	8:54	0854	13.3	55.94	6.53	1616.9	1616.9	2.59
HEN08D	5/31/2023	15:10	1510	13.8	56.84	6.63	2246.5	2246.5	1.55
HEN10	5/31/2023	9:22	0922	17.5	63.5	6.79	845.7	845.7	3.81
HEN12	5/31/2023	11:37	1137	15.7	60.26	7.17	817.4	817.4	5.17
HEN13	5/31/2023	12:04	1204	16.2	61.16	7.2	813.7	813.7	5.2
HEN16	6/1/2023	9:40	0940	18.8	65.84	7.21	807	807	2.82
HEN17	6/1/2023	10:08	1008	15.9	60.62	6.96	872.1	872.1	8.01
HEN18S	5/31/2023	14:15	1415	17.2	62.96	7.36	921	921	0.85
HEN18D	5/31/2023	13:49	1349	17.5	63.5	7.19	921.7	921.7	0.86
HEN21R	5/31/2023	11:09	1109	13.2	55.76	7.37	1152.6	1152.6	1.12
HEN22	5/31/2023	14:01	1401	15.7	60.26	7.58	998.8	998.8	1.43
HEN22D	5/31/2023	14:19	1419	15.9	60.62	7.24	1119	1119	1.41
HEN23	5/31/2023	12:00	1200	13	55.4	7.41	1282	1282	1.55
HEN25	5/31/2023	12:59	1259	13.4	56.12	7.15	881.5	881.5	2.45
HEN26	5/31/2023	12:41	1241	15	59	7.06	1058.7	1058.7	1.42
HEN27	5/31/2023	9:15	0915	12	53.6	6.98	1128.8	1128.8	1.05
Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)
Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)
HEN32	5/31/2023	9:45	0945	11	51.8	6.92	997.2	997.2	1.24
Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)
HEN34	5/31/2023	10:39	1039	12.3	54.14	6.92	1247.9	1247.9	1.6
HEN35	5/31/2023	10:09	1009	12.9	55.22	6.88	1647.1	1647.1	1.6
Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)
HEN40S	6/1/2023	10:34	1034	16.9	62.42	7.68	805.7	805.7	1.34
HEN45S	6/1/2023	11:06	1106	19.9	67.82	6.94	1114.4	1114.4	1.11
HEN46	5/31/2023	11:00	1100	16.1	60.98	7.1	815.3	815.3	4.84
HEN47	5/31/2023	9:56	0956	18.1	64.58	6.89	868.3	868.3	3.6
HEN49	5/31/2023	12:19	1219	14.9	58.82	7.04	1078.8	1078.8	1.36
HEN50	5/31/2023	13:37	1337	15.5	59.9	7.35	1054.6	1054.6	1.17
HEN51	5/31/2023	11:37	1137	12.9	55.22	7.24	1128.8	1128.8	1.5
HEN52	6/1/2023	10:29	1029	17.3	63.14	7.49	816.8	816.8	3.71

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	JR,JC/TAC,BG

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)
HEN54	5/31/2023	10:27	1027	17.1	62.78	7.07	827.9	827.9	5.71
Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)
HENXPW01	6/1/2023	8:58	0858	16.5	61.7	10.99	1116.4	1116.4	1.1
HENXPW02	6/1/2023	9:25	0925	16.3	61.34	11.82	3688	3688	1.57
HENXPW03	6/1/2023	9:52	0952	15.5	59.9	11.4	1573.1	1573.1	1.35
Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)
Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)
Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)
Well ID	Date	Time	Time (adj)	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)	ODO (mg/L)

Site Sampling Event								
LIMS Workorder								
Technician								
Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)	DTB (ft)	DTW (ft)	MP Elev (ft)	GW Elev (ft)	LIMS ID
HEN02	-0.24	132.4			44.96			23051600-001A
HEN03R	0.61	116			35.04			23051600-002A
HEN05R	-0.52	144.2			41.35			23051600-003A
HEN05DR	-0.78	145.8			41.32			23051600-004A
HEN07	-3.05	154.7			67.8			23051600-005A
HEN08	-3.01	167.7			53.84			23051600-006A
HEN08D	-2.01	77.1			54.12			23051600-007A
HEN10	-0.87	145.3			50.78			23051600-008A
HEN12	-0.77	147.9			51.21			23051600-009A
HEN13	-0.78	152.2			51.21			23051600-010A
HEN16	-2.83	138.1			54.57			23051600-011A
HEN17	-0.91	151.1			55.96			23051600-012A
HEN18S	-0.81	134.9			40.86			23051600-013A
HEN18D	16.77	140.1			40.91			23051600-014A
HEN21R	42.19	-178.5			5.92			23051600-015A
HEN22	-2.68	48.8			18.45			23051600-016A
HEN22D	1.83	-121			19.1			23051600-017A
HEN23	-1.79	-127.1			16.72			23051600-018A
HEN25	-1.34	36.3			15.94			23051600-019A
HEN26	-2.77	18.3			16			23051600-020A
HEN27	8.18	-15.7			4.14			23051600-021A
Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)		6.62			23051600-022A
Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)		6.56			23051600-023A
HEN32	6.19	85.7			5.22			23051600-024A
Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)		4.03			23051600-025A
HEN34	1.79	-82.7			8.66			23051600-026A
HEN35	2.18	104.8			8.3			23051600-027A
Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)		15.32			23051600-028A
HEN40S	-2.71	124.2			40.54			23051600-029A
HEN45S	2.52	137.8			20.42			23051600-030A
HEN46	-0.46	139.6			51.4			23051600-031A
HEN47	-0.83	144.7			55.66			23051600-032A
HEN49	21.09	-19			21.54			23051600-033A
HEN50	1.85	33.5			18.25			23051600-034A
HEN51	6.08	-135.3			18.5			23051600-035A
HEN52	2.82	92.2			53.89			23051600-036A

Site Sampling Event
LIMS Workorder
Technician

Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)	DTB (ft)	DTW (ft)	MP Elev (ft)	GW Elev (ft)	LIMS ID
HEN54	-0.33	148.6			53.23			23051600-037A
Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)		50.55			23051600-038A
HENXPW01	1.99	-172.4			10.25			23051600-039A
HENXPW02	1.35	-74.7			15.37			23051600-040A
HENXPW03	-0.23	-35.9			6.41			23051600-041A
Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)		7.17			23051600-042A
Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)		440.5			23051600-043A
Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)					23051600-044A
Well ID	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)		53.84			23051600-045A

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN02	6/1/2023	10:56	1056	44.96		12.9	55.22	7.68	855.3	855.3
HEN02	6/1/2023	10:59	1059	44.96		12.2	53.96	7.03	997.9	997.9
HEN02	6/1/2023	11:02	1102	44.96		12.2	53.96	6.89	1012.2	1012.2

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN02	6/1/2023	8.69	0.45	114.6	
HEN02	6/1/2023	2.31	-0.11	127.1	
HEN02	6/1/2023	2.31	-0.24	132.4	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN03R	5/31/2023	13:06	1306	35.04		18.5	65.3	7.47	928.9	928.9
HEN03R	5/31/2023	13:09	1309	35.04		18.4	65.12	7.31	927.4	927.4
HEN03R	5/31/2023	13:12	1312	35.04		18.4	65.12	7.27	926.7	926.7

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN03R	5/31/2023	0.95	3.21	116	
HEN03R	5/31/2023	0.82	1.17	116	
HEN03R	5/31/2023	0.78	0.61	116	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN05R	5/31/2023	15:11	1511	41.35		17.1	62.78	7.65	858.7	858.7
HEN05R	5/31/2023	15:14	1514	41.35		17.2	62.96	7.61	858	858
HEN05R	5/31/2023	15:17	1517	41.35		17.1	62.78	7.6	857.7	857.7

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN05R	5/31/2023	1.4	1.09	145.1	
HEN05R	5/31/2023	1.07	-0.05	144.8	
HEN05R	5/31/2023	1.03	-0.52	144.2	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN05DR	5/31/2023	14:52	1452	41.32		17.3	63.14	7.53	861.5	861.5
HEN05DR	5/31/2023	14:55	1455	41.32		17.4	63.32	7.44	864.8	864.8
HEN05DR	5/31/2023	14:58	1458	41.32		17.5	63.5	7.43	864.3	864.3

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN05DR	5/31/2023	3.51	-0.34	146.5	
HEN05DR	5/31/2023	1.22	-0.35	146.6	
HEN05DR	5/31/2023	1.1	-0.78	145.8	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN07	6/1/2023	11:39	1139	67.8		11.8	53.24	6.7	1199.7	1199.7
HEN07	6/1/2023	11:42	1142	67.8		11.8	53.24	6.68	1206.5	1206.5
HEN07	6/1/2023	11:45	1145	67.8		11.8	53.24	6.66	1209.8	1209.8

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN07	6/1/2023	3.3	-2.91	152.9	
HEN07	6/1/2023	2.88	-2.95	154	
HEN07	6/1/2023	2.6	-3.05	154.7	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN08	6/1/2023	8:48	0848	53.84		13.4	56.12	6.52	1615.4	1615.4
HEN08	6/1/2023	8:51	0851	53.84		13.3	55.94	6.53	1615.8	1615.8
HEN08	6/1/2023	8:54	0854	53.84		13.3	55.94	6.53	1616.9	1616.9

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN08	6/1/2023	2.95	-2.93	169.5	
HEN08	6/1/2023	2.73	-2.96	168.6	
HEN08	6/1/2023	2.59	-3.01	167.7	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN08D	5/31/2023	15:04	1504	54.12		13.9	57.02	6.65	2259.7	2259.7
HEN08D	5/31/2023	15:07	1507	54.12		13.9	57.02	6.64	2251.9	2251.9
HEN08D	5/31/2023	15:10	1510	54.12		13.8	56.84	6.63	2246.5	2246.5

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN08D	5/31/2023	2.5	-0.62	68.5	
HEN08D	5/31/2023	1.85	-1.36	73.3	
HEN08D	5/31/2023	1.55	-2.01	77.1	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN10	5/31/2023	9:16	0916	50.78		17.5	63.5	6.72	848.9	848.9
HEN10	5/31/2023	9:19	0919	50.78		17.5	63.5	6.76	846.3	846.3
HEN10	5/31/2023	9:22	0922	50.78		17.5	63.5	6.79	845.7	845.7

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN10	5/31/2023	3.43	-0.43	145.1	
HEN10	5/31/2023	3.71	-0.86	145.2	
HEN10	5/31/2023	3.81	-0.87	145.3	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN12	5/31/2023	11:31	1131	51.21		16.3	61.34	7.56	827.5	827.5
HEN12	5/31/2023	11:34	1134	51.21		15.7	60.26	7.25	816.9	816.9
HEN12	5/31/2023	11:37	1137	51.21		15.7	60.26	7.17	817.4	817.4

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN12	5/31/2023	6.12	-0.14	139.8	
HEN12	5/31/2023	5.16	-0.7	144.7	
HEN12	5/31/2023	5.17	-0.77	147.9	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN13	5/31/2023	11:58	1158	51.21		16.1	60.98	7.21	815.2	815.2
HEN13	5/31/2023	12:01	1201	51.21		16.2	61.16	7.2	814.4	814.4
HEN13	5/31/2023	12:04	1204	51.21		16.2	61.16	7.2	813.7	813.7

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN13	5/31/2023	5.24	-0.34	151.1	
HEN13	5/31/2023	5.21	-0.77	151.7	
HEN13	5/31/2023	5.2	-0.78	152.2	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN16	6/1/2023	9:34	0934	54.57		18.8	65.84	7.22	806.9	806.9
HEN16	6/1/2023	9:37	0937	54.57		18.7	65.66	7.21	807	807
HEN16	6/1/2023	9:40	0940	54.57		18.8	65.84	7.21	807	807

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN16	6/1/2023	3.09	-2.75	137.7	
HEN16	6/1/2023	2.92	-2.85	138.1	
HEN16	6/1/2023	2.82	-2.83	138.1	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN17	6/1/2023	10:02	1002	55.96		15.9	60.62	6.99	874.7	874.7
HEN17	6/1/2023	10:05	1005	55.96		15.9	60.62	6.97	873	873
HEN17	6/1/2023	10:08	1008	55.96		15.9	60.62	6.96	872.1	872.1

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN17	6/1/2023	8.14	-0.9	148.6	
HEN17	6/1/2023	8.09	-1.64	150.4	
HEN17	6/1/2023	8.01	-0.91	151.1	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN18S	5/31/2023	14:09	1409	40.86		17.2	62.96	7.37	919.8	919.8
HEN18S	5/31/2023	14:12	1412	40.86		17.2	62.96	7.36	920.3	920.3
HEN18S	5/31/2023	14:15	1415	40.86		17.2	62.96	7.36	921	921

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN18S	5/31/2023	0.87	-0.5	136	
HEN18S	5/31/2023	0.84	-0.74	135.3	
HEN18S	5/31/2023	0.85	-0.81	134.9	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN18D	5/31/2023	13:43	1343	40.91		17.5	63.5	7.24	920.9	920.9
HEN18D	5/31/2023	13:46	1346	40.91		17.5	63.5	7.2	923.1	923.1
HEN18D	5/31/2023	13:49	1349	40.91		17.5	63.5	7.19	921.7	921.7

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN18D	5/31/2023	1.16	5.27	139.7	
HEN18D	5/31/2023	1	12.32	140.2	
HEN18D	5/31/2023	0.86	16.77	140.1	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN21R	5/31/2023	10:57	1057	5.92		13.1	55.58	7.34	1149.1	1149.1
HEN21R	5/31/2023	11:00	1100	5.92		13.1	55.58	7.35	1150.9	1150.9
HEN21R	5/31/2023	11:03	1103	5.92		13	55.4	7.36	1152.8	1152.8
HEN21R	5/31/2023	11:06	1106	5.92		13.1	55.58	7.36	1150.1	1150.1
HEN21R	5/31/2023	11:09	1109	5.92		13.2	55.76	7.37	1152.6	1152.6

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN21R	5/31/2023	1.91	69.19	-157.6	
HEN21R	5/31/2023	1.53	50.27	-167.6	
HEN21R	5/31/2023	1.33	54.99	-173.5	
HEN21R	5/31/2023	1.21	46.74	-177	
HEN21R	5/31/2023	1.12	42.19	-178.5	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN22	5/31/2023	13:55	1355	18.45		15.9	60.62	7.58	1000.6	1000.6
HEN22	5/31/2023	13:58	1358	18.45		15.8	60.44	7.58	1000.3	1000.3
HEN22	5/31/2023	14:01	1401	18.45		15.7	60.26	7.58	998.8	998.8

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN22	5/31/2023	2.78	-0.9	56.8	
HEN22	5/31/2023	1.8	-2.23	52.4	
HEN22	5/31/2023	1.43	-2.68	48.8	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN22D	5/31/2023	14:13	1413	19.1		15.9	60.62	7.24	1126.4	1126.4
HEN22D	5/31/2023	14:16	1416	19.1		15.9	60.62	7.24	1122.3	1122.3
HEN22D	5/31/2023	14:19	1419	19.1		15.9	60.62	7.24	1119	1119

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN22D	5/31/2023	2.87	4.8	-108	
HEN22D	5/31/2023	1.74	3.75	-118.3	
HEN22D	5/31/2023	1.41	1.83	-121	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN23	5/31/2023	11:54	1154	16.72		12.9	55.22	7.4	1295.7	1295.7
HEN23	5/31/2023	11:57	1157	16.72		12.9	55.22	7.41	1289.1	1289.1
HEN23	5/31/2023	12:00	1200	16.72		13	55.4	7.41	1282	1282

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN23	5/31/2023	3.09	-0.46	-128.2	
HEN23	5/31/2023	1.96	-1.38	-132.4	
HEN23	5/31/2023	1.55	-1.79	-127.1	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN25	5/31/2023	12:53	1253	15.94		13.5	56.3	7.17	893.9	893.9
HEN25	5/31/2023	12:56	1256	15.94		13.4	56.12	7.15	885.4	885.4
HEN25	5/31/2023	12:59	1259	15.94		13.4	56.12	7.15	881.5	881.5

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN25	5/31/2023	2.94	9.17	34.3	
HEN25	5/31/2023	2.49	0.38	34.8	
HEN25	5/31/2023	2.45	-1.34	36.3	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN26	5/31/2023	12:35	1235	16		15	59	7.1	1059.8	1059.8
HEN26	5/31/2023	12:38	1238	16		14.9	58.82	7.07	1058	1058
HEN26	5/31/2023	12:41	1241	16		15	59	7.06	1058.7	1058.7

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN26	5/31/2023	2.58	-1.65	19.6	
HEN26	5/31/2023	1.75	-2.66	18.3	
HEN26	5/31/2023	1.42	-2.77	18.3	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN27	5/31/2023	9:06	0906	4.14		12	53.6	6.97	1128	1128
HEN27	5/31/2023	9:09	0909	4.14		11.9	53.42	6.98	1128.4	1128.4
HEN27	5/31/2023	9:12	0912	4.14		11.9	53.42	6.98	1128	1128
HEN27	5/31/2023	9:15	0915	4.14		12	53.6	6.98	1128.8	1128.8

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN27	5/31/2023	1.22	11.64	3.1	
HEN27	5/31/2023	1.15	9.39	-4.6	
HEN27	5/31/2023	1.09	5.47	-10.3	
HEN27	5/31/2023	1.05	8.18	-15.7	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN30	5/30/2023	1509	1509							

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	
Well ID	Date
HEN30	5/30/2023

ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
------------	-----------------	----------	--------------------

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN31	5/30/2023	1509	1509							

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	
Well ID	Date
HEN31	5/30/2023

ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
------------	-----------------	----------	--------------------

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN32	5/31/2023	9:33	0933	5.22		11.1	51.98	6.98	1001.2	1001.2
HEN32	5/31/2023	9:36	0936	5.22		11	51.8	6.95	999.6	999.6
HEN32	5/31/2023	9:39	0939	5.22		11	51.8	6.93	999	999
HEN32	5/31/2023	9:42	0942	5.22		11.1	51.98	6.92	997.5	997.5
HEN32	5/31/2023	9:45	0945	5.22		11	51.8	6.92	997.2	997.2

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN32	5/31/2023	2.69	31.45	83.2	
HEN32	5/31/2023	1.9	19.9	84	
HEN32	5/31/2023	1.56	14.63	84.9	
HEN32	5/31/2023	1.37	9.91	85.3	
HEN32	5/31/2023	1.24	6.19	85.7	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN33	5/30/2023	1515	1515							

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	
Well ID	Date
HEN33	5/30/2023

ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
------------	-----------------	----------	--------------------

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN34	5/31/2023	10:33	1033	8.66		12.2	53.96	7.02	1201.8	1201.8
HEN34	5/31/2023	10:36	1036	8.66		12.2	53.96	6.94	1225.3	1225.3
HEN34	5/31/2023	10:39	1039	8.66		12.3	54.14	6.92	1247.9	1247.9

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN34	5/31/2023	2.92	10.71	-13	
HEN34	5/31/2023	1.98	4.75	-64.2	
HEN34	5/31/2023	1.6	1.79	-82.7	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN35	5/31/2023	10:03	1003	8.3		13	55.4	6.89	1663.9	1663.9
HEN35	5/31/2023	10:06	1006	8.3		12.9	55.22	6.88	1652.8	1652.8
HEN35	5/31/2023	10:09	1009	8.3		12.9	55.22	6.88	1647.1	1647.1

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN35	5/31/2023	3.18	8.32	107.4	
HEN35	5/31/2023	2.04	3.93	106.1	
HEN35	5/31/2023	1.6	2.18	104.8	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN36	5/30/2023	1528	1528							

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	
Well ID	Date
HEN36	5/30/2023

ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
------------	-----------------	----------	--------------------

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN40S	6/1/2023	10:28	1028	40.54		17	62.6	7.67	805.5	805.5
HEN40S	6/1/2023	10:31	1031	40.54		16.9	62.42	7.67	804.2	804.2
HEN40S	6/1/2023	10:34	1034	40.54		16.9	62.42	7.68	805.7	805.7

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN40S	6/1/2023	1.94	-2.52	126.4	
HEN40S	6/1/2023	1.55	-2.72	125.1	
HEN40S	6/1/2023	1.34	-2.71	124.2	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN45S	6/1/2023	11:00	1100	20.42		19.9	67.82	6.94	1114.4	1114.4
HEN45S	6/1/2023	11:03	1103	20.42		19.9	67.82	6.94	1113.9	1113.9
HEN45S	6/1/2023	11:06	1106	20.42		19.9	67.82	6.94	1114.4	1114.4

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN45S	6/1/2023	1.53	4.52	136.5	
HEN45S	6/1/2023	1.26	2.67	137.5	
HEN45S	6/1/2023	1.11	2.52	137.8	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN46	5/31/2023	10:54	1054	51.4		16.4	61.52	7.25	818.5	818.5
HEN46	5/31/2023	10:57	1057	51.4		16.2	61.16	7.14	815.9	815.9
HEN46	5/31/2023	11:00	1100	51.4		16.1	60.98	7.1	815.3	815.3

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN46	5/31/2023	5.15	0.24	131.4	
HEN46	5/31/2023	4.91	-0.06	136.5	
HEN46	5/31/2023	4.84	-0.46	139.6	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN47	5/31/2023	9:50	0950	55.66		18.1	64.58	6.94	868.4	868.4
HEN47	5/31/2023	9:53	0953	55.66		18.1	64.58	6.9	867.3	867.3
HEN47	5/31/2023	9:56	0956	55.66		18.1	64.58	6.89	868.3	868.3

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN47	5/31/2023	3.73	-0.04	141.7	
HEN47	5/31/2023	3.63	0.03	143.4	
HEN47	5/31/2023	3.6	-0.83	144.7	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN49	5/31/2023	12:10	1210	21.54		14.8	58.64	7.16	1082.6	1082.6
HEN49	5/31/2023	12:13	1213	21.54		14.8	58.64	7.07	1080.4	1080.4
HEN49	5/31/2023	12:16	1216	21.54		14.7	58.46	7.05	1079.3	1079.3
HEN49	5/31/2023	12:19	1219	21.54		14.9	58.82	7.04	1078.8	1078.8

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN49	5/31/2023	5.26	6.14	-68.4	
HEN49	5/31/2023	2.34	20.09	-39.8	
HEN49	5/31/2023	1.65	23.12	-27.3	
HEN49	5/31/2023	1.36	21.09	-19	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN50	5/31/2023	13:31	1331	18.25		15.5	59.9	7.34	1055.5	1055.5
HEN50	5/31/2023	13:34	1334	18.25		15.6	60.08	7.35	1054.7	1054.7
HEN50	5/31/2023	13:37	1337	18.25		15.5	59.9	7.35	1054.6	1054.6

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN50	5/31/2023	1.48	10.75	37.6	
HEN50	5/31/2023	1.29	5.59	35.2	
HEN50	5/31/2023	1.17	1.85	33.5	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HEN51	5/31/2023	11:28	1128	18.5		13	55.4	7.2	1126.5	1126.5
HEN51	5/31/2023	11:31	1131	18.5		13	55.4	7.22	1126.6	1126.6
HEN51	5/31/2023	11:34	1134	18.5		12.9	55.22	7.23	1127	1127
HEN51	5/31/2023	11:37	1137	18.5		12.9	55.22	7.24	1128.8	1128.8

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN51	5/31/2023	2.56	9.63	-121.3	
HEN51	5/31/2023	1.96	8.84	-128.8	
HEN51	5/31/2023	1.66	6.89	-133	
HEN51	5/31/2023	1.5	6.08	-135.3	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN52	6/1/2023	10:23	1023	53.89		18.1	64.58	8.37	874.4	874.4
HEN52	6/1/2023	10:26	1026	53.89		17.4	63.32	7.77	820.1	820.1
HEN52	6/1/2023	10:29	1029	53.89		17.3	63.14	7.49	816.8	816.8

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN52	6/1/2023	6.13	3.09	64.1	
HEN52	6/1/2023	3.85	6.07	80.1	
HEN52	6/1/2023	3.71	2.82	92.2	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN54	5/31/2023	10:21	1021	53.23		17.2	62.96	7.23	855.8	855.8
HEN54	5/31/2023	10:24	1024	53.23		17.2	62.96	7.11	828.3	828.3
HEN54	5/31/2023	10:27	1027	53.23		17.1	62.78	7.07	827.9	827.9

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN54	5/31/2023	5.9	1.43	140.7	
HEN54	5/31/2023	5.73	0.45	145.4	
HEN54	5/31/2023	5.71	-0.33	148.6	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN55	5/30/2023	1438	1438							

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	
Well ID	Date
HEN55	5/30/2023

ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
------------	-----------------	----------	--------------------

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HENXPW01	6/1/2023	8:49	0849	10.25		16.7	62.06	11.01	1109.1	1109.1
HENXPW01	6/1/2023	8:52	0852	10.25		16.7	62.06	10.98	1109.8	1109.8
HENXPW01	6/1/2023	8:55	0855	10.25		16.6	61.88	10.98	1114.3	1114.3
HENXPW01	6/1/2023	8:58	0858	10.25		16.5	61.7	10.99	1116.4	1116.4

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HENXPW01	6/1/2023	1.54	7.68	-123.4	
HENXPW01	6/1/2023	1.29	2.59	-147.2	
HENXPW01	6/1/2023	1.18	2.15	-161.9	
HENXPW01	6/1/2023	1.1	1.99	-172.4	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HENXPW02	6/1/2023	9:19	0919	15.37		16.6	61.88	11.76	3687.5	3687.5
HENXPW02	6/1/2023	9:22	0922	15.37		16.3	61.34	11.8	3686.2	3686.2
HENXPW02	6/1/2023	9:25	0925	15.37		16.3	61.34	11.82	3688	3688

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HENXPW02	6/1/2023	2.1	4.88	-53.1	
HENXPW02	6/1/2023	1.88	3.53	-66.7	
HENXPW02	6/1/2023	1.57	1.35	-74.7	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HENXPW03	6/1/2023	9:46	0946	6.41		15.3	59.54	11.52	1574.7	1574.7
HENXPW03	6/1/2023	9:49	0949	6.41		15.4	59.72	11.42	1564.2	1564.2
HENXPW03	6/1/2023	9:52	0952	6.41		15.5	59.9	11.4	1573.1	1573.1

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HENXPW03	6/1/2023	1.95	0.56	-30.6	
HENXPW03	6/1/2023	1.5	0	-33.5	
HENXPW03	6/1/2023	1.35	-0.23	-35.9	

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HENXSG01	May-23	1403	1403							

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	
Well ID	Date
HENXSG01	May-23

ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
------------	-----------------	----------	--------------------

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (µS/cm)	Sp Cond (µmhos/cm @25C)
HENYSGILRIVER	5/30/2023	1321	1321							

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	
Well ID	Date
HENYSGILRIVER	5/30/2023

ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
------------	-----------------	----------	--------------------

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	
Well ID	Date
FIELD Blank	6/1/2023

Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
822	0822							

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	
Well ID	Date
FIELD Blank	6/1/2023

ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
------------	-----------------	----------	--------------------

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	Time	Time (adj)	DTW	Drawdown	Temp (deg C)	Temp (deg F)	pH (SU)	Sp Cond (μS/cm)	Sp Cond (μmhos/cm @25C)
HEN08 Dup	6/1/2023	8:48	0848	53.8		13.4	56.12	6.52	1615.4	1615.4
HEN08 Dup	6/1/2023	8:51	0851	53.8		13.3	55.94	6.53	1615.8	1615.8
HEN08 Dup	6/1/2023	8:54	0854	53.8		13.3	55.94	6.53	1616.9	1616.9

Site Sampling Event	HEN-Q2-2023
LIMS Workorder	23051600
Technician	

Well ID	Date	ODO (mg/L)	Turbidity (NTU)	ORP (mV)	Purge Volume (gal)
HEN08 Dup	6/1/2023	2.95	-2.93	169.5	
HEN08 Dup	6/1/2023	2.73	-2.96	168.6	
HEN08 Dup	6/1/2023	2.59	-3.01	167.7	

Field Analysis Log

Cross Reference to Sample ID	Date mm/dd/yy	Time	Temp. C	pH Results			Conductivity			Other: _____			
				Reading 1	Reading 2	LCSD	Range Factor	Reading 1	Reading 2	DF	Read1/units	DF	Read2/units
LCS	5/31/23	8:40	22.9	7.08				1414					
ccv		15:57	28.7	7.09				1412					

**** Field Meter ID for Temp, pH & Conductivity : Eco Rental

**** Field Meter ID for (): _____

	SW846	Std Methods		Lot #		Lot #		Lot #
Field Temp SOP 1156		2550 B	pH 4.0 Buffer	WC	Conductivity Std. 1412	74610	Std. _____	_____
pH in the Field SOP 1152	9040B	4500-H B	pH 7.0 Buffer	WC 230210B	Conductivity Std. _____	_____	Std. _____	_____
Field Cond. SOP 1155	9050A	2510 B	pH 10.0 Buffer	WC 230126C	Conductivity Std. _____	_____	Std. _____	_____
Other: _____			pH LCS/LCSD 7	WC 221117B	Conductivity LCS/LCSD _____	_____	LCS/LCSD _____	_____

pH Calibration			Conductivity Calibration			Calibration		
	Reading			Reading	units	Std	Units	Reading
Date: 5/31/23	4.00	4.00		μS	0-199.9			
Time: 8:30	7.00	7.01	1412	μS	0-1999	1412		
	10.00	10.02		mS	0-19.99			

Field Analyst Sig & Date: Juan Carlos 5/31/23
 Reviewed By & Date: _____
 Reviewed By & Date: _____

Field Analyst Sig & Date: Juan Carlos 5/31/23
 Reviewed By & Date: _____
 Reviewed By & Date: _____

Field Analyst Sig & Date: _____
 Reviewed By & Date: _____
 Reviewed By & Date: _____

Comments:

Field Analysis Log

Cross Reference to Sample ID	Date mm/dd/yy	Time	Temp. C	pH Results			Conductivity			Other: _____			
				Reading 1	Reading 2	LCSD	Range Factor	Reading 1	Reading 2	DF	Read1/units	DF	Read2/units
LCS	6/1/23	8:21	24.3	7.10				1414					
CCV	6/1/23	11:15	25.2	7.10				1417					

**** Field Meter ID for Temp, pH & Conductivity : Eco Rental

**** Field Meter ID for (): _____

	SW846	Std Methods		Lot #		Lot #	
Field Temp SOP 1156		2550 B	pH 4.0 Buffer	WC	Conductivity Std. 1412	74610	Std. _____
pH in the Field SOP 1152	9040B	4500-H B	pH 7.0 Buffer	WC 230210B	Conductivity Std. _____		Std. _____
Field Cond. SOP 1155	9050A	2510 B	pH 10.0 Buffer	WC 230126C	Conductivity Std. _____		Std. _____
Other: _____			pH LCS/LCSD _7_	WC 221117B	Conductivity LCS/LCSD _____		LCS/LCSD _____

pH Calibration			Conductivity Calibration			Calibration		
	Reading			Reading	units		Units	Reading
	4.00	<u>4.00</u>		μS	0-199.9	Std		
Date: <u>6/1/23</u>	7.00	<u>7.01</u>	<u>1412</u>	μS	0-1999	Std		
Time: <u>8:10</u>	10.00	<u>10.01</u>		mS	0-19.99	Std		
Field Analyst Sig & Date: <u>Tracy Carzde 6/1/23</u>			Field Analyst Sig & Date: <u>Tracy Carzde 6/1/23</u>			Field Analyst Sig & Date: _____		
Reviewed By & Date: _____			Reviewed By & Date: _____			Reviewed By & Date: _____		
Reviewed By & Date: _____			Reviewed By & Date: _____			Reviewed By & Date: _____		

Comments:

ANALYTICAL REPORT

PREPARED FOR

Attn: Brian Voelker
Vistra Energy Corp
133 S 4th, Suite 206
Springfield, Illinois 62701
Generated 11/16/23 10:56:43 Revision 3

JOB DESCRIPTION

HEN-23Q3
HEN_257_804

JOB NUMBER

500-238579-1

Job Notes

This report may not be reproduced except in full, and with written approval from the laboratory. The results relate only to the samples tested. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Chicago Project Manager.

Authorization



Generated
11/16/23 10:56:43
Revision 3

Authorized for release by
Dirk Nelson, Project Management Assistant II
Dirk.Nelson@et.eurofinsus.com
Designee for
Donna Campbell, Manager of Project Management
Donna.Campbell@et.eurofinsus.com
(217)519-2114

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Table of Contents

Cover Page	1
Table of Contents	3
Case Narrative	4
Method Summary	5
Sample Summary	6
Client Sample Results	7
Definitions	26
QC Association	27
Surrogate Summary	35
QC Sample Results	36
Chronicle	52
Certification Summary	59
Chain of Custody	60
Receipt Checklists	77
Field Data Sheets	78



Case Narrative

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Job ID: 500-238579-1

Laboratory: Eurofins Chicago

Narrative

Job Narrative 500-238579-1

Revision

The report being provided is a revision of the original report sent on 10/29/23. The report (revision 3) is being revised due to: COCs missing signature/date/time. Please remove all "Alkalinity (SM 2320B)" results.

Report revision history

Revision 1 - 11/07/23 - Reason - need to report program report and comprehensive report.

Revision 2 - 11/07/23 - Reason - Report Rev(1) is comprehensive. Rev(2) is for individual program report.

Receipt

The samples were received on 8/23/2023 10:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 28 coolers at receipt time were 0.1° C, 0.1° C, 0.2° C, 0.3° C, 0.4° C, 0.5° C, 0.6° C, 0.7° C, 0.8° C, 1.0° C, 1.2° C, 1.2° C, 1.3° C, 1.3° C, 1.3° C, 1.6° C, 1.7° C, 1.7° C, 1.7° C, 1.7° C, 2.0° C, 2.0° C, 2.0° C, 2.8° C, 2.9° C, 2.9° C, 3.0° C and 3.7° C.

Metals

Method 6020B: The initial low level calibration verification (ICVL) result for batch 735519 was above the upper control limit for Be. Sample results were non-detects, and have been reported as qualified data.

Method 6020B: The initial low level calibration verification (ICVL) result for batch 736032 was above the upper control limit for Be. Sample results were non-detects, and have been reported as qualified data.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Field Service / Mobile Lab

Method Field Sampling: "Depth to Water (ft from MP)" value reported is the value recorded in the "WL Reading on Transducer (ft)" column on the SAR-4 form for the following samples: HEN_21R (500-238579-1), HEN_22&D (500-238579-2), HEN_23 (500-238579-3), HEN_23_FD (500-238579-4), HEN_32 (500-238579-5), HEN_51 (500-238579-6), HEN_27 (500-238579-26), HEN_35 (500-238579-27), HEN_34 (500-238579-44), HEN_22 (500-238579-46) and HEN_50 (500-238579-47).

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

General Chemistry

Method 300.0: The method blank for analytical batch 500-729898 contained Chloride above the method detection limit. This target analyte concentration was less than the reporting limit (RL) in the method blank; therefore, re-extraction and/or re-analysis of samples was not performed.

Methods 300.0: The method blank for analytical batch 500-731549 contained Chloride above the method detection limit. This target analyte concentration was less than the reporting limit (RL) in the method blank; therefore, re-extraction and/or re-analysis of samples was not performed.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 590-238579-1
SDG: HEN_257_804

Method	Method Description	Protocol	Laboratory
200.7 Rev 4.4	Metals (ICP)	EPA	EET CHI
6020B	Metals (ICP/MS)	SW846	EET CHI
7470A	Mercury (CVAA)	SW846	EET CHI
300.0	Anions, Ion Chromatography	EPA	EET CHI
SM 2320B	Alkalinity	SM	EET CHI
SM 2540C	Solids, Total Dissolved (TDS)	SM	EET CHI
Field Sampling	Field Sampling	EPA	EET CHI
200.7	Preparation, Total Recoverable Metals	EPA	EET CHI
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET CHI
7470A	Preparation, Mercury	SW846	EET CHI
FILTRATION	Sample Filtration	None	EET CHI

Protocol References:

EPA = US Environmental Protection Agency

None = None

SM = "Standard Methods For The Examination Of Water And Wastewater"

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET CHI = Eurofins Chicago, 2417 Bond Street, University Park, IL 60484, TEL (708)534-5200

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
500-238579-1	HEN_21R	Water	08/22/23 13:45	08/23/23 10:00
500-238579-2	HEN_22&D	Water	08/22/23 09:10	08/23/23 10:00
500-238579-3	HEN_23	Water	08/22/23 11:20	08/23/23 10:00
500-238579-4	HEN_23_FD	Water	08/22/23 11:20	08/23/23 10:00
500-238579-5	HEN_32	Water	08/22/23 11:15	08/23/23 10:00
500-238579-6	HEN_51	Water	08/22/23 15:56	08/23/23 10:00
500-238579-7	HEN_25	Water	08/22/23 14:30	08/23/23 10:00
500-238579-8	HEN_26	Water	08/22/23 15:35	08/23/23 10:00
500-238579-26	HEN_27	Water	08/24/23 09:00	08/25/23 09:32
500-238579-27	HEN_35	Water	08/24/23 10:10	08/25/23 09:32
500-238579-44	HEN_34	Water	08/25/23 11:25	08/25/23 15:00
500-238579-45	HEN_49	Water	08/25/23 10:05	08/25/23 15:00
500-238579-46	HEN_22	Water	08/25/23 08:50	08/25/23 15:00
500-238579-47	HEN_50	Water	08/25/23 11:25	08/25/23 15:00
500-238579-48	WPCP_FB	Water	08/28/23 07:30	08/28/23 15:00
500-238579-61	HEN_30	Water	08/22/23 10:00	08/28/23 15:00
500-238579-62	HEN_31	Water	08/22/23 09:55	08/28/23 15:00
500-238579-63	HEN_33	Water	08/22/23 10:18	08/28/23 15:00
500-238579-64	HEN_36	Water	08/22/23 09:30	08/28/23 15:00

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
MINIHAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_21R

Lab Sample ID: 500-238579-1

Date Collected: 08/22/23 13:45

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.026	F1	0.010	0.0040	mg/L		08/25/23 09:24	09/19/23 15:00	2

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		08/29/23 08:50	09/05/23 14:31	1
Arsenic	0.023		0.0010	0.00023	mg/L		08/29/23 08:50	09/05/23 14:31	1
Barium	0.30		0.0025	0.00073	mg/L		08/29/23 08:50	09/05/23 14:31	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		08/29/23 08:50	09/05/23 14:31	1
Boron	1.7		0.050	0.013	mg/L		08/29/23 08:50	10/04/23 22:46	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		08/29/23 08:50	09/05/23 14:31	1
Calcium	120		0.20	0.044	mg/L		08/29/23 08:50	09/05/23 14:31	1
Chromium	0.0026	J	0.0050	0.0011	mg/L		08/29/23 08:50	09/05/23 14:31	1
Cobalt	0.0014		0.0010	0.00040	mg/L		08/29/23 08:50	09/05/23 14:31	1
Lead	0.0028		0.00050	0.00019	mg/L		08/29/23 08:50	09/05/23 14:31	1
Magnesium	39		0.20	0.049	mg/L		08/29/23 08:50	09/05/23 14:31	1
Molybdenum	0.0097		0.0050	0.0025	mg/L		08/29/23 08:50	09/05/23 14:31	1
Potassium	2.8		0.50	0.11	mg/L		08/29/23 08:50	09/05/23 14:31	1
Selenium	<0.0025		0.0025	0.00098	mg/L		08/29/23 08:50	09/05/23 14:31	1
Sodium	45		0.20	0.077	mg/L		08/29/23 08:50	10/04/23 22:46	1
Thallium	<0.0020		0.0020	0.00057	mg/L		08/29/23 08:50	09/05/23 14:31	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		08/30/23 11:30	08/31/23 06:58	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	95		5.0	0.58	mg/L			08/28/23 20:55	5
Fluoride (EPA 300.0)	0.23	J	1.0	0.19	mg/L			08/28/23 20:40	1
Sulfate (EPA 300.0)	94		5.0	1.0	mg/L			08/28/23 20:55	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	370		5.0	3.7	mg/L			08/28/23 16:42	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/28/23 16:42	1
Total Dissolved Solids (SM 2540C)	730		10	4.3	mg/L			08/28/23 18:38	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.51				SU			08/22/23 13:45	1
Field Temperature	16.6				Degrees C			08/22/23 13:45	1
Oxidation Reduction Potential	-136.3				millivolts			08/22/23 13:45	1
Oxygen, Dissolved	0.21				mg/L			08/22/23 13:45	1
Specific Conductance	762				umhos/cm			08/22/23 13:45	1
Turbidity	34.8				NTU			08/22/23 13:45	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_22&D

Lab Sample ID: 500-238579-2

Date Collected: 08/22/23 09:10

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.017		0.0050	0.0020	mg/L		08/25/23 09:24	09/19/23 15:12	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		08/29/23 08:50	09/05/23 14:35	1
Arsenic	0.0013		0.0010	0.00023	mg/L		08/29/23 08:50	09/05/23 14:35	1
Barium	0.066		0.0025	0.00073	mg/L		08/29/23 08:50	09/05/23 14:35	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		08/29/23 08:50	09/05/23 14:35	1
Boron	1.3		0.050	0.013	mg/L		08/29/23 08:50	10/04/23 22:50	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		08/29/23 08:50	09/05/23 14:35	1
Calcium	120		0.20	0.044	mg/L		08/29/23 08:50	09/05/23 14:35	1
Chromium	<0.0050		0.0050	0.0011	mg/L		08/29/23 08:50	09/05/23 14:35	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		08/29/23 08:50	09/05/23 14:35	1
Lead	<0.00050		0.00050	0.00019	mg/L		08/29/23 08:50	09/05/23 14:35	1
Magnesium	41		0.20	0.049	mg/L		08/29/23 08:50	09/05/23 14:35	1
Molybdenum	0.0067		0.0050	0.0025	mg/L		08/29/23 08:50	09/05/23 14:35	1
Potassium	3.1		0.50	0.11	mg/L		08/29/23 08:50	09/05/23 14:35	1
Selenium	<0.0025		0.0025	0.00098	mg/L		08/29/23 08:50	09/05/23 14:35	1
Sodium	44		0.20	0.077	mg/L		08/29/23 08:50	10/04/23 22:50	1
Thallium	<0.0020		0.0020	0.00057	mg/L		08/29/23 08:50	09/05/23 14:35	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		08/30/23 11:30	08/31/23 07:00	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	97		5.0	0.58	mg/L			08/28/23 21:25	5
Fluoride (EPA 300.0)	0.22	J	1.0	0.19	mg/L			08/28/23 21:10	1
Sulfate (EPA 300.0)	96		5.0	1.0	mg/L			08/28/23 21:25	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	340		5.0	3.7	mg/L			08/28/23 16:52	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/28/23 16:52	1
Total Dissolved Solids (SM 2540C)	690		10	4.3	mg/L			08/28/23 18:41	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.30				SU			08/22/23 09:10	1
Field Temperature	18.0				Degrees C			08/22/23 09:10	1
Oxidation Reduction Potential	-82.1				millivolts			08/22/23 09:10	1
Oxygen, Dissolved	0.91				mg/L			08/22/23 09:10	1
Specific Conductance	731				umhos/cm			08/22/23 09:10	1
Turbidity	24.8				NTU			08/22/23 09:10	1

Eurofins Chicago

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_23

Date Collected: 08/22/23 11:20

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-3

Matrix: Water

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.0063		0.0050	0.0020	mg/L		08/25/23 09:24	09/19/23 15:16	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		08/29/23 08:50	09/05/23 14:38	1
Arsenic	0.00089	J	0.0010	0.00023	mg/L		08/29/23 08:50	09/05/23 14:38	1
Barium	0.042		0.0025	0.00073	mg/L		08/29/23 08:50	09/05/23 14:38	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		08/29/23 08:50	09/05/23 14:38	1
Boron	8.1		0.050	0.013	mg/L		08/29/23 08:50	10/04/23 22:54	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		08/29/23 08:50	09/05/23 14:38	1
Calcium	110		0.20	0.044	mg/L		08/29/23 08:50	09/05/23 14:38	1
Chromium	<0.0050		0.0050	0.0011	mg/L		08/29/23 08:50	09/05/23 14:38	1
Cobalt	0.00047	J	0.0010	0.00040	mg/L		08/29/23 08:50	09/05/23 14:38	1
Lead	<0.00050		0.00050	0.00019	mg/L		08/29/23 08:50	09/05/23 14:38	1
Magnesium	78		0.20	0.049	mg/L		08/29/23 08:50	09/05/23 14:38	1
Molybdenum	0.015		0.0050	0.0025	mg/L		08/29/23 08:50	09/05/23 14:38	1
Potassium	2.9		0.50	0.11	mg/L		08/29/23 08:50	09/05/23 14:38	1
Selenium	<0.0025		0.0025	0.00098	mg/L		08/29/23 08:50	09/05/23 14:38	1
Sodium	44		0.20	0.077	mg/L		08/29/23 08:50	10/04/23 22:54	1
Thallium	<0.0020		0.0020	0.00057	mg/L		08/29/23 08:50	09/05/23 14:38	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		08/30/23 11:30	08/31/23 07:02	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	53		50	5.8	mg/L			08/28/23 21:56	50
Fluoride (EPA 300.0)	0.23	J	1.0	0.19	mg/L			08/28/23 21:41	1
Sulfate (EPA 300.0)	460		50	10	mg/L			08/28/23 21:56	50
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	150		5.0	3.7	mg/L			08/28/23 17:04	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/28/23 17:04	1
Total Dissolved Solids (SM 2540C)	950		10	4.3	mg/L			08/28/23 18:43	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.40				SU			08/22/23 11:20	1
Field Temperature	15.0				Degrees C			08/22/23 11:20	1
Oxidation Reduction Potential	-124.3				millivolts			08/22/23 11:20	1
Oxygen, Dissolved	0.18				mg/L			08/22/23 11:20	1
Specific Conductance	832				umhos/cm			08/22/23 11:20	1
Turbidity	9.1				NTU			08/22/23 11:20	1

Eurofins Chicago

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_23_FD

Lab Sample ID: 500-238579-4

Date Collected: 08/22/23 11:20

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.0055		0.0050	0.0020	mg/L		08/25/23 09:24	09/19/23 15:21	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		08/29/23 08:50	09/05/23 14:42	1
Arsenic	0.00094	J	0.0010	0.00023	mg/L		08/29/23 08:50	09/05/23 14:42	1
Barium	0.043		0.0025	0.00073	mg/L		08/29/23 08:50	09/05/23 14:42	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		08/29/23 08:50	09/05/23 14:42	1
Boron	7.9		0.050	0.013	mg/L		08/29/23 08:50	10/04/23 22:58	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		08/29/23 08:50	09/05/23 14:42	1
Calcium	110		0.20	0.044	mg/L		08/29/23 08:50	09/05/23 14:42	1
Chromium	<0.0050		0.0050	0.0011	mg/L		08/29/23 08:50	09/05/23 14:42	1
Cobalt	0.00048	J	0.0010	0.00040	mg/L		08/29/23 08:50	09/05/23 14:42	1
Lead	<0.00050		0.00050	0.00019	mg/L		08/29/23 08:50	09/05/23 14:42	1
Magnesium	80		0.20	0.049	mg/L		08/29/23 08:50	09/05/23 14:42	1
Molybdenum	0.016		0.0050	0.0025	mg/L		08/29/23 08:50	09/05/23 14:42	1
Potassium	3.0		0.50	0.11	mg/L		08/29/23 08:50	09/05/23 14:42	1
Selenium	<0.0025		0.0025	0.00098	mg/L		08/29/23 08:50	09/05/23 14:42	1
Sodium	42		0.20	0.077	mg/L		08/29/23 08:50	10/04/23 22:58	1
Thallium	<0.0020		0.0020	0.00057	mg/L		08/29/23 08:50	09/05/23 14:42	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		08/30/23 11:30	08/31/23 07:04	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	53		50	5.8	mg/L			08/28/23 22:56	50
Fluoride (EPA 300.0)	0.23	J	1.0	0.19	mg/L			08/28/23 22:41	1
Sulfate (EPA 300.0)	460		50	10	mg/L			08/28/23 22:56	50
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	160		5.0	3.7	mg/L			08/28/23 17:13	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/28/23 17:13	1
Total Dissolved Solids (SM 2540C)	950		10	4.3	mg/L			08/28/23 18:46	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.40				SU			08/22/23 11:20	1
Field Temperature	15.0				Degrees C			08/22/23 11:20	1
Oxidation Reduction Potential	-124.3				millivolts			08/22/23 11:20	1
Oxygen, Dissolved	0.18				mg/L			08/22/23 11:20	1
Specific Conductance	832				umhos/cm			08/22/23 11:20	1
Turbidity	9.1				NTU			08/22/23 11:20	1

Eurofins Chicago

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
MINIHAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_32

Lab Sample ID: 500-238579-5

Date Collected: 08/22/23 11:15

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.0048	J	0.0050	0.0020	mg/L		08/25/23 09:24	09/19/23 15:25	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		08/29/23 08:50	09/05/23 14:45	1
Arsenic	0.00049	J	0.0010	0.00023	mg/L		08/29/23 08:50	09/05/23 14:45	1
Barium	0.039		0.0025	0.00073	mg/L		08/29/23 08:50	09/05/23 14:45	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		08/29/23 08:50	09/05/23 14:45	1
Boron	0.14		0.050	0.013	mg/L		08/29/23 08:50	10/04/23 23:01	1
Cadmium	0.00021	J	0.00050	0.00017	mg/L		08/29/23 08:50	09/05/23 14:45	1
Calcium	100		0.20	0.044	mg/L		08/29/23 08:50	09/05/23 14:45	1
Chromium	<0.0050		0.0050	0.0011	mg/L		08/29/23 08:50	09/05/23 14:45	1
Cobalt	0.0014		0.0010	0.00040	mg/L		08/29/23 08:50	09/05/23 14:45	1
Lead	<0.00050		0.00050	0.00019	mg/L		08/29/23 08:50	09/05/23 14:45	1
Magnesium	39		0.20	0.049	mg/L		08/29/23 08:50	09/05/23 14:45	1
Molybdenum	<0.0050		0.0050	0.0025	mg/L		08/29/23 08:50	09/05/23 14:45	1
Potassium	2.1		0.50	0.11	mg/L		08/29/23 08:50	09/05/23 14:45	1
Selenium	<0.0025		0.0025	0.00098	mg/L		08/29/23 08:50	09/05/23 14:45	1
Sodium	38		0.20	0.077	mg/L		08/29/23 08:50	10/04/23 23:01	1
Thallium	<0.0020		0.0020	0.00057	mg/L		08/29/23 08:50	09/05/23 14:45	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		08/30/23 11:30	08/31/23 07:06	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	68		2.0	0.23	mg/L			08/28/23 23:27	2
Fluoride (EPA 300.0)	0.22	J	1.0	0.19	mg/L			08/28/23 23:12	1
Sulfate (EPA 300.0)	66		2.0	0.41	mg/L			08/28/23 23:27	2
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	320		5.0	3.7	mg/L			08/28/23 17:22	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/28/23 17:22	1
Total Dissolved Solids (SM 2540C)	570		10	4.3	mg/L			08/28/23 18:48	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.09				SU			08/22/23 11:15	1
Field Temperature	13.8				Degrees C			08/22/23 11:15	1
Oxidation Reduction Potential	151.7				millivolts			08/22/23 11:15	1
Oxygen, Dissolved	0.09				mg/L			08/22/23 11:15	1
Specific Conductance	715				umhos/cm			08/22/23 11:15	1
Turbidity	5.33				NTU			08/22/23 11:15	1

Eurofins Chicago

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
MINIHAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_51

Lab Sample ID: 500-238579-6

Date Collected: 08/22/23 15:56

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.025		0.0050	0.0020	mg/L		08/25/23 09:24	09/19/23 15:29	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		08/29/23 08:50	09/05/23 14:49	1
Arsenic	0.019		0.0010	0.00023	mg/L		08/29/23 08:50	09/05/23 14:49	1
Barium	0.10		0.0025	0.00073	mg/L		08/29/23 08:50	09/05/23 14:49	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		08/29/23 08:50	09/05/23 14:49	1
Boron	1.3		0.050	0.013	mg/L		08/29/23 08:50	10/04/23 23:05	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		08/29/23 08:50	09/05/23 14:49	1
Calcium	110		0.20	0.044	mg/L		08/29/23 08:50	09/05/23 14:49	1
Chromium	0.0011	J	0.0050	0.0011	mg/L		08/29/23 08:50	09/05/23 14:49	1
Cobalt	0.00086	J	0.0010	0.00040	mg/L		08/29/23 08:50	09/05/23 14:49	1
Lead	0.0012		0.00050	0.00019	mg/L		08/29/23 08:50	09/05/23 14:49	1
Magnesium	37		0.20	0.049	mg/L		08/29/23 08:50	09/05/23 14:49	1
Molybdenum	0.0089		0.0050	0.0025	mg/L		08/29/23 08:50	09/05/23 14:49	1
Potassium	5.6		0.50	0.11	mg/L		08/29/23 08:50	09/05/23 14:49	1
Selenium	<0.0025		0.0025	0.00098	mg/L		08/29/23 08:50	09/05/23 14:49	1
Sodium	52		0.20	0.077	mg/L		08/29/23 08:50	10/04/23 23:05	1
Thallium	<0.0020		0.0020	0.00057	mg/L		08/29/23 08:50	09/05/23 14:49	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		08/30/23 11:30	08/31/23 07:08	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	94		5.0	0.58	mg/L			08/28/23 23:57	5
Fluoride (EPA 300.0)	0.23	J	1.0	0.19	mg/L			08/28/23 23:42	1
Sulfate (EPA 300.0)	90		5.0	1.0	mg/L			08/28/23 23:57	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	340		5.0	3.7	mg/L			08/28/23 17:31	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/28/23 17:31	1
Total Dissolved Solids (SM 2540C)	680		10	4.3	mg/L			08/28/23 18:51	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.37				SU			08/22/23 15:56	1
Field Temperature	17.3				Degrees C			08/22/23 15:56	1
Oxidation Reduction Potential	-128.6				millivolts			08/22/23 15:56	1
Oxygen, Dissolved	0.27				mg/L			08/22/23 15:56	1
Specific Conductance	730				umhos/cm			08/22/23 15:56	1
Turbidity	26.2				NTU			08/22/23 15:56	1

Eurofins Chicago

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_25
Date Collected: 08/22/23 14:30
Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-7
Matrix: Water

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	14.02				ft			08/22/23 14:30	1

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_26

Date Collected: 08/22/23 15:35

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-8

Matrix: Water

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	13.26				ft			08/22/23 15:35	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
MINIHAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_27

Lab Sample ID: 500-238579-26

Date Collected: 08/24/23 09:00

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.024		0.0050	0.0020	mg/L		09/21/23 19:27	09/26/23 16:16	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		08/29/23 08:50	09/05/23 16:04	1
Arsenic	0.0010		0.0010	0.00023	mg/L		08/29/23 08:50	09/05/23 16:04	1
Barium	0.084		0.0025	0.00073	mg/L		08/29/23 08:50	09/05/23 16:04	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		08/29/23 08:50	09/05/23 16:04	1
Boron	2.0		0.050	0.013	mg/L		08/29/23 08:50	10/05/23 00:28	1
Cadmium	0.00025	J	0.00050	0.00017	mg/L		08/29/23 08:50	09/05/23 16:04	1
Calcium	120		0.20	0.044	mg/L		08/29/23 08:50	09/05/23 16:04	1
Chromium	<0.0050		0.0050	0.0011	mg/L		08/29/23 08:50	09/05/23 16:04	1
Cobalt	0.0026		0.0010	0.00040	mg/L		08/29/23 08:50	09/05/23 16:04	1
Lead	0.00020	J	0.00050	0.00019	mg/L		08/29/23 08:50	09/05/23 16:04	1
Magnesium	37		0.20	0.049	mg/L		08/29/23 08:50	09/05/23 16:04	1
Molybdenum	0.0047	J	0.0050	0.0025	mg/L		08/29/23 08:50	09/05/23 16:04	1
Potassium	3.5		0.50	0.11	mg/L		08/29/23 08:50	09/05/23 16:04	1
Selenium	<0.0025		0.0025	0.00098	mg/L		08/29/23 08:50	09/05/23 16:04	1
Sodium	52		0.20	0.077	mg/L		08/29/23 08:50	10/05/23 00:28	1
Thallium	<0.0020		0.0020	0.00057	mg/L		08/29/23 08:50	09/05/23 16:04	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.000090	J	0.00020	0.000079	mg/L		08/30/23 11:30	08/31/23 07:44	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	91	B	10	1.2	mg/L			08/29/23 20:04	10
Fluoride (EPA 300.0)	0.22	J	1.0	0.19	mg/L			08/29/23 19:49	1
Sulfate (EPA 300.0)	110		10	2.1	mg/L			08/29/23 20:04	10
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	340		5.0	3.7	mg/L			08/30/23 16:17	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/30/23 16:17	1
Total Dissolved Solids (SM 2540C)	660		10	4.3	mg/L			08/28/23 21:33	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.33				SU			08/24/23 09:00	1
Field Temperature	12.5				Degrees C			08/24/23 09:00	1
Oxidation Reduction Potential	-33.7				millivolts			08/24/23 09:00	1
Oxygen, Dissolved	0.07				mg/L			08/24/23 09:00	1
Specific Conductance	816				umhos/cm			08/24/23 09:00	1
Turbidity	48.89				NTU			08/24/23 09:00	1

Eurofins Chicago

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_35

Date Collected: 08/24/23 10:10

Date Received: 08/25/23 09:32

Lab Sample ID: 500-238579-27

Matrix: Water

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.034		0.0050	0.0020	mg/L		09/21/23 19:27	09/26/23 16:20	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		09/01/23 08:58	10/05/23 02:37	1
Arsenic	0.00094	J B	0.0010	0.00023	mg/L		09/01/23 08:58	10/05/23 02:37	1
Barium	0.047		0.0025	0.00073	mg/L		09/01/23 08:58	10/05/23 02:37	1
Beryllium	<0.0010	^1+	0.0010	0.00053	mg/L		09/01/23 08:58	10/05/23 02:37	1
Boron	12		0.050	0.013	mg/L		09/01/23 08:58	10/05/23 02:37	1
Cadmium	0.00031	J	0.00050	0.00017	mg/L		09/01/23 08:58	10/05/23 02:37	1
Calcium	320	B	0.20	0.044	mg/L		09/01/23 08:58	10/05/23 02:37	1
Chromium	<0.0050		0.0050	0.0011	mg/L		09/01/23 08:58	10/05/23 02:37	1
Cobalt	0.0012		0.0010	0.00040	mg/L		09/01/23 08:58	10/05/23 02:37	1
Lead	<0.00050		0.00050	0.00019	mg/L		09/01/23 08:58	10/05/23 02:37	1
Magnesium	42		0.20	0.049	mg/L		09/01/23 08:58	10/05/23 02:37	1
Molybdenum	0.076		0.0050	0.0025	mg/L		09/01/23 08:58	10/05/23 02:37	1
Potassium	14		0.50	0.11	mg/L		09/01/23 08:58	10/05/23 02:37	1
Selenium	<0.0025		0.0025	0.00098	mg/L		09/01/23 08:58	10/06/23 22:48	1
Sodium	30	B	0.20	0.077	mg/L		09/01/23 08:58	10/05/23 02:37	1
Thallium	<0.0020		0.0020	0.00057	mg/L		09/01/23 08:58	10/09/23 12:31	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		08/30/23 11:30	08/31/23 07:47	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	37	B	1.0	0.12	mg/L			08/29/23 20:19	1
Fluoride (EPA 300.0)	0.20	J	1.0	0.19	mg/L			08/29/23 20:19	1
Sulfate (EPA 300.0)	890		100	21	mg/L			08/29/23 20:35	100
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	210		5.0	3.7	mg/L			08/30/23 16:27	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/30/23 16:27	1
Total Dissolved Solids (SM 2540C)	1600		10	4.3	mg/L			08/28/23 21:36	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	8.87				ft			08/24/23 10:10	1
Field pH	7.03				SU			08/24/23 10:10	1
Field Temperature	16.2				Degrees C			08/24/23 10:10	1
Oxidation Reduction Potential	161.7				millivolts			08/24/23 10:10	1
Oxygen, Dissolved	1.47				mg/L			08/24/23 10:10	1
Specific Conductance	1358				umhos/cm			08/24/23 10:10	1
Turbidity	2.81				NTU			08/24/23 10:10	1

Eurofins Chicago

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_34

Lab Sample ID: 500-238579-44

Date Collected: 08/25/23 11:25

Matrix: Water

Date Received: 08/25/23 15:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.013		0.0050	0.0020	mg/L		09/21/23 19:27	09/26/23 17:19	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		09/01/23 08:58	10/05/23 03:30	1
Arsenic	0.00086	J B	0.0010	0.00023	mg/L		09/01/23 08:58	10/05/23 03:30	1
Barium	0.11		0.0025	0.00073	mg/L		09/01/23 08:58	10/05/23 03:30	1
Beryllium	<0.0010	^1+	0.0010	0.00053	mg/L		09/01/23 08:58	10/05/23 03:30	1
Boron	0.075		0.050	0.013	mg/L		09/01/23 08:58	10/05/23 03:30	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		09/01/23 08:58	10/05/23 03:30	1
Calcium	150	B	0.20	0.044	mg/L		09/01/23 08:58	10/05/23 03:30	1
Chromium	<0.0050		0.0050	0.0011	mg/L		09/01/23 08:58	10/05/23 03:30	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		09/01/23 08:58	10/05/23 03:30	1
Lead	<0.00050		0.00050	0.00019	mg/L		09/01/23 08:58	10/05/23 03:30	1
Magnesium	40		0.20	0.049	mg/L		09/01/23 08:58	10/05/23 03:30	1
Molybdenum	<0.0050		0.0050	0.0025	mg/L		09/01/23 08:58	10/05/23 03:30	1
Potassium	0.42	J	0.50	0.11	mg/L		09/01/23 08:58	10/05/23 03:30	1
Selenium	<0.0025		0.0025	0.00098	mg/L		09/01/23 08:58	10/06/23 23:36	1
Sodium	44	B	0.20	0.077	mg/L		09/01/23 08:58	10/05/23 03:30	1
Thallium	<0.0020		0.0020	0.00057	mg/L		09/01/23 08:58	10/09/23 13:19	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.00015	J	0.00020	0.000079	mg/L		08/31/23 11:45	09/01/23 07:52	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	69		5.0	0.58	mg/L			08/30/23 03:39	5
Fluoride (EPA 300.0)	0.19	J	1.0	0.19	mg/L			08/30/23 03:24	1
Sulfate (EPA 300.0)	46		1.0	0.21	mg/L			08/30/23 03:24	1
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	570		5.0	3.7	mg/L			08/31/23 17:19	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/31/23 17:19	1
Total Dissolved Solids (SM 2540C)	760		10	4.3	mg/L			08/30/23 19:57	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	8.98				ft			08/25/23 11:25	1
Field pH	7.08				SU			08/25/23 11:25	1
Field Temperature	12.8				Degrees C			08/25/23 11:25	1
Oxidation Reduction Potential	-110.7				millivolts			08/25/23 11:25	1
Oxygen, Dissolved	0.20				mg/L			08/25/23 11:25	1
Specific Conductance	972				umhos/cm			08/25/23 11:25	1
Turbidity	4.81				NTU			08/25/23 11:25	1

Eurofins Chicago

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_49

Lab Sample ID: 500-238579-45

Date Collected: 08/25/23 10:05

Matrix: Water

Date Received: 08/25/23 15:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.023		0.0050	0.0020	mg/L		09/21/23 19:27	09/26/23 17:24	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		09/01/23 08:58	10/06/23 23:40	1
Arsenic	0.00049	J	0.0010	0.00023	mg/L		09/01/23 08:58	10/06/23 23:40	1
Barium	0.062		0.0025	0.00073	mg/L		09/01/23 08:58	10/06/23 23:40	1
Beryllium	<0.0010	^1+	0.0010	0.00053	mg/L		09/01/23 08:58	10/06/23 23:40	1
Boron	0.69	B	0.050	0.013	mg/L		10/09/23 18:08	10/11/23 10:15	1
Cadmium	0.0013		0.00050	0.00017	mg/L		09/01/23 08:58	10/06/23 23:40	1
Calcium	99	B	0.20	0.044	mg/L		09/01/23 08:58	10/06/23 23:40	1
Chromium	<0.0050		0.0050	0.0011	mg/L		09/01/23 08:58	10/06/23 23:40	1
Cobalt	0.0033		0.0010	0.00040	mg/L		09/01/23 08:58	10/06/23 23:40	1
Lead	0.00036	J	0.00050	0.00019	mg/L		09/01/23 08:58	10/06/23 23:40	1
Magnesium	32	F1	0.20	0.049	mg/L		09/01/23 08:58	10/06/23 23:40	1
Molybdenum	0.023		0.0050	0.0025	mg/L		10/09/23 18:08	10/10/23 12:58	1
Potassium	11		0.50	0.11	mg/L		09/01/23 08:58	10/06/23 23:40	1
Selenium	<0.0025		0.0025	0.00098	mg/L		09/01/23 08:58	10/06/23 23:40	1
Sodium	56		0.20	0.077	mg/L		09/01/23 08:58	10/06/23 23:40	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/09/23 18:08	10/10/23 12:58	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		09/01/23 12:30	09/05/23 07:16	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	95	F1	5.0	0.58	mg/L			08/30/23 05:10	5
Fluoride (EPA 300.0)	0.24	J	1.0	0.19	mg/L			08/30/23 03:54	1
Sulfate (EPA 300.0)	78		5.0	1.0	mg/L			08/30/23 05:10	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	330		5.0	3.7	mg/L			08/31/23 17:29	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/31/23 17:29	1
Total Dissolved Solids (SM 2540C)	620		10	4.3	mg/L			08/30/23 20:03	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	19.65				ft			08/25/23 10:05	1
Field pH	7.12				SU			08/25/23 10:05	1
Field Temperature	15.3				Degrees C			08/25/23 10:05	1
Oxidation Reduction Potential	58.2				millivolts			08/25/23 10:05	1
Oxygen, Dissolved	0.11				mg/L			08/25/23 10:05	1
Specific Conductance	698				umhos/cm			08/25/23 10:05	1
Turbidity	123.6				NTU			08/25/23 10:05	1

Eurofins Chicago

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_22

Lab Sample ID: 500-238579-46

Date Collected: 08/25/23 08:50

Matrix: Water

Date Received: 08/25/23 15:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.049		0.0050	0.0020	mg/L		09/21/23 19:27	09/26/23 17:40	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		09/01/23 08:58	10/05/23 03:45	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		09/01/23 08:58	10/05/23 03:45	1
Barium	0.013		0.0025	0.00073	mg/L		09/01/23 08:58	10/05/23 03:45	1
Beryllium	<0.0010	^1+	0.0010	0.00053	mg/L		09/01/23 08:58	10/05/23 03:45	1
Boron	0.13		0.050	0.013	mg/L		09/01/23 08:58	10/05/23 03:45	1
Cadmium	0.00029	J	0.00050	0.00017	mg/L		09/01/23 08:58	10/05/23 03:45	1
Calcium	23	B	0.20	0.044	mg/L		09/01/23 08:58	10/05/23 03:45	1
Chromium	<0.0050		0.0050	0.0011	mg/L		09/01/23 08:58	10/05/23 03:45	1
Cobalt	0.00076	J	0.0010	0.00040	mg/L		09/01/23 08:58	10/05/23 03:45	1
Lead	<0.00050		0.00050	0.00019	mg/L		09/01/23 08:58	10/05/23 03:45	1
Magnesium	7.1		0.20	0.049	mg/L		09/01/23 08:58	10/05/23 03:45	1
Molybdenum	0.0050		0.0050	0.0025	mg/L		09/01/23 08:58	10/05/23 03:45	1
Potassium	2.5		0.50	0.11	mg/L		09/01/23 08:58	10/05/23 03:45	1
Selenium	0.015		0.0025	0.00098	mg/L		09/01/23 08:58	10/10/23 12:14	1
Sodium	12	B	0.20	0.077	mg/L		09/01/23 08:58	10/05/23 03:45	1
Thallium	<0.0020		0.0020	0.00057	mg/L		09/01/23 08:58	10/10/23 12:14	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		09/01/23 12:30	09/05/23 07:24	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	89		10	1.2	mg/L			08/30/23 06:11	10
Fluoride (EPA 300.0)	0.22	J	1.0	0.19	mg/L			08/30/23 05:56	1
Sulfate (EPA 300.0)	120		10	2.1	mg/L			08/30/23 06:11	10
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	240		5.0	3.7	mg/L			08/31/23 17:39	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/31/23 17:39	1
Total Dissolved Solids (SM 2540C)	640		10	4.3	mg/L			08/30/23 20:10	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.67				SU			08/25/23 08:50	1
Field Temperature	16.1				Degrees C			08/25/23 08:50	1
Oxidation Reduction Potential	77.8				millivolts			08/25/23 08:50	1
Oxygen, Dissolved	0.12				mg/L			08/25/23 08:50	1
Specific Conductance	653				umhos/cm			08/25/23 08:50	1
Turbidity	4.31				NTU			08/25/23 08:50	1

Eurofins Chicago

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_50

Lab Sample ID: 500-238579-47

Date Collected: 08/25/23 11:25

Matrix: Water

Date Received: 08/25/23 15:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.025		0.0050	0.0020	mg/L		09/21/23 19:27	09/26/23 17:53	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		09/01/23 08:58	10/05/23 03:49	1
Arsenic	0.00072	J B	0.0010	0.00023	mg/L		09/01/23 08:58	10/05/23 03:49	1
Barium	0.064		0.0025	0.00073	mg/L		09/01/23 08:58	10/05/23 03:49	1
Beryllium	<0.0010	^1+	0.0010	0.00053	mg/L		09/01/23 08:58	10/05/23 03:49	1
Boron	0.59		0.050	0.013	mg/L		09/01/23 08:58	10/05/23 03:49	1
Cadmium	0.0014		0.00050	0.00017	mg/L		09/01/23 08:58	10/05/23 03:49	1
Calcium	100	B	0.20	0.044	mg/L		09/01/23 08:58	10/05/23 03:49	1
Chromium	<0.0050		0.0050	0.0011	mg/L		09/01/23 08:58	10/05/23 03:49	1
Cobalt	0.0035		0.0010	0.00040	mg/L		09/01/23 08:58	10/05/23 03:49	1
Lead	0.00040	J	0.00050	0.00019	mg/L		09/01/23 08:58	10/05/23 03:49	1
Magnesium	31		0.20	0.049	mg/L		09/01/23 08:58	10/05/23 03:49	1
Molybdenum	0.025		0.0050	0.0025	mg/L		09/01/23 08:58	10/05/23 03:49	1
Potassium	11		0.50	0.11	mg/L		09/01/23 08:58	10/05/23 03:49	1
Selenium	<0.0025		0.0025	0.00098	mg/L		09/01/23 08:58	10/10/23 12:19	1
Sodium	54	B	0.20	0.077	mg/L		09/01/23 08:58	10/05/23 03:49	1
Thallium	<0.0020		0.0020	0.00057	mg/L		09/01/23 08:58	10/10/23 12:19	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		09/01/23 12:30	09/05/23 07:27	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	87		5.0	0.58	mg/L			08/30/23 06:41	5
Fluoride (EPA 300.0)	0.20	J	1.0	0.19	mg/L			08/30/23 06:26	1
Sulfate (EPA 300.0)	93		5.0	1.0	mg/L			08/30/23 06:41	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	280		5.0	3.7	mg/L			08/31/23 17:48	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			08/31/23 17:48	1
Total Dissolved Solids (SM 2540C)	610		10	4.3	mg/L			08/30/23 20:13	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.47				SU			08/25/23 11:25	1
Field Temperature	16.7				Degrees C			08/25/23 11:25	1
Oxidation Reduction Potential	88.0				millivolts			08/25/23 11:25	1
Oxygen, Dissolved	0.12				mg/L			08/25/23 11:25	1
Specific Conductance	665				umhos/cm			08/25/23 11:25	1
Turbidity	3.98				NTU			08/25/23 11:25	1

Eurofins Chicago

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: WPCP_FB

Lab Sample ID: 500-238579-48

Date Collected: 08/28/23 07:30

Matrix: Water

Date Received: 08/28/23 15:00

General Chemistry - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride, Dissolved (EPA 300.0)	11		1.0	0.12	mg/L			09/11/23 15:48	1
Fluoride, Dissolved (EPA 300.0)	0.30	J	1.0	0.19	mg/L			09/11/23 15:48	1
Sulfate, Dissolved (EPA 300.0)	23		1.0	0.21	mg/L			09/11/23 15:48	1

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_30

Date Collected: 08/22/23 10:00

Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-61

Matrix: Water

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	4.85				ft			08/22/23 10:00	1

Client Sample Results

APPENDIX A.
 INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
 Project/Site: HEN-23Q3

Job ID: 500-238579-1
 Job ID: 500-238579-1
 SDG: HEN_257_804

Client Sample ID: HEN_31
Date Collected: 08/22/23 09:55
Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-62
Matrix: Water

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	4.85				ft			08/22/23 09:55	1

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_33
Date Collected: 08/22/23 10:18
Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-63
Matrix: Water

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	2.8				ft			08/22/23 10:18	1

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_36
Date Collected: 08/22/23 09:30
Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-64
Matrix: Water

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	13.58				ft			08/22/23 09:30	1

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

Definitions/Glossary

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
JEN-257_804
SDG: HEN_257_804

Qualifiers

Metals

Qualifier	Qualifier Description
^1+	Initial Calibration Verification (ICV) is outside acceptance limits, high biased.
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.
B	Compound was found in the blank and sample.
F1	MS and/or MSD recovery exceeds control limits.
F2	MS/MSD RPD exceeds control limits
F3	Duplicate RPD exceeds the control limit
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

General Chemistry

Qualifier	Qualifier Description
B	Compound was found in the blank and sample.
F1	MS and/or MSD recovery exceeds control limits.
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Metals

Prep Batch: 729478

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total Recoverable	Water	200.7	
500-238579-2	HEN_22&D	Total Recoverable	Water	200.7	
500-238579-3	HEN_23	Total Recoverable	Water	200.7	
500-238579-4	HEN_23_FD	Total Recoverable	Water	200.7	
500-238579-5	HEN_32	Total Recoverable	Water	200.7	
500-238579-6	HEN_51	Total Recoverable	Water	200.7	
MB 500-729478/1-A	Method Blank	Total Recoverable	Water	200.7	
LCS 500-729478/2-A	Lab Control Sample	Total Recoverable	Water	200.7	
500-238579-1 MS	HEN_21R	Total Recoverable	Water	200.7	
500-238579-1 DU	HEN_21R	Total Recoverable	Water	200.7	

Prep Batch: 729685

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-45 MSD	HEN_49_MSD	Total Recoverable	Water	200.7	

Prep Batch: 729866

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total Recoverable	Water	3005A	
500-238579-2	HEN_22&D	Total Recoverable	Water	3005A	
500-238579-3	HEN_23	Total Recoverable	Water	3005A	
500-238579-4	HEN_23_FD	Total Recoverable	Water	3005A	
500-238579-5	HEN_32	Total Recoverable	Water	3005A	
500-238579-6	HEN_51	Total Recoverable	Water	3005A	
500-238579-26	HEN_27	Total Recoverable	Water	3005A	
MB 500-729866/1-A	Method Blank	Total Recoverable	Water	3005A	
LCS 500-729866/2-A	Lab Control Sample	Total Recoverable	Water	3005A	
500-238579-G-8-G MS	500-238579-G-8-G MS	Total Recoverable	Water	3005A	
500-238579-G-8-H MSD	500-238579-G-8-H MSD	Total Recoverable	Water	3005A	
500-238579-G-8-F DU	500-238579-G-8-F DU	Total Recoverable	Water	3005A	

Prep Batch: 730135

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total/NA	Water	7470A	
500-238579-2	HEN_22&D	Total/NA	Water	7470A	
500-238579-3	HEN_23	Total/NA	Water	7470A	
500-238579-4	HEN_23_FD	Total/NA	Water	7470A	
500-238579-5	HEN_32	Total/NA	Water	7470A	
500-238579-6	HEN_51	Total/NA	Water	7470A	
500-238579-26	HEN_27	Total/NA	Water	7470A	
500-238579-27	HEN_35	Total/NA	Water	7470A	
MB 500-730135/12-A	Method Blank	Total/NA	Water	7470A	
LCS 500-730135/13-A	Lab Control Sample	Total/NA	Water	7470A	
500-238579-G-8-K MS	500-238579-G-8-K MS	Total/NA	Water	7470A	
500-238579-G-8-L MSD	500-238579-G-8-L MSD	Total/NA	Water	7470A	
500-238579-G-8-J DU	500-238579-G-8-J DU	Total/NA	Water	7470A	

Analysis Batch: 730327

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total/NA	Water	7470A	730135
500-238579-2	HEN_22&D	Total/NA	Water	7470A	730135
500-238579-3	HEN_23	Total/NA	Water	7470A	730135

Eurofins Chicago

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Metals (Continued)

Analysis Batch: 730327 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-4	HEN_23_FD	Total/NA	Water	7470A	730135
500-238579-5	HEN_32	Total/NA	Water	7470A	730135
500-238579-6	HEN_51	Total/NA	Water	7470A	730135
500-238579-26	HEN_27	Total/NA	Water	7470A	730135
500-238579-27	HEN_35	Total/NA	Water	7470A	730135
MB 500-730135/12-A	Method Blank	Total/NA	Water	7470A	730135
LCS 500-730135/13-A	Lab Control Sample	Total/NA	Water	7470A	730135
500-238579-G-8-K MS	500-238579-G-8-K MS	Total/NA	Water	7470A	730135
500-238579-G-8-L MSD	500-238579-G-8-L MSD	Total/NA	Water	7470A	730135
500-238579-G-8-J DU	500-238579-G-8-J DU	Total/NA	Water	7470A	730135

Prep Batch: 730358

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-44	HEN_34	Total/NA	Water	7470A	
MB 500-730358/12-A	Method Blank	Total/NA	Water	7470A	
LCS 500-730358/13-A	Lab Control Sample	Total/NA	Water	7470A	

Filtration Batch: 730368

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 500-730368/1-C	Method Blank	Total/NA	Water	FILTRATION	

Analysis Batch: 730525

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MRL 500-730525/21	Lab Control Sample	Total/NA	Water	200.7 Rev 4.4	

Prep Batch: 730528

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-27	HEN_35	Total Recoverable	Water	3005A	
500-238579-44	HEN_34	Total Recoverable	Water	3005A	
500-238579-45	HEN_49	Total Recoverable	Water	3005A	
500-238579-46	HEN_22	Total Recoverable	Water	3005A	
500-238579-47	HEN_50	Total Recoverable	Water	3005A	
MB 500-730528/1-A	Method Blank	Total Recoverable	Water	3005A	
LCS 500-730528/2-A	Lab Control Sample	Total Recoverable	Water	3005A	
500-238579-45 MS	HEN_49_MS	Total Recoverable	Water	3005A	
500-238579-45 MSD	HEN_49_MSD	Total Recoverable	Water	3005A	
500-238579-45 DU	HEN_49	Total Recoverable	Water	3005A	

Analysis Batch: 730570

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-44	HEN_34	Total/NA	Water	7470A	730358
MB 500-730358/12-A	Method Blank	Total/NA	Water	7470A	730358
LCS 500-730358/13-A	Lab Control Sample	Total/NA	Water	7470A	730358

Prep Batch: 730601

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-45	HEN_49	Total/NA	Water	7470A	
500-238579-46	HEN_22	Total/NA	Water	7470A	
500-238579-47	HEN_50	Total/NA	Water	7470A	
MB 500-730368/1-C	Method Blank	Total/NA	Water	7470A	730368
MB 500-730601/12-A	Method Blank	Total/NA	Water	7470A	

Eurofins Chicago

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Metals (Continued)

Prep Batch: 730601 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
LCS 500-730601/13-A	Lab Control Sample	Total/NA	Water	7470A	
500-238579-45 MS	HEN_49_MS	Total/NA	Water	7470A	
500-238579-45 MSD	HEN_49_MSD	Total/NA	Water	7470A	
500-238579-45 DU	HEN_49	Total/NA	Water	7470A	

Analysis Batch: 730809

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-45	HEN_49	Total/NA	Water	7470A	730601
500-238579-46	HEN_22	Total/NA	Water	7470A	730601
500-238579-47	HEN_50	Total/NA	Water	7470A	730601
MB 500-730368/1-C	Method Blank	Total/NA	Water	7470A	730601
MB 500-730601/12-A	Method Blank	Total/NA	Water	7470A	730601
LCS 500-730601/13-A	Lab Control Sample	Total/NA	Water	7470A	730601
500-238579-45 MS	HEN_49_MS	Total/NA	Water	7470A	730601
500-238579-45 MSD	HEN_49_MSD	Total/NA	Water	7470A	730601
500-238579-45 DU	HEN_49	Total/NA	Water	7470A	730601

Analysis Batch: 731002

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total Recoverable	Water	6020B	729866
500-238579-2	HEN_22&D	Total Recoverable	Water	6020B	729866
500-238579-3	HEN_23	Total Recoverable	Water	6020B	729866
500-238579-4	HEN_23_FD	Total Recoverable	Water	6020B	729866
500-238579-5	HEN_32	Total Recoverable	Water	6020B	729866
500-238579-6	HEN_51	Total Recoverable	Water	6020B	729866
500-238579-26	HEN_27	Total Recoverable	Water	6020B	729866
MB 500-729866/1-A	Method Blank	Total Recoverable	Water	6020B	729866
LCS 500-729866/2-A	Lab Control Sample	Total Recoverable	Water	6020B	729866
500-238579-G-8-G MS	500-238579-G-8-G MS	Total Recoverable	Water	6020B	729866
500-238579-G-8-H MSD	500-238579-G-8-H MSD	Total Recoverable	Water	6020B	729866
500-238579-G-8-F DU	500-238579-G-8-F DU	Total Recoverable	Water	6020B	729866

Analysis Batch: 733174

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total Recoverable	Water	200.7 Rev 4.4	729478
500-238579-2	HEN_22&D	Total Recoverable	Water	200.7 Rev 4.4	729478
500-238579-3	HEN_23	Total Recoverable	Water	200.7 Rev 4.4	729478
500-238579-4	HEN_23_FD	Total Recoverable	Water	200.7 Rev 4.4	729478
500-238579-5	HEN_32	Total Recoverable	Water	200.7 Rev 4.4	729478
500-238579-6	HEN_51	Total Recoverable	Water	200.7 Rev 4.4	729478
MB 500-729478/1-A	Method Blank	Total Recoverable	Water	200.7 Rev 4.4	729478
LCS 500-729478/2-A	Lab Control Sample	Total Recoverable	Water	200.7 Rev 4.4	729478
500-238579-1 MS	HEN_21R	Total Recoverable	Water	200.7 Rev 4.4	729478
500-238579-1 DU	HEN_21R	Total Recoverable	Water	200.7 Rev 4.4	729478

Prep Batch: 733472

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-26	HEN_27	Total Recoverable	Water	200.7	
500-238579-27	HEN_35	Total Recoverable	Water	200.7	
500-238579-44	HEN_34	Total Recoverable	Water	200.7	
500-238579-45	HEN_49	Total Recoverable	Water	200.7	

Eurofins Chicago

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Metals (Continued)

Prep Batch: 733472 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-46	HEN_22	Total Recoverable	Water	200.7	
500-238579-47	HEN_50	Total Recoverable	Water	200.7	
MB 500-733472/1-A	Method Blank	Total Recoverable	Water	200.7	
LCS 500-733472/2-A	Lab Control Sample	Total Recoverable	Water	200.7	
500-238579-45 MS	HEN_49_MS	Total Recoverable	Water	200.7	
500-238579-47 MS	HEN_50	Total Recoverable	Water	200.7	
500-238579-45 DU	HEN_49	Total Recoverable	Water	200.7	
500-238579-47 DU	HEN_50	Total Recoverable	Water	200.7	

Analysis Batch: 734227

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-26	HEN_27	Total Recoverable	Water	200.7 Rev 4.4	733472
500-238579-27	HEN_35	Total Recoverable	Water	200.7 Rev 4.4	733472
500-238579-44	HEN_34	Total Recoverable	Water	200.7 Rev 4.4	733472
500-238579-45	HEN_49	Total Recoverable	Water	200.7 Rev 4.4	733472
500-238579-46	HEN_22	Total Recoverable	Water	200.7 Rev 4.4	733472
500-238579-47	HEN_50	Total Recoverable	Water	200.7 Rev 4.4	733472
MB 500-733472/1-A	Method Blank	Total Recoverable	Water	200.7 Rev 4.4	733472
LCS 500-733472/2-A	Lab Control Sample	Total Recoverable	Water	200.7 Rev 4.4	733472
500-238579-45 MS	HEN_49_MS	Total Recoverable	Water	200.7 Rev 4.4	733472
500-238579-47 MS	HEN_50	Total Recoverable	Water	200.7 Rev 4.4	733472
500-238579-45 DU	HEN_49	Total Recoverable	Water	200.7 Rev 4.4	733472
500-238579-47 DU	HEN_50	Total Recoverable	Water	200.7 Rev 4.4	733472

Analysis Batch: 735077

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-45 MSD	HEN_49_MSD	Total Recoverable	Water	200.7 Rev 4.4	729865

Analysis Batch: 735519

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total Recoverable	Water	6020B	729866
500-238579-2	HEN_22&D	Total Recoverable	Water	6020B	729866
500-238579-3	HEN_23	Total Recoverable	Water	6020B	729866
500-238579-4	HEN_23_FD	Total Recoverable	Water	6020B	729866
500-238579-5	HEN_32	Total Recoverable	Water	6020B	729866
500-238579-6	HEN_51	Total Recoverable	Water	6020B	729866
500-238579-26	HEN_27	Total Recoverable	Water	6020B	729866
500-238579-27	HEN_35	Total Recoverable	Water	6020B	730528
500-238579-44	HEN_34	Total Recoverable	Water	6020B	730528
500-238579-46	HEN_22	Total Recoverable	Water	6020B	730528
500-238579-47	HEN_50	Total Recoverable	Water	6020B	730528
MB 500-729866/1-A	Method Blank	Total Recoverable	Water	6020B	729866
MB 500-730528/1-A	Method Blank	Total Recoverable	Water	6020B	730528
LCS 500-729866/2-A	Lab Control Sample	Total Recoverable	Water	6020B	729866
LCS 500-730528/2-A	Lab Control Sample	Total Recoverable	Water	6020B	730528
500-238579-G-8-G MS	500-238579-G-8-G MS	Total Recoverable	Water	6020B	729866
500-238579-G-8-H MSD	500-238579-G-8-H MSD	Total Recoverable	Water	6020B	729866
500-238579-G-8-F DU	500-238579-G-8-F DU	Total Recoverable	Water	6020B	729866

Eurofins Chicago

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Metals

Analysis Batch: 736032

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-27	HEN_35	Total Recoverable	Water	6020B	730528
500-238579-44	HEN_34	Total Recoverable	Water	6020B	730528
500-238579-45	HEN_49	Total Recoverable	Water	6020B	730528
MB 500-730528/1-A	Method Blank	Total Recoverable	Water	6020B	730528
LCS 500-730528/2-A	Lab Control Sample	Total Recoverable	Water	6020B	730528
500-238579-45 MS	HEN_49_MS	Total Recoverable	Water	6020B	730528
500-238579-45 MSD	HEN_49_MSD	Total Recoverable	Water	6020B	730528
500-238579-45 DU	HEN_49	Total Recoverable	Water	6020B	730528

Prep Batch: 736115

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-45	HEN_49	Total Recoverable	Water	3005A	
MB 500-736115/1-A	Method Blank	Total Recoverable	Water	3005A	
LCS 500-736115/2-A	Lab Control Sample	Total Recoverable	Water	3005A	
500-238579-45 MS	HEN_49_MS	Total Recoverable	Water	3005A	
500-238579-45 MSD	HEN_49_MSD	Total Recoverable	Water	3005A	
500-238579-45 DU	HEN_49	Total Recoverable	Water	3005A	

Analysis Batch: 736227

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-27	HEN_35	Total Recoverable	Water	6020B	730528
500-238579-44	HEN_34	Total Recoverable	Water	6020B	730528
MB 500-730528/1-A	Method Blank	Total Recoverable	Water	6020B	730528
LCS 500-730528/2-A	Lab Control Sample	Total Recoverable	Water	6020B	730528

Analysis Batch: 736355

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-45	HEN_49	Total Recoverable	Water	6020B	736115
500-238579-46	HEN_22	Total Recoverable	Water	6020B	730528
500-238579-47	HEN_50	Total Recoverable	Water	6020B	730528
MB 500-736115/1-A	Method Blank	Total Recoverable	Water	6020B	736115
LCS 500-736115/2-A	Lab Control Sample	Total Recoverable	Water	6020B	736115
500-238579-45 MS	HEN_49_MS	Total Recoverable	Water	6020B	736115
500-238579-45 MSD	HEN_49_MSD	Total Recoverable	Water	6020B	736115
500-238579-45 DU	HEN_49	Total Recoverable	Water	6020B	736115

Analysis Batch: 736513

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-45	HEN_49	Total Recoverable	Water	6020B	736115
MB 500-736115/1-A	Method Blank	Total Recoverable	Water	6020B	736115
LCS 500-736115/2-A	Lab Control Sample	Total Recoverable	Water	6020B	736115
500-238579-45 MS	HEN_49_MS	Total Recoverable	Water	6020B	736115
500-238579-45 MSD	HEN_49_MSD	Total Recoverable	Water	6020B	736115
500-238579-45 DU	HEN_49	Total Recoverable	Water	6020B	736115

General Chemistry

Analysis Batch: 729689

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total/NA	Water	300.0	
500-238579-1	HEN_21R	Total/NA	Water	300.0	

Eurofins Chicago

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

General Chemistry (Continued)

Analysis Batch: 729689 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-2	HEN_22&D	Total/NA	Water	300.0	
500-238579-2	HEN_22&D	Total/NA	Water	300.0	
500-238579-3	HEN_23	Total/NA	Water	300.0	
500-238579-3	HEN_23	Total/NA	Water	300.0	
500-238579-4	HEN_23_FD	Total/NA	Water	300.0	
500-238579-4	HEN_23_FD	Total/NA	Water	300.0	
500-238579-5	HEN_32	Total/NA	Water	300.0	
500-238579-5	HEN_32	Total/NA	Water	300.0	
500-238579-6	HEN_51	Total/NA	Water	300.0	
500-238579-6	HEN_51	Total/NA	Water	300.0	
MB 500-729689/34	Method Blank	Total/NA	Water	300.0	
LCS 500-729689/35	Lab Control Sample	Total/NA	Water	300.0	
500-238579-I-8 MS	500-238579-I-8 MS	Total/NA	Water	300.0	
500-238579-I-8 MS	500-238579-I-8 MS	Total/NA	Water	300.0	
500-238579-J-8 MSD	500-238579-J-8 MSD	Total/NA	Water	300.0	
500-238579-J-8 MSD	500-238579-J-8 MSD	Total/NA	Water	300.0	

Analysis Batch: 729793

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total/NA	Water	SM 2540C	
500-238579-2	HEN_22&D	Total/NA	Water	SM 2540C	
500-238579-3	HEN_23	Total/NA	Water	SM 2540C	
500-238579-4	HEN_23_FD	Total/NA	Water	SM 2540C	
500-238579-5	HEN_32	Total/NA	Water	SM 2540C	
500-238579-6	HEN_51	Total/NA	Water	SM 2540C	
MB 500-729793/1	Method Blank	Total/NA	Water	SM 2540C	
LCS 500-729793/2	Lab Control Sample	Total/NA	Water	SM 2540C	

Analysis Batch: 729794

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-26	HEN_27	Total/NA	Water	SM 2540C	
500-238579-27	HEN_35	Total/NA	Water	SM 2540C	
MB 500-729794/1	Method Blank	Total/NA	Water	SM 2540C	
LCS 500-729794/2	Lab Control Sample	Total/NA	Water	SM 2540C	

Analysis Batch: 729808

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total/NA	Water	SM 2320B	
500-238579-2	HEN_22&D	Total/NA	Water	SM 2320B	
500-238579-3	HEN_23	Total/NA	Water	SM 2320B	
500-238579-4	HEN_23_FD	Total/NA	Water	SM 2320B	
500-238579-5	HEN_32	Total/NA	Water	SM 2320B	
500-238579-6	HEN_51	Total/NA	Water	SM 2320B	
MB 500-729808/3	Method Blank	Total/NA	Water	SM 2320B	
LCS 500-729808/4	Lab Control Sample	Total/NA	Water	SM 2320B	

Analysis Batch: 729898

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-26	HEN_27	Total/NA	Water	300.0	
500-238579-26	HEN_27	Total/NA	Water	300.0	
500-238579-27	HEN_35	Total/NA	Water	300.0	

Eurofins Chicago

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

General Chemistry (Continued)

Analysis Batch: 729898 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-27	HEN_35	Total/NA	Water	300.0	
500-238579-44	HEN_34	Total/NA	Water	300.0	
500-238579-44	HEN_34	Total/NA	Water	300.0	
500-238579-45	HEN_49	Total/NA	Water	300.0	
500-238579-45	HEN_49	Total/NA	Water	300.0	
500-238579-46	HEN_22	Total/NA	Water	300.0	
500-238579-46	HEN_22	Total/NA	Water	300.0	
500-238579-47	HEN_50	Total/NA	Water	300.0	
500-238579-47	HEN_50	Total/NA	Water	300.0	
MB 500-729898/3	Method Blank	Total/NA	Water	300.0	
MB 500-729898/44	Method Blank	Total/NA	Water	300.0	
LCS 500-729898/4	Lab Control Sample	Total/NA	Water	300.0	
LCS 500-729898/45	Lab Control Sample	Total/NA	Water	300.0	
500-238579-45 MS	HEN_49	Total/NA	Water	300.0	
500-238579-45 MS	HEN_49_MS	Total/NA	Water	300.0	
500-238579-45 MSD	HEN_49_MSD	Total/NA	Water	300.0	
500-238579-45 MSD	HEN_49_MSD	Total/NA	Water	300.0	

Analysis Batch: 730144

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 500-730144/3	Method Blank	Total/NA	Water	300.0	
LCS 500-730144/4	Lab Control Sample	Total/NA	Water	300.0	
500-238579-45 MS	HEN_49_MS	Total/NA	Water	300.0	
500-238579-45 MSD	HEN_49_MSD	Total/NA	Water	300.0	

Analysis Batch: 730218

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-44	HEN_34	Total/NA	Water	SM 2540C	
500-238579-45	HEN_49	Total/NA	Water	SM 2540C	
500-238579-46	HEN_22	Total/NA	Water	SM 2540C	
500-238579-47	HEN_50	Total/NA	Water	SM 2540C	
MB 500-730218/1	Method Blank	Total/NA	Water	SM 2540C	
LCS 500-730218/2	Lab Control Sample	Total/NA	Water	SM 2540C	
500-238579-45 MS	HEN_49_MS	Total/NA	Water	SM 2540C	
500-238579-45 MSD	HEN_49_MSD	Total/NA	Water	SM 2540C	
500-238579-44 DU	HEN_34	Total/NA	Water	SM 2540C	

Analysis Batch: 730242

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-26	HEN_27	Total/NA	Water	SM 2320B	
500-238579-27	HEN_35	Total/NA	Water	SM 2320B	
MB 500-730242/3	Method Blank	Total/NA	Water	SM 2320B	
LCS 500-730242/4	Lab Control Sample	Total/NA	Water	SM 2320B	

Analysis Batch: 730652

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-44	HEN_34	Total/NA	Water	SM 2320B	
500-238579-45	HEN_49	Total/NA	Water	SM 2320B	
500-238579-46	HEN_22	Total/NA	Water	SM 2320B	
500-238579-47	HEN_50	Total/NA	Water	SM 2320B	
MB 500-730652/3	Method Blank	Total/NA	Water	SM 2320B	

Eurofins Chicago

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

General Chemistry (Continued)

Analysis Batch: 730652 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
LCS 500-730652/4	Lab Control Sample	Total/NA	Water	SM 2320B	

Analysis Batch: 731549

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 500-731549/3	Method Blank	Total/NA	Water	300.0	
LCS 500-731549/4	Lab Control Sample	Total/NA	Water	300.0	
500-238579-45 MS	HEN_49_MS	Total/NA	Water	300.0	
500-238579-L-45 MSD	500-238579-L-45 MSD	Dissolved	Water	300.0	

Filtration Batch: 731713

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-48	WPCP_FB	Dissolved	Water	FILTRATION	
MB 500-731713/1-A	Method Blank	Dissolved	Water	FILTRATION	
LCS 500-731713/2-A	Lab Control Sample	Dissolved	Water	FILTRATION	

Analysis Batch: 731812

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-48	WPCP_FB	Dissolved	Water	300.0	731713
MB 500-731713/1-A	Method Blank	Dissolved	Water	300.0	731713
LCS 500-731713/2-A	Lab Control Sample	Dissolved	Water	300.0	731713

Field Service / Mobile Lab

Analysis Batch: 731893

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total/NA	Water	Field Sampling	
500-238579-2	HEN_22&D	Total/NA	Water	Field Sampling	
500-238579-3	HEN_23	Total/NA	Water	Field Sampling	
500-238579-4	HEN_23_FD	Total/NA	Water	Field Sampling	
500-238579-5	HEN_32	Total/NA	Water	Field Sampling	
500-238579-6	HEN_51	Total/NA	Water	Field Sampling	
500-238579-7	HEN_25	Total/NA	Water	Field Sampling	
500-238579-8	HEN_26	Total/NA	Water	Field Sampling	
500-238579-26	HEN_27	Total/NA	Water	Field Sampling	
500-238579-27	HEN_35	Total/NA	Water	Field Sampling	
500-238579-44	HEN_34	Total/NA	Water	Field Sampling	
500-238579-45	HEN_49	Total/NA	Water	Field Sampling	
500-238579-46	HEN_22	Total/NA	Water	Field Sampling	
500-238579-47	HEN_50	Total/NA	Water	Field Sampling	
500-238579-61	HEN_30	Total/NA	Water	Field Sampling	
500-238579-62	HEN_31	Total/NA	Water	Field Sampling	
500-238579-63	HEN_33	Total/NA	Water	Field Sampling	
500-238579-64	HEN_36	Total/NA	Water	Field Sampling	

Surrogate Summary

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-11
JEN-250804
SDG: HEN_257_801

Method: 8260D - Volatile Organic Compounds by GC/MS

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Surrogate Recovery (Acceptance Limits)			
		DCA (75-126)	TOL (75-120)	BFB (72-124)	DBFM (75-120)
500-238579-13	HEN_18&D	92	89	99	107
500-238579-14	Trip Blank	93	88	99	106
500-238579-21	HEN_02	89	89	97	105
500-238579-22	Trip Blank	91	88	99	108
500-238579-23	HEN_10	92	90	96	106
500-238579-28	HEN_07	90	90	100	105
500-238579-29	Trip Blank	91	89	97	103
500-238579-30	HEN_08	91	90	100	105
500-238579-31	Trip Blank	91	88	96	106
500-238579-32	HEN_08&D	92	92	100	105
500-238579-34	HEN_08_FD	91	88	98	107
500-238579-34 MS	HEN_08_FD	92	89	91	108
500-238579-34 MSD	HEN_08_FD	92	90	90	109
500-238579-48	WPCP_FB	106	87	95	102
500-238579-49	Trip Blank	103	87	97	98
500-238579-51	HEN_18#S	110	84	99	99
500-238579-52	Trip Blank	103	86	95	98
500-238579-53	HEN_03R	113	85	97	104
500-238579-53 MS	HEN_03R_MS	114	83	96	106
500-238579-53 MSD	HEN_03R_MSD	109	84	95	104
500-238579-54	Trip Blank	105	85	95	100
500-238579-56	HEN_45#S	107	85	97	102
LCS 500-730295/5	Lab Control Sample	94	90	90	107
LCS 500-730655/4	Lab Control Sample	101	86	95	100
MB 500-730295/7	Method Blank	91	90	100	107
MB 500-730655/6	Method Blank	104	85	97	100

Surrogate Legend

DCA = 1,2-Dichloroethane-d4 (Surr)

TOL = Toluene-d8 (Surr)

BFB = 4-Bromofluorobenzene (Surr)

DBFM = Dibromofluoromethane (Surr)

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: 200.7 Rev 4.4 - Metals (ICP)

Lab Sample ID: MRL 500-730525/21
Matrix: Water
Analysis Batch: 730525

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	MRL Result	MRL Qualifier	Unit	D	%Rec	%Rec Limits
Lithium	0.0100	0.0106	^1+	mg/L		106	70 - 130

Lab Sample ID: MB 500-729478/1-A
Matrix: Water
Analysis Batch: 733174

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 729478

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	<0.0050		0.0050	0.0020	mg/L		08/25/23 09:24	09/19/23 14:52	1

Lab Sample ID: LCS 500-729478/2-A
Matrix: Water
Analysis Batch: 733174

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 729478

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Lithium	0.250	0.256		mg/L		103	85 - 115

Lab Sample ID: 500-238579-1 MS
Matrix: Water
Analysis Batch: 733174

Client Sample ID: HEN_21R
Prep Type: Total Recoverable
Prep Batch: 729478

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Lithium	0.026	F1	0.250	0.290		mg/L		106	70 - 130

Lab Sample ID: 500-238579-1 DU
Matrix: Water
Analysis Batch: 733174

Client Sample ID: HEN_21R
Prep Type: Total Recoverable
Prep Batch: 729478

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Lithium	0.026	F1	0.0391	F3	mg/L		40	20

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 735077

Client Sample ID: HEN_49_MSD
Prep Type: Total Recoverable
Prep Batch: 729685

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Lithium	0.023		0.250	0.310		mg/L		115	70 - 130	8	20

Lab Sample ID: MB 500-733472/1-A
Matrix: Water
Analysis Batch: 734227

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 733472

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	<0.0050		0.0050	0.0020	mg/L		09/21/23 19:27	09/26/23 15:55	1

Lab Sample ID: LCS 500-733472/2-A
Matrix: Water
Analysis Batch: 734227

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 733472

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Lithium	0.250	0.262		mg/L		105	85 - 115

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: 200.7 Rev 4.4 - Metals (ICP)

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 734227

Client Sample ID: HEN_49_MS
Prep Type: Total Recoverable
Prep Batch: 733472

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Lithium	0.023		0.250	0.286		mg/L		105	70 - 130

Lab Sample ID: 500-238579-47 MS
Matrix: Water
Analysis Batch: 734227

Client Sample ID: HEN_50
Prep Type: Total Recoverable
Prep Batch: 733472

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Lithium	0.025		0.250	0.286		mg/L		104	70 - 130

Lab Sample ID: 500-238579-45 DU
Matrix: Water
Analysis Batch: 734227

Client Sample ID: HEN_49
Prep Type: Total Recoverable
Prep Batch: 733472

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Lithium	0.023		0.0241		mg/L		4	20

Lab Sample ID: 500-238579-47 DU
Matrix: Water
Analysis Batch: 734227

Client Sample ID: HEN_50
Prep Type: Total Recoverable
Prep Batch: 733472

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Lithium	0.025		0.0252		mg/L		1	20

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 500-729866/1-A
Matrix: Water
Analysis Batch: 731002

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		08/29/23 08:50	09/05/23 14:24	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		08/29/23 08:50	09/05/23 14:24	1
Barium	<0.0025		0.0025	0.00073	mg/L		08/29/23 08:50	09/05/23 14:24	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		08/29/23 08:50	09/05/23 14:24	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		08/29/23 08:50	09/05/23 14:24	1
Calcium	<0.20		0.20	0.044	mg/L		08/29/23 08:50	09/05/23 14:24	1
Chromium	<0.0050		0.0050	0.0011	mg/L		08/29/23 08:50	09/05/23 14:24	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		08/29/23 08:50	09/05/23 14:24	1
Lead	<0.00050		0.00050	0.00019	mg/L		08/29/23 08:50	09/05/23 14:24	1
Magnesium	<0.20		0.20	0.049	mg/L		08/29/23 08:50	09/05/23 14:24	1
Molybdenum	<0.0050		0.0050	0.0025	mg/L		08/29/23 08:50	09/05/23 14:24	1
Potassium	<0.50		0.50	0.11	mg/L		08/29/23 08:50	09/05/23 14:24	1
Selenium	<0.0025		0.0025	0.00098	mg/L		08/29/23 08:50	09/05/23 14:24	1
Thallium	<0.0020		0.0020	0.00057	mg/L		08/29/23 08:50	09/05/23 14:24	1

Eurofins Chicago

QC Sample Results

APPENDIX A.

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: MB 500-729866/1-A
Matrix: Water
Analysis Batch: 735519

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	<0.050		0.050	0.013	mg/L		08/29/23 08:50	10/04/23 22:39	1
Sodium	<0.20		0.20	0.077	mg/L		08/29/23 08:50	10/04/23 22:39	1

Lab Sample ID: LCS 500-729866/2-A
Matrix: Water
Analysis Batch: 731002

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Antimony	0.500	0.522		mg/L		104	80 - 120
Arsenic	0.100	0.0921		mg/L		92	80 - 120
Barium	0.500	0.527		mg/L		105	80 - 120
Beryllium	0.0500	0.0547		mg/L		109	80 - 120
Cadmium	0.0500	0.0515		mg/L		103	80 - 120
Calcium	10.0	10.2		mg/L		102	80 - 120
Chromium	0.200	0.214		mg/L		107	80 - 120
Cobalt	0.500	0.546		mg/L		109	80 - 120
Lead	0.100	0.116		mg/L		116	80 - 120
Magnesium	10.0	10.4		mg/L		104	80 - 120
Molybdenum	1.00	0.986		mg/L		99	80 - 120
Potassium	10.0	9.96		mg/L		100	80 - 120
Selenium	0.100	0.0939		mg/L		94	80 - 120
Thallium	0.100	0.115		mg/L		115	80 - 120

Lab Sample ID: LCS 500-729866/2-A
Matrix: Water
Analysis Batch: 735519

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	0.934		mg/L		93	80 - 120
Sodium	10.0	9.62		mg/L		96	80 - 120

Lab Sample ID: 500-238579-G-8-G MS
Matrix: Water
Analysis Batch: 731002

Client Sample ID: 500-238579-G-8-G MS
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Antimony	<0.0030	F1	0.500	0.534		mg/L		107	75 - 125
Arsenic	0.00047	J F1 F2	0.100	0.0984		mg/L		98	75 - 125
Barium	0.14	F1 F2	0.500	0.663		mg/L		105	75 - 125
Beryllium	<0.0010	F1	0.0500	0.0492		mg/L		98	75 - 125
Cadmium	0.0015	F1 F2	0.0500	0.0526		mg/L		102	75 - 125
Calcium	100		10.0	108	4	mg/L		59	75 - 125
Chromium	<0.0050	F1	0.200	0.196		mg/L		98	75 - 125
Cobalt	0.0019	F1 F2	0.500	0.475		mg/L		95	75 - 125
Lead	0.00049	J F1 F2	0.100	0.111		mg/L		110	75 - 125
Magnesium	35	F1 F2	10.0	43.4		mg/L		84	75 - 125
Molybdenum	<0.0050	F1	1.00	1.04		mg/L		104	75 - 125
Potassium	8.2	F1 F2	10.0	17.1		mg/L		90	75 - 125
Selenium	<0.0025	F1	0.100	0.0986		mg/L		99	75 - 125

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

APPENDIX A.
Job ID: 500-238579-1
SDG: HEN_257_804

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: 500-238579-G-8-G MS
Matrix: Water
Analysis Batch: 731002

Client Sample ID: 500-238579-G-8-G MS
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Thallium	<0.0020	F1	0.100	0.111		mg/L		111	75 - 125

Lab Sample ID: 500-238579-G-8-G MS
Matrix: Water
Analysis Batch: 735519

Client Sample ID: 500-238579-G-8-G MS
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	0.60	F1 F2	1.00	1.40		mg/L		80	75 - 125
Sodium	50		10.0	55.1	4	mg/L		50	75 - 125

Lab Sample ID: 500-238579-G-8-H MSD
Matrix: Water
Analysis Batch: 731002

Client Sample ID: 500-238579-G-8-H MSD
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Antimony	<0.0030	F1	0.500	<0.0030	F1	mg/L		0	75 - 125	NC	20
Arsenic	0.00047	J F1 F2	0.100	0.000410	J F1 F2	mg/L		-0.06	75 - 125	198	20
Barium	0.14	F1 F2	0.500	0.138	F1 F2	mg/L		0.07	75 - 125	131	20
Beryllium	<0.0010	F1	0.0500	<0.0010	F1	mg/L		0	75 - 125	NC	20
Cadmium	0.0015	F1 F2	0.0500	0.00143	F1 F2	mg/L		-0.07	75 - 125	189	20
Calcium	100		10.0	102	4	mg/L		0.9	75 - 125	6	20
Chromium	<0.0050	F1	0.200	<0.0050	F1	mg/L		0	75 - 125	NC	20
Cobalt	0.0019	F1 F2	0.500	0.00194	F1 F2	mg/L		0.01	75 - 125	198	20
Lead	0.00049	J F1 F2	0.100	0.000502	F1 F2	mg/L		0.01	75 - 125	198	20
Magnesium	35	F1 F2	10.0	35.3	F1 F2	mg/L		4	75 - 125	21	20
Molybdenum	<0.0050	F1	1.00	<0.0050	F1	mg/L		0	75 - 125	NC	20
Potassium	8.2	F1 F2	10.0	8.17	F1 F2	mg/L		0.03	75 - 125	71	20
Selenium	<0.0025	F1	0.100	<0.0025	F1	mg/L		0	75 - 125	NC	20
Thallium	<0.0020	F1	0.100	<0.0020	F1	mg/L		0	75 - 125	NC	20

Lab Sample ID: 500-238579-G-8-H MSD
Matrix: Water
Analysis Batch: 735519

Client Sample ID: 500-238579-G-8-H MSD
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	0.60	F1 F2	1.00	0.607	F1 F2	mg/L		1	75 - 125	79	20
Sodium	50		10.0	50.2	4	mg/L		1	75 - 125	9	20

Lab Sample ID: 500-238579-G-8-F DU
Matrix: Water
Analysis Batch: 731002

Client Sample ID: 500-238579-G-8-F DU
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Antimony	<0.0030	F1	<0.0030		mg/L		NC	20
Arsenic	0.00047	J F1 F2	0.000396	J	mg/L		16	20
Barium	0.14	F1 F2	0.139		mg/L		0.8	20
Beryllium	<0.0010	F1	<0.0010		mg/L		NC	20
Cadmium	0.0015	F1 F2	0.00138		mg/L		6	20
Calcium	100		102		mg/L		0.6	20
Chromium	<0.0050	F1	<0.0050		mg/L		NC	20

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: 500-238579-G-8-F DU
Matrix: Water
Analysis Batch: 731002

Client Sample ID: 500-238579-G-8-F DU
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	Limit
Cobalt	0.0019	F1 F2	0.00187		mg/L		0	20
Lead	0.00049	J F1 F2	0.000522		mg/L		6	20
Magnesium	35	F1 F2	35.4		mg/L		2	20
Molybdenum	<0.0050	F1	<0.0050		mg/L		NC	20
Potassium	8.2	F1 F2	8.19		mg/L		0.2	20
Selenium	<0.0025	F1	<0.0025		mg/L		NC	20
Thallium	<0.0020	F1	<0.0020		mg/L		NC	20

Lab Sample ID: 500-238579-G-8-F DU
Matrix: Water
Analysis Batch: 735519

Client Sample ID: 500-238579-G-8-F DU
Prep Type: Total Recoverable
Prep Batch: 729866

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	Limit
Boron	0.60	F1 F2	0.591		mg/L		0.8	20
Sodium	50		49.6		mg/L		1	20

Lab Sample ID: MB 500-730528/1-A
Matrix: Water
Analysis Batch: 735519

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 730528

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		09/01/23 08:58	10/05/23 02:29	1
Arsenic	0.000279	J	0.0010	0.00023	mg/L		09/01/23 08:58	10/05/23 02:29	1
Barium	<0.0025		0.0025	0.00073	mg/L		09/01/23 08:58	10/05/23 02:29	1
Beryllium	<0.0010	^1+	0.0010	0.00053	mg/L		09/01/23 08:58	10/05/23 02:29	1
Boron	<0.050		0.050	0.013	mg/L		09/01/23 08:58	10/05/23 02:29	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		09/01/23 08:58	10/05/23 02:29	1
Calcium	0.0704	J	0.20	0.044	mg/L		09/01/23 08:58	10/05/23 02:29	1
Chromium	<0.0050		0.0050	0.0011	mg/L		09/01/23 08:58	10/05/23 02:29	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		09/01/23 08:58	10/05/23 02:29	1
Lead	<0.00050		0.00050	0.00019	mg/L		09/01/23 08:58	10/05/23 02:29	1
Magnesium	<0.20		0.20	0.049	mg/L		09/01/23 08:58	10/05/23 02:29	1
Molybdenum	<0.0050		0.0050	0.0025	mg/L		09/01/23 08:58	10/05/23 02:29	1
Potassium	<0.50		0.50	0.11	mg/L		09/01/23 08:58	10/05/23 02:29	1
Sodium	0.104	J	0.20	0.077	mg/L		09/01/23 08:58	10/05/23 02:29	1

Lab Sample ID: MB 500-730528/1-A
Matrix: Water
Analysis Batch: 736032

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 730528

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Selenium	<0.0025		0.0025	0.00098	mg/L		09/01/23 08:58	10/06/23 22:41	1

Lab Sample ID: MB 500-730528/1-A
Matrix: Water
Analysis Batch: 736227

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 730528

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Thallium	<0.0020		0.0020	0.00057	mg/L		09/01/23 08:58	10/09/23 12:24	1

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 500-730528/2-A
Matrix: Water
Analysis Batch: 735519

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 730528

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Antimony	0.500	0.507		mg/L		101	80 - 120
Arsenic	0.100	0.0933		mg/L		93	80 - 120
Barium	0.500	0.546		mg/L		109	80 - 120
Beryllium	0.0500	0.0507	^1+	mg/L		101	80 - 120
Boron	1.00	0.920		mg/L		92	80 - 120
Cadmium	0.0500	0.0504		mg/L		101	80 - 120
Calcium	10.0	9.67		mg/L		97	80 - 120
Chromium	0.200	0.207		mg/L		103	80 - 120
Cobalt	0.500	0.519		mg/L		104	80 - 120
Lead	0.100	0.112		mg/L		112	80 - 120
Magnesium	10.0	9.71		mg/L		97	80 - 120
Molybdenum	1.00	0.975		mg/L		97	80 - 120
Potassium	10.0	10.1		mg/L		101	80 - 120
Sodium	10.0	9.79		mg/L		98	80 - 120

Lab Sample ID: LCS 500-730528/2-A
Matrix: Water
Analysis Batch: 736032

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 730528

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Selenium	0.100	0.0967		mg/L		97	80 - 120

Lab Sample ID: LCS 500-730528/2-A
Matrix: Water
Analysis Batch: 736227

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 730528

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Thallium	0.100	0.111		mg/L		111	80 - 120

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 736032

Client Sample ID: HEN_49_MS
Prep Type: Total Recoverable
Prep Batch: 730528

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Antimony	<0.0030		0.500	0.514		mg/L		103	75 - 125
Arsenic	0.00049	J	0.100	0.0994		mg/L		99	75 - 125
Barium	0.062		0.500	0.590		mg/L		106	75 - 125
Beryllium	<0.0010	^1+	0.0500	0.0439	^1+	mg/L		88	75 - 125
Cadmium	0.0013		0.0500	0.0509		mg/L		99	75 - 125
Calcium	99	B	10.0	102	4	mg/L		31	75 - 125
Chromium	<0.0050		0.200	0.176		mg/L		88	75 - 125
Cobalt	0.0033		0.500	0.439		mg/L		87	75 - 125
Lead	0.00036	J	0.100	0.104		mg/L		104	75 - 125
Magnesium	32	F1	10.0	38.8	F1	mg/L		64	75 - 125
Potassium	11		10.0	18.8		mg/L		79	75 - 125
Selenium	<0.0025		0.100	0.0977		mg/L		98	75 - 125
Sodium	56		10.0	59.7	4	mg/L		42	75 - 125

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
Job ID: 500-238579-1
SDG: HEN_257_804

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 736032

Client Sample ID: HEN_49_MSD
Prep Type: Total Recoverable
Prep Batch: 730528

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Antimony	<0.0030		0.500	0.517		mg/L		103	75 - 125	1	20
Arsenic	0.00049	J	0.100	0.0996		mg/L		99	75 - 125	0	20
Barium	0.062		0.500	0.587		mg/L		105	75 - 125	0	20
Beryllium	<0.0010	^1+	0.0500	0.0452	^1+	mg/L		90	75 - 125	3	20
Cadmium	0.0013		0.0500	0.0527		mg/L		103	75 - 125	4	20
Calcium	99	B	10.0	101	4	mg/L		25	75 - 125	1	20
Chromium	<0.0050		0.200	0.181		mg/L		90	75 - 125	3	20
Cobalt	0.0033		0.500	0.445		mg/L		88	75 - 125	1	20
Lead	0.00036	J	0.100	0.104		mg/L		104	75 - 125	0	20
Magnesium	32	F1	10.0	39.0	F1	mg/L		67	75 - 125	1	20
Potassium	11		10.0	19.0		mg/L		81	75 - 125	1	20
Selenium	<0.0025		0.100	0.0982		mg/L		98	75 - 125	0	20
Sodium	56		10.0	60.3	4	mg/L		48	75 - 125	1	20

Lab Sample ID: 500-238579-45 DU
Matrix: Water
Analysis Batch: 736032

Client Sample ID: HEN_49
Prep Type: Total Recoverable
Prep Batch: 730528

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Antimony	<0.0030		<0.0030		mg/L		NC	20
Arsenic	0.00049	J	0.000470	J	mg/L		4	20
Barium	0.062		0.0613		mg/L		2	20
Beryllium	<0.0010	^1+	<0.0010	^1+	mg/L		NC	20
Cadmium	0.0013		0.00138		mg/L		3	20
Calcium	99	B	99.2		mg/L		0.6	20
Chromium	<0.0050		<0.0050		mg/L		NC	20
Cobalt	0.0033		0.00338		mg/L		1	20
Lead	0.00036	J	0.000410	J	mg/L		14	20
Magnesium	32	F1	32.3		mg/L		0.3	20
Potassium	11		10.9		mg/L		0.09	20
Selenium	<0.0025		<0.0025		mg/L		NC	20
Sodium	56		54.4		mg/L		2	20

Lab Sample ID: MB 500-736115/1-A
Matrix: Water
Analysis Batch: 736355

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 736115

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Molybdenum	<0.0050		0.0050	0.0025	mg/L		10/09/23 18:08	10/10/23 12:50	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/09/23 18:08	10/10/23 12:50	1

Lab Sample ID: MB 500-736115/1-A
Matrix: Water
Analysis Batch: 736513

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 736115

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.0255	J	0.050	0.013	mg/L		10/09/23 18:08	10/11/23 10:08	1

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 500-736115/2-A
Matrix: Water
Analysis Batch: 736355

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 736115

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Molybdenum	1.00	0.899		mg/L		90	80 - 120
Thallium	0.100	0.113		mg/L		113	80 - 120

Lab Sample ID: LCS 500-736115/2-A
Matrix: Water
Analysis Batch: 736513

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 736115

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	1.03		mg/L		103	80 - 120

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 736355

Client Sample ID: HEN_49_MS
Prep Type: Total Recoverable
Prep Batch: 736115

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Molybdenum	0.023		1.00	0.938		mg/L		91	75 - 125
Thallium	<0.0020		0.100	0.113		mg/L		113	75 - 125

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 736513

Client Sample ID: HEN_49_MS
Prep Type: Total Recoverable
Prep Batch: 736115

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	0.69	B	1.00	1.57		mg/L		88	75 - 125

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 736355

Client Sample ID: HEN_49_MSD
Prep Type: Total Recoverable
Prep Batch: 736115

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Molybdenum	0.023		1.00	0.909		mg/L		89	75 - 125	3	20
Thallium	<0.0020		0.100	0.111		mg/L		111	75 - 125	1	20

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 736513

Client Sample ID: HEN_49_MSD
Prep Type: Total Recoverable
Prep Batch: 736115

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	0.69	B	1.00	1.60		mg/L		92	75 - 125	2	20

Lab Sample ID: 500-238579-45 DU
Matrix: Water
Analysis Batch: 736355

Client Sample ID: HEN_49
Prep Type: Total Recoverable
Prep Batch: 736115

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Molybdenum	0.023		0.0228		mg/L		0.06	20
Thallium	<0.0020		<0.0020		mg/L		NC	20

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: 500-238579-45 DU
Matrix: Water
Analysis Batch: 736513

Client Sample ID: HEN_49
Prep Type: Total Recoverable
Prep Batch: 736115

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Boron	0.69	B	0.682		mg/L		0.7	20

Method: 7470A - Mercury (CVAA)

Lab Sample ID: MB 500-730135/12-A
Matrix: Water
Analysis Batch: 730327

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 730135

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		08/30/23 11:30	08/31/23 06:53	1

Lab Sample ID: LCS 500-730135/13-A
Matrix: Water
Analysis Batch: 730327

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 730135

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Mercury	0.00201	0.00206		mg/L		103	80 - 120

Lab Sample ID: 500-238579-G-8-K MS
Matrix: Water
Analysis Batch: 730327

Client Sample ID: 500-238579-G-8-K MS
Prep Type: Total/NA
Prep Batch: 730135

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Mercury	<0.00020		0.00100	0.00106		mg/L		106	75 - 125

Lab Sample ID: 500-238579-G-8-L MSD
Matrix: Water
Analysis Batch: 730327

Client Sample ID: 500-238579-G-8-L MSD
Prep Type: Total/NA
Prep Batch: 730135

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Mercury	<0.00020		0.00100	0.00107		mg/L		107	75 - 125	1	20

Lab Sample ID: 500-238579-G-8-J DU
Matrix: Water
Analysis Batch: 730327

Client Sample ID: 500-238579-G-8-J DU
Prep Type: Total/NA
Prep Batch: 730135

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Mercury	<0.00020		<0.00020		mg/L		NC	20

Lab Sample ID: MB 500-730358/12-A
Matrix: Water
Analysis Batch: 730570

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 730358

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		08/31/23 11:45	09/01/23 06:55	1

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

APPENDIX A.
Job ID: 500-238579-1
SDG: HEN_257_804

Method: 7470A - Mercury (CVAA) (Continued)

Lab Sample ID: LCS 500-730358/13-A
Matrix: Water
Analysis Batch: 730570

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 730358

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Mercury	0.00201	0.00201		mg/L		100	80 - 120

Lab Sample ID: MB 500-730368/1-C
Matrix: Water
Analysis Batch: 730809

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 730601

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		09/01/23 12:30	09/05/23 06:57	1

Lab Sample ID: MB 500-730601/12-A
Matrix: Water
Analysis Batch: 730809

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 730601

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000079	mg/L		09/01/23 12:30	09/05/23 06:53	1

Lab Sample ID: LCS 500-730601/13-A
Matrix: Water
Analysis Batch: 730809

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 730601

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Mercury	0.00201	0.00209		mg/L		104	80 - 120

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 730809

Client Sample ID: HEN_49_MS
Prep Type: Total/NA
Prep Batch: 730601

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Mercury	<0.00020		0.00100	0.00106		mg/L		106	75 - 125

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 730809

Client Sample ID: HEN_49_MSD
Prep Type: Total/NA
Prep Batch: 730601

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Mercury	<0.00020		0.00100	0.00109		mg/L		109	75 - 125	3	20

Lab Sample ID: 500-238579-45 DU
Matrix: Water
Analysis Batch: 730809

Client Sample ID: HEN_49
Prep Type: Total/NA
Prep Batch: 730601

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Mercury	<0.00020		<0.00020		mg/L		NC	20

QC Sample Results

APPENDIX A.

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: 300.0 - Anions, Ion Chromatography

Lab Sample ID: MB 500-729689/34

Matrix: Water

Analysis Batch: 729689

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	<1.0		1.0	0.12	mg/L			08/28/23 18:23	1
Fluoride	<1.0		1.0	0.19	mg/L			08/28/23 18:23	1
Sulfate	<1.0		1.0	0.21	mg/L			08/28/23 18:23	1

Lab Sample ID: LCS 500-729689/35

Matrix: Water

Analysis Batch: 729689

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	20.0	19.6		mg/L		98	90 - 110
Fluoride	20.0	20.2		mg/L		101	90 - 110
Sulfate	20.0	20.9		mg/L		104	90 - 110

Lab Sample ID: 500-238579-I-8 MS

Matrix: Water

Analysis Batch: 729689

Client Sample ID: 500-238579-I-8 MS

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Fluoride	0.22	J	10.0	8.87		mg/L		86	80 - 120

Lab Sample ID: 500-238579-I-8 MS

Matrix: Water

Analysis Batch: 729689

Client Sample ID: 500-238579-I-8 MS

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	93		50.0	144		mg/L		103	80 - 120
Sulfate	77		50.0	130		mg/L		105	80 - 120

Lab Sample ID: 500-238579-J-8 MSD

Matrix: Water

Analysis Batch: 729689

Client Sample ID: 500-238579-J-8 MSD

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Fluoride	0.22	J	10.0	8.92		mg/L		87	80 - 120	1	20

Lab Sample ID: 500-238579-J-8 MSD

Matrix: Water

Analysis Batch: 729689

Client Sample ID: 500-238579-J-8 MSD

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Chloride	93		50.0	144		mg/L		102	80 - 120	0	20
Sulfate	77		50.0	130		mg/L		105	80 - 120	0	20

Lab Sample ID: MB 500-729898/3

Matrix: Water

Analysis Batch: 729898

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.120	J	1.0	0.12	mg/L			08/29/23 10:28	1
Fluoride	<1.0		1.0	0.19	mg/L			08/29/23 10:28	1

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: 300.0 - Anions, Ion Chromatography (Continued)

Lab Sample ID: MB 500-729898/3
Matrix: Water
Analysis Batch: 729898

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Sulfate	<1.0		1.0	0.21	mg/L			08/29/23 10:28	1

Lab Sample ID: MB 500-729898/44
Matrix: Water
Analysis Batch: 729898

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	<1.0		1.0	0.12	mg/L			08/29/23 20:50	1
Fluoride	<1.0		1.0	0.19	mg/L			08/29/23 20:50	1
Sulfate	<1.0		1.0	0.21	mg/L			08/29/23 20:50	1

Lab Sample ID: LCS 500-729898/4
Matrix: Water
Analysis Batch: 729898

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	20.0	19.6		mg/L		98	90 - 110
Fluoride	20.0	20.2		mg/L		101	90 - 110
Sulfate	20.0	20.9		mg/L		104	90 - 110

Lab Sample ID: LCS 500-729898/45
Matrix: Water
Analysis Batch: 729898

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	20.0	19.7		mg/L		98	90 - 110
Fluoride	20.0	20.4		mg/L		102	90 - 110
Sulfate	20.0	20.9		mg/L		104	90 - 110

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 729898

Client Sample ID: HEN_49
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Fluoride	0.24	J	10.0	9.02		mg/L		88	80 - 120

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 729898

Client Sample ID: HEN_49_MS
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Sulfate	78		50.0	132		mg/L		108	80 - 120

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 729898

Client Sample ID: HEN_49_MSD
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Fluoride	0.24	J	10.0	8.91		mg/L		87	80 - 120	1	20

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: 300.0 - Anions, Ion Chromatography (Continued)

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 729898

Client Sample ID: HEN_49_MSD
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Sulfate	78		50.0	131		mg/L		106	80 - 120	1	20

Lab Sample ID: MB 500-730144/3
Matrix: Water
Analysis Batch: 730144

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	<1.0		1.0	0.12	mg/L			08/30/23 13:15	1

Lab Sample ID: LCS 500-730144/4
Matrix: Water
Analysis Batch: 730144

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	20.0	19.5		mg/L		97	90 - 110

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 730144

Client Sample ID: HEN_49_MS
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	95	F1	50.0	149		mg/L		108	80 - 120

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 730144

Client Sample ID: HEN_49_MSD
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Chloride	95	F1	50.0	149		mg/L		106	80 - 120	0	20

Lab Sample ID: MB 500-731549/3
Matrix: Water
Analysis Batch: 731549

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.158	J	1.0	0.12	mg/L			09/10/23 13:21	1
Fluoride	<1.0		1.0	0.19	mg/L			09/10/23 13:21	1
Sulfate	<1.0		1.0	0.21	mg/L			09/10/23 13:21	1

Lab Sample ID: LCS 500-731549/4
Matrix: Water
Analysis Batch: 731549

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	20.0	18.8		mg/L		94	90 - 110
Fluoride	20.0	18.8		mg/L		94	90 - 110
Sulfate	20.0	20.2		mg/L		101	90 - 110

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

APPENDIX A.
Job ID: 500-238579-1
SDG: HEN_257_804

Method: 300.0 - Anions, Ion Chromatography (Continued)

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 731549

Client Sample ID: HEN_49_MS
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Fluoride	0.24	J	10.0	8.59		mg/L		84	80 - 120

Lab Sample ID: 500-238579-L-45 MSD
Matrix: Water
Analysis Batch: 731549

Client Sample ID: 500-238579-L-45 MSD
Prep Type: Dissolved

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Fluoride	0.26	J	10.0	8.45		mg/L		82	80 - 120	1	20

Lab Sample ID: MB 500-731713/1-A
Matrix: Water
Analysis Batch: 731812

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride, Dissolved	<1.0		1.0	0.12	mg/L			09/11/23 15:17	1
Fluoride, Dissolved	<1.0		1.0	0.19	mg/L			09/11/23 15:17	1
Sulfate, Dissolved	<1.0		1.0	0.21	mg/L			09/11/23 15:17	1

Lab Sample ID: LCS 500-731713/2-A
Matrix: Water
Analysis Batch: 731812

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride, Dissolved	20.0	18.7		mg/L		93	90 - 110
Fluoride, Dissolved	20.0	18.7		mg/L		94	90 - 110
Sulfate, Dissolved	20.0	20.2		mg/L		101	90 - 110

Method: SM 2320B - Alkalinity

Lab Sample ID: MB 500-729808/3
Matrix: Water
Analysis Batch: 729808

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bicarbonate Alkalinity as CaCO3	<5.0		5.0	3.7	mg/L			08/28/23 15:43	1
Carbonate Alkalinity as CaCO3	<5.0		5.0	3.7	mg/L			08/28/23 15:43	1

Lab Sample ID: LCS 500-729808/4
Matrix: Water
Analysis Batch: 729808

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Alkalinity	100	92.6		mg/L		93	90 - 110

Lab Sample ID: MB 500-730242/3
Matrix: Water
Analysis Batch: 730242

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bicarbonate Alkalinity as CaCO3	<5.0		5.0	3.7	mg/L			08/30/23 15:42	1

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

APPENDIX A.
Job ID: 590-238579-1
SDG: HEN_257_804

Method: SM 2320B - Alkalinity (Continued)

Lab Sample ID: MB 500-730242/3
Matrix: Water
Analysis Batch: 730242

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Carbonate Alkalinity as CaCO ₃	<5.0		5.0	3.7	mg/L			08/30/23 15:42	1

Lab Sample ID: LCS 500-730242/4
Matrix: Water
Analysis Batch: 730242

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Alkalinity	100	90.2		mg/L		90	90 - 110

Lab Sample ID: MB 500-730652/3
Matrix: Water
Analysis Batch: 730652

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bicarbonate Alkalinity as CaCO ₃	<5.0		5.0	3.7	mg/L			08/31/23 16:08	1
Carbonate Alkalinity as CaCO ₃	<5.0		5.0	3.7	mg/L			08/31/23 16:08	1

Lab Sample ID: LCS 500-730652/4
Matrix: Water
Analysis Batch: 730652

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Alkalinity	100	90.8		mg/L		91	90 - 110

Method: SM 2540C - Solids, Total Dissolved (TDS)

Lab Sample ID: MB 500-729793/1
Matrix: Water
Analysis Batch: 729793

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Dissolved Solids	<10		10	4.3	mg/L			08/28/23 18:23	1

Lab Sample ID: LCS 500-729793/2
Matrix: Water
Analysis Batch: 729793

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Total Dissolved Solids	250	248		mg/L		99	80 - 120

Lab Sample ID: MB 500-729794/1
Matrix: Water
Analysis Batch: 729794

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Dissolved Solids	<10		10	4.3	mg/L			08/28/23 20:37	1

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-1
SDG: HEN_257_804

Method: SM 2540C - Solids, Total Dissolved (TDS) (Continued)

Lab Sample ID: LCS 500-729794/2
Matrix: Water
Analysis Batch: 729794

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Total Dissolved Solids	250	232		mg/L		93	80 - 120

Lab Sample ID: MB 500-730218/1
Matrix: Water
Analysis Batch: 730218

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Dissolved Solids	<10		10	4.3	mg/L			08/30/23 19:32	1

Lab Sample ID: LCS 500-730218/2
Matrix: Water
Analysis Batch: 730218

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Total Dissolved Solids	250	242		mg/L		97	80 - 120

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 730218

Client Sample ID: HEN_49_MS
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Total Dissolved Solids	620		250	914		mg/L		118	75 - 125

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 730218

Client Sample ID: HEN_49_MSD
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Total Dissolved Solids	620		250	922		mg/L		122	75 - 125	1	20

Lab Sample ID: 500-238579-44 DU
Matrix: Water
Analysis Batch: 730218

Client Sample ID: HEN_34
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Total Dissolved Solids	760		756		mg/L		0.3	5

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_21R

Date Collected: 08/22/23 13:45

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-1

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			729478	BDE	EET CHI	08/25/23 09:24 - 08/25/23 09:54 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		2	733174	RB	EET CHI	09/19/23 15:00
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	731002	EH	EET CHI	09/05/23 14:31
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/04/23 22:46
Total/NA	Prep	7470A			730135	MJG	EET CHI	08/30/23 11:30 - 08/30/23 13:30 ¹
Total/NA	Analysis	7470A		1	730327	MJG	EET CHI	08/31/23 06:58
Total/NA	Analysis	300.0		1	729689	W1T	EET CHI	08/28/23 20:40
Total/NA	Analysis	300.0		5	729689	W1T	EET CHI	08/28/23 20:55
Total/NA	Analysis	SM 2320B		1	729808	EH	EET CHI	08/28/23 16:42
Total/NA	Analysis	SM 2540C		1	729793	CLB	EET CHI	08/28/23 18:38
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 13:45

Client Sample ID: HEN_22&D

Date Collected: 08/22/23 09:10

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-2

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			729478	BDE	EET CHI	08/25/23 09:24 - 08/25/23 09:54 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	733174	RB	EET CHI	09/19/23 15:12
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	731002	EH	EET CHI	09/05/23 14:35
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/04/23 22:50
Total/NA	Prep	7470A			730135	MJG	EET CHI	08/30/23 11:30 - 08/30/23 13:30 ¹
Total/NA	Analysis	7470A		1	730327	MJG	EET CHI	08/31/23 07:00
Total/NA	Analysis	300.0		1	729689	W1T	EET CHI	08/28/23 21:10
Total/NA	Analysis	300.0		5	729689	W1T	EET CHI	08/28/23 21:25
Total/NA	Analysis	SM 2320B		1	729808	EH	EET CHI	08/28/23 16:52
Total/NA	Analysis	SM 2540C		1	729793	CLB	EET CHI	08/28/23 18:41
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 09:10

Client Sample ID: HEN_23

Date Collected: 08/22/23 11:20

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-3

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			729478	BDE	EET CHI	08/25/23 09:24 - 08/25/23 09:54 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	733174	RB	EET CHI	09/19/23 15:16
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	731002	EH	EET CHI	09/05/23 14:38
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/04/23 22:54

Eurofins Chicago

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_23

Date Collected: 08/22/23 11:20

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-3

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	7470A			730135	MJG	EET CHI	08/30/23 11:30 - 08/30/23 13:30 ¹
Total/NA	Analysis	7470A		1	730327	MJG	EET CHI	08/31/23 07:02
Total/NA	Analysis	300.0		1	729689	W1T	EET CHI	08/28/23 21:41
Total/NA	Analysis	300.0		50	729689	W1T	EET CHI	08/28/23 21:56
Total/NA	Analysis	SM 2320B		1	729808	EH	EET CHI	08/28/23 17:04
Total/NA	Analysis	SM 2540C		1	729793	CLB	EET CHI	08/28/23 18:43
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 11:20

Client Sample ID: HEN_23_FD

Date Collected: 08/22/23 11:20

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-4

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			729478	BDE	EET CHI	08/25/23 09:24 - 08/25/23 09:54 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	733174	RB	EET CHI	09/19/23 15:21
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	731002	EH	EET CHI	09/05/23 14:42
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/04/23 22:58
Total/NA	Prep	7470A			730135	MJG	EET CHI	08/30/23 11:30 - 08/30/23 13:30 ¹
Total/NA	Analysis	7470A		1	730327	MJG	EET CHI	08/31/23 07:04
Total/NA	Analysis	300.0		1	729689	W1T	EET CHI	08/28/23 22:41
Total/NA	Analysis	300.0		50	729689	W1T	EET CHI	08/28/23 22:56
Total/NA	Analysis	SM 2320B		1	729808	EH	EET CHI	08/28/23 17:13
Total/NA	Analysis	SM 2540C		1	729793	CLB	EET CHI	08/28/23 18:46
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 11:20

Client Sample ID: HEN_32

Date Collected: 08/22/23 11:15

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-5

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			729478	BDE	EET CHI	08/25/23 09:24 - 08/25/23 09:54 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	733174	RB	EET CHI	09/19/23 15:25
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	731002	EH	EET CHI	09/05/23 14:45
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/04/23 23:01
Total/NA	Prep	7470A			730135	MJG	EET CHI	08/30/23 11:30 - 08/30/23 13:30 ¹
Total/NA	Analysis	7470A		1	730327	MJG	EET CHI	08/31/23 07:06
Total/NA	Analysis	300.0		1	729689	W1T	EET CHI	08/28/23 23:12
Total/NA	Analysis	300.0		2	729689	W1T	EET CHI	08/28/23 23:27
Total/NA	Analysis	SM 2320B		1	729808	EH	EET CHI	08/28/23 17:22

Eurofins Chicago

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_32

Date Collected: 08/22/23 11:15

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-5

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	SM 2540C		1	729793	CLB	EET CHI	08/28/23 18:48
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 11:15

Client Sample ID: HEN_51

Date Collected: 08/22/23 15:56

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-6

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			729478	BDE	EET CHI	08/25/23 09:24 - 08/25/23 09:54 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	733174	RB	EET CHI	09/19/23 15:29
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	731002	EH	EET CHI	09/05/23 14:49
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/04/23 23:05
Total/NA	Prep	7470A			730135	MJG	EET CHI	08/30/23 11:30 - 08/30/23 13:30 ¹
Total/NA	Analysis	7470A		1	730327	MJG	EET CHI	08/31/23 07:08
Total/NA	Analysis	300.0		1	729689	W1T	EET CHI	08/28/23 23:42
Total/NA	Analysis	300.0		5	729689	W1T	EET CHI	08/28/23 23:57
Total/NA	Analysis	SM 2320B		1	729808	EH	EET CHI	08/28/23 17:31
Total/NA	Analysis	SM 2540C		1	729793	CLB	EET CHI	08/28/23 18:51
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 15:56

Client Sample ID: HEN_25

Date Collected: 08/22/23 14:30

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-7

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 14:30

Client Sample ID: HEN_26

Date Collected: 08/22/23 15:35

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-8

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 15:35

Client Sample ID: HEN_27

Date Collected: 08/24/23 09:00

Date Received: 08/25/23 09:32

Lab Sample ID: 500-238579-26

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			733472	MC	EET CHI	09/21/23 19:27 - 09/22/23 00:27 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	734227	RN	EET CHI	09/26/23 16:16
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	731002	EH	EET CHI	09/05/23 16:04

Eurofins Chicago

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_27

Date Collected: 08/24/23 09:00

Date Received: 08/25/23 09:32

Lab Sample ID: 500-238579-26

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	3005A			729866	BDE	EET CHI	08/29/23 08:50 - 08/29/23 09:20 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/05/23 00:28
Total/NA	Prep	7470A			730135	MJG	EET CHI	08/30/23 11:30 - 08/30/23 13:30 ¹
Total/NA	Analysis	7470A		1	730327	MJG	EET CHI	08/31/23 07:44
Total/NA	Analysis	300.0		1	729898	W1T	EET CHI	08/29/23 19:49
Total/NA	Analysis	300.0		10	729898	W1T	EET CHI	08/29/23 20:04
Total/NA	Analysis	SM 2320B		1	730242	EH	EET CHI	08/30/23 16:17
Total/NA	Analysis	SM 2540C		1	729794	CLB	EET CHI	08/28/23 21:33
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/24/23 09:00

Client Sample ID: HEN_35

Date Collected: 08/24/23 10:10

Date Received: 08/25/23 09:32

Lab Sample ID: 500-238579-27

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			733472	MC	EET CHI	09/21/23 19:27 - 09/22/23 00:27 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	734227	RN	EET CHI	09/26/23 16:20
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/05/23 02:37
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	736032	BJH	EET CHI	10/06/23 22:48
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	736227	JP	EET CHI	10/09/23 12:31
Total/NA	Prep	7470A			730135	MJG	EET CHI	08/30/23 11:30 - 08/30/23 13:30 ¹
Total/NA	Analysis	7470A		1	730327	MJG	EET CHI	08/31/23 07:47
Total/NA	Analysis	300.0		1	729898	W1T	EET CHI	08/29/23 20:19
Total/NA	Analysis	300.0		100	729898	W1T	EET CHI	08/29/23 20:35
Total/NA	Analysis	SM 2320B		1	730242	EH	EET CHI	08/30/23 16:27
Total/NA	Analysis	SM 2540C		1	729794	CLB	EET CHI	08/28/23 21:36
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/24/23 10:10

Client Sample ID: HEN_34

Date Collected: 08/25/23 11:25

Date Received: 08/25/23 15:00

Lab Sample ID: 500-238579-44

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			733472	MC	EET CHI	09/21/23 19:27 - 09/22/23 00:27 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	734227	RN	EET CHI	09/26/23 17:19
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/05/23 03:30
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	736032	BJH	EET CHI	10/06/23 23:36
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	736227	JP	EET CHI	10/09/23 13:19

Eurofins Chicago

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_34

Date Collected: 08/25/23 11:25

Date Received: 08/25/23 15:00

Lab Sample ID: 500-238579-44

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	7470A			730358	MJG	EET CHI	08/31/23 11:45 - 08/31/23 13:45 ¹
Total/NA	Analysis	7470A		1	730570	MJG	EET CHI	09/01/23 07:52
Total/NA	Analysis	300.0		1	729898	W1T	EET CHI	08/30/23 03:24
Total/NA	Analysis	300.0		5	729898	W1T	EET CHI	08/30/23 03:39
Total/NA	Analysis	SM 2320B		1	730652	EH	EET CHI	08/31/23 17:19
Total/NA	Analysis	SM 2540C		1	730218	CLB	EET CHI	08/30/23 19:57
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/25/23 11:25

Client Sample ID: HEN_49

Date Collected: 08/25/23 10:05

Date Received: 08/25/23 15:00

Lab Sample ID: 500-238579-45

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			733472	MC	EET CHI	09/21/23 19:27 - 09/22/23 00:27 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	734227	RN	EET CHI	09/26/23 17:24
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	736032	BJH	EET CHI	10/06/23 23:40
Total Recoverable	Prep	3005A			736115	MC	EET CHI	10/09/23 18:08 - 10/09/23 23:08 ¹
Total Recoverable	Analysis	6020B		1	736355	BJH	EET CHI	10/10/23 12:58
Total Recoverable	Prep	3005A			736115	MC	EET CHI	10/09/23 18:08 - 10/09/23 23:08 ¹
Total Recoverable	Analysis	6020B		1	736513	BJH	EET CHI	10/11/23 10:15
Total/NA	Prep	7470A			730601	MJG	EET CHI	09/01/23 12:30 - 09/01/23 14:30 ¹
Total/NA	Analysis	7470A		1	730809	MJG	EET CHI	09/05/23 07:16
Total/NA	Analysis	300.0		1	729898	W1T	EET CHI	08/30/23 03:54
Total/NA	Analysis	300.0		5	729898	W1T	EET CHI	08/30/23 05:10
Total/NA	Analysis	SM 2320B		1	730652	EH	EET CHI	08/31/23 17:29
Total/NA	Analysis	SM 2540C		1	730218	CLB	EET CHI	08/30/23 20:03
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/25/23 10:05

Client Sample ID: HEN_22

Date Collected: 08/25/23 08:50

Date Received: 08/25/23 15:00

Lab Sample ID: 500-238579-46

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			733472	MC	EET CHI	09/21/23 19:27 - 09/22/23 00:27 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	734227	RN	EET CHI	09/26/23 17:40
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/05/23 03:45
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	736355	BJH	EET CHI	10/10/23 12:14
Total/NA	Prep	7470A			730601	MJG	EET CHI	09/01/23 12:30 - 09/01/23 14:30 ¹
Total/NA	Analysis	7470A		1	730809	MJG	EET CHI	09/05/23 07:24
Total/NA	Analysis	300.0		1	729898	W1T	EET CHI	08/30/23 05:56
Total/NA	Analysis	300.0		10	729898	W1T	EET CHI	08/30/23 06:11

Eurofins Chicago

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_22

Date Collected: 08/25/23 08:50

Date Received: 08/25/23 15:00

Lab Sample ID: 500-238579-46

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	SM 2320B		1	730652	EH	EET CHI	08/31/23 17:39
Total/NA	Analysis	SM 2540C		1	730218	CLB	EET CHI	08/30/23 20:10
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/25/23 08:50

Client Sample ID: HEN_50

Date Collected: 08/25/23 11:25

Date Received: 08/25/23 15:00

Lab Sample ID: 500-238579-47

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			733472	MC	EET CHI	09/21/23 19:27 - 09/22/23 00:27 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	734227	RN	EET CHI	09/26/23 17:53
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	735519	BJH	EET CHI	10/05/23 03:49
Total Recoverable	Prep	3005A			730528	BDE	EET CHI	09/01/23 08:58 - 09/01/23 09:28 ¹
Total Recoverable	Analysis	6020B		1	736355	BJH	EET CHI	10/10/23 12:19
Total/NA	Prep	7470A			730601	MJG	EET CHI	09/01/23 12:30 - 09/01/23 14:30 ¹
Total/NA	Analysis	7470A		1	730809	MJG	EET CHI	09/05/23 07:27
Total/NA	Analysis	300.0		1	729898	W1T	EET CHI	08/30/23 06:26
Total/NA	Analysis	300.0		5	729898	W1T	EET CHI	08/30/23 06:41
Total/NA	Analysis	SM 2320B		1	730652	EH	EET CHI	08/31/23 17:48
Total/NA	Analysis	SM 2540C		1	730218	CLB	EET CHI	08/30/23 20:13
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/25/23 11:25

Client Sample ID: WPCP_FB

Date Collected: 08/28/23 07:30

Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-48

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Filtration	FILTRATION			731713	EH	EET CHI	09/11/23 14:01
Dissolved	Analysis	300.0		1	731812	EH	EET CHI	09/11/23 15:48

Client Sample ID: HEN_30

Date Collected: 08/22/23 10:00

Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-61

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 10:00

Client Sample ID: HEN_31

Date Collected: 08/22/23 09:55

Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-62

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 09:55

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-1
SDG: HEN_257_804

Client Sample ID: HEN_33

Date Collected: 08/22/23 10:18

Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-63

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 10:18

Client Sample ID: HEN_36

Date Collected: 08/22/23 09:30

Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-64

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	Field Sampling		1	731893	DN	EET CHI	08/22/23 09:30

¹ This procedure uses a method stipulated length of time for the process. Both start and end times are displayed.

Laboratory References:

EET CHI = Eurofins Chicago, 2417 Bond Street, University Park, IL 60484, TEL (708)534-5200

Accreditation/Certification Summary

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 590-238579-1
SDG: HEN_257_804

Laboratory: Eurofins Chicago

Unless otherwise noted, all analytes for this laboratory were covered under each accreditation/certification below.

Authority	Program	Identification Number	Expiration Date
Illinois	NELAP	IL00035	04-29-24

The following analytes are included in this report, but the laboratory is not certified by the governing authority. This list may include analytes for which the agency does not offer certification.

Analysis Method	Prep Method	Matrix	Analyte
200.7 Rev 4.4	200.7	Water	Lithium
Field Sampling		Water	Depth to Water (ft from MP)
Field Sampling		Water	Field pH
Field Sampling		Water	Field Temperature
Field Sampling		Water	Oxidation Reduction Potential
Field Sampling		Water	Oxygen, Dissolved
Field Sampling		Water	Specific Conductance
Field Sampling		Water	Turbidity
SM 2320B		Water	Bicarbonate Alkalinity as CaCO ₃
SM 2320B		Water	Carbonate Alkalinity as CaCO ₃

500-23A525

Page: 1 of 1

 $1.5 \rightarrow 1.2$

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

3

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page: 1 of 1

4

PLER: Allison Beckwith
PLER: Beckwith

500-238579

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:		Page: 1 of 1	
Company: Vistra Corp/A3		Report To: Brian Voelker		Attention: Jason Stuckey		REGULATORY AGENCY NPDES GROUND WATER DRINKING WATER UST RCRA OTHER	
Address:		Copy To: Jason Stuckey		Company Name: Vistra Corp			
Email To: Brian.Voelker@VistraCorp.com		Purchase Order No.:		Address: see Section A			
Phone: (217) 753-8911 Fax:		Project Name:		Project Manager:		Site Location	
Requested Due Date/TAT: 10 day		Project Number: 2285		Profile #:		STATE: IL	

ITEM #	Section D Required Client Information	Valid Matrix Codes MATRIXCODE DRINKING WATER DW WATER WT WASTE WATER WW PRODUCT P SOIL/SOLID SL OIL OL WIPE WP AIR AR OTHER OT TISSUE TS	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives										Analysis Test Y/N	Requested Analysis Filtered (Y/N)										Residual Chlorine (Y/N)	Project No./ Lab I.D.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
					DATE	TIME			Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other	HEN_257_801	HEN_257_802		HEN_257_803	HEN_257_804	HEN_811_801	HEN_845_802-805	HEN_845_803	HEN_845_804	HEN_CLOSURE_802-805	HEN_CLOSURE_804	HEN_SUP_000	HEN_WPCP_East			HEN_WPCP_West																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
1	HEN_32				8/22/23	1115																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS
HEN-23Q3 Rev 0	<i>[Signature]</i>	8/22/23	1700	Stephanie Hemondley EEA	8/23/23	1000	1-1-108 Y Y Y

SAMPLER NAME AND SIGNATURE				Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER: CHRIS TREMBLAY							
SIGNATURE of SAMPLER: <i>[Signature]</i> DATE Signed (MM/DD/YY): 8/22/23							

500-2385128
8/23/23

Page: 1 of 1

Requested Analysis Filtered (Y/N)	
-----------------------------------	--

6

11/16/23 (Rev. 3)

HEN-257-804

79

500-238576

85

8/23/23

Page: 1 of

Page: 1 of 8/23/23

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:		Page: 1 of 3		
Company: Vistra Corp/A3		Report To: Brian Voelker		Attention: Jason Stuckey		REGULATORY AGENCY		
Address: 3030 Warrenville, Ste 418		Copy To: Jason Stuckey		Company Name: Vistra Corp				
Lisle, IL 60532				Address: see Section A				
Email To: Brian.Voelker@VistraCorp.com		Purchase Order No.:		Quote Reference:		NPDES	GROUND WATER	DRINKING WATER
Phone: (217) 753-8911		Project Name:		Project Manager:		UST	RCRA	OTHER
Fax:		Project Number: 50021987		Profile #:		Site Location	IL	
Requested Due Date/TAT: 10 day						STATE:		

ITEM #	Section D Required Client Information	Valid Matrix Codes <u>MATRIX</u> <u>CODE</u>	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives								$\downarrow$ Analysis Test $\downarrow$	Y/N $\downarrow$	Requested Analysis Filtered (Y/N)										Project No./ Lab I.D.
					DATE	TIME			Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other			HEN_257_801	HEN_257_802	HEN_257_803	HEN_257_804	HEN_811_801	HEN_845_802-805	HEN_845_803	HEN_845_804	HEN_CLOSURE_802-805	HEN_CLOSURE_804	
1	HEN_25				8/22/23	1430										X								X	X				
2																													
3																													
4																													
5																													
6																													
7																													
8																													
9																													
10																													
11																													
12																													
13																													
14																													
15																													
16																													

ADDITIONAL COMMENTS
HEN-23Q3 Rev 0

RELINQUISHED BY / AFFILIATION
Closter

DATE
8/23/23

TIME
1700

ACCEPTED BY / AFFILIATION
Alex Scott

DATE
8/23/23

TIME
1000

SAMPLE CONDITIONS

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER: <i>Chris Thompson</i>					
SIGNATURE of SAMPLER: <i>[Signature]</i>	DATE Signed (MM/DD/YY): <i>8/22/23</i>				

 $0.6 \rightarrow 0.3, 1.0 \rightarrow 0.7$

500-2385-8

Page: 1 of 1

8

13
14
15

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER: JAMES TREMBLE					
SIGNATURE of SAMPLER: [Signature] DATE Signed (MM/DD/YY): 8/22/23					

$$0.6 \rightarrow 0.3, 1.0 \rightarrow 0.7$$

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page 1 of 1

05+02

500-238579

Page 1 of 1

Section A Required Client Information		Section B Required Project Information		Section C Invoice Information		Page 1 of 1	
Company Vistra Corp/A3		Report To Brian Voelker		Attention Jason Stuckey		REGULATORY AGENCY	
Address		Copy To Jason Stuckey		Company Name Vistra Corp			
				Address see Section A			
Email To Brian.Voelke@VistraCorp.com		Purchase Order No		Quote Reference		NPDES GROUND WATER DRINKING WATER	
Phone (217) 753-8911 Fax:		Project Name		Project Manager		UST RCRA OTHER	
Requested Due Date/TAT 10 day		Project Number: 2285		Profile #:		Site Location STATE IL	

 $0.5 + 0.2$

500-238579

Page 1 of 1

Section A Required Client Information		Section B Required Project Information		Section C Invoice Information		Page 1 of 1		
Company: Vistra Corp/A3		Report To: Brian Voelker		Attention: Jason Stuckey		REGULATORY AGENCY		
Address:		Copy To: Jason Stuckey		Company Name: Vistra Corp				
				Address: see Section A		NPDES GROUND WATER DRINKING WATER		
Email To: Brian.Voelker@VistraCorp.com		Purchase Order No.		Quote Reference		UST RCRA OTHER		
Phone: (217) 753-8911 Fax:		Project Name:		Project Manager:		Site Location STATE IL		
Requested Due Date/TAT: 10 day		Project Number: 2285		Profile #:				

[illegible]

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER					
SIGNATURE of SAMPLER	DATE Signed (MM/DD/YY)				
 Chris DeBury					
 Chris DeBury	8/28/23				

500-238579

Page 1 of 1

45

13

14

15

SAMPLER NAME AND SIGNATURE		Temp in C	Received on Ice (Y/N)	Custody Sealed Coder (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER	SIGNATURE of SAMPLER				
ALLISON BECKETT	DATE Signed (MM/DD/YY): 9/15/23				

0.8 → 0.5, 2.3 → 2.0

500-238579

Page 1 of 1

45

The Chain-of-Custody is a LEGAL DOCUMENT All relevant fields must be completed accurately

Section A Required Client Information			Section B Required Project Information		Section C Invoice Information		Page 1 of 1		
Company: Vistra Corp			Report To: Brian Voelker		Attention: Jason Stuckey		REGULATORY AGENCY		
Address: 13498 E 900th St			Copy To: Jason Stuckey		Company Name: Vistra Corp				
					Address: see Section A		NPDES	GROUND WATER	DRINKING WATER
Email To: Brian.Voelker@VistraCorp.com			Purchase Order No		Quote Reference:		UST	RCRA	OTHER
Phone: (217) 753-8911	Fax:		Project Name		Project Manager:		Site Location	IL	
Requested Due Date/TAT 10 day			Project Number 2285		Profile #:				
							STATE:		

[illegible]

500-238579

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page 1 of 1

7

21417

Chain of Custody Record

Client Information		Lab PM		Carrier Tracking No's		COG No	
Client Contact Brian Voelker		Phone		E-Mail Carlene McCutcheon@eurofinsus.com		State of Origin	
Company Vistra Energy Corp		F V D		Analysis Requested		Page 1 of 1	
Address Zimmer Generating Station 1781 US Rte 52		Due Date Requested		Job #		500-115777-47579 1	
City Moscow		TAT Requested (days)		Preservation Codes		A HCL M Hexane B NaOH N None C Zn Acetate P AsNaO ₂ D H ₂ SO ₄ Q Na ₂ CO ₃ F NaHSO ₄ R Na ₂ SO ₄ G MeOH S H ₂ SO ₄ H Ascorbic Acid T SP Dodecylglycolate I Ce U Acetone J DI Water V MCAA K EDTA W pH 4-5 L EDTA Y Inzma Z Other (specify)	
Phone 217-412-6605(Tel)		PO # 2382094		Other			
Email brian.voelker@vistraenergy.com		WQ #					
Project Name HEN_50		Project # 50021987					
Site		SSO No.					
Sample Identification		Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, AA=Air)	Special Instructions/Note	
HEN_50		8/25/23	1125		Water		
Possible Hazard Identification		Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)					
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological		☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months					
Deliverable Requested I II IV Other (specify)		Special Instructions, QC Requirements					
Empty Kit Returned by		Date	Time	Method of Shipment			
Received by		Date/Time	Signature	Date/Time		Signature	
Received by		Date/Time	Signature	Date/Time		Signature	
Received by		Date/Time	Signature	Date/Time		Signature	
Custody Seals Intact Yes ☐ No ☐		Custody Seal No		Custody Seal No			

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Login Sample Receipt Checklist

Client: Vistra Energy Corp

Job Number: 500-238579-1

SDG Number: HEN_257_804

Login Number: 238579

List Number: 1

Creator: Scott, Sherri L

List Source: Eurofins Chicago

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	0.6,0.7,0.3,1.2,0.8,0.4,0.1,2.9,1.7,3.7,1.0,2.8,0.2,2.0,2.9,0.1,1.63,0.1,3,0.5,2
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	False	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	False	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	False	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

SAR-3: Episodic Depth to Groundwater Measurements
All DTWs on SAR-3 must be collected within 24 hours.
Plant: HEN
Event: HEN-23Q3 Rev 0

Well	Unique ID	Date	Time	Measured Depth to Water (ft bmp)	Comments	Initials
02	HEN_02	8/21/23	1200	41.84		CT
04R	HEN_04R	8/21/23	1035	37.08		CT
05R	HEN_05IR	8/21/23	1105	38.69		CT
05DR	HEN_05&DR	8/21/23	1115	38.73		CT
06	HEN_06	8/21/23	1140	20.8		CT
10	HEN_10	8/21/23	0955	48.28		CT
11	HEN_11	8/21/23	0950	48.33		CT
15	HEN_15	8/21/23	1030	47.19		CT
19S	HEN_19#S	8/21/23	1045	37.2		CT
19D	HEN_19&D	8/21/23	1040	37.34		CT
25	HEN_25	8/22/23	0945	14.02 14.02	measured	CT
26	HEN_26	8/22/23	0940	13.26		CT
30	HEN_30	8/22/23	1000	4.85		CT
31	HEN_31	8/22/23	0955	4.85		CT
33	HEN_33	8/22/23	1018	2.8		CT
36	HEN_36	8/22/23	0930	13.58		CT
40S	HEN_40#S	8/21/23	1050	37.92		CT
45S	HEN_45#S	8/21/23	1105	18.98		CT
48	HEN_48	8/21/23	1055	N/A	* Could not measure due to gas	CT
XPW01	HEN_XPW01_pore	8/21/23	1005	9.45		CT
XPW02	HEN_XPW02_pore	8/21/23	1010	14.19		CT
XPW03	HEN_XPW03_pore	8/21/23	1020	4.86		CT
XSG01	HEN_XSG01					
SG02	HEN_YSG_ILRIVER					

U:6/21/23 GKJ

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>Hennepin, IL 8/21/23 @ 1140</u> Well Number <u>HEN-000</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?						
6. Is there a lock present?	X					
7. Bumper posts in good condition?	X					
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?			X			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	31.09ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad		X				
Slope away from casing?			X			
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:	DTW: 20.80 ft pump installed					
* Major well repair are those that require a subcontractor or separate mobilization to complete						

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>Hennepin, IL 8/11/23 @ 10:00 AM</u> Well Number <u>HEN-195</u>					X	
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	39.92 ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal setting?						
21. Well clearly visible and labeled?	X					
Comments:						
<u>DTW: 37.24 pump installed</u>						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

Site	<u>Hammock, IL</u>		
Inspection Date	<u>9/21/23 @ 1040</u>		
Well Number	<u>HE-N-19D</u>		

Major wells repairs * required to maintain well integrity?	Yes	No	NA
		<u>X</u>	

Stick-up Monitoring Wells

1. Outer protective Casing

- Not corroded
- Not dented
- Not cracked
- Not loose

2. Inner casing

- Not corroded
- Not dented
- Not cracked
- Not loose

3. Are there weep holes in outer casing?

4. Weep holes able to drain?

5. Is there a lockable cap present?

6. Is there a lock present?

7. Bumper posts in good condition?

Flushmount Monitoring Wells

8. Can the lid be secured tightly?

9. Does the lid have a gasket that seals?

10. No water in the flushmount?

11. Is the well cap lockable?

12. Is there a lock present?

All Monitoring Wells

Downhole Condition

12. Water level measuring point clearly marked?

13. No obstructions in well?

14. No plant roots or vegetation in well?

15. No sediment in bottom of well?

If present, how much sediment?

16. Installed as total depth.

17. Measured total depth of well.

General Condition

18. Concrete pad installed?

19. Concrete pad

Slope away from casing?

Not deteriorated?

Not heaved or below surrounding grade?

20. No surface seal settling?

21. Well clearly visible and labeled?

Comments:

Comments

DIV: 37.34 pump in well

* Major well repair are those that require a subcontractor or separate mobilization to complete

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>HENNEPIN, IL 8/21/23 @ 1035</u> Well Number <u>HEN-01R</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing						
Not corroded	Yes	No	NA			
Not dented		X				
Not cracked						
Not loose						
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?						
16. Installed as total depth.	ft					
17. Measured total depth of well.	42.38ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?	X					
Not deteriorated?	X					
Not heaved or below surrounding grade?						
20. No surface seal setting?		X				
21. Well clearly visible and labeled?	X					
Comments:						
<u>Pad is cracked & may need repairs 37.08 DTW</u>						

* Major well repair are those that require a subcontractor or separate mobilization to complete

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date Well Number	Hennepin, IL HEN-15				X	
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?	X					
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?						
16. Installed as total depth.	ft					
17. Measured total depth of well.	50.3 ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad		X				
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:						
contains pump! DTW: 47.19ft						
Top of bump: 50.3ft						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>Hennepin, IL 8/21/23 @ 0950</u>						
Well Number <u>11</u>					X	
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented		X				
Not cracked		X				
Not loose		X				
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented		X				
Not cracked		X				
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?						
6. Is there a lock present?	X					
7. Bumper posts in good condition?	X					
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?		X				
11. Is the well cap lockable?		X				
12. Is there a lock present?		X				
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?			X			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?		X				
If present, how much sediment?	—	ft				
16. Installed as total depth.	10	ft				
17. Measured total depth of well.	10	ft				
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad		X				
Slope away from casing?		X				
Not deteriorated?		X				
Not heaved or below surrounding grade?		X				
20. No surface seal settling?		X				
21. Well clearly visible and labeled?	X					
Comments:						
<u>DTN: 48834</u>						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date Well Number	Comments					
Stick-up Monitoring Wells						
1. Outer protective casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?	X					
7. Bumper posts in good condition?	X					
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?						
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?						
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:						
DTW: on App						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION								HEN-20		
Site: Hennepin, IL						Client: Ramboll				
Project Number:		Task #:		Start Date: 8/22/23		Time: 0800				
Field Personnel: Allison Beckwith			Finish Date:		Time: 1015					
WELL INFORMATION				EVENT TYPE						
Well ID: HEN-22D Casing ID: 2 inches				☐ Well Development	☒ Low-Flow / Low Stress Sampling					
				☐ Well Volume Approach Sampling	☐ Other (Specify):					
WATER QUALITY INDICATOR PARAMETERS (continued)										
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	+/-0.5 Temp. (°C)	+/-0.1 pH (SU)	+/-0.5 SEC or Cond. (µS/cm)	Dissolved Oxygen ±0.3 (mg/L) OR Turbidity +5% or +/-1 (NTU)	+/-1.0 ORP (mv)	Visual Clarity
	0819				17.1	7.56	0.712	3.04	-12.6	clear
	0824				17.9	7.35	0.722	1.06	-68.0	
	0829				17.8	7.29	0.728	1.07	-66.0	
	0834				17.7	7.29	0.729	0.85	-72.0	
	0839	2.0			18.2	7.29	0.730	0.84	-75.7	
	0844				18.6	7.30	0.730	0.87	-79.6	
	0849				19.0	7.30	0.731	0.85	-81.7	
	0854				18.0	7.30	0.729	0.05	-84.1	
	0859				17.7	7.30	0.731	0.83	-83.0	
	0904	3.5			18.0	7.30	0.731	0.91	-82.1	
NOTES (continued)								ABBREVIATIONS		
Samples taken @ 0910 Ferrous iron: Under range @ 0920								Cond - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured		
								ORP - Oxidation Reduction Potential SEC - Specific Electrical Conducance SU - Standard Units Temp - Temperature °C - Degrees Celsius		

P_1 of 1

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/22/23 @ 1200</u> Well Number <u>HEN-23</u>	Comments					
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?			X			
4. Weep holes able to drain?		X				
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
12. Water level measuring point clearly marked?	Yes	No	NA			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?						
If present, how much sediment?	— ft					
16. Installed as total depth.	— ft					
17. Measured total depth of well.	— ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad		X				
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments: <u>DTW's in app</u>						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>						Client: <u>Ramboll</u>					
Project Number: _____				Task #: _____		Start Date: <u>8/22/23</u>				Time: <u>1040</u>	
Field Personnel: <u>Allison Beckwith</u>				Finish Date: _____		Time: <u>1210</u>					
WELL INFORMATION					EVENT TYPE						
Well ID: <u>HEC-23</u>					☐ Well Development ☒ Low-Flow / Low Stress Sampling						
Casing ID: <u>2</u> inches					☐ Well Volume Approach Sampling ☐ Other (Specify): _____						
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	1041				15.8	7.39	0.836	2.91	3.61	-94.6	clear
	1040				15.7	7.40	0.836	1.32	3.75	-113.9	
	1051				15.4	7.42	0.838	0.49	3.79	-129.0	
	1050	1.5			15.5	7.37	0.837	0.35	3.80	-128.2	
	1101				15.4	7.37	0.835	0.26	5.81	-128.7	
	1100				15.2	7.39	0.835	0.21	6.69	-126.8	
	1111				15.4	7.39	0.833	0.26	7.9	-125.8	
	1110	3.0			15.0	7.40	0.832	0.18	9.1	-124.3	
NOTES (continued)								ABBREVIATIONS			
Samples taken @ 1120 Ferrous iron: Under range @ 1145								Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

P 1 of 1

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/22/23 @ 1308</u>						
Well Number <u>HEN-21R</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?			X			
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?		X				
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad		X				
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?		X				
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/22/23</u>		Time: <u>1300</u>	
Field Personnel: <u>Allison Beckert</u>				Finish Date: _____				Time: <u>1430</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-21R</u>				☐ Well Development ☒ Low-Flow / Low Stress Sampling ☐ Well Volume Approach Sampling ☐ Other (Specify): _____							
Casing ID: <u>2</u> inches											
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (Military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	1311 1311				17.8	7.56	0.768	1.17	59.8	-129.4	Clear
	1310 1310				17.3	7.54	0.764	1.22	58.5	-139.8	✓
	1321 1321				17.2	7.54	0.705	1.06	41.69	-139.9	Brownish
	1320 1320				17.1	7.53	0.768	1.16	33.94	-136.1	
	1331 1331	2.5			17.9	7.52	0.765	0.95	34.3	-137.2	
	1330 1330				17.1	7.53	0.763	0.930	32.3	-134.9	
	1341 1341	3.0			16.6	7.51	0.742	0.21	34.8	-136.3	
NOTES (continued)							ABBREVIATIONS				
Samples taken @ 1345 ferrous iron: 0.916 ppm							Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

P 1 of 1

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>Hennepin IL 8/12/23 @ 1:15</u> Well Number <u>HEN-51</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?						
6. Is there a lock present?	X					
7. BUMPER posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?			X			
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?	— ft					
16. Installed as total depth.	— ft					
17. Measured total depth of well.	— ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?						
Not deteriorated?		X				
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments: <u>DTW on app</u>						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/22/23</u>		Time: <u>1500</u>	
Field Personnel: <u>Allison Beckler</u>				Finish Date: _____				Time: _____			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-51</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling			
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	<u>1506</u>				<u>18.9</u>	<u>7.45</u>	<u>0.725</u>	<u>5.56</u>	<u>10.51</u>	<u>21.3</u>	<u>Clear</u>
	<u>1511</u>				<u>17.3</u>	<u>7.30</u>	<u>0.734</u>	<u>2.38</u>	<u>12.19</u>	<u>-88.3</u>	
	<u>1516</u>				<u>16.8</u>	<u>7.32</u>	<u>0.736</u>	<u>1.26</u>	<u>11.17</u>	<u>-105.3</u>	
	<u>1521</u>	<u>1.0</u>			<u>17.1</u>	<u>7.34</u>	<u>0.737</u>	<u>0.92</u>	<u>31.84</u>	<u>-115.5</u>	
	<u>1526</u>				<u>17.1</u>	<u>7.35</u>	<u>0.735</u>	<u>0.73</u>	<u>88.21</u>	<u>-122.1</u>	
	<u>1531</u>				<u>16.6</u>	<u>7.35</u>	<u>0.737</u>	<u>0.68</u>	<u>200.2</u>	<u>-124.5</u>	
	<u>1536</u>	<u>2.0</u>			<u>17.3</u>	<u>7.36</u>	<u>0.738</u>	<u>0.38</u>	<u>22.5</u>	<u>-126.7</u>	
	<u>1541</u>				<u>17.2</u>	<u>7.37</u>	<u>0.734</u>	<u>0.33</u>	<u>24.2</u>	<u>-127.4</u>	
	<u>1546</u>				<u>17.1</u>	<u>7.37</u>	<u>0.733</u>	<u>0.30</u>	<u>25.7</u>	<u>-127.7</u>	
	<u>1551</u>	<u>3.0</u>			<u>17.3</u>	<u>7.37</u>	<u>0.730</u>	<u>0.27</u>	<u>26.2</u>	<u>-128.0</u>	
NOTES (continued)								ABBREVIATIONS			
Samples taken @ 1556 Ferrous iron: 1.744 ppm @ 1618								Cond - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

P 1 of 1

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date Well Number	Comments					
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded						
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?						
Comments:						
DTM=on app						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/25/23</u>		Time: <u>08:15</u>	
Field Personnel: <u>ALISON BECKETT</u>				Finish Date: _____				Time: <u>09:20</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-22</u>				☐ Well Development ☒ Low-Flow / Low Stress Sampling							
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling ☐ Other (Specify): _____							
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	<u>0821</u>				<u>16.2</u>	<u>7.08</u>	<u>0.456</u>	<u>1.47</u>	<u>4.00</u>	<u>113.9</u>	<u>Clear</u>
	<u>0820</u>				<u>16.1</u>	<u>7.68</u>	<u>0.653</u>	<u>0.27</u>	<u>4.10</u>	<u>92.0</u>	
	<u>0831</u>	<u>2.5</u>			<u>16.1</u>	<u>7.69</u>	<u>0.453</u>	<u>0.18</u>	<u>4.14</u>	<u>87.2</u>	
	<u>0836</u>				<u>16.1</u>	<u>7.48</u>	<u>0.653</u>	<u>0.14</u>	<u>4.20</u>	<u>78.8</u>	
	<u>0841</u>	<u>5</u>			<u>16.1</u>	<u>7.68</u>	<u>0.653</u>	<u>0.13</u>	<u>4.24</u>	<u>77.6</u>	
	<u>0846</u>	<u>5.5</u>			<u>16.1</u>	<u>7.07</u>	<u>0.453</u>	<u>0.12</u>	<u>4.31</u>	<u>77.8</u>	
NOTES (continued)							ABBREVIATIONS				
Samples taken @0850 Ferrrous iron sample @0920: Under range							Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Site		Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date <u>4/22/23</u> Well Number <u>4CV32</u>							
Stick-up Monitoring Wells							
1. Outer protective Casing		Yes	No	NA	Comments		
Not corroded			☒				
Not dented			☒				
Not cracked			☒				
Not loose			☒				
2. Inner casing		Yes	No	NA			
Not corroded			☒				
Not dented			☒				
Not cracked			☒				
Not loose		Yes	No	NA			
3. Are there weep holes in outer casing?			☒				
4. Weep holes able to drain?			☒				
5. Is there a lockable cap present?			☒				
6. Is there a lock present?		☒					
7. Bumper posts in good condition?		☒					
Flushmount Monitoring Wells							
8. Can the lid be secured tightly?		Yes	No	NA			
9. Does the lid have a gasket that seals?			☒				
10. No water in the flushmount?			☒				
11. Is the well cap lockable?			☒				
12. Is there a lock present?			☒				
All Monitoring Wells							
Downhole Condition		Yes	No	NA			
12. Water level measuring point clearly marked?			☒				
13. No obstructions in well?			☒				
14. No plant roots or vegetation in well?			☒				
15. No sediment in bottom of well?			☒				
If present, how much sediment?		ft					
16. Installed as total depth.		ft					
17. Measured total depth of well.		ft					
General Condition							
18. Concrete pad installed?		Yes	No	NA			
19. Concrete pad		☒	☒				
Slope away from casing?			☒				
Not deteriorated?			☒				
Not heaved or below surrounding grade?			☒				
20. No surface seal settling?			☒				
21. Well clearly visible and labeled?		☒	☒				
Comments:							

* Major well repair are those that require a subcontractor or separate mobilization to complete

PROJECT INFORMATION											
Site: <u>HENNEPIN</u>				Client: <u>1035</u>							
Project Number: <u>2023 0711</u>				Task #: _____				Start Date: <u>8/22/23</u>		Time: <u>10:22</u>	
Field Personnel: <u>C. TREMBLAY</u>				Finish Date: _____				Time: <u>11:35</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEW-32</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling			
Casing ID: _____ inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	10% CLIO Turbidity (NTU)	ORP (mV)	Visual Clarity
PRE	1040	1			37	7.1	37	10%	4.69	+10	CLEAR
SAMPLE	1048				14.0	7.10	0.718	0.45	41.69	123.6	
	1053				13.9	7.11	0.716	0.21	20.60	165.2	
	1058				13.8	7.10	0.715	0.12	13.02	160.1	
	1103	3			13.8	7.10	0.715	0.09	8.77	156.9	
	1108				13.8	7.10	0.716	0.09	7.30	153.9	
	1113	3.25			13.8	7.07	0.715	0.08	5.33	151.7	
	1118										
NOTES (continued)								ABBREVIATIONS			
SAMPLE 1115 FI UNDERWAY								Cond. - Actual Conductivity FT BTOP - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date	8/22/23					
Well Number	33 @ 1018					
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?	X		X			
6. Is there a lock present?	X	X	X			
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?		X				
13. No obstructions in well?						
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	36-12 ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad			X			
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?		X				
21. Well clearly visible and labeled?		X				
Comments:	DTW 7-81 same as well Overhaul needs					
* Major well repair are those that require a subcontractor or separate mobilization to complete						

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/22/23</u> Well Number <u>3D</u> @ 1600						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?			X			
6. Is there a lock present?	X					
7. Bumper posts in good condition?	X					
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?		X				
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?		X				
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	18.6 ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?		X				
Not deteriorated?		X				
Not heaved or below surrounding grade?		X				
20. No surface seal settling?		X				
21. Well clearly visible and labeled?	X					
Comments: <u>PHV 4.85</u> <u>hns DMF</u>						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA																																																
Inspection Date Well Number	Stick-up Monitoring Wells			Comments																																																		
2/22/2023 38	1. Outer protective Casing Not corroded Not dented Not cracked Not loose			<table border="1"> <tr><td>Yes</td><td>No</td><td>NA</td></tr> <tr><td></td><td>X</td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> </table>			Yes	No	NA		X																																											
Yes	No	NA																																																				
	X																																																					
2. Inner casing Not corroded Not dented Not cracked Not loose	<table border="1"> <tr><td>Yes</td><td>No</td><td>NA</td></tr> <tr><td></td><td>X</td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> </table>			Yes	No	NA		X																	<table border="1"> <tr><td>Yes</td><td>No</td><td>NA</td></tr> <tr><td></td><td></td><td>X</td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> </table>			Yes	No	NA			X																					
Yes	No	NA																																																				
	X																																																					
Yes	No	NA																																																				
		X																																																				
3. Are there weep holes in outer casing? 4. Weep holes able to drain? 5. Is there a lockable cap present? 6. Is there a lock present? 7. Bumper posts in good condition?	<table border="1"> <tr><td>Yes</td><td>No</td><td>NA</td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> </table>			Yes	No	NA																			<table border="1"> <tr><td>Yes</td><td>No</td><td>NA</td></tr> <tr><td></td><td></td><td>X</td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> </table>			Yes	No	NA			X																					
Yes	No	NA																																																				
Yes	No	NA																																																				
		X																																																				
Flushmount Monitoring Wells 8. Can the lid be secured tightly? 9. Does the lid have a gasket that seals? 10. No water in the flushmount? 11. Is the well cap lockable? 12. Is there a lock present?	<table border="1"> <tr><td>Yes</td><td>No</td><td>NA</td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> </table>			Yes	No	NA																			<table border="1"> <tr><td>Yes</td><td>No</td><td>NA</td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> </table>			Yes	No	NA																								
Yes	No	NA																																																				
Yes	No	NA																																																				
All Monitoring Wells Downhole Condition 12. Water level measuring point clearly marked? 13. No obstructions in well? 14. No plant roots or vegetation in well? 15. No sediment in bottom of well? If present, how much sediment? 16. Installed as total depth. 17. Measured total depth of well.	<table border="1"> <tr><td>Yes</td><td>No</td><td>NA</td></tr> <tr><td></td><td></td><td>X</td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> </table>			Yes	No	NA			X																<table border="1"> <tr><td>ft</td><td></td><td></td></tr> <tr><td>ft</td><td></td><td></td></tr> <tr><td>8 ft</td><td></td><td></td></tr> </table>			ft			ft			8 ft																				
Yes	No	NA																																																				
		X																																																				
ft																																																						
ft																																																						
8 ft																																																						
General Condition 18. Concrete pad installed? 19. Concrete pad Slope away from casing? Not deteriorated? Not heaved or below surrounding grade? 20. No surface seal settling? 21. Well clearly visible and labeled? Comments:	<table border="1"> <tr><td>Yes</td><td>No</td><td>NA</td></tr> <tr><td>X</td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> </table>			Yes	No	NA	X																					<table border="1"> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td></tr> </table>																										
Yes	No	NA																																																				
X																																																						
DTW 4.85																																																						
* Major well repair are those that require a subcontractor or separate mobilization to complete																																																						

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/12/2012</u> Well Number <u>HW25</u> <u>0945</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition						
12. Water level measuring point clearly marked?	Yes	No	NA			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?		X				
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	15.71 ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?		X				
Not deteriorated?		X				
Not heaved or below surrounding grade?		X				
20. No surface seal setting?		X				
21. Well clearly visible and labeled?	X					
Comments:						
Well HAS pump * water SFT UP TO SURFACE NOTICED BRASS DTW 14.02 FST224, HAD CRACK DTW W/10 PUMP 135						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: _____				Client: _____							
Project Number: _____				Task #: _____				Start Date: <u>8/22/23</u>		Time: <u>1335</u>	
Field Personnel: <u>C. Trumbly</u>				Finish Date: _____				Time: <u>1455</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>25</u>				☐ Well Development ☐ Low-Flow / Low Stress Sampling							
Casing ID: _____ inches				☐ Well Volume Approach Sampling ☐ Other (Specify): _____							
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
PRA	1342		13.8								Cloudy
PURGE	1348	0.25	13.51						65.57		CLEAR
SAMPLE	1350		13.51	0	17.0	7.25	0.519	1.52	65.57	171.1	
	1355				16.6	7.25	0.519	1.46	42.11	171.7	
	1400				16.6	7.24	0.517	1.46	26.88	172.4	
	1405		13.51	0	16.6	7.24	0.516	1.48	17.97	173.8	
	1410				16.3	7.23	0.516	1.51	13.11	174.6	
	1415	3			16.6	7.23	0.516	1.52	9.47	175.2	
	1420				16.5	7.22	0.514	1.56	8.29	175.9	
	1425	4	13.51	0	16.6	7.22	0.514	1.59	6.43	176.5	
	1430										
NOTES (continued)								ABBREVIATIONS			
* GEOTECH PUMP FE - UNDERWAY SAMPLE @ 1430								Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

[illegible]

PROJECT INFORMATION											
Site: _____				Client: _____							
Project Number: _____				Task #: _____				Start Date: <u>8/22/23</u>		Time: <u>1455</u>	
Field Personnel: <u>TREMBLAY</u>				Finish Date: _____				Time: _____			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>26</u>				☐ Well Development				☐ Low-Flow / Low Stress Sampling			
Casing ID: _____ inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
PURGE	1500	0.1	13.8								CLEAR
SAMPLE	1506		13.8		17.3	7.09	0.784	0.51	2.31	186.1	
	1511				17.2	7.09	0.784	0.18	2.37	183.6	
	1516	1.5			17.1	7.09	0.784	0.16	2.40	181.8	
	1521				17.0	7.09	0.785	0.04	2.41	179.9	
	1526				17.0	7.09	0.784	0.02	2.44	178.6	
	1531	3.0	13.9	- 0.1	16.9	7.09	0.784	0.02	2.50	177.0	
NOTES (continued)								ABBREVIATIONS			
F3 UNDERLY Sample @ 1535								Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>Hennepin, IL 8/23/2013</u> Well Number <u>HEN-42</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked		X				
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?	X					
7. Bumper posts in good condition?	X					
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?		X				
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments: <u>DTU: on app</u>						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: _____							
Project Number: _____				Task #: _____				Start Date: <u>8/23/23</u>		Time: <u>1855</u>	
Field Personnel: <u>Allison Beckert</u>				Finish Date: _____				Time: <u>1407</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-47</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling			
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	<u>1501</u>				<u>22.9</u>	<u>7.03</u>	<u>0.404</u>	<u>6.05</u>	<u>3.85</u>	<u>113.7</u>	<u>clear</u>
	<u>1506</u>				<u>21.6</u>	<u>7.03</u>	<u>0.440</u>	<u>2.36</u>	<u>3.18</u>	<u>148.2</u>	
	<u>1511</u>	<u>1.0</u>			<u>21.6</u>	<u>7.03</u>	<u>0.440</u>	<u>2.05</u>	<u>3.12</u>	<u>152.0</u>	
	<u>1514</u>				<u>21.6</u>	<u>7.03</u>	<u>0.439</u>	<u>1.79</u>	<u>3.02</u>	<u>154.6</u>	
	<u>1521</u>				<u>21.5</u>	<u>7.03</u>	<u>0.441</u>	<u>1.68</u>	<u>3.01</u>	<u>156.2</u>	
	<u>1526</u>	<u>2.5</u>			<u>21.5</u>	<u>7.04</u>	<u>0.439</u>	<u>1.52</u>	<u>3.20</u>	<u>155.3</u>	
NOTES (continued)							ABBREVIATIONS				
Samples taken @ 1530 Ferrous iron @ 1600 : Under range							Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>Hennepin 8/13/23 @ 1105</u> Well Number <u>HEN-12</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?	X					
6. Is there a lock present?						
7. Bumper posts in good condition?	X					
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?		X	X			
13. No obstructions in well?						
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad		X				
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?			X			
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:						
DTW: DRAPP						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/23/23</u>		Time: <u>0930</u>	
Field Personnel: <u>Allison Belushi</u>				Finish Date: _____				Time: <u>1040</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HE-12</u>				☐ Well Development ☒ Low-Flow / Low Stress Sampling							
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling ☐ Other (Specify): _____							
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
		1038			21.3	7.81	0.551	9.73	3.92	149.6	clear
		1043			19.7	7.39	0.559	2.45	3.25	159.4	
		1048	1.5		19.6	7.35	0.559	2.01	3.10	157.1	
		1053			19.6	7.33	0.559	1.94	3.10	155.7	
		1058	2.5		19.5	7.31	0.559	1.91	3.11	155.1	
		1103			19.5	7.30	0.559	1.89	3.05	154.8	
		1108	4.0		19.5	7.30	0.558	1.88	3.0	154.1	
NOTES (continued)								ABBREVIATIONS			
Samples taken @ 1010 Ferrrous iron @ 1019: under range								Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date Well Number	Henpin 12 8/23/23 @ 815 HEN-410					
Stick-up Monitoring Wells						
1. Outer protective casing	Yes	No	NA	Comments		
Not corroded						
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded						
Not dented						
Not cracked						
Not loose						
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
12. Water level measuring point clearly marked?	Yes	No	NA			
13. No obstructions in well?						
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?						
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?						
Comments:						
DTM: ON APP						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

[illegible]

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	HENNEPIN, IL			Major wells repairs* required to maintain well integrity?	Yes	No	NA
Inspection Date	8/23/23 @ 1330						
Well Number	HEN-54						

	Yes	No	NA	
Stick-up Monitoring Wells				
1. Outer protective Casing	Yes	No	NA	Comments
Not corroded		X		
Not dented				
Not cracked				
Not loose		X		
Flushmount Monitoring Wells				
2. Inner casing	Yes	No	NA	Comments
Not corroded		X		
Not dented				
Not cracked		X		
Not loose	Yes	No	NA	
3. Are there weep holes in outer casing?			X	
4. Weep holes able to drain?				
5. Is there a lockable cap present?				
6. Is there a lock present?	X			
7. Bumper posts in good condition?	X			
Flushmount Monitoring Wells				
8. Can the lid be secured tightly?	Yes	No	NA	Comments
9. Does the lid have a gasket that seals?			X	
10. No water in the flushmount?				
11. Is the well cap lockable?			X	
12. Is there a lock present?				
All Monitoring Wells				
Downhole Condition				
12. Water level measuring point clearly marked?	Yes	No	NA	Comments
13. No obstructions in well?		X	X	
14. No plant roots or vegetation in well?		X		
15. No sediment in bottom of well?				
If present, how much sediment?	ft			
16. Installed as total depth.	ft			
17. Measured total depth of well.	ft			
General Condition				
18. Concrete pad installed?	Yes	No	NA	Comments
19. Concrete pad	X			
Slope away from casing?		X		
Not deteriorated?				
Not heaved or below surrounding grade?		X		
20. No surface seal settling?				
21. Well clearly visible and labeled?	X			
Comments:				
DTN: on app				
* Major well repair are those that require a subcontractor or separate mobilization to complete				

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>						Client: <u>Ramboll</u>					
Project Number: _____				Task #: _____		Start Date: <u>8/23/23</u>				Time: <u>1300</u>	
Field Personnel: <u>Allison Beckett</u>				Finish Date: _____		Time: <u>1455</u>					
WELL INFORMATION					EVENT TYPE						
Well ID: <u>HEN-54</u>					☐ Well Development		☒ Low-Flow / Low Stress Sampling				
Casing ID: <u>2</u> inches					☐ Well Volume Approach Sampling		☐ Other (Specify): _____				
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
13	1314 1314				22.7 22.7	7.36	0.5105	0.10	5.99	113.9	clear
13	1319 1319				23.0	7.32	0.574	3.58	24.10	128.2	
13	1324 1324	1.0			22.7	7.31	0.577	3.00	23.14	133.1	
13	1329 1329				22.4	7.31	0.576	2.71	19.6	131.4 131.4	
13	1334 1334				22.3	7.31	0.577	2.49	18.41	139.0 139.0	
13	1339 1339				22.4	7.30	0.577	2.40	14.50	140.2	
	1344				22.3	7.31	0.577	2.39	14.88	140.1	
	1349	2.5			22.6	7.30	0.576	2.31	13.82	141.0	
NOTES (continued)								ABBREVIATIONS			
samples taken @ 1350 Ferrous iron sample @ 1450: 5.371								Cond. - Actual Conductivity FT BTOP - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date	HENNEPIN IL 9/23/23 @ 1110					
Well Number	HEN-13					
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded	X			oxidized & rusty		
Not dented		X				
Not cracked						
Not loose		X				
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?						
6. Is there a lock present?	X					
7. Bumper posts in good condition?	X					
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?			X			
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition						
12. Water level measuring point clearly marked?	Yes	No	NA			
13. No obstructions in well?			X			
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad		X				
Slope away from casing?						
Not deteriorated?			X			
Not heaved or below surrounding grade?						
20. No surface seal settling?			X			
21. Well clearly visible and labeled?	X					
Comments:						
DNV-DNAPP						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/23/23</u>		Time: <u>1055</u>	
Field Personnel: <u>Allison Belkett</u>				Finish Date: _____				Time: <u>1255</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-13</u>				☐ Well Development ☒ Low-Flow / Low Stress Sampling							
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling ☐ Other (Specify): _____							
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	1057				21.5	7.33	0.552	1.30	3.19	152.0	Clear
	1102				21.0	7.37	0.502	3.07	3.18	152.7	
	1107	1.00			21.0	7.38	0.503	3.47	3.19	151.1	
	1112				21.0	7.38	0.503	2.33	3.20	149.9	
	1117				21.0	7.39	0.503	2.23	3.21	149.9	
	1122	2.0			21.4	7.39	0.503	2.10	3.05	150.2	↓
NOTES (continued)							ABBREVIATIONS				
samples taken @ 1125 Ferrous iron @ 1145: under range dupe @ 1125							Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Site		Major wells repairs* required to maintain well integrity?		
Inspection Date	Well Number	Yes	No	NA
8/03/03	187			
Stick-up Monitoring Wells				
1. Outer protective Casing	Yes	No	NA	Comments
Not corroded		X		
Not dented				
Not cracked				
Not loose				
2. Inner casing	Yes	No	NA	
Not corroded		X		
Not dented				
Not cracked				
Not loose				
3. Are there weep holes in outer casing?	Yes	No	NA	
4. Weep holes able to drain?		X		
5. Is there a lockable cap present?				
6. Is there a lock present?				
7. Bumper posts in good condition?				
Flushmount Monitoring Wells				
8. Can the lid be secured tightly?	Yes	No	NA	
9. Does the lid have a gasket that seals?				
10. No water in the flushmount?				
11. Is the well cap lockable?				
12. Is there a lock present?				
All Monitoring Wells				
Downhole Condition	Yes	No	NA	
12. Water level measuring point clearly marked?		X		
13. No obstructions in well?				
14. No plant roots or vegetation in well?				
15. No sediment in bottom of well?				
If present, how much sediment?	ft			
16. Installed as total depth.	ft			
17. Measured total depth of well.	ft			
General Condition				
18. Concrete pad installed?	Yes	No	NA	
19. Concrete pad		X		
Slope away from casing?				
Not deteriorated?				
Not heaved or below surrounding grade?				
20. No surface seal settling?		X		
21. Well clearly visible and labeled?				
Comments:				

* Major well repair are those that require a subcontractor or separate mobilization to complete

PROJECT INFORMATION											
Site: _____				Client: _____							
Project Number: <u>2023-074</u>				Task #: _____				Start Date: <u>8/23/23</u>		Time: <u>1318</u>	
Field Personnel: <u>TREMBLAY</u>				Finish Date: _____				Time: <u>1435</u>			
WELL INFORMATION					EVENT TYPE						
Well ID: <u>14D</u>					☐ Well Development ☐ Low-Flow / Low Stress Sampling						
Casing ID: _____ inches					☐ Well Volume Approach Sampling ☐ Other (Specify): _____						
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
<u>PURGE</u>											
<u>PURGE</u>	<u>1330</u>	<u>0.1</u>									<u>CLEAR</u>
	<u>1333</u>				<u>21.3</u>	<u>7.22</u>	<u>0.692</u>	<u>2.84</u>	<u>15.81</u>	<u>169.2</u>	
	<u>1338</u>				<u>21.3</u>	<u>7.17</u>	<u>0.688</u>	<u>0.78</u>	<u>6.81</u>	<u>79.1</u>	
	<u>1343</u>	<u>1.5</u>			<u>21.2</u>	<u>7.17</u>	<u>0.684</u>	<u>0.33</u>	<u>10.25</u>	<u>72.2</u>	
	<u>1348</u>				<u>21.2</u>	<u>7.17</u>	<u>0.684</u>	<u>0.18</u>	<u>11.18</u>	<u>71.7</u>	
	<u>1353</u>				<u>21.1</u>	<u>7.18</u>	<u>0.684</u>	<u>0.17</u>	<u>10.44</u>	<u>68.3</u>	
	<u>1358</u>	<u>2</u>			<u>21.2</u>	<u>7.18</u>	<u>0.685</u>	<u>0.17</u>	<u>10.26</u>	<u>68.2</u>	
NOTES (continued)								ABBREVIATIONS			
<u>SAMPLE @ 1405</u> <u>F1 - UNDER</u>								Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/21/23</u> Well Number <u>HEN-05DP</u>					X	
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?	Yes	No	NA			
6. Is there a lock present?		X				
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?						
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?						
If present, how much sediment?						
16. Installed as total depth.	1 ft					
17. Measured total depth of well.	108.10 ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments: <u>DNV 3879 PUMP installed</u>						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>HENNEPIN</u>		Client: _____									
Project Number: <u>2023 0711</u>		Task #: _____									
Field Personnel: <u>C. Tremblay</u>		Start Date: <u>8/23/23</u>									
		Finish Date: _____									
Time: <u>1155</u>		Time: <u>1305</u>									
WELL INFORMATION				EVENT TYPE							
Well ID: <u>05 DR</u>		☐ Well Development		☒ Low-Flow / Low Stress Sampling							
Casing ID: _____ inches		☐ Well Volume Approach Sampling		☐ Other (Specify): _____							
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
PRE	1155	0.75	38.73	0							
PURGE	1205	0.75	38.73	0							CLEAR
	1210	0.75	38.73	0	21.2	7.41	0.632	0.77	2.81	169.5	
	1215		38.73	0	20.6	7.41	0.631	0.28	2.54	167.7	
	1220		38.73	0	20.6	7.42	0.631	0.20	2.67	165.1	
	1225	1.25	38.73		20.8	7.41	0.631	0.18	2.23	163.5	
	1230		38.73		20.8	7.41	0.631	0.16	2.35	161.7	
	1235		38.73		20.8	7.41	0.631	0.15	2.51	160.2	
	1240		38.73		20.8	7.41	0.631	0.15	2.12	158.8	
NOTES (continued)							ABBREVIATIONS				
SAMPLE @ - 1145 FI - HANDPUMP							Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date	8/21/23 @ 1105					
Well Number	HEN-05R					
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?						
16. Installed as total depth.						
17. Measured total depth of well.						
	ft					
	410.05 ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments: DTW: 38.00 pmp installed						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin</u>				Client: _____							
Project Number: <u>2023-0711</u>				Task #: _____				Start Date: <u>8/23/23</u>		Time: <u>1036</u>	
Field Personnel: <u>C. TREMBLAY</u>				Finish Date: _____				Time: <u>1150</u>			
WELL INFORMATION					EVENT TYPE						
Well ID: <u>05R</u>					☐ Well Development ☐ Low-Flow / Low Stress Sampling						
Casing ID: _____ inches					☐ Well Volume Approach Sampling ☐ Other (Specify): _____						
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
PRE	1036		38.69								
PURGE	1042	0.1	38.69	Q			0.646	1.60	27.51	112.9	CLEAR
SAMPLE	1048	0.5	38.69	Q	20.6	7.61	0.646	1.60	27.51	112.9	↓
	1053		38.69	Q	20.6	7.61	0.644	0.36	18.70	136.8	
	1058		38.69	Q	20.5	7.61	0.643	0.23	12.41	141.0	
	1103	1.25	38.69	Q	20.8	7.61	0.643	0.19	8.77	142.8	
	1108		38.69	Q	20.6	7.61	0.644	0.17	7.00	143.7	
	1113		38.69	Q	20.8	7.61	0.643	0.15	5.15	144.0	
	1118	2.5	38.69	Q	20.6	7.61	0.645	0.14	4.41	144.2	
	1123				20.3	7.62	0.644	0.14	3.55	144.2	
NOTES (continued)								ABBREVIATIONS			
SAMPLE@ - 1130 FI - 0.806 ppm								Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Monitoring Well Evaluation Checklist

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/21/23 @ 1055</u> Well Number <u>HEN-48</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented	X	X		SPACE DEUT		
Not cracked		X				
Not loose	X			WELL IS LOOSE		
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented		X				
Not cracked	X			TOWER CASE CRACKED		
Not loose	X					
3. Are there weep holes in outer casing?	Yes	No	NA			
4. Weep holes able to drain?		X				
5. Is there a lockable cap present?	X					
6. Is there a lock present?	X					
7. Bumper posts in good condition?	X					
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?	X					
10. No water in the flushmount?			X			
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?	X			CRACKED WEL		
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?			X			
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?	X					
Not deteriorated?		X				
Not heaved or below surrounding grade?	X					
20. No surface seal settling?	X					
21. Well clearly visible and labeled?	X					
Comments:						
<u>LOOSE NOT TAKE WATER LEVEL READING DUE TO BLOCKAGE</u>						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION															
Site: <u>HEMPERU</u>		Client: _____													
Project Number: <u>2023 021</u>		Task #: _____		Start Date: <u>8/23/23</u>		Time: <u>0931</u>									
Field Personnel: <u>_____</u>		Finish Date: _____		Time: <u>1030</u>											
WELL INFORMATION				EVENT TYPE											
Well ID: <u>48</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling							
Casing ID: _____ inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____							
WATER QUALITY INDICATOR PARAMETERS (continued)															
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity				
PURGE	0937	0.11			20.9	7.63	0.601	1.93	5.23	163.4	CLEAR				
SAMPLE	0943	0.75			20.9	7.63	0.601	1.93	5.23	163.4	↓				
	0948				20.8	7.62	0.590	0.50	4.37	160.2					
	0953				20.7	7.62	0.589	0.24	3.28	137.8					
	0958				20.5	7.62	0.589	0.18	2.71	154.3					
	1003	2.25			20.7	7.62	0.589	0.15	2.22	152.0					
	1008				20.7	7.62	0.589	0.13	2.30	150.3					
	1013				20.7	7.62	0.589	0.12	2.09	148.7					
	1018	3			20.8	7.62	0.589	0.11	2.01	147.4					
NOTES (continued)								ABBREVIATIONS							
* WELL HAS OBSTRUCTION INSIDE CASING. COULD NOT MEASURE WATER SAMPLE @ - 1020 FI - UNDERWAY								Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured				ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date	Hennepin, IL 8/21/23 @ 1050					
Well Number	HEN-405					
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?	X					
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
15. No sediment in bottom of well?						
If present, how much sediment?	— ft					
16. Installed as total depth.	30.92 ft					
17. Measured total depth of well.						
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:	37.92' 30.92 ft pump installed					
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>HENNECP2</u>				Client: _____							
Project Number: <u>2023 0711</u>				Task #: _____		Start Date: <u>8/23/23</u>		Time: <u>0820</u>			
Field Personnel: <u>C. TREMBLAY</u>				Finish Date: _____		Time: <u>0913</u>					
WELL INFORMATION					EVENT TYPE						
Well ID: <u>405</u>					☐ Well Development ☒ Low-Flow / Low Stress Sampling						
Casing ID: _____ inches					☐ Well Volume Approach Sampling ☐ Other (Specify): _____						
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
PRE	0832		37.92	0							
Purge	0836	0.1	37.92	0							CLEAR
Sample	0841		37.92	0	19.0	7.89	0.581	2.20	4.25	147.6	↓
	0846	1.5	37.92	0	18.8	7.89	0.579	0.41	3.29	143.4	
	0851		37.92	0	19.7	7.88	0.579	0.44	2.58	139.1	
	0856		37.92	0	18.7	7.88	0.579	0.37	2.16	135.7	
	0901	2:75	37.92	0	18.8	7.88	0.579	0.37	2.13	133.5	
NOTES (continued)								ABBREVIATIONS			
Sample @ 0905 FI - HAND PUMP								Cond. - Actual Conductivity FT BTOP - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
<u>Hennepin</u>						
Inspection Date	<u>8/24/23</u>					
Well Number	<u>HGP-35</u>					
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
3. Are there weep holes in outer casing?	Yes	No	NA			
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?		X				
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?		X				
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?		X				
Not deteriorated?		X				
Not heaved or below surrounding grade?		X				
20. No surface seal settling?		X				
21. Well clearly visible and labeled?	X					
Comments:						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: _____				Client: _____							
Project Number: _____				Task #: _____				Start Date: <u>8/24</u>		Time: <u>0930</u>	
Field Personnel: <u>TREMBLAY</u>				Finish Date: _____				Time: <u>1038</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN 35</u>				☐ Well Development				☐ Low-Flow / Low Stress Sampling			
Casing ID: _____ inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
PURGE	<u>0940</u>	<u>0.1</u>			<u>+3%</u>	<u>+1</u>	<u>3%</u>	<u>10%</u>	<u>10%</u>	<u>+10</u>	<u>CLEAR</u>
SAMPLE	<u>0946</u>				<u>16.5</u>	<u>7.10</u>	<u>0.926</u>	<u>8.28</u>	<u>14.30</u>	<u>159.9</u>	
	<u>0951</u>				<u>16.2</u>	<u>7.04</u>	<u>0.918</u>	<u>6.78</u>	<u>15.97</u>	<u>169.8</u>	
	<u>0956</u>	<u>1.0</u>			<u>16.3</u>	<u>7.03</u>	<u>1.369</u>	<u>2.16</u>	<u>7.70</u>	<u>163.8</u>	
	<u>1001</u>				<u>16.2</u>	<u>7.03</u>	<u>1.378</u>	<u>1.87</u>	<u>2.67</u>	<u>162.0</u>	
	<u>1006</u>	<u>2.0</u>			<u>16.2</u>	<u>7.03</u>	<u>1.358</u>	<u>1.47</u>	<u>2.81</u>	<u>161.7</u>	
	<u>1011</u>										
NOTES (continued)								ABBREVIATIONS			
<u>FE - UNDER UNDER</u> <u>SAMPLE @ 1010</u>								Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date	8/24/23					
Well Number	HEN-52					
Stick-up Monitoring Wells						
1. Outer protective casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose		X				
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked		X				
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?		X				
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?			X			
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?		X				
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:						
DTW: on app						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION															
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>											
Project Number: _____				Task #: _____				Start Date: <u>8/24/23</u>				Time: <u>0905</u>			
Field Personnel: <u>Allison Beckert</u>				Finish Date: _____				Time: <u>1020</u>							
WELL INFORMATION						EVENT TYPE									
Well ID: <u>HEN-S2</u>						☐ Well Development ☒ Low-Flow / Low Stress Sampling									
Casing ID: <u>2</u> inches						☐ Well Volume Approach Sampling ☐ Other (Specify): _____									
WATER QUALITY INDICATOR PARAMETERS (continued)															
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity				
0	0909				21.5	7.10	0.035	7.57	5.56	147.7	Clear				
	0914				23.6	7.01	0.005	2.02	5.95	152.3					
	0919	1.0			23.8	7.06	0.009	1.39	4.68	149.7					
	0924				23.9	7.05	0.012	1.21	4.27	147.2					
	0929	2.0			23.9	7.04	0.013	1.03	4.25	146.5					
25	0934				24.0	7.04	0.014	1.96	4.08	145.8					
NOTES (continued)								ABBREVIATIONS							
Samples taken @ 0940 Ferrous iron @ 1011: Under range								Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured							
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius							

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date HENNEPIN, IL 9/24/23 @ 1400						
Well Number HEN-80						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded						
Not dented		X				
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?			X			
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?	X					
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?			X			
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?			X			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal setting?		X				
21. Well clearly visible and labeled?	X					
Comments:						
DIVISION APP						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/24/23</u>		Time: <u>1140</u>	
Field Personnel: <u>Allison Beckwith</u>				Finish Date: _____				Time: <u>1311</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-88D</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling			
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	<u>1154</u>				<u>18.7</u>	<u>7.03</u>	<u>1.330</u>	<u>0.45</u>	<u>4.29</u>	<u>182.5</u>	<u>clear</u>
	<u>1159</u>				<u>17.7</u>	<u>6.104</u>	<u>1.420</u>	<u>0.88</u>	<u>193.7</u>		
	<u>1204</u>				<u>17.7</u>	<u>6.58</u>	<u>1.433</u>	<u>0.98</u>	<u>5.34</u>	<u>194.0</u>	
	<u>1209</u>	<u>1.0</u>			<u>17.4</u>	<u>6.58</u>	<u>1.430</u>	<u>0.70</u>	<u>4.10</u>	<u>193.0</u>	
	<u>1214</u>				<u>17.5</u>	<u>6.58</u>	<u>1.432</u>	<u>0.75</u>	<u>4.57</u>	<u>192.4</u>	
	<u>1219</u>	<u>2.0</u>			<u>17.3</u>	<u>6.59</u>	<u>1.435</u>	<u>0.03</u>	<u>4.32</u>	<u>192.0</u>	
NOTES (continued)								ABBREVIATIONS			
Samples taken @ 1225 Ferrous iron sample @ 1232: under range								Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>Hennepin, IL 8/24/2013</u> Well Number <u>HEN-07</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition						
12. Water level measuring point clearly marked?	Yes	No	NA			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?						
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad		X				
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:						
						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin IL</u>				Client: _____							
Project Number: _____				Task #: _____				Start Date: <u>8/24/23</u>		Time: <u>1320</u>	
Field Personnel: <u>Allison Beckert</u>				Finish Date: _____				Time: <u>1430</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-07</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling			
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	<u>1332</u>				<u>14.4</u>	<u>6.98</u>	<u>0.727</u>	<u>5.73</u>	<u>5.16</u>	<u>144.3</u>	<u>clear</u>
	<u>1337</u>				<u>14.0</u>	<u>6.97</u>	<u>0.698</u>	<u>4.25</u>	<u>4.45</u>	<u>174.5</u>	
	<u>1342</u>	<u>2.0</u>			<u>13.9</u>	<u>6.916</u>	<u>0.701</u>	<u>4.20</u>	<u>4.09</u>	<u>170.0</u>	
	<u>1347</u>				<u>13.9</u>	<u>6.94</u>	<u>0.760</u>	<u>4.16</u>	<u>3.85</u>	<u>178.7</u>	
	<u>1352</u>	<u>3.0</u>			<u>13.8</u>	<u>6.93</u>	<u>0.699</u>	<u>4.16</u>	<u>3.57</u>	<u>179.6</u>	
	<u>1357</u>				<u>13.8</u>	<u>6.91</u>	<u>0.699</u>	<u>4.15</u>	<u>3.55</u>	<u>179.9</u>	
NOTES (continued)								ABBREVIATIONS			
Samples taken @ 1400 Ferrous iron sample @ 1430: under range								Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date						
Well Number						
Stick-up Monitoring Wells Flushmount Monitoring Wells						
1. Outer protective Casing Not corroded Not dented Not cracked Not loose				Yes	No	NA
2. Inner casing Not corroded Not dented Not cracked Not loose				Yes	No	NA
3. Are there weep holes in outer casing? 4. Weep holes able to drain? 5. Is there a lockable cap present? 6. Is there a lock present? 7. Bumper posts in good condition?				Yes	No	NA
8. Can the lid be secured tightly? 9. Does the lid have a gasket that seals? 10. No water in the flushmount? 11. Is the well cap lockable? 12. Is there a lock present?				Yes	No	NA
Downhole Condition 12. Water level measuring point clearly marked? 13. No obstructions in well? 14. No plant roots or vegetation in well? 15. No sediment in bottom of well? If present, how much sediment? 16. Installed as total depth. 17. Measured total depth of well.				Yes	No	NA
General Condition 18. Concrete pad installed? 19. Concrete pad Slope away from casing? Not deteriorated? Not heaved or below surrounding grade? 20. No surface seal settling? 21. Well clearly visible and labeled?				Yes	No	NA
Comments:						

* Major well repair are those that require a subcontractor or separate mobilization to complete

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/21/21</u>		Time: <u>1435</u>	
Field Personnel: <u>Allison Bell</u>				Finish Date: _____				Time: <u>1620</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>08</u>				☐ Well Development ☒ Low-Flow / Low Stress Sampling							
Casing ID: _____ inches				☐ Well Volume Approach Sampling ☐ Other (Specify): _____							
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	<u>1443</u>				<u>14.7</u>	<u>6.62</u>	<u>1.228</u>	<u>1.54</u>	<u>3.85</u>	<u>192.1</u>	<u>Clear</u>
	<u>1449</u>				<u>14.6</u>	<u>6.58</u>	<u>1.239</u>	<u>1.30</u>	<u>3.61</u>	<u>194.1</u>	
	<u>1453</u>	<u>2.5</u>			<u>14.7</u>	<u>6.69</u>	<u>1.239</u>	<u>1.22</u>	<u>3.53</u>	<u>188.9</u>	
	<u>1458</u>				<u>14.6</u>	<u>6.69</u>	<u>1.243</u>	<u>1.19</u>	<u>3.50</u>	<u>188.1</u>	
	<u>1503</u>				<u>14.6</u>	<u>6.72</u>	<u>1.244</u>	<u>1.17</u>	<u>3.49</u>	<u>188.6</u>	
	<u>1508</u>				<u>14.7</u>	<u>6.72</u>	<u>1.241</u>	<u>1.16</u>	<u>3.49</u>	<u>188.6</u>	
NOTES (continued)								ABBREVIATIONS			
<u>Samples taken @ 1510</u> <u>Ferrous iron sampled @ 1530: under range</u> <u>dupe @ 1510</u>								Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/24/23</u> Well Number <u>27</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?	X					
6. Is there a lock present?	X					
7. BUMPER posts in good condition?	X					
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
12. Water level measuring point clearly marked?	Yes	No	NA			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?		X				
Not deteriorated?		X				
Not heaved or below surrounding grade?		X				
20. No surface seal settling?		X				
21. Well clearly visible and labeled?	X					
Comments:						

* Major well repair are those that require a subcontractor or separate mobilization to complete

PROJECT INFORMATION											
Site: _____				Client: _____							
Project Number: _____				Task #: _____				Start Date: <u>8/24</u>		Time: <u>0820</u>	
Field Personnel: <u>TRUMBLY</u>				Finish Date: _____				Time: <u>0921</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEW 27</u>				☐ Well Development ☐ Low-Flow / Low Stress Sampling							
Casing ID: _____ inches				☐ Well Volume Approach Sampling ☐ Other (Specify): _____							
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
0824											
PURGE	<u>0824</u>	<u>0.1</u>									<u>CLEAR</u>
SAMPLE	<u>0828</u>				<u>12.9</u>	<u>7.21</u>	<u>0.819</u>	<u>0.50</u>	<u>13.75</u>	<u>0.1</u>	
	<u>0833</u>	<u>1</u>			<u>13.0</u>	<u>7.22</u>	<u>0.817</u>	<u>0.09</u>	<u>25.15</u>	<u>-20.3</u>	
	<u>0938</u>				<u>13.5</u>	<u>7.24</u>	<u>0.813</u>	<u>0.04</u>	<u>45.33</u>	<u>-29.8</u>	
	<u>0943</u>				<u>12.8</u>	<u>7.32</u>	<u>0.816</u>	<u>0.04</u>	<u>46.72</u>	<u>-31.5</u>	
	<u>0848</u>	<u>2.75</u>			<u>12.4</u>	<u>7.33</u>	<u>0.816</u>	<u>0.06</u>	<u>47.09</u>	<u>-32.9</u>	
	<u>0853</u>	<u>3.0</u>			<u>12.5</u>	<u>7.33</u>	<u>0.816</u>	<u>0.07</u>	<u>48.81</u>	<u>-33.7</u>	
	<u>0854</u>										
NOTES (continued)							ABBREVIATIONS				
<u>FEUNDER</u> <u>SAMPLE @ 0900</u>							Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>Hennepin, IL 8/21/23 @ 1200</u> Well Number <u>HEN-02</u>					X	
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose		X				
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?			X			
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?						
If present, how much sediment?	— ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	47.10 ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?		X				
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:	DTN: 41.84 ft pump installed					
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/24/2023</u>		Time: <u>1025</u>	
Field Personnel: <u>Allison Beckett</u>				Finish Date: _____				Time: <u>1120</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-02</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling			
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	<u>1032</u>		<u>41.17</u>		<u>15.4</u>	<u>7.12</u>	<u>0.1079</u>	<u>5.70</u>	<u>5.80</u>	<u>156.5</u>	<u>Clear</u>
	<u>1037</u>		<u>41.17</u>		<u>14.2</u>	<u>6.81</u>	<u>0.1087</u>	<u>0.63</u>	<u>5.08</u>	<u>172.7</u>	
	<u>1042</u>	<u>2.0</u>	<u>41.17</u>		<u>14.0</u>	<u>6.78</u>	<u>0.1085</u>	<u>0.38</u>	<u>5.12</u>	<u>174.3</u>	
	<u>1047</u>		<u>41.16</u>		<u>14.1</u>	<u>6.81</u>	<u>0.1084</u>	<u>0.31</u>	<u>4.31</u>	<u>172.3</u>	
	<u>1052</u>	<u>3.0</u>	<u>41.15</u>		<u>14.0</u>	<u>6.83</u>	<u>0.1084</u>	<u>0.27</u>	<u>3.99</u>	<u>170.8</u>	
	<u>1057</u>				<u>14.0</u>	<u>6.83</u>	<u>0.1086</u>	<u>0.27</u>	<u>4.17</u>	<u>170.1</u>	
	<u>1102</u>	<u>4.0</u>			<u>14.0</u>	<u>6.83</u>	<u>0.1085</u>	<u>0.24</u>	<u>3.85</u>	<u>169.1</u>	↓
NOTES (continued)							ABBREVIATIONS				
Samples taken @ 1105 *NO FERROUS IRON SAMPLE*							Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>9/21/23 @ 1010</u> Well Number <u>HEN-XP NOC - Pave</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition						
12. Water level measuring point clearly marked?	Yes	No	NA			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?						
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments: <u>DTW: 14.39 ft</u>						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: _____				Client: _____							
Project Number: _____				Task #: _____				Start Date: <u>8/24/23</u>		Time: <u>1252</u>	
Field Personnel: <u>TRUMBULL</u>				Finish Date: _____				Time: <u>1450</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>XPW02</u>				☐ Well Development				☐ Low-Flow / Low Stress Sampling			
Casing ID: _____ inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
PRE	<u>1256</u>	<u>4</u>	<u>14.03</u>								
PURGE	<u>1304</u>	<u>0.1</u>	<u>14.19</u>	<u>-0.16</u>							<u>CLEAR</u>
SAMPLE	<u>1308</u>	<u>1.0</u>	<u>14.58</u>	<u>-0.39</u>	<u>19.4</u>	<u>12.03</u>	<u>3.071</u>	<u>0.91</u>	<u>89.87</u>	<u>-116.0</u>	
	<u>1313</u>		<u>14.92</u>	<u>-0.36</u>	<u>19.2</u>	<u>12.13</u>	<u>3.111</u>	<u>0.21</u>	<u>59.77</u>	<u>-155.7</u>	
	<u>1318</u>		<u>15.0</u>	<u>-0.18</u>	<u>19.4</u>	<u>12.14</u>	<u>3.109</u>	<u>0.14</u>	<u>40.43</u>	<u>-165.2</u>	
	<u>1323</u>	<u>2.5</u>	<u>15.1</u>	<u>-0.1</u>	<u>19.3</u>	<u>12.16</u>	<u>3.129</u>	<u>0.10</u>	<u>28.61</u>	<u>-168.5</u>	
	<u>1328</u>		<u>15.13</u>	<u>-0.03</u>	<u>19.8</u>	<u>12.16</u>	<u>3.146</u>	<u>0.12</u>	<u>29.94</u>	<u>-157.5</u>	
	<u>1333</u>		<u>15.15</u>	<u>-0.02</u>	<u>19.7</u>	<u>12.17</u>	<u>3.163</u>	<u>0.12</u>	<u>22.84</u>	<u>-152.3</u>	
	<u>1338</u>	<u>3.25</u>	<u>15.15</u>	<u>0</u>	<u>19.7</u>	<u>12.17</u>	<u>3.191</u>	<u>0.12</u>	<u>23.05</u>	<u>-148.4</u>	
NOTES (continued)							ABBREVIATIONS				
FI - 0.109 Sample - 1345 EB - 1345							Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/21/23 @ 1005</u> Well Number <u>HENXPDN 01 - PORE</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?		X				
6. Is there a lock present?	X					
7. Bumper posts in good condition?	X					
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition						
12. Water level measuring point clearly marked?	Yes	No	NA			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?		X				
If present, how much sediment?	<u>14.13</u> ft					
16. Installed as total depth.	<u>17.13</u> ft					
17. Measured total depth of well.						
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad		X				
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?		X				
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:						
<u>DTW: 9.45 ft Bottom of casing: 17.13 ft</u>						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: _____				Client: _____							
Project Number: _____				Task #: _____				Start Date: <u>8/24/23</u>		Time: <u>1125</u>	
Field Personnel: <u>CT Rangel</u>				Finish Date: _____				Time: <u>1230</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>XPW01</u>				☐ Well Development ☒ Low-Flow / Low Stress Sampling ☐ Well Volume Approach Sampling ☐ Other (Specify): _____							
Casing ID: _____ inches											
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
<u>PPE</u>	<u>1125</u>		<u>9.45</u>								
<u>PURGE</u>	<u>1130</u>	<u>0.1</u>	<u>9.45</u>	<u>Q</u>							<u>CLEAR</u>
<u>SAMPLE</u>	<u>1135</u>	<u>0.25</u>	<u>9.45</u>	<u>Q</u>	<u>16.5</u>	<u>11.30</u>	<u>0.783</u>	<u>0.37</u>	<u>9.22</u>	<u>-241.6</u>	
	<u>1140</u>		<u>9.45</u>	<u>Q</u>	<u>19.5</u>	<u>11.31</u>	<u>0.795</u>	<u>0.22</u>	<u>10.51</u>	<u>-242.4</u>	
	<u>1145</u>	<u>1.0</u>	<u>9.45</u>	<u>Q</u>	<u>16.8</u>	<u>11.33</u>	<u>0.801</u>	<u>0.17</u>	<u>13.54</u>	<u>-244.1</u>	
	<u>1150</u>		<u>9.45</u>	<u>Q</u>	<u>19.0</u>	<u>11.33</u>	<u>0.804</u>	<u>0.11</u>	<u>17.05</u>	<u>-248.5</u>	
	<u>1155</u>		<u>9.45</u>	<u>Q</u>	<u>19.2</u>	<u>11.34</u>	<u>0.808</u>	<u>0.11</u>	<u>21.53</u>	<u>-259.5</u>	
	<u>1200</u>	<u>2.25</u>	<u>9.45</u>	<u>Q</u>	<u>17.6</u>	<u>11.39</u>	<u>0.815</u>	<u>0.11</u>	<u>54.09</u>	<u>-271.9</u>	
	<u>1205</u>		<u>9.45</u>	<u>Q</u>	<u>17.7</u>	<u>11.39</u>	<u>0.817</u>	<u>0.10</u>	<u>57.11</u>	<u>-278.6</u>	
	<u>1210</u>	<u>3.5</u>	<u>9.45</u>	<u>Q</u>	<u>17.7</u>	<u>11.39</u>	<u>0.818</u>	<u>0.10</u>	<u>55.97</u>	<u>-279.1</u>	
NOTES (continued)							ABBREVIATIONS				
<u>Sample @ 1215</u> <u>FT - under</u> <u>EQUIPMENT BANK @ 1215</u>							Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date Well Number	Hennepin IL 8/21/23 @ 1010 HEN-XPNO3-P012				X	
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?						
5. Is there a lockable cap present?	X					
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?						
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
	19.11					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal setting?						
21. Well clearly visible and labeled?	X					
Comments:						
DTW: 9.86 ft.						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: _____				Client: _____							
Project Number: _____				Task #: _____				Start Date: <u>8/24/23</u>		Time: <u>1455</u>	
Field Personnel: <u>Crew 314</u>				Finish Date: _____						Time: _____	
WELL INFORMATION						EVENT TYPE					
Well ID: <u>XPW03</u>						☐ Well Development ☐ Low-Flow / Low Stress Sampling ☐ Well Volume Approach Sampling ☐ Other (Specify): _____					
Casing ID: _____ inches											
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µS/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
<u>PRE</u>	<u>1457</u>		<u>4.26</u>								
	<u>1500</u>	<u>1.0</u>	<u>5.16</u>	<u>-0.3</u>	<u>16.7</u>	<u>11.71</u>	<u>1.41</u>	<u>0.82</u>	<u>5.</u>		
	<u>1506</u>		<u>5.16</u>	<u>Q</u>	<u>16.7</u>	<u>11.71</u>	<u>1.141</u>	<u>0.82</u>	<u>5.92</u>	<u>-3.2</u>	
	<u>1511</u>		<u>5.16</u>	<u>Q</u>	<u>16.6</u>	<u>11.79</u>	<u>1.144</u>	<u>0.11</u>	<u>13.62</u>	<u>-22.1</u>	
	<u>1516</u>	<u>2</u>	<u>5.16</u>	<u>Q</u>	<u>16.7</u>	<u>11.79</u>	<u>1.146</u>	<u>0.11</u>	<u>9.31</u>	<u>-30.8</u>	
	<u>1521</u>		<u>5.16</u>	<u>Q</u>	<u>16.8</u>	<u>11.78</u>	<u>1.149</u>	<u>0.10</u>	<u>9.28</u>	<u>-37.3</u>	
	<u>1526</u>	<u>2.5</u>	<u>5.16</u>	<u>Q</u>	<u>16.7</u>	<u>11.79</u>	<u>1.149</u>	<u>0.11</u>	<u>9.97</u>	<u>-41.9</u>	
	<u>1531</u>										
	<u>1536</u>										
NOTES (continued)							ABBREVIATIONS				
<u>FI UNDER</u> <u>SAMPLE - 1530</u> <u>EB -</u>							Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/21/23</u> @ <u>0955</u> Well Number <u>10</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented		X				
Not cracked		X				
Not loose		X				
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented		X				
Not cracked		X				
Not loose		X				
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?		X				
6. Is there a lock present?		X				
7. Bumper posts in good condition?		X				
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?			X			
11. Is the well cap lockable?			X			
12. Is there a lock present?			X			
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?			X			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?		X				
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	48.45ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?		X				
Not deteriorated?		X				
Not heaved or below surrounding grade?		X				
20. No surface seal settling?		X				
21. Well clearly visible and labeled?	X					
Comments:						
DTW: 48.28 ft Bottom of casing / top of pump 48.45						
* Major well repair are those that require a subcontractor or separate mobilization to complete						


PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/24/23</u>		Time: <u>0810</u>	
Field Personnel: <u>Amison Beckwith</u>				Finish Date: _____				Time: <u>0900</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-10</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling			
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
0	0810		48.15		22.8	7.15	0.1019	1.52	4.08	138.0	Clear
	0821		48.12		23.1	7.06	0.022	0.73	4.50	144.0	
	0826	2.0	48.12		23.1	7.05	0.024	0.57	7.00	144.2	
	0831		48.12		23.1	7.04	0.025	0.55	10.15	142.8	
	0836	3.0	48.11		23.2	7.04	0.025	0.53	4.50	141.8	
2.5	0841	3.5	48.11		23.2	7.04	0.025	0.52	3.90	140.9	↓
NOTES (continued)							ABBREVIATIONS				
Samples taken @ 0845 *NO FERROUS IRON SAMPLE*							Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date Well Number	Stick-up Monitoring Wells			Comments		
1. Outer protective Casing Not corroded Not dented Not cracked Not loose	☒ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA
2. Inner casing Not corroded Not dented Not cracked Not loose	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA
3. Are there weep holes in outer casing? 4. Weep holes able to drain? 5. Is there a lockable cap present? 6. Is there a lock present? 7. Bumper posts in good condition?	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA
Flushmount Monitoring Wells 8. Can the lid be secured tightly? 9. Does the lid have a gasket that seals? 10. No water in the flushmount? 11. Is the well cap lockable? 12. Is there a lock present?	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA
All Monitoring Wells Downhole Condition 12. Water level measuring point clearly marked? 13. No obstructions in well? 14. No plant roots or vegetation in well? 15. No sediment in bottom of well? If present, how much sediment? 16. Installed as total depth. 17. Measured total depth of well.	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA
General Condition 18. Concrete pad installed? 19. Concrete pad Slope away from casing? Not deteriorated? Not heaved or below surrounding grade? 20. No surface seal settling? 21. Well clearly visible and labeled?	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA	☐ Yes ☐ No ☐ NA
Comments:						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION													
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>									
Project Number: _____				Task #: _____				Start Date: <u>8/25/23</u>				Time: <u>10:55</u>	
Field Personnel: <u>Alison Beckwith</u>				Finish Date: _____				Time: <u>12:00</u>					
WELL INFORMATION				EVENT TYPE									
Well ID: <u>HEN-50</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling					
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____					
WATER QUALITY INDICATOR PARAMETERS (continued)													
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity		
10	058				16.8	7.53	0.0044	0.01	3104.79	81.2	clear		
11	03				16.7	7.50	0.003	0.59	384.4	112.5			
11	09	2.0			16.8	7.49	0.0044	0.17	4.33	109.3			
11	13				16.9	7.49	0.005	0.14	4.31	98.5			
11	18	4.0			16.7	7.48	0.005	0.12	4.06	87.2			
11	23				16.7	7.47	0.005	0.12	3.98	88.0			
NOTES (continued)								ABBREVIATIONS					
Samples taken @ 1125 Ferrrous iron sample @ 1140: under range								Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured					
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature *C - Degrees Celsius					

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>2/25/23</u> Well Number <u>HEV 34</u> Stick-up Monitoring Wells						
1. Outer protective Casing Not corroded Not dented Not cracked Not loose	Yes	No	NA	Comments 		
2. Inner casing Not corroded Not dented Not cracked Not loose	Yes	No	NA			
3. Are there weep holes in outer casing? 4. Weep holes able to drain? 5. Is there a lockable cap present? 6. Is there a lock present? 7. Bumper posts in good condition?	Yes	No	NA			
Flushmount Monitoring Wells 8. Can the lid be secured tightly? 9. Does the lid have a gasket that seals? 10. No water in the flushmount? 11. Is the well cap lockable? 12. Is there a lock present?						
All Monitoring Wells Downhole Condition 12. Water level measuring point clearly marked? 13. No obstructions in well? 14. No plant roots or vegetation in well? 15. No sediment in bottom of well? If present, how much sediment? 16. Installed as total depth. 17. Measured total depth of well.	Yes	No	NA			
General Condition 18. Concrete pad installed? 19. Concrete pad Slope away from casing? Not deteriorated? Not heaved or below surrounding grade? 20. No surface seal settling? 21. Well clearly visible and labeled?	Yes	No	NA			
Comments:						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

[illegible]

Site		Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/25/23</u> Well Number <u>HEN 49</u>							
Stick-up Monitoring Wells		Comments					
1. Outer protective Casing		Yes	No	NA			
Not corroded			X				
Not dented							
Not cracked							
Not loose							
2. Inner casing		Yes	No	NA			
Not corroded			X				
Not dented							
Not cracked							
Not loose							
3. Are there weep holes in outer casing?		Yes	No	NA			
4. Weep holes able to drain?							
5. Is there a lockable cap present?			X				
6. Is there a lock present?			X				
7. Bumper posts in good condition?			X				
Flushmount Monitoring Wells		Yes	No	NA			
8. Can the lid be secured tightly?							
9. Does the lid have a gasket that seals?							
10. No water in the flushmount?							
11. Is the well cap lockable?							
12. Is there a lock present?							
All Monitoring Wells		Yes	No	NA			
Downhole Condition		Yes	No	NA			
12. Water level measuring point clearly marked?			X				
13. No obstructions in well?			X				
14. No plant roots or vegetation in well?			X				
15. No sediment in bottom of well?			X				
If present, how much sediment?		ft					
16. Installed as total depth.		ft					
17. Measured total depth of well.		ft					
General Condition		Yes	No	NA			
18. Concrete pad installed?			X				
19. Concrete pad							
Slope away from casing?			X				
Not deteriorated?			X				
Not heaved or below surrounding grade?			X				
20. No surface seal settling?			X				
21. Well clearly visible and labeled?			X				
Comments:							
BATTERY WAS REPLACED + WOULD NOT CORRECTLY, WELL WAS CHANGED MANUALLY							
* Major well repair are those that require a subcontractor or separate mobilization to complete							

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/25/23</u>		Time: <u>0925</u>	
Field Personnel: <u>Allison Belmont</u>				Finish Date: _____				Time: <u>1055</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-49</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling			
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
09	1032		19.65		15.5	7.2	0.700	1.40	72.1	-1.5	Clear
09	1037		19.65		15.3	7.13	0.698	0.22	92.38	38.0	Brown & Murky
09	1042	2.0	19.65		15.4	7.12	0.1098	0.17	110.79	48.10	
09	1047		19.64		15.4	7.12	0.1098	0.15	122.4	57.7	
09	1052		19.65		15.4	7.12	0.647	0.13	121.9	58.8	
09	1057	5.0	19.64		15.4	7.12	0.698	0.12	122.9	59.1	
10	1102		19.65		15.3	7.12	0.698	0.11	123.6	58.2	
NOTES (continued)							ABBREVIATIONS				
Sample taken @ 1105 Ferrous iron sample @ 1030: under range							Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/23/23</u> <u>0815</u> Well Number <u>HN-10</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?			X			
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition	Yes	No	NA			
18. Concrete pad installed?	X					
19. Concrete pad						
Slope away from casing?						
Not deteriorated?						
Not heaved or below surrounding grade?			X			
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:						

* Major well repair are those that require a subcontractor or separate mobilization to complete

DTW: 53.90, dead batteries/transfer is friend

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/28/23</u>		Time: <u>0800</u>	
Field Personnel: <u>Alison Burrell</u>				Finish Date: _____				Time: <u>0905</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-10</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling			
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	<u>0808</u>		<u>53.90</u>		<u>19.9</u>	<u>7.47</u>	<u>0.550</u>	<u>8.13</u>	<u>4.40</u>	<u>114.5</u>	<u>clear</u>
	<u>0813</u>		<u>53.90</u>		<u>22.5</u>	<u>7.23</u>	<u>0.553</u>	<u>1.41</u>	<u>3.88</u>	<u>131.4</u>	
	<u>0818</u>		<u>53.90</u>		<u>22.7</u>	<u>7.23</u>	<u>0.554</u>	<u>1.21</u>	<u>3.92</u>	<u>131.1</u>	
	<u>0823</u>	<u>1.0</u>	<u>53.90</u>		<u>22.8</u>	<u>7.23</u>	<u>0.556</u>	<u>0.53</u>	<u>3.85</u>	<u>126.8</u>	
	<u>0828</u>		<u>53.90</u>		<u>22.8</u>	<u>7.23</u>	<u>0.556</u>	<u>0.41</u>	<u>3.89</u>	<u>123.5</u>	
	<u>0833</u>	<u>2.0</u>	<u>53.90</u>		<u>22.8</u>	<u>7.23</u>	<u>0.556</u>	<u>0.37</u>	<u>3.99</u>	<u>122.2</u>	<u>✓</u>
NOTES (continued)							ABBREVIATIONS				
<u>Samples taken @ 0835</u> <u>Ferrus iron sample @ 0850: Under range</u>							Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius				

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/28/23 @ 0915</u> Well Number <u>HEN-17</u>						
Stick-up Monitoring Wells						
1. Outer protective casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?			X			
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?		X				
Not deteriorated?		X		CRACKED		
Not heaved or below surrounding grade?						
20. No surface seal settling?		X				
21. Well clearly visible and labeled?		X				
Comments:						
DTM: ON APP						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION															
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>											
Project Number: _____				Task #: _____				Start Date: <u>8/28/23</u>		Time: <u>0905</u>					
Field Personnel: <u>Amison Burkett</u>				Finish Date: _____				Time: <u>1030</u>							
WELL INFORMATION				EVENT TYPE											
Well ID: <u>HEN-17</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling							
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____							
WATER QUALITY INDICATOR PARAMETERS (continued)															
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity				
	0911				22.4	7.15	0.565	5.91	5.06	137.9	clear				
	0916				22.7	7.35	0.514	6.13	3.97	140.7	↓				
	0921				22.5	7.35	0.508	6.06	4.08	144.3	↓				
	0926	1.0			22.5	7.35	0.508	6.00	3.96	146.5	↓				
	0931				22.4	7.34	0.507	5.88	3.99	147.6	↓				
	0936	2.0			22.4	7.34	0.506	5.76	4.02	148.2	↓				
NOTES (continued)								ABBREVIATIONS							
Samples taken @ 0940 Ferrous iron sample @ 0945: under range dupe @ 0940								Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured				ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs* required to maintain well integrity?			Yes	No	NA
Inspection Date <u>8/17/28</u> Well Number <u>03R</u>						
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented		X				
Not cracked		X				
Not loose		X				
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented		X				
Not cracked		X				
Not loose		X				
3. Are there weep holes in outer casing?	Yes	No	NA			
4. Weep holes able to drain?		X				
5. Is there a lockable cap present?		X				
6. Is there a lock present?		X				
7. Bumper posts in good condition?		X				
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?		X				
10. No water in the flushmount?		X				
11. Is the well cap lockable?		X				
12. Is there a lock present?		X				
All Monitoring Wells						
Downhole Condition						
12. Water level measuring point clearly marked?	Yes	No	NA			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?		X				
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad		X				
Slope away from casing?		X				
Not deteriorated?		X				
Not heaved or below surrounding grade?		X				
20. No surface seal settling?		X				
21. Well clearly visible and labeled?		X				
Comments:						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

Monitoring Well Evaluation Checklist

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date Well Number	8/28/23 185					
Stick-up Monitoring Wells						
1. Outer protective casing	Yes	No	NA	Comments		
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
3. Are there weep holes in outer casing?						
4. Weep holes able to drain?			X			
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition						
12. Water level measuring point clearly marked?	Yes	No	NA			
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?		X				
15. No sediment in bottom of well?		X				
If present, how much sediment?	ft					
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad						
Slope away from casing?		X				
Not deteriorated?		X				
Not heaved or below surrounding grade?		X				
20. No surface seal settling?		X				
21. Well clearly visible and labeled?	X					
Comments:						
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: _____				Client: _____							
Project Number: _____				Task #: _____		Start Date: <u>8/28/23</u>		Time: <u>0800</u>			
Field Personnel: <u>Travis Lay</u>				Finish Date: _____		Time: <u>0905</u>					
WELL INFORMATION				EVENT TYPE							
Well ID: <u>185</u>				☐ Well Development ☒ Low-Flow / Low Stress Sampling ☐ Well Volume Approach Sampling ☐ Other (Specify): _____							
Casing ID: _____ inches											
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
<u>Purge</u>	<u>0810</u>	<u>0.25</u>									<u>Clear</u>
	<u>0811</u>				<u>16.8</u>	<u>7.52</u>	<u>0.666</u>	<u>2.30</u>	<u>5.45</u>	<u>104.0</u>	
	<u>0816</u>				<u>16.7</u>	<u>7.39</u>	<u>0.661</u>	<u>0.42</u>	<u>3.20</u>	<u>103.2</u>	
	<u>0821</u>				<u>16.8</u>	<u>7.39</u>	<u>0.661</u>	<u>0.26</u>	<u>2.61</u>	<u>98.1</u>	
	<u>0826</u>	<u>2.25</u>			<u>16.8</u>	<u>7.38</u>	<u>0.661</u>	<u>0.22</u>	<u>2.49</u>	<u>75.5</u>	
	<u>0831</u>	<u>2.5</u>			<u>16.8</u>	<u>7.38</u>	<u>0.661</u>	<u>0.20</u>	<u>2.46</u>	<u>94.1</u>	
	<u>0836</u>										
	<u>0841</u>										
	<u>0846</u>										
NOTES (continued)							ABBREVIATIONS				
<u>FI - UNDER</u> <u>0835</u> <u>sample</u>							Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured				
							ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celcius				

Site	Major wells repairs * required to maintain well integrity?			Yes	No	NA
Inspection Date	8/22/23 @ 1125					
Well Number	HEN-465					
Stick-up Monitoring Wells						
1. Outer protective Casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose						
2. Inner casing	Yes	No	NA			
Not corroded		X				
Not dented						
Not cracked						
Not loose	Yes	No	NA			
3. Are there weep holes in outer casing?		X				
4. Weep holes able to drain?						
5. Is there a lockable cap present?						
6. Is there a lock present?						
7. Bumper posts in good condition?						
Flushmount Monitoring Wells						
8. Can the lid be secured tightly?	Yes	No	NA			
9. Does the lid have a gasket that seals?						
10. No water in the flushmount?						
11. Is the well cap lockable?						
12. Is there a lock present?						
All Monitoring Wells						
Downhole Condition	Yes	No	NA			
12. Water level measuring point clearly marked?						
13. No obstructions in well?		X				
14. No plant roots or vegetation in well?						
15. No sediment in bottom of well?						
If present, how much sediment?						
16. Installed as total depth.	ft					
17. Measured total depth of well.	ft					
	3019 ft					
General Condition						
18. Concrete pad installed?	Yes	No	NA			
19. Concrete pad	X					
Slope away from casing?		X				
Not deteriorated?						
Not heaved or below surrounding grade?						
20. No surface seal settling?						
21. Well clearly visible and labeled?	X					
Comments:	DTW: 18.98 pump installed					
* Major well repair are those that require a subcontractor or separate mobilization to complete						

PROJECT INFORMATION											
Site: <u>Hennepin, IL</u>				Client: <u>Ramboll</u>							
Project Number: _____				Task #: _____				Start Date: <u>8/28/23</u>		Time: <u>1040</u>	
Field Personnel: <u>Allison Beckwith</u>				Finish Date: _____				Time: <u>1140</u>			
WELL INFORMATION				EVENT TYPE							
Well ID: <u>HEN-455</u>				☐ Well Development				☒ Low-Flow / Low Stress Sampling			
Casing ID: <u>2</u> inches				☐ Well Volume Approach Sampling				☐ Other (Specify): _____			
WATER QUALITY INDICATOR PARAMETERS (continued)											
Sampling Stage	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C)	pH (SU)	SEC or Cond. (µs/cm)	Dissolved Oxygen (mg/L)	Turbidity (NTU)	ORP (mV)	Visual Clarity
	<u>1044</u>		<u>18.98</u>		<u>19.3</u>	<u>7.32</u>	<u>0.704</u>	<u>3.27</u>	<u>9.13</u>	<u>57.9</u>	<u>Clear</u>
	<u>1049</u>		<u>18.97</u>		<u>19.1</u>	<u>7.17</u>	<u>0.641</u>	<u>0.25</u>	<u>148.24</u>	<u>108.9</u>	<u>Brown/murky</u>
	<u>1054</u>	<u>2.5</u>	<u>18.98</u>		<u>19.1</u>	<u>7.16</u>	<u>0.640</u>	<u>0.22</u>	<u>130.16</u>	<u>111.7</u>	
	<u>1059</u>		<u>18.98</u>		<u>19.1</u>	<u>7.16</u>	<u>0.640</u>	<u>0.19</u>	<u>89.9</u>	<u>110.1</u>	
	<u>1104</u>		<u>18.98</u>		<u>19.1</u>	<u>7.16</u>	<u>0.640</u>	<u>0.18</u>	<u>107.30</u>	<u>118.4</u>	
	<u>1109</u>	<u>5.0</u>	<u>18.98</u>		<u>19.1</u>	<u>7.16</u>	<u>0.640</u>	<u>0.17</u>	<u>54.30</u>	<u>119.2</u>	
	<u>1118</u>		<u>18.98</u>		<u>19.1</u>	<u>7.16</u>	<u>0.640</u>	<u>0.17</u>	<u>55.06</u>	<u>120.2</u>	
NOTES (continued)								ABBREVIATIONS			
Samples taken @ 1115 1115 Ferrous iron sample @ 1130: under range								Cond. - Actual Conductivity FT BTOT - Feet Below Top of Casing na - Not Applicable nm - Not Measured			
								ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius			

SAR-4: Depth to Groundwater Measurements - On-site Transducer Downloads
All DTWs on SAR-4 form may be collected at anytime during the sampling event.
Plant: HEN
Event: HEN-23Q3 Rev 0

Well	Unique ID	Date	Time	Measured Depth to Water (ft bmp)	On-site Transducer Data					Comments	Initials
					Data Logger Serial No.	Does Data Logger Serial No. Match?	WL Reading on Transducer (ft)	Data down-loaded?	Batt (H/M/L)		
03R	HEN_03R	8/28/2023	9:06	See transducer reading	21615140	y	448.07	y	h		CT
07	HEN_07	8/24/2023	13:20	See transducer reading	21615139	y	450.45	y	h		AB
08	HEN_08	8/24/2023	14:35	See transducer reading	21615138	y	448.33	y	h		AB
08D	HEN_08&D	8/24/2023	11:40	See transducer reading	21615598	y	448.09	y	h		AB
12	HEN_12	8/23/2023	9:30	See transducer reading	21615520	y	448.17	y	h		AB
13	HEN_13	8/23/2023	10:55	See transducer reading	21615515	y	448.22	y	h		AB
16	HEN_16	8/28/2023	8:00	53.9	21615137	y	N/A	n	h	Replaced battery, issues connecting to hobo link, manually gauged well.	AB
17	HEN_17	8/28/2023	9:05	See transducer reading	21615500	y	449.15	y	h		AB
18S	HEN_18#S	8/28/2023	8:00	See transducer reading	21615482	y	448.12	y	h		CT
18D	HEN_18&D	8/23/2023	13:18	See transducer reading	21615609	y	448.08	y	h		CT
21R	HEN_21R	8/22/2023	13:00	See transducer reading	21615613	y	447.73	y	h		AB
22	HEN_22	8/25/2023	8:15	See transducer reading	21615497	y	447.26	y	h		AB
22D	HEN_22&D	8/22/2023	8:00	See transducer reading	21564134	y	447.57	y	h		AB
23	HEN_23	8/22/2023	10:40	See transducer reading	21615600	y	447.92	y	h		AB
27	HEN_27	8/24/2023	8:20	See transducer reading	21615576	y	447.77	y	h		CT
32	HEN_32	8/22/2023	10:35	See transducer reading	21615487	y	447.64	y	h		CT

SAR-4: Depth to Groundwater Measurements - On-site Transducer Downloads
All DTWs on SAR-4 form may be collected at anytime during the sampling event.
Plant: HEN
Event: HEN-23Q3 Rev 0

Well	Unique ID	Date	Time	Measured Depth to Water (ft bmp)	On-site Transducer Data					Comments	Initials
					Data Logger Serial No.	Does Data Logger Serial No. Match?	WL Reading on Transducer (ft)	Data down-loaded?	Batt (H/M/L)		
34	HEN_34	8/25/2023	10:53	See transducer reading	21615509	y	440.58	y	h	Replaced battery 8/25/23	CT
35	HEN_35	8/24/2023	9:30	See transducer reading	21615510	y	447.64	y	h		CT
46	HEN_46	8/23/2023	8:10	See transducer reading	21615491	y	448.28	y	h		AB
47	HEN_47	8/23/2023	14:55	See transducer reading	21615505	y	447.94	y	h		AB
49	HEN_49	8/25/2023	9:25	19.65	21615490	y	N/A	n	h	Replaced battery, issues connecting to hobo link, manually gauged well.	AB
50	HEN_50	8/25/2023	10:55	See transducer reading	21615489	y	-0.03	y	h		AB
51	HEN_51	8/22/2023	15:00	See transducer reading	21615608	y	447.74	y	h		AB
52	HEN_52	8/24/2023	9:05	See transducer reading	21615145	y	448.12	y	h		AB
54	HEN_54	8/23/2023	13:00	See transducer reading	21615143	y	448.03	y	h		AB
55	HEN_55	8/23/2023	12:55	See transducer reading	21615612	y	corrupted file	y	h	Data was downloaded, data did not save correctly/ corrupt	AB

U: 6/21/23 GKJ

ANALYTICAL REPORT

PREPARED FOR

Attn: Brian Voelker
Vistra Energy Corp
133 S 4th, Suite 206
Springfield, Illinois 62701
Generated 10/11/2023 6:27:15 PM

JOB DESCRIPTION

HEN-23Q3
SDG NUMBER HEN_SUP_000_0 RAD

JOB NUMBER

500-238579-10

Job Notes

This report may not be reproduced except in full, and with written approval from the laboratory. The results relate only to the samples tested. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Chicago Project Manager.

Authorization



Generated
10/11/2023 6:27:15 PM

Authorized for release by
Carlene McCutcheon, Senior Project Manager
Carlene.McCutcheon@et.eurofinsus.com
(708)325-6562

Table of Contents

Cover Page	1
Table of Contents	3
Case Narrative	4
Method Summary	13
Sample Summary	14
Client Sample Results	15
Definitions	54
QC Association	55
QC Sample Results	58
Chronicle	64
Certification Summary	74
Chain of Custody	75
Receipt Checklists	93
Tracer Carrier Summary	95



Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Job ID: 500-238579-10

Laboratory: Eurofins Chicago

Narrative

Job Narrative 500-238579-10

Receipt

The samples were received on 8/23/2023 10:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 28 coolers at receipt time were 0.1° C, 0.1° C, 0.2° C, 0.3° C, 0.4° C, 0.5° C, 0.6° C, 0.7° C, 0.8° C, 1.0° C, 1.2° C, 1.2° C, 1.3° C, 1.3° C, 1.3° C, 1.6° C, 1.7° C, 1.7° C, 1.7° C, 1.7° C, 2.0° C, 2.0° C, 2.0° C, 2.8° C, 2.9° C, 2.9° C, 3.0° C and 3.7° C.

RAD

Method 903.0: Radium-226 batch 626172:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_25 (500-238579-7), HEN_26 (500-238579-8), HEN_26_MS (500-238579-8[MS]), HEN_26_MSD (500-238579-8[MSD]), (LCS 160-626172/2-A) and (MB 160-626172/1-A).

Method 903.0: Radium-226 batch 626178:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_XPW01_pore (500-238579-36), HEN_XPW01_pore_EB (500-238579-37), HEN_XPW02_pore (500-238579-38), HEN_XPW02_pore_EB (500-238579-39), HEN_XPW03_pore (500-238579-40), HEN_XPW03_pore_EB (500-238579-41), (LCS 160-626178/2-A), (MB 160-626178/1-A), (500-238579-N-45-A), (500-238579-N-45-B MS) and (500-238579-N-45-C MSD).

Method 904.0: Radium-228 prep batch 160-626179:

The following sample(s) did not meet the requested limit (RL) due to the reduced sample volume attributed to the presence of matrix interference. During preparation the analyst visually noted matrix effects. The data have been reported with this narrative.

HEN_XPW01_pore (500-238579-36).

Method 904.0: Radium-228 prep batch 160-626179:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_XPW01_pore (500-238579-36), HEN_XPW01_pore_EB (500-238579-37), HEN_XPW02_pore (500-238579-38), HEN_XPW02_pore_EB (500-238579-39), HEN_XPW03_pore (500-238579-40), HEN_XPW03_pore_EB (500-238579-41), (LCS 160-626179/2-A), (MB 160-626179/1-A), (500-238579-N-45-D), (500-238579-N-45-E MS) and (500-238579-N-45-F MSD) .

Method 904.0: Radium-228 prep batch 160-626177:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_25 (500-238579-7), HEN_26 (500-238579-8), HEN_26_MS (500-238579-8[MS]), HEN_26_MSD (500-238579-8[MSD]), (LCS 160-626177/2-A) and (MB 160-626177/1-A).

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Narrative

Job Narrative 500-238579-14

Receipt

The samples were received on 8/23/2023 10:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 28 coolers at receipt time were 0.1° C, 0.1° C, 0.2° C, 0.3° C, 0.4° C, 0.5° C, 0.6° C, 0.7° C, 0.8° C, 1.0° C, 1.2° C, 1.2° C, 1.3° C, 1.3° C, 1.3° C, 1.6° C, 1.7° C, 1.7° C, 1.7° C, 1.7° C, 2.0° C, 2.0° C, 2.0° C, 2.8° C, 2.9° C, 2.9° C, 3.0° C and 3.7° C.

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Job ID: 500-238579-10 (Continued)

Laboratory: Eurofins Chicago (Continued)

RAD

Method 903.0: Radium-226 batch 626180:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_03R (500-238579-53), HEN_03R_MS (500-238579-53[MS]), HEN_03R_MSD (500-238579-53[MSD]), (LCS 160-626180/2-A) and (MB 160-626180/1-A).

Method 903.0: Radium-226 batch 626172:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_18&D (500-238579-13), HEN_07 (500-238579-28), HEN_08 (500-238579-30), (LCS 160-626172/2-A), (MB 160-626172/1-A), (500-238579-N-8-A), (500-238579-N-8-B MS) and (500-238579-N-8-C MSD).

Method 903.0: Radium-226 batch 626178:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_08&D (500-238579-32), HEN_08_FD (500-238579-34), HEN_257_FB (500-238579-42), HEN_18#S (500-238579-51), HEN_45#S (500-238579-56), (LCS 160-626178/2-A), (MB 160-626178/1-A), (500-238579-N-45-A), (500-238579-N-45-B MS) and (500-238579-N-45-C MSD).

Method 904.0: Radium-228 prep batch 160-626182:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_03R (500-238579-53), HEN_03R_MS (500-238579-53[MS]), HEN_03R_MSD (500-238579-53[MSD]), (LCS 160-626182/2-A) and (MB 160-626182/1-A).

Method 904.0: Radium-228 prep batch 160-626179:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_08&D (500-238579-32), HEN_08_FD (500-238579-34), HEN_257_FB (500-238579-42), HEN_18#S (500-238579-51), HEN_45#S (500-238579-56), (LCS 160-626179/2-A), (MB 160-626179/1-A), (500-238579-N-45-D), (500-238579-N-45-E MS) and (500-238579-N-45-F MSD).

Method 904.0: Radium-228 prep batch 160-626177:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_18&D (500-238579-13), HEN_07 (500-238579-28), HEN_08 (500-238579-30), (LCS 160-626177/2-A), (MB 160-626177/1-A), (500-238579-N-8-D), (500-238579-N-8-E MS) and (500-238579-N-8-F MSD).

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Narrative

Job Narrative 500-238579-16

Receipt

The samples were received on 8/23/2023 10:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 28 coolers at receipt time were 0.1° C, 0.1° C, 0.2° C, 0.3° C, 0.4° C, 0.5° C, 0.6° C, 0.7° C, 0.8° C, 1.0° C, 1.2° C, 1.2° C, 1.3° C, 1.3° C, 1.3° C, 1.6° C, 1.7° C, 1.7° C, 1.7° C, 1.7° C, 2.0° C, 2.0° C, 2.0° C, 2.8° C, 2.9° C, 2.9° C, 3.0° C and 3.7° C.

RAD

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Job ID: 500-238579-10 (Continued)

Laboratory: Eurofins Chicago (Continued)

Method 903.0: Radium-226 batch 626180:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_03R (500-238579-53), HEN_03R_MS (500-238579-53[MS]), HEN_03R_MSD (500-238579-53[MSD]), (LCS 160-626180/2-A) and (MB 160-626180/1-A).

Method 903.0: Radium-226 batch 626172:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_18&D (500-238579-13), HEN_07 (500-238579-28), HEN_08 (500-238579-30), (LCS 160-626172/2-A), (MB 160-626172/1-A), (500-238579-N-8-A), (500-238579-N-8-B MS) and (500-238579-N-8-C MSD).

Method 903.0: Radium-226 batch 626178:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_08&D (500-238579-32), HEN_08_FD (500-238579-34), HEN_18#S (500-238579-51), HEN_45#S (500-238579-56), (LCS 160-626178/2-A), (MB 160-626178/1-A), (500-238579-N-45-A), (500-238579-N-45-B MS) and (500-238579-N-45-C MSD).

Method 904.0: Radium-228 prep batch 160-626182:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_03R (500-238579-53), HEN_03R_MS (500-238579-53[MS]), HEN_03R_MSD (500-238579-53[MSD]), (LCS 160-626182/2-A) and (MB 160-626182/1-A).

Method 904.0: Radium-228 prep batch 160-626179:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_08&D (500-238579-32), HEN_08_FD (500-238579-34), HEN_18#S (500-238579-51), HEN_45#S (500-238579-56), (LCS 160-626179/2-A), (MB 160-626179/1-A), (500-238579-N-45-D), (500-238579-N-45-E MS) and (500-238579-N-45-F MSD).

Method 904.0: Radium-228 prep batch 160-626177:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_18&D (500-238579-13), HEN_07 (500-238579-28), HEN_08 (500-238579-30), (LCS 160-626177/2-A), (MB 160-626177/1-A), (500-238579-N-8-D), (500-238579-N-8-E MS) and (500-238579-N-8-F MSD).

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Narrative

Job Narrative 500-238579-18

Receipt

The samples were received on 8/23/2023 10:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 28 coolers at receipt time were 0.1° C, 0.1° C, 0.2° C, 0.3° C, 0.4° C, 0.5° C, 0.6° C, 0.7° C, 0.8° C, 1.0° C, 1.2° C, 1.2° C, 1.3° C, 1.3° C, 1.3° C, 1.6° C, 1.7° C, 1.7° C, 1.7° C, 1.7° C, 2.0° C, 2.0° C, 2.0° C, 2.8° C, 2.9° C, 2.9° C, 3.0° C and 3.7° C.

RAD

Method 903.0: Radium-226 batch 626180:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Job ID: 500-238579-10 (Continued)

Laboratory: Eurofins Chicago (Continued)

applied as the Activity Reference Date.

HEN_03R (500-238579-53), HEN_03R_MS (500-238579-53[MS]), HEN_03R_MSD (500-238579-53[MSD]), (LCS 160-626180/2-A) and (MB 160-626180/1-A).

Method 903.0: Radium-226 batch 626172:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_18&D (500-238579-13), HEN_07 (500-238579-28), HEN_08 (500-238579-30), (LCS 160-626172/2-A), (MB 160-626172/1-A), (500-238579-N-8-A), (500-238579-N-8-B MS) and (500-238579-N-8-C MSD).

Method 903.0: Radium-226 batch 626178:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_08&D (500-238579-32), HEN_08_FD (500-238579-34), HEN_18#S (500-238579-51), HEN_45#S (500-238579-56), (LCS 160-626178/2-A), (MB 160-626178/1-A), (500-238579-N-45-A), (500-238579-N-45-B MS) and (500-238579-N-45-C MSD).

Method 904.0: Radium-228 prep batch 160-626182:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_03R (500-238579-53), HEN_03R_MS (500-238579-53[MS]), HEN_03R_MSD (500-238579-53[MSD]), (LCS 160-626182/2-A) and (MB 160-626182/1-A).

Method 904.0: Radium-228 prep batch 160-626179:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_08&D (500-238579-32), HEN_08_FD (500-238579-34), HEN_18#S (500-238579-51), HEN_45#S (500-238579-56), (LCS 160-626179/2-A), (MB 160-626179/1-A), (500-238579-N-45-D), (500-238579-N-45-E MS) and (500-238579-N-45-F MSD).

Method 904.0: Radium-228 prep batch 160-626177:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_18&D (500-238579-13), HEN_07 (500-238579-28), HEN_08 (500-238579-30), (LCS 160-626177/2-A), (MB 160-626177/1-A), (500-238579-N-8-D), (500-238579-N-8-E MS) and (500-238579-N-8-F MSD).

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Narrative

Job Narrative 500-238579-2

Receipt

The samples were received on 8/23/2023 10:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 28 coolers at receipt time were 0.1° C, 0.1° C, 0.2° C, 0.3° C, 0.4° C, 0.5° C, 0.6° C, 0.7° C, 0.8° C, 1.0° C, 1.2° C, 1.2° C, 1.3° C, 1.3° C, 1.3° C, 1.6° C, 1.7° C, 1.7° C, 1.7° C, 1.7° C, 2.0° C, 2.0° C, 2.0° C, 2.8° C, 2.9° C, 2.9° C, 3.0° C and 3.7° C.

RAD

Method 903.0: Radium-226 batch 626172

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_21R (500-238579-1), HEN_22&D (500-238579-2), HEN_23 (500-238579-3), HEN_23_FD (500-238579-4), HEN_32 (500-238579-5), HEN_51 (500-238579-6), HEN_27 (500-238579-26), HEN_35 (500-238579-27), (LCS 160-626172/2-A), (MB 160-626172/1-A), (500-238579-N-8-A), (500-238579-N-8-B MS) and (500-238579-N-8-C MSD)

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Job ID: 500-238579-10 (Continued)

Laboratory: Eurofins Chicago (Continued)

Method 903.0: Radium-226 batch 626178

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_34 (500-238579-44), HEN_49 (500-238579-45), HEN_49_MS (500-238579-45[MS]), HEN_49_MSD (500-238579-45[MSD]), HEN_22 (500-238579-46), HEN_50 (500-238579-47), (LCS 160-626178/2-A) and (MB 160-626178/1-A)

Method 904.0: Radium-228 prep batch 160-626179:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_34 (500-238579-44), HEN_49 (500-238579-45), HEN_49_MS (500-238579-45[MS]), HEN_49_MSD (500-238579-45[MSD]), HEN_22 (500-238579-46), HEN_50 (500-238579-47), (LCS 160-626179/2-A) and (MB 160-626179/1-A)

Method 904.0: Radium-228 prep batch 160-626177:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_21R (500-238579-1), HEN_22&D (500-238579-2), HEN_23 (500-238579-3), HEN_23_FD (500-238579-4), HEN_32 (500-238579-5), HEN_51 (500-238579-6), HEN_27 (500-238579-26), HEN_35 (500-238579-27), (LCS 160-626177/2-A), (MB 160-626177/1-A), (500-238579-N-8-D), (500-238579-N-8-E MS) and (500-238579-N-8-F MSD)

Method PrecSep_0:

Method PrecSep-21:

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Narrative

Job Narrative 500-238579-21

Receipt

The samples were received on 8/23/2023 10:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 28 coolers at receipt time were 0.1° C, 0.1° C, 0.2° C, 0.3° C, 0.4° C, 0.5° C, 0.6° C, 0.7° C, 0.8° C, 1.0° C, 1.2° C, 1.2° C, 1.3° C, 1.3° C, 1.3° C, 1.6° C, 1.7° C, 1.7° C, 1.7° C, 1.7° C, 2.0° C, 2.0° C, 2.0° C, 2.8° C, 2.9° C, 2.9° C, 3.0° C and 3.7° C.

RAD

Method 903.0: Radium-226 batch 626180

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_17-FD (500-238579-60), (LCS 160-626180/2-A), (MB 160-626180/1-A), (500-238579-T-53-A), (500-238579-T-53-B MS) and (500-238579-T-53-C MSD)

Method 903.0: Radium-226 batch 626172

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_12 (500-238579-15), HEN_13 (500-238579-16), HEN_46 (500-238579-18), HEN_47 (500-238579-19), HEN_54 (500-238579-20), HEN_52 (500-238579-25), HEN_07 (500-238579-28), HEN_08 (500-238579-30), (LCS 160-626172/2-A), (MB 160-626172/1-A), (500-238579-N-8-A), (500-238579-N-8-B MS) and (500-238579-N-8-C MSD)

Method 903.0: Radium-226 batch 626178

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Job ID: 500-238579-10 (Continued)

Laboratory: Eurofins Chicago (Continued)

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_08&D (500-238579-32), HEN_08_FD (500-238579-34), HEN_16 (500-238579-58), HEN_17 (500-238579-59), (LCS 160-626178/2-A), (MB 160-626178/1-A), (500-238579-N-45-A), (500-238579-N-45-B MS) and (500-238579-N-45-C MSD)

Method 904.0: Radium-228 prep batch 160-626182:

The detection goal was not met for the following sample(s). The samples and batch QC were prepped at full volume. Matrix interferences are suspected because the method blank achieved the detection goal demonstrating acceptable sample preparation and instrument performance. Analytical results are reported with the detection limit achieved. HEN_17-FD (500-238579-60)

Method 904.0: Radium-228 prep batch 160-626182:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_17-FD (500-238579-60), (LCS 160-626182/2-A), (MB 160-626182/1-A), (500-238579-T-53-D), (500-238579-T-53-E MS) and (500-238579-T-53-F MSD)

Method 904.0: Radium-228 prep batch 160-626179:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_08&D (500-238579-32), HEN_08_FD (500-238579-34), HEN_16 (500-238579-58), HEN_17 (500-238579-59), (LCS 160-626179/2-A), (MB 160-626179/1-A), (500-238579-N-45-D), (500-238579-N-45-E MS) and (500-238579-N-45-F MSD)

Method 904.0: Radium-228 prep batch 160-626177:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_12 (500-238579-15), HEN_13 (500-238579-16), HEN_46 (500-238579-18), HEN_47 (500-238579-19), HEN_54 (500-238579-20), HEN_52 (500-238579-25), HEN_07 (500-238579-28), HEN_08 (500-238579-30), (LCS 160-626177/2-A), (MB 160-626177/1-A), (500-238579-N-8-D), (500-238579-N-8-E MS) and (500-238579-N-8-F MSD)

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Narrative

Job Narrative 500-238579-23

Receipt

The samples were received on 8/23/2023 10:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 28 coolers at receipt time were 0.1° C, 0.1° C, 0.2° C, 0.3° C, 0.4° C, 0.5° C, 0.6° C, 0.7° C, 0.8° C, 1.0° C, 1.2° C, 1.2° C, 1.3° C, 1.3° C, 1.3° C, 1.6° C, 1.7° C, 1.7° C, 1.7° C, 1.7° C, 2.0° C, 2.0° C, 2.0° C, 2.8° C, 2.9° C, 2.9° C, 3.0° C and 3.7° C.

RAD

Method 903.0: Radium-226 batch 626180

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_17-FD (500-238579-60), (LCS 160-626180/2-A), (MB 160-626180/1-A), (500-238579-T-53-A), (500-238579-T-53-B MS) and (500-238579-T-53-C MSD)

Method 903.0: Radium-226 batch 626172

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Job ID: 500-238579-10 (Continued)

Laboratory: Eurofins Chicago (Continued)

sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_12 (500-238579-15), HEN_13 (500-238579-16), HEN_46 (500-238579-18), HEN_47 (500-238579-19), HEN_54 (500-238579-20), HEN_52 (500-238579-25), HEN_07 (500-238579-28), HEN_08 (500-238579-30), (LCS 160-626172/2-A), (MB 160-626172/1-A), (500-238579-N-8-A), (500-238579-N-8-B MS) and (500-238579-N-8-C MSD)

Method 903.0: Radium-226 batch 626178

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_08&D (500-238579-32), HEN_08_FD (500-238579-34), 845_803_FB (500-238579-50), HEN_16 (500-238579-58), HEN_17 (500-238579-59), (LCS 160-626178/2-A), (MB 160-626178/1-A), (500-238579-N-45-A), (500-238579-N-45-B MS) and (500-238579-N-45-C MSD)

Method 904.0: Radium-228 prep batch 160-626182:

The detection goal was not met for the following sample(s). The samples and batch QC were prepped at full volume. Matrix interferences are suspected because the method blank achieved the detection goal demonstrating acceptable sample preparation and instrument performance. Analytical results are reported with the detection limit achieved. HEN_17-FD (500-238579-60)

Method 904.0: Radium-228 prep batch 160-626182:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_17-FD (500-238579-60), (LCS 160-626182/2-A), (MB 160-626182/1-A), (500-238579-T-53-D), (500-238579-T-53-E MS) and (500-238579-T-53-F MSD)

Method 904.0: Radium-228 prep batch 160-626179:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_08&D (500-238579-32), HEN_08_FD (500-238579-34), 845_803_FB (500-238579-50), HEN_16 (500-238579-58), HEN_17 (500-238579-59), (LCS 160-626179/2-A), (MB 160-626179/1-A), (500-238579-N-45-D), (500-238579-N-45-E MS) and (500-238579-N-45-F MSD)

Method 904.0: Radium-228 prep batch 160-626177:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_12 (500-238579-15), HEN_13 (500-238579-16), HEN_46 (500-238579-18), HEN_47 (500-238579-19), HEN_54 (500-238579-20), HEN_52 (500-238579-25), HEN_07 (500-238579-28), HEN_08 (500-238579-30), (LCS 160-626177/2-A), (MB 160-626177/1-A), (500-238579-N-8-D), (500-238579-N-8-E MS) and (500-238579-N-8-F MSD)

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Narrative

Job Narrative 500-238579-4

Receipt

The samples were received on 8/23/2023 10:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 28 coolers at receipt time were 0.1° C, 0.1° C, 0.2° C, 0.3° C, 0.4° C, 0.5° C, 0.6° C, 0.7° C, 0.8° C, 1.0° C, 1.2° C, 1.2° C, 1.3° C, 1.3° C, 1.3° C, 1.6° C, 1.7° C, 1.7° C, 1.7° C, 1.7° C, 2.0° C, 2.0° C, 2.0° C, 2.8° C, 2.9° C, 2.9° C, 3.0° C and 3.7° C.

RAD

Method 903.0: Radium-226 batch 626172

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Job ID: 500-238579-10 (Continued)

Laboratory: Eurofins Chicago (Continued)

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_21R (500-238579-1), HEN_22&D (500-238579-2), HEN_23 (500-238579-3), HEN_23_FD (500-238579-4), HEN_32 (500-238579-5), HEN_51 (500-238579-6), HEN_27 (500-238579-26), HEN_35 (500-238579-27), (LCS 160-626172/2-A), (MB 160-626172/1-A), (500-238579-N-8-A), (500-238579-N-8-B MS) and (500-238579-N-8-C MSD)

Method 903.0: Radium-226 batch 626178

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_34 (500-238579-44), HEN_49 (500-238579-45), HEN_49_MS (500-238579-45[MS]), HEN_49_MSD (500-238579-45[MSD]), HEN_22 (500-238579-46), HEN_50 (500-238579-47), (LCS 160-626178/2-A) and (MB 160-626178/1-A)

Method 904.0: Radium-228 prep batch 160-626179:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_34 (500-238579-44), HEN_49 (500-238579-45), HEN_49_MS (500-238579-45[MS]), HEN_49_MSD (500-238579-45[MSD]), HEN_22 (500-238579-46), HEN_50 (500-238579-47), (LCS 160-626179/2-A) and (MB 160-626179/1-A)

Method 904.0: Radium-228 prep batch 160-626177:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_21R (500-238579-1), HEN_22&D (500-238579-2), HEN_23 (500-238579-3), HEN_23_FD (500-238579-4), HEN_32 (500-238579-5), HEN_51 (500-238579-6), HEN_27 (500-238579-26), HEN_35 (500-238579-27), (LCS 160-626177/2-A), (MB 160-626177/1-A), (500-238579-N-8-D), (500-238579-N-8-E MS) and (500-238579-N-8-F MSD)

Method PrecSep_0:

Method PrecSep-21:

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Narrative

Job Narrative 500-238579-6

Receipt

The samples were received on 8/23/2023 10:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 28 coolers at receipt time were 0.1° C, 0.1° C, 0.2° C, 0.3° C, 0.4° C, 0.5° C, 0.6° C, 0.7° C, 0.8° C, 1.0° C, 1.2° C, 1.2° C, 1.3° C, 1.3° C, 1.3° C, 1.6° C, 1.7° C, 1.7° C, 1.7° C, 1.7° C, 2.0° C, 2.0° C, 2.0° C, 2.8° C, 2.9° C, 2.9° C, 3.0° C and 3.7° C.

RAD

Method 903.0: Radium-226 batch 626172

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_21R (500-238579-1), HEN_23 (500-238579-3), HEN_23_FD (500-238579-4), HEN_32 (500-238579-5), HEN_51 (500-238579-6), HEN_27 (500-238579-26), HEN_35 (500-238579-27), (LCS 160-626172/2-A), (MB 160-626172/1-A), (500-238579-N-8-A), (500-238579-N-8-B MS) and (500-238579-N-8-C MSD)

Method 903.0: Radium-226 batch 626178

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Job ID: 500-238579-10 (Continued)

Laboratory: Eurofins Chicago (Continued)

sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date.

HEN_34 (500-238579-44), HEN_49 (500-238579-45), HEN_49_MS (500-238579-45[MS]), HEN_49_MSD (500-238579-45[MSD]), HEN_22 (500-238579-46), HEN_50 (500-238579-47), (LCS 160-626178/2-A) and (MB 160-626178/1-A)

Method 904.0: Radium-228 prep batch 160-626179:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_34 (500-238579-44), HEN_49 (500-238579-45), HEN_49_MS (500-238579-45[MS]), HEN_49_MSD (500-238579-45[MSD]), HEN_22 (500-238579-46), HEN_50 (500-238579-47), (LCS 160-626179/2-A) and (MB 160-626179/1-A)

Method 904.0: Radium-228 prep batch 160-626177:

Any minimum detectable concentration (MDC), critical value (DLC), or Safe Drinking Water Act detection limit (SDWA DL) is sample-specific unless otherwise stated elsewhere in this narrative. Radiochemistry sample results are reported with the count date/time applied as the Activity Reference Date. HEN_21R (500-238579-1), HEN_23 (500-238579-3), HEN_23_FD (500-238579-4), HEN_32 (500-238579-5), HEN_51 (500-238579-6), HEN_27 (500-238579-26), HEN_35 (500-238579-27), (LCS 160-626177/2-A), (MB 160-626177/1-A), (500-238579-N-8-D), (500-238579-N-8-E MS) and (500-238579-N-8-F MSD)

Method PrecSep_0:

Method PrecSep-21:

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

SDG: HEN_SUP_000_0 RAD

Method	Method Description	Protocol	Laboratory
903.0	Radium-226 (GFPC)	EPA	EET SL
904.0	Radium-228 (GFPC)	EPA	EET SL
Ra226_Ra228 Pos	Combined Radium-226 and Radium-228	TAL-STL	EET SL
PrecSep_0	Preparation, Precipitate Separation	None	EET SL
PrecSep-21	Preparation, Precipitate Separation (21-Day In-Growth)	None	EET SL

Protocol References:

EPA = US Environmental Protection Agency

None = None

TAL-STL = TestAmerica Laboratories, St. Louis, Facility Standard Operating Procedure.

Laboratory References:

EET SL = Eurofins St. Louis, 13715 Rider Trail North, Earth City, MO 63045, TEL (314)298-8566

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
500-238579-1	HEN_21R	Water	08/22/23 13:45	08/23/23 10:00
500-238579-2	HEN_22&D	Water	08/22/23 09:10	08/23/23 10:00
500-238579-3	HEN_23	Water	08/22/23 11:20	08/23/23 10:00
500-238579-4	HEN_23_FD	Water	08/22/23 11:20	08/23/23 10:00
500-238579-5	HEN_32	Water	08/22/23 11:15	08/23/23 10:00
500-238579-6	HEN_51	Water	08/22/23 15:56	08/23/23 10:00
500-238579-7	HEN_25	Water	08/22/23 14:30	08/23/23 10:00
500-238579-8	HEN_26	Water	08/22/23 15:35	08/23/23 10:00
500-238579-13	HEN_18&D	Water	08/23/23 14:05	08/24/23 09:38
500-238579-15	HEN_12	Water	08/23/23 10:10	08/24/23 09:38
500-238579-16	HEN_13	Water	08/23/23 11:25	08/24/23 09:38
500-238579-18	HEN_46	Water	08/23/23 08:55	08/24/23 09:38
500-238579-19	HEN_47	Water	08/23/23 15:30	08/24/23 09:38
500-238579-20	HEN_54	Water	08/23/23 13:50	08/24/23 09:38
500-238579-25	HEN_52	Water	08/24/23 09:40	08/25/23 09:32
500-238579-26	HEN_27	Water	08/24/23 09:00	08/25/23 09:32
500-238579-27	HEN_35	Water	08/24/23 10:10	08/25/23 09:32
500-238579-28	HEN_07	Water	08/24/23 14:00	08/25/23 09:32
500-238579-30	HEN_08	Water	08/24/23 15:10	08/25/23 09:32
500-238579-32	HEN_08&D	Water	08/24/23 12:25	08/25/23 09:32
500-238579-34	HEN_08_FD	Water	08/24/23 15:10	08/25/23 09:32
500-238579-36	HEN_XPW01_pore	Water	08/24/23 12:15	08/25/23 09:32
500-238579-37	HEN_XPW01_pore_EB	Water	08/24/23 12:15	08/25/23 09:32
500-238579-38	HEN_XPW02_pore	Water	08/24/23 13:45	08/25/23 09:32
500-238579-39	HEN_XPW02_pore_EB	Water	08/24/23 13:45	08/25/23 09:32
500-238579-40	HEN_XPW03_pore	Water	08/24/23 15:30	08/25/23 09:32
500-238579-41	HEN_XPW03_pore_EB	Water	08/24/23 15:30	08/25/23 09:32
500-238579-42	HEN_257_FB	Water	08/25/23 12:00	08/25/23 15:00
500-238579-44	HEN_34	Water	08/25/23 11:25	08/25/23 15:00
500-238579-45	HEN_49	Water	08/25/23 10:05	08/25/23 15:00
500-238579-46	HEN_22	Water	08/25/23 08:50	08/25/23 15:00
500-238579-47	HEN_50	Water	08/25/23 11:25	08/25/23 15:00
500-238579-50	845_803_FB	Water	08/28/23 12:00	08/28/23 15:00
500-238579-51	HEN_18#S	Water	08/28/23 08:35	08/28/23 15:00
500-238579-53	HEN_03R	Water	08/28/23 09:45	08/28/23 15:00
500-238579-56	HEN_45#S	Water	08/28/23 11:15	08/28/23 15:00
500-238579-58	HEN_16	Water	08/28/23 08:35	08/28/23 15:00
500-238579-59	HEN_17	Water	08/28/23 09:40	08/28/23 15:00
500-238579-60	HEN_17-FD	Water	08/28/23 09:40	08/28/23 15:00

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_21R

Lab Sample ID: 500-238579-1

Date Collected: 08/22/23 13:45

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.614		0.187	0.195	1.00	0.167	pCi/L	08/31/23 10:39	09/25/23 09:27	1
Radium-226	0.614		0.187	0.195	1.00	0.167	pCi/L	08/31/23 10:39	09/25/23 09:27	1
Radium-226	0.614		0.187	0.195	1.00	0.167	pCi/L	08/31/23 10:39	09/25/23 09:27	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	90.1		30 - 110					08/31/23 10:39	09/25/23 09:27	1
Ba Carrier	90.1		30 - 110					08/31/23 10:39	09/25/23 09:27	1
Ba Carrier	90.1		30 - 110					08/31/23 10:39	09/25/23 09:27	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.209	U	0.489	0.489	1.00	0.855	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.209	U	0.489	0.489	1.00	0.855	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.209	U	0.489	0.489	1.00	0.855	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	90.1		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	90.1		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	90.1		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	82.6		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	82.6		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	82.6		30 - 110					08/31/23 10:56	09/19/23 12:23	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.823	U	0.524	0.526	5.00	0.855	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.823	U	0.524	0.526	5.00	0.855	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.823	U	0.524	0.526	5.00	0.855	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_22&D

Lab Sample ID: 500-238579-2

Date Collected: 08/22/23 09:10

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.710		0.165	0.177	1.00	0.110	pCi/L	08/31/23 10:39	09/25/23 09:28	1
Radium-226	0.710		0.165	0.177	1.00	0.110	pCi/L	08/31/23 10:39	09/25/23 09:28	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.3		30 - 110					08/31/23 10:39	09/25/23 09:28	1
Ba Carrier	91.3		30 - 110					08/31/23 10:39	09/25/23 09:28	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.548	U	0.400	0.404	1.00	0.611	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.548	U	0.400	0.404	1.00	0.611	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.3		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	91.3		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	81.9		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	81.9		30 - 110					08/31/23 10:56	09/19/23 12:23	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	1.26		0.433	0.441	5.00	0.611	pCi/L		09/27/23 15:51	1
Radium 226 and 228	1.26		0.433	0.441	5.00	0.611	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_23

Lab Sample ID: 500-238579-3

Date Collected: 08/22/23 11:20

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0778	U	0.0660	0.0664	1.00	0.0940	pCi/L	08/31/23 10:39	09/25/23 09:28	1
Radium-226	0.0778	U	0.0660	0.0664	1.00	0.0940	pCi/L	08/31/23 10:39	09/25/23 09:28	1
Radium-226	0.0778	U	0.0660	0.0664	1.00	0.0940	pCi/L	08/31/23 10:39	09/25/23 09:28	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	96.5		30 - 110					08/31/23 10:39	09/25/23 09:28	1
Ba Carrier	96.5		30 - 110					08/31/23 10:39	09/25/23 09:28	1
Ba Carrier	96.5		30 - 110					08/31/23 10:39	09/25/23 09:28	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.177	U	0.379	0.379	1.00	0.658	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.177	U	0.379	0.379	1.00	0.658	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.177	U	0.379	0.379	1.00	0.658	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	96.5		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	96.5		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	96.5		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	78.9		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	78.9		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	78.9		30 - 110					08/31/23 10:56	09/19/23 12:23	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.255	U	0.385	0.385	5.00	0.658	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.255	U	0.385	0.385	5.00	0.658	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.255	U	0.385	0.385	5.00	0.658	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_23_FD

Lab Sample ID: 500-238579-4

Date Collected: 08/22/23 11:20

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0729	U	0.0738	0.0741	1.00	0.115	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Radium-226	0.0729	U	0.0738	0.0741	1.00	0.115	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Radium-226	0.0729	U	0.0738	0.0741	1.00	0.115	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	94.0		30 - 110					08/31/23 10:39	09/25/23 09:34	1
Ba Carrier	94.0		30 - 110					08/31/23 10:39	09/25/23 09:34	1
Ba Carrier	94.0		30 - 110					08/31/23 10:39	09/25/23 09:34	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.118	U	0.314	0.314	1.00	0.558	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.118	U	0.314	0.314	1.00	0.558	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.118	U	0.314	0.314	1.00	0.558	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	94.0		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	94.0		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	94.0		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	80.0		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	80.0		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	80.0		30 - 110					08/31/23 10:56	09/19/23 12:23	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.191	U	0.323	0.323	5.00	0.558	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.191	U	0.323	0.323	5.00	0.558	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.191	U	0.323	0.323	5.00	0.558	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_32

Lab Sample ID: 500-238579-5

Date Collected: 08/22/23 11:15

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0898	U	0.0943	0.0947	1.00	0.151	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Radium-226	0.0898	U	0.0943	0.0947	1.00	0.151	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Radium-226	0.0898	U	0.0943	0.0947	1.00	0.151	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	92.8		30 - 110					08/31/23 10:39	09/25/23 09:34	1
Ba Carrier	92.8		30 - 110					08/31/23 10:39	09/25/23 09:34	1
Ba Carrier	92.8		30 - 110					08/31/23 10:39	09/25/23 09:34	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.225	U	0.373	0.373	1.00	0.636	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.225	U	0.373	0.373	1.00	0.636	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.225	U	0.373	0.373	1.00	0.636	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	92.8		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	92.8		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	92.8		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	78.1		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	78.1		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	78.1		30 - 110					08/31/23 10:56	09/19/23 12:23	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.315	U	0.385	0.385	5.00	0.636	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.315	U	0.385	0.385	5.00	0.636	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.315	U	0.385	0.385	5.00	0.636	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_51

Lab Sample ID: 500-238579-6

Date Collected: 08/22/23 15:56

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.712		0.206	0.216	1.00	0.192	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Radium-226	0.712		0.206	0.216	1.00	0.192	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Radium-226	0.712		0.206	0.216	1.00	0.192	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.3		30 - 110					08/31/23 10:39	09/25/23 09:34	1
Ba Carrier	91.3		30 - 110					08/31/23 10:39	09/25/23 09:34	1
Ba Carrier	91.3		30 - 110					08/31/23 10:39	09/25/23 09:34	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.323	U	0.445	0.446	1.00	0.746	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.323	U	0.445	0.446	1.00	0.746	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.323	U	0.445	0.446	1.00	0.746	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.3		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	91.3		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	91.3		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	82.2		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	82.2		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	82.2		30 - 110					08/31/23 10:56	09/19/23 12:23	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	1.03		0.490	0.496	5.00	0.746	pCi/L		09/27/23 15:51	1
Radium 226 and 228	1.03		0.490	0.496	5.00	0.746	pCi/L		09/27/23 15:51	1
Radium 226 and 228	1.03		0.490	0.496	5.00	0.746	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_25

Lab Sample ID: 500-238579-7

Date Collected: 08/22/23 14:30

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.124	U	0.0917	0.0924	1.00	0.132	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	94.5		30 - 110					08/31/23 10:39	09/25/23 09:34	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.0383	U	0.333	0.333	1.00	0.610	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	94.5		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	79.6		30 - 110					08/31/23 10:56	09/19/23 12:23	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.162	U	0.345	0.346	5.00	0.610	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_26

Lab Sample ID: 500-238579-8

Date Collected: 08/22/23 15:35

Matrix: Water

Date Received: 08/23/23 10:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.306		0.132	0.134	1.00	0.159	pCi/L	08/31/23 10:39	09/25/23 09:34	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	89.6		30 - 110					08/31/23 10:39	09/25/23 09:34	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.320	U	0.304	0.306	1.00	0.654	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	89.6		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	82.6		30 - 110					08/31/23 10:56	09/19/23 12:23	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.306	U	0.331	0.334	5.00	0.654	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
 INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
 Project/Site: HEN-23Q3

Job ID: 500-238579-10
 SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_18&D

Lab Sample ID: 500-238579-13

Date Collected: 08/23/23 14:05

Matrix: Water

Date Received: 08/24/23 09:38

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.141		0.0860	0.0870	1.00	0.110	pCi/L	08/31/23 10:39	09/25/23 09:35	1
Radium-226	0.141		0.0860	0.0870	1.00	0.110	pCi/L	08/31/23 10:39	09/25/23 09:35	1
Radium-226	0.141		0.0860	0.0870	1.00	0.110	pCi/L	08/31/23 10:39	09/25/23 09:35	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.1		30 - 110					08/31/23 10:39	09/25/23 09:35	1
Ba Carrier	93.1		30 - 110					08/31/23 10:39	09/25/23 09:35	1
Ba Carrier	93.1		30 - 110					08/31/23 10:39	09/25/23 09:35	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.208	U	0.357	0.357	1.00	0.611	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.208	U	0.357	0.357	1.00	0.611	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.208	U	0.357	0.357	1.00	0.611	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.1		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	93.1		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	93.1		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	80.4		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	80.4		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	80.4		30 - 110					08/31/23 10:56	09/19/23 12:24	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.349	U	0.367	0.367	5.00	0.611	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.349	U	0.367	0.367	5.00	0.611	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.349	U	0.367	0.367	5.00	0.611	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
 INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
 Project/Site: HEN-23Q3

Job ID: 500-238579-10
 SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_12

Lab Sample ID: 500-238579-15

Date Collected: 08/23/23 10:10

Matrix: Water

Date Received: 08/24/23 09:38

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0183	U	0.0574	0.0574	1.00	0.110	pCi/L	08/31/23 10:39	09/25/23 09:35	1
Radium-226	0.0183	U	0.0574	0.0574	1.00	0.110	pCi/L	08/31/23 10:39	09/25/23 09:35	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	95.8		30 - 110					08/31/23 10:39	09/25/23 09:35	1
Ba Carrier	95.8		30 - 110					08/31/23 10:39	09/25/23 09:35	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.273	U	0.439	0.440	1.00	0.743	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.273	U	0.439	0.440	1.00	0.743	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	95.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	95.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	80.0		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	80.0		30 - 110					08/31/23 10:56	09/19/23 12:24	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.291	U	0.443	0.444	5.00	0.743	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.291	U	0.443	0.444	5.00	0.743	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_13

Lab Sample ID: 500-238579-16

Date Collected: 08/23/23 11:25

Matrix: Water

Date Received: 08/24/23 09:38

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0389	U	0.0708	0.0709	1.00	0.126	pCi/L	08/31/23 10:39	09/25/23 09:35	1
Radium-226	0.0389	U	0.0708	0.0709	1.00	0.126	pCi/L	08/31/23 10:39	09/25/23 09:35	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	85.4		30 - 110					08/31/23 10:39	09/25/23 09:35	1
Ba Carrier	85.4		30 - 110					08/31/23 10:39	09/25/23 09:35	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.0984	U	0.357	0.357	1.00	0.643	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.0984	U	0.357	0.357	1.00	0.643	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	85.4		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	85.4		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	77.4		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	77.4		30 - 110					08/31/23 10:56	09/19/23 12:23	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.137	U	0.364	0.364	5.00	0.643	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.137	U	0.364	0.364	5.00	0.643	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_46

Lab Sample ID: 500-238579-18

Date Collected: 08/23/23 08:55

Matrix: Water

Date Received: 08/24/23 09:38

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0922	U	0.0796	0.0800	1.00	0.118	pCi/L	08/31/23 10:39	09/25/23 09:35	1
Radium-226	0.0922	U	0.0796	0.0800	1.00	0.118	pCi/L	08/31/23 10:39	09/25/23 09:35	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	90.1		30 - 110					08/31/23 10:39	09/25/23 09:35	1
Ba Carrier	90.1		30 - 110					08/31/23 10:39	09/25/23 09:35	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.462	U	0.366	0.368	1.00	0.563	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Radium-228	0.462	U	0.366	0.368	1.00	0.563	pCi/L	08/31/23 10:56	09/19/23 12:23	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	90.1		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Ba Carrier	90.1		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	80.4		30 - 110					08/31/23 10:56	09/19/23 12:23	1
Y Carrier	80.4		30 - 110					08/31/23 10:56	09/19/23 12:23	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.554	U	0.375	0.377	5.00	0.563	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.554	U	0.375	0.377	5.00	0.563	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_47

Lab Sample ID: 500-238579-19

Date Collected: 08/23/23 15:30

Matrix: Water

Date Received: 08/24/23 09:38

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.125	U	0.0906	0.0913	1.00	0.129	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.125	U	0.0906	0.0913	1.00	0.129	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.1		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	93.1		30 - 110					08/31/23 10:39	09/25/23 09:36	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.0500	U	0.314	0.314	1.00	0.578	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.0500	U	0.314	0.314	1.00	0.578	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.1		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	93.1		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	79.3		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	79.3		30 - 110					08/31/23 10:56	09/19/23 12:24	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.175	U	0.327	0.327	5.00	0.578	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.175	U	0.327	0.327	5.00	0.578	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
 INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
 Project/Site: HEN-23Q3

Job ID: 500-238579-10
 SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_54

Lab Sample ID: 500-238579-20

Date Collected: 08/23/23 13:50

Matrix: Water

Date Received: 08/24/23 09:38

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.161		0.112	0.113	1.00	0.160	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.161		0.112	0.113	1.00	0.160	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.8		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	91.8		30 - 110					08/31/23 10:39	09/25/23 09:36	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.0451	U	0.356	0.356	1.00	0.649	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.0451	U	0.356	0.356	1.00	0.649	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	91.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	79.3		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	79.3		30 - 110					08/31/23 10:56	09/19/23 12:24	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.206	U	0.373	0.374	5.00	0.649	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.206	U	0.373	0.374	5.00	0.649	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_52

Lab Sample ID: 500-238579-25

Date Collected: 08/24/23 09:40

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.143		0.0996	0.100	1.00	0.143	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.143		0.0996	0.100	1.00	0.143	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	89.6		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	89.6		30 - 110					08/31/23 10:39	09/25/23 09:36	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.336	U	0.377	0.379	1.00	0.616	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.336	U	0.377	0.379	1.00	0.616	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	89.6		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	89.6		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	74.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	74.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.479	U	0.390	0.392	5.00	0.616	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.479	U	0.390	0.392	5.00	0.616	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_27

Lab Sample ID: 500-238579-26

Date Collected: 08/24/23 09:00

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.131	U	0.0948	0.0956	1.00	0.137	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.131	U	0.0948	0.0956	1.00	0.137	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.131	U	0.0948	0.0956	1.00	0.137	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	95.3		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	95.3		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	95.3		30 - 110					08/31/23 10:39	09/25/23 09:36	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.0486	U	0.306	0.306	1.00	0.589	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	-0.0486	U	0.306	0.306	1.00	0.589	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	-0.0486	U	0.306	0.306	1.00	0.589	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	95.3		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	95.3		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	95.3		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	79.3		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	79.3		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	79.3		30 - 110					08/31/23 10:56	09/19/23 12:24	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.131	U	0.320	0.321	5.00	0.589	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.131	U	0.320	0.321	5.00	0.589	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.131	U	0.320	0.321	5.00	0.589	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_35

Lab Sample ID: 500-238579-27

Date Collected: 08/24/23 10:10

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0626	U	0.0710	0.0712	1.00	0.114	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.0626	U	0.0710	0.0712	1.00	0.114	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.0626	U	0.0710	0.0712	1.00	0.114	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.5		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	93.5		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	93.5		30 - 110					08/31/23 10:39	09/25/23 09:36	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.235	U	0.369	0.370	1.00	0.626	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.235	U	0.369	0.370	1.00	0.626	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.235	U	0.369	0.370	1.00	0.626	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.5		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	93.5		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	93.5		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	82.2		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	82.2		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	82.2		30 - 110					08/31/23 10:56	09/19/23 12:24	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.297	U	0.376	0.377	5.00	0.626	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.297	U	0.376	0.377	5.00	0.626	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.297	U	0.376	0.377	5.00	0.626	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_07

Lab Sample ID: 500-238579-28

Date Collected: 08/24/23 14:00

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.311		0.119	0.122	1.00	0.121	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.311		0.119	0.122	1.00	0.121	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.311		0.119	0.122	1.00	0.121	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.311		0.119	0.122	1.00	0.121	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.311		0.119	0.122	1.00	0.121	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	88.8		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	88.8		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	88.8		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	88.8		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	88.8		30 - 110					08/31/23 10:39	09/25/23 09:36	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.170	U	0.371	0.371	1.00	0.647	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.170	U	0.371	0.371	1.00	0.647	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.170	U	0.371	0.371	1.00	0.647	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.170	U	0.371	0.371	1.00	0.647	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	0.170	U	0.371	0.371	1.00	0.647	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	88.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	88.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	88.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	88.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	88.8		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	77.4		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	77.4		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	77.4		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	77.4		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	77.4		30 - 110					08/31/23 10:56	09/19/23 12:24	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.481	U	0.390	0.391	5.00	0.647	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.481	U	0.390	0.391	5.00	0.647	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.481	U	0.390	0.391	5.00	0.647	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.481	U	0.390	0.391	5.00	0.647	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.481	U	0.390	0.391	5.00	0.647	pCi/L		09/27/23 15:51	1

Eurofins Chicago

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_08

Lab Sample ID: 500-238579-30

Date Collected: 08/24/23 15:10

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.241		0.108	0.110	1.00	0.125	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.241		0.108	0.110	1.00	0.125	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.241		0.108	0.110	1.00	0.125	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.241		0.108	0.110	1.00	0.125	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Radium-226	0.241		0.108	0.110	1.00	0.125	pCi/L	08/31/23 10:39	09/25/23 09:36	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.6		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	91.6		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	91.6		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	91.6		30 - 110					08/31/23 10:39	09/25/23 09:36	1
Ba Carrier	91.6		30 - 110					08/31/23 10:39	09/25/23 09:36	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.128	U	0.280	0.280	1.00	0.572	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	-0.128	U	0.280	0.280	1.00	0.572	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	-0.128	U	0.280	0.280	1.00	0.572	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	-0.128	U	0.280	0.280	1.00	0.572	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Radium-228	-0.128	U	0.280	0.280	1.00	0.572	pCi/L	08/31/23 10:56	09/19/23 12:24	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.6		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	91.6		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	91.6		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	91.6		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Ba Carrier	91.6		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	81.9		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	81.9		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	81.9		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	81.9		30 - 110					08/31/23 10:56	09/19/23 12:24	1
Y Carrier	81.9		30 - 110					08/31/23 10:56	09/19/23 12:24	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.241	U	0.300	0.301	5.00	0.572	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.241	U	0.300	0.301	5.00	0.572	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.241	U	0.300	0.301	5.00	0.572	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.241	U	0.300	0.301	5.00	0.572	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.241	U	0.300	0.301	5.00	0.572	pCi/L		09/27/23 15:51	1

Eurofins Chicago

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_08&D

Lab Sample ID: 500-238579-32

Date Collected: 08/24/23 12:25

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.162		0.107	0.108	1.00	0.145	pCi/L	08/31/23 10:58	09/22/23 18:49	1
Radium-226	0.162		0.107	0.108	1.00	0.145	pCi/L	08/31/23 10:58	09/22/23 18:49	1
Radium-226	0.162		0.107	0.108	1.00	0.145	pCi/L	08/31/23 10:58	09/22/23 18:49	1
Radium-226	0.162		0.107	0.108	1.00	0.145	pCi/L	08/31/23 10:58	09/22/23 18:49	1
Radium-226	0.162		0.107	0.108	1.00	0.145	pCi/L	08/31/23 10:58	09/22/23 18:49	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.1		30 - 110					08/31/23 10:58	09/22/23 18:49	1
Ba Carrier	93.1		30 - 110					08/31/23 10:58	09/22/23 18:49	1
Ba Carrier	93.1		30 - 110					08/31/23 10:58	09/22/23 18:49	1
Ba Carrier	93.1		30 - 110					08/31/23 10:58	09/22/23 18:49	1
Ba Carrier	93.1		30 - 110					08/31/23 10:58	09/22/23 18:49	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.411	U	0.348	0.350	1.00	0.543	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Radium-228	0.411	U	0.348	0.350	1.00	0.543	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Radium-228	0.411	U	0.348	0.350	1.00	0.543	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Radium-228	0.411	U	0.348	0.350	1.00	0.543	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Radium-228	0.411	U	0.348	0.350	1.00	0.543	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.1		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Ba Carrier	93.1		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Ba Carrier	93.1		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Ba Carrier	93.1		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Ba Carrier	93.1		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	82.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	82.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	82.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	82.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	82.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.573		0.364	0.366	5.00	0.543	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.573		0.364	0.366	5.00	0.543	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.573		0.364	0.366	5.00	0.543	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.573		0.364	0.366	5.00	0.543	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.573		0.364	0.366	5.00	0.543	pCi/L		09/27/23 15:51	1

Eurofins Chicago

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_08_FD

Lab Sample ID: 500-238579-34

Date Collected: 08/24/23 15:10

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.434		0.153	0.158	1.00	0.148	pCi/L	08/31/23 10:58	09/22/23 18:50	1
Radium-226	0.434		0.153	0.158	1.00	0.148	pCi/L	08/31/23 10:58	09/22/23 18:50	1
Radium-226	0.434		0.153	0.158	1.00	0.148	pCi/L	08/31/23 10:58	09/22/23 18:50	1
Radium-226	0.434		0.153	0.158	1.00	0.148	pCi/L	08/31/23 10:58	09/22/23 18:50	1
Radium-226	0.434		0.153	0.158	1.00	0.148	pCi/L	08/31/23 10:58	09/22/23 18:50	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.6		30 - 110					08/31/23 10:58	09/22/23 18:50	1
Ba Carrier	91.6		30 - 110					08/31/23 10:58	09/22/23 18:50	1
Ba Carrier	91.6		30 - 110					08/31/23 10:58	09/22/23 18:50	1
Ba Carrier	91.6		30 - 110					08/31/23 10:58	09/22/23 18:50	1
Ba Carrier	91.6		30 - 110					08/31/23 10:58	09/22/23 18:50	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.470	U	0.399	0.401	1.00	0.629	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Radium-228	0.470	U	0.399	0.401	1.00	0.629	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Radium-228	0.470	U	0.399	0.401	1.00	0.629	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Radium-228	0.470	U	0.399	0.401	1.00	0.629	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Radium-228	0.470	U	0.399	0.401	1.00	0.629	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Ba Carrier	91.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Ba Carrier	91.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Ba Carrier	91.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Ba Carrier	91.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	85.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	85.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	85.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	85.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	85.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.904		0.427	0.431	5.00	0.629	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.904		0.427	0.431	5.00	0.629	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.904		0.427	0.431	5.00	0.629	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.904		0.427	0.431	5.00	0.629	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.904		0.427	0.431	5.00	0.629	pCi/L		09/27/23 15:51	1

Eurofins Chicago

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_XPW01_pore

Lab Sample ID: 500-238579-36

Date Collected: 08/24/23 12:15

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.104	U	0.299	0.299	1.00	0.558	pCi/L	08/31/23 10:58	09/22/23 18:50	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	30.3		30 - 110					08/31/23 10:58	09/22/23 18:50	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	1.40	U G	1.38	1.39	1.00	2.22	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	30.3		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	85.6		30 - 110					08/31/23 11:08	09/19/23 12:11	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	1.51	U	1.41	1.42	5.00	2.22	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_XPW01_pore_EB

Lab Sample ID: 500-238579-37

Date Collected: 08/24/23 12:15

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.00189	U	0.0740	0.0740	1.00	0.149	pCi/L	08/31/23 10:58	09/22/23 18:50	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	96.3		30 - 110					08/31/23 10:58	09/22/23 18:50	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.00858	U	0.262	0.262	1.00	0.498	pCi/L	08/31/23 11:08	09/19/23 12:11	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	96.3		30 - 110					08/31/23 11:08	09/19/23 12:11	1
Y Carrier	87.5		30 - 110					08/31/23 11:08	09/19/23 12:11	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.00189	U	0.272	0.272	5.00	0.498	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_XPW02_pore

Lab Sample ID: 500-238579-38

Date Collected: 08/24/23 13:45

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.131	U	0.144	0.144	1.00	0.232	pCi/L	08/31/23 10:58	09/22/23 18:50	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.3		30 - 110					08/31/23 10:58	09/22/23 18:50	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.293	U	0.399	0.400	1.00	0.670	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.3		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	83.7		30 - 110					08/31/23 11:08	09/19/23 12:13	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.424	U	0.424	0.425	5.00	0.670	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
 INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
 Project/Site: HEN-23Q3

Job ID: 500-238579-10
 SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_XPW02_pore_EB

Lab Sample ID: 500-238579-39

Date Collected: 08/24/23 13:45

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.188		0.119	0.120	1.00	0.161	pCi/L	08/31/23 10:58	09/22/23 18:50	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.1		30 - 110					08/31/23 10:58	09/22/23 18:50	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.257	U	0.283	0.284	1.00	0.600	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.1		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	83.4		30 - 110					08/31/23 11:08	09/19/23 12:13	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.188	U	0.307	0.308	5.00	0.600	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_XPW03_pore

Lab Sample ID: 500-238579-40

Date Collected: 08/24/23 15:30

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0406	U	0.0691	0.0692	1.00	0.119	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	94.5		30 - 110					08/31/23 10:58	09/22/23 21:06	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.376	U	0.399	0.401	1.00	0.650	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	94.5		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	81.5		30 - 110					08/31/23 11:08	09/19/23 12:13	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.417	U	0.405	0.407	5.00	0.650	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
 INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
 Project/Site: HEN-23Q3

Job ID: 500-238579-10
 SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_XPW03_pore_EB

Lab Sample ID: 500-238579-41

Date Collected: 08/24/23 15:30

Matrix: Water

Date Received: 08/25/23 09:32

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0195	U	0.0635	0.0636	1.00	0.114	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.5		30 - 110					08/31/23 10:58	09/22/23 21:06	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.187	U	0.374	0.375	1.00	0.645	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.5		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	81.5		30 - 110					08/31/23 11:08	09/19/23 12:13	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.207	U	0.379	0.380	5.00	0.645	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_257_FB

Lab Sample ID: 500-238579-42

Date Collected: 08/25/23 12:00

Matrix: Water

Date Received: 08/25/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0356	U	0.0546	0.0547	1.00	0.0932	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.0		30 - 110					08/31/23 10:58	09/22/23 21:06	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.202	U	0.296	0.297	1.00	0.501	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.0		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	83.4		30 - 110					08/31/23 11:08	09/19/23 12:13	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.238	U	0.301	0.302	5.00	0.501	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_34

Lab Sample ID: 500-238579-44

Date Collected: 08/25/23 11:25

Matrix: Water

Date Received: 08/25/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.324		0.0935	0.0980	1.00	0.0946	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Radium-226	0.324		0.0935	0.0980	1.00	0.0946	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Radium-226	0.324		0.0935	0.0980	1.00	0.0946	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.0		30 - 110					08/31/23 10:58	09/22/23 21:06	1
Ba Carrier	99.0		30 - 110					08/31/23 10:58	09/22/23 21:06	1
Ba Carrier	99.0		30 - 110					08/31/23 10:58	09/22/23 21:06	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.499	U	0.371	0.374	1.00	0.569	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Radium-228	0.499	U	0.371	0.374	1.00	0.569	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Radium-228	0.499	U	0.371	0.374	1.00	0.569	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.0		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Ba Carrier	99.0		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Ba Carrier	99.0		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	82.6		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	82.6		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	82.6		30 - 110					08/31/23 11:08	09/19/23 12:13	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.823		0.383	0.387	5.00	0.569	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.823		0.383	0.387	5.00	0.569	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.823		0.383	0.387	5.00	0.569	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_49

Lab Sample ID: 500-238579-45

Date Collected: 08/25/23 10:05

Matrix: Water

Date Received: 08/25/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.235		0.0893	0.0918	1.00	0.107	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Radium-226	0.235		0.0893	0.0918	1.00	0.107	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Radium-226	0.235		0.0893	0.0918	1.00	0.107	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.3		30 - 110					08/31/23 10:58	09/22/23 21:06	1
Ba Carrier	91.3		30 - 110					08/31/23 10:58	09/22/23 21:06	1
Ba Carrier	91.3		30 - 110					08/31/23 10:58	09/22/23 21:06	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.558		0.363	0.366	1.00	0.535	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Radium-228	0.558		0.363	0.366	1.00	0.535	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Radium-228	0.558		0.363	0.366	1.00	0.535	pCi/L	08/31/23 11:08	09/19/23 12:13	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.3		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Ba Carrier	91.3		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Ba Carrier	91.3		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	84.9		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	84.9		30 - 110					08/31/23 11:08	09/19/23 12:13	1
Y Carrier	84.9		30 - 110					08/31/23 11:08	09/19/23 12:13	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.793		0.374	0.377	5.00	0.535	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.793		0.374	0.377	5.00	0.535	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.793		0.374	0.377	5.00	0.535	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_22

Lab Sample ID: 500-238579-46

Date Collected: 08/25/23 08:50

Matrix: Water

Date Received: 08/25/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0944	U	0.0710	0.0715	1.00	0.107	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Radium-226	0.0944	U	0.0710	0.0715	1.00	0.107	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Radium-226	0.0944	U	0.0710	0.0715	1.00	0.107	pCi/L	08/31/23 10:58	09/22/23 21:06	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	96.0		30 - 110					08/31/23 10:58	09/22/23 21:06	1
Ba Carrier	96.0		30 - 110					08/31/23 10:58	09/22/23 21:06	1
Ba Carrier	96.0		30 - 110					08/31/23 10:58	09/22/23 21:06	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.238	U	0.297	0.297	1.00	0.492	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Radium-228	0.238	U	0.297	0.297	1.00	0.492	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Radium-228	0.238	U	0.297	0.297	1.00	0.492	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	96.0		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Ba Carrier	96.0		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Ba Carrier	96.0		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	86.7		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	86.7		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	86.7		30 - 110					08/31/23 11:08	09/19/23 12:17	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.333	U	0.305	0.305	5.00	0.492	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.333	U	0.305	0.305	5.00	0.492	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.333	U	0.305	0.305	5.00	0.492	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_50

Lab Sample ID: 500-238579-47

Date Collected: 08/25/23 11:25

Matrix: Water

Date Received: 08/25/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.289		0.107	0.110	1.00	0.100	pCi/L	08/31/23 10:58	09/25/23 09:25	1
Radium-226	0.289		0.107	0.110	1.00	0.100	pCi/L	08/31/23 10:58	09/25/23 09:25	1
Radium-226	0.289		0.107	0.110	1.00	0.100	pCi/L	08/31/23 10:58	09/25/23 09:25	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	95.0		30 - 110					08/31/23 10:58	09/25/23 09:25	1
Ba Carrier	95.0		30 - 110					08/31/23 10:58	09/25/23 09:25	1
Ba Carrier	95.0		30 - 110					08/31/23 10:58	09/25/23 09:25	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.463	U	0.355	0.357	1.00	0.545	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Radium-228	0.463	U	0.355	0.357	1.00	0.545	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Radium-228	0.463	U	0.355	0.357	1.00	0.545	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	95.0		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Ba Carrier	95.0		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Ba Carrier	95.0		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	84.1		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	84.1		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	84.1		30 - 110					08/31/23 11:08	09/19/23 12:17	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.752		0.371	0.374	5.00	0.545	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.752		0.371	0.374	5.00	0.545	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.752		0.371	0.374	5.00	0.545	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: 845_803_FB

Lab Sample ID: 500-238579-50

Date Collected: 08/28/23 12:00

Matrix: Water

Date Received: 08/28/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.00967	U	0.0532	0.0532	1.00	0.107	pCi/L	08/31/23 10:58	09/25/23 09:25	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	97.3		30 - 110					08/31/23 10:58	09/25/23 09:25	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.0520	U	0.256	0.256	1.00	0.504	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	97.3		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	83.7		30 - 110					08/31/23 11:08	09/19/23 12:17	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.00967	U	0.261	0.261	5.00	0.504	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_18#S

Lab Sample ID: 500-238579-51

Date Collected: 08/28/23 08:35

Matrix: Water

Date Received: 08/28/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.000	U	0.0558	0.0558	1.00	0.117	pCi/L	08/31/23 10:58	09/25/23 09:25	1
Radium-226	0.000	U	0.0558	0.0558	1.00	0.117	pCi/L	08/31/23 10:58	09/25/23 09:25	1
Radium-226	0.000	U	0.0558	0.0558	1.00	0.117	pCi/L	08/31/23 10:58	09/25/23 09:25	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.3		30 - 110					08/31/23 10:58	09/25/23 09:25	1
Ba Carrier	93.3		30 - 110					08/31/23 10:58	09/25/23 09:25	1
Ba Carrier	93.3		30 - 110					08/31/23 10:58	09/25/23 09:25	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.245	U	0.311	0.312	1.00	0.517	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Radium-228	0.245	U	0.311	0.312	1.00	0.517	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Radium-228	0.245	U	0.311	0.312	1.00	0.517	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.3		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Ba Carrier	93.3		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Ba Carrier	93.3		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	81.9		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	81.9		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	81.9		30 - 110					08/31/23 11:08	09/19/23 12:17	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.245	U	0.316	0.317	5.00	0.517	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.245	U	0.316	0.317	5.00	0.517	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.245	U	0.316	0.317	5.00	0.517	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_03R

Lab Sample ID: 500-238579-53

Date Collected: 08/28/23 09:45

Matrix: Water

Date Received: 08/28/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0552	U	0.0678	0.0680	1.00	0.111	pCi/L	08/31/23 11:10	09/25/23 09:22	1
Radium-226	0.0552	U	0.0678	0.0680	1.00	0.111	pCi/L	08/31/23 11:10	09/25/23 09:22	1
Radium-226	0.0552	U	0.0678	0.0680	1.00	0.111	pCi/L	08/31/23 11:10	09/25/23 09:22	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	89.3		30 - 110					08/31/23 11:10	09/25/23 09:22	1
Ba Carrier	89.3		30 - 110					08/31/23 11:10	09/25/23 09:22	1
Ba Carrier	89.3		30 - 110					08/31/23 11:10	09/25/23 09:22	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.414	U	0.360	0.362	1.00	0.821	pCi/L	08/31/23 11:15	09/18/23 15:35	1
Radium-228	-0.414	U	0.360	0.362	1.00	0.821	pCi/L	08/31/23 11:15	09/18/23 15:35	1
Radium-228	-0.414	U	0.360	0.362	1.00	0.821	pCi/L	08/31/23 11:15	09/18/23 15:35	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	89.3		30 - 110					08/31/23 11:15	09/18/23 15:35	1
Ba Carrier	89.3		30 - 110					08/31/23 11:15	09/18/23 15:35	1
Ba Carrier	89.3		30 - 110					08/31/23 11:15	09/18/23 15:35	1
Y Carrier	84.5		30 - 110					08/31/23 11:15	09/18/23 15:35	1
Y Carrier	84.5		30 - 110					08/31/23 11:15	09/18/23 15:35	1
Y Carrier	84.5		30 - 110					08/31/23 11:15	09/18/23 15:35	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.0552	U	0.366	0.368	5.00	0.821	pCi/L		09/26/23 15:38	1
Radium 226 and 228	0.0552	U	0.366	0.368	5.00	0.821	pCi/L		09/26/23 15:38	1
Radium 226 and 228	0.0552	U	0.366	0.368	5.00	0.821	pCi/L		09/26/23 15:38	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_45#S

Lab Sample ID: 500-238579-56

Date Collected: 08/28/23 11:15

Matrix: Water

Date Received: 08/28/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.226		0.117	0.119	1.00	0.133	pCi/L	08/31/23 10:58	09/25/23 09:28	1
Radium-226	0.226		0.117	0.119	1.00	0.133	pCi/L	08/31/23 10:58	09/25/23 09:28	1
Radium-226	0.226		0.117	0.119	1.00	0.133	pCi/L	08/31/23 10:58	09/25/23 09:28	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.5		30 - 110					08/31/23 10:58	09/25/23 09:28	1
Ba Carrier	93.5		30 - 110					08/31/23 10:58	09/25/23 09:28	1
Ba Carrier	93.5		30 - 110					08/31/23 10:58	09/25/23 09:28	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.297	U	0.409	0.410	1.00	0.687	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Radium-228	0.297	U	0.409	0.410	1.00	0.687	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Radium-228	0.297	U	0.409	0.410	1.00	0.687	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.5		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Ba Carrier	93.5		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Ba Carrier	93.5		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	81.9		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	81.9		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	81.9		30 - 110					08/31/23 11:08	09/19/23 12:17	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.522	U	0.425	0.427	5.00	0.687	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.522	U	0.425	0.427	5.00	0.687	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.522	U	0.425	0.427	5.00	0.687	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_16

Lab Sample ID: 500-238579-58

Date Collected: 08/28/23 08:35

Matrix: Water

Date Received: 08/28/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0461	U	0.0589	0.0591	1.00	0.0975	pCi/L	08/31/23 10:58	09/25/23 09:28	1
Radium-226	0.0461	U	0.0589	0.0591	1.00	0.0975	pCi/L	08/31/23 10:58	09/25/23 09:28	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.3		30 - 110					08/31/23 10:58	09/25/23 09:28	1
Ba Carrier	99.3		30 - 110					08/31/23 10:58	09/25/23 09:28	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.460	U	0.343	0.345	1.00	0.522	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Radium-228	0.460	U	0.343	0.345	1.00	0.522	pCi/L	08/31/23 11:08	09/19/23 12:17	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.3		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Ba Carrier	99.3		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	83.4		30 - 110					08/31/23 11:08	09/19/23 12:17	1
Y Carrier	83.4		30 - 110					08/31/23 11:08	09/19/23 12:17	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.506	U	0.348	0.350	5.00	0.522	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.506	U	0.348	0.350	5.00	0.522	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
 INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
 HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
 Project/Site: HEN-23Q3

Job ID: 500-238579-10
 SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_17

Lab Sample ID: 500-238579-59

Date Collected: 08/28/23 09:40

Matrix: Water

Date Received: 08/28/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0741	U	0.0682	0.0685	1.00	0.101	pCi/L	08/31/23 10:58	09/25/23 09:28	1
Radium-226	0.0741	U	0.0682	0.0685	1.00	0.101	pCi/L	08/31/23 10:58	09/25/23 09:28	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.5		30 - 110					08/31/23 10:58	09/25/23 09:28	1
Ba Carrier	93.5		30 - 110					08/31/23 10:58	09/25/23 09:28	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.136	U	0.327	0.327	1.00	0.574	pCi/L	08/31/23 11:08	09/19/23 12:18	1
Radium-228	0.136	U	0.327	0.327	1.00	0.574	pCi/L	08/31/23 11:08	09/19/23 12:18	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	93.5		30 - 110					08/31/23 11:08	09/19/23 12:18	1
Ba Carrier	93.5		30 - 110					08/31/23 11:08	09/19/23 12:18	1
Y Carrier	83.4		30 - 110					08/31/23 11:08	09/19/23 12:18	1
Y Carrier	83.4		30 - 110					08/31/23 11:08	09/19/23 12:18	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.210	U	0.334	0.334	5.00	0.574	pCi/L		09/27/23 15:51	1
Radium 226 and 228	0.210	U	0.334	0.334	5.00	0.574	pCi/L		09/27/23 15:51	1

Client Sample Results

APPENDIX A.
INITIAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_17-FD

Lab Sample ID: 500-238579-60

Date Collected: 08/28/23 09:40

Matrix: Water

Date Received: 08/28/23 15:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0774	U	0.0770	0.0773	1.00	0.121	pCi/L	08/31/23 11:10	09/25/23 09:22	1
Radium-226	0.0774	U	0.0770	0.0773	1.00	0.121	pCi/L	08/31/23 11:10	09/25/23 09:22	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.1		30 - 110					08/31/23 11:10	09/25/23 09:22	1
Ba Carrier	91.1		30 - 110					08/31/23 11:10	09/25/23 09:22	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.809	U G	0.691	0.695	1.00	1.09	pCi/L	08/31/23 11:15	09/18/23 15:35	1
Radium-228	0.809	U G	0.691	0.695	1.00	1.09	pCi/L	08/31/23 11:15	09/18/23 15:35	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.1		30 - 110					08/31/23 11:15	09/18/23 15:35	1
Ba Carrier	91.1		30 - 110					08/31/23 11:15	09/18/23 15:35	1
Y Carrier	77.8		30 - 110					08/31/23 11:15	09/18/23 15:35	1
Y Carrier	77.8		30 - 110					08/31/23 11:15	09/18/23 15:35	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.886	U	0.695	0.699	5.00	1.09	pCi/L		09/26/23 15:38	1
Radium 226 and 228	0.886	U	0.695	0.699	5.00	1.09	pCi/L		09/26/23 15:38	1

Definitions/Glossary

Client: Vistra Energy Corp
 Project/Site: HEN-23Q3

Job ID: 500-238579-10
 JEN-250864
 SDG: HEN_SUP_000_0 RAD

Qualifiers

Rad

Qualifier	Qualifier Description
G	The Sample MDC is greater than the requested RL.
U	Result is less than the sample detection limit.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Rad

Prep Batch: 626172

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total/NA	Water	PrecSep-21	
500-238579-2	HEN_22&D	Total/NA	Water	PrecSep-21	
500-238579-3	HEN_23	Total/NA	Water	PrecSep-21	
500-238579-4	HEN_23_FD	Total/NA	Water	PrecSep-21	
500-238579-5	HEN_32	Total/NA	Water	PrecSep-21	
500-238579-6	HEN_51	Total/NA	Water	PrecSep-21	
500-238579-7	HEN_25	Total/NA	Water	PrecSep-21	
500-238579-8	HEN_26	Total/NA	Water	PrecSep-21	
500-238579-13	HEN_18&D	Total/NA	Water	PrecSep-21	
500-238579-15	HEN_12	Total/NA	Water	PrecSep-21	
500-238579-16	HEN_13	Total/NA	Water	PrecSep-21	
500-238579-18	HEN_46	Total/NA	Water	PrecSep-21	
500-238579-19	HEN_47	Total/NA	Water	PrecSep-21	
500-238579-20	HEN_54	Total/NA	Water	PrecSep-21	
500-238579-25	HEN_52	Total/NA	Water	PrecSep-21	
500-238579-26	HEN_27	Total/NA	Water	PrecSep-21	
500-238579-27	HEN_35	Total/NA	Water	PrecSep-21	
500-238579-28	HEN_07	Total/NA	Water	PrecSep-21	
500-238579-30	HEN_08	Total/NA	Water	PrecSep-21	
MB 160-626172/1-A	Method Blank	Total/NA	Water	PrecSep-21	
LCS 160-626172/2-A	Lab Control Sample	Total/NA	Water	PrecSep-21	
500-238579-8 MS	HEN_26_MS	Total/NA	Water	PrecSep-21	
500-238579-8 MSD	HEN_26_MSD	Total/NA	Water	PrecSep-21	

Prep Batch: 626177

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-1	HEN_21R	Total/NA	Water	PrecSep_0	
500-238579-2	HEN_22&D	Total/NA	Water	PrecSep_0	
500-238579-3	HEN_23	Total/NA	Water	PrecSep_0	
500-238579-4	HEN_23_FD	Total/NA	Water	PrecSep_0	
500-238579-5	HEN_32	Total/NA	Water	PrecSep_0	
500-238579-6	HEN_51	Total/NA	Water	PrecSep_0	
500-238579-7	HEN_25	Total/NA	Water	PrecSep_0	
500-238579-8	HEN_26	Total/NA	Water	PrecSep_0	
500-238579-13	HEN_18&D	Total/NA	Water	PrecSep_0	
500-238579-15	HEN_12	Total/NA	Water	PrecSep_0	
500-238579-16	HEN_13	Total/NA	Water	PrecSep_0	
500-238579-18	HEN_46	Total/NA	Water	PrecSep_0	
500-238579-19	HEN_47	Total/NA	Water	PrecSep_0	
500-238579-20	HEN_54	Total/NA	Water	PrecSep_0	
500-238579-25	HEN_52	Total/NA	Water	PrecSep_0	
500-238579-26	HEN_27	Total/NA	Water	PrecSep_0	
500-238579-27	HEN_35	Total/NA	Water	PrecSep_0	
500-238579-28	HEN_07	Total/NA	Water	PrecSep_0	
500-238579-30	HEN_08	Total/NA	Water	PrecSep_0	
MB 160-626177/1-A	Method Blank	Total/NA	Water	PrecSep_0	
LCS 160-626177/2-A	Lab Control Sample	Total/NA	Water	PrecSep_0	
500-238579-8 MS	HEN_26_MS	Total/NA	Water	PrecSep_0	
500-238579-8 MSD	HEN_26_MSD	Total/NA	Water	PrecSep_0	

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Rad

Prep Batch: 626178

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-32	HEN_08&D	Total/NA	Water	PrecSep-21	
500-238579-34	HEN_08_FD	Total/NA	Water	PrecSep-21	
500-238579-36	HEN_XPW01_pore	Total/NA	Water	PrecSep-21	
500-238579-37	HEN_XPW01_pore_EB	Total/NA	Water	PrecSep-21	
500-238579-38	HEN_XPW02_pore	Total/NA	Water	PrecSep-21	
500-238579-39	HEN_XPW02_pore_EB	Total/NA	Water	PrecSep-21	
500-238579-40	HEN_XPW03_pore	Total/NA	Water	PrecSep-21	
500-238579-41	HEN_XPW03_pore_EB	Total/NA	Water	PrecSep-21	
500-238579-42	HEN_257_FB	Total/NA	Water	PrecSep-21	
500-238579-44	HEN_34	Total/NA	Water	PrecSep-21	
500-238579-45	HEN_49	Total/NA	Water	PrecSep-21	
500-238579-46	HEN_22	Total/NA	Water	PrecSep-21	
500-238579-47	HEN_50	Total/NA	Water	PrecSep-21	
500-238579-50	845_803_FB	Total/NA	Water	PrecSep-21	
500-238579-51	HEN_18#S	Total/NA	Water	PrecSep-21	
500-238579-56	HEN_45#S	Total/NA	Water	PrecSep-21	
500-238579-58	HEN_16	Total/NA	Water	PrecSep-21	
500-238579-59	HEN_17	Total/NA	Water	PrecSep-21	
MB 160-626178/1-A	Method Blank	Total/NA	Water	PrecSep-21	
LCS 160-626178/2-A	Lab Control Sample	Total/NA	Water	PrecSep-21	
500-238579-45 MS	HEN_49_MS	Total/NA	Water	PrecSep-21	
500-238579-45 MSD	HEN_49_MSD	Total/NA	Water	PrecSep-21	

Prep Batch: 626179

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-32	HEN_08&D	Total/NA	Water	PrecSep_0	
500-238579-34	HEN_08_FD	Total/NA	Water	PrecSep_0	
500-238579-36	HEN_XPW01_pore	Total/NA	Water	PrecSep_0	
500-238579-37	HEN_XPW01_pore_EB	Total/NA	Water	PrecSep_0	
500-238579-38	HEN_XPW02_pore	Total/NA	Water	PrecSep_0	
500-238579-39	HEN_XPW02_pore_EB	Total/NA	Water	PrecSep_0	
500-238579-40	HEN_XPW03_pore	Total/NA	Water	PrecSep_0	
500-238579-41	HEN_XPW03_pore_EB	Total/NA	Water	PrecSep_0	
500-238579-42	HEN_257_FB	Total/NA	Water	PrecSep_0	
500-238579-44	HEN_34	Total/NA	Water	PrecSep_0	
500-238579-45	HEN_49	Total/NA	Water	PrecSep_0	
500-238579-46	HEN_22	Total/NA	Water	PrecSep_0	
500-238579-47	HEN_50	Total/NA	Water	PrecSep_0	
500-238579-50	845_803_FB	Total/NA	Water	PrecSep_0	
500-238579-51	HEN_18#S	Total/NA	Water	PrecSep_0	
500-238579-56	HEN_45#S	Total/NA	Water	PrecSep_0	
500-238579-58	HEN_16	Total/NA	Water	PrecSep_0	
500-238579-59	HEN_17	Total/NA	Water	PrecSep_0	
MB 160-626179/1-A	Method Blank	Total/NA	Water	PrecSep_0	
LCS 160-626179/2-A	Lab Control Sample	Total/NA	Water	PrecSep_0	
500-238579-45 MS	HEN_49_MS	Total/NA	Water	PrecSep_0	
500-238579-45 MSD	HEN_49_MSD	Total/NA	Water	PrecSep_0	

Prep Batch: 626180

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-53	HEN_03R	Total/NA	Water	PrecSep-21	

Eurofins Chicago

QC Association Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Rad (Continued)

Prep Batch: 626180 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-60	HEN_17-FD	Total/NA	Water	PrecSep-21	
MB 160-626180/1-A	Method Blank	Total/NA	Water	PrecSep-21	
LCS 160-626180/2-A	Lab Control Sample	Total/NA	Water	PrecSep-21	
500-238579-53 MS	HEN_03R_MS	Total/NA	Water	PrecSep-21	
500-238579-53 MSD	HEN_03R_MSD	Total/NA	Water	PrecSep-21	

Prep Batch: 626182

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-238579-53	HEN_03R	Total/NA	Water	PrecSep_0	
500-238579-60	HEN_17-FD	Total/NA	Water	PrecSep_0	
MB 160-626182/1-A	Method Blank	Total/NA	Water	PrecSep_0	
LCS 160-626182/2-A	Lab Control Sample	Total/NA	Water	PrecSep_0	
500-238579-53 MS	HEN_03R_MS	Total/NA	Water	PrecSep_0	
500-238579-53 MSD	HEN_03R_MSD	Total/NA	Water	PrecSep_0	

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Method: 903.0 - Radium-226 (GFPC)

Lab Sample ID: MB 160-626172/1-A
Matrix: Water
Analysis Batch: 629490

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 626172

Analyte	MB Result	MB Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.03516	U	0.0558	0.0559	1.00	0.0976	pCi/L	08/31/23 10:39	09/25/23 09:27	1
Carrier	MB %Yield	MB Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	89.8		30 - 110					08/31/23 10:39	09/25/23 09:27	1

Lab Sample ID: LCS 160-626172/2-A
Matrix: Water
Analysis Batch: 629490

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 626172

Analyte		Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits
Radium-226		11.3	10.33		1.10	1.00	0.102	pCi/L	91	75 - 125
Carrier	LCS %Yield	LCS Qualifier	Limits							
Ba Carrier	93.1		30 - 110							

Lab Sample ID: 500-238579-8 MS
Matrix: Water
Analysis Batch: 629491

Client Sample ID: HEN_26_MS
Prep Type: Total/NA
Prep Batch: 626172

Analyte	Sample Result	Sample Qual	Spike Added	MS Result	MS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits
Radium-226	0.306		11.3	10.96		1.17	1.00	0.112	pCi/L	95	60 - 140
Carrier	MS %Yield	MS Qualifier	Limits								
Ba Carrier	84.4		30 - 110								

Lab Sample ID: 500-238579-8 MSD
Matrix: Water
Analysis Batch: 629491

Client Sample ID: HEN_26_MSD
Prep Type: Total/NA
Prep Batch: 626172

Analyte	Sample Result	Sample Qual	Spike Added	MSD Result	MSD Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits	RER	RER Limit
Radium-226	0.306		11.4	10.84		1.16	1.00	0.121	pCi/L	92	60 - 140	0.05	1
Carrier	MSD %Yield	MSD Qualifier	Limits										
Ba Carrier	88.3		30 - 110										

Lab Sample ID: MB 160-626178/1-A
Matrix: Water
Analysis Batch: 629278

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 626178

Analyte	MB Result	MB Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.01063	U	0.0857	0.0857	1.00	0.166	pCi/L	08/31/23 10:58	09/22/23 18:49	1

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

APPENDIX A.
Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Method: 903.0 - Radium-226 (GFPC) (Continued)

Lab Sample ID: MB 160-626178/1-A
Matrix: Water
Analysis Batch: 629278

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 626178

Carrier	MB %Yield	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
Ba Carrier	99.3		30 - 110	08/31/23 10:58	09/22/23 18:49	1

Lab Sample ID: LCS 160-626178/2-A
Matrix: Water
Analysis Batch: 629278

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 626178

Analyte	Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits
Radium-226	11.3	10.95		1.19	1.00	0.166	pCi/L	97	75 - 125
Carrier	LCS %Yield	LCS Qualifier	Limits						
Ba Carrier	100		30 - 110						

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 629278

Client Sample ID: HEN_49_MS
Prep Type: Total/NA
Prep Batch: 626178

	Sample	Sample	Spike	MS	MS	Total					%Rec		
Analyte	Result	Qual	Added	Result	Qual	Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	Limits		
Radium-226	0.235		11.4	11.42		1.13	1.00	0.107	pCi/L	99	60 - 140		
Carrier	MS %Yield	MS Qualifier	Limits										
Ba Carrier	90.6		30 - 110										

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 629278

Client Sample ID: HEN_49_MSD
Prep Type: Total/NA
Prep Batch: 626178

Analyte	Sample Result	Sample Qual	Spike Added	MSD Result	MSD Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits	RER	RER Limit
Radium-226	0.235		11.4	10.73		1.08	1.00	0.133	pCi/L	92	60 - 140	0.31	1
Carrier	MSD %Yield	MSD Qualifier	Limits										
Ba Carrier	87.1		30 - 110										

Lab Sample ID: MB 160-626180/1-A
Matrix: Water
Analysis Batch: 629275

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 626180

Analyte	MB Result	MB Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	-0.02184	U	0.0535	0.0535	1.00	0.128	pCi/L	08/31/23 11:10	09/22/23 14:34	1
Carrier	MB %Yield	MB Qualifier	Limits							
Ba Carrier	94.8		30 - 110							

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Method: 903.0 - Radium-226 (GFPC) (Continued)

Lab Sample ID: LCS 160-626180/2-A
Matrix: Water
Analysis Batch: 629275

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 626180

Analyte			Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-226			11.3	10.99		1.18	1.00	0.129	pCi/L	97	75 - 125		
	LCS	LCS											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	94.0		30 - 110										

Lab Sample ID: 500-238579-53 MS
Matrix: Water
Analysis Batch: 629490

Client Sample ID: HEN_03R_MS
Prep Type: Total/NA
Prep Batch: 626180

Analyte	Sample Result	Sample Qual	Spike Added	MS Result	MS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-226	0.0552	U	11.4	10.03		1.07	1.00	0.110	pCi/L	88	60 - 140		
	MS	MS											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	90.3		30 - 110										

Lab Sample ID: 500-238579-53 MSD
Matrix: Water
Analysis Batch: 629490

Client Sample ID: HEN_03R_MSD
Prep Type: Total/NA
Prep Batch: 626180

Analyte	Sample Result	Sample Qual	Spike Added	MSD Result	MSD Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits	RER	RER Limit
Radium-226	0.0552	U	11.4	10.90		1.15	1.00	0.147	pCi/L	95	60 - 140	0.39	1
	MSD	MSD											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	94.8		30 - 110										

Method: 904.0 - Radium-228 (GFPC)

Lab Sample ID: MB 160-626177/1-A
Matrix: Water
Analysis Batch: 628708

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 626177

			Count	Total						
	MB	MB	Uncert.	Uncert.						
Analyte	Result	Qualifier	(2σ+/-)	(2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.5950	U	0.421	0.425	1.00	0.643	pCi/L	08/31/23 10:56	09/19/23 12:22	1
Carrier	MB	MB								
	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	89.8		30 - 110					08/31/23 10:56	09/19/23 12:22	1
Y Carrier	85.2		30 - 110					08/31/23 10:56	09/19/23 12:22	1

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Method: 904.0 - Radium-228 (GFPC) (Continued)

Lab Sample ID: LCS 160-626177/2-A
Matrix: Water
Analysis Batch: 628708

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 626177

Analyte			Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-228			7.86	8.916		1.27	1.00	0.622	pCi/L	113	75 - 125		
	LCS	LCS											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	93.1		30 - 110										
Y Carrier	84.1		30 - 110										

Lab Sample ID: 500-238579-8 MS
Matrix: Water
Analysis Batch: 628708

Client Sample ID: HEN_26_MS
Prep Type: Total/NA
Prep Batch: 626177

Analyte	Sample Result	Sample Qual	Spike Added	MS Result	MS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-228	-0.320	U	7.81	9.721		1.43	1.00	0.665	pCi/L	124	60 - 140		
	MS	MS											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	84.4		30 - 110										
Y Carrier	77.0		30 - 110										

Lab Sample ID: 500-238579-8 MSD
Matrix: Water
Analysis Batch: 628708

Client Sample ID: HEN_26_MSD
Prep Type: Total/NA
Prep Batch: 626177

Analyte	Sample Result	Sample Qual	Spike Added	MSD Result	MSD Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits	RER	RER Limit
Radium-228	-0.320	U	7.91	9.754		1.42	1.00	0.783	pCi/L	123	60 - 140	0.01	1
	MSD	MSD											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	88.3		30 - 110										
Y Carrier	81.9		30 - 110										

Lab Sample ID: MB 160-626179/1-A
Matrix: Water
Analysis Batch: 628698

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 626179

Analyte	MB Result	MB Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.09226	U	0.278	0.278	1.00	0.547	pCi/L	08/31/23 11:08	09/19/23 12:10	1
	MB	MB								
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.3		30 - 110					08/31/23 11:08	09/19/23 12:10	1
Y Carrier	82.2		30 - 110					08/31/23 11:08	09/19/23 12:10	1

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Method: 904.0 - Radium-228 (GFPC) (Continued)

Lab Sample ID: LCS 160-626179/2-A
Matrix: Water
Analysis Batch: 628698

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 626179

Analyte			Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-228			7.86	8.022		1.13	1.00	0.476	pCi/L	102	75 - 125		
	LCS	LCS											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	100		30 - 110										
Y Carrier	87.5		30 - 110										

Lab Sample ID: 500-238579-45 MS
Matrix: Water
Analysis Batch: 628698

Client Sample ID: HEN_49_MS
Prep Type: Total/NA
Prep Batch: 626179

Analyte	Sample Result	Sample Qual	Spike Added	MS Result	MS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-228	0.558		7.88	8.928		1.30	1.00	0.617	pCi/L	106	60 - 140		
	MS	MS											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	90.6		30 - 110										
Y Carrier	79.6		30 - 110										

Lab Sample ID: 500-238579-45 MSD
Matrix: Water
Analysis Batch: 628698

Client Sample ID: HEN_49_MSD
Prep Type: Total/NA
Prep Batch: 626179

Analyte	Sample Result	Sample Qual	Spike Added	MSD Result	MSD Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits	RER	RER Limit
Radium-228	0.558		7.91	8.905		1.29	1.00	0.616	pCi/L	105	60 - 140	0.01	1
	MSD	MSD											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	87.1		30 - 110										
Y Carrier	84.1		30 - 110										

Lab Sample ID: MB 160-626182/1-A
Matrix: Water
Analysis Batch: 628632

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 626182

Analyte	MB Result	MB Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.08319	U	0.303	0.304	1.00	0.545	pCi/L	08/31/23 11:15	09/18/23 12:29	1
	MB	MB								
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	94.8		30 - 110					08/31/23 11:15	09/18/23 12:29	1
Y Carrier	90.8		30 - 110					08/31/23 11:15	09/18/23 12:29	1

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Job ID: 500-238579-10
Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Method: 904.0 - Radium-228 (GFPC) (Continued)

Lab Sample ID: LCS 160-626182/2-A
Matrix: Water
Analysis Batch: 628632

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 626182

Analyte			Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-228			7.87	8.699		1.26	1.00	0.571	pCi/L	111	75 - 125		
	LCS	LCS											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	94.0		30 - 110										
Y Carrier	81.5		30 - 110										

Lab Sample ID: 500-238579-53 MS
Matrix: Water
Analysis Batch: 628632

Client Sample ID: HEN_03R_MS
Prep Type: Total/NA
Prep Batch: 626182

Analyte	Sample Result	Sample Qual	Spike Added	MS Result	MS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-228	-0.414	U	7.89	8.647		1.46	1.00	0.860	pCi/L	110	60 - 140		
	MS	MS											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	90.3		30 - 110										
Y Carrier	80.0		30 - 110										

Lab Sample ID: 500-238579-53 MSD
Matrix: Water
Analysis Batch: 628632

Client Sample ID: HEN_03R_MSD
Prep Type: Total/NA
Prep Batch: 626182

Analyte	Sample Result	Sample Qual	Spike Added	MSD Result	MSD Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits	RER	RER Limit
Radium-228	-0.414	U	7.91	8.231		1.33	1.00	0.739	pCi/L	104	60 - 140	0.15	1
	MSD	MSD											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	94.8		30 - 110										
Y Carrier	89.3		30 - 110										

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_21R

Lab Sample ID: 500-238579-1

Date Collected: 08/22/23 13:45

Matrix: Water

Date Received: 08/23/23 10:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:27
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:23
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_22&D

Lab Sample ID: 500-238579-2

Date Collected: 08/22/23 09:10

Matrix: Water

Date Received: 08/23/23 10:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:28
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:23
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_23

Lab Sample ID: 500-238579-3

Date Collected: 08/22/23 11:20

Matrix: Water

Date Received: 08/23/23 10:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:28
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:23
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_23_FD

Lab Sample ID: 500-238579-4

Date Collected: 08/22/23 11:20

Matrix: Water

Date Received: 08/23/23 10:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:34
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:23
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_32

Date Collected: 08/22/23 11:15

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-5

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:34
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:23
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_51

Date Collected: 08/22/23 15:56

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-6

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:34
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:23
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_25

Date Collected: 08/22/23 14:30

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-7

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:34
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:23
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_26

Date Collected: 08/22/23 15:35

Date Received: 08/23/23 10:00

Lab Sample ID: 500-238579-8

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:34
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:23
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_18&D

Lab Sample ID: 500-238579-13

Date Collected: 08/23/23 14:05

Matrix: Water

Date Received: 08/24/23 09:38

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:35
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:24
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_12

Lab Sample ID: 500-238579-15

Date Collected: 08/23/23 10:10

Matrix: Water

Date Received: 08/24/23 09:38

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:35
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:24
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_13

Lab Sample ID: 500-238579-16

Date Collected: 08/23/23 11:25

Matrix: Water

Date Received: 08/24/23 09:38

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:35
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628709	SCB	EET SL	09/19/23 12:23
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_46

Lab Sample ID: 500-238579-18

Date Collected: 08/23/23 08:55

Matrix: Water

Date Received: 08/24/23 09:38

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:35
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628709	SCB	EET SL	09/19/23 12:23
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_47

Date Collected: 08/23/23 15:30

Date Received: 08/24/23 09:38

Lab Sample ID: 500-238579-19

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:36
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628709	SCB	EET SL	09/19/23 12:24
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_54

Date Collected: 08/23/23 13:50

Date Received: 08/24/23 09:38

Lab Sample ID: 500-238579-20

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629491	FLC	EET SL	09/25/23 09:36
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628709	SCB	EET SL	09/19/23 12:24
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_52

Date Collected: 08/24/23 09:40

Date Received: 08/25/23 09:32

Lab Sample ID: 500-238579-25

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629493	FLC	EET SL	09/25/23 09:36
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628709	SCB	EET SL	09/19/23 12:24
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_27

Date Collected: 08/24/23 09:00

Date Received: 08/25/23 09:32

Lab Sample ID: 500-238579-26

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629493	FLC	EET SL	09/25/23 09:36
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628709	SCB	EET SL	09/19/23 12:24
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_35

Date Collected: 08/24/23 10:10

Date Received: 08/25/23 09:32

Lab Sample ID: 500-238579-27

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629493	FLC	EET SL	09/25/23 09:36
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628709	SCB	EET SL	09/19/23 12:24
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_07

Date Collected: 08/24/23 14:00

Date Received: 08/25/23 09:32

Lab Sample ID: 500-238579-28

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629493	FLC	EET SL	09/25/23 09:36
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628709	SCB	EET SL	09/19/23 12:24
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_08

Date Collected: 08/24/23 15:10

Date Received: 08/25/23 09:32

Lab Sample ID: 500-238579-30

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626172	KAC	EET SL	08/31/23 10:39
Total/NA	Analysis	903.0		1	629493	FLC	EET SL	09/25/23 09:36
Total/NA	Prep	PrecSep_0			626177	KAC	EET SL	08/31/23 10:56
Total/NA	Analysis	904.0		1	628709	SCB	EET SL	09/19/23 12:24
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_08&D

Date Collected: 08/24/23 12:25

Date Received: 08/25/23 09:32

Lab Sample ID: 500-238579-32

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 18:49
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:11
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_08_FD

Lab Sample ID: 500-238579-34

Date Collected: 08/24/23 15:10

Matrix: Water

Date Received: 08/25/23 09:32

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 18:50
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:11
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_XPW01_pore

Lab Sample ID: 500-238579-36

Date Collected: 08/24/23 12:15

Matrix: Water

Date Received: 08/25/23 09:32

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 18:50
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:11
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_XPW01_pore_EB

Lab Sample ID: 500-238579-37

Date Collected: 08/24/23 12:15

Matrix: Water

Date Received: 08/25/23 09:32

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 18:50
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:11
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_XPW02_pore

Lab Sample ID: 500-238579-38

Date Collected: 08/24/23 13:45

Matrix: Water

Date Received: 08/25/23 09:32

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 18:50
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:13
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_XPW02_pore_EB

Lab Sample ID: 500-238579-39

Date Collected: 08/24/23 13:45

Matrix: Water

Date Received: 08/25/23 09:32

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 18:50
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:13
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_XPW03_pore

Lab Sample ID: 500-238579-40

Date Collected: 08/24/23 15:30

Matrix: Water

Date Received: 08/25/23 09:32

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 21:06
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:13
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_XPW03_pore_EB

Lab Sample ID: 500-238579-41

Date Collected: 08/24/23 15:30

Matrix: Water

Date Received: 08/25/23 09:32

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 21:06
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:13
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_257_FB

Lab Sample ID: 500-238579-42

Date Collected: 08/25/23 12:00

Matrix: Water

Date Received: 08/25/23 15:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 21:06
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:13
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_34

Date Collected: 08/25/23 11:25

Date Received: 08/25/23 15:00

Lab Sample ID: 500-238579-44

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 21:06
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:13
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_49

Date Collected: 08/25/23 10:05

Date Received: 08/25/23 15:00

Lab Sample ID: 500-238579-45

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 21:06
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:13
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_22

Date Collected: 08/25/23 08:50

Date Received: 08/25/23 15:00

Lab Sample ID: 500-238579-46

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629278	SCB	EET SL	09/22/23 21:06
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:17
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_50

Date Collected: 08/25/23 11:25

Date Received: 08/25/23 15:00

Lab Sample ID: 500-238579-47

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:25
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:17
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: 845_803_FB

Lab Sample ID: 500-238579-50

Date Collected: 08/28/23 12:00

Matrix: Water

Date Received: 08/28/23 15:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:25
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:17
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_18#S

Lab Sample ID: 500-238579-51

Date Collected: 08/28/23 08:35

Matrix: Water

Date Received: 08/28/23 15:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:25
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:17
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_03R

Lab Sample ID: 500-238579-53

Date Collected: 08/28/23 09:45

Matrix: Water

Date Received: 08/28/23 15:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626180	KAC	EET SL	08/31/23 11:10
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:22
Total/NA	Prep	PrecSep_0			626182	KAC	EET SL	08/31/23 11:15
Total/NA	Analysis	904.0		1	628632	SCB	EET SL	09/18/23 15:35
Total/NA	Analysis	Ra226_Ra228 Pos		1	629684	SCB	EET SL	09/26/23 15:38

Client Sample ID: HEN_45#S

Lab Sample ID: 500-238579-56

Date Collected: 08/28/23 11:15

Matrix: Water

Date Received: 08/28/23 15:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:28
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:17
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Client Sample ID: HEN_16

Date Collected: 08/28/23 08:35

Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-58

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:28
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628698	FLC	EET SL	09/19/23 12:17
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_17

Date Collected: 08/28/23 09:40

Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-59

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626178	KAC	EET SL	08/31/23 10:58
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:28
Total/NA	Prep	PrecSep_0			626179	KAC	EET SL	08/31/23 11:08
Total/NA	Analysis	904.0		1	628708	SCB	EET SL	09/19/23 12:18
Total/NA	Analysis	Ra226_Ra228 Pos		1	629874	EMH	EET SL	09/27/23 15:51

Client Sample ID: HEN_17-FD

Date Collected: 08/28/23 09:40

Date Received: 08/28/23 15:00

Lab Sample ID: 500-238579-60

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			626180	KAC	EET SL	08/31/23 11:10
Total/NA	Analysis	903.0		1	629490	SCB	EET SL	09/25/23 09:22
Total/NA	Prep	PrecSep_0			626182	KAC	EET SL	08/31/23 11:15
Total/NA	Analysis	904.0		1	628632	SCB	EET SL	09/18/23 15:35
Total/NA	Analysis	Ra226_Ra228 Pos		1	629684	SCB	EET SL	09/26/23 15:38

Laboratory References:

EET SL = Eurofins St. Louis, 13715 Rider Trail North, Earth City, MO 63045, TEL (314)298-8566

Accreditation/Certification Summary

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Laboratory: Eurofins St. Louis

Unless otherwise noted, all analytes for this laboratory were covered under each accreditation/certification below.

Authority	Program	Identification Number	Expiration Date
Illinois	NELAP	200023	11-30-23

The following analytes are included in this report, but the laboratory is not certified by the governing authority. This list may include analytes for which the agency does not offer certification.

Analysis Method	Prep Method	Matrix	Analyte
903.0	PrecSep-21	Water	Radium-226
904.0	PrecSep_0	Water	Radium-228
Ra226_Ra228 Pos		Water	Radium 226 and 228

Eurofins Chicago

2417 Bond Street

University Park, IL 60484

Phone: 708-534-5200 Fax: 708-534-5211

Chain of Custody Record



Environment Testing

Client Information (Sub Contract Lab)		Sampler:	Lab PM:	Carrier Tracking No(s):	COC No:							
Client Contact:		Phone:	McCUTCHEON, Carlene	State of Origin:	500-178415.1							
Shipping/Receiving			E-Mail:	Illinois	Page: 1 of 2							
Company:			Carlene.McCutcheon@et.eurofins.com		Job #:							
TestAmerica Laboratories, Inc.					500-238579-21							
Address:												
13715 Rider Trail North,												
City:												
Earth City												
State, Zip:												
MO, 63045												
Phone:												
314-298-8566(Tel) 314-298-8757(Fax)												
Email:												
Project Name:												
HEN-23Q3												
Site:												
Due Date Requested:		Analysis Requested										
9/25/2023												
TAT Requested (days):												
PO #:												
WO #:												
Project #:												
50021987												
SSOW#:												
Sample Identification - Client ID (Lab ID)		Sample Date	Sample Time	Sample Type (C=Comp, G=Grab)	Matrix (W=water, S=solid, S=solid, B=biomass, A=air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	903.0/PreSep_21 Z	904.0/PreSep_0 Z	Ra226_228GFPc_P1 Z	Total Number of Containers	Special Instructions/Note:
HEN_12 (500-238579-15)		8/23/23	10:10 Central		Water			X	X		2	
HEN_13 (500-238579-16)		8/23/23	11:25 Central		Water			X	X		2	
HEN_46 (500-238579-18)		8/23/23	08:55 Central		Water			X	X		2	
HEN_47 (500-238579-19)		8/23/23	15:30 Central		Water			X	X		2	
HEN_54 (500-238579-20)		8/23/23	13:50 Central		Water			X	X		2	
HEN_52 (500-238579-25)		8/24/23	09:40 Central		Water			X	X		2	
HEN_07 (500-238579-28)		8/24/23	14:00 Central		Water			X	X		2	
HEN_08 (500-238579-30)		8/24/23	15:10 Central		Water			X	X		2	
HEN_08&D (500-238579-32)		8/24/23	12:25 Central		Water			X	X		2	

Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.

Possible Hazard Identification

Unconfirmed

Deliverable Requested: I, II, III, IV, Other (specify)

Primary Deliverable Rank: 2

Empty Kit Relinquished by:

Date:

Time:

Method of Shipment:

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)

☐ Return To Client ☐ Disposal By Lab ☐ Archive For Months

Special Instructions/QC Requirements:

Relinquished by: *Stephanie Hemond* Date/Time: *8/29/23 15:00* Company: *FED EX*

Relinquished by: *Stephanie Hemond* Date/Time: *8/30/23 09:00* Company: *ETAT*

Relinquished by: *Stephanie Hemond* Date/Time: *8/30/23 09:00* Company: *ETAT*

Custody Seals Intact: ☐ Yes ☐ No

Custody Seal No.:

Cooler Temperature(s) °C and Other Remarks:

Chain of Custody Record



Environment Testing

Client Information (Sub Contract Lab)		Sampler:	Lab PM:	Carrier Tracking No(s):	COC No:							
Client Contact: Shipping/Receiving		Phone:	McCUTCHEON, Carlene		500-1784152							
Company: TestAmerica Laboratories, Inc.			E-Mail: Carlene.McCutcheon@et.eurofins.com	State of Origin: Illinois	Page 2 of 2							
Address: 13715 Rider Trail North,		Due Date Requested: 9/25/2023	Job #: 500-238579-21									
City: Earth City	TAT Requested (days):		Preservation Codes:									
State/Zip: MO, 63045			A - HCL M - Hexane N - None O - AsNaO2 P - Na2O4S Q - Na2SO3 R - Na2SO3 S - H2SO4 T - TSP Dodecahydrate U - Acetone V - MCAA W - pH 4-5 Y - Trizma Z - other (specify)									
Phone: 314-298-8566(Tel) 314-298-8757(Fax)	PO #:		Other:									
Email:	WO #:											
Project Name: HEN-23Q3	Project #: 50021987											
Site:	SSOW#:											
Sample Identification - Client ID (Lab ID)		Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, B=biomass, A=air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	903.0/PreSep_21 Z	904.0/PreSep_0 Z	Ra226_228GFPc_P1 Z	Total Number of Containers	Special Instructions/Note:
HEN_08_FD (500-238579-34)		8/24/23	15:10 Central		Water			X	X	X	2	
Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/test/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.												
Possible Hazard Identification												
Unconfirmed												
Deliverable Requested: I, II, III, IV, Other (specify)												
Primary Deliverable Rank: 2												
Empty Kit Relinquished by:												
Date:												
Relinquished by: <i>Stephanie Hemmick</i>												
Date/Time: 8/19/23 1500												
Relinquished by: <i>FED EX</i>												
Date/Time:												
Relinquished by:												
Date/Time:												
Custody Seals Intact: ☐ Yes ☐ No												
Custody Seal No.:												
Cooler Temperature(s) °C and Other Remarks:												
Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)												
☐ Return To Client ☐ Disposal By Lab ☐ Archive For Months												
Special Instructions/QC Requirements:												
Method of Shipment:												
Received by: <i>FED EX</i>												
Date/Time: 8/30/23 0900												
Relinquished by: <i>STASH</i>												
Date/Time:												

Chain of Custody Record



Client Information (Sub Contract Lab)		Sampler:	Lab PM:	Carrier Tracking No(s):	COC No:						
Client Contact:		Phone:	McCUTCHEON, Carlene		500-178415.1						
Shipping/Receiving			E-Mail:	State of Origin:	Page						
Company:			Carlene.McCUTCHEON@et.eurofins.com	Illinois	Page 1 of 2						
TestAmerica Laboratories, Inc.				Accreditations Required (See note):	Job #:						
Address:				NELAP - Illinois	500-238579-6						
City:											
Earth City											
State, Zip:											
MO, 63045											
Phone:											
314-298-8566(Tel) 314-298-8757(Fax)											
Email:											
Project Name:											
HEN-23Q3											
Site:											
SSOW#:											
Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=soil, B=biomass, A=air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	903.0/PreSep_21 AF	904.0/PreSep_0 AF	R226_228GFP_C/AF	Total Number of Containers	Special Instructions/Note:
HEN_21R (500-238579-1)	8/22/23	13:45 Central		Water	X		X	X		2	
HEN_23 (500-238579-3)	8/22/23	11:20 Central		Water	X		X	X		2	
HEN_23_FD (500-238579-4)	8/22/23	11:20 Central		Water	X		X	X		2	
HEN_32 (500-238579-5)	8/22/23	11:15 Central		Water	X		X	X		2	
HEN_51 (500-238579-6)	8/22/23	15:56 Central		Water	X		X	X		2	
HEN_27 (500-238579-26)	8/24/23	09:00 Central		Water	X		X	X		2	
HEN_35 (500-238579-27)	8/24/23	10:10 Central		Water	X		X	X		2	
HEN_34 (500-238579-44)	8/25/23	11:25 Central		Water	X		X	X		2	
HEN_49 (500-238579-45)	8/25/23	10:05 Central		Water	X		X	X		2	

Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analysis & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.

Possible Hazard Identification
Unconfirmed
Deliverable Requested: I, II, III, IV, Other (specify) _____

Primary Deliverable Rank: 2

Empty Kit Relinquished by: _____ Date: _____

Relinquished by: Stephanie Hernandez Date/Time: 8/29/23 1500 Company: EEEP

Relinquished by: FED EX Date/Time: _____ Company: _____

Relinquished by: _____ Date/Time: _____ Company: _____

Custody Seals Intact: _____ Custody Seal No.: _____

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months

Special Instructions/QC Requirements: _____

Method of Shipment: _____ Date/Time: _____

Received by: Shantay - Sharkey Date/Time: 8/30/23 0100 Company: EEEP

Received by: _____ Date/Time: _____ Company: _____

Cooler Temperature(s) °C and Other Remarks: _____

Client Information (Sub Contract Lab)				Sampler:		Lab PM:		Carrier Tracking No(s):		COC No:	
Client Contact: Shipping/Receiving				Phone:		McCUTCHEON, Carlene		State of Origin:		500-178415.1	
Company: TestAmerica Laboratories, Inc.						E-Mail: Carlene McCutcheon@et.eurofins.com		Illinois		Page 1 of 2	
Address: 13715 Rider Trail North, Earth City, MO, 63045				PO #:		314-298-8566(Tel) 314-298-8757(Fax)		Job #:		500-238579-4	
Project Name: HEN-23Q3				WO #:				Accreditations Required (See note): NELAP - Illinois		Preservation Codes:	
Site:				Project #:		50021987				A - HCL B - NaOH C - Zn Acetate D - Nitric Acid E - NaHSO4 F - MeOH G - Amchlor H - Ascorbic Acid I - Ice J - DI Water K - EDTA L - EDA Other:	
Due Date Requested: 9/14/2023				TAT Requested (days):				Analysis Requested			
Sample Identification - Client ID (Lab ID)				Sample Date		Sample Time		Sample Type (C=comp, G=grab)		Matrix (W=water, S=solid, O=oil, BT=tissue, A=air)	
Sample Identification - Client ID (Lab ID)				Sample Date		Sample Time		Sample Type (C=comp, G=grab)		Matrix (W=water, S=solid, O=oil, BT=tissue, A=air)	
HEN_21R (500-238579-1)				8/22/23		13:45 Central		Water		Field Filtered Sample (Yes or No)	
HEN_22&D (500-238579-2)				8/22/23		09:10 Central		Water		Perform MS/MSD (Yes or No)	
HEN_23 (500-238579-3)				8/22/23		11:20 Central		Water		903.0/P/PreSep_21 AD	
HEN_23_FD (500-238579-4)				8/22/23		11:20 Central		Water		904.0/P/PreSep_0 AD	
HEN_32 (500-238579-5)				8/22/23		11:15 Central		Water		Raz26_2286PFC_P/ AD	
HEN_51 (500-238579-6)				8/22/23		15:56 Central		Water			
HEN_27 (500-238579-26)				8/24/23		09:00 Central		Water			
HEN_35 (500-238579-27)				8/24/23		10:10 Central		Water			
HEN_34 (500-238579-44)				8/25/23		11:25 Central		Water			
Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/test/main being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.											
Possible Hazard Identification											
Unconfirmed											
Deliverable Requested: I, II, III, IV, Other (specify)											
Empty Kit Relinquished by:											
Relinquished by: Stephanie Hernandez											
Relinquished by: Stephanie Hernandez											
Relinquished by: Stephanie Hernandez											
Custody Seal No.: A Yes A No											
Custody Seal Intact: A Yes A No											

Chain of Custody Record

Client Information (Sub Contract Lab)						Sampler:	Lab PM:	Carrier Tracking No(s):	COC No:
Shipping/Receiving						Phone:	McCUTCHEON, Carlene		500-178415.2
Company:						E-Mail:	Carlene.McCutcheon@et.eurofins.com	State of Origin:	Page:
TestAmerica Laboratories, Inc.								Illinois	Page 2 of 2
Address:						Job #:			
13715 Rider Trail North,						500-238579-4			
City:						Preservation Codes:			
Earth City						A - HCL M - Hexane N - None O - AsNaO2 P - Na2O4S Q - Na2SO3 R - Na2SO4 S - H2SO4 T - TSP Dodecahydrate U - Acetone V - MCAA W - pH 4-5 Y - Trizma Z - other (specify) Other:			
State, Zip: MO, 63045									
Phone:									
Email:									
Project Name:									
HEN-23Q3									
Site:									
Due Date Requested:						Analysis Requested			
9/14/2023									
TAT Requested (days):									
PO #:									
WO #:									
Project #:									
50021987									
SSOW#:									
Sample Identification - Client ID (Lab ID)						Total Number of Containers			
Sample Date						Field Filtered Sample (Yes or No)			
Sample Time						Perform MS/MSD (Yes or No)			
Sample Type (C=comp, G=grab)						903.0/PrecSep_21 AD			
Matrix (Weater, Seawater, Industrial, etc.)						904.0/PrecSep_0 AD			
Preservation Code:						Ra226_228GFP_C PI AD			
HEN_49 (500-238579-45)	8/25/23	10:05 Central	Water	X	X	X	X	X	2
HEN_49_MS (500-238579-45MS)	8/25/23	10:05 Central	Water	X	X	X	X	X	3
HEN_49_MSD (500-238579-45MSD)	8/25/23	10:05 Central	Water	X	X	X	X	X	3
HEN_22 (500-238579-46)	8/25/23	08:50 Central	Water	X	X	X	X	X	2
HEN_50 (500-238579-47)	8/25/23	11:25 Central	Water	X	X	X	X	X	2
Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/test/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.									
Possible Hazard Identification									
Unconfirmed									
Deliverable Requested: I, II, III, IV, Other (specify)									
Primary Deliverable Rank: 2									
Empty Kit Relinquished by:									
Relinquished by: Stephanie Homander									
Date/Time: 8/29/23 10:00									
FED EX									
Relinquished by:									
Date/Time:									
Relinquished by:									
Date/Time:									
Custody Seal Intact: A Yes A No									
Custody Seal No.:									

Chain of Custody Record



Client Information (Sub Contract Lab)		Lab PM: McCUTCHEON, Carlene		Camer Tracking No(s):		COC No: 500-178415.1																			
Client Contact: Shipping/Receiving		Phone:		State of Origin: Illinois		Page: Page 1 of 2																			
Company: TestAmerica Laboratories, Inc.		E-Mail: Carlene.McCUTCHEON@et.eurofins.com		Accreditations Required (See note): NELAP - Illinois		Job #: 500-238579-23																			
Address: 13715 Rider Trail North, City: Earth City State, Zip: MO, 63045 Phone: 314-298-8566(Tel) 314-298-8757(Fax) Email:		Due Date Requested: 9/14/2023 TAT Requested (days): PO #: WO #: Project #: 50021987 Site: SSOW#:		Analysis Requested																					
				Preservation Codes: A - HCL B - NaOH C - Zn Acetate D - Nitric Acid E - NaHSO4 F - MeOH G - Anchlor H - Ascorbic Acid I - Ice J - DI Water K - EDTA L - EDA Other: M - Hexane N - None O - AsNaO2 P - Na2O4S Q - Na2SO3 R - Na2S2O3 S - H2SO4 T - TSP Dodecahydrate U - Acetone V - MCAA W - pH 4-5 Y - Trizma Z - other (specify)																					
Sample Identification - Client ID (Lab ID)		Sample Date		Sample Time		Sample Type (C=Comp, G=grab)		Matrix (Water, Solid, Onwaste/soil, B1+Tissue, A=Air)		Field Filtered Sample (Yes or No)		Perform MS/MSD (Yes or No)		903.0/PreSep_21 AC		904.0/PreSep_0 AC		R226_228GFP_C PI AC		903.0/PreSep_21 AC-23		Total Number of containers		Special Instructions/Note:	
HEN_12 (500-238579-15)		8/23/23		10:10 Central		Water		Water		X		X		X		X		X		X		2		ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT HENNEPIN POWER PLANT, OLD WEST ASH POND HEN-257-804	
HEN_13 (500-238579-16)		8/23/23		11:25 Central		Water		Water		X		X		X		X		X		X		2			
HEN_46 (500-238579-18)		8/23/23		08:55 Central		Water		Water		X		X		X		X		X		X		2			
HEN_47 (500-238579-19)		8/23/23		15:30 Central		Water		Water		X		X		X		X		X		X		2			
HEN_54 (500-238579-20)		8/23/23		13:50 Central		Water		Water		X		X		X		X		X		X		2			
HEN_52 (500-238579-25)		8/24/23		09:40 Central		Water		Water		X		X		X		X		X		X		2			
HEN_07 (500-238579-28)		8/24/23		14:00 Central		Water		Water		X		X		X		X		X		X		2			
HEN_08 (500-238579-30)		8/24/23		15:10 Central		Water		Water		X		X		X		X		X		X		2			
HEN_08&D (500-238579-32)		8/24/23		12:25 Central		Water		Water		X		X		X		X		X		X		2			
Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/test/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.																									
Possible Hazard Identification																									
Unconfirmed																									
Deliverable Requested: I, II, III, IV, Other (specify)																									
Primary Deliverable Rank: 2																									
Empty Kit Relinquished by:																									
Date:																									
Time:																									
Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)																									
☐ Return To Client ☐ Disposal By Lab ☐ Archive For																									
Special Instructions/QC Requirements:																									
Received by:																									
Date/Time:																									
Company:																									
Received by:																									
Date/Time:																									
Company:																									
Received by:																									
Date/Time:																									
Company:																									
Cooler Temperature(s) °C and Other Remarks:																									
Custody Seal No.:																									
A Yes A No																									

Phone: 708-534-5200 Fax: 708-534-5211

Age Group	Percentage
1	10%
2	10%
3	10%
4	10%
5	10%
6	10%
7	10%
8	10%
9	10%
10	10%
11	10%
12	10%
13	10%
14	10%

Chain of Custody Record



Client Information (Sub Contract Lab)				Sampler:	Lab PM:	Camera Tracking No(s):	COC No:							
Shipping/Receiving				Phone:	McCutcheon, Carlene		500-178415.1							
Company:					E-Mail:	State of Origin:	Page:							
TestAmerica Laboratories, Inc.					Carlene.McCutcheon@eurofinsus.com	Illinois	Page 1 of 2							
Address:				Accreditations Required (See note):										
13715 Rider Trail North,				NELAP - Illinois										
City:				Due Date Requested:										
Earth City				9/14/2023										
State, Zip:				TAT Requested (days):										
MO, 63045														
Phone:				PO #:										
314-298-8566(Tel) 314-298-8757(Fax)														
Email:				WO #:										
Project Name:				Project #:										
HEN-23Q3				50021987										
Site:				SSOW#:										
Sample Identification - Client ID (Lab ID)				Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=biomass, A=air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	903.0/P/PreSep_21 AA	904.0/P/PreSep_0 AA	Ra226_228GFPc_P1 AA	Total Number of containers	Special Instructions/Note:
HEN_21R (500-238579-1)				8/22/23	13:45 Central		Water			X	X	X	2	
HEN_22D (500-238579-2)				8/22/23	09:10 Central		Water			X	X	X	2	
HEN_23 (500-238579-3)				8/22/23	11:20 Central		Water			X	X	X	2	
HEN_23_FD (500-238579-4)				8/22/23	11:20 Central		Water			X	X	X	2	
HEN_32 (500-238579-5)				8/22/23	11:15 Central		Water			X	X	X	2	
HEN_51 (500-238579-6)				8/22/23	15:56 Central		Water			X	X	X	2	
HEN_27 (500-238579-26)				8/24/23	09:00 Central		Water			X	X	X	2	
HEN_35 (500-238579-27)				8/24/23	10:10 Central		Water			X	X	X	2	
HEN_34 (500-238579-44)				8/25/23	11:25 Central		Water			X	X	X	2	
Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.														
Possible Hazard Identification														
Unconfirmed														
Deliverable Requested: I, II, III, IV, Other (specify)														
Primary Deliverable Rank: 2														
Empty Kit Relinquished by:														
Date:														
Time:														
Relinquished by: <i>Sophomire Hemondy</i>														
Date/Time: 8/19/23 1500														
Relinquished by: <i>FED EX</i>														
Date/Time:														
Relinquished by:														
Date/Time:														
Custody Seal No.:														
A Yes A No														
Custody Seals Intact:														
Cooler Temperature(s) °C and Other Remarks:														

Chain of Custody Record



Client Information (Sub Contract Lab)			Lab PM: McCUTCHEON, CARLENE		COC No: 500-178415.2						
Client Contact: McCUTCHEON, CARLENE			E-Mail: Carlene.McCutcheon@et.eurofins.com		Page: Page 2 of 2						
Shipping/Receiving Company: TestAmerica Laboratories, Inc.			State of Origin: Illinois		Job #: 500-238579-2						
Address: 13715 Rider Trail North, Earth City, MO 63045			Accreditations Required (See note): NELAP - Illinois		Preservation Codes: A - HCL B - NaOH C - Zn Acetate D - Nitric Acid E - NaHSO4 F - MeOH G - Amchlor H - Ascorbic Acid I - Ice J - DI Water K - EDTA L - EDA M - Hexane N - None O - AsNaO2 P - Na2O4S Q - Na2SO3 R - Na2SO3 S - H2SO4 T - TSP Dodecahydrate U - Acetone V - MCAA W - pH 4-5 Y - Trizma Z - other (specify)						
Due Date Requested: 9/14/2023			Analysis Requested								
TAT Requested (days):											
PO #:											
WO #:											
Project #:											
SSOW#:											
Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=tissue, A=air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	903.0/PrecSep_21 AA	904.0/PrecSep_0 AA	Ra226_228GFPc_P1 AA	Total Number of Containers	Special Instructions/Note:
HEN_49 (500-238579-45)	8/25/23	10:05 Central		Water			X	X	X	2	
HEN_49_MS (500-238579-45MS)	8/25/23	10:05 Central	MS	Water			X	X	X	3	
HEN_49_MSD (500-238579-45MSD)	8/25/23	10:05 Central	MSD	Water			X	X	X	3	
HEN_22 (500-238579-46)	8/25/23	08:50 Central		Water			X	X	X	2	
HEN_50 (500-238579-47)	8/25/23	11:25 Central		Water			X	X	X	2	
Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.											
Possible Hazard Identification											
Unconfirmed											
Deliverable Requested: I, II, III, IV, Other (specify)											
Primary Deliverable Rank: 2											
Empty Kit Relinquished by:											
Relinquished by: Stephanie Hernandez Date/Time: 8/19/23 1500											
Relinquished by: FEDEX Date/Time: 8/30/23 0900											
Relinquished by: FEDEX Date/Time: 8/30/23 0900											
Custody Seal No.: 8/30/23 0900											
Custody Seal Intact: Yes											

Client Information (Sub Contract Lab)				Sampler:		Lab PM:		Carrier Tracking No(s):		COC No:	
Client Contact: Shipping/Receiving				Phone:		McCUTCHEON, Carlene		State of Origin:		500-178415.1	
Company: Tesi/America Laboratories, Inc.						E-Mail:		Illinois		Page: 1 of 1	
Address: 13715 Rider Trail North,				PO #:		Accreditations Required (See note):		Job #:		500-238579-18	
City: Earth City				WO #:		NELAP - Illinois					
State, Zip: MO, 63045				Project #:		Analysis Requested					
Phone: 314-298-8566(Tel) 314-298-8757(Fax)				SSOW#:		Due Date Requested:					
Email:				50021987		TAT Requested (days):					
Project Name: HEN-23Q3											
Site:											

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=oil, BT=tissue, A=air)	Field Filtered Sample (Yes or No)		Perform MS/MSD (Yes or No)		903.0/PreSep_21 AE		904.0/PreSep_0 AE		Raz26_228GFCP_P/ AE		903.0/PreSep_21 AE-18		Total Number of containers	Special Instructions/Note:
					Preservation Code:	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	903.0/PreSep_21 AE	904.0/PreSep_0 AE	Raz26_228GFCP_P/ AE	903.0/PreSep_21 AE-18							
HEN_18&D (500-238579-13)	8/23/23	14:05 Central		Water				X	X		X						2	
HEN_07 (500-238579-28)	8/24/23	14:00 Central		Water				X	X		X						2	
HEN_08 (500-238579-30)	8/24/23	15:10 Central		Water				X	X		X						2	
HEN_08&D (500-238579-32)	8/24/23	12:25 Central		Water				X	X		X						2	
HEN_08 FD (500-238579-34)	8/24/23	15:10 Central		Water				X	X		X						2	
HEN_18#S (500-238579-51)	8/28/23	08:35 Central		Water				X	X		X						2	
HEN_03R (500-238579-53)	8/28/23	09:45 Central		Water				X	X		X						2	
HEN_03R (500-238579-53MS)	8/28/23	09:45 Central	MS	Water				X	X		X						3	
HEN_03R (500-238579-53MSD)	8/28/23	09:45 Central	MSD	Water				X	X		X						3	

Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/test/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.

Possible Hazard Identification			
Unconfirmed			
Deliverable Requested: I, II, III, IV, Other (specify)		Primary Deliverable Rank: 2	
Empty Kit Relinquished by:			
Relinquished by: <i>Suphanie Hemandouy</i>		Date/Time: 8/30/23 1500	
Relinquished by:		Date/Time:	
Relinquished by:		Date/Time:	
Custody Seals Intact: ☒ Yes ☐ No		Custody Seal No.:	

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)			
☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months			
Special Instructions/QC Requirements:			
Method of Shipment:			
Received by: <i>Bryana Sharkey</i>		Date/Time: 8/30/23 0900	
Received by:		Date/Time:	
Received by:		Date/Time:	

Chain of Custody Record



eurofins

Environment Testing

Client Information (Sub Contract Lab)		Lab PM:		Carrier Tracking No(s):		COC No:						
Client Contact:		McCutcheon, Carlene				500-178415.1						
Shipping/Receiving		E-Mail:		State of Origin:		Page:						
Company:		Carlene.McCutcheon@et.eurofins.com		Illinois		Page 1 of 1						
Address:		Accreditations Required (See note):		Job #:		Preservation Codes:						
13715 Rider Trail North,		NELAP - Illinois		500-238579-16		M - Hexane N - None O - AsNaO2 P - Na2O4S Q - Na2SO3 R - NaHSO4 S - H2SO4 T - TSP Dodecahydrate U - Acetone V - MCAA W - pH 4-5 Y - Trizma Z - other (specify)						
City:		Due Date Requested:		Analysis Requested		Total Number of containers						
Earth City		9/14/2023										
State, Zip:		TAT Requested (days):										
MO, 63045												
Phone:		PO #:										
314-298-8566(Tel) 314-298-8757(Fax)												
Email:		WO #:										
Project Name:		Project #:										
HEN-2303		50021987										
Site:		SSOW#:										
Sample Identification - Client ID (Lab ID)		Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=wastewater, B=biomass, A=air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	903.0/PreSep_21 AB	904.0/PreSep_0 AB	Ra226_228GFP_C/AB	903.0/PreSep_21 AB-16	Special Instructions/Note:
HEN_18&D (500-238579-13)		8/23/23	14:05 Central	Water	Water			X	X	X		
HEN_07 (500-238579-28)		8/24/23	14:00 Central	Water	Water			X	X	X		
HEN_08 (500-238579-30)		8/24/23	15:10 Central	Water	Water			X	X	X		
HEN_08&D (500-238579-32)		8/24/23	12:25 Central	Water	Water			X	X	X		
HEN_08_FD (500-238579-34)		8/24/23	15:10 Central	Water	Water			X	X	X		
HEN_18#S (500-238579-51)		8/28/23	08:35 Central	Water	Water			X	X	X		
HEN_03R (500-238579-53)		8/28/23	09:45 Central	Water	Water			X	X	X		
HEN_03R (500-238579-53MS)		8/28/23	09:45 Central	MS	Water			X	X	X		
HEN_03R (500-238579-53MSD)		8/28/23	09:45 Central	MSD	Water			X	X	X		

Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/test/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.

Possible Hazard Identification

Unconfirmed

Deliverable Requested: I, II, III, IV, Other (specify) _____

Primary Deliverable Rank: 2

Empty Kit Relinquished by: _____ Date: _____

Relinquished by: *Stephanie Hemminger* Date/Time: *8/19/23 1500* Company: *FEDEX*

Relinquished by: _____ Date/Time: _____ Company: _____

Relinquished by: _____ Date/Time: _____ Company: _____

Custody Seals Intact: ☐ Yes ☐ No

Custody Seal No.: _____

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)

☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months

Special Instructions/QC Requirements:

Time: _____ Method of Shipment: _____

Received by: *FEDEX* Date/Time: _____ Company: _____

Received by: *Bruna Sharkey - Monahan* Date/Time: *8/30/23 0900* Company: *ET-457*

Received by: _____ Date/Time: _____ Company: _____

Cooler Temperature(s) °C and Other Remarks: _____

Chain of Custody Record



Client Information (Sub Contract Lab)		Sampler:	Lab PM:	Carrier Tracking No(s):	COC No:
Client Contact:		Phone:	McCUTCHEON, Carlene		500-178415-1
Shipping/Receiving			E-Mail:	State of Origin:	Page:
Company:			Carlene.McCUTCHEON@et.eurofins.com	Illinois	Page 1 of 2
Test/America Laboratories, Inc.			Accreditations Required (See note):	Job #:	
Address:			NELAP - Illinois	500-238579-14	
City:					
Earth City					
State, Zip:					
MO, 63045					
Phone:					
314-298-8566(Tel) 314-298-8757(Fax)					
Email:					
Project Name:					
HEN-2303					
Site:					
SSOW#:					
Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Preservation Code:	Matrix (W=water, S=solid, O=oil, B=biomass, A=air)
HEN_18&D (500-238579-13)	8/23/23	14:05 Central			Water
HEN_07 (500-238579-28)	8/24/23	14:00 Central			Water
HEN_08 (500-238579-30)	8/24/23	15:10 Central			Water
HEN_08&D (500-238579-32)	8/24/23	12:25 Central			Water
HEN_08_FD (500-238579-34)	8/24/23	15:10 Central			Water
HEN_257_FB (500-238579-42)	8/25/23	12:00 Central			Water
HEN_18#S (500-238579-51)	8/28/23	08:35 Central			Water
HEN_03R (500-238579-53)	8/28/23	09:45 Central			Water
HEN_03R (500-238579-53MS)	8/28/23	09:45 Central	MS		Water

Sample ID	Perform MS/MSD (Yes or No)	Field Filtered Sample (Yes or No)	903.0/PreSep_21 Y	904.0/PreSep_0 Y	903.0/PreSep_21 Y-14	Total Number of Containers	Special Instructions/Note:
HEN_18&D (500-238579-13)	X	X	X	X	X	2	
HEN_07 (500-238579-28)	X	X	X	X	X	2	
HEN_08 (500-238579-30)	X	X	X	X	X	2	
HEN_08&D (500-238579-32)	X	X	X	X	X	2	
HEN_08_FD (500-238579-34)	X	X	X	X	X	2	
HEN_257_FB (500-238579-42)	X	X	X	X	X	2	
HEN_18#S (500-238579-51)	X	X	X	X	X	2	
HEN_03R (500-238579-53)	X	X	X	X	X	2	
HEN_03R (500-238579-53MS)	X	X	X	X	X	3	

Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/test/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.

Possible Hazard Identification		Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)	
Unconfirmed	Deliverable Requested: I, II, III, IV, Other (specify)	Return To Client	Disposal By Lab
	Primary Deliverable Rank: 2	☐	☐
Empty Kit Relinquished by:		Special Instructions/QC Requirements:	
Date:		Time:	
Relinquished by: Stephanie Hernandez		Received by: FEDEX	
Date/Time: 8/19/23 1300		Date/Time:	
Relinquished by:		Received by:	
Date/Time:		Date/Time:	
Relinquished by: FEDEX		Received by: Diana Shanley - HEN-257-804	
Date/Time:		Date/Time:	
Custody Seal No.:		Cooler Temperature(s) °C and Other Remarks:	
Δ Yes Δ No			

ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Preservation Codes:
M - Hexane
N - None
O - AsNaO2
P - Na2O4S
Q - Na2SO3
R - Na2SO4
S - H2SO4
T - TSP Dodecahydrate
U - Acetone
V - MCAA
W - DI Water
X - EDTA
Y - Trizma
Z - other (specify)
Other:

Chain of Custody Record



Client Information (Sub Contract Lab)				Sampler:	Lab PM:	Carrier Tracking No(s):	COC No:			
Client Contact:				Phone:	McCUTCHEON, Carlene		500-178415.1			
Shipping/Receiving					E-Mail:	State of Origin:	Page:			
Company:					Carlene McCutcheon@eurofins.com	Illinois	Page 1 of 2			
Address:				Accreditations Required (See note):		Job #:				
13715 Rider Trail North,				NELAP - Illinois		500-238579-10				
City:	Earth City			Due Date Requested:						
State, Zip:	MO, 63045			9/14/2023						
Phone:	314-298-8566(Tel) 314-298-8757(Fax)			TAT Requested (days):						
Email:				PO #:						
				WO #:						
Project Name:	HEN-2303			Project #:						
Site:				SSOW#:						
Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=wastewater, BT=tissue, A=air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	904.0/PresSep_0 AG	Ra226_228GFP_C PI AG	Total Number of Containers	Special Instructions/Note:
HEN_25 (500-238579-7)	8/22/23	14:30 Central		Water	X	X	X	X	2	
HEN_26 (500-238579-8)	8/22/23	15:35 Central		Water	X	X	X	X	2	
HEN_26_MS (500-238579-8MS)	8/22/23	15:35 Central	MS	Water	X	X	X	X	2	
HEN_26_MSD (500-238579-8MSD)	8/22/23	15:35 Central	MSD	Water	X	X	X	X	2	
HEN_XPW01_pore (500-238579-36)	8/24/23	12:15 Central		Water	X	X	X	X	2	
HEN_XPW01_pore_EB (500-238579-37)	8/24/23	12:15 Central		Water	X	X	X	X	2	
HEN_XPW02_pore (500-238579-38)	8/24/23	13:45 Central		Water	X	X	X	X	2	
HEN_XPW02_pore_EB (500-238579-39)	8/24/23	13:45 Central		Water	X	X	X	X	4	
HEN_XPW03_pore (500-238579-40)	8/24/23	15:30 Central		Water	X	X	X	X	2	

Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/test/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.

Possible Hazard Identification

Unconfirmed

Deliverable Requested: I, II, III, IV, Other (specify) _____ Primary Deliverable Rank: 2

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)

☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months

Special Instructions/QC Requirements:

Empty Kit Relinquished by: _____ Date: _____ Method of Shipment: _____

Relinquished by: *Stephanie Hernandez* Date/Time: *8/19/23 1500* Company: *EEIA*

Relinquished by: _____ Date/Time: _____ Company: _____

Relinquished by: _____ Date/Time: _____ Company: _____

Custody Seals Intact: ☐ Yes ☐ No

Custody Seal No.: _____

Cooler Temperature(s) °C and Other Remarks: _____

Chain of Custody Record



Client Information (Sub Contract Lab)			Sampler: Lab PM: McCutcheon, Carlene		Carrier Tracking No(s):		COC No: 500-178415.2																																																			
Client Contact: Shipping/Receiving			Phone:		State of Origin: Illinois		Page: Page 2 of 2																																																			
Company: TestAmerica Laboratories, Inc.			E-Mail: Carlene.McCutcheon@et.eurofinsus.com		Accreditations Required (See note): NELAP - Illinois		Job #: 500-238579-10																																																			
Address: 13715 Rider Trail North, Earth City, MO 63045			Due Date Requested: 9/14/2023		Analysis Requested		Preservation Codes:																																																			
Phone: 314-298-8566(Tel) 314-298-8757(Fax)			TAT Requested (days):		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th>Field Filtered Sample (Yes or No)</th> <th>Perform MS/MSD (Yes or No)</th> <th>903.0/PrecSep_21 AG</th> <th>904.0/PrecSep_0 AG</th> <th>Ra226_228GFP_C PI AG</th> <th>Total Number of containers</th> </tr> <tr> <td></td> <td></td> <td>X</td> <td>X</td> <td>X</td> <td>2</td> </tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td></tr> </table>		Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	903.0/PrecSep_21 AG	904.0/PrecSep_0 AG	Ra226_228GFP_C PI AG	Total Number of containers			X	X	X	2													<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td>A - HCL</td><td>M - Hexane</td></tr> <tr> <td>B - NaOH</td><td>N - None</td></tr> <tr> <td>C - Zn Acetate</td><td>O - AsNaO2</td></tr> <tr> <td>D - Nitric Acid</td><td>P - Na2O4S</td></tr> <tr> <td>E - NaHSO4</td><td>Q - Na2SO3</td></tr> <tr> <td>F - MeOH</td><td>R - Na2S2O3</td></tr> <tr> <td>G - Amchlor</td><td>S - H2SO4</td></tr> <tr> <td>H - Ascorbic Acid</td><td>T - TSP Dodecahydrate</td></tr> <tr> <td>I - Ice</td><td>U - Acetone</td></tr> <tr> <td>J - DI Water</td><td>V - MCAA</td></tr> <tr> <td>K - EDTA</td><td>W - pH 4-5</td></tr> <tr> <td>L - EDA</td><td>Y - Trizma</td></tr> <tr> <td colspan="2">Z - other (specify)</td></tr> </table>		A - HCL	M - Hexane	B - NaOH	N - None	C - Zn Acetate	O - AsNaO2	D - Nitric Acid	P - Na2O4S	E - NaHSO4	Q - Na2SO3	F - MeOH	R - Na2S2O3	G - Amchlor	S - H2SO4	H - Ascorbic Acid	T - TSP Dodecahydrate	I - Ice	U - Acetone	J - DI Water	V - MCAA	K - EDTA	W - pH 4-5	L - EDA	Y - Trizma	Z - other (specify)	
Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	903.0/PrecSep_21 AG	904.0/PrecSep_0 AG	Ra226_228GFP_C PI AG			Total Number of containers																																																			
		X	X	X			2																																																			
A - HCL	M - Hexane																																																									
B - NaOH	N - None																																																									
C - Zn Acetate	O - AsNaO2																																																									
D - Nitric Acid	P - Na2O4S																																																									
E - NaHSO4	Q - Na2SO3																																																									
F - MeOH	R - Na2S2O3																																																									
G - Amchlor	S - H2SO4																																																									
H - Ascorbic Acid	T - TSP Dodecahydrate																																																									
I - Ice	U - Acetone																																																									
J - DI Water	V - MCAA																																																									
K - EDTA	W - pH 4-5																																																									
L - EDA	Y - Trizma																																																									
Z - other (specify)																																																										
Project Name: HEN-23Q3			PO #:		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th>Sample Date</th> <th>Sample Time</th> <th>Sample Type (C=Comp, G=grab)</th> <th>Preservation Code:</th> <th>Matrix (W=water, S=solid, O=waste/oil, B=tissue, A=lab)</th> </tr> <tr> <td>8/24/23</td> <td>15:30 Central</td> <td></td> <td></td> <td>Water</td> </tr> <tr><td></td><td></td><td></td><td></td><td></td></tr> </table>		Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Preservation Code:	Matrix (W=water, S=solid, O=waste/oil, B=tissue, A=lab)	8/24/23	15:30 Central			Water						Sample Identification - Client ID (Lab ID) HEN_XPW03_pore_EB (500-238579-41)																																				
Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Preservation Code:	Matrix (W=water, S=solid, O=waste/oil, B=tissue, A=lab)																																																						
8/24/23	15:30 Central			Water																																																						
Site:			WO #:																																																							
SSOW#:			Project #:																																																							
Special Instructions/Note: ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT HENNEPIN POWER PLANT, OLD WEST ASH POND HEN-257-804																																																										

Possible Hazard Identification

Unconfirmed Deliverable Requested: I, II, III, IV, Other (specify) _____

Primary Deliverable Rank: 2

Empty Kit Relinquished by: _____

Relinquished by: Stephanie Hemondy Date/Time: 8/19/23 1500

Relinquished by: FED EX Date/Time: _____

Relinquished by: _____ Date/Time: _____

Custody Seals Intact: Yes Custody Seal No.: _____

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)

☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months

Special Instructions/QC Requirements: _____

Method of Shipment: _____

Received by: EEA Date/Time: _____

Received by: FED EX Date/Time: _____

Received by: Stephanie Hemondy Date/Time: 8/30/23 0500

Company: _____

Company: _____

Company: EEA

Cooler Temperature(s) °C and Other Remarks: _____

Chain of Custody Record



Client Information (Sub Contract Lab)		Lab PM: McCutcheon, Carlene		Carrier Tracking No(s):		COC No: 500-178415-1																			
Client Contact: Shipping/Receiving		Phone:		State of Origin: Illinois		Page: Page 1 of 2																			
Company: TestAmerica Laboratories, Inc.		E-Mail: Carlene.McCutcheon@et.eurofins.com		Accreditations Required (See note): NELAP - Illinois		Job #: 500-238579-1																			
Address: 13715 Rider Trail North,		Due Date Requested: 9/25/2023		Analysis Requested																					
City: Earth City		TAT Requested (days):		Preservation Codes:																					
State Zip: MO. 63045				A - HCL N - None O - AsNaO2 P - Na2O4S Q - Na2SO3 R - Na2S2O3 S - H2SO4 T - TSP Dodecahydrate U - Acetone V - MCAA W - pH 4-5 Y - Trizma Z - other (specify)																					
Phone: 314-298-8566(Tel) 314-298-8757(Fax)		PO #:		Other:																					
Email:		WO #:																							
Project Name: HEN-2303		Project #: 50021987																							
Site:		SSOW#:																							
Sample Identification - Client ID (Lab ID)		Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=wastefl, B=biol, A=air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	903.0/PrecSep_21 Y-14	904.0/PrecSep_0 Y	Ra226_228GFPc_P/Y	903.0/PrecSep_21 AB-16	904.0/PrecSep_0 AB	Ra226_228GFPc_P/AB	903.0/PrecSep_21 AE-18	904.0/PrecSep_0 AE	Ra226_228GFPc_P/AE	903.0/PrecSep_21 Z-21	904.0/PrecSep_0 Z	Ra226_228GFPc_P/Z	903.0/PrecSep_21 AC-23	Total Number of containers	Special Instructions/Note:			
HEN_45#S (500-238579-56)	8/28/23	11:15 Central	Water			X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	2				
HEN_16 (500-238579-58)	8/28/23	08:35 Central	Water																		2				
HEN_17 (500-238579-59)	8/28/23	09:40 Central	Water																		2				
HEN_17-FD (500-238579-60)	8/28/23	09:40 Central	Water																		2				
Note: Since laboratory accreditations are subject to change, Eurofins Chicago places the ownership of method, analyte & accreditation compliance upon our subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/test/matrix being analyzed, the samples must be shipped back to the Eurofins Chicago laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins Chicago attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins Chicago.																									
Possible Hazard Identification																									
Unconfirmed																									
Deliverable Requested: I, II, III, IV, Other (specify)																									
Primary Deliverable Rank: 2																									
Empty Kit Relinquished by:																									
Date:																									
Relinquished by: Stephenie Hemondy																									
Date/Time: 8/29/23 1500																									
Relinquished by: FED EX																									
Date/Time:																									
Relinquished by:																									
Date/Time:																									
Custody Seals Intact: Custody Seal No.:																									
Delta Yes Delta No																									
Cooler Temperature(s) °C and Other Remarks:																									
Received by: FED EX																									
Date/Time:																									
Received by: Briana Sharkey - Sharkey8/28/23 0900																									
Date/Time:																									
Received by:																									
Date/Time:																									
Special Instructions/QC Requirements:																									
Return To Client Disposal By Lab Archive For Months																									
Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)																									
Method of Shipment:																									
Date/Time:																									
Company:																									
Date/Time:																									
Company:																									
Date/Time:																									
Company:																									

[illegible]

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Login Sample Receipt Checklist

Client: Vistra Energy Corp

Job Number: 500-238579-10
SDG Number: HEN_SUP_000_0 RAD

Login Number: 238579

List Number: 1

Creator: Scott, Sherri L

List Source: Eurofins Chicago

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	0.6,0.7,0.3,1.2,0.8,0.4,0.1,2.9,1.7,3.7,1.0,2.8,0.2,2.0,2.9,0.1,1.63,0.1,3,0.5,2
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	False	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	False	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	False	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND
HEN-257-804

Login Sample Receipt Checklist

Client: Vistra Energy Corp

Job Number: 500-238579-10
SDG Number: HEN_SUP_000_0 RAD

Login Number: 238579

List Number: 3

Creator: Sharkey-Gonzalez, Briana L

List Source: Eurofins St. Louis

List Creation: 08/30/23 01:27 PM

Question	Answer	Comment
Radioactivity wasn't checked or is <=/ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	N/A	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Tracer/Carrier Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Method: 903.0 - Radium-226 (GFPC)

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Yield (Acceptance Limits)		
		Ba (30-110)	Ba (30-110)	Ba (30-110)
500-238579-1	HEN_21R	90.1	90.1	90.1
500-238579-3	HEN_23	96.5	96.5	96.5
500-238579-4	HEN_23_FD	94.0	94.0	94.0
500-238579-5	HEN_32	92.8	92.8	92.8
500-238579-6	HEN_51	91.3	91.3	91.3
500-238579-7	HEN_25	94.5	94.5	94.5
500-238579-8	HEN_26	89.6	89.6	89.6
500-238579-8 MS	HEN_26_MS	84.4	84.4	84.4
500-238579-8 MSD	HEN_26_MSD	88.3	88.3	88.3
500-238579-13	HEN_18&D	93.1	93.1	93.1
500-238579-26	HEN_27	95.3	95.3	95.3
500-238579-27	HEN_35	93.5	93.5	93.5
500-238579-36	HEN_XPW01_pore	30.3	30.3	30.3
500-238579-37	HEN_XPW01_pore_EB	96.3	96.3	96.3
500-238579-38	HEN_XPW02_pore	99.3	99.3	99.3
500-238579-39	HEN_XPW02_pore_EB	93.1	93.1	93.1
500-238579-40	HEN_XPW03_pore	94.5	94.5	94.5
500-238579-41	HEN_XPW03_pore_EB	99.5	99.5	99.5
500-238579-42	HEN_257_FB	99.0	99.0	99.0
500-238579-44	HEN_34	99.0	99.0	99.0
500-238579-45	HEN_49	91.3	91.3	91.3
500-238579-45 MS	HEN_49_MS	90.6	90.6	90.6
500-238579-45 MSD	HEN_49_MSD	87.1	87.1	87.1
500-238579-46	HEN_22	96.0	96.0	96.0
500-238579-47	HEN_50	95.0	95.0	95.0
500-238579-50	845_803_FB	97.3	97.3	97.3
500-238579-51	HEN_18#S	93.3	93.3	93.3
500-238579-53	HEN_03R	89.3	89.3	89.3
500-238579-53 MS	HEN_03R_MS	90.3	90.3	90.3
500-238579-53 MSD	HEN_03R_MSD	94.8	94.8	94.8
500-238579-56	HEN_45#S	93.5	93.5	93.5
LCS 160-626172/2-A	Lab Control Sample	93.1	93.1	93.1
LCS 160-626178/2-A	Lab Control Sample	100	100	100
LCS 160-626180/2-A	Lab Control Sample	94.0	94.0	94.0
MB 160-626172/1-A	Method Blank	89.8	89.8	89.8
MB 160-626178/1-A	Method Blank	99.3	99.3	99.3
MB 160-626180/1-A	Method Blank	94.8	94.8	94.8

Tracer/Carrier Legend

Ba = Ba Carrier

Method: 903.0 - Radium-226 (GFPC)

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Yield (Acceptance Limits)		
		Ba (30-110)	Ba (30-110)	Ba (30-110)
500-238579-28	HEN_07	88.8	88.8	88.8
500-238579-30	HEN_08	91.6	91.6	91.6
500-238579-32	HEN_08&D	93.1	93.1	93.1

Eurofins Chicago

Tracer/Carrier Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Method: 903.0 - Radium-226 (GFPC) (Continued)

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Yield (Acceptance Limits)				
		Ba (30-110)	Ba (30-110)	Ba (30-110)	Ba (30-110)	Ba (30-110)
500-238579-34	HEN_08_FD	91.6	91.6	91.6	91.6	91.6
Tracer/Carrier Legend						
Ba = Ba Carrier						

Method: 903.0 - Radium-226 (GFPC)

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Yield (Acceptance Limits)	
		Ba (30-110)	Ba (30-110)
500-238579-2	HEN_22&D	91.3	91.3
500-238579-15	HEN_12	95.8	95.8
500-238579-16	HEN_13	85.4	85.4
500-238579-18	HEN_46	90.1	90.1
500-238579-19	HEN_47	93.1	93.1
500-238579-20	HEN_54	91.8	91.8
500-238579-25	HEN_52	89.6	89.6
500-238579-58	HEN_16	99.3	99.3
500-238579-59	HEN_17	93.5	93.5
500-238579-60	HEN_17-FD	91.1	91.1
Tracer/Carrier Legend			
Ba = Ba Carrier			

Method: 904.0 - Radium-228 (GFPC)

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Yield (Acceptance Limits)					
		Ba (30-110)	Y (30-110)	Ba (30-110)	Y (30-110)	Y (30-110)	Y (30-110)
500-238579-1	HEN_21R	90.1	82.6	90.1	82.6	82.6	82.6
500-238579-3	HEN_23	96.5	78.9	96.5	78.9	78.9	78.9
500-238579-4	HEN_23_FD	94.0	80.0	94.0	80.0	80.0	80.0
500-238579-5	HEN_32	92.8	78.1	92.8	78.1	78.1	78.1
500-238579-6	HEN_51	91.3	82.2	91.3	82.2	82.2	82.2
500-238579-7	HEN_25	94.5	79.6	94.5	79.6	79.6	79.6
500-238579-8	HEN_26	89.6	82.6	89.6	82.6	82.6	82.6
500-238579-8 MS	HEN_26_MS	84.4	77.0	84.4	77.0	77.0	77.0
500-238579-8 MSD	HEN_26_MSD	88.3	81.9	88.3	81.9	81.9	81.9
500-238579-13	HEN_18&D	93.1	80.4	93.1	80.4	80.4	80.4
500-238579-26	HEN_27	95.3	79.3	95.3	79.3	79.3	79.3
500-238579-27	HEN_35	93.5	82.2	93.5	82.2	82.2	82.2
500-238579-36	HEN_XPW01_pore	30.3	85.6	30.3	85.6	85.6	85.6
500-238579-37	HEN_XPW01_pore_EB	96.3	87.5	96.3	87.5	87.5	87.5
500-238579-38	HEN_XPW02_pore	99.3	83.7	99.3	83.7	83.7	83.7
500-238579-39	HEN_XPW02_pore_EB	93.1	83.4	93.1	83.4	83.4	83.4
500-238579-40	HEN_XPW03_pore	94.5	81.5	94.5	81.5	81.5	81.5
500-238579-41	HEN_XPW03_pore_EB	99.5	81.5	99.5	81.5	81.5	81.5
500-238579-42	HEN_257_FB	99.0	83.4	99.0	83.4	83.4	83.4
500-238579-44	HEN_34	99.0	82.6	99.0	82.6	82.6	82.6
500-238579-45	HEN_49	91.3	84.9	91.3	84.9	84.9	84.9

Eurofins Chicago

Tracer/Carrier Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Method: 904.0 - Radium-228 (GFPC) (Continued)

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Yield (Acceptance Limits)					
		Ba (30-110)	Y (30-110)	Ba (30-110)	Y (30-110)	Y (30-110)	Y (30-110)
500-238579-45 MS	HEN_49_MS	90.6	79.6	90.6	79.6	79.6	79.6
500-238579-45 MSD	HEN_49_MSD	87.1	84.1	87.1	84.1	84.1	84.1
500-238579-46	HEN_22	96.0	86.7	96.0	86.7	86.7	86.7
500-238579-47	HEN_50	95.0	84.1	95.0	84.1	84.1	84.1
500-238579-50	845_803_FB	97.3	83.7	97.3	83.7	83.7	83.7
500-238579-51	HEN_18#S	93.3	81.9	93.3	81.9	81.9	81.9
500-238579-53	HEN_03R	89.3	84.5	89.3	84.5	84.5	84.5
500-238579-53 MS	HEN_03R_MS	90.3	80.0	90.3	80.0	80.0	80.0
500-238579-53 MSD	HEN_03R_MSD	94.8	89.3	94.8	89.3	89.3	89.3
500-238579-56	HEN_45#S	93.5	81.9	93.5	81.9	81.9	81.9
LCS 160-626177/2-A	Lab Control Sample	93.1	84.1	93.1	84.1	84.1	84.1
LCS 160-626179/2-A	Lab Control Sample	100	87.5	100	87.5	87.5	87.5
LCS 160-626182/2-A	Lab Control Sample	94.0	81.5	94.0	81.5	81.5	81.5
MB 160-626177/1-A	Method Blank	89.8	85.2	89.8	85.2	85.2	85.2
MB 160-626179/1-A	Method Blank	99.3	82.2	99.3	82.2	82.2	82.2
MB 160-626182/1-A	Method Blank	94.8	90.8	94.8	90.8	90.8	90.8

Tracer/Carrier Legend

Ba = Ba Carrier

Y = Y Carrier

Method: 904.0 - Radium-228 (GFPC)

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Yield (Acceptance Limits)					
		Ba (30-110)	Ba (30-110)	Ba (30-110)	Ba (30-110)	Ba (30-110)	Y (30-110)
500-238579-28	HEN_07	88.8	88.8	88.8	88.8	88.8	77.4
500-238579-30	HEN_08	91.6	91.6	91.6	91.6	91.6	81.9
500-238579-32	HEN_08&D	93.1	93.1	93.1	93.1	93.1	82.6
500-238579-34	HEN_08_FD	91.6	91.6	91.6	91.6	91.6	85.6

Percent Yield (Acceptance Limits)

Lab Sample ID	Client Sample ID	Y (30-110)	Y (30-110)
		(30-110)	(30-110)
500-238579-28	HEN_07	77.4	77.4
500-238579-30	HEN_08	81.9	81.9
500-238579-32	HEN_08&D	82.6	82.6
500-238579-34	HEN_08_FD	85.6	85.6

Tracer/Carrier Legend

Ba = Ba Carrier

Y = Y Carrier

Method: 904.0 - Radium-228 (GFPC)

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Yield (Acceptance Limits)			
		Ba (30-110)	Ba (30-110)	Y (30-110)	Y (30-110)
500-238579-2	HEN_22&D	91.3	91.3	81.9	81.9
500-238579-15	HEN_12	95.8	95.8	80.0	80.0
500-238579-16	HEN_13	85.4	85.4	77.4	77.4

Eurofins Chicago

Tracer/Carrier Summary

APPENDIX A.
ANNUAL GROUNDWATER MONITORING AND CORRECTIVE ACTION REPORT
HENNEPIN POWER PLANT, OLD WEST ASH POND

Client: Vistra Energy Corp
Project/Site: HEN-23Q3

Job ID: 500-238579-10
SDG: HEN_SUP_000_0 RAD

Method: 904.0 - Radium-228 (GFPC) (Continued)

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Yield (Acceptance Limits)			
		Ba (30-110)	Ba (30-110)	Y (30-110)	Y (30-110)
500-238579-18	HEN_46	90.1	90.1	80.4	80.4
500-238579-19	HEN_47	93.1	93.1	79.3	79.3
500-238579-20	HEN_54	91.8	91.8	79.3	79.3
500-238579-25	HEN_52	89.6	89.6	74.8	74.8
500-238579-58	HEN_16	99.3	99.3	83.4	83.4
500-238579-59	HEN_17	93.5	93.5	83.4	83.4
500-238579-60	HEN_17-FD	91.1	91.1	77.8	77.8


Tracer/Carrier Legend

Ba = Ba Carrier

Y = Y Carrier


APPENDIX B
STATISTICAL METHODOLOGY FOR DETERMINATION
OF BACKGROUND VALUES

Notes
%ND = Percent non-detected samples
sd = standard deviation
k = kappa for tolerance limit (95% confidence/95% coverage)



APPENDIX C
STATISTICAL METHODOLOGY FOR DETERMINATION OF
STATISTICALLY SIGNIFICANT LEVELS

Notes
%ND = Percent non-detected samples
MK = Mann-Kendall Trend Test
<u>Alpha Levels</u>
Normality = 0.01
MK Trend = 0.01
Residuals = 0.01
Confidence Level= 0.01



APPENDIX D

ALTERNATIVE SOURCE DEMONSTRATIONS

Prepared for
Dynegy Midwest Generation, LLC

Date
May 1, 2023

Project No.
1940103649-010

**40 C.F.R. § 257.95(G)(3)(II):
ALTERNATE SOURCE DEMONSTRATION
OLD WEST ASH POND (POND NO. 1 AND
POND NO. 3) AND OLD WEST POLISHING
POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS
CCR UNIT 804**

CERTIFICATIONS


I, Brian G. Hennings, a professional geologist in good standing in the State of Illinois, certify that the information in this report is accurate as of the date of my signature below. The content of this report is not to be used other than for its intended purpose and meaning, or for extrapolations beyond the interpretations contained herein.



Brian G. Hennings
Professional Geologist
196-001482
Illinois
Ramboll Americas Engineering Solutions, Inc.
Date: May 1, 2023



I, Eric J. Tlachac, a qualified professional engineer in good standing in the State of Illinois, certify that the information in this report is accurate as of the date of my signature below. The content of this report is not to be used other than for its intended purpose and meaning, or for extrapolations beyond the interpretations contained herein.



Eric J. Tlachac
Qualified Professional Engineer
062-063091
Illinois
Ramboll Americas Engineering Solutions, Inc.
Date: May 1, 2023



CONTENTS

1.	Introduction	3
2.	Background	4
2.1	Site Location and Description	4
2.2	Groundwater Monitoring	4
2.3	Site History	4
2.4	Site Hydrogeology and Stratigraphy	5
3.	Alternate Source Demonstration: Lines of Evidence	7
3.1	LOE #1: Concentrations of Cadmium are Lower than those Observed in Leachate Samples	7
3.2	LOE #2: Cadmium Concentrations are Negatively Correlated with Concentrations of CCR Indicator Parameters	7
3.3	LOE #3: Cadmium Concentrations were Detected in Nearby Aquifer Materials and Geochemical Conditions Support Mobilization	8
4.	Conclusions	11
5.	References	12

TABLES (IN TEXT)

Table A Operational History of OWAP

FIGURES (IN TEXT)

Figure A Scatter Plot of Cadmium Versus Boron and Sulfate Concentrations at Monitoring Well 22

Figure B Time Series Showing Mann-Kendall Trend Test Results for Cadmium and pH at Monitoring Well 22

Figure C Cadmium Speciation Results at Monitoring Well 22 (presented as the percent of total cadmium present on a molar basis)

FIGURES (ATTACHED)

Figure 1 Monitoring Well Location Map

Figure 2 Potentiometric Surface Map – September 13-14, 2022

Figure 3 Leachate Sample Location Map

APPENDICES

Appendix A Groundwater Elevation Contour Maps

ACRONYMS AND ABBREVIATIONS

40 C.F.R.	Title 40 of the Code of Federal Regulations
A5D	Assessment Monitoring Round 5
AP2	Ash Pond No. 2
AP4	Ash Pond No. 4
ASD	Alternate Source Demonstration
CCR	coal combustion residuals
CCR Rule	40 C.F.R. § 257 Subpart D
Closure Plan	Closure and Post-Closure Care Plan
CMA	Corrective Measures Assessment
DMG	Dynegy Midwest Generation, LLC
EPRI	Electric Power Research Institute
Geosyntec	Geosyntec Consultants, Inc.
GWPS	Groundwater Protection Standard
Hennepin East	includes Landfill, AP2, AP4, and East Ash Pond
HPP	Hennepin Power Plant
IEPA	Illinois Environmental Protection Agency
LOE(s)	line(s) of evidence
mg/kg	milligrams per kilogram
mg/L	milligrams per liter
MNA	monitored natural attenuation
mV	millivolts
NAVD88	North American Vertical Datum of 1988
No.	Number
NRT/OBG	Natural Resource Technology, an OBG Company
OWAP	Old West Ash Pond (Pond Number No. 1 and Pond No. 3) and Old West Polishing Pond
Ramboll	Ramboll Americas Engineering Solutions, Inc.
redox	reduction-oxidation
RL	reporting limit
SSI	Statistically Significant Increase
SSL	Statistically Significant Level
USGS	United States Geological Survey

1. INTRODUCTION

Title 40 of the Code of Federal Regulations (40 C.F.R.) § 257.95(g)(3)(ii) allows the owner or operator of a coal combustion residuals (CCR) unit 90 days from the date of determination of a Statistically Significant Level (SSL) over the Groundwater Protection Standard (GWPS) of groundwater constituents listed in Appendix IV of 40 C.F.R. § 257 to complete a written demonstration that a source other than the CCR unit being monitored caused the SSL(s), or that the SSL(s) resulted from error in sampling, analysis, statistical evaluation, or natural variation in groundwater quality (Alternate Source Demonstration [ASD]).

This ASD has been prepared on behalf of Dynegy Midwest Generation, LLC (DMG), by Ramboll Americas Engineering Solutions, Inc. (Ramboll) to provide pertinent information pursuant to 40 C.F.R. § 257.95(g)(3)(ii) for the Old West Ash Pond (Pond Number [No.] 1 and Pond No. 3) and Old West Polishing Pond, collectively referred to as the OWAP, located at Hennepin Power Plant (HPP) near Hennepin, Illinois.

The most recent Assessment Monitoring sampling event (Assessment Monitoring Round 5D [A5D]) samples were collected on September 13-14, 2022, and analytical data were received on October 31, 2022. Analytical data from A5D were evaluated in accordance with the Statistical Analysis Plan (Natural Resource Technology, an OBG Company [NRT/OBG], 2017a) to determine any Statistically Significant Increases (SSIs) of Appendix III parameters over background concentrations and SSLs of Appendix IV parameters over GWPSs. That evaluation identified the following SSLs at downgradient monitoring wells:

- Arsenic at wells 21R and 51
- Cadmium at well 22
- Lithium at well 22

A Corrective Measures Assessment (CMA) was completed in 2019 for the arsenic and lithium SSLs, and further evaluation of monitored natural attenuation (MNA) as an associated groundwater remedy is in progress.

Pursuant to 40 C.F.R. § 257.95(g)(3)(ii), the lines of evidence (LOEs) described in **Section 3** demonstrate that sources other than the OWAP were the cause of the cadmium SSL listed above. This ASD was completed by May 1, 2023, within 90 days of determination of the SSL, as required by 40 C.F.R. § 257.95(g)(3)(ii).

2. BACKGROUND

2.1 Site Location and Description

The HPP is located in the northwest quarter of Section 26, Township 33 North, Range 2 West, Putnam County, Illinois and approximately 3 miles north-northeast of the Village of Hennepin.

The OWAP is one of four CCR units regulated under 40 C.F.R. § 257 Subpart D (CCR Rule) at the HPP. Three CCR units (the Landfill, Ash Pond No. 2 [AP2], and the East Ash Pond) and one unit not regulated by the CCR Rule (Ash Pond No. 4 [AP4]) are located adjacent to each other and east of the HPP and are collectively known as Hennepin East. The OWAP is located west of the HPP. Areas surrounding the OWAP include agricultural land with scattered groupings or rows of trees to the southeast and low-lying floodplains of the Donnelley Wildlife Management Area to the southwest and west. The OWAP and surrounding properties are shown on **Figure 1**.

2.2 Groundwater Monitoring

The OWAP groundwater monitoring system for compliance with the CCR Rule consists of two background monitoring wells (32 and 34) and six compliance monitoring wells (21R, 22, 23, 35, 49, and 51). This monitoring network also includes two monitoring wells (22D and 50) installed to delineate groundwater impacts as required by 40 C.F.R. § 257.95(g)(1). A map showing the groundwater monitoring system, including the CCR unit and monitoring wells, is presented in **Figure 1**.

Groundwater samples are collected and analyzed in accordance with the Sampling and Analysis Plan prepared for the OWAP (NRT/OBG, 2017b). Statistical evaluation of analytical data is performed in accordance with the Statistical Analysis Plan (NRT/OBG, 2017a).

2.3 Site History

The HPP has two coal-fired generating units constructed in 1953 and 1959 with a total capacity of 210 Megawatts. Operations were ceased in November 2019. The coal source changed several times during the plant's operational history.

DMG operated the OWAP from 1952 through 1996. It consists of two closed units, the Old West Ash Pond and the Old West Polishing Pond (**Figure 1**). The Old West Ash Pond consists of the 9.3-acre Pond No. 1 at the eastern end of the impoundment and the 16.4-acre Pond No. 3 within the central portion of the impoundment. The 4.7-acre Old West Polishing Pond is situated at the western end of the impoundment. All ponds were previously bermed to approximately 15 feet above grade using locally occurring sandy soils. A portion of the Old West Polishing Pond berm was removed after CCR material was removed during closure of this unit in 2020.

During operation, service water was used to sluice fly ash, bottom ash, and low-volume wastes to the OWAP. At the time it was removed from service in late 1996, there was no surface water discharge and all sluice water ex-filtrated via evapotranspiration, seepage through the berms, or leakage through the base of the ponds. Coal ash sluiced to the OWAP was a by-product of the combustion of high-sulfur Illinois coal. The operational history of the OWAP is summarized in **Table A** below.

Table A. Operational History of OWAP

Date	Event
1952-1955	Construction of OWAP, Pond No. 1. Berms were constructed from locally sandy materials to an original elevation (since modified) of 457 feet NAVD88.
1968	Construction of OWAP, Pond No. 3. Berms were constructed to an elevation of 457 feet NAVD88.
1979	Berms surrounding the OWAP were raised by three feet to an elevation of 460 feet NAVD88.
1988-1989	Ponds No. 1 and No. 3 within the OWAP were consolidated and divided into primary and secondary cells, and the berm around the primary portion was raised five feet to an elevation of 465 feet NAVD88. It was after this consolidation that surface water discharge from the impoundment ceased.
1996	OWAP Ponds No. 1 and No. 3 were removed from service.
2020	OWAP Ponds No. 1 and No. 3 were closed in-place and Old West Polishing Pond was closed by removal (CCR consolidated into Ponds No. 1 and No. 3) in accordance with the IEPA-approved closure plan.

NAVD88 = North American Vertical Datum of 1988

The *Closure and Post-Closure Care Plan, Old West Ash Pond, Old West Polishing Pond at DMG, Hennepin Power Station* (Closure Plan) was submitted to Illinois Environmental Protection Agency (IEPA) in 2017 (Geosyntec Consultants, Inc. [Geosyntec], 2017). The Closure Plan was approved by IEPA in a letter dated June 19, 2018. The approved Closure Plan summarized the planned closure of the OWAP, which included dewatering the CCR, if needed, mechanical excavation of material from the Old West Polishing Pond for use as structural fill in the OWAP, grading within the OWAP, constructing an alternative cover system consisting of geomembrane and vegetated cover soils in direct contract with the graded CCR, and establishment of a vegetative cover. Closure construction was completed on November 17, 2020.

2.4 Site Hydrogeology and Stratigraphy

A detailed hydrogeological assessment of the HPP was completed and submitted as part of the Closure Plan (NRT/OBG, 2017c) Information pertinent to this ASD is included in this report; however, more complete information on site hydrogeology and stratigraphy is available in the Closure Plan (Geosyntec, 2017).

There are three dominant geomorphic features in the immediate vicinity of the HPP: an upper river terrace at an elevation of about 500 to 550 feet NAVD88, a lower river terrace at an elevation of about 450 to 460 feet NAVD88, and the current river valley filled with alluvium to an elevation of about 445 feet NAVD88. The HPP and the eastern portion of the OWAP (Pond No. 1) are on the lower terrace. The western portion of the OWAP (Pond No. 3 and Old West Polishing Pond) overlies alluvium.

The hydrogeological assessment identified that the stratigraphy within and immediately surrounding the OWAP consists of fill, unlithified river alluvium, and Pleistocene-age glacial outwash deposits overlying Pennsylvanian-age shale bedrock. The perimeter berms of the OWAP contain variable amounts of CCR and re-worked native silt, clay, and sand. Where undisturbed or partially excavated, the native surficial soil at the site is poorly drained, moderately permeable silty clay loam formed as alluvium in floodplains.

There are two hydrogeologic units present at the HPP: alluvium and Henry Formation sands and gravels. The river laid deposits are identified as Cahokia Alluvium. The Henry Formation sands and gravels make up the upper and lower terraces and fill the valley beneath the alluvium. The Henry Formation and alluvium together comprise the Uppermost Aquifer at the OWAP and extend from the water table to the bedrock.

The OWAP overlies both glacial deposits (Henry Formation) and alluvium (Cahokia Alluvium). The OWAP, specifically Pond No. 1, rests on top of lower terrace glacial deposits, and the eastern portion of Pond No. 3 overlies alluvial sand. The western portion of Pond No. 3 and the Old West Polishing Pond overlie silty clay alluvial channel fill deposits.

The Pennsylvanian-age bedrock consists of interbedded layers of shale with thin limestone, sandstone, and coal beds. The shale bedrock unit has low hydraulic conductivity and defines the lower boundary of the Uppermost Aquifer.

The direction of groundwater flow and hydraulic gradient within the Uppermost Aquifer varies with the elevation of the Illinois River (select groundwater elevation contour maps are provided in **Appendix A**). During normal river stage the direction of groundwater flow is most often toward the river, but comparison of groundwater and river elevation data indicate reversals in this flow direction during times of high river elevations. The relative duration of these events is short, which leads to the determination of a predominant groundwater flow direction toward the river.

Groundwater elevations were obtained from measurements in monitoring wells on September 13-14, 2022 prior to the ASD sampling event at the site. Groundwater elevations for the OWAP during the ASD sampling event are shown in **Figure 2** and ranged from 444.74 feet NAVD88 (in well 33) to 448.60 feet NAVD88 (in well 36). Groundwater flow was generally toward the Illinois River.

3. ALTERNATE SOURCE DEMONSTRATION: LINES OF EVIDENCE

As allowed by 40 C.F.R. § 257.95(g)(3)(ii), this ASD demonstrates that sources other than the OWAP (the CCR unit) caused the cadmium SSL. LOEs supporting this ASD include the following:

1. Concentrations of cadmium are lower than those observed in leachate samples.
2. Cadmium concentrations are negatively correlated with concentrations of CCR indicator parameters.
3. Cadmium concentrations were detected in nearby aquifer materials and geochemical conditions support mobilization.

Data and information supporting these LOEs are discussed in more detail below.

3.1 LOE #1: Concentrations of Cadmium are Lower than those Observed in Leachate Samples

Leachate samples were collected from multiple locations within the OWAP in April and September of 2017 (**Figure 3**). Analytical results from locations L4, LPZ1, LPZ3, and LPZ17, sampled on April 25, 2017, indicate that total cadmium concentrations were less than laboratory reporting limits (RL) (less than 0.001 milligrams per liter [mg/L]). Analytical results from locations L4 and LPZ17, sampled on September 6, 2017, indicate that the total cadmium concentration in the sample from L4 was below the RL (less than 0.001 mg/L) and the total cadmium concentration in the sample from LPZ17 was 0.0013 mg/L.

The cadmium concentrations detected in the leachate samples are less than the lower confidence limit of cadmium concentrations observed in well 22 (0.00527 mg/L).

3.2 LOE #2: Cadmium Concentrations are Negatively Correlated with Concentrations of CCR Indicator Parameters

Boron and sulfate are common indicators of CCR impacts to groundwater due to their leachability from CCR and mobility in groundwater (Electric Power Research Institute [EPRI], 2012). If an SSL is identified for a monitored parameter but concentrations of boron and sulfate are not correlated with that parameter, it is unlikely that the CCR unit is the source of the SSL.

Figure A on the following page provides a scatter plot of cadmium versus boron and sulfate concentrations (collected from 2015 through the ASD sampling event) in monitoring well 22 (the location of the cadmium SSL), along with the results of a Spearman correlation test for non-parametric data (these data were determined to be not normally distributed). The results of the test at each well are described by the p-value and rho (Spearman correlation coefficient) included in each plot. Typically, a p-value greater than 0.05 is considered to be a statistically insignificant relationship. The range of rho falls between -1 and 1, with a perfect correlation equal to -1 or 1. The closer rho is to 0, the less of a correlation exists in the data.

The results of the correlation analyses indicates that concentrations of cadmium observed at monitoring well 22 are negatively correlated with concentrations of boron and sulfate, common indicators of CCR impacts to groundwater. **Figure A** illustrates the inverse relationship between

cadmium concentrations and boron or sulfate concentrations in groundwater at monitoring well 22, where the p-values are less than 0.001 and rho is close to -1.




Figure A. Scatter Plot of Cadmium Versus Boron and Sulfate Concentrations at Monitoring Well 22

Cadmium concentrations are negatively correlated with boron and sulfate concentrations in the downgradient monitoring well, indicating the OWAP is not the source of the cadmium SSL.

3.3 LOE #3: Cadmium Concentrations were Detected in Nearby Aquifer Materials and Geochemical Conditions Support Mobilization

Soil samples were collected from four borings near the East Ash Pond in 2021 to support a Hydrogeologic Characterization Report for the East Ash Pond (Ramboll, 2021). Results of chemical analyses of the soil samples indicate that cadmium concentrations in the Henry Formation sands and gravels ranged from 1.13 to 1.65 milligrams per kilogram (mg/kg) with an average cadmium concentration of 1.36 mg/kg. Results of cadmium analyses from samples within the Cahokia Alluvium were slightly more variable, ranging from 0.57 to 1.34 mg/kg, with an average cadmium concentration of 0.97 mg/kg. Additionally, a sample of bedrock was obtained and yielded a cadmium concentration of 0.75 mg/kg. The Cahokia alluvium, Henry Formation, and bedrock tested at the East Ash Pond are all present at the OWAP as documented in the Hydrogeologic Characterization Report (NRT/OBG, 2017c).

Geochemical conditions that would affect cadmium mobility in groundwater at monitoring well 22 were evaluated. The primary geochemical conditions influencing cadmium mobility in non-sulfidic groundwater are pH and the association of cadmium with ligands. Cadmium will desorb from solid phases, and therefore exhibit greater mobility in groundwater, under lower pH conditions (Kubier et al., 2019). Additionally, cadmium can be mobilized from the solid phase via forming soluble complexes with certain ligands (e.g., CdCl^+ , $\text{Cd}(\text{SO}_4)_2^{2-}$, or dissolved organic molecules) (Kubier et al., 2019). Because reduction-oxidation (redox) conditions at monitoring well 22 are insufficiently reducing to drive sulfide formation, sulfide is unlikely to occur at monitoring well 22. Therefore, the potential for pH and the formation of soluble cadmium complexes to mobilize cadmium at well 22 were assessed as described below.

Changes in pH at monitoring well 22 were evaluated using a Mann-Kendall trend test. Over the same time frame that cadmium concentrations have been increasing, pH values exhibit a statistically significant downward trend (**Figure B**). Because cadmium is more mobile in groundwater under lower pH conditions, the decrease in pH could have contributed to the increased mobilization and concentrations of cadmium in groundwater at monitoring well 22.




Figure B. Time Series Showing Mann-Kendall Trend Test Results for Cadmium and pH at Monitoring Well 22

Complexation with chloride and sulfate can also contribute to cadmium mobilization from the solid phase due to the formation of more mobile species (Kubier et al., 2019). Therefore, a basic cadmium speciation analysis was conducted using PHREEQC using the LLNL thermodynamic database¹ (United States Geological Survey [USGS], 2021). Samples included in the analysis were those collected under 40 C.F.R. § 257 monitoring, plus two samples collected in 2013. These earlier samples were included to achieve a more complete picture of geochemical conditions associated with low cadmium concentrations at monitoring well 22. Inputs to the speciation model were temperature, pH, redox potential, and concentrations of cadmium, chloride, and sulfate. For samples in which cadmium was not detected, the RL was used as the cadmium concentration input to the speciation model. Because redox measurements were not available for all samples, the median value (59.5 millivolts [mV], out of a range of -67 mV to 168 mV) was used as the redox input to the speciation model for all samples.

¹ Except for $\text{Cd}(\text{SO}_4)_2^{2-}$, which used thermodynamic data from the Oak Ridge National Laboratory AQUA-MER database.




Figure C. Cadmium Speciation Results at Monitoring Well 22 (presented as the percent of total cadmium present on a molar basis)

Eight cadmium species² were evaluated for their contribution to total cadmium, and only Cd²⁺ and CdCl⁺ contributed more than 1 percent to any sample (on a molar basis). **Figure C** shows the proportion of total cadmium that was present as Cd²⁺ and CdCl⁺ in each sample. When total cadmium concentrations were low, Cd²⁺ was the dominant cadmium species. Due to its higher charge, Cd²⁺ is more likely to sorb to aquifer solids (Kubier et al., 2019). Increasing total cadmium concentrations coincide with an increasing prevalence, and eventual predominance, of CdCl⁺, a more mobile cadmium species.

The downward trend in pH and the cadmium speciation analysis indicates that cadmium concentrations in groundwater samples from well 22 increased when geochemical conditions facilitated greater mobility of cadmium through dissolution out of the aquifer material due to lower pH and the increased formation of mobile CdCl⁺. The increase in cadmium concentrations was likely due to the cadmium naturally present in the Henry Formation becoming mobilized due to changing geochemical conditions.

² Cd²⁺, CdOH⁺, Cd(OH)₂, Cd(OH)Cl, CdCl⁺, CdCl₂, CdSO₄, Cd(SO₄)₂²⁻

4. CONCLUSIONS

Based on these three LOEs, it has been demonstrated that the OWAP is not the source of the cadmium SSL identified in well 22.

1. Concentrations of cadmium are lower than those observed in leachate samples.
2. Cadmium concentrations are negatively correlated with concentrations of CCR indicator parameters.
3. Cadmium concentrations were detected in nearby aquifer materials and geochemical conditions support mobilization.

Based on the LOEs presented, the following alternate sources are the cause of the SSL observed in the OWAP compliance well:

- Cadmium: SSL for cadmium may be caused by mobilization of naturally occurring cadmium out of aquifer materials due to favorable geochemical conditions.

This information serves as the written ASD report prepared in accordance with 40 C.F.R. § 257.95(g)(3)(ii) that the cadmium SSL observed during the ASD monitoring event was not caused by the OWAP but was from other sources.

5. REFERENCES

Electric Power Research Institute (EPRI), 2012. Groundwater Quality Signatures for Assessing Potential Impacts from Coal Combustion Product Leachate. EPRI, Palo Alto, CA. 1017923.

Geosyntec Consultants, Inc. (Geosyntec), 2017. Closure and Post Closure Care Plan, Old West Ash Pond, Old West Polishing Pond at Dynegy Midwest Generation, LLC, Hennepin Power Station.

Kubier A, Wilkin RT, and Pichler T., 2019. Cadmium in soils and groundwater: A review. *Appl Geochem* 108: 1-16. 10.1016/j.apgeochem.2019.104388.

Natural Resource Technology, an OBG Company (NRT/OBG), 2017a. Statistical Analysis Plan, Baldwin Energy Complex, Havana Power Station, Hennepin Power Station, Wood River Power Station, Dynegy Midwest Generation, LLC. October 17, 2017.

Natural Resource Technology, an OBG Company (NRT/OBG), 2017b. Sampling and Analysis Plan, Old West Ash Pond (Pond No. 1 and Pond No. 3) and Hennepin Old West Polishing Pond, Hennepin Power Station, Hennepin, Illinois, Project No. 2285, Revision 0. October 17, 2017.

Natural Resource Technology, an OBG Company (NRT/OBG), 2017c. Hydrogeologic Site Characterization Report, West Ash Pond System, Hennepin Power Station, Hennepin, Illinois. December 20, 2017.

Ramboll Americas Engineering Solutions, Inc. (Ramboll), 2021. Hydrogeologic Site Characterization Report, East Ash Pond, Hennepin Power Plant, Hennepin, Illinois. October 25, 2021.

United States Environmental Protection Agency, 2020. Disposal of Coal Combustion Residuals from Electric Utilities, 40 C.F.R. § 257 Subpart D, published April 17, 2015, updated 2020. Accessed from URL <https://www.ecfr.gov/current/title-40/chapter-I/subchapter-I/part-257/subpart-D#page-top>

United States Geological Survey (USGS), 2021. PHREEQC. Version 3. Accessed from URL <https://www.usgs.gov/software/phreeqc-version-3>

FIGURES



- COMPLIANCE MONITORING WELL
- BACKGROUND MONITORING WELL
- MONITORING WELL
- PART 257 REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- SITE FEATURE
- PROPERTY BOUNDARY

0 200 400
Feet


MONITORING WELL LOCATION
MAP

ALTERNATE SOURCE DEMONSTRATION
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

FIGURE 1

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.





- COMPLIANCE MONITORING WELL
- BACKGROUND MONITORING WELL
- MONITORING WELL
- GROUNDWATER ELEVATION CONTOUR (1-FT CONTOUR INTERVAL, NAVD88)
- INFERRED GROUNDWATER ELEVATION CONTOUR
- GROUNDWATER FLOW DIRECTION
- WEST ASH POND SYSTEM
- LIMITS OF FINAL COVER
- PROPERTY BOUNDARY

NOTES:
1. ELEVATIONS IN PARENTHESES WERE NOT USED FOR CONTOURING.
2. ELEVATION CONTOURS SHOWN IN FEET, NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)
*ILLINOIS RIVER ELEVATION OBTAINED FROM STAFF GAGE SG02, LOCATED AT THE HENNEPIN POWER PLANT



**POTENTIOMETRIC SURFACE MAP
SEPTEMBER 13-14, 2022**

**ALTERNATE SOURCE DEMONSTRATION
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS**

FIGURE 2

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.





Service Layer Credits: Source: Esri, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

LEACHATE SAMPLE LOCATION MAP

ALTERNATE SOURCE DEMONSTRATION
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

FIGURE 3

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.



APPENDICES


APPENDIX A

GROUNDWATER ELEVATION CONTOUR MAPS

9/11/2019 2:57:49 PM

Y:\Mapping\Projects\2202285\MXD\GW Contours\Round 2019 20\HennepinWest_GW Contours.mxd

Service Layer Credits: Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community




NOTES:
 * = GROUNDWATER ELEVATIONS WERE NOT USED FOR CONTOURING
 NM = NOT MEASURED
 GROUNDWATER ELEVATIONS IN FEET NAVD88.
 GAUGING DATA FROM USGS 05558300 ILLINOIS RIVER AT HENRY, IL LOCATED APPROXIMATELY 15 MILES DOWNSTREAM OF HENNEPIN POWER STATION.

- CCR RULE MONITORING WELL LOCATION
- NON-CCR RULE MONITORING WELL LOCATION
- GROUNDWATER ELEVATION CONTOUR (1-FOOT INTERVAL)
- - - INFERRED GROUNDWATER ELEVATION CONTOUR
- GROUNDWATER FLOW DIRECTION
- CCR MONITORED MULTI-UNIT
- CCR UNIT

HENNEPIN OLD WEST ASH POND (POND NO.1 AND POND NO. 3) AND HENNEPIN OLD WEST POLISHING POND (UNIT ID: 804)
 GROUNDWATER ELEVATION CONTOUR MAP
 JUNE 18, 2019

CCR RULE GROUNDWATER MONITORING
 HENNEPIN POWER STATION
 HENNEPIN, ILLINOIS




O'BRIEN & GERE ENGINEERS, INC.

10/17/2019 6:24:07 PM


Y:\Mapping\Projects\222285\MXD\GW Contours\Round 2019 30\PR2019 30 HennepinWest GW Contours.mxd

Service Layer Credits: Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community



HENNEPIN OLD WEST ASH POND (POND NO.1 AND POND NO. 3) AND HENNEPIN OLD WEST POLISHING POND (UNIT ID: 804)
 GROUNDWATER ELEVATION CONTOUR MAP
 SEPTEMBER 17, 2019

CCR RULE GROUNDWATER MONITORING
 HENNEPIN POWER STATION
 HENNEPIN, ILLINOIS



O'BRIEN & GERE ENGINEERS, INC.

Prepared for
Dynegy Midwest Generation, LLC

Date
October 11, 2023

Project No.
1940103649-010

**40 C.F.R. § 257.95(G)(3)(II):
ALTERNATIVE SOURCE
DEMONSTRATION
OLD WEST ASH POND (POND NO. 1 AND
POND NO. 3) AND OLD WEST POLISHING
POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS
CCR UNIT 804**

CERTIFICATIONS

I, Eric J. Tlachac, a qualified professional engineer in good standing in the State of Illinois, certify that the information in this report is accurate as of the date of my signature below. The content of this report is not to be used other than for its intended purpose and meaning, or for extrapolations beyond the interpretations contained herein.


Eric J. Tlachac
Qualified Professional Engineer
062-063091
Illinois
Ramboll Americas Engineering Solutions, Inc.
Date: October 11, 2023



I, Brian G. Hennings, a professional geologist in good standing in the State of Illinois, certify that the information in this report is accurate as of the date of my signature below. The content of this report is not to be used other than for its intended purpose and meaning, or for extrapolations beyond the interpretations contained herein.


Brian G. Hennings
Professional Geologist
196-001482
Illinois
Ramboll Americas Engineering Solutions, Inc.
Date: October 11, 2023



CONTENTS

1.	Introduction	3
2.	Background	4
2.1	Site Location and Description	4
2.2	Groundwater Monitoring	4
2.3	Site History	4
2.4	Site Hydrogeology and Stratigraphy	5
3.	Alternative Source Demonstration: Lines of Evidence	7
3.1	LOE #1: Concentrations of Cadmium in Porewater Samples are Lower Than Those Observed in Well 22	7
3.2	LOE #2: Cadmium Concentrations are Not Correlated with Concentrations of CCR Indicator Parameters	7
3.3	LOE #3: An Aquifer Solids and Geochemical Evaluation Identified Naturally Occurring Cadmium Associated with the Subsurface Alluvium as a Source of Cadmium in the Uppermost Aquifer that can be Mobilized Under Declining pH Conditions Observed at the WAPS	8
4.	Conclusions	10
5.	References	11

TABLES (IN TEXT)

Table A Operational History of the West Ash Pond System

FIGURES (IN TEXT)

Figure A Scatter Plot of Cadmium Versus Boron and Sulfate Concentrations at Monitoring Well 22

FIGURES (ATTACHED)

Figure 1 Monitoring Well Location Map

Figure 2 Potentiometric Surface Map – February 28, 2023

Figure 3 Leachate Sample Location Map

APPENDICES

Appendix A Groundwater Elevation Contour Maps

Appendix B Porewater Analytical Data

Appendix C Supporting Groundwater Analytical Data

Appendix D Technical Memorandum – Evaluation of Cadmium Sources within Aquifer Solids, Hennepin Power Plant – West Ash Pond System (Geosyntec Consultants, Inc., 2023)

ACRONYMS AND ABBREVIATIONS

40 C.F.R.	Title 40 of the Code of Federal Regulations
AP2	Ash Pond No. 2
AP4	Ash Pond No. 4
ASD	Alternative Source Demonstration
CCR	coal combustion residuals
CCR Rule	40 C.F.R. § 257 Subpart D
Closure Plan	Closure and Post-Closure Care Plan
CMA	Corrective Measures Assessment
DMG	Dynegy Midwest Generation, LLC
EPRI	Electric Power Research Institute
Geosyntec	Geosyntec Consultants, Inc.
GWPS	Groundwater Protection Standard
Hennepin East	includes Landfill, AP2, AP4, and East Ash Pond
HPP	Hennepin Power Plant
IEPA	Illinois Environmental Protection Agency
LOE(s)	line(s) of evidence
mg/L	milligrams per liter
MNA	monitored natural attenuation
NAVD88	North American Vertical Datum of 1988
No.	Number
NRT/OBG	Natural Resource Technology, an OBG Company
OWAP	Old West Ash Pond (Pond Number No. 1 and Pond No. 3) and Old West Polishing Pond
OWPP	Old West Polishing Pond
Ramboll	Ramboll Americas Engineering Solutions, Inc.
RL	reporting limit
SSI	Statistically Significant Increase
SSL	Statistically Significant Level
UA	Uppermost Aquifer
WAPS	West Ash Pond System CCR multi-unit, includes OWAP and OWPP

1. INTRODUCTION

Title 40 of the Code of Federal Regulations (40 C.F.R.) § 257.95(g)(3)(ii) allows the owner or operator of a coal combustion residuals (CCR) unit 90 days from the date of determination of a Statistically Significant Level (SSL) over the Groundwater Protection Standard (GWPS) of constituents listed in Appendix IV of 40 C.F.R. § 257 to complete a written demonstration that a source other than the CCR unit being monitored caused the SSL(s), or that the SSL(s) resulted from error in sampling, analysis, statistical evaluation, or natural variation in groundwater quality (Alternative Source Demonstration [ASD]).

This ASD has been prepared on behalf of Dynegy Midwest Generation, LLC (DMG), by Ramboll Americas Engineering Solutions, Inc. (Ramboll) to provide pertinent information pursuant to 40 C.F.R. § 257.95(g)(3)(ii) for the Old West Ash Pond (Pond Number [No.] 1 and Pond No. 3) (OWAP) and Old West Polishing Pond (OWPP), located at Hennepin Power Plant (HPP) near Hennepin, Illinois. The OWAP and OWPP are constituent parts of the CCR multi-unit system, collectively referred to as the West Ash Pond System (WAPS).

The most recent Assessment Monitoring sampling event (A6) samples were collected on February 28, 2023, and analytical data were received on April 14, 2023. Analytical data from A6 were evaluated in accordance with Multi-Site Sampling and Analysis Plan (SAP) (Ramboll, 2023) to determine any Statistically Significant Increases (SSIs) of Appendix III parameters over background concentrations and SSLs of Appendix IV parameters over GWPSs. That evaluation was completed by July 13, 2023, and identified the following SSLs at compliance monitoring wells:

- Arsenic at wells 21R and 51
- Cadmium at well 22

A Corrective Measures Assessment (CMA) was completed in 2019 that applies to the arsenic SSL, and further evaluation of monitored natural attenuation (MNA) as an associated groundwater remedy is in progress.

Pursuant to 40 C.F.R. § 257.95(g)(3)(ii), the lines of evidence (LOEs) described in **Section 3** demonstrate that sources other than the WAPS were the cause of the cadmium SSL listed above. This ASD was completed by October 11, 2023, within 90 days of determination of the SSL, as required by 40 C.F.R. § 257.95(g)(3)(ii).

2. BACKGROUND

2.1 Site Location and Description

The HPP is located in the northwest quarter of Section 26, Township 33 North, Range 2 West, Putnam County, Illinois and approximately 3 miles north-northeast of the Village of Hennepin.

The WAPS is one of four CCR units regulated under 40 C.F.R. § 257 Subpart D (CCR Rule) at the HPP. Three CCR units (the Landfill, Ash Pond No. 2 [AP2], and the East Ash Pond) and one unit not regulated by the CCR Rule (Ash Pond No. 4 [AP4]) are located adjacent to each other and east of the HPP and are collectively known as Hennepin East. The WAPS is located west of the HPP. Areas surrounding the WAPS include agricultural land with scattered groupings or rows of trees to the southeast and low-lying floodplains of the Donnelley Wildlife Management Area to the southwest and west. The WAPS and surrounding properties are shown on **Figure 1**.

2.2 Groundwater Monitoring

The WAPS groundwater monitoring system for compliance with the CCR Rule consists of two background monitoring wells (32 and 34) and nine compliance monitoring wells (21R, 22, 22D, 23, 27, 35, 49, 50, and 51) (Ramboll, 2022a). A map showing the groundwater monitoring system, including the CCR unit and monitoring wells, is presented in **Figure 1**.

Groundwater samples are collected and analyzed in accordance with the Multi-Site SAP (Ramboll, 2023). Statistical evaluation of analytical data is performed in accordance with Multi-Site Statistical Analysis Plan (Ramboll, 2022b).

2.3 Site History

The HPP has two coal-fired generating units constructed in 1953 and 1959 with a total capacity of 210 Megawatts. Operations were ceased in November 2019.

DMG operated the WAPS from 1952 through 1996. It consists of two closed units, the OWAP and the OWPP (**Figure 1**). The OWAP consists of the 9.3-acre Pond No. 1 at the eastern end of the impoundment and the 16.4-acre Pond No. 3 within the central portion of the impoundment. The 4.7-acre OWPP is situated at the western end of the impoundment. All ponds were previously bermed to approximately 15 feet above grade using locally occurring sandy soils. A portion of the OWPP berm was removed after CCR material was removed during closure of this unit in 2020.

During operation, service water was used to sluice fly ash, bottom ash, and low-volume wastes to the WAPS. At the time it was removed from service in late 1996, there was no surface water discharge and all sluice water ex-filtrated via evapotranspiration, seepage through the berms, or leakage through the base of the ponds. Coal ash sluiced to the WAPS was a by-product of the combustion of high-sulfur Illinois coal. The operational history of the WAPS is summarized in **Table A** on the following page.

Table A. Operational History of the West Ash Pond System

Date	Event
1952-1955	Construction of OWAP, Pond No. 1. Berms were constructed from locally sandy materials to an original elevation (since modified) of 457 feet NAVD88.
1968	Construction of OWAP, Pond No. 3. Berms were constructed to an elevation of 457 feet NAVD88.
1979	Berms surrounding the OWAP Ponds No. 1 and No. 3 were raised by three feet to an elevation of 460 feet NAVD88.
1988-1989	Ponds No. 1 and No. 3 within the OWAP were consolidated and divided into primary and secondary cells, and the berm around the primary portion was raised five feet to an elevation of 465 feet NAVD88. It was after this consolidation that surface water discharge from the impoundment ceased.
1996	OWAP Ponds No. 1 and No. 3 were removed from service.
2020	OWAP Ponds No. 1 and No. 3 were closed in place and OWPP was closed by removal (CCR consolidated into Ponds No. 1 and No. 3) in accordance with the IEPA-approved closure plan.

NAVD88 = North American Vertical Datum of 1988

The *Closure and Post-Closure Care Plan, Old West Ash Pond, Old West Polishing Pond at DMG, Hennepin Power Station* (Closure Plan) was submitted to Illinois Environmental Protection Agency (IEPA) in 2017 (Geosyntec Consultants, Inc. [Geosyntec], 2017). The Closure Plan was approved by IEPA in a letter dated June 19, 2018. The approved Closure Plan summarized the planned closure of the WAPS, which included dewatering the CCR, if needed, mechanical excavation of material from the OWPP for use as structural fill in the WAPS, grading within the WAPS, constructing an alternative cover system consisting of geomembrane and vegetated cover soils in direct contact with the graded CCR, and establishment of a vegetative cover. Closure construction was completed on November 17, 2020.

2.4 Site Hydrogeology and Stratigraphy

Information pertinent to this ASD is included in this report; however, a detailed hydrogeological assessment of the site hydrogeology and stratigraphy of the HPP was completed and included in the Hydrogeologic Site Characterization Report, submitted as part of the Closure Plan (NRT/OBG, 2017).

There are three dominant geomorphic features in the immediate vicinity of the HPP: an upper river terrace at an elevation of about 500 to 550 feet NAVD88, a lower river terrace at an elevation of about 450 to 460 feet NAVD88, and the current river valley filled with alluvium to an elevation of about 445 feet NAVD88. The HPP and the eastern portion of the WAPS (OWAP Pond No. 1) are on the lower terrace. The western portion of the WAPS (OWAP Pond No. 3 and OWPP) overlies alluvium.

The hydrogeological assessment identified that the stratigraphy within and immediately surrounding the WAPS consists of fill, unlithified river alluvium, and Pleistocene-age glacial outwash deposits overlying Pennsylvanian-age shale bedrock. The perimeter berms of the WAPS contain variable amounts of CCR and re-worked native silt, clay, and sand. Where undisturbed or

partially excavated, the native surficial soil at the site is poorly drained, moderately permeable silty clay loam formed as alluvium in floodplains.

There are two hydrogeologic units present at the HPP: alluvium and Henry Formation sands and gravels. The river laid deposits are identified as Cahokia Alluvium. The Henry Formation sands and gravels make up the upper and lower terraces and fill the valley beneath the alluvium. The Henry Formation and alluvium together comprise the Uppermost Aquifer (UA) at the WAPS and extend from the water table to the bedrock.

The WAPS overlies both glacial deposits (Henry Formation) and alluvium (Cahokia Alluvium). The WAPS, specifically OWAP Pond No. 1, rests on top of lower terrace glacial deposits, and the eastern portion of Pond No. 3 overlies alluvial sand. The western portion of Pond No. 3 and the OWPP overlie silty clay alluvial channel fill deposits.

The Pennsylvanian-age bedrock consists of interbedded layers of shale with thin limestone, sandstone, and coal beds. The shale bedrock unit has low hydraulic conductivity and defines the lower boundary of the UA.

The direction of groundwater flow and hydraulic gradient within the UA varies with the elevation of the Illinois River (select groundwater elevation contour maps are provided in **Appendix A**). During normal river stage the direction of groundwater flow is most often toward the river, but comparison of groundwater and river elevation data indicate reversals in this flow direction during times of high river elevations. The relative duration of these events is short, which leads to the determination of a predominant groundwater flow direction toward the river.

Groundwater elevations for the WAPS during the A6 sampling event on February 28, 2023 are shown in **Figure 2** and ranged from 446.09 feet NAVD88 (in well 23) to 447.20 feet NAVD88 (in well 50). During this monitoring event, the Illinois River elevation was observed to be greater than the groundwater elevations observed in wells near the river, which can lead to temporary reversal in groundwater flow as mentioned in the preceding paragraph. The groundwater elevation contours on the potentiometric surface map (**Figure 2**) illustrate the presence of relatively high groundwater elevations originating from the Illinois River to the north. Under these hydraulic conditions, groundwater will flow towards the lower heads (*i.e.*, well 23).

3. ALTERNATIVE SOURCE DEMONSTRATION: LINES OF EVIDENCE

As allowed by 40 C.F.R. § 257.95(g)(3)(ii), this ASD demonstrates that sources other than the WAPS (the CCR unit) caused the cadmium SSL. LOEs supporting this ASD include the following:

1. Concentrations of cadmium in porewater samples are lower than those observed in well 22.
2. Cadmium concentrations are not correlated with concentrations of CCR indicator parameters.
3. An aquifer solids and geochemical evaluation identified naturally occurring cadmium associated with the subsurface alluvium as a source of cadmium in the Uppermost Aquifer that can be mobilized under declining pH conditions observed at the WAPS.

Data and information supporting these LOEs are discussed in more detail below.

3.1 LOE #1: Concentrations of Cadmium in Porewater Samples are Lower Than Those Observed in Well 22

Porewater samples were collected from multiple locations shown on **Figure 3** within the WAPS in April and September of 2017 (**Appendix B**). Analytical results from locations L4, LPZ1, LPZ3, and LPZ17, sampled on April 25, 2017, indicate that total cadmium concentrations were less than laboratory reporting limits (RL) (less than 0.001 milligrams per liter [mg/L]). Analytical results from locations L4 and LPZ17, sampled on September 6, 2017, indicate that the total cadmium concentration in the sample from L4 was below the RL (less than 0.001 mg/L) and the total cadmium concentration in the sample from LPZ17 was 0.0013 mg/L.

The cadmium concentrations detected in the leachate samples are less than the lower confidence limit of cadmium concentrations observed in well 22 (0.00614 mg/L). Analytical data used to support the calculation of lower confidence limits are included in **Appendix C**.

3.2 LOE #2: Cadmium Concentrations are Not Correlated with Concentrations of CCR Indicator Parameters

Boron and sulfate are common indicators of CCR impacts to groundwater due to their leachability from CCR and mobility in groundwater (Electric Power Research Institute [EPRI], 2012). If an SSL is identified for a monitored parameter but concentrations of boron and sulfate are not correlated with that parameter, it is unlikely that the CCR unit is the source of the SSL.

Figure A on the following page provides a scatter plot of cadmium versus boron and sulfate concentrations (collected from 2015 through the A6 sampling event) in monitoring well 22 (the location of the cadmium SSL), along with the results of a Kendall correlation test for non-parametric data (these data were determined to be not normally distributed). The results of the test at each well are described by the p-value and tau (Kendall correlation coefficient) included in each plot. Typically, a p-value greater than 0.05 is considered to be a statistically insignificant relationship. The range of tau falls between -1 and 1, with a perfect correlation equal to -1 or 1. The closer tau is to 0, the less of a correlation exists in the data.

The results of the correlation analyses indicate that concentrations of cadmium observed at monitoring well 22 are not correlated with concentrations of boron and sulfate, common indicators of CCR impacts to groundwater. **Figure A** illustrates the inverse relationship between cadmium concentrations and boron or sulfate concentrations in groundwater at monitoring well 22, where the p-values are less than 0.001 and tau values are negative.




Figure A. Scatter Plot of Cadmium Versus Boron and Sulfate Concentrations at Monitoring Well 22

Cadmium concentrations are not correlated with boron and sulfate concentrations in compliance monitoring well 22, indicating the WAPS is not the source of the cadmium SSL. Analytical data used to support this correlation analysis is included in **Appendix C**.

3.3 LOE #3: An Aquifer Solids and Geochemical Evaluation Identified Naturally Occurring Cadmium Associated with the Subsurface Alluvium as a Source of Cadmium in the Uppermost Aquifer that can be Mobilized Under Declining pH Conditions Observed at the WAPS

Solid phase analyses were completed on samples of UA materials collected from the Site to support the conclusion that cadmium concentrations in groundwater observed in well 22 are associated with naturally occurring cadmium in the UA materials. A review of the geochemical and site conditions to evaluate the influence of the UA solid-phase mineralogy and geochemistry on groundwater composition was completed by Geosyntec and is included as **Appendix D**. The following conclusions were made based on the results of the aquifer solids evaluation and geochemical modeling:

- Solid-phase samples collected from soil borings completed near background well 34 and compliance well 22 contained cadmium, with the highest total cadmium concentrations observed in samples collected from the screened interval of well 22.
- The majority of cadmium in the solid phase is associated with the weak acid extractable fraction (which includes carbonates) and the reducing agent extractable fraction (which includes iron/manganese oxides). Carbonate minerals make up approximately 18-25% of

the solid phase materials and magnetite (an iron oxide mineral) was present in all solid phase samples.

- Literature supports two potential mechanisms of cadmium mobilization under declining pH conditions observed at the WAPS: the dissolution of calcite containing coprecipitated cadmium, and the desorption of cadmium from iron oxide mineral surfaces.
- There has been a downward shift in pH in groundwater at well 22 since approximately 2013 with a corresponding increase in cadmium concentrations.
- Thermodynamic reaction pathway modeling supports the conclusion that both mechanisms of cadmium mobilization (dissolution of cadmium-substituted carbonate minerals and desorption from iron oxides) should occur within the range of the observed groundwater pH decrease at well 22.

Evaluation of the solid phase material and geochemical modeling results using site-specific solid-phase data suggest that naturally occurring cadmium associated with the subsurface alluvium comprising the UA at the Site may drive the cadmium concentrations at well 22 under changing geochemical conditions.

4. CONCLUSIONS

Based on these three LOEs, it has been demonstrated that the WAPS is not the source of the cadmium SSL identified in well 22.

1. Concentrations of cadmium in porewater samples are lower than those observed in well 22.
2. Cadmium concentrations are not correlated with concentrations of CCR indicator parameters.
3. An aquifer solids and geochemical evaluation identified naturally occurring cadmium associated with the subsurface alluvium as a source of cadmium in the Uppermost Aquifer that can be mobilized under declining pH conditions observed at the WAPS.

Based on the LOEs presented, the following alternative sources are the cause of the SSL observed in the WAPS compliance well 22:

- Cadmium: SSL for cadmium is caused by mobilization of naturally occurring cadmium out of aquifer materials due to favorable geochemical conditions.

This information serves as the written ASD report prepared in accordance with 40 C.F.R. § 257.95(g)(3)(ii) that the cadmium SSL observed during the A6 monitoring event was not caused by the WAPS but was from other sources.

5. REFERENCES

Code of Federal Regulations, Title 40, Chapter I, Subchapter I, Part 257, Subpart D, Standards for the Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments, effective April 17, 2015. Accessed from URL <https://www.ecfr.gov/current/title-40/chapter-I/subchapter-I/part-257/subpart-D#page-top>

Electric Power Research Institute (EPRI), 2012. Groundwater Quality Signatures for Assessing Potential Impacts from Coal Combustion Product Leachate. EPRI, Palo Alto, CA. 1017923.

Geosyntec Consultants, Inc. (Geosyntec), 2017. Closure and Post Closure Care Plan, Old West Ash Pond, Old West Polishing Pond at Dynegy Midwest Generation, LLC, Hennepin Power Station.

Geosyntec Consultants, Inc., 2023. Technical Memorandum – Evaluation of Cadmium Sources within Aquifer Solids, Hennepin Power Plant – West Ash Pond System, September 12, 2023.

Natural Resource Technology, an OBG Company (NRT/OBG), 2017. Hydrogeologic Site Characterization Report, West Ash Pond System, Hennepin Power Station, Hennepin, Illinois. December 20, 2017.

Ramboll Americas Engineering Solutions, Inc. (Ramboll), 2022a. 40 C.F.R. § 257 Groundwater Monitoring Plan, West Ash Pond System, Hennepin Power Plant, Hennepin, Illinois. December 28, 2022.

Ramboll Americas Engineering Solutions, Inc. (Ramboll), 2022b. *Multi-Site Statistical Analysis Plan*. December 28, 2022.

Ramboll Americas Engineering Solutions, Inc. (Ramboll), 2023. *Multi-Site Sampling and Analysis Plan, Revision 1*. October 10, 2023.

FIGURES



- COMPLIANCE MONITORING WELL
- BACKGROUND MONITORING WELL
- MONITORING WELL
- 40 C.F.R. § 257 REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- SITE FEATURE
- PROPERTY BOUNDARY

0 200 400
Feet


MONITORING WELL LOCATION
MAP

ALTERNATE SOURCE DEMONSTRATION
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

FIGURE 1

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.





- COMPLIANCE MONITORING WELL
- BACKGROUND MONITORING WELL
- MONITORING WELL
- GROUNDWATER ELEVATION CONTOUR (1 FT CONTOUR INTERVAL, NAVD88)
- INFERRED GROUNDWATER ELEVATION CONTOUR
- GROUNDWATER FLOW DIRECTION
- 40 C.F.R. § 257 REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- PROPERTY BOUNDARY

NOTES:

1.ELEVATIONS IN PARENTHESES WERE NOT USED FOR CONTOURING.

2. ELEVATION CONTOURS SHOWN IN FEET, NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)

*ILLINOIS RIVER ELEVATION OBTAINED FROM STAFF GAGE SG02, LOCATED AT THE HENNEPIN POWER PLANT

0 200 400 Feet

POTENTIOMETRIC SURFACE MAP FEBRUARY 28, 2023

ALTERNATE SOURCE DEMONSTRATION
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

FIGURE 2

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.





- LEACHATE WELL
- 40 C.F.R. § 257 REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- PROPERTY BOUNDARY

0 200 400
Feet

LEACHATE SAMPLE LOCATION
MAP

ALTERNATE SOURCE DEMONSTRATION
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

FIGURE 3

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.



APPENDICES


APPENDIX A

GROUNDWATER ELEVATION CONTOUR MAPS

9/11/2019 2:57:49 PM


Y:\Mapping\Projects\22\2285\MXD\GW Contours\Round 2019 20\Round2019 20 HennepinWest GW Contours.mxd

Service Layer Credits: Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community



HENNEPIN OLD WEST ASH POND (POND NO.1 AND POND NO. 3) AND HENNEPIN OLD WEST POLISHING POND (UNIT ID: 804)
 GROUNDWATER ELEVATION CONTOUR MAP
 JUNE 18, 2019

CCR RULE GROUNDWATER MONITORING
 HENNEPIN POWER STATION
 HENNEPIN, ILLINOIS




O'BRIEN & GERE ENGINEERS, INC.

10/17/2019 6:24:07 PM


Y:\Mapping\Projects\222285\MXD\GW Contours\Round 2019 30\HennepinWest GW Contours.mxd

Service Layer Credits: Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community





HENNEPIN OLD WEST ASH POND (POND NO.1 AND POND NO. 3) AND HENNEPIN OLD WEST POLISHING POND (UNIT ID: 804)
 GROUNDWATER ELEVATION CONTOUR MAP
 SEPTEMBER 17, 2019

CCR RULE GROUNDWATER MONITORING
 HENNEPIN POWER STATION
 HENNEPIN, ILLINOIS



O'BRIEN & GERE ENGINEERS, INC.





GROUNDWATER ELEVATION CONTOUR MAP SEPTEMBER 2, 2020

HENNEPIN OLD WEST ASH POND
(POND NO.1 AND POND NO. 3)
AND HENNEPIN OLD WEST
POLISHING POND (UNIT ID: 804)
HENNEPIN POWER STATION
HENNEPIN, ILLINOIS

RAMBOLL US CORPORATION
A RAMBOLL COMPANY

RAMBOLL



PROJECT: 169000X.XXX | DATED: 3/25/2022 | DESIGNER: galammc
Y:\Mapping\Projects\22\2285\MXD\GW_Contours\Round_2021\Hennepin\OWAP_804\HEN OWAP GWE Contours D9A4D 20210908.mxd



- BACKGROUND WELL
- COMPLIANCE WELL
- MONITORING WELL
- GROUNDWATER ELEVATION CONTOUR (1 FT CONTOUR INTERVAL, NAVD88)
- INFERRED GROUNDWATER ELEVATION CONTOUR
- GROUNDWATER FLOW ARROW
- PART 257 REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- PROPERTY BOUNDARY

NOTES:
1.ELEVATIONS IN PARENTHESES WERE NOT USED FOR CONTOURING.
2. ELEVATION CONTOURS SHOWN IN FEET, NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)



**GROUNDWATER CONTOUR
ELEVATION MAP
SEPTEMBER 8, 2021**

**2021 ANNUAL GROUNDWATER MONITORING
AND CORRECTIVE ACTION REPORT
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS**

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.



Service Layer Credits: Source: Esri, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

PROJECT: 169000XXXX | DATED: 10/13/2022 | DESIGNER: galarmc
Y:\Mapping\Projects\22\2285MXD\GW_Contours\Round_2022\Hennepin\OWAP_804\HEN OWAP 804 Pot Surface 20220321.mxd



RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.





- COMPLIANCE MONITORING WELL
- BACKGROUND MONITORING WELL
- MONITORING WELL
- GROUNDWATER ELEVATION CONTOUR (1 FT CONTOUR INTERVAL, NAVD88)
- INFERRED GROUNDWATER ELEVATION CONTOUR
- GROUNDWATER FLOW DIRECTION
- PART 257 REGULATED UNIT (SUBJECT UNIT)
- LIMITS OF FINAL COVER
- PROPERTY BOUNDARY

NOTES:

1.ELEVATIONS IN PARENTHESES WERE NOT USED FOR CONTOURING.

2. ELEVATION CONTOURS SHOWN IN FEET, NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)

*ILLINOIS RIVER ELEVATION OBTAINED FROM STAFF GAGE SG02, LOCATED AT THE HENNEPIN POWER PLANT

0 200 400 Feet

GROUNDWATER CONTOUR ELEVATION MAP SEPTEMBER 13 AND 14, 2022

2022 ANNUAL GROUNDWATER MONITORING
AND CORRECTIVE ACTION REPORT
OLD WEST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.



APPENDIX B

POREWATER ANALYTICAL DATA

May 08, 2017

Steve Wiskes
Natural Resource Technology, Inc.
2422 East Washington Street
Suite 104
Bloomington, IL 61704
TEL: (414) 837-3614
FAX: (414) 837-3608



RE: Hennepin Pond 1 & 2 Additional Testing

WorkOrder: 17040224

Dear Steve Wiskes:

TEKLAB, INC received 9 samples on 4/27/2017 4:40:00 PM for the analysis presented in the following report.

Samples are analyzed on an as received basis unless otherwise requested and documented. The sample results contained in this report relate only to the requested analytes of interest as directed on the chain of custody. NELAP accredited fields of testing are indicated by the letters NELAP under the Certification column. Unless otherwise documented within this report, Teklab Inc. analyzes samples utilizing the most current methods in compliance with 40CFR. All tests are performed in the Collinsville, IL laboratory unless otherwise noted in the Case Narrative.

All quality control criteria applicable to the test methods employed for this project have been satisfactorily met and are in accordance with NELAP except where noted. The following report shall not be reproduced, except in full, without the written approval of Teklab, Inc.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,



Michael L. Austin
Project Manager
(618)344-1004 ex 16
MAustin@teklabinc.com



Report Contents

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

This reporting package includes the following:

Cover Letter	1
Report Contents	2
Definitions	3
Case Narrative	4
Laboratory Results	5
Sample Summary	18
Dates Report	19
Quality Control Results	23
Receiving Check List	34
Chain of Custody	Appended

Client: Natural Resource Technology, Inc.**Work Order:** 17040224**Client Project:** Hennepin Pond 1 & 2 Additional Testing**Report Date:** 08-May-17**Abbr Definition**

CCV	Continuing calibration verification is a check of a standard to determine the state of calibration of an instrument between recalibration.
DF	Dilution factor is the dilution performed during analysis only and does not take into account any dilutions made during sample preparation. The reported result is final and includes all dilutions factors.
DNI	Did not ignite
DUP	Laboratory duplicate is an aliquot of a sample taken from the same container under laboratory conditions for independent processing and analysis independently of the original aliquot.
ICV	Initial calibration verification is a check of a standard to determine the state of calibration of an instrument before sample analysis is initiated.
IDPH	IL Dept. of Public Health
LCS	Laboratory control sample, spiked with verified known amounts of analytes, is analyzed exactly like a sample to establish intra-laboratory or analyst specific precision and bias or to assess the performance of all or a portion of the measurement system. The acceptable recovery range is in the QC Package (provided upon request).
LCSD	Laboratory control sample duplicate is a replicate laboratory control sample that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).
MBLK	Method blank is a sample of a matrix similar to the batch of associated sample (when available) that is free from the analytes of interest and is processed simultaneously with and under the same conditions as samples through all steps of the analytical procedures, and in which no target analytes or interferences should present at concentrations that impact the analytical results for sample analyses.
MDL	Method detection limit means the minimum concentration of a substance that can be measured and reported with 99% confidence that the analyte concentration is greater than zero.
MS	Matrix spike is an aliquot of matrix fortified (spiked) with known quantities of specific analytes that is subjected to the entire analytical procedures in order to determine the effect of the matrix on an approved test method's recovery system. The acceptable recovery range is listed in the QC Package (provided upon request).
MSD	Matrix spike duplicate means a replicate matrix spike that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).
MW	Molecular weight
ND	Not Detected at the Reporting Limit
NELAP	NELAP Accredited
PQL	Practical quantitation limit means the lowest level that can be reliably achieved within specified limits of precision and accuracy during routine laboratory operation conditions. The acceptable recovery range is listed in the QC Package (provided upon request).
RL	The reporting limit the lowest level that the data is displayed in the final report. The reporting limit may vary according to customer request or sample dilution. The reporting limit may not be less than the MDL.
RPD	Relative percent difference is a calculated difference between two recoveries (ie. MS/MSD). The acceptable recovery limit is listed in the QC Package (provided upon request).
SPK	The spike is a known mass of target analyte added to a blank sample or sub-sample; used to determine recovery deficiency or for other quality control purposes.
Surr	Surrogates are compounds which are similar to the analytes of interest in chemical composition and behavior in the analytical process, but which are not normally found in environmental samples.
TIC	Tentatively identified compound: Analytes tentatively identified in the sample by using a library search. Only results not in the calibration standard will be reported as tentatively identified compounds. Results for tentatively identified compounds that are not present in the calibration standard, but are assigned a specific chemical name based upon the library search, are calculated using total peak areas from reconstructed ion chromatograms and a response factor of one. The nearest Internal Standard is used for the calculation. The results of any TICs must be considered estimated, and are flagged with a "T". If the estimated result is above the calibration range it is flagged "ET"
TNTC	Too numerous to count (> 200 CFU)

Qualifiers

# - Unknown hydrocarbon	B - Analyte detected in associated Method Blank
E - Value above quantitation range	H - Holding times exceeded
I - Associated internal standard was outside method criteria	M - Manual Integration used to determine area response
ND - Not Detected at the Reporting Limit	R - RPD outside accepted recovery limits
S - Spike Recovery outside recovery limits	T - TIC(Tentatively identified compound)
X - Value exceeds Maximum Contaminant Level	

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Cooler Receipt Temp: 4.62 °C

An employee of Teklab, Inc. collected the sample(s).

LPZ-5 will not be reported; the well was dry. TM/EAH 4/27/17

LPZ-17 to be used as alternate sampling point for LPZ-5. MLA 5/1/17

Locations and Accreditations

	Collinsville	Springfield	Kansas City	Collinsville Air
Address	5445 Horseshoe Lake Road Collinsville, IL 62234-7425	3920 Pintail Dr Springfield, IL 62711-9415	8421 Nieman Road Lenexa, KS 66214	5445 Horseshoe Lake Road Collinsville, IL 62234-7425
Phone	(618) 344-1004	(217) 698-1004	(913) 541-1998	(618) 344-1004
Fax	(618) 344-1005	(217) 698-1005	(913) 541-1998	(618) 344-1005
Email	jhriley@teklabinc.com	KKlostermann@teklabinc.com	KNelson@teklabinc.com	EHurley@teklabinc.com

State	Dept	Cert #	NELAP	Exp Date	Lab
Illinois	IEPA	100226	NELAP	1/31/2018	Collinsville
Kansas	KDHE	E-10374	NELAP	4/30/2018	Collinsville
Louisiana	LDEQ	166493	NELAP	6/30/2017	Collinsville
Louisiana	LDEQ	166578	NELAP	6/30/2017	Collinsville
Texas	TCEQ	T104704515-12-1	NELAP	7/31/2017	Collinsville
Arkansas	ADEQ	88-0966		3/14/2018	Collinsville
Illinois	IDPH	17584		5/31/2017	Collinsville
Indiana	ISDH	C-IL-06		1/31/2018	Collinsville
Kentucky	KDEP	98006		12/31/2017	Collinsville
Kentucky	UST	0073		1/31/2018	Collinsville
Missouri	MDNR	00930		5/31/2017	Collinsville
Missouri	MDNR	930		1/31/2018	Collinsville
Oklahoma	ODEQ	9978		8/31/2017	Collinsville

Client: Natural Resource Technology, Inc.
 Client Project: Hennepin Pond 1 & 2 Additional Testing
 Lab ID: 17040224-001
 Matrix: LEACHATE

Work Order: 17040224
 Report Date: 08-May-17

Client Sample ID: L4

Collection Date: 04/25/2017 17:22

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		11.10	ft	1	04/25/2017 0:00	R232332
STANDARD METHOD 4500-H B FIELD								
pH		1.00		7.60		1	04/25/2017 17:22	R232332
STANDARD METHODS 2130 B FIELD								
Turbidity		1.0		< 1.0	NTU	1	04/25/2017 17:22	R232332
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential		-300		-149	mV	1	04/25/2017 17:22	R232332
STANDARD METHODS 2510 B FIELD								
Conductivity		1		940	µS/cm	1	04/25/2017 17:22	R232332
STANDARD METHODS 2550 B FIELD								
Temperature		0		19.54	°C	1	04/25/2017 17:22	R232332
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved		1.00		< 1.00	mg/L	1	04/25/2017 17:22	R232332
STANDARD METHODS 2320 B								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	05/02/2017 16:21	R232320
STANDARD METHODS 2320 B (TOTAL)								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		316	mg/L	1	05/02/2017 16:21	R232319
STANDARD METHODS 2540 C (TOTAL)								
Total Dissolved Solids	NELAP	20		900	mg/L	1	04/28/2017 14:54	R232219
SW-846 9036 (TOTAL)								
Sulfate	NELAP	100		370	mg/L	10	05/02/2017 1:02	R232246
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.28	mg/L	1	04/28/2017 16:21	R232156
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		10	mg/L	1	05/02/2017 0:54	R232262
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.050		190	mg/L	1	04/28/2017 18:45	129686
Magnesium	NELAP	0.050		26.9	mg/L	1	04/28/2017 18:45	129686
Potassium	NELAP	0.500		9.33	mg/L	5	05/01/2017 18:38	129686
Sodium	NELAP	0.050		58.4	mg/L	1	04/28/2017 18:45	129686
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		3.0	µg/L	5	05/02/2017 12:07	129687
Arsenic	NELAP	1.0		35.1	µg/L	5	05/02/2017 12:07	129687
Barium	NELAP	1.0		50.6	µg/L	5	05/02/2017 12:07	129687
Beryllium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:07	129687
Boron	NELAP	25.0		21200	µg/L	5	05/04/2017 10:28	129687
Cadmium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:07	129687
Chromium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:07	129687
Cobalt	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:07	129687
Lead	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:07	129687
Lithium	NELAP	1.0		45.5	µg/L	5	05/02/2017 12:07	129687
Molybdenum	NELAP	1.0		77.9	µg/L	5	05/02/2017 12:07	129687
Selenium	NELAP	1.0		1.4	µg/L	5	05/02/2017 12:07	129687
Thallium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:07	129687



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Lab ID: 17040224-001

Client Sample ID: L4

Matrix: LEACHATE

Collection Date: 04/25/2017 17:22

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	05/01/2017 12:14	129695

Client: Natural Resource Technology, Inc.
 Client Project: Hennepin Pond 1 & 2 Additional Testing
 Lab ID: 17040224-002
 Matrix: LEACHATE

Work Order: 17040224
 Report Date: 08-May-17
 Client Sample ID: LPZ-1
 Collection Date: 04/25/2017 17:34

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		3.94	ft	1	04/25/2017 0:00	R232332
STANDARD METHOD 4500-H B FIELD								
pH		1.00		9.10		1	04/25/2017 17:34	R232332
STANDARD METHODS 2130 B FIELD								
Turbidity		1.0		5.6	NTU	1	04/25/2017 17:34	R232332
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential		-300		-177	mV	1	04/25/2017 17:34	R232332
STANDARD METHODS 2510 B FIELD								
Conductivity		1		1550	µS/cm	1	04/25/2017 17:34	R232332
STANDARD METHODS 2550 B FIELD								
Temperature		0		18.67	°C	1	04/25/2017 17:34	R232332
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved		1.00		< 1.00	mg/L	1	04/25/2017 17:34	R232332
STANDARD METHODS 2320 B								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		84	mg/L	1	05/02/2017 16:29	R232320
STANDARD METHODS 2320 B (TOTAL)								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	05/02/2017 16:29	R232319
STANDARD METHODS 2540 C (TOTAL)								
Total Dissolved Solids	NELAP	20		1600	mg/L	1	04/28/2017 14:55	R232219
SW-846 9036 (TOTAL)								
Sulfate	NELAP	200		926	mg/L	20	05/03/2017 15:57	R232369
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		< 0.10	mg/L	1	04/28/2017 16:25	R232156
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		39	mg/L	1	05/02/2017 1:02	R232262
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.050	S	370	mg/L	1	04/28/2017 18:49	129686
Magnesium	NELAP	0.050		8.46	mg/L	1	04/28/2017 18:49	129686
Potassium	NELAP	1.00		45.6	mg/L	10	05/01/2017 18:42	129686
Sodium	NELAP	0.050	S	65.1	mg/L	1	04/28/2017 18:49	129686
<i>MS QC limits for Ca & Na are not applicable due to high sample/spike ratio.</i>								
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		3.2	µg/L	5	05/02/2017 12:15	129687
Arsenic	NELAP	1.0		31.1	µg/L	5	05/02/2017 12:15	129687
Barium	NELAP	1.0		59.6	µg/L	5	05/02/2017 12:15	129687
Beryllium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:15	129687
Boron	NELAP	500	S	28300	µg/L	100	05/03/2017 12:18	129687
Cadmium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:15	129687
Chromium	NELAP	1.0		2.1	µg/L	5	05/02/2017 12:15	129687
Cobalt	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:15	129687
Lead	NELAP	1.0		1.2	µg/L	5	05/02/2017 12:15	129687
Lithium	NELAP	1.0		109	µg/L	5	05/02/2017 12:15	129687
Molybdenum	NELAP	20.0	S	3400	µg/L	100	05/03/2017 12:18	129687
Selenium	NELAP	1.0		8.6	µg/L	5	05/02/2017 12:15	129687
Thallium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:15	129687



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing
Lab ID: 17040224-002
Matrix: LEACHATE

Work Order: 17040224
Report Date: 08-May-17
Client Sample ID: LPZ-1
Collection Date: 04/25/2017 17:34

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
<i>MS QC limits for B and Mo are not applicable due to high sample/spike ratio.</i>								
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	05/01/2017 8:10	129707

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing
Lab ID: 17040224-003
Matrix: LEACHATE

Work Order: 17040224
Report Date: 08-May-17

Client Sample ID: LPZ-3

Collection Date: 04/25/2017 18:00

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		11.02	ft	1	04/25/2017 0:00	R232332
STANDARD METHOD 4500-H B FIELD								
pH		1.00		10.0		1	04/25/2017 18:00	R232332
STANDARD METHODS 2130 B FIELD								
Turbidity		1.0		< 1.0	NTU	1	04/25/2017 18:00	R232332
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential		-300		-87	mV	1	04/25/2017 18:00	R232332
STANDARD METHODS 2510 B FIELD								
Conductivity		1		688	µS/cm	1	04/25/2017 18:00	R232332
STANDARD METHODS 2550 B FIELD								
Temperature		0		17.93	°C	1	04/25/2017 18:00	R232332
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved		1.00		< 1.00	mg/L	1	04/25/2017 18:00	R232332
STANDARD METHODS 2320 B								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		52	mg/L	1	05/02/2017 16:35	R232320
STANDARD METHODS 2320 B (TOTAL)								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	05/02/2017 16:35	R232319
STANDARD METHODS 2540 C (TOTAL)								
Total Dissolved Solids	NELAP	20		768	mg/L	1	04/28/2017 14:55	R232219
SW-846 9036 (TOTAL)								
Sulfate	NELAP	100		375	mg/L	10	05/02/2017 1:37	R232246
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		< 0.10	mg/L	1	04/28/2017 16:29	R232156
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		7	mg/L	1	05/02/2017 1:10	R232262
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.050		214	mg/L	1	04/28/2017 19:00	129686
Magnesium	NELAP	0.050		0.956	mg/L	1	04/28/2017 19:00	129686
Potassium	NELAP	0.500		13.4	mg/L	5	05/01/2017 18:53	129686
Sodium	NELAP	0.050		7.40	mg/L	1	04/28/2017 19:00	129686
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		4.1	µg/L	5	05/02/2017 12:47	129687
Arsenic	NELAP	1.0		12.3	µg/L	5	05/02/2017 12:47	129687
Barium	NELAP	1.0		25.4	µg/L	5	05/02/2017 12:47	129687
Beryllium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:47	129687
Boron	NELAP	25.0		21900	µg/L	5	05/04/2017 10:36	129687
Cadmium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:47	129687
Chromium	NELAP	1.0		31.7	µg/L	5	05/02/2017 12:47	129687
Cobalt	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:47	129687
Lead	NELAP	1.0		8.9	µg/L	5	05/02/2017 12:47	129687
Lithium	NELAP	1.0		52.0	µg/L	5	05/02/2017 12:47	129687
Molybdenum	NELAP	1.0		264	µg/L	5	05/02/2017 12:47	129687
Selenium	NELAP	1.0		112	µg/L	5	05/02/2017 12:47	129687
Thallium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:47	129687



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Lab ID: 17040224-003

Client Sample ID: LPZ-3

Matrix: LEACHATE

Collection Date: 04/25/2017 18:00

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	05/01/2017 8:12	129707



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Lab ID: 17040224-005

Client Sample ID: LPZ-13

Matrix: LEACHATE

Collection Date: 04/25/2017 13:07

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		5.59	ft	1	04/25/2017 0:00	R232332



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Lab ID: 17040224-006

Client Sample ID: LPZ-15

Matrix: LEACHATE

Collection Date: 04/25/2017 13:10

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		5.59	ft	1	04/25/2017 0:00	R232332

Client: Natural Resource Technology, Inc.
 Client Project: Hennepin Pond 1 & 2 Additional Testing
 Lab ID: 17040224-007
 Matrix: LEACHATE

Work Order: 17040224
 Report Date: 08-May-17
 Client Sample ID: LPZ-17
 Collection Date: 04/25/2017 18:44

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		13.93	ft	1	04/25/2017 0:00	R232332
STANDARD METHOD 4500-H B FIELD								
pH		1.00		10.0		1	04/25/2017 18:44	R232332
STANDARD METHODS 2130 B FIELD								
Turbidity		1.0		28	NTU	1	04/25/2017 18:44	R232332
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential		-300		-163	mV	1	04/25/2017 18:44	R232332
STANDARD METHODS 2510 B FIELD								
Conductivity		1		1780	µS/cm	1	04/25/2017 18:44	R232332
STANDARD METHODS 2550 B FIELD								
Temperature		0		20.48	°C	1	04/25/2017 18:44	R232332
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved		1.00		< 1.00	mg/L	1	04/25/2017 18:44	R232332
STANDARD METHODS 2320 B								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		80	mg/L	1	05/02/2017 16:42	R232320
STANDARD METHODS 2320 B (TOTAL)								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	05/02/2017 16:42	R232319
STANDARD METHODS 2540 C (TOTAL)								
Total Dissolved Solids	NELAP	20		2090	mg/L	1	05/01/2017 13:34	R232278
SW-846 9036 (TOTAL)								
Sulfate	NELAP	500		1270	mg/L	50	05/03/2017 16:24	R232369
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		< 0.10	mg/L	1	05/02/2017 13:17	R232279
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		< 5	mg/L	1	05/02/2017 1:45	R232262
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.050	S	578	mg/L	1	05/02/2017 10:20	129737
Magnesium	NELAP	0.050		1.32	mg/L	1	05/02/2017 10:20	129737
Potassium	NELAP	0.500	S	26.5	mg/L	5	05/02/2017 12:51	129737
Sodium	NELAP	0.050		16.1	mg/L	1	05/02/2017 10:20	129737
<i>MS QC limits for K are not applicable due to high sample/spike ratio.</i>								
<i>MS QC limits for Ca are not applicable due to high sample/spike ratio.</i>								
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		1.0	µg/L	5	05/02/2017 18:08	129738
Arsenic	NELAP	1.0		26.5	µg/L	5	05/02/2017 18:08	129738
Barium	NELAP	1.0		92.0	µg/L	5	05/02/2017 18:08	129738
Beryllium	NELAP	1.0		< 1.0	µg/L	5	05/03/2017 14:13	129738
Boron	NELAP	25.0	S	26900	µg/L	5	05/03/2017 14:13	129738
Cadmium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 18:08	129738
Chromium	NELAP	1.0		3.8	µg/L	5	05/03/2017 14:13	129738
Cobalt	NELAP	1.0		1.2	µg/L	5	05/03/2017 14:13	129738
Lead	NELAP	1.0		7.7	µg/L	5	05/02/2017 18:08	129738
Lithium		1.0		97.5	µg/L	5	05/03/2017 14:13	129738
Molybdenum	NELAP	1.0		289	µg/L	5	05/02/2017 18:08	129738
Selenium	NELAP	1.0		118	µg/L	5	05/02/2017 18:08	129738



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Lab ID: 17040224-007

Client Sample ID: LPZ-17

Matrix: LEACHATE

Collection Date: 04/25/2017 18:44

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Thallium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 18:08	129738
<i>MS QC limits for B are not applicable due to high sample/spike ratio.</i>								
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	05/01/2017 14:18	129736

Client: Natural Resource Technology, Inc.
 Client Project: Hennepin Pond 1 & 2 Additional Testing
 Lab ID: 17040224-008
 Matrix: LEACHATE

Work Order: 17040224
 Report Date: 08-May-17
 Client Sample ID: L4 DUP
 Collection Date: 04/25/2017 17:22

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		11.10	ft	1	04/25/2017 0:00	R232332
STANDARD METHOD 4500-H B FIELD								
pH		1.00		7.60		1	04/25/2017 17:22	R232332
STANDARD METHODS 2130 B FIELD								
Turbidity		1.0		< 1.0	NTU	1	04/25/2017 17:22	R232332
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential		-300		-149	mV	1	04/25/2017 17:22	R232332
STANDARD METHODS 2510 B FIELD								
Conductivity		1		940	µS/cm	1	04/25/2017 17:22	R232332
STANDARD METHODS 2550 B FIELD								
Temperature		0		19.54	°C	1	04/25/2017 17:22	R232332
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved		1.00		< 1.00	mg/L	1	04/25/2017 17:22	R232332
STANDARD METHODS 2320 B								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	05/02/2017 16:47	R232320
STANDARD METHODS 2320 B (TOTAL)								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		282	mg/L	1	05/02/2017 16:47	R232319
STANDARD METHODS 2540 C (TOTAL)								
Total Dissolved Solids	NELAP	20		926	mg/L	1	04/28/2017 14:56	R232219
SW-846 9036 (TOTAL)								
Sulfate	NELAP	100		388	mg/L	10	05/02/2017 2:01	R232246
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.26	mg/L	1	04/28/2017 16:34	R232156
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		11	mg/L	1	05/02/2017 1:53	R232262
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.050		185	mg/L	1	04/28/2017 19:03	129686
Magnesium	NELAP	0.050		27.6	mg/L	1	04/28/2017 19:03	129686
Potassium	NELAP	0.500		9.87	mg/L	5	05/01/2017 18:56	129686
Sodium	NELAP	0.050		48.8	mg/L	1	04/28/2017 19:03	129686
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		3.0	µg/L	5	05/02/2017 12:55	129687
Arsenic	NELAP	1.0		27.0	µg/L	5	05/02/2017 12:55	129687
Barium	NELAP	1.0		46.3	µg/L	5	05/02/2017 12:55	129687
Beryllium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:55	129687
Boron	NELAP	25.0		23900	µg/L	5	05/04/2017 10:44	129687
Cadmium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:55	129687
Chromium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:55	129687
Cobalt	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:55	129687
Lead	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:55	129687
Lithium	NELAP	1.0		48.9	µg/L	5	05/02/2017 12:55	129687
Molybdenum	NELAP	1.0		83.0	µg/L	5	05/02/2017 12:55	129687
Selenium	NELAP	1.0		1.4	µg/L	5	05/02/2017 12:55	129687
Thallium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 12:55	129687



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Lab ID: 17040224-008

Client Sample ID: L4 DUP

Matrix: LEACHATE

Collection Date: 04/25/2017 17:22

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	05/01/2017 8:14	129707

Client: Natural Resource Technology, Inc.
 Client Project: Hennepin Pond 1 & 2 Additional Testing
 Lab ID: 17040224-009
 Matrix: LEACHATE

Work Order: 17040224
 Report Date: 08-May-17
 Client Sample ID: Field Blank
 Collection Date: 04/25/2017 19:00

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
STANDARD METHODS 2320 B								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	05/02/2017 16:55	R232320
STANDARD METHODS 2320 B (TOTAL)								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		2	mg/L	1	05/02/2017 16:55	R232319
STANDARD METHODS 2540 C (TOTAL)								
Total Dissolved Solids	NELAP	20		< 20	mg/L	1	04/28/2017 14:56	R232219
SW-846 9036 (TOTAL)								
Sulfate	NELAP	10		< 10	mg/L	1	05/02/2017 2:04	R232246
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		< 0.10	mg/L	1	04/28/2017 16:41	R232156
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		< 5	mg/L	1	05/02/2017 2:02	R232262
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.050		0.068	mg/L	1	04/28/2017 19:07	129686
Magnesium	NELAP	0.050		< 0.050	mg/L	1	04/28/2017 19:07	129686
Potassium	NELAP	0.100		< 0.100	mg/L	1	04/28/2017 19:07	129686
Sodium	NELAP	0.050		< 0.050	mg/L	1	04/28/2017 19:07	129686
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
Arsenic	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
Barium	NELAP	1.0		1.1	µg/L	5	05/02/2017 13:03	129687
Beryllium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
Boron	NELAP	25.0		< 25.0	µg/L	5	05/03/2017 12:10	129687
Cadmium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
Chromium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
Cobalt	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
Lead	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
Lithium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
Molybdenum	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
Selenium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
Thallium	NELAP	1.0		< 1.0	µg/L	5	05/02/2017 13:03	129687
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	05/01/2017 8:17	129707

Client: Natural Resource Technology, Inc.**Work Order:** 17040224**Client Project:** Hennepin Pond 1 & 2 Additional Testing**Report Date:** 08-May-17

Lab Sample ID	Client Sample ID	Matrix	Fractions	Collection Date
17040224-001	L4	Leachate	2	04/25/2017 17:22
17040224-002	LPZ-1	Leachate	2	04/25/2017 17:34
17040224-003	LPZ-3	Leachate	2	04/25/2017 18:00
17040224-004	LPZ-5	Leachate	2	04/25/2017 13:30
17040224-005	LPZ-13	Leachate	1	04/25/2017 13:07
17040224-006	LPZ-15	Leachate	1	04/25/2017 13:10
17040224-007	LPZ-17	Leachate	2	04/25/2017 18:44
17040224-008	L4 DUP	Leachate	2	04/25/2017 17:22
17040224-009	Field Blank	Leachate	2	04/25/2017 19:00

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
	Test Name				
17040224-001A	L4	04/25/2017 17:22	04/27/2017 16:40		
	Field Elevation Measurements				04/25/2017 0:00
	Standard Method 4500-H B Field				04/25/2017 17:22
	Standard Methods 2130 B Field				04/25/2017 17:22
	Standard Methods 18th Ed. 2580 B Field				04/25/2017 17:22
	Standard Methods 2320 B				05/02/2017 16:21
	Standard Methods 2320 B (Total)				05/02/2017 16:21
	Standard Methods 2510 B Field				04/25/2017 17:22
	Standard Methods 2540 C (Total)				04/28/2017 14:54
	Standard Methods 2550 B Field				04/25/2017 17:22
	Standard Methods 4500-O G Field				04/25/2017 17:22
	SW-846 9036 (Total)				05/02/2017 1:02
	SW-846 9214 (Total)				04/28/2017 16:21
	SW-846 9251 (Total)				05/02/2017 0:54
17040224-001B	L4	04/25/2017 17:22	04/27/2017 16:40		
	SW-846 3005A, 6010B, Metals by ICP (Total)			04/28/2017 9:04	04/28/2017 18:45
	SW-846 3005A, 6010B, Metals by ICP (Total)			04/28/2017 9:04	05/01/2017 18:38
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			04/28/2017 9:09	05/02/2017 12:07
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			04/28/2017 9:09	05/04/2017 10:28
	SW-846 7470A (Total)			04/28/2017 11:25	05/01/2017 12:14
17040224-002A	LPZ-1	04/25/2017 17:34	04/27/2017 16:40		
	Field Elevation Measurements				04/25/2017 0:00
	Standard Method 4500-H B Field				04/25/2017 17:34
	Standard Methods 2130 B Field				04/25/2017 17:34
	Standard Methods 18th Ed. 2580 B Field				04/25/2017 17:34
	Standard Methods 2320 B				05/02/2017 16:29
	Standard Methods 2320 B (Total)				05/02/2017 16:29
	Standard Methods 2510 B Field				04/25/2017 17:34
	Standard Methods 2540 C (Total)				04/28/2017 14:55
	Standard Methods 2550 B Field				04/25/2017 17:34
	Standard Methods 4500-O G Field				04/25/2017 17:34
	SW-846 9036 (Total)				05/03/2017 15:57
	SW-846 9214 (Total)				04/28/2017 16:25
	SW-846 9251 (Total)				05/02/2017 1:02
17040224-002B	LPZ-1	04/25/2017 17:34	04/27/2017 16:40		
	SW-846 3005A, 6010B, Metals by ICP (Total)			04/28/2017 9:04	04/28/2017 18:49
	SW-846 3005A, 6010B, Metals by ICP (Total)			04/28/2017 9:04	05/01/2017 18:42

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			04/28/2017 9:09	05/02/2017 12:15
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			04/28/2017 9:09	05/03/2017 12:18
	SW-846 7470A (Total)			04/28/2017 15:10	05/01/2017 8:10
17040224-003A	LPZ-3	04/25/2017 18:00	04/27/2017 16:40		
	Field Elevation Measurements				04/25/2017 0:00
	Standard Method 4500-H B Field				04/25/2017 18:00
	Standard Methods 2130 B Field				04/25/2017 18:00
	Standard Methods 18th Ed. 2580 B Field				04/25/2017 18:00
	Standard Methods 2320 B				05/02/2017 16:35
	Standard Methods 2320 B (Total)				05/02/2017 16:35
	Standard Methods 2510 B Field				04/25/2017 18:00
	Standard Methods 2540 C (Total)				04/28/2017 14:55
	Standard Methods 2550 B Field				04/25/2017 18:00
	Standard Methods 4500-O G Field				04/25/2017 18:00
	SW-846 9036 (Total)				05/02/2017 1:37
	SW-846 9214 (Total)				04/28/2017 16:29
	SW-846 9251 (Total)				05/02/2017 1:10
17040224-003B	LPZ-3	04/25/2017 18:00	04/27/2017 16:40		
	SW-846 3005A, 6010B, Metals by ICP (Total)			04/28/2017 9:04	04/28/2017 19:00
	SW-846 3005A, 6010B, Metals by ICP (Total)			04/28/2017 9:04	05/01/2017 18:53
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			04/28/2017 9:09	05/02/2017 12:47
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			04/28/2017 9:09	05/04/2017 10:36
	SW-846 7470A (Total)			04/28/2017 15:10	05/01/2017 8:12
17040224-004A	LPZ-5	04/25/2017 13:30	04/27/2017 16:40		
	Standard Methods 2320 B (Total)				05/02/2017 14:13
	Standard Methods 2540 C (Total)				04/28/2017 14:56
17040224-005A	LPZ-13	04/25/2017 13:07	04/27/2017 16:40		
	Field Elevation Measurements				04/25/2017 0:00
17040224-006A	LPZ-15	04/25/2017 13:10	04/27/2017 16:40		
	Field Elevation Measurements				04/25/2017 0:00
17040224-007A	LPZ-17	04/25/2017 18:44	04/27/2017 16:40		
	Field Elevation Measurements				04/25/2017 0:00
	Standard Method 4500-H B Field				04/25/2017 18:44
	Standard Methods 2130 B Field				04/25/2017 18:44
	Standard Methods 18th Ed. 2580 B Field				04/25/2017 18:44
	Standard Methods 2320 B				05/02/2017 16:42
	Standard Methods 2320 B (Total)				05/02/2017 16:42

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	Standard Methods 2510 B Field				04/25/2017 18:44
	Standard Methods 2540 C (Total)				05/01/2017 13:34
	Standard Methods 2550 B Field				04/25/2017 18:44
	Standard Methods 4500-O G Field				04/25/2017 18:44
	SW-846 9036 (Total)				05/03/2017 16:24
	SW-846 9214 (Total)				05/02/2017 13:17
	SW-846 9251 (Total)				05/02/2017 1:45
17040224-007B	LPZ-17	04/25/2017 18:44	04/27/2017 16:40		
	SW-846 3005A, 6010B, Metals by ICP (Total)			05/01/2017 11:23	05/02/2017 10:20
	SW-846 3005A, 6010B, Metals by ICP (Total)			05/01/2017 11:23	05/02/2017 12:51
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			05/01/2017 11:25	05/02/2017 18:08
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			05/01/2017 11:25	05/03/2017 14:13
	SW-846 7470A (Total)			05/01/2017 11:03	05/01/2017 14:18
17040224-008A	L4 DUP	04/25/2017 17:22	04/27/2017 16:40		
	Field Elevation Measurements				04/25/2017 0:00
	Standard Method 4500-H B Field				04/25/2017 17:22
	Standard Methods 2130 B Field				04/25/2017 17:22
	Standard Methods 18th Ed. 2580 B Field				04/25/2017 17:22
	Standard Methods 2320 B				05/02/2017 16:47
	Standard Methods 2320 B (Total)				05/02/2017 16:47
	Standard Methods 2510 B Field				04/25/2017 17:22
	Standard Methods 2540 C (Total)				04/28/2017 14:56
	Standard Methods 2550 B Field				04/25/2017 17:22
	Standard Methods 4500-O G Field				04/25/2017 17:22
	SW-846 9036 (Total)				05/02/2017 2:01
	SW-846 9214 (Total)				04/28/2017 16:34
	SW-846 9251 (Total)				05/02/2017 1:53
17040224-008B	L4 DUP	04/25/2017 17:22	04/27/2017 16:40		
	SW-846 3005A, 6010B, Metals by ICP (Total)			04/28/2017 9:04	04/28/2017 19:03
	SW-846 3005A, 6010B, Metals by ICP (Total)			04/28/2017 9:04	05/01/2017 18:56
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			04/28/2017 9:09	05/02/2017 12:55
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			04/28/2017 9:09	05/04/2017 10:44
	SW-846 7470A (Total)			04/28/2017 15:10	05/01/2017 8:14
17040224-009A	Field Blank	04/25/2017 19:00	04/27/2017 16:40		
	Standard Methods 2320 B				05/02/2017 16:55
	Standard Methods 2320 B (Total)				05/02/2017 16:55
	Standard Methods 2540 C (Total)				04/28/2017 14:56

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
	Test Name				
	SW-846 9036 (Total)				05/02/2017 2:04
	SW-846 9214 (Total)				04/28/2017 16:41
	SW-846 9251 (Total)				05/02/2017 2:02
17040224-009B	Field Blank	04/25/2017 19:00	04/27/2017 16:40		
	SW-846 3005A, 6010B, Metals by ICP (Total)			04/28/2017 9:04	04/28/2017 19:07
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			04/28/2017 9:09	05/02/2017 13:03
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			04/28/2017 9:09	05/03/2017 12:10
	SW-846 7470A (Total)			04/28/2017 15:10	05/01/2017 8:17

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing

Work Order: 17040224
Report Date: 08-May-17

STANDARD METHOD 4500-H B FIELD

Batch R232332 SampType: LCS		Units							
SampID: LCS-R232332									
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
pH	1.00		7.02	7.000	0	100.3	99.1	100.9	04/25/2017
pH	1.00		7.00	7.000	0	100.0	99.1	100.9	04/26/2017
pH	1.00		7.00	7.000	0	100.0	99.1	100.9	04/27/2017

STANDARD METHODS 2510 B FIELD

Batch R232332		SampType: LCS		Units µS/cm					
SampID: LCS-R232332									
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Conductivity	1		1420	1409	0	100.6	90	110	04/27/2017
Conductivity	1		1410	1409	0	100.3	90	110	04/25/2017

STANDARD METHODS 2510 B FIELD

Batch R232332		SampType: LCS		Units µmhos/cm						
SampID: LCS-R232332										Date
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Conductivity	10		1410	1412	0	100.1	90	110	04/26/2017	

STANDARD METHODS 2540 C (TOTAL)

Batch R232219		SampType: MBLK		Units mg/L							
SampID: MBLK											Date
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Total Dissolved Solids		20		< 20						04/28/2017	
Total Dissolved Solids		20		< 20						04/28/2017	
Total Dissolved Solids		20		< 20						04/28/2017	
Total Dissolved Solids		20		< 20						04/28/2017	
Total Dissolved Solids		20		< 20						04/28/2017	

Batch R232219		SampType: LCS		Units mg/L							
SampID: LCS											Date
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Total Dissolved Solids		20		1000	1000	0	100.2	90	110	04/28/2017	

Batch R232219		SampType: LCSQC		Units mg/L						
SampID: LCSQC										
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Total Dissolved Solids		20		986	1000	0	98.6	90	110	04/28/2017
Total Dissolved Solids		20		998	1000	0	99.8	90	110	04/28/2017
Total Dissolved Solids		20		984	1000	0	98.4	90	110	04/28/2017
Total Dissolved Solids		20		988	1000	0	98.8	90	110	04/28/2017

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing

Work Order: 17040224
Report Date: 08-May-17

STANDARD METHODS 2540 C (TOTAL)

Batch R232219		SampType: DUP		Units mg/L				RPD Limit 5			
SampID: 17040224-001ADUP											Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Total Dissolved Solids		20		908				900.0	0.88	04/28/2017	

Batch R232278		SampType: MBLK		Units mg/L						
SampID: MBLK										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Total Dissolved Solids	20		< 20						05/01/2017	
Total Dissolved Solids	20		< 20						05/01/2017	

Batch R232278		SampType: LCS		Units mg/L							
SampID: LCS											Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Total Dissolved Solids		20		988	1000	0	98.8	90	110	05/01/2017	

Batch R232278		SampType: LCSQC		Units mg/L						
SampID: LCSQC										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Total Dissolved Solids		20		972	1000	0	97.2	90	110	05/01/2017

Batch R232278		SampType: DUP	Units mg/L					RPD Limit 5			
SampID: 17040224-007ADUP											
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Total Dissolved Solids		20		2110				2094	0.86	05/01/2017	

SW-846 9036 (TOTAL)

Batch R232246		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Sulfate		10		< 10						05/01/2017	

Batch R232246		SampType: LCS		Units mg/L						
SampID: ICV/LCS										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Sulfate		10		19	20.00	0	93.6	90	110	05/01/2017

Batch R232246		SampType: MS		Units mg/L						
SampID: 17040224-003AMS										
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Sulfate		100		469	100.0	375.4	93.2	85	115	05/02/2017

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing

Work Order: 17040224
Report Date: 08-May-17

SW-846 9036 (TOTAL)

Batch R232246		SampType: MSD		Units mg/L				RPD Limit 10		
SampID: 17040224-003AMSD										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Sulfate		100		485	100.0	375.4	109.9	468.7	3.50	05/02/2017

Batch R232369		SampType: MBLK		Units mg/L							
SampID: ICB/MBLK											Date
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Sulfate		10		< 10						05/03/2017	

Batch R232369		SampType: LCS		Units mg/L						
SampID: ICV/LCS										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Sulfate		10		20	20.00	0	100.0	90	110	05/03/2017

SW-846 9214 (TOTAL)

Batch R232156		SampType: MBLK		Units mg/L							
SampID: MBLK											Date
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Fluoride		0.10		< 0.10						04/28/2017	

Batch R232156		SampType: LCS		Units mg/L						
SampID: LCS										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Fluoride		0.10		1.00	1.000	0	100.4	90	110	04/28/2017

Batch R232156		SampType: MS		Units mg/L							
SampID: 17040224-008AMS											Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		2.30	2.000	0.2570	102.0	85	115	04/28/2017	

Batch R232156		SampType: MSD		Units mg/L				RPD Limit 10			
SampID: 17040224-008AMSD										Date Analyzed	
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Fluoride		0.10		2.22	2.000	0.2570	98.0	2.298	3.54	04/28/2017	

Batch R232279		SampType: MBLK		Units mg/L						
SampID: MBLK										Date
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Fluoride		0.10		< 0.10						05/02/2017

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing

Work Order: 17040224
Report Date: 08-May-17

SW-846 9214 (TOTAL)

Batch R232279		SampType: LCS		Units mg/L							Date Analyzed
SampID: LCS											
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			Date Analyzed
Fluoride	0.10		0.98	1.000	0	97.6	90	110			05/02/2017

Batch R232279		SampType: MS		Units mg/L							Date Analyzed
SampID: 17040224-007AMS											
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			Date Analyzed
Fluoride	0.10		1.89	2.000	0.05300	92.0	85	115			05/02/2017

Batch R232279		SampType: MSD		Units mg/L				RPD Limit 10		
SampID: 17040224-007AMSD										
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Fluoride		0.10		1.94	2.000	0.05300	94.6	1.892	2.76	05/02/2017

SW-846 9251 (TOTAL)

Batch R232262		SampType: MBLK		Units mg/L							Date Analyzed
SampID: ICB/MBLK											
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			Date Analyzed
Chloride	5		< 5								05/01/2017

Batch R232262		SampType: LCS		Units mg/L							Date Analyzed
SampID: ICB/LCS											
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			Date Analyzed
Chloride	5		20	20.00	0	99.9	90	110			05/01/2017

Batch R232262		SampType: MS		Units mg/L							Date Analyzed
SampID: 17040224-003AMS											
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			Date Analyzed
Chloride	5		25	20.00	6.820	92.5	85	115			05/02/2017

Batch R232262		SampType: MSD	Units mg/L				RPD Limit 15			Date Analyzed
SampID: 17040224-003AMSD										
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Chloride	5		25	20.00	6.820	92.8	25.32	0.24		05/02/2017

Batch R232398		SampType: MBLK		Units mg/L							Date Analyzed
SampID: ICB/MBLK											
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			Date Analyzed
Chloride	5		< 5								05/03/2017

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing

Work Order: 17040224
Report Date: 08-May-17

SW-846 9251 (TOTAL)

Batch R232398		SampType: LCS		Units mg/L						
SampID: ICV/LCS										
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Chloride	5		21	20.00	0	104.6	90	110	05/03/2017	

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 129686		SampType: MBLK		Units mg/L						
SampID: MBLK-129686										
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Calcium	0.050		< 0.050	0.05000	0	0	-100	100	04/28/2017	
Calcium	0.0500		< 0.0500	0.05000	0	0	-100	100	04/28/2017	
Magnesium	0.0500		< 0.0500	0.05000	0	0	-100	100	04/28/2017	
Magnesium	0.050		< 0.050	0.05000	0	0	-100	100	04/28/2017	
Potassium	0.100		< 0.100	0.1000	0	0	-100	100	04/28/2017	
Potassium	0.100		< 0.100	0.1000	0	0	-100	100	04/28/2017	
Sodium	0.0500		< 0.0500	0.05000	0	0	-100	100	04/28/2017	
Sodium	0.050		< 0.050	0.05000	0	0	-100	100	04/28/2017	

Batch 129686		SampType: LCS		Units mg/L						
SampID: LCS-129686										
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Calcium	0.0500		2.55	2.500	0	102.0	85	115	04/28/2017	
Calcium	0.050		2.55	2.500	0	102.0	85	115	04/28/2017	
Magnesium	0.0500		2.56	2.500	0	102.4	85	115	04/28/2017	
Magnesium	0.050		2.56	2.500	0	102.4	85	115	04/28/2017	
Potassium	0.100		2.32	2.500	0	92.6	85	115	04/28/2017	
Potassium	0.100		2.32	2.500	0	92.6	85	115	04/28/2017	
Sodium	0.050		2.34	2.500	0	93.4	85	115	04/28/2017	
Sodium	0.0500		2.34	2.500	0	93.4	85	115	04/28/2017	

Batch 129686		SampType: MS		Units mg/L							
SampID: 17040224-002BMS											Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Calcium		0.050	S	368	2.500	370.2	-84.0	75	125	04/28/2017	
Magnesium		0.050		10.8	2.500	8.455	93.8	75	125	04/28/2017	
Potassium		1.00		47.7	2.500	45.62	84.8	75	125	05/01/2017	
Sodium		0.050	S	66.6	2.500	65.09	62.0	75	125	04/28/2017	

Batch 129686		SampType: MSD		Units mg/L				RPD Limit 20		
SampID: 17040224-002BMSD										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Calcium		0.050	S	374	2.500	370.2	152.0	368.1	1.59	04/28/2017
Magnesium		0.050		11.0	2.500	8.455	102.6	10.80	2.02	04/28/2017
Potassium		1.00		47.6	2.500	45.62	79.2	47.74	0.29	05/01/2017
Sodium		0.050		67.6	2.500	65.09	102.0	66.64	1.49	04/28/2017

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 129737		SampType: MBLK		Units mg/L					
SampID: MBLK-129737									
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Calcium	0.050		< 0.050	0.05000	0	45.6	-100	100	05/02/2017
Magnesium	0.050		< 0.050	0.05000	0	0	-100	100	05/02/2017
Potassium	0.100		< 0.100	0.1000	0	0	-100	100	05/02/2017
Sodium	0.050		< 0.050	0.05000	0	49.6	-100	100	05/02/2017

Batch 129737		SampType: LCS		Units mg/L						
SampID: LCS-129737										Date
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Calcium	0.050		2.55	2.500	0	102.2	85	115	05/02/2017	
Magnesium	0.050		2.54	2.500	0	101.5	85	115	05/02/2017	
Potassium	0.100		2.37	2.500	0	94.8	85	115	05/02/2017	
Sodium	0.050		2.34	2.500	0	93.4	85	115	05/02/2017	

Batch 129737		SampType: MS		Units mg/L						
SampID: 17040224-007BMS										
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Calcium	0.050	S	579	2.500	577.9	44.0	75	125	05/02/2017	
Magnesium	0.050		3.89	2.500	1.323	102.7	75	125	05/02/2017	
Potassium	0.500	S	29.8	2.500	26.53	131.2	75	125	05/02/2017	
Sodium	0.050		18.6	2.500	16.12	97.6	75	125	05/02/2017	

Batch 129737		SampType: MSD		Units mg/L				RPD Limit 20		
SampID: 17040224-007BMSD										
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed
Calcium		0.050	S	581	2.500	577.9	128.0	579.0	0.36	05/02/2017
Magnesium		0.050		3.91	2.500	1.323	103.4	3.890	0.44	05/02/2017
Potassium		0.500		29.6	2.500	26.53	121.2	29.81	0.84	05/02/2017
Sodium		0.050		18.7	2.500	16.12	102.0	18.56	0.59	05/02/2017

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 129687 **SampType:** MBLK Units $\mu\text{g/L}$

SampID: MBLK-129687

Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony	1.0		< 1.0	1.000	0	0	-100	100	05/01/2017
Arsenic	1.0		< 1.0	1.000	0	0	-100	100	05/01/2017
Barium	1.0		< 1.0	1.000	0	0	-100	100	05/01/2017
Beryllium	1.0		< 1.0	1.000	0	0	-100	100	05/01/2017
Boron	25.0		< 25.0	25.00	0	0	-100	100	05/01/2017
Cadmium	1.0		< 1.0	1.000	0	0	-100	100	05/01/2017
Chromium	1.0		< 1.0	1.000	0	0	-100	100	05/01/2017
Cobalt	1.0		< 1.0	1.000	0	0	-100	100	05/01/2017
Lead	1.0		< 1.0	1.000	0	0	-100	100	05/01/2017
Lithium	1.0		< 1.0	1.000	0	81.2	-100	100	05/01/2017
Molybdenum	1.0		< 1.0	1.000	0	0	-100	100	05/01/2017
Selenium	1.0		< 1.0	1.000	0	0	-100	100	05/01/2017
Thallium	1.0		< 1.0	1.000	0	66.4	-100	100	05/01/2017

Batch 129687 **SampType:** LCS Units $\mu\text{g/L}$

SampID: LCS-129687

Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony	1.0		519	500.0	0	103.8	80	120	05/01/2017
Arsenic	1.0		544	500.0	0	108.9	80	120	05/01/2017
Barium	1.0		2110	2000	0	105.6	80	120	05/01/2017
Beryllium	1.0		57.5	50.00	0	115.0	80	120	05/01/2017
Boron	25.0		575	500.0	0	115.0	80	120	05/01/2017
Cadmium	1.0		52.5	50.00	0	105.0	80	120	05/01/2017
Chromium	1.0		203	200.0	0	101.6	80	120	05/01/2017
Cobalt	1.0		508	500.0	0	101.7	80	120	05/01/2017
Lead	1.0		545	500.0	0	108.9	80	120	05/01/2017
Lithium	1.0		536	500.0	0	107.2	80	120	05/02/2017
Molybdenum	1.0		514	500.0	0	102.9	80	120	05/01/2017
Selenium	1.0		540	500.0	0	108.0	80	120	05/01/2017
Thallium	1.0		264	250.0	0	105.5	80	120	05/01/2017

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 129687		SampType: MS		Units µg/L							
SampID: 17040224-002BMS											Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit			
Antimony	1.0		515	500.0	3.232	102.4	75	125		05/02/2017	
Arsenic	1.0		553	500.0	31.11	104.4	75	125		05/02/2017	
Barium	1.0		2130	2000	59.60	103.4	75	125		05/02/2017	
Beryllium	1.0		49.7	50.00	0	99.3	75	125		05/02/2017	
Boron	500	S	27000	500.0	28330	-273.2	75	125		05/03/2017	
Cadmium	1.0		51.2	50.00	0.6986	101.1	75	125		05/02/2017	
Chromium	1.0		192	200.0	2.088	95.0	75	125		05/02/2017	
Cobalt	1.0		475	500.0	0.3738	94.9	75	125		05/02/2017	
Lead	1.0		522	500.0	1.153	104.2	75	125		05/02/2017	
Lithium	1.0		638	500.0	109.4	105.7	75	125		05/02/2017	
Molybdenum	20.0		3810	500.0	3403	80.7	75	125		05/03/2017	
Selenium	1.0		498	500.0	8.572	97.9	75	125		05/02/2017	
Thallium	1.0		252	250.0	0	100.8	75	125		05/02/2017	

Batch 129687		SampType: MSD		Units µg/L				RPD Limit 20		
SampID: 17040224-002BMSD										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Antimony	1.0		515	500.0	3.232	102.3	515.5	0.17	05/02/2017	
Arsenic	1.0		550	500.0	31.11	103.9	553.3	0.52	05/02/2017	
Barium	1.0		2120	2000	59.60	103.1	2127	0.26	05/02/2017	
Beryllium	1.0		48.9	50.00	0	97.8	49.67	1.53	05/02/2017	
Boron	500	S	26700	500.0	28330	-321.1	26960	0.89	05/03/2017	
Cadmium	1.0		50.9	50.00	0.6986	100.4	51.23	0.65	05/02/2017	
Chromium	1.0		192	200.0	2.088	95.2	192.1	0.20	05/02/2017	
Cobalt	1.0		474	500.0	0.3738	94.7	474.9	0.22	05/02/2017	
Lead	1.0		519	500.0	1.153	103.6	522.2	0.55	05/02/2017	
Lithium	1.0		650	500.0	109.4	108.2	638.0	1.89	05/02/2017	
Molybdenum	20.0	S	3770	500.0	3403	74.3	3806	0.84	05/03/2017	
Selenium	1.0		504	500.0	8.572	99.0	498.3	1.06	05/02/2017	
Thallium	1.0		250	250.0	0	99.8	252.0	0.96	05/02/2017	

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 129738 **SampType:** MBLK Units $\mu\text{g/L}$

SampID: MBLK-129738

Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony	1.0		< 1.0	1.000	0	0	-100	100	05/02/2017
Arsenic	1.0		< 1.0	1.000	0	0	-100	100	05/02/2017
Barium	1.0		< 1.0	1.000	0	0	-100	100	05/02/2017
Beryllium	1.0		< 1.0	1.000	0	0	-100	100	05/03/2017
Boron	25.0		< 25.0	25.00	0	0	-100	100	05/03/2017
Cadmium	1.0		< 1.0	1.000	0	0	-100	100	05/02/2017
Chromium	1.0		< 1.0	1.000	0	0	-100	100	05/03/2017
Cobalt	1.0		< 1.0	1.000	0	0	-100	100	05/03/2017
Lead	1.0		< 1.0	1.000	0	0	-100	100	05/02/2017
Lithium	1.0		< 1.0	1.000	0	59.6	-100	100	05/03/2017
Molybdenum	1.0		< 1.0	1.000	0	0	-100	100	05/02/2017
Selenium	1.0		< 1.0	1.000	0	0	-100	100	05/02/2017
Thallium	1.0		< 1.0	1.000	0	0	-100	100	05/02/2017

Batch 129738 **SampType:** LCS Units $\mu\text{g/L}$

SampID: LCS-129738

Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony	1.0		457	500.0	0	91.3	80	120	05/02/2017
Arsenic	1.0		478	500.0	0	95.5	80	120	05/02/2017
Barium	1.0		1890	2000	0	94.6	80	120	05/02/2017
Beryllium	1.0		51.3	50.00	0	102.5	80	120	05/03/2017
Boron	25.0		502	500.0	0	100.3	80	120	05/03/2017
Cadmium	1.0		45.6	50.00	0	91.1	80	120	05/02/2017
Chromium	1.0		183	200.0	0	91.7	80	120	05/03/2017
Cobalt	1.0		468	500.0	0	93.6	80	120	05/03/2017
Lead	1.0		476	500.0	0	95.1	80	120	05/02/2017
Lithium	1.0		550	500.0	0	110.0	80	120	05/03/2017
Molybdenum	1.0		449	500.0	0	89.9	80	120	05/02/2017
Selenium	1.0		462	500.0	0	92.4	80	120	05/02/2017
Thallium	1.0		229	250.0	0	91.7	80	120	05/02/2017

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 129738		SampType: MS		Units µg/L						
SampID: 17040224-007BMS										Date
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Antimony	1.0		472	500.0	1.019	94.2	75	125	05/02/2017	
Arsenic	1.0		501	500.0	26.45	94.8	75	125	05/02/2017	
Barium	1.0		2020	2000	91.99	96.6	75	125	05/02/2017	
Beryllium	1.0		49.7	50.00	0	99.4	75	125	05/03/2017	
Boron	25.0	S	28200	500.0	26930	245.2	75	125	05/03/2017	
Cadmium	1.0		46.7	50.00	0.6973	92.1	75	125	05/02/2017	
Chromium	1.0		185	200.0	3.761	90.8	75	125	05/03/2017	
Cobalt	1.0		458	500.0	1.193	91.5	75	125	05/03/2017	
Lead	1.0		493	500.0	7.712	97.1	75	125	05/02/2017	
Lithium	1.0		627	500.0	97.46	105.9	75	125	05/03/2017	
Molybdenum	1.0		753	500.0	289.0	92.7	75	125	05/02/2017	
Selenium	1.0		567	500.0	118.1	89.7	75	125	05/02/2017	
Thallium	1.0		232	250.0	0	92.8	75	125	05/02/2017	

Batch 129738		SampType: MSD		Units µg/L				RPD Limit 20		
SampID: 17040224-007BMSD										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Antimony	1.0		465	500.0	1.019	92.8	472.2	1.54	05/02/2017	
Arsenic	1.0		499	500.0	26.45	94.5	500.7	0.29	05/02/2017	
Barium	1.0		1990	2000	91.99	94.9	2024	1.65	05/02/2017	
Beryllium	1.0		48.9	50.00	0	97.7	49.72	1.73	05/03/2017	
Boron	25.0	S	27900	500.0	26930	192.9	28160	0.93	05/03/2017	
Cadmium	1.0		46.2	50.00	0.6973	91.0	46.75	1.17	05/02/2017	
Chromium	1.0		186	200.0	3.761	91.2	185.3	0.48	05/03/2017	
Cobalt	1.0		464	500.0	1.193	92.6	458.5	1.25	05/03/2017	
Lead	1.0		487	500.0	7.712	95.9	493.5	1.26	05/02/2017	
Lithium	1.0		617	500.0	97.46	103.8	627.1	1.68	05/03/2017	
Molybdenum	1.0		745	500.0	289.0	91.1	752.7	1.08	05/02/2017	
Selenium	1.0		567	500.0	118.1	89.7	566.7	0.03	05/02/2017	
Thallium	1.0		231	250.0	0	92.3	232.0	0.55	05/02/2017	

SW-846 7470A (TOTAL)

Batch 129695		SampType: MBLK		Units µg/L						Date Analyzed
SampID: MBLK-129695										
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Mercury	0.20		< 0.20	0.2000	0	0	-100	100	05/01/2017	

Batch 129695		SampType: LCS		Units µg/L						
SampID: LCS-129695										Date
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Mercury	0.20		5.14	5.000	0	102.8	85	115	05/01/2017	

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing

Work Order: 17040224
Report Date: 08-May-17

SW-846 7470A (TOTAL)

Batch 129707		SampType: MBLK		Units µg/L							Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Mercury		0.20		< 0.20	0.2000	0	0	-100	100	05/01/2017	

Batch 129707		SampType: LCS		Units µg/L							Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Mercury		0.20		4.64	5.000	0	92.8	85	115	05/01/2017	

Batch 129707		SampType: MS		Units µg/L							Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Mercury		0.20		4.66	5.000	0	93.2	75	125	05/01/2017	

Batch 129707		SampType: MSD		Units µg/L		RPD Limit 15					Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Mercury		0.20		4.64	5.000	0	92.8	4.661	0.40	05/01/2017	

Batch 129736		SampType: MBLK		Units µg/L							Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Mercury		0.20		< 0.20	0.2000	0	0	-100	100	05/01/2017	

Batch 129736		SampType: LCS		Units µg/L							Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Mercury		0.20		5.26	5.000	0	105.2	85	115	05/01/2017	

Batch 129736		SampType: MS		Units µg/L							Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Mercury		0.20		5.05	5.000	0	101.0	75	125	05/01/2017	

Batch 129736		SampType: MSD		Units µg/L		RPD Limit 15					Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Mercury		0.20		4.96	5.000	0	99.2	5.049	1.79	05/01/2017	



Receiving Check List

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17040224

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 08-May-17

Carrier: Tim Mathis

Received By: AMD

Completed by:

On:

27-Apr-17

Amber M. Dilallo

Reviewed by:

On:

27-Apr-17

Elizabeth A. Hurley

Pages to follow:

Chain of custody

1

Extra pages included

8

Shipping container/cooler in good condition?

Yes ☒

No ☐

Not Present ☐

Temp °C 4.62

Type of thermal preservation?

None ☐

Ice ☒

Blue Ice ☐

Dry Ice ☐

Chain of custody present?

Yes ☒

No ☐

Chain of custody signed when relinquished and received?

Yes ☒

No ☐

Chain of custody agrees with sample labels?

Yes ☐

No ☒

Samples in proper container/bottle?

Yes ☒

No ☐

Sample containers intact?

Yes ☒

No ☐

Sufficient sample volume for indicated test?

Yes ☒

No ☐

All samples received within holding time?

Yes ☒

No ☐

Reported field parameters measured:

Field ☒

Lab ☐

NA ☐

Container/Temp Blank temperature in compliance?

Yes ☒

No ☐

When thermal preservation is required, samples are compliant with a temperature between 0.1°C - 6.0°C, or when samples are received on ice the same day as collected.

Water – at least one vial per sample has zero headspace?

Yes ☐

No ☐

No VOA vials ☒

Water - TOX containers have zero headspace?

Yes ☐

No ☐

No TOX containers ☒

Water - pH acceptable upon receipt?

Yes ☐

No ☒

NA ☐

NPDES/CWA TCN interferences checked/treated in the field?

Yes ☐

No ☐

NA ☒

Any No responses must be detailed below or on the COC.

Additional Nitric Acid was needed in L4, LPZ-3, and LPZ-17 upon arrival at the laboratory. AMD 4/27/17

No containers were labeled as LPZ-17. Per Tim Mathis, LPZ-17 was collected in containers labeled as LPZ-5 which was dry. EAH 5/1/17

pg. 1 of 1 Work order # 17040224

TEKLAB, INC. 5445 Horseshoe Lake Road - Collinsville, IL 62234 - Phone: (618) 344-1004 - Fax: (618) 344-1005

[illegible]

The individual signing this agreement on behalf of the client, acknowledges that he/she has read and understands the terms and conditions of this agreement, and that he/she has the authority to sign on behalf of the client. See www.teklabinc.com for terms and conditions.

BottleOrder: 37016



11/20/77

September 22, 2017

Steve Wiskes
Natural Resource Technology, Inc.
2422 East Washington Street
Suite 104
Bloomington, IL 61704
TEL: (414) 837-3614
FAX: (414) 837-3608



RE: Hennepin Pond 1 & 2 Additional Testing

WorkOrder: 17081821

Dear Steve Wiskes:

TEKLAB, INC received 9 samples on 9/8/2017 1:10:00 PM for the analysis presented in the following report.

Samples are analyzed on an as received basis unless otherwise requested and documented. The sample results contained in this report relate only to the requested analytes of interest as directed on the chain of custody. NELAP accredited fields of testing are indicated by the letters NELAP under the Certification column. Unless otherwise documented within this report, Teklab Inc. analyzes samples utilizing the most current methods in compliance with 40CFR. All tests are performed in the Collinsville, IL laboratory unless otherwise noted in the Case Narrative.

All quality control criteria applicable to the test methods employed for this project have been satisfactorily met and are in accordance with NELAP except where noted. The following report shall not be reproduced, except in full, without the written approval of Teklab, Inc.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,



Michael L. Austin
Project Manager
(618)344-1004 ex 16
MAustin@teklabinc.com



Report Contents

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

This reporting package includes the following:

Cover Letter	1
Report Contents	2
Definitions	3
Case Narrative	4
Accreditations	5
Laboratory Results	6
Sample Summary	15
Dates Report	16
Quality Control Results	19
Receiving Check List	25
Chain of Custody	Appended

Client: Natural Resource Technology, Inc.**Work Order:** 17081821**Client Project:** Hennepin Pond 1 & 2 Additional Testing**Report Date:** 22-Sep-17**Abbr Definition**

CCV	Continuing calibration verification is a check of a standard to determine the state of calibration of an instrument between recalibration.
DF	Dilution factor is the dilution performed during analysis only and does not take into account any dilutions made during sample preparation. The reported result is final and includes all dilutions factors.
DNI	Did not ignite
DUP	Laboratory duplicate is an aliquot of a sample taken from the same container under laboratory conditions for independent processing and analysis independently of the original aliquot.
ICV	Initial calibration verification is a check of a standard to determine the state of calibration of an instrument before sample analysis is initiated.
IDPH	IL Dept. of Public Health
LCS	Laboratory control sample, spiked with verified known amounts of analytes, is analyzed exactly like a sample to establish intra-laboratory or analyst specific precision and bias or to assess the performance of all or a portion of the measurement system. The acceptable recovery range is in the QC Package (provided upon request).
LCSD	Laboratory control sample duplicate is a replicate laboratory control sample that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).
MBLK	Method blank is a sample of a matrix similar to the batch of associated sample (when available) that is free from the analytes of interest and is processed simultaneously with and under the same conditions as samples through all steps of the analytical procedures, and in which no target analytes or interferences should present at concentrations that impact the analytical results for sample analyses.
MDL	Method detection limit means the minimum concentration of a substance that can be measured and reported with 99% confidence that the analyte concentration is greater than zero.
MS	Matrix spike is an aliquot of matrix fortified (spiked) with known quantities of specific analytes that is subjected to the entire analytical procedures in order to determine the effect of the matrix on an approved test method's recovery system. The acceptable recovery range is listed in the QC Package (provided upon request).
MSD	Matrix spike duplicate means a replicate matrix spike that is prepared and analyzed in order to determine the precision of the approved test method. The acceptable recovery range is listed in the QC Package (provided upon request).
MW	Molecular weight
ND	Not Detected at the Reporting Limit
NELAP	NELAP Accredited
PQL	Practical quantitation limit means the lowest level that can be reliably achieved within specified limits of precision and accuracy during routine laboratory operation conditions. The acceptable recovery range is listed in the QC Package (provided upon request).
RL	The reporting limit the lowest level that the data is displayed in the final report. The reporting limit may vary according to customer request or sample dilution. The reporting limit may not be less than the MDL.
RPD	Relative percent difference is a calculated difference between two recoveries (ie. MS/MSD). The acceptable recovery limit is listed in the QC Package (provided upon request).
SPK	The spike is a known mass of target analyte added to a blank sample or sub-sample; used to determine recovery deficiency or for other quality control purposes.
Surr	Surrogates are compounds which are similar to the analytes of interest in chemical composition and behavior in the analytical process, but which are not normally found in environmental samples.
TIC	Tentatively identified compound: Analytes tentatively identified in the sample by using a library search. Only results not in the calibration standard will be reported as tentatively identified compounds. Results for tentatively identified compounds that are not present in the calibration standard, but are assigned a specific chemical name based upon the library search, are calculated using total peak areas from reconstructed ion chromatograms and a response factor of one. The nearest Internal Standard is used for the calculation. The results of any TICs must be considered estimated, and are flagged with a "T". If the estimated result is above the calibration range it is flagged "ET"
TNTC	Too numerous to count (> 200 CFU)

Qualifiers

# - Unknown hydrocarbon	B - Analyte detected in associated Method Blank
E - Value above quantitation range	H - Holding times exceeded
I - Associated internal standard was outside method criteria	J - Analyte detected below quantitation limits
M - Manual Integration used to determine area response	ND - Not Detected at the Reporting Limit
R - RPD outside accepted recovery limits	S - Spike Recovery outside recovery limits
T - TIC(Tentatively identified compound)	X - Value exceeds Maximum Contaminant Level

Client: Natural Resource Technology, Inc.**Work Order:** 17081821**Client Project:** Hennepin Pond 1 & 2 Additional Testing**Report Date:** 22-Sep-17**Cooler Receipt Temp:** 1.02 °C

An employee of Teklab, Inc. collected the sample(s).

LPZ-1, LPZ-3, and LPZ-5 will not be reported; wells were dry. TM/EAH 9/8/17

LPZ-17 to be used as alternate sampling point for LPZ-5. MLA 9/8/17

Locations

Collinsville

Address 5445 Horseshoe Lake Road
Collinsville, IL 62234-7425

Phone (618) 344-1004

Fax (618) 344-1005

Email jhriley@teklabinc.com

Collinsville Air

Address 5445 Horseshoe Lake Road
Collinsville, IL 62234-7425

Phone (618) 344-1004

Fax (618) 344-1005

Email EHurley@teklabinc.com

Springfield

Address 3920 Pintail Dr
Springfield, IL 62711-9415

Phone (217) 698-1004

Fax (217) 698-1005

Email KKlostermann@teklabinc.com

Chicago

Address 1319 Butterfield Rd.
Downers Grove, IL 60515

Phone (630) 324-6855

Fax

Email jhriley@teklabinc.com

Kansas City

Address 8421 Nieman Road
Lenexa, KS 66214

Phone (913) 541-1998

Fax (913) 541-1998

Email jhriley@teklabinc.com

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

State	Dept	Cert #	NELAP	Exp Date	Lab
Illinois	IEPA	100226	NELAP	1/31/2018	Collinsville
Kansas	KDHE	E-10374	NELAP	4/30/2018	Collinsville
Louisiana	LDEQ	166493	NELAP	6/30/2018	Collinsville
Louisiana	LDEQ	166578	NELAP	6/30/2018	Collinsville
Texas	TCEQ	T104704515-12-1	NELAP	7/31/2018	Collinsville
Arkansas	ADEQ	88-0966		3/14/2018	Collinsville
Illinois	IDPH	17584		5/31/2019	Collinsville
Indiana	ISDH	C-IL-06		1/31/2018	Collinsville
Kentucky	KDEP	98006		12/31/2017	Collinsville
Kentucky	UST	0073		1/31/2018	Collinsville
Louisiana	LDPH	LA170027		12/31/2017	Collinsville
Missouri	MDNR	930		1/31/2018	Collinsville
Missouri	MDNR	00930		5/31/2017	Collinsville
Oklahoma	ODEQ	9978		8/31/2018	Collinsville
Tennessee	TDEC	04905		1/31/2018	Collinsville

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing
Lab ID: 17081821-001
Matrix: LEACHATE

Work Order: 17081821
Report Date: 22-Sep-17
Client Sample ID: L4
Collection Date: 09/06/2017 15:15

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		14.57	ft	1	09/06/2017 15:15	R237731
STANDARD METHOD 4500-H B FIELD								
pH		1.00		7.85		1	09/06/2017 15:15	R237731
STANDARD METHODS 2130 B FIELD								
Turbidity		1.0		8.5	NTU	1	09/06/2017 15:15	R237731
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential		-300		-85	mV	1	09/06/2017 15:15	R237731
STANDARD METHODS 2510 B FIELD								
Conductivity		1		1130	µS/cm	1	09/06/2017 15:15	R237731
STANDARD METHODS 2550 B FIELD								
Temperature		0		14.72	°C	1	09/06/2017 15:15	R237731
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved		1.00		< 1.00	mg/L	1	09/06/2017 15:15	R237731
STANDARD METHODS 2320 B								
Alkalinity, Total (as CaCO ₃)	NELAP	0		220	mg/L	1	09/11/2017 15:05	R237563
STANDARD METHODS 2320 B								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	09/11/2017 15:05	R237566
STANDARD METHODS 2320 B (TOTAL)								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		220	mg/L	1	09/11/2017 15:05	R237565
STANDARD METHODS 2540 C (TOTAL)								
Total Dissolved Solids	NELAP	20		972	mg/L	1	09/12/2017 16:16	R237592
SW-846 9036 (TOTAL)								
Sulfate	NELAP	200		419	mg/L	20	09/12/2017 15:46	R237579
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.19	mg/L	1	09/08/2017 18:28	R237461
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		21	mg/L	1	09/12/2017 15:08	R237578
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.050		202	mg/L	1	09/11/2017 14:25	133977
Magnesium	NELAP	0.050		35.1	mg/L	1	09/11/2017 14:25	133977
Potassium	NELAP	0.200		12.7	mg/L	2	09/12/2017 14:25	133977
Sodium	NELAP	0.050		35.1	mg/L	1	09/11/2017 14:25	133977
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		5.1	µg/L	5	09/11/2017 15:16	133980
Arsenic	NELAP	1.0		61.0	µg/L	5	09/11/2017 15:16	133980
Barium	NELAP	1.0		51.8	µg/L	5	09/11/2017 15:16	133980
Beryllium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:16	133980
Boron	NELAP	25.0		32000	µg/L	5	09/11/2017 15:16	133980
Cadmium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:16	133980
Chromium	NELAP	1.0	J	0.3	µg/L	5	09/11/2017 15:16	133980
Cobalt	NELAP	1.0	J	0.3	µg/L	5	09/11/2017 15:16	133980
Lead	NELAP	1.0		< 1.0	µg/L	5	09/12/2017 14:29	133980
Lithium		1.0		62.7	µg/L	5	09/11/2017 15:16	133980
Molybdenum	NELAP	1.0		77.3	µg/L	5	09/11/2017 15:16	133980
Selenium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:16	133980



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

Lab ID: 17081821-001

Client Sample ID: L4

Matrix: LEACHATE

Collection Date: 09/06/2017 15:15

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Thallium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:16	133980
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	09/11/2017 9:32	133984



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

Lab ID: 17081821-005

Client Sample ID: LPZ-13

Matrix: LEACHATE

Collection Date: 09/07/2017 15:00

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		12.85	ft	1	09/07/2017 15:00	R237731



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

Lab ID: 17081821-006

Client Sample ID: LPZ-15

Matrix: LEACHATE

Collection Date: 09/07/2017 15:45

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		15.05	ft	1	09/07/2017 15:45	R237731

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing
Lab ID: 17081821-007
Matrix: LEACHATE

Work Order: 17081821
Report Date: 22-Sep-17
Client Sample ID: LPZ-17
Collection Date: 09/06/2017 15:01

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		15.92	ft	1	09/06/2017 15:01	R237731
STANDARD METHOD 4500-H B FIELD								
pH		1.00		10.46		1	09/06/2017 15:01	R237731
STANDARD METHODS 2130 B FIELD								
Turbidity		1.0		9.8	NTU	1	09/06/2017 15:01	R237731
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential		-300		-230	mV	1	09/06/2017 15:01	R237731
STANDARD METHODS 2510 B FIELD								
Conductivity		1		1820	µS/cm	1	09/06/2017 15:01	R237731
STANDARD METHODS 2550 B FIELD								
Temperature		0		16.84	°C	1	09/06/2017 15:01	R237731
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved		1.00		< 1.00	mg/L	1	09/06/2017 15:01	R237731
STANDARD METHODS 2320 B								
Alkalinity, Total (as CaCO ₃)	NELAP	0		162	mg/L	1	09/11/2017 15:20	R237563
STANDARD METHODS 2320 B								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		68	mg/L	1	09/11/2017 15:20	R237566
STANDARD METHODS 2320 B (TOTAL)								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	09/11/2017 15:20	R237565
STANDARD METHODS 2540 C (TOTAL)								
Total Dissolved Solids	NELAP	20		1910	mg/L	1	09/12/2017 16:16	R237592
SW-846 9036 (TOTAL)								
Sulfate	NELAP	500		1120	mg/L	50	09/12/2017 16:03	R237579
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10	J	0.05	mg/L	1	09/08/2017 18:30	R237461
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		16	mg/L	1	09/12/2017 15:54	R237578
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.050	S	538	mg/L	1	09/11/2017 14:31	133977
Magnesium	NELAP	0.050		2.63	mg/L	1	09/11/2017 14:31	133977
Potassium	NELAP	0.500		25.5	mg/L	5	09/12/2017 14:35	133977
Sodium	NELAP	0.050		21.6	mg/L	1	09/11/2017 14:31	133977
<i>MS QC limits for Ca are not applicable due to high sample/spike ratio.</i>								
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		1.3	µg/L	5	09/11/2017 15:24	133980
Arsenic	NELAP	1.0		38.1	µg/L	5	09/11/2017 15:24	133980
Barium	NELAP	1.0		97.2	µg/L	5	09/11/2017 15:24	133980
Beryllium	NELAP	1.0	J	0.8	µg/L	5	09/11/2017 15:24	133980
Boron	NELAP	25.0	S	28600	µg/L	5	09/11/2017 15:24	133980
Cadmium	NELAP	1.0		1.3	µg/L	5	09/11/2017 15:24	133980
Chromium	NELAP	1.0		8.3	µg/L	5	09/11/2017 15:24	133980
Cobalt	NELAP	1.0		2.3	µg/L	5	09/11/2017 15:24	133980
Lead	NELAP	1.0		15.3	µg/L	5	09/12/2017 14:37	133980
Lithium	NELAP	1.0		90.3	µg/L	5	09/11/2017 15:24	133980
Molybdenum	NELAP	1.0		299	µg/L	5	09/11/2017 15:24	133980

Client: Natural Resource Technology, Inc.**Work Order:** 17081821**Client Project:** Hennepin Pond 1 & 2 Additional Testing**Report Date:** 22-Sep-17**Lab ID:** 17081821-007**Client Sample ID:** LPZ-17**Matrix:** LEACHATE**Collection Date:** 09/06/2017 15:01

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Selenium	NELAP	1.0		7.0	µg/L	5	09/11/2017 15:24	133980
Thallium	NELAP	1.0	J	0.5	µg/L	5	09/11/2017 15:24	133980
<i>MS QC limits for B are not applicable due to high sample/spike ratio.</i>								
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	09/11/2017 9:46	133984

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing
Lab ID: 17081821-008
Matrix: LEACHATE

Work Order: 17081821
Report Date: 22-Sep-17
Client Sample ID: L4 DUP
Collection Date: 09/06/2017 15:15

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
FIELD ELEVATION MEASUREMENTS								
Depth to leachate from measuring point		0		14.57	ft	1	09/06/2017 15:15	R237731
STANDARD METHOD 4500-H B FIELD								
pH		1.00		7.85		1	09/06/2017 15:15	R237731
STANDARD METHODS 2130 B FIELD								
Turbidity		1.0		8.5	NTU	1	09/06/2017 15:15	R237731
STANDARD METHODS 18TH ED. 2580 B FIELD								
Oxidation-Reduction Potential		-300		-85	mV	1	09/06/2017 15:15	R237731
STANDARD METHODS 2510 B FIELD								
Conductivity		1		1130	µS/cm	1	09/06/2017 15:15	R237731
STANDARD METHODS 2550 B FIELD								
Temperature		0		14.72	°C	1	09/06/2017 15:15	R237731
STANDARD METHODS 4500-O G FIELD								
Oxygen, Dissolved		1.00		< 1.00	mg/L	1	09/06/2017 15:15	R237731
STANDARD METHODS 2320 B								
Alkalinity, Total (as CaCO ₃)	NELAP	0		226	mg/L	1	09/11/2017 15:28	R237563
STANDARD METHODS 2320 B								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	09/11/2017 15:28	R237566
STANDARD METHODS 2320 B (TOTAL)								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		226	mg/L	1	09/11/2017 15:28	R237565
STANDARD METHODS 2540 C (TOTAL)								
Total Dissolved Solids	NELAP	20		954	mg/L	1	09/12/2017 16:46	R237592
SW-846 9036 (TOTAL)								
Sulfate	NELAP	100		439	mg/L	10	09/12/2017 16:11	R237579
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		0.19	mg/L	1	09/08/2017 18:34	R237461
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		22	mg/L	1	09/12/2017 16:02	R237578
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.050		210	mg/L	1	09/11/2017 14:48	133977
Magnesium	NELAP	0.050		35.2	mg/L	1	09/11/2017 14:48	133977
Potassium	NELAP	0.200		12.5	mg/L	2	09/12/2017 14:53	133977
Sodium	NELAP	0.050		35.3	mg/L	1	09/11/2017 14:48	133977
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		4.5	µg/L	5	09/11/2017 15:33	133980
Arsenic	NELAP	1.0		66.4	µg/L	5	09/11/2017 15:33	133980
Barium	NELAP	1.0		59.1	µg/L	5	09/11/2017 15:33	133980
Beryllium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:33	133980
Boron	NELAP	25.0		33300	µg/L	5	09/11/2017 15:33	133980
Cadmium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:33	133980
Chromium	NELAP	1.0	J	0.3	µg/L	5	09/11/2017 15:33	133980
Cobalt	NELAP	1.0	J	0.3	µg/L	5	09/11/2017 15:33	133980
Lead	NELAP	1.0		< 1.0	µg/L	5	09/12/2017 14:45	133980
Lithium	NELAP	1.0		63.8	µg/L	5	09/11/2017 15:33	133980
Molybdenum	NELAP	1.0		74.4	µg/L	5	09/11/2017 15:33	133980
Selenium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:33	133980



Laboratory Results

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

Lab ID: 17081821-008

Client Sample ID: L4 DUP

Matrix: LEACHATE

Collection Date: 09/06/2017 15:15

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Thallium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:33	133980
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	09/11/2017 9:49	133984

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing
Lab ID: 17081821-009
Matrix: LEACHATE

Work Order: 17081821
Report Date: 22-Sep-17
Client Sample ID: Field Blank
Collection Date: 09/06/2017 15:25

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Batch
STANDARD METHODS 2320 B								
Alkalinity, Total (as CaCO ₃)	NELAP	0		2	mg/L	1	09/11/2017 15:33	R237563
STANDARD METHODS 2320 B								
Alkalinity, Carbonate (as CaCO ₃)	NELAP	0		0	mg/L	1	09/11/2017 15:33	R237566
STANDARD METHODS 2320 B (TOTAL)								
Alkalinity, Bicarbonate (as CaCO ₃)	NELAP	0		2	mg/L	1	09/11/2017 15:33	R237565
STANDARD METHODS 2540 C (TOTAL)								
Total Dissolved Solids	NELAP	20	J	10	mg/L	1	09/12/2017 16:46	R237592
SW-846 9036 (TOTAL)								
Sulfate	NELAP	10		< 10	mg/L	1	09/12/2017 16:13	R237579
SW-846 9214 (TOTAL)								
Fluoride	NELAP	0.10		< 0.10	mg/L	1	09/08/2017 18:35	R237461
SW-846 9251 (TOTAL)								
Chloride	NELAP	5		< 5	mg/L	1	09/12/2017 16:10	R237578
SW-846 3005A, 6010B, METALS BY ICP (TOTAL)								
Calcium	NELAP	0.050		< 0.050	mg/L	1	09/11/2017 14:54	133977
Magnesium	NELAP	0.050		< 0.050	mg/L	1	09/11/2017 14:54	133977
Potassium	NELAP	0.100		< 0.100	mg/L	1	09/12/2017 15:02	133977
Sodium	NELAP	0.050		< 0.050	mg/L	1	09/11/2017 14:54	133977
SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)								
Antimony	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
Arsenic	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
Barium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
Beryllium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
Boron	NELAP	25.0	J	21	µg/L	5	09/12/2017 14:21	133980
Cadmium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
Chromium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
Cobalt	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
Lead	NELAP	1.0		< 1.0	µg/L	5	09/12/2017 14:21	133980
Lithium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
Molybdenum	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
Selenium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
Thallium	NELAP	1.0		< 1.0	µg/L	5	09/11/2017 15:41	133980
SW-846 7470A (TOTAL)								
Mercury	NELAP	0.20		< 0.20	µg/L	1	09/11/2017 9:52	133984

Client: Natural Resource Technology, Inc.**Work Order:** 17081821**Client Project:** Hennepin Pond 1 & 2 Additional Testing**Report Date:** 22-Sep-17

Lab Sample ID	Client Sample ID	Matrix	Fractions	Collection Date
17081821-001	L4	Leachate	2	09/06/2017 15:15
17081821-002	LPZ-1	Leachate	1	09/06/2017 13:48
17081821-003	LPZ-3	Leachate	1	09/06/2017 13:40
17081821-004	LPZ-5	Leachate	1	09/06/2017 13:36
17081821-005	LPZ-13	Leachate	1	09/07/2017 15:00
17081821-006	LPZ-15	Leachate	1	09/07/2017 15:45
17081821-007	LPZ-17	Leachate	2	09/06/2017 15:01
17081821-008	L4 DUP	Leachate	2	09/06/2017 15:15
17081821-009	Field Blank	Leachate	2	09/06/2017 15:25

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
	Test Name				
17081821-001A	L4	09/06/2017 15:15	09/08/2017 13:10		
	Field Elevation Measurements				09/06/2017 15:15
	Standard Method 4500-H B Field				09/06/2017 15:15
	Standard Methods 2130 B Field				09/06/2017 15:15
	Standard Methods 2320 B				09/11/2017 15:05
	Standard Methods 18th Ed. 2580 B Field				09/06/2017 15:15
	Standard Methods 2320 B				09/11/2017 15:05
	Standard Methods 2320 B (Total)				09/11/2017 15:05
	Standard Methods 2510 B Field				09/06/2017 15:15
	Standard Methods 2540 C (Total)				09/12/2017 16:16
	Standard Methods 2550 B Field				09/06/2017 15:15
	Standard Methods 4500-O G Field				09/06/2017 15:15
	SW-846 9036 (Total)				09/12/2017 15:46
	SW-846 9214 (Total)				09/08/2017 18:28
	SW-846 9251 (Total)				09/12/2017 15:08
17081821-001B	L4	09/06/2017 15:15	09/08/2017 13:10		
	SW-846 3005A, 6010B, Metals by ICP (Total)			09/08/2017 14:09	09/11/2017 14:25
	SW-846 3005A, 6010B, Metals by ICP (Total)			09/08/2017 14:09	09/12/2017 14:25
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			09/08/2017 14:31	09/11/2017 15:16
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			09/08/2017 14:31	09/12/2017 14:29
	SW-846 7470A (Total)			09/08/2017 14:51	09/11/2017 9:32
17081821-005A	LPZ-13	09/07/2017 15:00	09/08/2017 13:10		
	Field Elevation Measurements				09/07/2017 15:00
17081821-006A	LPZ-15	09/07/2017 15:45	09/08/2017 13:10		
	Field Elevation Measurements				09/07/2017 15:45
17081821-007A	LPZ-17	09/06/2017 15:01	09/08/2017 13:10		
	Field Elevation Measurements				09/06/2017 15:01
	Standard Method 4500-H B Field				09/06/2017 15:01
	Standard Methods 2130 B Field				09/06/2017 15:01
	Standard Methods 2320 B				09/11/2017 15:20
	Standard Methods 18th Ed. 2580 B Field				09/06/2017 15:01
	Standard Methods 2320 B				09/11/2017 15:20
	Standard Methods 2320 B (Total)				09/11/2017 15:20
	Standard Methods 2510 B Field				09/06/2017 15:01
	Standard Methods 2540 C (Total)				09/12/2017 16:16
	Standard Methods 2550 B Field				09/06/2017 15:01
	Standard Methods 4500-O G Field				09/06/2017 15:01

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

Sample ID	Client Sample ID	Collection Date	Received Date		
	Test Name			Prep Date/Time	Analysis Date/Time
	SW-846 9036 (Total)				09/12/2017 16:03
	SW-846 9214 (Total)				09/08/2017 18:30
	SW-846 9251 (Total)				09/12/2017 15:54
17081821-007B	LPZ-17	09/06/2017 15:01	09/08/2017 13:10		
	SW-846 3005A, 6010B, Metals by ICP (Total)			09/08/2017 14:09	09/11/2017 14:31
	SW-846 3005A, 6010B, Metals by ICP (Total)			09/08/2017 14:09	09/12/2017 14:35
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			09/08/2017 14:31	09/11/2017 15:24
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			09/08/2017 14:31	09/12/2017 14:37
	SW-846 7470A (Total)			09/08/2017 14:51	09/11/2017 9:46
17081821-008A	L4 DUP	09/06/2017 15:15	09/08/2017 13:10		
	Field Elevation Measurements				09/06/2017 15:15
	Standard Method 4500-H B Field				09/06/2017 15:15
	Standard Methods 2130 B Field				09/06/2017 15:15
	Standard Methods 2320 B				09/11/2017 15:28
	Standard Methods 18th Ed. 2580 B Field				09/06/2017 15:15
	Standard Methods 2320 B				09/11/2017 15:28
	Standard Methods 2320 B (Total)				09/11/2017 15:28
	Standard Methods 2510 B Field				09/06/2017 15:15
	Standard Methods 2540 C (Total)				09/12/2017 16:46
	Standard Methods 2550 B Field				09/06/2017 15:15
	Standard Methods 4500-O G Field				09/06/2017 15:15
	SW-846 9036 (Total)				09/12/2017 16:11
	SW-846 9214 (Total)				09/08/2017 18:34
	SW-846 9251 (Total)				09/12/2017 16:02
17081821-008B	L4 DUP	09/06/2017 15:15	09/08/2017 13:10		
	SW-846 3005A, 6010B, Metals by ICP (Total)			09/08/2017 14:09	09/11/2017 14:48
	SW-846 3005A, 6010B, Metals by ICP (Total)			09/08/2017 14:09	09/12/2017 14:53
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			09/08/2017 14:31	09/11/2017 15:33
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			09/08/2017 14:31	09/12/2017 14:45
	SW-846 7470A (Total)			09/08/2017 14:51	09/11/2017 9:49
17081821-009A	Field Blank	09/06/2017 15:25	09/08/2017 13:10		
	Standard Methods 2320 B				09/11/2017 15:33
	Standard Methods 2320 B				09/11/2017 15:33
	Standard Methods 2320 B (Total)				09/11/2017 15:33
	Standard Methods 2540 C (Total)				09/12/2017 16:46
	SW-846 9036 (Total)				09/12/2017 16:13
	SW-846 9214 (Total)				09/08/2017 18:35



Dates Report

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

Sample ID	Client Sample ID	Collection Date	Received Date	Prep Date/Time	Analysis Date/Time
	Test Name				
	SW-846 9251 (Total)				09/12/2017 16:10
17081821-009B	Field Blank	09/06/2017 15:25	09/08/2017 13:10		
	SW-846 3005A, 6010B, Metals by ICP (Total)			09/08/2017 14:09	09/11/2017 14:54
	SW-846 3005A, 6010B, Metals by ICP (Total)			09/08/2017 14:09	09/12/2017 15:02
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			09/08/2017 14:31	09/11/2017 15:41
	SW-846 3005A, 6020A, Metals by ICPMS (Total)			09/08/2017 14:31	09/12/2017 14:21
	SW-846 7470A (Total)			09/08/2017 14:51	09/11/2017 9:52

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing

Work Order: 17081821
Report Date: 22-Sep-17

STANDARD METHOD 4500-H B FIELD

Batch R237731		SampType: LCS		Units						
SampID: LCS-R237731										Date
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
pH	1.00		7.00	7.000	0	100.0	99.1	100.9	09/06/2017	

STANDARD METHODS 2510 B FIELD

Batch R237731		SampType: LCS		Units μ mhos/cm						
SampID: LCS-R237731										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Conductivity	1		1410	1412	0	99.9	90	110	09/06/2017	

STANDARD METHODS 2320 B

Batch R237563		SampType: MBLK		Units mg/L							
SampID: MBLK											Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Alkalinity, Total (as CaCO3)		0		0						09/11/2017	

Batch R237563		SampType: LCS		Units mg/L						
SampID: LCS										Date
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Alkalinity, Total (as CaCO3)		0		230	232.0	0	99.1	90	110	09/11/2017

Batch R237563		SampType: MS		Units mg/L						
SampID: 17081821-001AMS										Date
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Alkalinity, Total (as CaCO3)		0		310	93.00	220.0	96.8	85	115	09/11/2017

Batch R237563		SampType: MSD	Units mg/L				RPD Limit 10			
SampID: 17081821-001AMSD										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Alkalinity, Total (as CaCO3)	0		308	93.00	220.0	94.6	310.0	0.65	09/11/2017	

STANDARD METHODS 2540 C (TOTAL)

Batch R237592		SampType: MBLK		Units mg/L						
SampID: MBLK										
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Total Dissolved Solids	20		< 20						09/12/2017	
Total Dissolved Solids	20		< 20						09/12/2017	
Total Dissolved Solids	20	J	12						09/12/2017	

Batch R237592		SampType: LCS		Units mg/L						
SampID: LCS										Date
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Total Dissolved Solids		20		990	1000	0	99.0	90	110	09/12/2017

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing

Work Order: 17081821
Report Date: 22-Sep-17

STANDARD METHODS 2540 C (TOTAL)

Batch R237592		SampType: LCSQC		Units mg/L						
SampID: LCSQC										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Total Dissolved Solids		20		932	1000	0	93.2	90	110	09/12/2017
Total Dissolved Solids		20		984	1000	0	98.4	90	110	09/12/2017

Batch R237592		SampType: DUP		Units mg/L					RPD Limit 5		
SampID: 17081821-001ADUP											
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	Date Analyzed	
Total Dissolved Solids		20		984				972.0	1.23	09/12/2017	

SW-846 9036 (TOTAL)

Batch R237579		SampType: MBLK		Units mg/L						
SampID: ICB/MBLK										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Sulfate		10		< 10						09/12/2017

Batch R237579		SampType: LCS		Units mg/L						
SampID: ICV/LCS										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Sulfate		10		20	20.00	0	98.9	90	110	09/12/2017

Batch R237579		SampType: MS		Units mg/L						
SampID: 17081821-001AMS										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Sulfate		200		597	200.0	418.6	89.2	85	115	09/12/2017

Batch R237579		SampType: MSD		Units mg/L				RPD Limit 10		
SampID: 17081821-001AMSD										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Sulfate		200		611	200.0	418.6	96.4	597.0	2.37	09/12/2017

SW-846 9214 (TOTAL)

Batch R237461		SampType: MBLK		Units mg/L							
SampID: MBLK										Date Analyzed	
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride		0.10		< 0.10						09/08/2017	

Batch R237461		SampType: LCS		Units mg/L						
SampID: LCS										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Fluoride		0.10		1.06	1.000	0	105.5	90	110	09/08/2017

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing

Work Order: 17081821
Report Date: 22-Sep-17

SW-846 9214 (TOTAL)

Batch R237461		SampType: MS		Units mg/L						
SampID: 17081821-007AMS										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Fluoride	0.10		2.16	2.000	0.05000	105.6	85	115	09/08/2017	

Batch R237461		SampType: MSD	Units mg/L				RPD Limit 10			
SampID: 17081821-007AMSD										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Fluoride		0.10		2.21	2.000	0.05000	107.8	2.162	2.01	09/08/2017

SW-846 9251 (TOTAL)

Batch R237578		SampType: MBLK	Units mg/L							
SampID: ICB/MBLK										Date
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed
Chloride		5		< 5						09/12/2017

Batch R237578		SampType: LCS		Units mg/L						
SampID: ICV/LCS										Date
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Chloride	5		21	20.00	0	105.3	90	110	09/12/2017	

Batch R237578		SampType: MS		Units mg/L						
SampID: 17081821-001AMS										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Chloride	5		38	20.00	20.81	86.4	85	115	09/12/2017	

Batch R237578		SampType: MSD	Units mg/L					RPD Limit 15		Date Analyzed
SampID: 17081821-001AMSD										
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Chloride	5		38	20.00	20.81	86.4	38.08	0.05	09/12/2017	

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 133977		SampType: MBLK		Units mg/L						
SampID: MBLK-133977										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Calcium	0.0500		< 0.0500	0.05000	0	0	-100	100	09/11/2017	
Calcium	0.0500		< 0.0500	0.05000	0	0	-100	100	09/11/2017	
Magnesium	0.0500		< 0.0500	0.05000	0	0	-100	100	09/11/2017	
Magnesium	0.0500		< 0.0500	0.05000	0	0	-100	100	09/11/2017	
Potassium	0.100		< 0.100	0.1000	0	0	-100	100	09/12/2017	
Sodium	0.0500		< 0.0500	0.05000	0	0	-100	100	09/11/2017	
Sodium	0.0500		< 0.0500	0.05000	0	0	-100	100	09/11/2017	

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

SW-846 3005A, 6010B, METALS BY ICP (TOTAL)

Batch 133977		SampType: LCS		Units mg/L						
SampID: LCS-133977										Date
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Analyzed	
Calcium	0.0500		2.68	2.500	0	107.4	85	115	09/11/2017	
Calcium	0.0500		2.61	2.500	0	104.3	85	115	09/11/2017	
Magnesium	0.0500		2.63	2.500	0	105.0	85	115	09/11/2017	
Magnesium	0.0500		2.68	2.500	0	107.3	85	115	09/11/2017	
Potassium	0.100		2.38	2.500	0	95.4	85	115	09/12/2017	
Sodium	0.0500		2.39	2.500	0	95.6	85	115	09/11/2017	
Sodium	0.0500		2.47	2.500	0	98.7	85	115	09/11/2017	

Batch 133977		SampType: MS		Units mg/L						
SampID: 17081821-007BMS										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Calcium	0.050	S	536	2.500	538.2	-100.0	75	125	09/11/2017	
Magnesium	0.050		5.24	2.500	2.627	104.3	75	125	09/11/2017	
Potassium	0.500		27.9	2.500	25.48	95.8	75	125	09/12/2017	
Sodium	0.050		23.7	2.500	21.56	85.2	75	125	09/11/2017	

Batch 133977		SampType: MSD		Units mg/L				RPD Limit 20		
SampID: 17081821-007BMSD										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Calcium		0.050	S	525	2.500	538.2	-532.0	535.7	2.04	09/11/2017
Magnesium		0.050		5.22	2.500	2.627	103.9	5.235	0.19	09/11/2017
Potassium		0.500		27.7	2.500	25.48	89.8	27.88	0.54	09/13/2017
Sodium		0.050		23.8	2.500	21.56	90.4	23.69	0.55	09/11/2017

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 133980		SampType: MBLK		Units µg/L						
SampID: MBLK-133980										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit		
Antimony	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	
Arsenic	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	
Barium	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	
Beryllium	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	
Boron	25.0		< 25.0	25.00	0	0	-100	100	09/11/2017	
Cadmium	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	
Chromium	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	
Cobalt	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	
Lead	1.0		< 1.0	1.000	0	0	-100	100	09/12/2017	
Lithium	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	
Molybdenum	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	
Selenium	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	
Thallium	1.0		< 1.0	1.000	0	0	-100	100	09/11/2017	

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 133980		SampType: LCS		Units µg/L						
SampID: LCS-133980										
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed	
Antimony	1.0		487	500.0	0	97.4	80	120	09/11/2017	
Arsenic	1.0		522	500.0	0	104.3	80	120	09/11/2017	
Barium	1.0		2020	2000	0	101.0	80	120	09/11/2017	
Beryllium	1.0		52.8	50.00	0	105.7	80	120	09/11/2017	
Boron	25.0		569	500.0	0	113.8	80	120	09/11/2017	
Cadmium	1.0		48.8	50.00	0	97.7	80	120	09/11/2017	
Chromium	1.0		203	200.0	0	101.6	80	120	09/11/2017	
Cobalt	1.0		513	500.0	0	102.7	80	120	09/11/2017	
Lead	1.0		514	500.0	0	102.9	80	120	09/11/2017	
Lithium	1.0		514	500.0	0	102.7	80	120	09/11/2017	
Molybdenum	1.0		491	500.0	0	98.2	80	120	09/11/2017	
Selenium	1.0		518	500.0	0	103.6	80	120	09/11/2017	
Thallium	1.0		238	250.0	0	95.1	80	120	09/11/2017	

Batch 133980		SampType: MS		Units µg/L					
SampID: 17081821-007BMS									
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	Date Analyzed
Antimony	1.0	S	485	500.0	1.257	96.8	75	125	09/11/2017
Arsenic	1.0		556	500.0	38.14	103.5	75	125	09/11/2017
Barium	1.0		2080	2000	97.21	99.0	75	125	09/11/2017
Beryllium	1.0		52.5	50.00	0.8463	103.3	75	125	09/11/2017
Boron	25.0		29800	500.0	28580	241.2	75	125	09/11/2017
Cadmium	1.0		49.2	50.00	1.346	95.7	75	125	09/11/2017
Chromium	1.0		204	200.0	8.319	97.8	75	125	09/11/2017
Cobalt	1.0		494	500.0	2.264	98.4	75	125	09/11/2017
Lead	1.0		520	500.0	15.27	101.0	75	125	09/12/2017
Lithium	1.0		595	500.0	90.27	101.0	75	125	09/11/2017
Molybdenum	1.0		794	500.0	299.0	99.1	75	125	09/11/2017
Selenium	1.0		494	500.0	7.005	97.4	75	125	09/11/2017
Thallium	1.0		241	250.0	0.5254	96.2	75	125	09/11/2017

Client: Natural Resource Technology, Inc.
Client Project: Hennepin Pond 1 & 2 Additional Testing

Work Order: 17081821
Report Date: 22-Sep-17

SW-846 3005A, 6020A, METALS BY ICPMS (TOTAL)

Batch 133980		SampType: MSD		Units µg/L				RPD Limit 20		
SampID: 17081821-007BMSD										Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD		
Antimony	1.0		482	500.0	1.257	96.2	485.5	0.64	09/11/2017	
Arsenic	1.0		544	500.0	38.14	101.1	555.9	2.22	09/11/2017	
Barium	1.0		2060	2000	97.21	98.0	2077	0.94	09/11/2017	
Beryllium	1.0		51.5	50.00	0.8463	101.4	52.50	1.87	09/11/2017	
Boron	25.0	S	28300	500.0	28580	-54.8	29790	5.09	09/11/2017	
Cadmium	1.0		48.8	50.00	1.346	94.9	49.20	0.82	09/11/2017	
Chromium	1.0		202	200.0	8.319	96.7	204.0	1.16	09/11/2017	
Cobalt	1.0		487	500.0	2.264	97.0	494.1	1.37	09/11/2017	
Lead	1.0		521	500.0	15.27	101.1	520.4	0.06	09/12/2017	
Lithium	1.0		584	500.0	90.27	98.7	595.1	1.93	09/11/2017	
Molybdenum	1.0		777	500.0	299.0	95.5	794.3	2.24	09/11/2017	
Selenium	1.0		485	500.0	7.005	95.7	494.2	1.80	09/11/2017	
Thallium	1.0		241	250.0	0.5254	96.1	241.0	0.12	09/11/2017	

SW-846 7470A (TOTAL)

Batch 133984		SampType: MBLK		Units µg/L						
SampID: MBLK-133984										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Mercury		0.20		< 0.20	0.2000	0	0	-100	100	
										09/11/2017

Batch 133984		SampType: LCS		Units µg/L					
SampID: LCS-133984									Date Analyzed
Analyses	RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Mercury	0.20		5.32	5.000	0	106.3	85	115	
									09/11/2017

Batch 133984		SampType: MS		Units µg/L						
SampID: 17081821-001BMS										Date Analyzed
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	Low Limit	High Limit	
Mercury		0.20		4.43	5.000	0	88.7	75	125	
										09/11/2017

Batch 133984		SampType: MSD		Units µg/L				RPD Limit 15		Date Analyzed
SampID: 17081821-001BMSD										
Analyses		RL	Qual	Result	Spike	SPK Ref Val	%REC	RPD Ref Val	%RPD	
Mercury		0.20		4.36	5.000	0	87.2	4.435	1.66	09/11/2017



Receiving Check List

<http://www.teklabinc.com/>

Client: Natural Resource Technology, Inc.

Work Order: 17081821

Client Project: Hennepin Pond 1 & 2 Additional Testing

Report Date: 22-Sep-17

Carrier: Tim Mathis

Received By: AMD

Completed by:

On:

08-Sep-17

Amber M. Dilallo

Reviewed by:

On:

08-Sep-17

Marvin L. Darling

Pages to follow:

Chain of custody

1

Extra pages included

16

Shipping container/cooler in good condition?

Yes ☒

No ☐

Not Present ☐

Temp °C 1.02

Type of thermal preservation?

None ☐

Ice ☒

Blue Ice ☐

Dry Ice ☐

Chain of custody present?

Yes ☒

No ☐

Chain of custody signed when relinquished and received?

Yes ☒

No ☐

Chain of custody agrees with sample labels?

Yes ☒

No ☐

Samples in proper container/bottle?

Yes ☒

No ☐

Sample containers intact?

Yes ☒

No ☐

Sufficient sample volume for indicated test?

Yes ☒

No ☐

All samples received within holding time?

Yes ☒

No ☐

Reported field parameters measured:

Field ☒

Lab ☐

NA ☐

Container/Temp Blank temperature in compliance?

Yes ☒

No ☐

When thermal preservation is required, samples are compliant with a temperature between 0.1°C - 6.0°C, or when samples are received on ice the same day as collected.

Water - at least one vial per sample has zero headspace?

Yes ☐

No ☐

No VOA vials ☒

Water - TOX containers have zero headspace?

Yes ☐

No ☐

No TOX containers ☒

Water - pH acceptable upon receipt?

Yes ☒

No ☐

NA ☐

NPDES/CWA TCN interferences checked/treated in the field?

Yes ☐

No ☐

NA ☒

Any No responses must be detailed below or on the COC.

APPENDIX C

SUPPORTING GROUNDWATER ANALYTICAL DATA

APPENDIX C.
SUPPORTING GROUNDWATER ANALYTICAL DATA
40 C.F.R. § 257: ALTERNATIVE SOURCE DEMONSTRATION
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	Well Type	Date	Parameter	Result	Unit
22	Compliance	12/10/2015	Boron, total	6.01	mg/L
22	Compliance	03/09/2016	Boron, total	5.85	mg/L
22	Compliance	06/07/2016	Boron, total	6.28	mg/L
22	Compliance	09/15/2016	Boron, total	5.75	mg/L
22	Compliance	12/07/2016	Boron, total	6.72	mg/L
22	Compliance	02/21/2017	Boron, total	5.47	mg/L
22	Compliance	04/25/2017	Boron, total	5.29	mg/L
22	Compliance	06/08/2017	Boron, total	4.99	mg/L
22	Compliance	06/13/2018	Boron, total	5.57	mg/L
22	Compliance	09/12/2018	Boron, total	4.66	mg/L
22	Compliance	12/12/2018	Boron, total	4.92	mg/L
22	Compliance	03/13/2019	Boron, total	5.75	mg/L
22	Compliance	06/19/2019	Boron, total	5.62	mg/L
22	Compliance	09/17/2019	Boron, total	5.37	mg/L
22	Compliance	12/11/2019	Boron, total	5.70	mg/L
22	Compliance	03/11/2020	Boron, total	5.20	mg/L
22	Compliance	06/03/2020	Boron, total	5.07	mg/L
22	Compliance	09/02/2020	Boron, total	4.72	mg/L
22	Compliance	12/09/2020	Boron, total	4.77	mg/L
22	Compliance	03/19/2021	Boron, total	4.89	mg/L
22	Compliance	06/23/2021	Boron, total	4.91	mg/L
22	Compliance	09/08/2021	Boron, total	4.39	mg/L
22	Compliance	12/08/2021	Boron, total	3.81	mg/L
22	Compliance	03/22/2022	Boron, total	4.84	mg/L
22	Compliance	06/07/2022	Boron, total	3.95	mg/L
22	Compliance	09/13/2022	Boron, total	3.42	mg/L
22	Compliance	12/27/2022	Boron, total	4.44	mg/L
22	Compliance	02/28/2023	Boron, total	4.51	mg/L
22	Compliance	05/31/2023	Boron, total	3.44	mg/L
22	Compliance	12/10/2015	Cadmium, total	0.00140	mg/L
22	Compliance	03/09/2016	Cadmium, total	0.00170	mg/L
22	Compliance	06/07/2016	Cadmium, total	0.00230	mg/L
22	Compliance	09/15/2016	Cadmium, total	0.00310	mg/L
22	Compliance	12/07/2016	Cadmium, total	0.00440	mg/L
22	Compliance	02/21/2017	Cadmium, total	0.00390	mg/L
22	Compliance	04/25/2017	Cadmium, total	0.00360	mg/L
22	Compliance	06/08/2017	Cadmium, total	0.00320	mg/L
22	Compliance	06/13/2018	Cadmium, total	0.00430	mg/L
22	Compliance	09/12/2018	Cadmium, total	0.00570	mg/L
22	Compliance	12/12/2018	Cadmium, total	0.00760	mg/L
22	Compliance	03/13/2019	Cadmium, total	0.00570	mg/L
22	Compliance	06/19/2019	Cadmium, total	0.00480	mg/L
22	Compliance	09/17/2019	Cadmium, total	0.00480	mg/L
22	Compliance	12/11/2019	Cadmium, total	0.00550	mg/L
22	Compliance	03/11/2020	Cadmium, total	0.00500	mg/L
22	Compliance	06/03/2020	Cadmium, total	0.00530	mg/L

APPENDIX C.
SUPPORTING GROUNDWATER ANALYTICAL DATA
40 C.F.R. § 257: ALTERNATIVE SOURCE DEMONSTRATION
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Well ID	Well Type	Date	Parameter	Result	Unit
22	Compliance	09/02/2020	Cadmium, total	0.00530	mg/L
22	Compliance	12/09/2020	Cadmium, total	0.00900	mg/L
22	Compliance	03/19/2021	Cadmium, total	0.00590	mg/L
22	Compliance	06/23/2021	Cadmium, total	0.00600	mg/L
22	Compliance	09/08/2021	Cadmium, total	0.00540	mg/L
22	Compliance	12/08/2021	Cadmium, total	0.00540	mg/L
22	Compliance	03/22/2022	Cadmium, total	0.00570	mg/L
22	Compliance	06/07/2022	Cadmium, total	0.00570	mg/L
22	Compliance	09/13/2022	Cadmium, total	0.00570	mg/L
22	Compliance	12/27/2022	Cadmium, total	0.00590	mg/L
22	Compliance	02/28/2023	Cadmium, total	0.00960	mg/L
22	Compliance	05/31/2023	Cadmium, total	0.00520	mg/L
22	Compliance	12/10/2015	Sulfate, total	221	mg/L
22	Compliance	03/09/2016	Sulfate, total	261	mg/L
22	Compliance	06/07/2016	Sulfate, total	255	mg/L
22	Compliance	09/15/2016	Sulfate, total	208	mg/L
22	Compliance	12/07/2016	Sulfate, total	204	mg/L
22	Compliance	02/21/2017	Sulfate, total	197	mg/L
22	Compliance	04/25/2017	Sulfate, total	213	mg/L
22	Compliance	06/08/2017	Sulfate, total	229	mg/L
22	Compliance	06/13/2018	Sulfate, total	219	mg/L
22	Compliance	09/12/2018	Sulfate, total	207	mg/L
22	Compliance	12/12/2018	Sulfate, total	181	mg/L
22	Compliance	03/13/2019	Sulfate, total	179	mg/L
22	Compliance	06/19/2019	Sulfate, total	249	mg/L
22	Compliance	09/17/2019	Sulfate, total	204	mg/L
22	Compliance	12/11/2019	Sulfate, total	187	mg/L
22	Compliance	03/11/2020	Sulfate, total	220	mg/L
22	Compliance	06/03/2020	Sulfate, total	214	mg/L
22	Compliance	09/02/2020	Sulfate, total	206	mg/L
22	Compliance	12/09/2020	Sulfate, total	201	mg/L
22	Compliance	03/19/2021	Sulfate, total	179	mg/L
22	Compliance	06/23/2021	Sulfate, total	168	mg/L
22	Compliance	09/08/2021	Sulfate, total	160	mg/L
22	Compliance	12/08/2021	Sulfate, total	146	mg/L
22	Compliance	03/22/2022	Sulfate, total	145	mg/L
22	Compliance	06/07/2022	Sulfate, total	134	mg/L
22	Compliance	09/13/2022	Sulfate, total	142	mg/L
22	Compliance	12/27/2022	Sulfate, total	141	mg/L
22	Compliance	02/28/2023	Sulfate, total	145	mg/L
22	Compliance	05/31/2023	Sulfate, total	123	mg/L

APPENDIX C.
SUPPORTING GROUNDWATER ANALYTICAL DATA
40 C.F.R. § 257: ALTERNATIVE SOURCE DEMONSTRATION
HENNEPIN POWER PLANT
OLD WEST ASH POND
HENNEPIN, IL

Notes:
mg/L = milligrams per liter

**APPENDIX D
TECHNICAL MEMORANDUM
EVALUATION OF CADMIUM SOURCES WITHIN AQUIFER
SOLIDS, HENNEPIN POWER PLANT - WEST ASH POND SYSTEM**

TECHNICAL MEMORANDUM

Date: October 9, 2023

To: Brian Voelker, Vistra

Copies to: Stu Cravens and Phil Morris, Vistra
Eric Tlachac and Brian Hennings, Ramboll

From: Allison Kreinberg and Ryan Fimmen, PhD, Geosyntec Consultants

Subject: Evaluation of Cadmium Sources within Aquifer Solids
Hennepin Power Plant – West Ash Pond System

This document serves as an Appendix to the October 11, 2023, Alternative Source Demonstration (ASD) for Hennepin (HEN) Power Plant West Ash Pond System (WAPS) (Site) for the sixth assessment monitoring event (A6) (referred to as the A6 ASD), completed to fulfill the requirements of Title 40 of the Code of Federal Regulations (40 C.F.R.) § 257.95(g)(3)(ii). A previous ASD prepared by Ramboll Americas Engineering Solutions, Inc. (Ramboll) in May 2023 concluded that the SSL of cadmium at downgradient monitoring well #22 could be attributed to sources other than the WAPS and was potentially related to changing groundwater pH (Ramboll 2023). Geosyntec Consultants, Inc. (Geosyntec) has completed a review of geochemical and site conditions at the Site to evaluate the influence of the uppermost aquifer solid-phase mineralogy and geochemistry on groundwater composition. Using additional evidence from laboratory analyses and geochemical modeling, this technical memorandum demonstrates that naturally occurring cadmium associated with aquifer solids throughout the Site is a source of elevated cadmium in Site groundwater.

SITE CONDITIONS

Site geology consists primarily of unlithified alluvial and glacial deposits overlying shale bedrock. These alluvial deposits consist of the fine-grained Cahokia Alluvium, and the gravelly, glacially deposited Henry Formation. The Cahokia Alluvium deposits at the Site extend to depths of less than 20 feet and are composed of sandy silts and clays that are interbedded with sand and gravel (OBG 2017). Henry Formation deposits at the Site underlie the Cahokia Alluvium. These deposits

extend in depth to the uppermost bedrock (to a maximum of 130 feet dependent upon location at the Site) and are composed of coarse-grained materials that include gravel, coarse sands, and cobbles. The Pennsylvanian-age bedrock consists of interbedded layers of shale with thin limestone, sandstone, and coal beds.

The Henry Formation and alluvium together comprise the Uppermost Aquifer (UA) at the WAPS and extend from the water table to the bedrock. The UA is unconfined and extends from the water table to the bedrock. Additional information regarding site hydrogeology and stratigraphy is provided in the A6 ASD prepared by Ramboll.

AQUIFER SOLIDS EVALUATION

The previous ASD report for cadmium at well #22 completed by Ramboll (2023) identified naturally occurring cadmium within soil samples collected from soil borings near the Hennepin East Ash Pond System. Additional aquifer solids samples were collected near the WAPS by Geosyntec and analyzed to evaluate whether subsurface material in the vicinity of the WAPS may account for reported cadmium concentrations in groundwater. The analytical results of the aquifer solids demonstrate that the aqueous groundwater cadmium concentrations at monitoring well #22 in excess of the GWPS are derived from the native mineralogy.

Samples were collected from soil borings advanced in March 2021 adjacent to background well #34 and compliance well #22¹. One sample was collected from the screened interval of monitoring well #34 (32–33 feet bgs) and two samples were collected from the screened interval of monitoring well #22 (26–27 feet bgs and 29–30 feet bgs). Well construction forms for both wells are provided in **Attachment 1**. Field observations of the sample lithologies (provided in Table 1) were generally consistent with the lithologies for the screened intervals of well #34 and well #22 provided in the boring logs (**Attachment 1**).

Samples were submitted for analysis of total cadmium, cadmium distribution within the aquifer solids using sequential extraction procedure (SEP), and mineralogy via X-ray diffraction (XRD). Results for total and SEP analyses of cadmium in these samples are presented in **Table 1**, and the analytical laboratory reports are provided as **Attachment 2**.

SEP is an analytical technique that uses progressively stronger reagents to solubilize metals from specific phases within the solid matrix and is used to infer associations between constituents and different classes of solids (Tessier et al. 1979). These classes of solids are identified based on their

¹ An aquifer solids sample was also collected from the screened interval of well #51 during this sampling event. Results of this sample are excluded from subsequent results tables and discussion to emphasize relevant findings. Analytical results of this sample are included in the Attachments section.

solubility under different reagents and include the exchangeable fraction, the carbonate-bound fraction, the iron/manganese oxide-bound fraction, the organic matter-bound fraction, and the residual fraction. To evaluate data quality in an SEP analysis, first the sum of individual extraction steps from the SEP was compared to the total cadmium concentration. The sum of the SEP is not expected to be exactly equal to the total metals analysis but should be generally consistent with the total metals result. The total cadmium concentrations ranged from 0.53 to 2.9 micrograms per gram of soil ($\mu\text{g/g}$). The summed concentrations of cadmium from the SEP analyses ranged from 0.45 to 2.6 $\mu\text{g/g}$. The results were generally consistent between the total metals analyses and the summed SEP steps, indicating good metals recovery and data quality.

These results indicate that cadmium is naturally present in both background and compliance well solid-phase samples at the Site. The highest cadmium concentrations were observed in the samples from monitoring well #22. The largest components of cadmium in all three samples were found to be associated with the weak-acid extractable fraction (including carbonates) and the reducing agent extractable fraction (including iron and manganese oxides) (**Table 1**). Smaller components of cadmium were found to be associated with the other fractions, although 69%–83% of cadmium from all three samples was associated with a combination of carbonates and iron/manganese oxides.

Mineralogical analyses were completed using XRD to evaluate the mineralogy of the aquifer solids. Mineralogy of the samples analyzed consists primarily of quartz, various carbonate minerals (dolomite, calcite, and ankerite), various feldspar minerals (albite and microcline), and muscovite (mica). Of the mineral groups identified as present within the aquifer solids via XRD, SEP testing quantified the largest component of cadmium was leached from the weak-acid extractable and reducing agent extractable fractions, which are often associated with carbonates and oxides, respectively (**Table 1**). Carbonate minerals were found in each sample analyzed at abundances of 18 to 25 weight percent (wt. %) (**Table 2**). Magnetite, an iron oxide mineral, was detected in every sample analyzed (**Table 2**). Based on the XRD results, these minerals are abundant in samples from both well #22 and well #34 of the WAPS, suggesting that these cadmium-associated minerals occur in the UA throughout the Site and constitute a natural source of cadmium. Mineralogy results are provided in **Table 2** and the laboratory analytical report is included as **Attachment 3**.

The association of cadmium with carbonate minerals, specifically calcite, is a well-studied phenomenon. Cadmium ions can readily substitute for calcium ions in the calcite crystal structure due to similarities in charge and ionic radii between the two ions (Lorens 1981, Tesoriero and Pankow 1996). This process is known to occur via initial sorption of aqueous cadmium ions to the hydrated surface layer of calcite crystals, which then become incorporated into the calcite crystal structure during new layer growth in a process known as co-precipitation (Papadopoulos and

Rowell 1988, Reeder 1996, Horner et al. 2011, Callagon et al. 2017). The primary control on calcite solubility in groundwater is pH, with calcite solubility increasing at lower pH.

Sorption of cadmium to iron oxide minerals is also well documented, as divalent transition metals such as cadmium are known to bind strongly to iron and manganese oxides (Cowan et al. 1991, Loganathan et al. 2012). Cadmium sorption to iron oxides is primarily a function of pH, aqueous cadmium concentrations, and aqueous concentrations of competitive divalent cations such as calcium and magnesium (Cowan et al. 1991).

Aquifer solids analyses completed for well #34 and well #22 show that aquifer solids are composed of approximately 18-25% carbonate minerals. SEP results indicate the dissolution of cadmium from aquifer solids with a weak acid, consistent with cadmium association with carbonate minerals. Therefore, cadmium co-precipitation with or dissolution from carbonate minerals would influence concentrations of aqueous cadmium. Dissolution of naturally occurring cadmium-bearing carbonates constitutes a potential alternative source of cadmium. SEP results also indicated that cadmium is associated with iron/manganese oxides such as magnetite, which was detected in the samples from both wells #34 and #22. Desorption of cadmium from magnetite constitutes an additional potential alternative source of cadmium in groundwater.

GEOCHEMICAL MODELING

The previous ASD report prepared by Ramboll (2023) for cadmium at well #22 noted a downward shift in pH values of groundwater at well #22 since approximately 2013 with a corresponding increase in cadmium concentrations (**Figure 1**). A decline in pH conditions may affect aqueous cadmium concentrations due to changes in cadmium speciation by destabilizing cadmium-substituted carbonate minerals in the UA. A decrease in pH could also result in mobilization of cadmium from the existing iron oxide mineral phases such as magnetite via desorption of cadmium from mineral surfaces and dissolution of these iron oxide minerals.

Geochemical equilibrium speciation modeling was used to evaluate the impact of pH changes on aqueous cadmium concentrations at well #22. Thermodynamic reaction pathway modeling was conducted using the React module of Geochemist's Workbench (GWB) geochemical modeling software package (version 17.0.1). The purpose of the model is to show the relationship between pH and aqueous cadmium concentrations as a function of the dissolution of cadmium-bearing carbonates and the desorption of cadmium from iron oxides.

The initial aqueous component of the geochemical model was populated using the groundwater composition of the most recent sample collected at well #22 on May 31, 2023 (**Table 3**). The pH value of the aqueous component was not defined and was set as a sliding scale to test the hypothesis

that pH changes may cause changes to aqueous cadmium concentrations. Solid-phase reactants were defined based on XRD results of the well #22 samples (**Table 3**). Magnetite was included in the system with an abundance of 0.5 wt. % to evaluate the influence of sorption and desorption of cadmium from the iron oxide fraction. To represent the cadmium-bearing carbonate phase, a cadmium-calcite source phase was included as a reactant at an abundance of 5.25 wt. % (averaged from calcite abundances of the two well #22 samples) to evaluate the impact that the dissolution of calcite with co-precipitated cadmium has on aqueous cadmium concentrations. This source phase was defined with a mineral formula of $(\text{Ca}_{0.85}\text{Cd}_{0.15})\text{CO}_3$, which was determined by calibrating the model output to the May 31, 2023, well #22 analytical results for aqueous cadmium and calcium. The calcite-otavite (cadmium carbonate) solid-solution series can occur in nature across all proportion ranges depending upon geochemical conditions. This can include either 100% calcium carbonate, 100% cadmium carbonate, or any proportion of calcium and cadmium carbonate in between these two end member compositions. The selected mineral formula contains a reasonable proportion of cadmium within the crystal structure to represent coprecipitation while still retaining the general calcite crystal structure and thermodynamic traits (Ma et al. 2022).

The WATEQ4F thermodynamic database developed by the United States Geological Survey was modified to include the cadmium-calcite source phase and was used in model calculations. Thermodynamic information for the cadmium-calcite source phase was populated using the experimentally derived solubility constants of the calcite-otavite solid-solution series from Ma et al. (2022). Sorption to iron oxides was incorporated into model calculations using the Dzombak and Morel (1990) two-layer surface complexation model, which is provided in GWB as sorption dataset FeOH.sdat. This sorption dataset was modified to include magnetite as an iron oxide mineral containing sorption sites. Iron minerals hematite, goethite, and $\text{Fe}(\text{OH})_3(\text{s})$ were suppressed during model simulations due to their absence in XRD results. Pure (*i.e.*, non-substituted) calcite was suppressed in favor of using of the cadmium-calcite source phase in calculations. A porosity value of 20% was used for the UA, as indicated in the *Hydrogeologic Monitoring Plan* (OBG 2017).

The geochemical model was used to show predictions of cadmium and calcium concentrations over the pH range observed in groundwater at well #22 from 2013 to the present (**Figure 2**). Calcium concentrations are shown to illustrate the effects of dissolution of the cadmium-calcite source phase on aqueous conditions. Generally, both calcium and cadmium concentrations are predicted to increase as pH decreases toward neutral. Aqueous concentrations of cadmium are predicted to increase with decreasing pH within the pH range of 8.2 standard units (SU) to approximately 7.2 SU due to dissolution of the cadmium-calcite source phase, which decreases from approximately 3.4 wt. % to 2.3 wt. % (**Figure 3A**). Around a pH value of 7.7 SU, the model predicts that desorption of cadmium from iron oxide minerals (magnetite) will begin to occur. As

pH continues to decrease, aqueous concentrations of cadmium are predicted to increase due to the concurrent effects of the dissolution of the cadmium-calcite phase and desorption of cadmium from magnetite (**Figure 3B**).

The geochemical model was calibrated by adjusting the cadmium-calcium ratio of the source phase to align (as near as possible) with the predicted aqueous cadmium and calcium concentrations at a pH of 7.58 SU (pH measured at well #22 on May 31, 2023 used for the aqueous input) with reported values. At a pH of 7.58 SU, the model predicted aqueous cadmium and calcium concentrations of 0.0024 and 71.74 mg/L respectively, compared to reported well #22 concentrations of 0.0052 and 87.1 mg/L (**Figure 2**). These results indicate that the model output aligns closely with observed values and that the model predictions are reasonable when compared to previously reported cadmium substitution rates (Ma et. al 2022).

CONCLUSION

Naturally occurring cadmium associated with the minerals of the UA solids at the Site was identified as a source for cadmium in Site groundwater. Solid-phase samples collected from background well #34 and compliance well #22 contained cadmium, with the highest total cadmium concentrations observed in samples collected from the screened interval of the well #22. SEP analyses of the solid-phase samples determined that the majority of cadmium in the solid phase is associated with the carbonate and iron/manganese oxide fractions. XRD confirmed the presence of magnetite (an iron oxide mineral) in all samples analyzed and identified carbonate minerals that make up approximately 18-25% of the solid phase. These solid phase results verify the presence of naturally occurring cadmium within the UA and suggest dual mechanisms of cadmium mobilization that are strongly supported by literature: (1) the dissolution of calcite containing coprecipitated cadmium within the crystal structure, and (2) the desorption of cadmium from iron oxide mineral surfaces (such as magnetite).

These potential mechanisms of cadmium mobilization were evaluated using a thermodynamic reaction pathway model. Groundwater analytical data and mineralogy results were used as model inputs to assess the impact that shifts in pH values of groundwater at monitoring well #22 are predicted to have on aqueous cadmium concentrations. Model results were successfully calibrated to observed concentrations, and the model supports the conclusion that both mechanisms of cadmium mobilization should occur within the pH range of groundwater observed at well #22 and may result in increases in aqueous cadmium concentrations as a function of observed decreases in pH of groundwater at the well.

The solid-phase assessment and geochemical modeling efforts support the determination that aqueous cadmium concentration increases at downgradient monitoring well #22 are related to naturally occurring mineral-water interactions within the UA and not a release from the WAPS.

REFERENCES

- Callagon, E.B.R., S.S. Lee, P.J. Eng, N. Laanait, N.C. Sturchio, K.L. Nagy, and P. Fenter. 2017. “Heteroepitaxial growth of cadmium carbonate at dolomite and calcite surfaces: Mechanisms and rates.” *Geochimica et Cosmochimica Acta* 205(15):360-380.
- Cowan, C., J. M. Zachara, and C. T. Resch. 1991. “Cadmium adsorption on iron oxides in the presence of alkaline-earth elements.” *Environmental Science Technologies* 25(3):437–446.
- Dzombak, D. A., and F. M. Morel. 1990. *Surface Complexation Modeling: Hydrous Ferric Oxide*. New York: Wiley-Interscience.
- Horner, T.J., R. E. M. Rickaby, and G. M. Henderson. 2011. “Isotopic fractionation of cadmium into calcite.” *Earth and Planetary Science Letters* 312(1):243–253.
- Loganathan, P., S. Vigneswaran, J. Kandasamy, and R. Naidu. 2012. “Cadmium sorption and desorption in soils: a review.” *Critical Reviews in Environmental Science and Technology* 42(5):489–533.
- Lorens, R. B. 1981. “Sr, Cd, Mn, and Co distribution coefficients in calcite as a function of calcite precipitation rates.” *Geochimica et Cosmochimica Acta* 45(4):553–561.
- Ma, C., F. Xu, Z. Zhu, H. Yang, P. Nong, Z. Kang, S. Tang, L. Zhang, and Y. Zhu. 2022. “Dissolution and solubility of the calcite-otavite solid solutions $[(Ca_{1-x}Cd_x)CO_3]$ at 25 °C.” *Minerals* 12(6):756.
- OBG. 2017. *Hydrogeologic Monitoring Plan – Hennepin West Ash Pond System*. Hennepin Power Station, Hennepin, Illinois. October.
- Papadopoulos, P., and D. L. Rowell. 1988. “The reactions of cadmium with calcium carbonate surfaces.” *European Journal of Soil Science* 39(1):23–36.
- Ramboll. 2023. *Alternative Source Demonstration – Old West Ash Pond (Pond No. 1 and Pond No. 3) and Old West Polishing Pond*. Hennepin Power Plant, Hennepin, Illinois, CCR Unit 804. Ramboll Americas Engineering Solutions, Inc. May.

- Reeder, R. J. 1996. "Interaction of divalent cobalt, zinc, cadmium, and barium with the calcite surface during layer growth." *Geochimica et Cosmochimica Acta* 60(9):1543–1552.
- Tesoriero, A. J., and J. F. Pankow. 1996. "Solid solution partitioning of Sr, Ba, and Cd to calcite." *Geochimica et Cosmochimica Acta* 60(6):1053–1063.
- Tessier, A., P. G. C. Campbell, and M. Bisson. 1979. "Sequential extraction procedure for the speciation of particulate trace metals." *Analytical Chemistry* 5(7):844–851.

TABLES

**Table 1 - Cadmium SEP Results Summary
Hennepin Power Plant**

Geosyntec Consultants, Inc.

Well ID			SB-22		SB-22		SB-34	
Depth (ft)			(26-27)		(29-30)		(32-33)	
Location			Downgradient		Downgradient		Background	
Total Cadmium			0.76		2.9		0.53	
SEP Fraction	SEP Reagent	SEP Results						
			Concentration	% of Total	Concentration	% of Total	Concentration	% of Total
1	Deionized Water	Water Soluble Fraction	<0.02	--	0.04	3%	<0.02	--
2	MgCl ₂	Exchangeable Metals Fraction	<0.02	--	0.24	9%	<0.02	--
3	Sodium acetate, acetic acid	Metals Bound to Carbonates Fraction	0.37	56%	0.69	27%	0.12	27%
4	Hydroxylamine HCl and acetic acid	Metals Bound to Fe/Mn Oxides Fraction	0.16	24%	1.1	42%	0.25	56%
5	HNO ₃ , H ₂ O ₂ , and ammonium acetate	Bound to Organic Material Fraction	0.03	5%	0.25	10%	0.03	7%
6	HNO ₃ , HCl, and HF	Residual Metals Fraction	0.10	15%	0.23	9%	0.05	11%
SEP Total			0.66	100%	2.6	100%	0.45	100%

Notes:

SEP - sequential extraction procedure

All results shown in microgram of cadmium per gram of soil (µg/g).

Non-detect values are shown as less than the detection limit.

The cadmium fraction associated with each SEP phase is shown.

% of total cadmium is calculated from the sum of the SEP fractions.

**Table 2 - Summary of X-Ray Diffraction Analysis
Hennepin Power Plant**

Geosyntec Consultants, Inc.

Well ID			MW-22	MW-22	MW-34
Depth (ft bgs)			(26-27)	(29-30)	(32-33)
Location			Downgradient	Downgradient	Upgradient
Boring Log Description			Fine sand	Gravel with sand and trace clay	Fine-medium sand
Mineral/Compound	Formula	Mineral Type	(wt %)	(wt %)	(wt %)
Quartz	SiO ₂	Silicate	57.0	54.5	53.0
Dolomite	CaMg(CO ₃) ₂	Carbonate	14.4	11.4	2.6
Albite	NaAlSi ₃ O ₈	Feldspar	7.3	9.8	7.1
Calcite	CaCO ₃	Carbonate	7.2	3.3	11.1
Muscovite	KAl ₂ (AlSi ₃ O ₁₀)(OH) ₂	Mica	2.1	7.4	7.9
Microcline	KAlSi ₃ O ₈	Feldspar	5.2	5.2	5.1
Ankerite	Ca(Fe,Mg)(CO ₃) ₂	Carbonate	2.9	2.8	6.0
Chlorite	(Fe,(Mg,Mn) ₅ ,Al)(Si ₃ Al)O ₁₀ (OH) ₈	Clay	1.9	2.7	3.4
Kaolinite	Al ₂ Si ₂ O ₅ (OH) ₄	Clay	0.6	2.5	3.4
Pyrite	FeS ₂	Sulfide	-	-	0.2
Magnetite	Fe ₃ O ₄	Oxide	0.5	0.4	0.4
Actinolite	Ca ₂ (Mg,Fe) ₃ Si ₈ O ₂₂ (OH) ₂	Amphibole	0.8	-	-
Carbonate Total			25	18	20

Notes:

Dashes indicate that the mineral was not identified by the analyst and not included in the refinement calculation for the sample

The weight percent quantities indicated have been normalized to a sum of 100%. The quantity of amorphous material has not been determined.

Sample depths are shown in feet below ground surface (ft bgs).

wt %: percentage by weight

Table 3 - Summary of Geochemical Model Inputs *Geosyntec Consultants, Inc.*
Hennepin Power Plant

Aqueous Phase			
Parameter	Unit	Input Value	Source
Calcium	mg/L	87.1	May 31, 2023 sampling event
Cadmium	mg/L	0.00520	May 31, 2023 sampling event
Chloride	mg/L	97.0	May 31, 2023 sampling event
Iron	mg/L	0.0200	May 31, 2023 sampling event
Magnesium	mg/L	32.0	May 31, 2023 sampling event
Manganese	mg/L	0.0511	May 31, 2023 sampling event
Potassium	mg/L	11.4	May 31, 2023 sampling event
Sodium	mg/L	55.8	May 31, 2023 sampling event
Sulfate	mg/L	123	May 31, 2023 sampling event
Total Alkalinity	mg/L	243	May 31, 2023 sampling event
Eh	V	0.249	May 31, 2023 sampling event
Temperature	°C	15.7	May 31, 2023 sampling event
pH	SU	6.5-9	Model variable
Solid Phase			
Reactant	Unit	Input Value	Source
Magnetite	wt. %	0.5	March 2021 sample XRD
Cadmium-Calcite Source Phase ^{1,2}	wt. %	5.25	March 2021 sample XRD (calcite)
Porosity	%	20	OBG, 2017

Notes:

mg/L: milligrams per liter

V: volts

°C: degrees Celsius


SU: standard units

wt. %: weight percentage

1. Mineral formula (Ca_{0.85}Cd_{0.25})CO₃

2: A log K value of -8.98 at 25°C, interpolated from experimental results of Ma et al. (2022), was used for thermodynamic calculations

FIGURES



Notes: pH values are measured in the field during sampling events and are shown in standard units (SU). Cadmium results are shown for unfiltered samples in units of milligrams per liter (mg/L).


pH and Cadmium Time Series Graph: Monitoring Well 22

Geosyntec
consultants

Columbus, OH

August 2023

Figure
1



Notes: pH values are shown in standard units (SU). Predicted concentrations of cadmium and calcium are shown in units of milligrams per liter (mg/L) on a log scale. The historic range of measured pH values at monitoring well 22 groundwater from 2013 to the present is indicated by the green shading. Reported concentrations of calcium and cadmium from the May 31, 2023, groundwater sample collected at monitoring well 22 are indicated by red dots


Geochemical Model Output – Aqueous Cadmium and Calcium Concentrations

Geosyntec
consultants

Columbus, OH

August 2023

Figure
2



Notes: pH values are shown in standard units (SU). Plot A displays predicted abundances of the cadmium-calcite source phase in units of weight percentage (wt. %). The historic range of measured pH values at monitoring well 22 groundwater from 2013 to the present is indicated by the green shading. Plot B displays the fraction of cadmium in the system that is predicted to sorb to iron oxide minerals.

Geochemical Model Output – Source Phase Abundance and Sorbed Cadmium Fraction

Geosyntec
consultants

Columbus, OH

August 2023

Figure
3

ATTACHMENT 1
Boring Logs - Wells 22 and 34

PROJECT Hydrogeologic Study
Hennepin Power Plant
 JOB NO. 82-1293

BORING W-2
 SHEET 1 OF 1

22

DEPTH (ft)	SAMPLE			SEE REMARK #	DESCRIPTION OF MATERIALS (Color Modifier MATERIAL Classification) Soil Classification System <u>Unified</u> Surface Elevation <u>461.4</u>	BLOWS (per 6 in)	DRY UNIT WEIGHT (pcf)	Shear Strength, tsf					
	NUMBER	INTERVAL AND TYPE	ADVANCED / RECOVERED (in)					SV Δ	QP $\frac{1}{2}$ $\square$	QU $\frac{1}{2}$ $\circ$	PL	NMC	LL
	1	AS			Brown Sandy CLAY, CL			0	1	2	+	•	x
-5	2	SS	18/9		Gray - Brown Silty CLAY Trace Sand, CL	3-5-5							
-10	3	SS	18/16		Brown Fine SAND w/Silt Trace Gravel, SM	5-7-5							
-15	4	SS	18/16		Gray-Brown GRAVEL w/Sand Trace Clay, GP	19-20-28							
-20	5	SS	18/18			17-27-38							
-25	6	SS	18/13		-Coal @ 25.4'	23-18-12							
-30	7	SS	18/15		Brown Fine SAND, SP	6-11-11							
-35	8	SS	18/6		Brown GRAVEL w/Sand Trace Clay, GP-GC								
					TOB	0-4-6							

DRILLING METHOD Hollow Auger
 DATE DRILLED 12/9/82
 DRILLED BY Roberts
 LOGGED BY Maxeiner
 PIEZOMETER Yes


GROUNDWATER LEVELS

Encountered at 8.0 Feet
 Hours after completion _____ Feet
6 Days after completion 8.0 Feet
 _____ after completion _____ Feet

NOTE: Refer to the attached GENERAL NOTES and NOTATION USED ON RECORDS OF SUBSURFACE EXPLORATION for abbreviations, explanations, and qualifications relative to this log.



John Mathes & Associates, Inc.



Not to Scale



PIEZOMETER W-2

22

Monitoring Well No. 34

PROJECT TITLE: Hennepin West Ash Impoundment

DATE: 8-22-96

LOGGED BY: Mueller/Tu

DRILL RIG: Hollow Stem Auger


HOLE DIA: 7 in.

SAMPLER: Split Spoon

DRILLER: Boart Longyear

FINAL GW: 7.54 ft.

HOLE ELEV: 448.19 ft. MSL



STMI

Notes:

Project No.
135-131

2511 N. 124th St. Suite 205
Brookfield, Wisconsin 53005-8208

Page 1 of 2

Monitoring Well No. 34

PROJECT TITLE: Hennepin West Ash Impoundment

DATE: 8-22-96

LOGGED BY: Mueller/Tu

DRILL RIG: Hollow Stem Auger


HOLE DIA: 7 in.

SAMPLER: Split Spoon

DRILLER: Boart Longyear

FINAL GW: 7.54 ft.

HOLE ELEV: 448.19 ft. MSL

DESCRIPTION	USCS CLASS	GRAPHIC LOG	DEPTH	SAMPLE	WELL CONSTRUCTION DETAIL
			20		
Clayey silt, trace to little fine-grained sand and shell fragments, soft, olive-gray. Wet.			21	C-1E	
			22		
			23		
			24		
			25		
			26		
Sand, fine-grained to medium-grained, well-sorted, quartz, trace of silt, loose. Yellowish brown color grades to olive gray below 31 ft.			27	C-1F	
			28		
			29		
			30		
			31		
			32		
			33		
			34		
			35		
			36		
			37		
			38		
			40		

STMI

2511 N. 124th St. Suite 205
Brookfield, Wisconsin 53005-8208

Notes:

Project No.
135-1.31

Page 2 of 2

ATTACHMENT 2
Sequential Extraction Procedure
Laboratory Analytical Reports

**SGS Canada Inc.**

P.O. Box 4300 - 185 Concession St.
 Lakefield - Ontario - K0L 2H0
 Phone: 705-652-2000 FAX: 705-652-6365

Project : Hennepin MNA

06-April-2021

SiREM Laboratory**Attn :** Michael Healey

130 Stone Road W
 Guelph, ON
 N1G 3Z2, Canada

Phone: 519-822-2265
 Fax: 519-822-3151

Date Rec. : 05 March 2021
LR Report: CA14198-MAR21
Reference: P.O# 80003210A

Copy: #1

CERTIFICATE OF ANALYSIS

Final Report

Analysis	1: Analysis Start Date	2: Analysis Start Time	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Sample Date & Time					04-Mar-21 12:15	04-Mar-21 12:30	04-Mar-21 12:40	04-Mar-21 13:00
Sulphide [%]	22-Mar-21	12:31	22-Mar-21	17:06	0.09	0.18	< 0.04	0.06
SO ₄ [%]	23-Mar-21	07:20	25-Mar-21	09:13	< 0.1	< 0.1	< 0.1	< 0.1
TOC [%]	22-Mar-21	02:08	22-Mar-21	17:06	1.92	3.55	0.339	4.55
TS LOI [mg/L]	11-Mar-21	19:34	16-Mar-21	09:39	64100	70500	15400	74800
Ag [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	< 0.05	0.06	< 0.05	0.08
Al [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	5000	8200	2800	3700
As [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	2.7	3.5	5.1	8.4
Ba [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	47	84	20	31
Be [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	0.29	0.50	0.20	0.87
B [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	5	10	6	7
Bi [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	0.23	0.59	0.13	0.26
Ca [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	52000	91000	56000	36000
Cd [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	0.53	0.89	0.76	2.9
Co [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	6.9	9.3	5.2	9.8
Cr [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	45	27	79	130
Cu [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	8	14	11	25
Fe [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	10000	14000	9400	12000
K [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	1200	1900	910	1200
Li [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	6	12	4	6
Mg [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	13000	15000	21000	16000
Mn [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	260	350	310	220
Mo [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	0.9	2.0	3.1	5.0
Na [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	180	170	190	160
Ni [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	12	19	15	43
Pb [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	6.1	11	7.7	28
P [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	380	430	350	330
Se [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	< 0.7	1.1	< 0.7	0.8
Si [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	7200	4500	5400	1600
Sb [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	< 0.8	< 0.8	< 0.8	< 0.8
Sn [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	1.1	0.6	< 0.5	0.5
Ti [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	0.16	0.25	0.13	0.26
U [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	0.65	1.2	1.3	1.8
V [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	12	18	17	41

SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - KOL 2H0
Phone: 705-652-2000 FAX: 705-652-6365

Project : Hennepin MNA

LR Report : CA14198-MAR21

Analysis	1: Analysis Start Date	2: Analysis Start Time	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
W [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	0.06	0.05	0.07	0.10
Y [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	5.7	8.0	6.1	7.6
Zn [µg/g]	05-Apr-21	14:43	06-Apr-21	11:29	40	67	46	91

Catharine Arnold

Catharine Arnold, B.Sc., C.Chem
Project Specialist,
Environment, Health & Safety



SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.

Lakefield - Ontario - KOL 2H0

Phone: 705-652-2000 FAX: 705-652-6365

SiREM Laboratory

Attn : Michael Healey

130 Stone Road W

Guelph, ON

N1G 3Z2, Canada

Phone: 519-822-2265

Fax: 519-822-3151

water soluble

Project : Hennepin MNA

30-March-2021

Date Rec. : 05 March 2021

LR Report: CA14201-MAR21

Reference: P.O# 800003210A

Copy: #1


CERTIFICATE OF ANALYSIS


Final Report

Analysis	1: Analysis Start Date	2: Analysis Start Time	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Sample Date & Time					04-Mar-21 12:15	04-Mar-21 12:30	04-Mar-21 12:40	04-Mar-21 13:00
Ag [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.05	< 0.05	< 0.05	< 0.05
Al [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	120	140	32	310
As [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.5	< 0.5	< 0.5	< 0.5
Ba [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	0.8	0.9	0.2	1.5
Be [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.02	< 0.02	< 0.02	0.02
B [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 1	1	< 1	1
Bi [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.09	< 0.09	< 0.09	< 0.09
Ca [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	500	600	220	410
Cd [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.02	< 0.02	< 0.02	0.04
Co [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	0.03	0.04	0.02	0.23
Cr [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.5	< 0.5	< 0.5	1.6
Cu [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.1	< 0.1	< 0.1	0.5
Fe [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	72	68	22	310
K [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	110	140	99	220
Li [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 2	< 2	< 2	< 2

Analysis	1: Analysis Start Date	2: Analysis Start Time	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Mg [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	89	120	100	140
Mn [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	1.4	1.3	0.5	4.0
Mo [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	0.1	0.6	0.1	0.3
Na [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	28	35	40	52
Ni [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.5	< 0.5	< 0.5	0.7
P [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	4	4	< 3	10
Pb [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.1	< 0.1	< 0.1	0.7
Si [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	300	290	120	740
Sb [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.8	< 0.8	< 0.8	< 0.8
Se [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.7	< 0.7	< 0.7	< 0.7
Sn [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.5	< 0.5	< 0.5	< 0.5
Tl [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.02	< 0.02	< 0.02	< 0.02
U [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	0.016	0.043	0.004	0.069
V [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 3	< 3	< 3	4
W [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.04	< 0.04	< 0.04	< 0.04
Y [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	0.045	0.042	0.029	0.15
Zn [µg/g]	26-Mar-21	11:11	26-Mar-21	17:50	< 0.7	< 0.7	< 0.7	2.5

Fraction 1 - Water Soluble


Catharine Arnold, B.Sc., C.Chem
Project Specialist,
Environment, Health & Safety





SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - KOL 2H0
Phone: 705-652-2000 FAX: 705-652-6365

SiREM Laboratory

Attn : Michael Healey

130 Stone Road W
Guelph, ON
N1G 3Z2, Canada

Phone: 519-822-2265
Fax: 519-822-3151

Fraction 1 Exchangeable Metals

Project : Hennepin MNA

30-March-2021

Date Rec. : 05 March 2021
LR Report: CA14202-MAR21
Reference: P.O# 800003210A

Copy: #1


CERTIFICATE OF ANALYSIS

Final Report

Analysis	1: Analysis Start Date	2: Analysis Start Time	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Sample Date & Time					04-Mar-21 12:15	04-Mar-21 12:30	04-Mar-21 12:40	04-Mar-21 13:00
Ag [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.05	< 0.05	< 0.05	< 0.05
Al [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	3	4	< 1	3
As [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.5	< 0.5	< 0.5	< 0.5
Ba [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	4.0	4.7	1.5	5.0
Be [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.02	< 0.02	< 0.02	< 0.02
B [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 1	< 1	< 1	< 1
Bi [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.09	< 0.09	< 0.09	< 0.09
Ca [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	2200	3200	1000	3500
Cd [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.02	< 0.02	< 0.02	0.24
Co [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	0.02	0.03	< 0.01	0.10
Cr [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.5	< 0.5	< 0.5	< 0.5
Cu [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	0.1	< 0.1	< 0.1	< 0.1
Fe [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	5	6	< 1	2
K [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	57	88	58	92
Li [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 2	< 2	< 2	< 2

Analysis	1: Analysis Start Date	2: Analysis Start Time	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Mn [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	6.5	8.5	1.5	17
Mo [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.1	0.1	< 0.1	< 0.1
Na [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	8	9	11	12
Ni [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.5	< 0.5	< 0.5	< 0.5
Pb [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.1	< 0.1	< 0.1	< 0.1
P [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 3	< 3	< 3	< 3
Sb [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.8	< 0.8	< 0.8	< 0.8
Se [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.7	< 0.7	< 0.7	< 0.7
Si [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	32	30	45	30
Sn [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.5	< 0.5	< 0.5	< 0.5
Tl [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.02	< 0.02	< 0.02	< 0.02
U [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	0.017	0.061	0.021	0.024
V [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 3	< 3	< 3	< 3
W [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.04	< 0.04	< 0.04	< 0.04
Y [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	0.006	0.006	0.004	0.008
Zn [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.7	< 0.7	< 0.7	< 0.7

Exchangeable Metals



 Catharine Arnold, B.Sc., C.Chem
 Project Specialist,
 Environment, Health & Safety



SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - KOL 2H0
Phone: 705-652-2000 FAX: 705-652-6365

SiREM Laboratory

Attn : Michael Healey

130 Stone Road W
Guelph, ON
N1G 3Z2, Canada

Phone: 519-822-2265
Fax: 519-822-3151

Fraction 2 Metals Bound to Carbonates

Project : Hennepin MNA

30-March-2021

Date Rec. : 05 March 2021
LR Report: CA14203-MAR21
Reference: P.O# 800003210A

Copy: #1


CERTIFICATE OF ANALYSIS

Final Report

Analysis	1: Analysis Start Date	2: Analysis Start Time	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Sample Date & Time					04-Mar-21 12:15	04-Mar-21 12:30	04-Mar-21 12:40	04-Mar-21 13:00
Ag [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.05	< 0.05	< 0.05	< 0.05
Al [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	5	2	28	6
As [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.5	< 0.5	< 0.5	< 0.5
Ba [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	20	22	6.0	7.5
Be [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.02	< 0.02	< 0.02	0.03
B [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 1	< 1	< 1	1
Bi [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.09	< 0.09	< 0.09	< 0.09
Ca [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	30000	30000	24000	13000
Cd [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	0.12	0.11	0.37	0.69
Co [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	0.39	0.39	1.1	1.1
Cr [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.5	< 0.5	2.6	9.6
Cu [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.1	< 0.1	0.2	< 0.1
Fe [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	8	4	41	32
K [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	41	49	45	67
Li [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 2	< 2	< 2	< 2

Analysis	1: Analysis Start Date	2: Analysis Start Time	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Mg [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	2800	4700	2200	7000
Mn [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	78	74	140	69
Mo [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.1	< 0.1	< 0.1	< 0.1
Ni [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.5	< 0.5	2.7	1.9
Pb [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	0.2	0.2	0.3	0.6
P [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 3	< 3	< 3	< 3
Sb [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.8	< 0.8	< 0.8	< 0.8
Se [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.7	< 0.7	< 0.7	< 0.7
Si [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	90	77	70	110
Sn [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.5	< 0.5	< 0.5	< 0.5
Tl [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.02	< 0.02	< 0.02	< 0.02
U [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	0.039	0.15	0.089	0.030
V [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 3	< 3	< 3	< 3
W [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	< 0.04	< 0.04	< 0.04	< 0.04
Y [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	0.57	0.26	1.0	0.23
Zn [µg/g]	26-Mar-21	11:11	26-Mar-21	17:51	1.4	1.4	1.6	1.7

Fraction 2 Metals Bound to Carbonates

Catharine Arnold

Catharine Arnold, B.Sc., C.Chem
Project Specialist,
Environment, Health & Safety



SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - K0L 2H0
Phone: 705-652-2000 FAX: 705-652-6365

SiREM Laboratory

Attn : Michael Healey

130 Stone Road W
Guelph, ON
N1G 3Z2, Canada

Phone: 519-822-2265
Fax: 519-822-3151

Fraction 3 Metals Bound to Fe and Mn Oxides

Project : Hennepin MNA

30-March-2021

Date Rec. : 05 March 2021
LR Report: CA14204-MAR21
Reference: P.O# 800003210A

Copy: #1



CERTIFICATE OF ANALYSIS

Final Report

Analysis	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Sample Date & Time			04-Mar-21 12:15	04-Mar-21 12:30	04-Mar-21 12:40	04-Mar-21 13:00
Ag [µg/g]	26-Mar-21	17:51	< 0.05	< 0.05	< 0.05	< 0.05
Al [µg/g]	26-Mar-21	17:51	270	320	270	230
As [µg/g]	26-Mar-21	17:51	0.8	0.9	< 0.5	< 0.5
Ba [µg/g]	26-Mar-21	17:51	8.6	29	3.4	5.9
Be [µg/g]	26-Mar-21	17:51	0.14	0.22	0.07	0.48
B [µg/g]	26-Mar-21	17:51	1	2	2	2
Bi [µg/g]	26-Mar-21	17:51	0.12	0.29	< 0.09	< 0.09
Ca [µg/g]	26-Mar-21	17:51	18000	49000	30000	18000
Cd [µg/g]	26-Mar-21	17:51	0.25	0.59	0.16	1.1
Co [µg/g]	26-Mar-21	17:51	1.4	2.2	0.70	2.6
Cr [µg/g]	26-Mar-21	17:51	14	5.3	30	28
Cu [µg/g]	26-Mar-21	17:51	0.1	< 0.1	1.6	0.3
Fe [µg/g]	26-Mar-21	17:51	3100	2500	1600	1100
K [µg/g]	26-Mar-21	17:51	54	73	61	82
Li [µg/g]	26-Mar-21	17:51	< 2	< 2	< 2	< 2

Analysis	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Mg [µg/g]	26-Mar-21	17:51	9000	7000	17000	10000
Mn [µg/g]	26-Mar-21	17:51	110	170	90	65
Mo [µg/g]	26-Mar-21	17:51	0.1	0.2	0.5	0.2
Na [µg/g]	26-Mar-21	17:51	850	3700	540	2200
Ni [µg/g]	26-Mar-21	17:51	2.9	3.7	3.1	9.9
Pb [µg/g]	26-Mar-21	17:51	3.1	5.7	3.1	7.7
P [µg/g]	26-Mar-21	17:51	100	71	59	35
Sb [µg/g]	26-Mar-21	17:51	< 0.8	< 0.8	< 0.8	< 0.8
Se [µg/g]	26-Mar-21	17:51	< 0.7	< 0.7	< 0.7	< 0.7
Si [µg/g]	26-Mar-21	17:51	480	450	410	410
Sn [µg/g]	26-Mar-21	17:51	< 0.5	< 0.5	< 0.5	< 0.5
Tl [µg/g]	26-Mar-21	17:51	0.02	0.03	0.03	< 0.02
U [µg/g]	26-Mar-21	17:51	0.095	0.19	0.27	0.31
V [µg/g]	26-Mar-21	17:51	< 3	< 3	< 3	4
W [µg/g]	26-Mar-21	17:51	< 0.04	< 0.04	< 0.04	< 0.04
Y [µg/g]	26-Mar-21	17:51	1.8	2.6	1.8	1.4
Zn [µg/g]	26-Mar-21	17:51	14	24	7.4	26

Fraction 3 Metals Bound to Fe and Mn Oxides



Catharine Arnold, B.Sc., C.Chem
Project Specialist,
Environment, Health & Safety



SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.

Lakefield - Ontario - KOL 2H0

Phone: 705-652-2000 FAX: 705-652-6365

SiREM Laboratory

Attn : Michael Healey

130 Stone Road W

Guelph, ON

N1G 3Z2, Canada

Phone: 519-822-2265

Fax: 519-822-3151

Fraction 4 Bound to Organic Material

30-March-2021

Date Rec. : 08 March 2021
LR Report: CA14205-MAR21
Reference: P.O# 800003210A

Copy: #1


CERTIFICATE OF ANALYSIS

Final Report

Analysis	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Sample Date & Time			04-Mar-21 12:15	04-Mar-21 12:30	04-Mar-21 12:40	04-Mar-21 13:00
Ag [µg/g]	26-Mar-21	17:51	< 0.05	< 0.05	< 0.05	< 0.05
Al [µg/g]	26-Mar-21	17:51	77	120	150	630
As [µg/g]	26-Mar-21	17:51	< 0.5	< 0.5	< 0.5	< 0.5
Ba [µg/g]	26-Mar-21	17:51	1.5	5.5	1.1	2.4
Be [µg/g]	26-Mar-21	17:51	< 0.02	< 0.02	< 0.02	0.18
B [µg/g]	26-Mar-21	17:51	< 1	1	< 1	< 1
Bi [µg/g]	26-Mar-21	17:51	< 0.09	< 0.09	< 0.09	< 0.09
Ca [µg/g]	26-Mar-21	17:51	1800	3700	600	1300
Cd [µg/g]	26-Mar-21	17:51	0.03	0.03	0.03	0.25
Co [µg/g]	26-Mar-21	17:51	1.0	0.87	0.12	1.1
Cr [µg/g]	26-Mar-21	17:51	3.8	2.5	3.3	20
Cu [µg/g]	26-Mar-21	17:51	2.0	3.4	1.0	11
Fe [µg/g]	26-Mar-21	17:51	170	180	34	1100
K [µg/g]	26-Mar-21	17:51	12	22	24	45
Li [µg/g]	26-Mar-21	17:51	< 2	< 2	< 2	< 2

Analysis	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Mg [µg/g]	26-Mar-21	17:51	1800	3400	240	490
Mn [µg/g]	26-Mar-21	17:51	5.1	7.5	3.5	11
Mo [µg/g]	26-Mar-21	17:51	0.2	0.1	0.3	1.0
Na [µg/g]	26-Mar-21	17:51	10	65	15	36
Ni [µg/g]	26-Mar-21	17:51	1.1	1.8	0.7	15
Pb [µg/g]	26-Mar-21	17:51	0.2	0.2	0.2	1.9
P [µg/g]	26-Mar-21	17:51	70	51	23	24
Sb [µg/g]	26-Mar-21	17:51	< 0.8	< 0.8	< 0.8	< 0.8
Se [µg/g]	26-Mar-21	17:51	< 0.7	0.9	< 0.7	< 0.7
Si [µg/g]	26-Mar-21	17:51	130	160	220	480
Sn [µg/g]	26-Mar-21	17:51	< 0.5	< 0.5	< 0.5	< 0.5
Tl [µg/g]	26-Mar-21	17:51	0.03	0.04	< 0.02	0.02
U [µg/g]	26-Mar-21	17:51	0.097	0.086	0.12	0.48
V [µg/g]	26-Mar-21	17:51	< 3	< 3	< 3	8
W [µg/g]	26-Mar-21	17:51	< 0.04	< 0.04	< 0.04	< 0.04
Y [µg/g]	26-Mar-21	17:51	0.42	0.31	1.0	3.0
Zn [µg/g]	26-Mar-21	17:51	2.5	2.8	1.7	9.7

Fraction 4 Bound to Organic Material



 Catharine Arnold, B.Sc., C.Chem
 Project Specialist,
 Environment, Health & Safety



SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - KOL 2H0
Phone: 705-652-2000 FAX: 705-652-6365

SiREM Laboratory

Attn : Michael Healey

130 Stone Road W
Guelph, ON
N1G 3Z2, Canada

Phone: 519-822-2265
Fax: 519-822-3151

Fraction 5 Residual metals

Project : Hennepin MNA

30-March-2021

Date Rec. : 05 March 2021
LR Report: CA14206-MAR21
Reference: P.O# 800003210A

Copy: #1

CERTIFICATE OF ANALYSIS

Final Report

Analysis	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Sample Date & Time			04-Mar-21 12:15	04-Mar-21 12:30	04-Mar-21 12:40	04-Mar-21 13:00
Ag [µg/g]	26-Mar-21	17:52	0.06	0.09	0.07	0.09
Al [µg/g]	26-Mar-21	17:52	22000	24000	14000	17000
As [µg/g]	26-Mar-21	17:52	1.9	2.7	3.9	6.6
Ba [µg/g]	26-Mar-21	17:52	190	170	130	130
Be [µg/g]	26-Mar-21	17:52	0.46	0.74	0.29	0.47
B [µg/g]	26-Mar-21	17:52	13	26	10	18
Bi [µg/g]	26-Mar-21	17:52	< 0.09	0.21	< 0.09	0.16
Ca [µg/g]	26-Mar-21	17:52	3000	4400	1800	1700
Cd [µg/g]	26-Mar-21	17:52	0.05	0.07	0.10	0.23
Co [µg/g]	26-Mar-21	17:52	3.9	5.4	2.9	3.9
Cr [µg/g]	26-Mar-21	17:52	37	39	54	98
Cu [µg/g]	26-Mar-21	17:52	5.7	9.6	7.4	9.7
Fe [µg/g]	26-Mar-21	17:52	8800	14000	8500	10000
K [µg/g]	26-Mar-21	17:52	9500	10000	6500	7500
Li [µg/g]	26-Mar-21	17:52	11	18	5	13



SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.

Lakefield - Ontario - K0L 2H0

Phone: 705-652-2000 FAX: 705-652-6365



Fraction 5 Residual metals

Project : Hennepin MNA

LR Report : CA14206-MAR21

Analysis	3: Analysis Completed Date	4: Analysis Completed Time	5: SB-34 32-33'	6: SB-51 42-43'	7: SB-22 26-27'	8: SB-22 29-30'
Mg [µg/g]	26-Mar-21	17:52	1900	2300	1100	1100
Mn [µg/g]	26-Mar-21	17:52	68	95	60	54
Mo [µg/g]	26-Mar-21	17:52	0.5	0.9	1.8	3.4
Na [µg/g]	26-Mar-21	17:52	4100	3200	3600	3900
Ni [µg/g]	26-Mar-21	17:52	8.2	14	7.4	11
Pb [µg/g]	26-Mar-21	17:52	5.2	6.5	5.3	17
P [µg/g]	26-Mar-21	17:52	130	210	160	200
Sb [µg/g]	26-Mar-21	17:52	< 0.8	< 0.8	< 0.8	1.0
Se [µg/g]	26-Mar-21	17:52	< 0.7	< 0.7	< 0.7	< 0.7
Si [µg/g]	26-Mar-21	17:52	8500	25000	34000	31000
Sn [µg/g]	26-Mar-21	17:52	2.9	3.6	2.9	4.3
Tl [µg/g]	26-Mar-21	17:52	0.23	0.34	0.15	0.29
U [µg/g]	26-Mar-21	17:52	0.84	1.4	1.0	1.3
V [µg/g]	26-Mar-21	17:52	28	49	25	78
W [µg/g]	26-Mar-21	17:52	0.24	0.40	0.15	0.23
Y [µg/g]	26-Mar-21	17:52	4.1	4.1	3.3	3.1
Zn [µg/g]	26-Mar-21	17:52	24	39	33	62

Fraction 5 Residual metals



 Catharine Arnold, B.Sc., C.Chem
 Project Specialist,
 Environment, Health & Safety

ATTACHMENT 3
X-Ray Diffraction
Laboratory Analytical Report



Quantitative X-Ray Diffraction by Rietveld Refinement

Report Prepared for: Environmental Services

Project Number/ LIMS No. Custom XRD/MI4516-MAR21

Sample Receipt: March 12, 2021

Sample Analysis: March 25, 2021

Reporting Date: April 8, 2021

Instrument: BRUKER AXS D8 Advance Diffractometer

Test Conditions: Co radiation, 35 kV, 40 mA
Regular Scanning: Step: 0.02°, Step time: 1s, 2θ range: 3-80°

Interpretations : PDF2/PDF4 powder diffraction databases issued by the International Center for Diffraction Data (ICDD). DiffracPlus Eva and Topas software.

Detection Limit : 0.5-2%. Strongly dependent on crystallinity.

Contents:

- 1) Method Summary
- 2) Quantitative XRD Results
- 3) XRD Pattern(s)

Kim Gibbs, H.B.Sc., P.Geo.
Senior Mineralogist

Huyun Zhou, Ph.D., P.Geo.
Senior Mineralogist

ACCREDITATION: SGS Minerals Services Lakefield is accredited to the requirements of ISO/IEC 17025 for specific tests as listed on our scope of accreditation, including geochemical, mineralogical and trade mineral tests. To view a list of the accredited methods, please visit the following website and search SGS Canada - Minerals Services - Lakefield: <http://palcan.scc.ca/SpecsSearch/GLSearchForm.do>.



Method Summary

The Rietveld Method of Mineral Identification by XRD (ME-LR-MIN-MET-MN-D05) method used by SGS Minerals Services is accredited to the requirements of ISO/IEC 17025.

Mineral Identification and Interpretation:

Mineral identification and interpretation involves matching the diffraction pattern of an unknown material to patterns of single-phase reference materials. The reference patterns are compiled by the Joint Committee on Powder Diffraction Standards - International Center for Diffraction Data (JCPDS-ICDD) database and released on software as Powder Diffraction Files (PDF).

Interpretations do not reflect the presence of non-crystalline and/or amorphous compounds, except when internal standards have been added by request. Mineral proportions may be strongly influenced by crystallinity, crystal structure and preferred orientations. Mineral or compound identification and quantitative analysis results should be accompanied by supporting chemical assay data or other additional tests.

Quantitative Rietveld Analysis:

Quantitative Rietveld Analysis is performed by using Topas 4.2 (Bruker AXS), a graphics based profile analysis program built around a non-linear least squares fitting system, to determine the amount of different phases present in a multicomponent sample. Whole pattern analyses are predicated by the fact that the X-ray diffraction pattern is a total sum of both instrumental and specimen factors. Unlike other peak intensity-based methods, the Rietveld method uses a least squares approach to refine a theoretical line profile until it matches the obtained experimental patterns.

Rietveld refinement is completed with a set of minerals specifically identified for the sample. Zero values indicate that the mineral was included in the refinement calculations, but the calculated concentration was less than 0.05wt%. Minerals not identified by the analyst are not included in refinement calculations for specific samples and are indicated with a dash.

DISCLAIMER: This document is issued by the Company under its General Conditions of Service accessible at <http://www.sgs.com/en/Terms-and-Conditions.aspx>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law.

WARNING: The sample(s) to which the findings recorded herein (the "Findings") relate was(were) drawn and / or provided by the Client or by a third party acting at the Client's direction. The Findings constitute no warranty of the sample's representativeness of any goods and strictly relate to the sample(s). The Company accepts no liability with regard to the origin or source from which the sample(s) is/are said to be extracted.

Summary of Rietveld Quantitative Analysis X-Ray Diffraction Results

Mineral/Compound	SB-34 32-33' MAR4516-01 (wt %)	SB-51 42-43' MAR4516-02 (wt %)	SB-22 26-27' MAR4516-03 (wt %)	SB-22 29-30' MAR4516-04 (wt %)
Quartz	53.0	33.1	57.0	54.5
Microcline	5.1	9.8	5.2	5.2
Chlorite	3.4	6.8	1.9	2.7
Kaolinite	3.4	3.4	0.6	2.5
Muscovite	7.9	12.5	2.1	7.4
Calcite	11.1	20.9	7.2	3.3
Dolomite	2.6	5.0	14.4	11.4
Ankerite	6.0	1.3	2.9	2.8
Pyrite	0.2	0.3	-	-
Magnetite	0.4	0.2	0.5	0.4
Albite	7.1	6.6	7.3	9.8
Actinolite	-	-	0.8	-
TOTAL	100	100	100	100


Zero values indicate that the mineral was included in the refinement, but the calculated concentration is below a measurable value.

Dashes indicate that the mineral was not identified by the analyst and not included in the refinement calculation for the sample.


The weight percent quantities indicated have been normalized to a sum of 100%. The quantity of amorphous material has not been determined.

Mineral/Compound	Formula
Quartz	SiO ₂
Microcline	KAlSi ₃ O ₈
Chlorite	(Fe,(Mg,Mn) ₅ ,Al)(Si ₃ Al)O ₁₀ (OH) ₈
Kaolinite	Al ₂ Si ₂ O ₅ (OH) ₄
Muscovite	KAl ₂ (AlSi ₃ O ₁₀)(OH) ₂
Calcite	CaCO ₃
Dolomite	CaMg(CO ₃) ₂
Ankerite	CaFe(CO ₃) ₂
Pyrite	FeS ₂
Magnetite	Fe ₃ O ₄
Albite	NaAlSi ₃ O ₈
Actinolite	Ca ₂ (Mg,Fe) ₅ Si ₈ O ₂₂ (OH) ₂

SB-34 32-33'



SB-22 26-27'



SB-22 29-30'

