



Dynegy Midwest Generation, LLC
1500 Eastport Plaza Drive
Collinsville, IL 62234

January 10, 2025

Illinois Environmental Protection Agency
DWPC – Permits MC#15
Attn: Part 845 Coal Combustion Residual Rule Submittal
1021 North Grand Avenue East
Springfield, IL 62794

Re: Hennepin Power Plant East Ash Pond; IEPA ID # W1550100002-05

Dear Mr. LeCrone:

In accordance with Title 35 of the Illinois Administrative Code (35 I.A.C.) Section (§) 845.610(b)(3)(D), Dynegy Midwest Generation, LLC is submitting groundwater monitoring data for the Quarter 4, 2024 sampling event at the Hennepin Power Plant East Ash Pond, identified by Illinois Environmental Protection Agency (IEPA) ID No. W1550100002-05. This data is being submitted and placed in the facility's operating record as required by 35 I.A.C. § 845.800(d)(15) within 60 days of receiving final laboratory analytical data. Results were evaluated for compliance with the groundwater protection standards (GWPSs) described in 35 I.A.C. § 845.600 to determine exceedances¹ of the GWPS.

Sincerely,

A handwritten signature in blue ink that reads "Dianna Tickner".

Dianna Tickner, PE, PMP
Senior Director, Demolition and Decommission

Enclosures

Groundwater Monitoring Data and Detected Exceedances, Quarter 4, 2024, East Ash Pond, Hennepin Power Plant, Hennepin, Illinois

¹ Throughout this document, "exceedance" or "exceedances" is intended to refer only to potential exceedances of proposed applicable background statistics or Groundwater Protection Standards (GWPSs) as described in the proposed groundwater monitoring program, which was submitted to the IEPA on October 25, 2021 as part of Dynegy Midwest Generation, LLC's operating permit application for Hennepin Power Plant East Ash Pond. That operating permit application, including the proposed groundwater monitoring program, remains under review by the IEPA and therefore Dynegy Midwest Generation, LLC has not identified any actual exceedances.

35 I.A.C. § 845.610(b)(3)(D)
GROUNDWATER MONITORING DATA AND DETECTED EXCEEDANCES¹
QUARTER 4, 2024
EAST ASH POND, HENNEPIN POWER PLANT, HENNEPIN, ILLINOIS

January 10, 2025

Samples were collected between October 8 and 10, 2024 and analyzed for the parameters listed in Title 35 of the Illinois Administrative Code (35 I.A.C.) § 845.600(a), calcium, and turbidity. Final laboratory analytical data was received on November 11, 2024.

The monitoring well locations are included in **Figure 1. Attachment A** summarizes the groundwater elevation data for the Quarter 4, 2024 sampling event. Groundwater elevation data was not collected for monitoring well 12 because the water level was below the top of the dedicated submersible pump. **Table 1** is a summary of the field parameters and analytical results. **Attachment B** contains the associated laboratory analytical reports and field data sheets for the Quarter 4, 2024 sampling event.

In accordance with 35 I.A.C. § 845.610(b)(3)(C) and the statistical analysis plan submitted with the operating permit application (Appendix A of the Groundwater Monitoring Plan², constituent concentrations observed at compliance monitoring wells in Quarter 4, 2024 were evaluated for compliance with the groundwater protection standards (GWPSs) described in 35 I.A.C. § 845.600 to determine exceedances of the GWPS (**Table 2**). **Attachment C** shows the results of the comparison to background levels.

The date of this submittal is considered to be the date that the exceedances were detected.

TABLES

Table 1	Field Parameters and Analytical Results - Quarter 4, 2024
Table 2	Evaluation of Compliance - Quarter 4, 2024

FIGURES

Figure 1	Monitoring Well Location Map
----------	------------------------------

ATTACHMENTS

Attachment A	Groundwater Elevation Data - Quarter 4, 2024
Attachment B	Laboratory Reports and Field Data Sheets - Quarter 4, 2024
Attachment C	Comparison to Background - Quarter 4, 2024

¹ Throughout this document, "exceedance" or "exceedances" is intended to refer only to potential exceedances of proposed applicable background statistics or Groundwater Protection Standards (GWPSs) as described in the proposed groundwater monitoring program, which was submitted to the IEPA on October 25, 2021 as part of Dynegy Midwest Generation, LLC's operating permit application for Hennepin Power Plant East Ash Pond. That operating permit application, including the proposed groundwater monitoring program, remains under review by the IEPA and therefore Dynegy Midwest Generation, LLC has not identified any actual exceedances.

² Ramboll Americas Engineering Solutions, Inc. (Ramboll), 2021. *Groundwater Monitoring Plan. East Ash Pond. Hennepin Power Plant. Hennepin, Illinois. October 25, 2021.*

TABLES

TABLE 1.
FIELD PARAMETERS AND ANALYTICAL RESULTS - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	Well Type	Event	Date	Parameter	Result	Unit
07	Background	E007	10/10/2024	Antimony, total	0.0013 U	mg/L
07	Background	E007	10/10/2024	Arsenic, total	0.00023 U	mg/L
07	Background	E007	10/10/2024	Barium, total	0.120	mg/L
07	Background	E007	10/10/2024	Beryllium, total	0.00053 U	mg/L
07	Background	E007	10/10/2024	Boron, total	0.0690	mg/L
07	Background	E007	10/10/2024	Cadmium, total	0.00017 U	mg/L
07	Background	E007	10/10/2024	Calcium, total	140	mg/L
07	Background	E007	10/10/2024	Chloride, total	54.0	mg/L
07	Background	E007	10/10/2024	Chromium, total	0.0011 U	mg/L
07	Background	E007	10/10/2024	Cobalt, total	0.00370	mg/L
07	Background	E007	10/10/2024	Dissolved Oxygen	5.60	mg/L
07	Background	E007	10/10/2024	Fluoride, total	0.110	mg/L
07	Background	E007	10/10/2024	Lead, total	0.00019 U	mg/L
07	Background	E007	10/10/2024	Lithium, total	0.00960	mg/L
07	Background	E007	10/10/2024	Mercury, total	0.000076 U	mg/L
07	Background	E007	10/10/2024	Molybdenum, total	0.0025 U	mg/L
07	Background	E007	10/10/2024	Oxidation Reduction Potential	113	mV
07	Background	E007	10/10/2024	pH (field)	6.8	SU
07	Background	E007	10/10/2024	Radium 226 + Radium 228, total	0.406	pCi/L
07	Background	E007	10/10/2024	Selenium, total	0.00098 U	mg/L
07	Background	E007	10/10/2024	Specific Conductance @ 25C (field)	1,144	micromhos/cm
07	Background	E007	10/10/2024	Sulfate, total	57.0	mg/L
07	Background	E007	10/10/2024	Temperature	11.5	degrees C
07	Background	E007	10/10/2024	Thallium, total	0.00057 U	mg/L
07	Background	E007	10/10/2024	Total Dissolved Solids	650	mg/L
07	Background	E007	10/10/2024	Turbidity, field	5.30	NTU
08	Background	E007	10/10/2024	Antimony, total	0.0013 U	mg/L
08	Background	E007	10/10/2024	Arsenic, total	0.00023 U	mg/L
08	Background	E007	10/10/2024	Barium, total	0.120	mg/L
08	Background	E007	10/10/2024	Beryllium, total	0.00053 U	mg/L
08	Background	E007	10/10/2024	Boron, total	0.110 J+	mg/L
08	Background	E007	10/10/2024	Cadmium, total	0.00041 J	mg/L
08	Background	E007	10/10/2024	Calcium, total	210	mg/L
08	Background	E007	10/10/2024	Chloride, total	240	mg/L
08	Background	E007	10/10/2024	Chromium, total	0.0011 U	mg/L
08	Background	E007	10/10/2024	Cobalt, total	0.00240	mg/L
08	Background	E007	10/10/2024	Dissolved Oxygen	1.89	mg/L
08	Background	E007	10/10/2024	Fluoride, total	0.086 J	mg/L
08	Background	E007	10/10/2024	Lead, total	0.00031 J	mg/L
08	Background	E007	10/10/2024	Lithium, total	0.0160	mg/L
08	Background	E007	10/10/2024	Mercury, total	0.000076 U	mg/L
08	Background	E007	10/10/2024	Molybdenum, total	0.0025 U	mg/L
08	Background	E007	10/10/2024	Oxidation Reduction Potential	146	mV
08	Background	E007	10/10/2024	pH (field)	6.5	SU
08	Background	E007	10/10/2024	Radium 226 + Radium 228, total	1.07	pCi/L
08	Background	E007	10/10/2024	Selenium, total	0.00098 U	mg/L

TABLE 1.
FIELD PARAMETERS AND ANALYTICAL RESULTS - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	Well Type	Event	Date	Parameter	Result	Unit
08	Background	E007	10/10/2024	Specific Conductance @ 25C (field)	1,549	micromhos/cm
08	Background	E007	10/10/2024	Sulfate, total	100	mg/L
08	Background	E007	10/10/2024	Temperature	13.7	degrees C
08	Background	E007	10/10/2024	Thallium, total	0.00057 U	mg/L
08	Background	E007	10/10/2024	Total Dissolved Solids	1,100	mg/L
08	Background	E007	10/10/2024	Turbidity, field	9.91	NTU
08D	Background	E007	10/08/2024	Antimony, total	0.0013 U	mg/L
08D	Background	E007	10/08/2024	Arsenic, total	0.00023 U	mg/L
08D	Background	E007	10/08/2024	Barium, total	0.0930	mg/L
08D	Background	E007	10/08/2024	Beryllium, total	0.00053 U	mg/L
08D	Background	E007	10/08/2024	Boron, total	0.0930 J+	mg/L
08D	Background	E007	10/08/2024	Cadmium, total	0.00039 J	mg/L
08D	Background	E007	10/08/2024	Calcium, total	170	mg/L
08D	Background	E007	10/08/2024	Chloride, total	240	mg/L
08D	Background	E007	10/08/2024	Chromium, total	0.0011 U	mg/L
08D	Background	E007	10/08/2024	Cobalt, total	0.00200	mg/L
08D	Background	E007	10/08/2024	Dissolved Oxygen	1.58	mg/L
08D	Background	E007	10/08/2024	Fluoride, total	0.100	mg/L
08D	Background	E007	10/08/2024	Lead, total	0.00032 J	mg/L
08D	Background	E007	10/08/2024	Lithium, total	0.0140	mg/L
08D	Background	E007	10/08/2024	Mercury, total	0.000076 U	mg/L
08D	Background	E007	10/08/2024	Molybdenum, total	0.0025 U	mg/L
08D	Background	E007	10/08/2024	Oxidation Reduction Potential	124	mV
08D	Background	E007	10/08/2024	pH (field)	6.7	SU
08D	Background	E007	10/08/2024	Radium 226 + Radium 228, total	0.773	pCi/L
08D	Background	E007	10/08/2024	Selenium, total	0.00098 U	mg/L
08D	Background	E007	10/08/2024	Specific Conductance @ 25C (field)	1,675	micromhos/cm
08D	Background	E007	10/08/2024	Sulfate, total	120	mg/L
08D	Background	E007	10/08/2024	Temperature	13.1	degrees C
08D	Background	E007	10/08/2024	Thallium, total	0.00057 U	mg/L
08D	Background	E007	10/08/2024	Total Dissolved Solids	1,100	mg/L
08D	Background	E007	10/08/2024	Turbidity, field	6.33	NTU
16	Background	E007	10/09/2024	Antimony, total	0.0013 U	mg/L
16	Background	E007	10/09/2024	Arsenic, total	0.00023 U	mg/L
16	Background	E007	10/09/2024	Barium, total	0.0720	mg/L
16	Background	E007	10/09/2024	Beryllium, total	0.00053 U	mg/L
16	Background	E007	10/09/2024	Boron, total	0.140 J+	mg/L
16	Background	E007	10/09/2024	Cadmium, total	0.00017 U	mg/L
16	Background	E007	10/09/2024	Calcium, total	82.0	mg/L
16	Background	E007	10/09/2024	Chloride, total	70.0	mg/L
16	Background	E007	10/09/2024	Chromium, total	0.0011 U	mg/L
16	Background	E007	10/09/2024	Cobalt, total	0.0004 U	mg/L
16	Background	E007	10/09/2024	Dissolved Oxygen	2.06	mg/L
16	Background	E007	10/09/2024	Fluoride, total	0.210	mg/L
16	Background	E007	10/09/2024	Lead, total	0.00019 U	mg/L
16	Background	E007	10/09/2024	Lithium, total	0.00560	mg/L

TABLE 1.
FIELD PARAMETERS AND ANALYTICAL RESULTS - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	Well Type	Event	Date	Parameter	Result	Unit
16	Background	E007	10/09/2024	Mercury, total	0.000076 U	mg/L
16	Background	E007	10/09/2024	Molybdenum, total	0.00640	mg/L
16	Background	E007	10/09/2024	Oxidation Reduction Potential	131	mV
16	Background	E007	10/09/2024	pH (field)	7.0	SU
16	Background	E007	10/09/2024	Radium 226 + Radium 228, total	0.157	pCi/L
16	Background	E007	10/09/2024	Selenium, total	0.00098 U	mg/L
16	Background	E007	10/09/2024	Specific Conductance @ 25C (field)	736	micromhos/cm
16	Background	E007	10/09/2024	Sulfate, total	62.0	mg/L
16	Background	E007	10/09/2024	Temperature	21.4	degrees C
16	Background	E007	10/09/2024	Thallium, total	0.00057 U	mg/L
16	Background	E007	10/09/2024	Total Dissolved Solids	460	mg/L
16	Background	E007	10/09/2024	Turbidity, field	5.24	NTU
17	Background	E007	10/09/2024	Antimony, total	0.0013 U	mg/L
17	Background	E007	10/09/2024	Arsenic, total	0.00023 U	mg/L
17	Background	E007	10/09/2024	Barium, total	0.0860	mg/L
17	Background	E007	10/09/2024	Beryllium, total	0.00053 U	mg/L
17	Background	E007	10/09/2024	Boron, total	0.130 J+	mg/L
17	Background	E007	10/09/2024	Cadmium, total	0.00017 U	mg/L
17	Background	E007	10/09/2024	Calcium, total	74.0	mg/L
17	Background	E007	10/09/2024	Chloride, total	89.0	mg/L
17	Background	E007	10/09/2024	Chromium, total	0.0011 U	mg/L
17	Background	E007	10/09/2024	Cobalt, total	0.0004 U	mg/L
17	Background	E007	10/09/2024	Dissolved Oxygen	4.98	mg/L
17	Background	E007	10/09/2024	Fluoride, total	0.230	mg/L
17	Background	E007	10/09/2024	Lead, total	0.00019 U	mg/L
17	Background	E007	10/09/2024	Lithium, total	0.00660	mg/L
17	Background	E007	10/09/2024	Mercury, total	0.000076 U	mg/L
17	Background	E007	10/09/2024	Molybdenum, total	0.0043 J	mg/L
17	Background	E007	10/09/2024	Oxidation Reduction Potential	135	mV
17	Background	E007	10/09/2024	pH (field)	7.0	SU
17	Background	E007	10/09/2024	Radium 226 + Radium 228, total	0.442	pCi/L
17	Background	E007	10/09/2024	Selenium, total	0.00098 U	mg/L
17	Background	E007	10/09/2024	Specific Conductance @ 25C (field)	762	micromhos/cm
17	Background	E007	10/09/2024	Sulfate, total	70.0	mg/L
17	Background	E007	10/09/2024	Temperature	22.6	degrees C
17	Background	E007	10/09/2024	Thallium, total	0.00057 U	mg/L
17	Background	E007	10/09/2024	Total Dissolved Solids	470	mg/L
17	Background	E007	10/09/2024	Turbidity, field	93	NTU
12	Compliance	E007	10/08/2024	Antimony, total	0.0013 U	mg/L
12	Compliance	E007	10/08/2024	Arsenic, total	0.00023 J	mg/L
12	Compliance	E007	10/08/2024	Barium, total	0.0580	mg/L
12	Compliance	E007	10/08/2024	Beryllium, total	0.00053 U	mg/L
12	Compliance	E007	10/08/2024	Boron, total	0.130 J+	mg/L
12	Compliance	E007	10/08/2024	Cadmium, total	0.00017 U	mg/L
12	Compliance	E007	10/08/2024	Calcium, total	77.0	mg/L
12	Compliance	E007	10/08/2024	Chloride, total	74.0	mg/L

TABLE 1.
FIELD PARAMETERS AND ANALYTICAL RESULTS - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	Well Type	Event	Date	Parameter	Result	Unit
12	Compliance	E007	10/08/2024	Chromium, total	0.0011 U	mg/L
12	Compliance	E007	10/08/2024	Cobalt, total	0.0004 U	mg/L
12	Compliance	E007	10/08/2024	Dissolved Oxygen	1.74	mg/L
12	Compliance	E007	10/08/2024	Fluoride, total	0.220	mg/L
12	Compliance	E007	10/08/2024	Lead, total	0.00019 U	mg/L
12	Compliance	E007	10/08/2024	Lithium, total	0.00900	mg/L
12	Compliance	E007	10/08/2024	Mercury, total	0.000076 U	mg/L
12	Compliance	E007	10/08/2024	Molybdenum, total	0.0140	mg/L
12	Compliance	E007	10/08/2024	Oxidation Reduction Potential	55.3	mV
12	Compliance	E007	10/08/2024	pH (field)	7.2	SU
12	Compliance	E007	10/08/2024	Radium 226 + Radium 228, total	0.867	pCi/L
12	Compliance	E007	10/08/2024	Selenium, total	0.00098 U	mg/L
12	Compliance	E007	10/08/2024	Specific Conductance @ 25C (field)	871	micromhos/cm
12	Compliance	E007	10/08/2024	Sulfate, total	61.0	mg/L
12	Compliance	E007	10/08/2024	Temperature	19.4	degrees C
12	Compliance	E007	10/08/2024	Thallium, total	0.00057 U	mg/L
12	Compliance	E007	10/08/2024	Total Dissolved Solids	470	mg/L
12	Compliance	E007	10/08/2024	Turbidity, field	2.79	NTU
13	Compliance	E007	10/08/2024	Antimony, total	0.0013 U	mg/L
13	Compliance	E007	10/08/2024	Arsenic, total	0.00037 J	mg/L
13	Compliance	E007	10/08/2024	Barium, total	0.0440	mg/L
13	Compliance	E007	10/08/2024	Beryllium, total	0.00053 U	mg/L
13	Compliance	E007	10/08/2024	Boron, total	0.170 J+	mg/L
13	Compliance	E007	10/08/2024	Cadmium, total	0.00017 U	mg/L
13	Compliance	E007	10/08/2024	Calcium, total	80.0	mg/L
13	Compliance	E007	10/08/2024	Chloride, total	66.0	mg/L
13	Compliance	E007	10/08/2024	Chromium, total	0.0011 J	mg/L
13	Compliance	E007	10/08/2024	Cobalt, total	0.0004 U	mg/L
13	Compliance	E007	10/08/2024	Dissolved Oxygen	1.37	mg/L
13	Compliance	E007	10/08/2024	Fluoride, total	0.190	mg/L
13	Compliance	E007	10/08/2024	Lead, total	0.00019 U	mg/L
13	Compliance	E007	10/08/2024	Lithium, total	0.0110	mg/L
13	Compliance	E007	10/08/2024	Mercury, total	0.000076 U	mg/L
13	Compliance	E007	10/08/2024	Molybdenum, total	0.0110	mg/L
13	Compliance	E007	10/08/2024	Oxidation Reduction Potential	57.4	mV
13	Compliance	E007	10/08/2024	pH (field)	7.3	SU
13	Compliance	E007	10/08/2024	Radium 226 + Radium 228, total	0.863	pCi/L
13	Compliance	E007	10/08/2024	Selenium, total	0.00098 U	mg/L
13	Compliance	E007	10/08/2024	Specific Conductance @ 25C (field)	865	micromhos/cm
13	Compliance	E007	10/08/2024	Sulfate, total	56.0	mg/L
13	Compliance	E007	10/08/2024	Temperature	18.4	degrees C
13	Compliance	E007	10/08/2024	Thallium, total	0.00057 U	mg/L
13	Compliance	E007	10/08/2024	Total Dissolved Solids	440	mg/L
13	Compliance	E007	10/08/2024	Turbidity, field	3.06	NTU
46	Compliance	E007	10/09/2024	Antimony, total	0.0013 U	mg/L
46	Compliance	E007	10/09/2024	Arsenic, total	0.00023 U	mg/L

TABLE 1.
FIELD PARAMETERS AND ANALYTICAL RESULTS - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	Well Type	Event	Date	Parameter	Result	Unit
46	Compliance	E007	10/09/2024	Barium, total	0.0740	mg/L
46	Compliance	E007	10/09/2024	Beryllium, total	0.00053 U	mg/L
46	Compliance	E007	10/09/2024	Boron, total	0.140 J+	mg/L
46	Compliance	E007	10/09/2024	Cadmium, total	0.00017 U	mg/L
46	Compliance	E007	10/09/2024	Calcium, total	81.0	mg/L
46	Compliance	E007	10/09/2024	Chloride, total	79.0	mg/L
46	Compliance	E007	10/09/2024	Chromium, total	0.0011 U	mg/L
46	Compliance	E007	10/09/2024	Cobalt, total	0.0004 U	mg/L
46	Compliance	E007	10/09/2024	Dissolved Oxygen	1.28	mg/L
46	Compliance	E007	10/09/2024	Fluoride, total	0.240	mg/L
46	Compliance	E007	10/09/2024	Lead, total	0.00019 U	mg/L
46	Compliance	E007	10/09/2024	Lithium, total	0.00760	mg/L
46	Compliance	E007	10/09/2024	Mercury, total	0.000076 U	mg/L
46	Compliance	E007	10/09/2024	Molybdenum, total	0.0200	mg/L
46	Compliance	E007	10/09/2024	Oxidation Reduction Potential	99.9	mV
46	Compliance	E007	10/09/2024	pH (field)	7.2	SU
46	Compliance	E007	10/09/2024	Radium 226 + Radium 228, total	0.526	pCi/L
46	Compliance	E007	10/09/2024	Selenium, total	0.00098 U	mg/L
46	Compliance	E007	10/09/2024	Specific Conductance @ 25C (field)	709	micromhos/cm
46	Compliance	E007	10/09/2024	Sulfate, total	61.0	mg/L
46	Compliance	E007	10/09/2024	Temperature	21.2	degrees C
46	Compliance	E007	10/09/2024	Thallium, total	0.00057 U	mg/L
46	Compliance	E007	10/09/2024	Total Dissolved Solids	450	mg/L
46	Compliance	E007	10/09/2024	Turbidity, field	7.28	NTU
47	Compliance	E007	10/09/2024	Antimony, total	0.0013 U	mg/L
47	Compliance	E007	10/09/2024	Arsenic, total	0.00023 U	mg/L
47	Compliance	E007	10/09/2024	Barium, total	0.0790	mg/L
47	Compliance	E007	10/09/2024	Beryllium, total	0.00053 U	mg/L
47	Compliance	E007	10/09/2024	Boron, total	0.160 J+	mg/L
47	Compliance	E007	10/09/2024	Cadmium, total	0.00017 U	mg/L
47	Compliance	E007	10/09/2024	Calcium, total	91.0	mg/L
47	Compliance	E007	10/09/2024	Chloride, total	71.0	mg/L
47	Compliance	E007	10/09/2024	Chromium, total	0.0011 U	mg/L
47	Compliance	E007	10/09/2024	Cobalt, total	0.0004 U	mg/L
47	Compliance	E007	10/09/2024	Dissolved Oxygen	1.98	mg/L
47	Compliance	E007	10/09/2024	Fluoride, total	0.260	mg/L
47	Compliance	E007	10/09/2024	Lead, total	0.00019 U	mg/L
47	Compliance	E007	10/09/2024	Lithium, total	0.0100	mg/L
47	Compliance	E007	10/09/2024	Mercury, total	0.000076 U	mg/L
47	Compliance	E007	10/09/2024	Molybdenum, total	0.0280	mg/L
47	Compliance	E007	10/09/2024	Oxidation Reduction Potential	119	mV
47	Compliance	E007	10/09/2024	pH (field)	7.0	SU
47	Compliance	E007	10/09/2024	Radium 226 + Radium 228, total	0.748	pCi/L
47	Compliance	E007	10/09/2024	Selenium, total	0.00098 U	mg/L
47	Compliance	E007	10/09/2024	Specific Conductance @ 25C (field)	727	micromhos/cm
47	Compliance	E007	10/09/2024	Sulfate, total	57.0	mg/L

TABLE 1.
FIELD PARAMETERS AND ANALYTICAL RESULTS - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	Well Type	Event	Date	Parameter	Result	Unit
47	Compliance	E007	10/09/2024	Temperature	19.6	degrees C
47	Compliance	E007	10/09/2024	Thallium, total	0.00057 U	mg/L
47	Compliance	E007	10/09/2024	Total Dissolved Solids	460	mg/L
47	Compliance	E007	10/09/2024	Turbidity, field	7.78	NTU
52	Compliance	E007	10/10/2024	Antimony, total	0.0013 U	mg/L
52	Compliance	E007	10/10/2024	Arsenic, total	0.00023 U	mg/L
52	Compliance	E007	10/10/2024	Barium, total	0.100	mg/L
52	Compliance	E007	10/10/2024	Beryllium, total	0.00053 U	mg/L
52	Compliance	E007	10/10/2024	Boron, total	0.320 J+	mg/L
52	Compliance	E007	10/10/2024	Cadmium, total	0.00017 U	mg/L
52	Compliance	E007	10/10/2024	Calcium, total	100	mg/L
52	Compliance	E007	10/10/2024	Chloride, total	72.0	mg/L
52	Compliance	E007	10/10/2024	Chromium, total	0.0011 U	mg/L
52	Compliance	E007	10/10/2024	Cobalt, total	0.0004 U	mg/L
52	Compliance	E007	10/10/2024	Dissolved Oxygen	1.44	mg/L
52	Compliance	E007	10/10/2024	Fluoride, total	0.260	mg/L
52	Compliance	E007	10/10/2024	Lead, total	0.00019 U	mg/L
52	Compliance	E007	10/10/2024	Lithium, total	0.00940	mg/L
52	Compliance	E007	10/10/2024	Mercury, total	0.000076 U	mg/L
52	Compliance	E007	10/10/2024	Molybdenum, total	0.0130	mg/L
52	Compliance	E007	10/10/2024	Oxidation Reduction Potential	41.7	mV
52	Compliance	E007	10/10/2024	pH (field)	6.9	SU
52	Compliance	E007	10/10/2024	Radium 226 + Radium 228, total	0.459	pCi/L
52	Compliance	E007	10/10/2024	Selenium, total	0.00098 U	mg/L
52	Compliance	E007	10/10/2024	Specific Conductance @ 25C (field)	1,008	micromhos/cm
52	Compliance	E007	10/10/2024	Sulfate, total	63.0	mg/L
52	Compliance	E007	10/10/2024	Temperature	19.8	degrees C
52	Compliance	E007	10/10/2024	Thallium, total	0.00057 U	mg/L
52	Compliance	E007	10/10/2024	Total Dissolved Solids	510	mg/L
52	Compliance	E007	10/10/2024	Turbidity, field	3.11	NTU
54	Compliance	E007	10/10/2024	Antimony, total	0.0013 U	mg/L
54	Compliance	E007	10/10/2024	Arsenic, total	0.00023 U	mg/L
54	Compliance	E007	10/10/2024	Barium, total	0.0520	mg/L
54	Compliance	E007	10/10/2024	Beryllium, total	0.00053 U	mg/L
54	Compliance	E007	10/10/2024	Boron, total	0.300 J+	mg/L
54	Compliance	E007	10/10/2024	Cadmium, total	0.00017 U	mg/L
54	Compliance	E007	10/10/2024	Calcium, total	79.0	mg/L
54	Compliance	E007	10/10/2024	Chloride, total	63.0	mg/L
54	Compliance	E007	10/10/2024	Chromium, total	0.0011 U	mg/L
54	Compliance	E007	10/10/2024	Cobalt, total	0.0004 U	mg/L
54	Compliance	E007	10/10/2024	Dissolved Oxygen	2.08	mg/L
54	Compliance	E007	10/10/2024	Fluoride, total	0.260	mg/L
54	Compliance	E007	10/10/2024	Lead, total	0.00019 U	mg/L
54	Compliance	E007	10/10/2024	Lithium, total	0.0100	mg/L
54	Compliance	E007	10/10/2024	Mercury, total	0.000076 U	mg/L
54	Compliance	E007	10/10/2024	Molybdenum, total	0.0300	mg/L

TABLE 1.
FIELD PARAMETERS AND ANALYTICAL RESULTS - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	Well Type	Event	Date	Parameter	Result	Unit
54	Compliance	E007	10/10/2024	Oxidation Reduction Potential	88.6	mV
54	Compliance	E007	10/10/2024	pH (field)	7.2	SU
54	Compliance	E007	10/10/2024	Radium 226 + Radium 228, total	0.128	pCi/L
54	Compliance	E007	10/10/2024	Selenium, total	0.00098 U	mg/L
54	Compliance	E007	10/10/2024	Specific Conductance @ 25C (field)	658	micromhos/cm
54	Compliance	E007	10/10/2024	Sulfate, total	57.0	mg/L
54	Compliance	E007	10/10/2024	Temperature	17.1	degrees C
54	Compliance	E007	10/10/2024	Thallium, total	0.00057 U	mg/L
54	Compliance	E007	10/10/2024	Total Dissolved Solids	470	mg/L
54	Compliance	E007	10/10/2024	Turbidity, field	8.51	NTU

Notes:
C = Celsius
cm = centimeter
Events:
E007 = Quarter 4, 2024 sampling event
mg/L = milligrams per liter
mV = millivolts
NTU = Nephelometric Turbidity Units
pCi/L = picocuries per liter
Result Code (if applicable):
NR¹ = Parameter not analyzed.
NS¹ = Well has been, or will be, abandoned; therefore, a sample was not collected.
NS² = Well either needs or was undergoing maintenance; therefore, a sample was not collected.
NS³ = The location was not accessible; therefore, a sample was not collected.
NS⁴ = The location could not be found; therefore, a sample was not collected.
NS⁵ = The location was damaged; therefore, a sample was not collected.
NS⁶ = Sampling pump could not yield a sample.
NS⁷ = Well was either dry or purged dry and did not recover sufficiently to yield adequate volume for a sample.
NS⁸ = A sample was not collected.
PM¹ = Parameter not analyzed as the well purged dry during sample collection and did not sufficiently recover to yield adequate sample volume for analysis.
Result qualifiers as defined in the United States Environmental Protection Agency’s *National Functional Guidelines for Inorganic Superfund Methods Data Review*, EPA 542-R-20-006. November 2020.:
J = The result is an estimated quantity. The associated numerical value is the approximate concentration of the analyte in the sample.
J+ = The result is an estimated quantity, but the result may be biased high.
U = The analyte was analyzed for, but was not detected above the level of the adjusted detection limit or quantitation limit, as appropriate.
SU = Standard Units

TABLE 2.
EVALUATION OF COMPLIANCE - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	HSU	Event	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	Compliance Result
12	UA	E007	Antimony, total	mg/L	12/09/15 - 10/08/24	23	100	All ND - Last	0.003	0.006	Standard	No Exceedance
12	UA	E007	Arsenic, total	mg/L	12/09/15 - 10/08/24	28	100	All ND - Last	0.001	0.010	Standard	No Exceedance
12	UA	E007	Barium, total	mg/L	12/09/15 - 10/08/24	30	0	CI around mean	0.053	2.0	Standard	No Exceedance
12	UA	E007	Beryllium, total	mg/L	12/09/15 - 10/08/24	22	100	All ND - Last	0.001	0.004	Standard	No Exceedance
12	UA	E007	Boron, total	mg/L	12/09/15 - 10/08/24	31	0	CB around T-S line	0.0367	2	Standard	No Exceedance
12	UA	E007	Cadmium, total	mg/L	12/09/15 - 10/08/24	32	91	CB around T-S line	0.000582	0.005	Standard	No Exceedance
12	UA	E007	Chloride, total	mg/L	12/09/15 - 10/08/24	31	0	CI around mean	70.6	435	Background	No Exceedance
12	UA	E007	Chromium, total	mg/L	12/09/15 - 10/08/24	28	97	CB around T-S line	0.0015	0.1	Standard	No Exceedance
12	UA	E007	Cobalt, total	mg/L	12/09/15 - 10/08/24	26	84	Most recent sample	0.001	0.0380	Background	No Exceedance
12	UA	E007	Fluoride, total	mg/L	12/09/15 - 10/08/24	31	2	CI around median	0.23	4.0	Standard	No Exceedance
12	UA	E007	Lead, total	mg/L	12/09/15 - 10/08/24	28	100	All ND - Last	0.0005	0.0075	Standard	No Exceedance
12	UA	E007	Lithium, total	mg/L	12/09/15 - 10/08/24	27	4	CB around linear reg	0.00605	0.04	Standard	No Exceedance
12	UA	E007	Mercury, total	mg/L	12/09/15 - 10/08/24	25	100	All ND - Last	0.0002	0.002	Standard	No Exceedance
12	UA	E007	Molybdenum, total	mg/L	12/09/15 - 10/08/24	30	0	CB around linear reg	0.00935	0.1	Standard	No Exceedance
12	UA	E007	pH (field)	SU	12/09/15 - 10/08/24	38	0	CI around mean	7.3/7.4	6.5/9.0	Standard/Standard	No Exceedance
12	UA	E007	Radium 226 + Radium 228, total	pCi/L	12/09/15 - 10/08/24	26	0	CI around geomean	0.376	5	Standard	No Exceedance
12	UA	E007	Selenium, total	mg/L	12/09/15 - 10/08/24	30	61	CI around median	0.001	0.05	Standard	No Exceedance
12	UA	E007	Sulfate, total	mg/L	12/09/15 - 10/08/24	31	0	CI around geomean	63.8	400	Standard	No Exceedance
12	UA	E007	Thallium, total	mg/L	12/09/15 - 10/08/24	22	100	All ND - Last	0.002	0.002	Standard	No Exceedance
12	UA	E007	Total Dissolved Solids	mg/L	12/09/15 - 10/08/24	27	0	CI around mean	467	1,620	Background	No Exceedance
13	UA	E007	Antimony, total	mg/L	12/09/15 - 10/08/24	23	97	CB around T-S line	0.001	0.006	Standard	No Exceedance
13	UA	E007	Arsenic, total	mg/L	12/09/15 - 10/08/24	28	97	CI around median	0.001	0.010	Standard	No Exceedance
13	UA	E007	Barium, total	mg/L	12/09/15 - 10/08/24	30	0	CI around mean	0.0433	2.0	Standard	No Exceedance
13	UA	E007	Beryllium, total	mg/L	12/09/15 - 10/08/24	22	100	All ND - Last	0.001	0.004	Standard	No Exceedance
13	UA	E007	Boron, total	mg/L	12/09/15 - 10/08/24	31	0	CB around linear reg	0.00209	2	Standard	No Exceedance
13	UA	E007	Cadmium, total	mg/L	12/09/15 - 10/08/24	32	98	CB around T-S line	0.000582	0.005	Standard	No Exceedance
13	UA	E007	Chloride, total	mg/L	12/09/15 - 10/08/24	31	0	CI around mean	72.9	435	Background	No Exceedance

TABLE 2.
EVALUATION OF COMPLIANCE - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	HSU	Event	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	Compliance Result
13	UA	E007	Chromium, total	mg/L	12/09/15 - 10/08/24	28	87	CB around T-S line	0.00173	0.1	Standard	No Exceedance
13	UA	E007	Cobalt, total	mg/L	12/09/15 - 10/08/24	26	84	Most recent sample	0.001	0.0380	Background	No Exceedance
13	UA	E007	Fluoride, total	mg/L	12/09/15 - 10/08/24	31	2	CI around median	0.2	4.0	Standard	No Exceedance
13	UA	E007	Lead, total	mg/L	12/09/15 - 10/08/24	28	97	CB around T-S line	0.000807	0.0075	Standard	No Exceedance
13	UA	E007	Lithium, total	mg/L	12/09/15 - 10/08/24	27	0	CB around linear reg	0.00953	0.04	Standard	No Exceedance
13	UA	E007	Mercury, total	mg/L	12/09/15 - 10/08/24	25	100	All ND - Last	0.0002	0.002	Standard	No Exceedance
13	UA	E007	Molybdenum, total	mg/L	12/09/15 - 10/08/24	30	24	CI around mean	0.0139	0.1	Standard	No Exceedance
13	UA	E007	pH (field)	SU	12/09/15 - 10/08/24	38	0	CI around mean	7.4/7.5	6.5/9.0	Standard/Standard	No Exceedance
13	UA	E007	Radium 226 + Radium 228, total	pCi/L	12/09/15 - 10/08/24	26	0	CI around mean	0.461	5	Standard	No Exceedance
13	UA	E007	Selenium, total	mg/L	12/09/15 - 10/08/24	30	49	CI around mean	0.00134	0.05	Standard	No Exceedance
13	UA	E007	Sulfate, total	mg/L	12/09/15 - 10/08/24	31	0	CI around mean	75.4	400	Standard	No Exceedance
13	UA	E007	Thallium, total	mg/L	12/09/15 - 10/08/24	22	100	All ND - Last	0.002	0.002	Standard	No Exceedance
13	UA	E007	Total Dissolved Solids	mg/L	12/09/15 - 10/08/24	30	0	CI around mean	483	1,620	Background	No Exceedance
46	UA	E007	Antimony, total	mg/L	12/09/15 - 10/09/24	22	100	All ND - Last	0.003	0.006	Standard	No Exceedance
46	UA	E007	Arsenic, total	mg/L	12/09/15 - 10/09/24	24	100	All ND - Last	0.001	0.010	Standard	No Exceedance
46	UA	E007	Barium, total	mg/L	12/09/15 - 10/09/24	26	0	CB around linear reg	0.0668	2.0	Standard	No Exceedance
46	UA	E007	Beryllium, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.001	0.004	Standard	No Exceedance
46	UA	E007	Boron, total	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	0.196	2	Standard	No Exceedance
46	UA	E007	Cadmium, total	mg/L	12/09/15 - 10/09/24	25	100	All ND - Last	0.0005	0.005	Standard	No Exceedance
46	UA	E007	Chloride, total	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	70.2	435	Background	No Exceedance
46	UA	E007	Chromium, total	mg/L	12/09/15 - 10/09/24	24	92	CB around T-S line	0.00172	0.1	Standard	No Exceedance
46	UA	E007	Cobalt, total	mg/L	12/09/15 - 10/09/24	25	100	All ND - Last	0.001	0.0380	Background	No Exceedance
46	UA	E007	Fluoride, total	mg/L	12/09/15 - 10/09/24	27	4	CI around median	0.24	4.0	Standard	No Exceedance
46	UA	E007	Lead, total	mg/L	12/09/15 - 10/09/24	24	100	All ND - Last	0.0005	0.0075	Standard	No Exceedance
46	UA	E007	Lithium, total	mg/L	12/09/15 - 10/09/24	26	4	CI around mean	0.00861	0.04	Standard	No Exceedance
46	UA	E007	Mercury, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.0002	0.002	Standard	No Exceedance
46	UA	E007	Molybdenum, total	mg/L	12/09/15 - 10/09/24	26	0	CB around T-S line	0.0107	0.1	Standard	No Exceedance

TABLE 2.
EVALUATION OF COMPLIANCE - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	HSU	Event	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	Compliance Result
46	UA	E007	pH (field)	SU	12/09/15 - 10/09/24	27	0	CB around linear reg	7.1/7.3	6.5/9.0	Standard/Standard	No Exceedance
46	UA	E007	Radium 226 + Radium 228, total	pCi/L	12/09/15 - 10/09/24	26	0	CI around geomean	0.306	5	Standard	No Exceedance
46	UA	E007	Selenium, total	mg/L	12/09/15 - 10/09/24	26	65	CI around median	0.001	0.05	Standard	No Exceedance
46	UA	E007	Sulfate, total	mg/L	12/09/15 - 10/09/24	27	0	CI around geomean	62.5	400	Standard	No Exceedance
46	UA	E007	Thallium, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.002	0.002	Standard	No Exceedance
46	UA	E007	Total Dissolved Solids	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	444	1,620	Background	No Exceedance
47	UA	E007	Antimony, total	mg/L	12/09/15 - 10/09/24	22	100	All ND - Last	0.003	0.006	Standard	No Exceedance
47	UA	E007	Arsenic, total	mg/L	12/09/15 - 10/09/24	24	96	CI around median	0.001	0.010	Standard	No Exceedance
47	UA	E007	Barium, total	mg/L	12/09/15 - 10/09/24	26	0	CI around mean	0.0791	2.0	Standard	No Exceedance
47	UA	E007	Beryllium, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.001	0.004	Standard	No Exceedance
47	UA	E007	Boron, total	mg/L	12/09/15 - 10/09/24	27	0	CI around geomean	0.219	2	Standard	No Exceedance
47	UA	E007	Cadmium, total	mg/L	12/09/15 - 10/09/24	25	100	All ND - Last	0.0005	0.005	Standard	No Exceedance
47	UA	E007	Chloride, total	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	73.6	435	Background	No Exceedance
47	UA	E007	Chromium, total	mg/L	12/09/15 - 10/09/24	24	96	CB around T-S line	0.00181	0.1	Standard	No Exceedance
47	UA	E007	Cobalt, total	mg/L	12/09/15 - 10/09/24	25	84	CI around median	0.001	0.0380	Background	No Exceedance
47	UA	E007	Fluoride, total	mg/L	12/09/15 - 10/09/24	27	4	CB around T-S line	0.213	4.0	Standard	No Exceedance
47	UA	E007	Lead, total	mg/L	12/09/15 - 10/09/24	24	100	All ND - Last	0.0005	0.0075	Standard	No Exceedance
47	UA	E007	Lithium, total	mg/L	12/09/15 - 10/09/24	26	0	CI around mean	0.00855	0.04	Standard	No Exceedance
47	UA	E007	Mercury, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.0002	0.002	Standard	No Exceedance
47	UA	E007	Molybdenum, total	mg/L	12/09/15 - 10/09/24	26	0	CB around linear reg	0.0144	0.1	Standard	No Exceedance
47	UA	E007	pH (field)	SU	12/09/15 - 10/09/24	27	0	CI around mean	7.0/7.1	6.5/9.0	Standard/Standard	No Exceedance
47	UA	E007	Radium 226 + Radium 228, total	pCi/L	12/09/15 - 10/09/24	26	0	CI around geomean	0.31	5	Standard	No Exceedance
47	UA	E007	Selenium, total	mg/L	12/09/15 - 10/09/24	25	88	CB around T-S line	0.001	0.05	Standard	No Exceedance
47	UA	E007	Sulfate, total	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	64.6	400	Standard	No Exceedance
47	UA	E007	Thallium, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.002	0.002	Standard	No Exceedance
47	UA	E007	Total Dissolved Solids	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	479	1,620	Background	No Exceedance
52	UA	E007	Antimony, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.003	0.006	Standard	No Exceedance

TABLE 2.
EVALUATION OF COMPLIANCE - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	HSU	Event	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	Compliance Result
52	UA	E007	Arsenic, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.001	0.010	Standard	No Exceedance
52	UA	E007	Barium, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	0.0755	2.0	Standard	No Exceedance
52	UA	E007	Beryllium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.001	0.004	Standard	No Exceedance
52	UA	E007	Boron, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	0.155	2	Standard	No Exceedance
52	UA	E007	Cadmium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.0005	0.005	Standard	No Exceedance
52	UA	E007	Chloride, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	72.9	435	Background	No Exceedance
52	UA	E007	Chromium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.005	0.1	Standard	No Exceedance
52	UA	E007	Cobalt, total	mg/L	02/24/21 - 10/10/24	16	94	Most recent sample	0.001	0.0380	Background	No Exceedance
52	UA	E007	Fluoride, total	mg/L	02/24/21 - 10/10/24	16	6	CI around geomean	0.264	4.0	Standard	No Exceedance
52	UA	E007	Lead, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.0005	0.0075	Standard	No Exceedance
52	UA	E007	Lithium, total	mg/L	02/24/21 - 10/10/24	16	12	CI around mean	0.00564	0.04	Standard	No Exceedance
52	UA	E007	Mercury, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.0002	0.002	Standard	No Exceedance
52	UA	E007	Molybdenum, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	0.0111	0.1	Standard	No Exceedance
52	UA	E007	pH (field)	SU	02/24/21 - 10/10/24	16	0	CI around mean	7.0/7.3	6.5/9.0	Standard/Standard	No Exceedance
52	UA	E007	Radium 226 + Radium 228, total	pCi/L	02/24/21 - 10/10/24	16	0	CI around mean	0.416	5	Standard	No Exceedance
52	UA	E007	Selenium, total	mg/L	02/24/21 - 10/10/24	16	94	CB around T-S line	0.001	0.05	Standard	No Exceedance
52	UA	E007	Sulfate, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	60.9	400	Standard	No Exceedance
52	UA	E007	Thallium, total	mg/L	02/24/21 - 10/10/24	16	94	CI around median	0.002	0.002	Standard	No Exceedance
52	UA	E007	Total Dissolved Solids	mg/L	02/24/21 - 10/10/24	15	0	CI around mean	451	1,620	Background	No Exceedance
54	UA	E007	Antimony, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.003	0.006	Standard	No Exceedance
54	UA	E007	Arsenic, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.001	0.010	Standard	No Exceedance
54	UA	E007	Barium, total	mg/L	02/24/21 - 10/10/24	16	0	CB around linear reg	0.0397	2.0	Standard	No Exceedance
54	UA	E007	Beryllium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.001	0.004	Standard	No Exceedance
54	UA	E007	Boron, total	mg/L	02/24/21 - 10/10/24	16	0	CB around linear reg	0.0597	2	Standard	No Exceedance
54	UA	E007	Cadmium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.0005	0.005	Standard	No Exceedance
54	UA	E007	Chloride, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	75.4	435	Background	No Exceedance
54	UA	E007	Chromium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.005	0.1	Standard	No Exceedance

TABLE 2.
EVALUATION OF COMPLIANCE - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	HSU	Event	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	GWPS	GWPS Source	Compliance Result
54	UA	E007	Cobalt, total	mg/L	02/24/21 - 10/10/24	16	88	CI around median	0.001	0.0380	Background	No Exceedance
54	UA	E007	Fluoride, total	mg/L	02/24/21 - 10/10/24	16	6	CB around T-S line	0.0699	4.0	Standard	No Exceedance
54	UA	E007	Lead, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.0005	0.0075	Standard	No Exceedance
54	UA	E007	Lithium, total	mg/L	02/24/21 - 10/10/24	16	0	CB around T-S line	0.00491	0.04	Standard	No Exceedance
54	UA	E007	Mercury, total	mg/L	02/24/21 - 10/10/24	16	94	CI around median	0.0002	0.002	Standard	No Exceedance
54	UA	E007	Molybdenum, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	0.0224	0.1	Standard	No Exceedance
54	UA	E007	pH (field)	SU	02/24/21 - 10/10/24	16	0	CI around mean	7.1/7.4	6.5/9.0	Standard/Standard	No Exceedance
54	UA	E007	Radium 226 + Radium 228, total	pCi/L	02/24/21 - 10/10/24	16	0	CI around geomean	0.123	5	Standard	No Exceedance
54	UA	E007	Selenium, total	mg/L	02/24/21 - 10/10/24	16	56	CB around T-S line	0.00194	0.05	Standard	No Exceedance
54	UA	E007	Sulfate, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	73.5	400	Standard	No Exceedance
54	UA	E007	Thallium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.002	0.002	Standard	No Exceedance
54	UA	E007	Total Dissolved Solids	mg/L	02/24/21 - 10/10/24	14	0	CI around mean	489	1,620	Background	No Exceedance

TABLE 2.
EVALUATION OF COMPLIANCE - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Notes:

Compliance Result:

No Exceedance: the statistical result did not exceed the GWPS.
Throughout this document, “exceedance” or “exceedances” is intended to refer only to potential exceedances of proposed applicable background statistics or Groundwater Protection Standards (GWPSs) as described in the proposed groundwater monitoring program which was submitted to the Illinois Environmental Protection Agency (IEPA) on October 25, 2021 as part of Dynegy Midwest Generation, LLC’s (DMG’s) operating permit application for the East Ash Pond. That operating permit application, including the proposed groundwater monitoring program, remains under review by the IEPA and, therefore, DMG has not identified any actual exceedances.

Events:

E007 = Quarter 4, 2024 sampling event

HSU = hydrostratigraphic unit:

UA = Uppermost Aquifer

mg/L = milligrams per liter

ND = non-detect

pCi/L = picocuries per liter

SU = standard units

Sample Count = number of samples from Sampled Date Range used to calculate the Statistical Result

Statistical Calculation = method used to calculate the statistical result:

All ND - Last = All results were below the reporting limit, and the last determined reporting limit is shown

CB around T-S line = Confidence band around Thiel-Sen line

CB around T-S line = Confidence band around Thiel-Sen line

CB around linear reg = Confidence band around linear regression

CI around geomean = Confidence interval around the geometric mean

CI around mean = Confidence interval around the mean

CI around median = Confidence interval around the median

Most recent sample = Result for the most recently collected sample used due to insufficient data

Statistical Result = calculated in accordance with the Statistical Analysis Plan using constituent concentrations observed at each monitoring well during all sampling events within the specified date range

Statistical Result Code (if applicable):

NR¹ = Parameter not analyzed.

NS¹ = Well has been, or will be, abandoned; therefore, a sample was not collected.

NS² = Well either needs or was undergoing maintenance; therefore, a sample was not collected.

NS³ = The location was not accessible; therefore, a sample was not collected.

NS⁴ = The location could not be found; therefore, a sample was not collected.

NS⁵ = The location was damaged; therefore, a sample was not collected.

NS⁶ = Sampling pump could not yield a sample.

NS⁷ = Well was either dry or purged dry and did not recover sufficiently to yield adequate volume for a sample.

NS⁸ = A sample was not collected.

PM¹ = Parameter not analyzed as the well purged dry during sample collection and did not sufficiently recover to yield adequate sample volume for analysis.

For pH, the values presented are the lower / upper limits

GWPS Source:

Background = background concentration

Standard = standard specified in 35 I.A.C. § 845.600(a)(1)

FIGURES



- BACKGROUND WELL
- COMPLIANCE WELL
- STAFF GAUGE
- REGULATED UNIT (SUBJECT UNIT)
- SITE FEATURE
- LIMITS OF FINAL COVER
- PROPERTY BOUNDARY

0 175 350
Feet

MONITORING WELL LOCATION
MAP

EAST ASH POND
HENNEPIN POWER PLANT
HENNEPIN, ILLINOIS

FIGURE 1

RAMBOLL AMERICAS
ENGINEERING SOLUTIONS, INC.



ATTACHMENTS

**ATTACHMENT A
GROUNDWATER ELEVATION DATA
QUARTER 4, 2024**

ATTACHMENT A.
GROUNDWATER ELEVATION DATA - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	Well Type	Date	Depth to Groundwater (feet BMP)	Groundwater Elevation (feet NAVD88)
07	Background	10/07/2024	69.10	449.69
08	Background	10/07/2024	54.71	446.80
08D	Background	10/07/2024	55.12	446.65
12	Compliance	10/07/2024	DM ⁴	
13	Compliance	10/07/2024	52.22	446.72
16	Background	10/07/2024	55.28	446.67
17	Background	10/07/2024	56.83	451.00
46	Compliance	10/07/2024	52.22	446.97
47	Compliance	10/07/2024	56.71	446.66
52	Compliance	10/07/2024	54.88	446.62
54	Compliance	10/07/2024	54.19	446.59
XSG01	Water Level	10/07/2024	10.55	487.09
SG02	Water Level	10/07/2024	NA	441.00

Notes:
BMP = below measuring point
Depth to Groundwater/Groundwater Elevation Code (if applicable):
DM¹ = Depth to water was not measured.
DM² = Depth to water was not measured because water was above or below the staff gage markings.
DM³ = Depth to water was not measured because the location was inaccessible.
DM⁴ = Depth to water was not measured because water level was below the top of the pump.
DM⁵ = Depth to water was not measured because water level was above the top of casing (artesian well).
DM⁶ = Depth to water was not measured because of damage to the well.
DM⁷ = Depth to water was not measured due to required pressure transducer maintenance.
DM⁸ = Lab provided groundwater elevation data and not depth to water.
NA = not available/not applicable
NAVD88 = North American Vertical Datum of 1988

**ATTACHMENT B
LABORATORY REPORTS AND FIELD DATA SHEETS
QUARTER 4, 2024**

ANALYTICAL REPORT

PREPARED FOR

Attn: Brian Voelker
Vistra Energy Corp
133 S 4th, Suite 206
Springfield, Illinois 62701

Generated 10/30/24 17:00:51

JOB DESCRIPTION

HEN-24Q4
HEN_845_803

JOB NUMBER

500-258038-10

Job Notes

This report may not be reproduced except in full, and with written approval from the laboratory. The results relate only to the samples tested. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Chicago Project Manager.

Authorization



Generated
10/30/24 17:00:51

Authorized for release by
Dirk Nelson, Project Management Assistant II
Dirk.Nelson@et.eurofinsus.com
(708)534-5200

Table of Contents

Cover Page	1
Table of Contents	3
Case Narrative	4
Detection Summary	5
Method Summary	13
Sample Summary	14
Client Sample Results	15
Definitions	31
QC Association	32
QC Sample Results	38
Chronicle	46
Certification Summary	52
Chain of Custody	53
Receipt Checklists	64
Field Data Sheets	65



Case Narrative

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10

Client: Vistra Energy Corp
Project: HEN-24Q4

Job ID: 500-258038-10

Eurofins Chicago

Job Narrative 500-258038-10

Receipt

The samples were received on 10/08/24 11:17. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 13 coolers at receipt time were 1.5° C, 1.5° C, 3.2° C, 3.5° C, 3.8° C, 4.0° C, 4.2° C, 4.9° C, 5.0° C, 5.2° C, 5.3° C, 5.9° C and 13.8° C.

Receipt Exceptions

The following samples were received at the laboratory at 13.8 C & 5.9 C.: HEN_07 (500-258038-33), HEN_08 (500-258038-34), HEN_52 (500-258038-35), HEN_54 (500-258038-36), HEN_54_FD (500-258038-37) and HEN_FB (500-258038-38). 13.8 C is outside the required temperature criteria of < 6 C. The samples are considered acceptable since it was collected and submitted to the laboratory on the same day and there is evidence that the chilling process has begun.

The Chain-of-Custody (COC) was incomplete as received. The COC is missing the Sample Date. Login sample dates were taken from the bottles, added to the COC and verified using the well development forms. Affected samples: HEN_05&DR (500-258038-4), HEN_05!R (500-258038-5), HEN_08&D (500-258038-6), HEN_12 (500-258038-7), HEN_13 (500-258038-8), HEN_18&D (500-258038-9), HEN_18#S (500-258038-10), HEN_21R (500-258038-11), HEN_21R_MS (500-258038-11[MS]), HEN_21R-MSD (500-258038-11[MSD]), HEN_27 (500-258038-12), HEN_32 (500-258038-13), HEN_34 (500-258038-14), HEN_35 (500-258038-15), HEN_35_FD (500-258038-16) and HEN_40#S (500-258038-17)

Method Field Sampling: Depth to water was not measured because water level was below the top of the pump for the following samples: HEN_12 (500-258038-7).

Metals

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

General Chemistry

Method SM 2320B: The method blank for analytical batch 500-791737 contained Alkalinity above the reporting limit (RL). Associated sample(s) were not re-extracted and/or re-analyzed because results were greater than 10X the value found in the method blank.

Method 300.0: The native sample, matrix spike, and matrix spike duplicate (MS/MSD) associated with analytical batch 500-790938 were performed at the same dilution. Due to the additional level of analyte present in the spiked samples, the concentration of Chloride in the MS/MSD was above the instrument calibration range. The data have been reported and qualified.

Method 300.0: The method blank for analytical batch 500-791383 contained Chloride above the method detection limit. This target analyte concentration was less than the reporting limit (RL) in the method blank; therefore, re-extraction and/or re-analysis of samples was not performed.

Method 300.0: The method blank for analytical batch 500-791804 contained Chloride above the method detection limit. This target analyte concentration was less than the reporting limit (RL) in the method blank; therefore, re-extraction and/or re-analysis of samples was not performed.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Eurofins Chicago

Detection Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_08&D

Lab Sample ID: 500-258038-6

Analyte	Result	Qualifier	RL	MDL	Unit	Dil	Fac	D	Method	Prep Type
Lithium	0.014		0.0050	0.0020	mg/L	1			200.7 Rev 4.4	Total Recoverable
Barium	0.093		0.0025	0.00073	mg/L	1			6020B	Total Recoverable
Boron	0.093	B	0.050	0.013	mg/L	1			6020B	Total Recoverable
Cadmium	0.00039	J	0.00050	0.00017	mg/L	1			6020B	Total Recoverable
Calcium	170		0.20	0.044	mg/L	1			6020B	Total Recoverable
Cobalt	0.0020		0.0010	0.00040	mg/L	1			6020B	Total Recoverable
Lead	0.00032	J	0.00050	0.00019	mg/L	1			6020B	Total Recoverable
Magnesium	49		0.20	0.049	mg/L	1			6020B	Total Recoverable
Potassium	3.2		0.50	0.11	mg/L	1			6020B	Total Recoverable
Sodium	180		0.20	0.077	mg/L	1			6020B	Total Recoverable
Chloride	240	B	20	2.3	mg/L	20			300.0	Total/NA
Sulfate	120		5.0	1.0	mg/L	5			300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	460	B	5.0	3.7	mg/L	1			SM 2320B	Total/NA
Total Dissolved Solids	1100		10	4.3	mg/L	1			SM 2540C	Total/NA
Fluoride	0.10		0.10	0.056	mg/L	1			SM 4500 F C	Total/NA
Depth to Water (ft from MP)	55.09				ft	1			Field Sampling	Total/NA
Field pH	6.65				SU	1			Field Sampling	Total/NA
Field Temperature	13.1				Degrees C	1			Field Sampling	Total/NA
Oxidation Reduction Potential	123.9				millivolts	1			Field Sampling	Total/NA
Oxygen, Dissolved	1.58				mg/L	1			Field Sampling	Total/NA
Specific Conductance	1675				umhos/cm	1			Field Sampling	Total/NA
Turbidity	6.33				NTU	1			Field Sampling	Total/NA

Client Sample ID: HEN_12

Lab Sample ID: 500-258038-7

Analyte	Result	Qualifier	RL	MDL	Unit	Dil	Fac	D	Method	Prep Type
Lithium	0.0090		0.0050	0.0020	mg/L	1			200.7 Rev 4.4	Total Recoverable
Arsenic	0.00023	J	0.0010	0.00023	mg/L	1			6020B	Total Recoverable
Barium	0.058		0.0025	0.00073	mg/L	1			6020B	Total Recoverable
Boron	0.13	B	0.050	0.013	mg/L	1			6020B	Total Recoverable
Calcium	77		0.20	0.044	mg/L	1			6020B	Total Recoverable
Magnesium	29		0.20	0.049	mg/L	1			6020B	Total Recoverable
Molybdenum	0.014		0.0050	0.0025	mg/L	1			6020B	Total Recoverable
Potassium	4.2		0.50	0.11	mg/L	1			6020B	Total Recoverable
Sodium	47		0.20	0.077	mg/L	1			6020B	Total Recoverable
Chloride	74		5.0	0.58	mg/L	5			300.0	Total/NA
Sulfate	61		5.0	1.0	mg/L	5			300.0	Total/NA

This Detection Summary does not include radiochemical test results.

Eurofins Chicago

Detection Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_12 (Continued)

Lab Sample ID: 500-258038-7

Analyte	Result	Qualifier	RL	MDL	Unit	Dil	Fac	D	Method	Prep Type
Bicarbonate Alkalinity as CaCO3	220	B	5.0	3.7	mg/L	1			SM 2320B	Total/NA
Total Dissolved Solids	470		10	4.3	mg/L	1			SM 2540C	Total/NA
Fluoride	0.22		0.10	0.056	mg/L	1			SM 4500 F C	Total/NA
Field pH	7.24				SU	1			Field Sampling	Total/NA
Field Temperature	19.4				Degrees C	1			Field Sampling	Total/NA
Oxidation Reduction Potential	55.3				millivolts	1			Field Sampling	Total/NA
Oxygen, Dissolved	1.74				mg/L	1			Field Sampling	Total/NA
Specific Conductance	871				umhos/cm	1			Field Sampling	Total/NA
Turbidity	2.79				NTU	1			Field Sampling	Total/NA

Client Sample ID: HEN_13

Lab Sample ID: 500-258038-8

Analyte	Result	Qualifier	RL	MDL	Unit	Dil	Fac	D	Method	Prep Type
Lithium	0.011		0.0050	0.0020	mg/L	1			200.7 Rev 4.4	Total Recoverable
Arsenic	0.00037	J	0.0010	0.00023	mg/L	1			6020B	Total Recoverable
Barium	0.044		0.0025	0.00073	mg/L	1			6020B	Total Recoverable
Boron	0.17	B	0.050	0.013	mg/L	1			6020B	Total Recoverable
Calcium	80		0.20	0.044	mg/L	1			6020B	Total Recoverable
Chromium	0.0011	J	0.0050	0.0011	mg/L	1			6020B	Total Recoverable
Magnesium	31		0.20	0.049	mg/L	1			6020B	Total Recoverable
Molybdenum	0.011		0.0050	0.0025	mg/L	1			6020B	Total Recoverable
Potassium	4.1		0.50	0.11	mg/L	1			6020B	Total Recoverable
Sodium	44		0.20	0.077	mg/L	1			6020B	Total Recoverable
Chloride	66		5.0	0.58	mg/L	5			300.0	Total/NA
Sulfate	56		5.0	1.0	mg/L	5			300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	230	B	5.0	3.7	mg/L	1			SM 2320B	Total/NA
Total Dissolved Solids	440		10	4.3	mg/L	1			SM 2540C	Total/NA
Fluoride	0.19		0.10	0.056	mg/L	1			SM 4500 F C	Total/NA
Depth to Water (ft from MP)	52.21				ft	1			Field Sampling	Total/NA
Field pH	7.30				SU	1			Field Sampling	Total/NA
Field Temperature	18.4				Degrees C	1			Field Sampling	Total/NA
Oxidation Reduction Potential	57.4				millivolts	1			Field Sampling	Total/NA
Oxygen, Dissolved	1.37				mg/L	1			Field Sampling	Total/NA
Specific Conductance	865				umhos/cm	1			Field Sampling	Total/NA
Turbidity	3.06				NTU	1			Field Sampling	Total/NA

Client Sample ID: HEN_16

Lab Sample ID: 500-258038-21

Analyte	Result	Qualifier	RL	MDL	Unit	Dil	Fac	D	Method	Prep Type
Lithium	0.0056		0.0050	0.0020	mg/L	1			200.7 Rev 4.4	Total Recoverable
Barium	0.072		0.0025	0.00073	mg/L	1			6020B	Total Recoverable
Boron	0.14	B	0.050	0.013	mg/L	1			6020B	Total Recoverable

This Detection Summary does not include radiochemical test results.

Eurofins Chicago

Detection Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_16 (Continued)

Lab Sample ID: 500-258038-21

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Calcium	82		0.20	0.044	mg/L	1		6020B	Total
									Recoverable
Magnesium	27		0.20	0.049	mg/L	1		6020B	Total
									Recoverable
Molybdenum	0.0064		0.0050	0.0025	mg/L	1		6020B	Total
									Recoverable
Potassium	3.9		0.50	0.11	mg/L	1		6020B	Total
									Recoverable
Sodium	50		0.20	0.077	mg/L	1		6020B	Total
									Recoverable
Chloride	70		5.0	0.58	mg/L	5		300.0	Total/NA
Sulfate	62		5.0	1.0	mg/L	5		300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	240		5.0	3.7	mg/L	1		SM 2320B	Total/NA
Total Dissolved Solids	460		10	4.3	mg/L	1		SM 2540C	Total/NA
Fluoride	0.21		0.10	0.056	mg/L	1		SM 4500 F C	Total/NA
Depth to Water (ft from MP)	55.15				ft	1		Field Sampling	Total/NA
Field pH	6.99				SU	1		Field Sampling	Total/NA
Field Temperature	21.4				Degrees C	1		Field Sampling	Total/NA
Oxidation Reduction Potential	130.9				millivolts	1		Field Sampling	Total/NA
Oxygen, Dissolved	2.06				mg/L	1		Field Sampling	Total/NA
Specific Conductance	736				umhos/cm	1		Field Sampling	Total/NA
Turbidity	5.24				NTU	1		Field Sampling	Total/NA

Client Sample ID: HEN_16_FD

Lab Sample ID: 500-258038-22

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Lithium	0.0064		0.0050	0.0020	mg/L	1		200.7 Rev 4.4	Total
									Recoverable
Barium	0.072		0.0025	0.00073	mg/L	1		6020B	Total
									Recoverable
Boron	0.13	B	0.050	0.013	mg/L	1		6020B	Total
									Recoverable
Calcium	83		0.20	0.044	mg/L	1		6020B	Total
									Recoverable
Magnesium	27		0.20	0.049	mg/L	1		6020B	Total
									Recoverable
Molybdenum	0.0063		0.0050	0.0025	mg/L	1		6020B	Total
									Recoverable
Potassium	4.0		0.50	0.11	mg/L	1		6020B	Total
									Recoverable
Sodium	51		0.20	0.077	mg/L	1		6020B	Total
									Recoverable
Chloride	72		5.0	0.58	mg/L	5		300.0	Total/NA
Sulfate	63		5.0	1.0	mg/L	5		300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	240		5.0	3.7	mg/L	1		SM 2320B	Total/NA
Total Dissolved Solids	480		10	4.3	mg/L	1		SM 2540C	Total/NA
Fluoride	0.21		0.10	0.056	mg/L	1		SM 4500 F C	Total/NA
Depth to Water (ft from MP)	55.15				ft	1		Field Sampling	Total/NA
Field pH	6.99				SU	1		Field Sampling	Total/NA
Field Temperature	21.4				Degrees C	1		Field Sampling	Total/NA
Oxidation Reduction Potential	130.9				millivolts	1		Field Sampling	Total/NA
Oxygen, Dissolved	2.06				mg/L	1		Field Sampling	Total/NA
Specific Conductance	736				umhos/cm	1		Field Sampling	Total/NA
Turbidity	5.24				NTU	1		Field Sampling	Total/NA

This Detection Summary does not include radiochemical test results.

Eurofins Chicago

Detection Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_17

Lab Sample ID: 500-258038-23

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Lithium	0.0066		0.0050	0.0020	mg/L	1		200.7 Rev 4.4	Total
Barium	0.086		0.0025	0.00073	mg/L	1		6020B	Recoverable
Boron	0.13	B	0.050	0.013	mg/L	1		6020B	Total
Calcium	74		0.20	0.044	mg/L	1		6020B	Recoverable
Magnesium	28		0.20	0.049	mg/L	1		6020B	Total
Molybdenum	0.0043	J	0.0050	0.0025	mg/L	1		6020B	Recoverable
Potassium	4.5		0.50	0.11	mg/L	1		6020B	Total
Sodium	61		0.20	0.077	mg/L	1		6020B	Recoverable
Chloride	89		5.0	0.58	mg/L	5		300.0	Total/NA
Sulfate	70		5.0	1.0	mg/L	5		300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	220		5.0	3.7	mg/L	1		SM 2320B	Total/NA
Total Dissolved Solids	470		10	4.3	mg/L	1		SM 2540C	Total/NA
Fluoride	0.23		0.10	0.056	mg/L	1		SM 4500 F C	Total/NA
Depth to Water (ft from MP)	56.30				ft	1		Field Sampling	Total/NA
Field pH	7.04				SU	1		Field Sampling	Total/NA
Field Temperature	22.6				Degrees C	1		Field Sampling	Total/NA
Oxidation Reduction Potential	134.7				millivolts	1		Field Sampling	Total/NA
Oxygen, Dissolved	4.98				mg/L	1		Field Sampling	Total/NA
Specific Conductance	762				umhos/cm	1		Field Sampling	Total/NA
Turbidity	92.96				NTU	1		Field Sampling	Total/NA

Client Sample ID: HEN_46

Lab Sample ID: 500-258038-28

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Lithium	0.0076		0.0050	0.0020	mg/L	1		200.7 Rev 4.4	Total
Barium	0.074		0.0025	0.00073	mg/L	1		6020B	Recoverable
Boron	0.14	B	0.050	0.013	mg/L	1		6020B	Total
Calcium	81		0.20	0.044	mg/L	1		6020B	Recoverable
Magnesium	30		0.20	0.049	mg/L	1		6020B	Total
Molybdenum	0.020		0.0050	0.0025	mg/L	1		6020B	Recoverable
Potassium	4.5		0.50	0.11	mg/L	1		6020B	Total
Sodium	54		0.20	0.077	mg/L	1		6020B	Recoverable
Chloride	79	B	5.0	0.58	mg/L	5		300.0	Total/NA
Sulfate	61		5.0	1.0	mg/L	5		300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	220		5.0	3.7	mg/L	1		SM 2320B	Total/NA
Total Dissolved Solids	450		10	4.3	mg/L	1		SM 2540C	Total/NA
Fluoride	0.24		0.10	0.056	mg/L	1		SM 4500 F C	Total/NA
Depth to Water (ft from MP)	52.27				ft	1		Field Sampling	Total/NA
Field pH	7.16				SU	1		Field Sampling	Total/NA

This Detection Summary does not include radiochemical test results.

Eurofins Chicago

Detection Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_46 (Continued)

Lab Sample ID: 500-258038-28

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Field Temperature	21.2				Degrees C	1		Field Sampling	Total/NA
Oxidation Reduction Potential	99.9				millivolts	1		Field Sampling	Total/NA
Oxygen, Dissolved	1.28				mg/L	1		Field Sampling	Total/NA
Specific Conductance	709				umhos/cm	1		Field Sampling	Total/NA
Turbidity	7.28				NTU	1		Field Sampling	Total/NA

Client Sample ID: HEN_47

Lab Sample ID: 500-258038-29

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Lithium	0.010		0.0050	0.0020	mg/L	1		200.7 Rev 4.4	Total Recoverable
Barium	0.079		0.0025	0.00073	mg/L	1		6020B	Total Recoverable
Boron	0.16	B	0.050	0.013	mg/L	1		6020B	Total Recoverable
Calcium	91		0.20	0.044	mg/L	1		6020B	Total Recoverable
Magnesium	31		0.20	0.049	mg/L	1		6020B	Total Recoverable
Molybdenum	0.028		0.0050	0.0025	mg/L	1		6020B	Total Recoverable
Potassium	4.4		0.50	0.11	mg/L	1		6020B	Total Recoverable
Sodium	47		0.20	0.077	mg/L	1		6020B	Total Recoverable
Chloride	71	B	5.0	0.58	mg/L	5		300.0	Total/NA
Sulfate	57		5.0	1.0	mg/L	5		300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	260		5.0	3.7	mg/L	1		SM 2320B	Total/NA
Total Dissolved Solids	460		10	4.3	mg/L	1		SM 2540C	Total/NA
Fluoride	0.26		0.10	0.056	mg/L	1		SM 4500 F C	Total/NA
Depth to Water (ft from MP)	56.60				ft	1		Field Sampling	Total/NA
Field pH	6.99				SU	1		Field Sampling	Total/NA
Field Temperature	19.6				Degrees C	1		Field Sampling	Total/NA
Oxidation Reduction Potential	118.9				millivolts	1		Field Sampling	Total/NA
Oxygen, Dissolved	1.98				mg/L	1		Field Sampling	Total/NA
Specific Conductance	727				umhos/cm	1		Field Sampling	Total/NA
Turbidity	7.78				NTU	1		Field Sampling	Total/NA

Client Sample ID: HEN_07

Lab Sample ID: 500-258038-33

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Lithium	0.0096		0.0050	0.0020	mg/L	1		200.7 Rev 4.4	Total Recoverable
Barium	0.12		0.0025	0.00073	mg/L	1		6020B	Total Recoverable
Boron	0.069	B	0.050	0.013	mg/L	1		6020B	Total Recoverable
Calcium	140		0.20	0.044	mg/L	1		6020B	Total Recoverable
Cobalt	0.0037		0.0010	0.00040	mg/L	1		6020B	Total Recoverable
Magnesium	43		0.20	0.049	mg/L	1		6020B	Total Recoverable
Potassium	2.7		0.50	0.11	mg/L	1		6020B	Total Recoverable

This Detection Summary does not include radiochemical test results.

Eurofins Chicago

Detection Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_07 (Continued)

Lab Sample ID: 500-258038-33

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Sodium	42		0.20	0.077	mg/L	1		6020B	Total Recoverable
Chloride	54	B	5.0	0.58	mg/L	5		300.0	Total/NA
Sulfate	57		5.0	1.0	mg/L	5		300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	390		5.0	3.7	mg/L	1		SM 2320B	Total/NA
Total Dissolved Solids	650		10	4.3	mg/L	1		SM 2540C	Total/NA
Fluoride	0.11		0.10	0.056	mg/L	1		SM 4500 F C	Total/NA
Depth to Water (ft from MP)	69.03				ft	1		Field Sampling	Total/NA
Field pH	6.79				SU	1		Field Sampling	Total/NA
Field Temperature	11.5				Degrees C	1		Field Sampling	Total/NA
Oxidation Reduction Potential	112.7				millivolts	1		Field Sampling	Total/NA
Oxygen, Dissolved	5.60				mg/L	1		Field Sampling	Total/NA
Specific Conductance	1144				umhos/cm	1		Field Sampling	Total/NA
Turbidity	5.30				NTU	1		Field Sampling	Total/NA

Client Sample ID: HEN_08

Lab Sample ID: 500-258038-34

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Lithium	0.016		0.0050	0.0020	mg/L	1		200.7 Rev 4.4	Total Recoverable
Barium	0.12		0.0025	0.00073	mg/L	1		6020B	Total Recoverable
Boron	0.11	B	0.050	0.013	mg/L	1		6020B	Total Recoverable
Cadmium	0.00041	J	0.00050	0.00017	mg/L	1		6020B	Total Recoverable
Calcium	210		0.20	0.044	mg/L	1		6020B	Total Recoverable
Cobalt	0.0024		0.0010	0.00040	mg/L	1		6020B	Total Recoverable
Lead	0.00031	J	0.00050	0.00019	mg/L	1		6020B	Total Recoverable
Magnesium	57		0.20	0.049	mg/L	1		6020B	Total Recoverable
Potassium	7.9		0.50	0.11	mg/L	1		6020B	Total Recoverable
Sodium	110		0.20	0.077	mg/L	1		6020B	Total Recoverable
Chloride	240	B	20	2.3	mg/L	20		300.0	Total/NA
Sulfate	100		5.0	1.0	mg/L	5		300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	460		5.0	3.7	mg/L	1		SM 2320B	Total/NA
Total Dissolved Solids	1100		10	4.3	mg/L	1		SM 2540C	Total/NA
Fluoride	0.086	J	0.10	0.056	mg/L	1		SM 4500 F C	Total/NA
Depth to Water (ft from MP)	54.52				ft	1		Field Sampling	Total/NA
Field pH	6.47				SU	1		Field Sampling	Total/NA
Field Temperature	13.7				Degrees C	1		Field Sampling	Total/NA
Oxidation Reduction Potential	145.6				millivolts	1		Field Sampling	Total/NA
Oxygen, Dissolved	1.89				mg/L	1		Field Sampling	Total/NA
Specific Conductance	1549				umhos/cm	1		Field Sampling	Total/NA
Turbidity	9.91				NTU	1		Field Sampling	Total/NA

This Detection Summary does not include radiochemical test results.

Eurofins Chicago

Detection Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_52

Lab Sample ID: 500-258038-35

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Lithium	0.0094		0.0050	0.0020	mg/L	1		200.7 Rev 4.4	Total Recoverable
Barium	0.10		0.0025	0.00073	mg/L	1		6020B	Total Recoverable
Boron	0.32	B	0.050	0.013	mg/L	1		6020B	Total Recoverable
Calcium	100		0.20	0.044	mg/L	1		6020B	Total Recoverable
Magnesium	32		0.20	0.049	mg/L	1		6020B	Total Recoverable
Molybdenum	0.013		0.0050	0.0025	mg/L	1		6020B	Total Recoverable
Potassium	5.4		0.50	0.11	mg/L	1		6020B	Total Recoverable
Sodium	57		0.20	0.077	mg/L	1		6020B	Total Recoverable
Chloride	72	B	5.0	0.58	mg/L	5		300.0	Total/NA
Sulfate	63		5.0	1.0	mg/L	5		300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	300		5.0	3.7	mg/L	1		SM 2320B	Total/NA
Total Dissolved Solids	510		10	4.3	mg/L	1		SM 2540C	Total/NA
Fluoride	0.26		0.10	0.056	mg/L	1		SM 4500 F C	Total/NA
Depth to Water (ft from MP)	54.74				ft	1		Field Sampling	Total/NA
Field pH	6.94				SU	1		Field Sampling	Total/NA
Field Temperature	19.8				Degrees C	1		Field Sampling	Total/NA
Oxidation Reduction Potential	41.7				millivolts	1		Field Sampling	Total/NA
Oxygen, Dissolved	1.44				mg/L	1		Field Sampling	Total/NA
Specific Conductance	1008				umhos/cm	1		Field Sampling	Total/NA
Turbidity	3.11				NTU	1		Field Sampling	Total/NA

Client Sample ID: HEN_54

Lab Sample ID: 500-258038-36

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Lithium	0.010		0.0050	0.0020	mg/L	1		200.7 Rev 4.4	Total Recoverable
Barium	0.052		0.0025	0.00073	mg/L	1		6020B	Total Recoverable
Boron	0.30	B	0.050	0.013	mg/L	1		6020B	Total Recoverable
Calcium	79		0.20	0.044	mg/L	1		6020B	Total Recoverable
Magnesium	30		0.20	0.049	mg/L	1		6020B	Total Recoverable
Molybdenum	0.030		0.0050	0.0025	mg/L	1		6020B	Total Recoverable
Potassium	4.4		0.50	0.11	mg/L	1		6020B	Total Recoverable
Sodium	48		0.20	0.077	mg/L	1		6020B	Total Recoverable
Chloride	63	B	5.0	0.58	mg/L	5		300.0	Total/NA
Sulfate	57		5.0	1.0	mg/L	5		300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	240		5.0	3.7	mg/L	1		SM 2320B	Total/NA
Total Dissolved Solids	470		10	4.3	mg/L	1		SM 2540C	Total/NA
Fluoride	0.26		0.10	0.056	mg/L	1		SM 4500 F C	Total/NA
Depth to Water (ft from MP)	54.05				ft	1		Field Sampling	Total/NA
Field pH	7.22				SU	1		Field Sampling	Total/NA

This Detection Summary does not include radiochemical test results.

Eurofins Chicago

Detection Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_54 (Continued)

Lab Sample ID: 500-258038-36

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Field Temperature	17.1				Degrees C	1		Field Sampling	Total/NA
Oxidation Reduction Potential	88.6				millivolts	1		Field Sampling	Total/NA
Oxygen, Dissolved	2.08				mg/L	1		Field Sampling	Total/NA
Specific Conductance	658				umhos/cm	1		Field Sampling	Total/NA
Turbidity	8.51				NTU	1		Field Sampling	Total/NA

Client Sample ID: HEN_54_FD

Lab Sample ID: 500-258038-37

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Lithium	0.010		0.0050	0.0020	mg/L	1		200.7 Rev 4.4	Total
Arsenic	0.00023	J	0.0010	0.00023	mg/L	1		6020B	Recoverable Total
Barium	0.053		0.0025	0.00073	mg/L	1		6020B	Recoverable Total
Boron	0.29	B	0.050	0.013	mg/L	1		6020B	Recoverable Total
Calcium	80		0.20	0.044	mg/L	1		6020B	Recoverable Total
Magnesium	30		0.20	0.049	mg/L	1		6020B	Recoverable Total
Molybdenum	0.030		0.0050	0.0025	mg/L	1		6020B	Recoverable Total
Potassium	4.3		0.50	0.11	mg/L	1		6020B	Recoverable Total
Sodium	47		0.20	0.077	mg/L	1		6020B	Recoverable Total
Chloride	63	B	5.0	0.58	mg/L	5		300.0	Total/NA
Sulfate	57		5.0	1.0	mg/L	5		300.0	Total/NA
Bicarbonate Alkalinity as CaCO3	240		5.0	3.7	mg/L	1		SM 2320B	Total/NA
Total Dissolved Solids	450		10	4.3	mg/L	1		SM 2540C	Total/NA
Fluoride	0.26		0.10	0.056	mg/L	1		SM 4500 F C	Total/NA
Depth to Water (ft from MP)	54.05				ft	1		Field Sampling	Total/NA
Field pH	7.22				SU	1		Field Sampling	Total/NA
Field Temperature	17.1				Degrees C	1		Field Sampling	Total/NA
Oxidation Reduction Potential	88.6				millivolts	1		Field Sampling	Total/NA
Oxygen, Dissolved	2.08				mg/L	1		Field Sampling	Total/NA
Specific Conductance	658				umhos/cm	1		Field Sampling	Total/NA
Turbidity	8.51				NTU	1		Field Sampling	Total/NA

Client Sample ID: HEN_55

Lab Sample ID: 500-258038-39

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Depth to Water (ft from MP)	52.32				ft	1		Field Sampling	Total/NA

Client Sample ID: HEN_XSG01

Lab Sample ID: 500-258038-40

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Depth to Water (ft from MP)	10.55				ft	1		Field Sampling	Total/NA

Client Sample ID: HEN_SG02_YSG_ILRIVER

Lab Sample ID: 500-258038-41

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Groundwater Elevation	441.0				ft	1		Field Sampling	Total/NA

This Detection Summary does not include radiochemical test results.

Eurofins Chicago

Method Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Method	Method Description	Protocol	Laboratory
200.7 Rev 4.4	Metals (ICP)	EPA	EET CHI
6020B	Metals (ICP/MS)	SW846	EET CHI
7470A	Mercury (CVAA)	SW846	EET CHI
300.0	Anions, Ion Chromatography	EPA	EET CHI
SM 2320B	Alkalinity	SM	EET CHI
SM 2540C	Solids, Total Dissolved (TDS)	SM	EET CHI
SM 4500 F C	Fluoride	SM	EET CHI
Field Sampling	Field Sampling	EPA	EET CHI
200.7	Preparation, Total Recoverable Metals	EPA	EET CHI
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET CHI
7470A	Preparation, Mercury	SW846	EET CHI

Protocol References:

EPA = US Environmental Protection Agency

SM = "Standard Methods For The Examination Of Water And Wastewater"

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET CHI = Eurofins Chicago, 2417 Bond Street, University Park, IL 60484, TEL (708)534-5200

Sample Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
500-258038-6	HEN_08&D	Water	10/08/24 08:15	10/09/24 12:00
500-258038-7	HEN_12	Water	10/08/24 09:15	10/09/24 12:00
500-258038-8	HEN_13	Water	10/08/24 08:20	10/09/24 12:00
500-258038-21	HEN_16	Water	10/09/24 15:05	10/10/24 11:10
500-258038-22	HEN_16_FD	Water	10/09/24 15:20	10/10/24 11:10
500-258038-23	HEN_17	Water	10/09/24 14:10	10/10/24 11:10
500-258038-28	HEN_46	Water	10/09/24 11:30	10/10/24 11:10
500-258038-29	HEN_47	Water	10/09/24 12:40	10/10/24 11:10
500-258038-33	HEN_07	Water	10/10/24 09:20	10/10/24 12:46
500-258038-34	HEN_08	Water	10/10/24 09:20	10/10/24 12:46
500-258038-35	HEN_52	Water	10/10/24 08:10	10/10/24 12:46
500-258038-36	HEN_54	Water	10/10/24 08:15	10/10/24 12:46
500-258038-37	HEN_54_FD	Water	10/10/24 08:25	10/10/24 12:46
500-258038-39	HEN_55	Water	10/07/24 11:57	10/08/24 11:17
500-258038-40	HEN_XSG01	Water	10/07/24 11:32	10/08/24 11:17
500-258038-41	HEN_SG02_YSG_ILRIVER	Water	10/07/24 10:25	10/08/24 11:17

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_08&D

Lab Sample ID: 500-258038-6

Date Collected: 10/08/24 08:15

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.014		0.0050	0.0020	mg/L		10/22/24 09:15	10/23/24 12:03	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:07	10/23/24 16:03	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:07	10/23/24 16:03	1
Barium	0.093		0.0025	0.00073	mg/L		10/22/24 09:07	10/23/24 16:03	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:07	10/23/24 16:03	1
Boron	0.093	B	0.050	0.013	mg/L		10/22/24 09:07	10/23/24 16:03	1
Cadmium	0.00039	J	0.00050	0.00017	mg/L		10/22/24 09:07	10/23/24 16:03	1
Calcium	170		0.20	0.044	mg/L		10/22/24 09:07	10/23/24 16:03	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:07	10/23/24 16:03	1
Cobalt	0.0020		0.0010	0.00040	mg/L		10/22/24 09:07	10/23/24 16:03	1
Lead	0.00032	J	0.00050	0.00019	mg/L		10/22/24 09:07	10/23/24 16:03	1
Magnesium	49		0.20	0.049	mg/L		10/22/24 09:07	10/23/24 16:03	1
Molybdenum	<0.0050		0.0050	0.0025	mg/L		10/22/24 09:07	10/23/24 16:03	1
Potassium	3.2		0.50	0.11	mg/L		10/22/24 09:07	10/23/24 16:03	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:07	10/23/24 16:03	1
Sodium	180		0.20	0.077	mg/L		10/22/24 09:07	10/23/24 16:03	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:07	10/23/24 16:03	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/21/24 11:05	10/22/24 08:38	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	240	B	20	2.3	mg/L			10/23/24 08:42	20
Sulfate (EPA 300.0)	120		5.0	1.0	mg/L			10/17/24 00:44	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	460	B	5.0	3.7	mg/L			10/21/24 13:21	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/21/24 13:21	1
Total Dissolved Solids (SM 2540C)	1100		10	4.3	mg/L			10/11/24 01:41	1
Fluoride (SM 4500 F C)	0.10		0.10	0.056	mg/L			10/10/24 13:30	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	55.09				ft			10/08/24 08:15	1
Field pH	6.65				SU			10/08/24 08:15	1
Field Temperature	13.1				Degrees C			10/08/24 08:15	1
Oxidation Reduction Potential	123.9				millivolts			10/08/24 08:15	1
Oxygen, Dissolved	1.58				mg/L			10/08/24 08:15	1
Specific Conductance	1675				umhos/cm			10/08/24 08:15	1
Turbidity	6.33				NTU			10/08/24 08:15	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_12

Date Collected: 10/08/24 09:15

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-7

Matrix: Water

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.0090		0.0050	0.0020	mg/L		10/22/24 09:15	10/23/24 12:08	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:07	10/23/24 16:06	1
Arsenic	0.00023	J	0.0010	0.00023	mg/L		10/22/24 09:07	10/23/24 16:06	1
Barium	0.058		0.0025	0.00073	mg/L		10/22/24 09:07	10/23/24 16:06	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:07	10/23/24 16:06	1
Boron	0.13	B	0.050	0.013	mg/L		10/22/24 09:07	10/23/24 16:06	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:07	10/23/24 16:06	1
Calcium	77		0.20	0.044	mg/L		10/22/24 09:07	10/23/24 16:06	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:07	10/23/24 16:06	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:07	10/23/24 16:06	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:07	10/23/24 16:06	1
Magnesium	29		0.20	0.049	mg/L		10/22/24 09:07	10/23/24 16:06	1
Molybdenum	0.014		0.0050	0.0025	mg/L		10/22/24 09:07	10/23/24 16:06	1
Potassium	4.2		0.50	0.11	mg/L		10/22/24 09:07	10/23/24 16:06	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:07	10/23/24 16:06	1
Sodium	47		0.20	0.077	mg/L		10/22/24 09:07	10/23/24 16:06	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:07	10/23/24 16:06	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/21/24 11:05	10/22/24 08:40	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	74		5.0	0.58	mg/L			10/17/24 01:47	5
Sulfate (EPA 300.0)	61		5.0	1.0	mg/L			10/17/24 01:47	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	220	B	5.0	3.7	mg/L			10/21/24 13:31	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/21/24 13:31	1
Total Dissolved Solids (SM 2540C)	470		10	4.3	mg/L			10/11/24 01:43	1
Fluoride (SM 4500 F C)	0.22		0.10	0.056	mg/L			10/10/24 13:34	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.24				SU			10/08/24 09:15	1
Field Temperature	19.4				Degrees C			10/08/24 09:15	1
Oxidation Reduction Potential	55.3				millivolts			10/08/24 09:15	1
Oxygen, Dissolved	1.74				mg/L			10/08/24 09:15	1
Specific Conductance	871				umhos/cm			10/08/24 09:15	1
Turbidity	2.79				NTU			10/08/24 09:15	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_13

Lab Sample ID: 500-258038-8

Date Collected: 10/08/24 08:20

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.011		0.0050	0.0020	mg/L		10/22/24 09:15	10/23/24 12:12	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:07	10/23/24 16:08	1
Arsenic	0.00037	J	0.0010	0.00023	mg/L		10/22/24 09:07	10/23/24 16:08	1
Barium	0.044		0.0025	0.00073	mg/L		10/22/24 09:07	10/23/24 16:08	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:07	10/23/24 16:08	1
Boron	0.17	B	0.050	0.013	mg/L		10/22/24 09:07	10/23/24 16:08	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:07	10/23/24 16:08	1
Calcium	80		0.20	0.044	mg/L		10/22/24 09:07	10/23/24 16:08	1
Chromium	0.0011	J	0.0050	0.0011	mg/L		10/22/24 09:07	10/23/24 16:08	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:07	10/23/24 16:08	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:07	10/23/24 16:08	1
Magnesium	31		0.20	0.049	mg/L		10/22/24 09:07	10/23/24 16:08	1
Molybdenum	0.011		0.0050	0.0025	mg/L		10/22/24 09:07	10/23/24 16:08	1
Potassium	4.1		0.50	0.11	mg/L		10/22/24 09:07	10/23/24 16:08	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:07	10/23/24 16:08	1
Sodium	44		0.20	0.077	mg/L		10/22/24 09:07	10/23/24 16:08	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:07	10/23/24 16:08	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/21/24 11:05	10/22/24 08:42	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	66		5.0	0.58	mg/L			10/17/24 02:18	5
Sulfate (EPA 300.0)	56		5.0	1.0	mg/L			10/17/24 02:18	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	230	B	5.0	3.7	mg/L			10/21/24 13:40	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/21/24 13:40	1
Total Dissolved Solids (SM 2540C)	440		10	4.3	mg/L			10/11/24 01:46	1
Fluoride (SM 4500 F C)	0.19		0.10	0.056	mg/L			10/10/24 13:49	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	52.21				ft			10/08/24 08:20	1
Field pH	7.30				SU			10/08/24 08:20	1
Field Temperature	18.4				Degrees C			10/08/24 08:20	1
Oxidation Reduction Potential	57.4				millivolts			10/08/24 08:20	1
Oxygen, Dissolved	1.37				mg/L			10/08/24 08:20	1
Specific Conductance	865				umhos/cm			10/08/24 08:20	1
Turbidity	3.06				NTU			10/08/24 08:20	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_16

Lab Sample ID: 500-258038-21

Date Collected: 10/09/24 15:05

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.0056		0.0050	0.0020	mg/L		10/22/24 09:15	10/23/24 13:28	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:07	10/23/24 17:12	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:07	10/23/24 17:12	1
Barium	0.072		0.0025	0.00073	mg/L		10/22/24 09:07	10/23/24 17:12	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:07	10/23/24 17:12	1
Boron	0.14	B	0.050	0.013	mg/L		10/22/24 09:07	10/23/24 17:12	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:07	10/23/24 17:12	1
Calcium	82		0.20	0.044	mg/L		10/22/24 09:07	10/23/24 17:12	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:07	10/23/24 17:12	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:07	10/23/24 17:12	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:07	10/23/24 17:12	1
Magnesium	27		0.20	0.049	mg/L		10/22/24 09:07	10/23/24 17:12	1
Molybdenum	0.0064		0.0050	0.0025	mg/L		10/22/24 09:07	10/23/24 17:12	1
Potassium	3.9		0.50	0.11	mg/L		10/22/24 09:07	10/23/24 17:12	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:07	10/23/24 17:12	1
Sodium	50		0.20	0.077	mg/L		10/22/24 09:07	10/23/24 17:12	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:07	10/23/24 17:12	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 10:07	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	70		5.0	0.58	mg/L			10/17/24 14:03	5
Sulfate (EPA 300.0)	62		5.0	1.0	mg/L			10/17/24 14:03	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	240		5.0	3.7	mg/L			10/22/24 16:39	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/22/24 16:39	1
Total Dissolved Solids (SM 2540C)	460		10	4.3	mg/L			10/11/24 03:14	1
Fluoride (SM 4500 F C)	0.21		0.10	0.056	mg/L			10/18/24 16:15	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	55.15				ft			10/09/24 15:05	1
Field pH	6.99				SU			10/09/24 15:05	1
Field Temperature	21.4				Degrees C			10/09/24 15:05	1
Oxidation Reduction Potential	130.9				millivolts			10/09/24 15:05	1
Oxygen, Dissolved	2.06				mg/L			10/09/24 15:05	1
Specific Conductance	736				umhos/cm			10/09/24 15:05	1
Turbidity	5.24				NTU			10/09/24 15:05	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_16_FD

Lab Sample ID: 500-258038-22

Date Collected: 10/09/24 15:20

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.0064		0.0050	0.0020	mg/L		10/22/24 09:15	10/23/24 13:41	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:07	10/23/24 17:14	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:07	10/23/24 17:14	1
Barium	0.072		0.0025	0.00073	mg/L		10/22/24 09:07	10/23/24 17:14	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:07	10/23/24 17:14	1
Boron	0.13	B	0.050	0.013	mg/L		10/22/24 09:07	10/23/24 17:14	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:07	10/23/24 17:14	1
Calcium	83		0.20	0.044	mg/L		10/22/24 09:07	10/23/24 17:14	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:07	10/23/24 17:14	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:07	10/23/24 17:14	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:07	10/23/24 17:14	1
Magnesium	27		0.20	0.049	mg/L		10/22/24 09:07	10/23/24 17:14	1
Molybdenum	0.0063		0.0050	0.0025	mg/L		10/22/24 09:07	10/23/24 17:14	1
Potassium	4.0		0.50	0.11	mg/L		10/22/24 09:07	10/23/24 17:14	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:07	10/23/24 17:14	1
Sodium	51		0.20	0.077	mg/L		10/22/24 09:07	10/23/24 17:14	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:07	10/23/24 17:14	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 10:10	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	72		5.0	0.58	mg/L			10/17/24 14:19	5
Sulfate (EPA 300.0)	63		5.0	1.0	mg/L			10/17/24 14:19	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	240		5.0	3.7	mg/L			10/22/24 16:48	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/22/24 16:48	1
Total Dissolved Solids (SM 2540C)	480		10	4.3	mg/L			10/11/24 03:17	1
Fluoride (SM 4500 F C)	0.21		0.10	0.056	mg/L			10/18/24 16:31	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	55.15				ft			10/09/24 15:20	1
Field pH	6.99				SU			10/09/24 15:20	1
Field Temperature	21.4				Degrees C			10/09/24 15:20	1
Oxidation Reduction Potential	130.9				millivolts			10/09/24 15:20	1
Oxygen, Dissolved	2.06				mg/L			10/09/24 15:20	1
Specific Conductance	736				umhos/cm			10/09/24 15:20	1
Turbidity	5.24				NTU			10/09/24 15:20	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_17

Lab Sample ID: 500-258038-23

Date Collected: 10/09/24 14:10

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.0066		0.0050	0.0020	mg/L		10/22/24 09:15	10/23/24 13:46	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:07	10/23/24 17:17	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:07	10/23/24 17:17	1
Barium	0.086		0.0025	0.00073	mg/L		10/22/24 09:07	10/23/24 17:17	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:07	10/23/24 17:17	1
Boron	0.13	B	0.050	0.013	mg/L		10/22/24 09:07	10/23/24 17:17	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:07	10/23/24 17:17	1
Calcium	74		0.20	0.044	mg/L		10/22/24 09:07	10/23/24 17:17	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:07	10/23/24 17:17	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:07	10/23/24 17:17	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:07	10/23/24 17:17	1
Magnesium	28		0.20	0.049	mg/L		10/22/24 09:07	10/23/24 17:17	1
Molybdenum	0.0043	J	0.0050	0.0025	mg/L		10/22/24 09:07	10/23/24 17:17	1
Potassium	4.5		0.50	0.11	mg/L		10/22/24 09:07	10/23/24 17:17	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:07	10/23/24 17:17	1
Sodium	61		0.20	0.077	mg/L		10/22/24 09:07	10/23/24 17:17	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:07	10/23/24 17:17	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 10:12	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	89		5.0	0.58	mg/L			10/17/24 14:34	5
Sulfate (EPA 300.0)	70		5.0	1.0	mg/L			10/17/24 14:34	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	220		5.0	3.7	mg/L			10/22/24 16:57	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/22/24 16:57	1
Total Dissolved Solids (SM 2540C)	470		10	4.3	mg/L			10/11/24 03:19	1
Fluoride (SM 4500 F C)	0.23		0.10	0.056	mg/L			10/18/24 16:35	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	56.30				ft			10/09/24 14:10	1
Field pH	7.04				SU			10/09/24 14:10	1
Field Temperature	22.6				Degrees C			10/09/24 14:10	1
Oxidation Reduction Potential	134.7				millivolts			10/09/24 14:10	1
Oxygen, Dissolved	4.98				mg/L			10/09/24 14:10	1
Specific Conductance	762				umhos/cm			10/09/24 14:10	1
Turbidity	92.96				NTU			10/09/24 14:10	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_46

Lab Sample ID: 500-258038-28

Date Collected: 10/09/24 11:30

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.0076		0.0050	0.0020	mg/L		10/22/24 09:18	10/23/24 12:19	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:09	10/22/24 22:17	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:09	10/22/24 22:17	1
Barium	0.074		0.0025	0.00073	mg/L		10/22/24 09:09	10/22/24 22:17	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:09	10/23/24 11:38	1
Boron	0.14	B	0.050	0.013	mg/L		10/22/24 09:09	10/23/24 11:38	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:09	10/23/24 11:38	1
Calcium	81		0.20	0.044	mg/L		10/22/24 09:09	10/22/24 22:17	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:09	10/22/24 22:17	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:09	10/23/24 11:38	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:09	10/22/24 22:17	1
Magnesium	30		0.20	0.049	mg/L		10/22/24 09:09	10/22/24 22:17	1
Molybdenum	0.020		0.0050	0.0025	mg/L		10/22/24 09:09	10/22/24 22:17	1
Potassium	4.5		0.50	0.11	mg/L		10/22/24 09:09	10/22/24 22:17	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:09	10/22/24 22:17	1
Sodium	54		0.20	0.077	mg/L		10/22/24 09:09	10/22/24 22:17	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:09	10/23/24 11:38	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 10:22	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	79	B	5.0	0.58	mg/L			10/23/24 09:13	5
Sulfate (EPA 300.0)	61		5.0	1.0	mg/L			10/23/24 09:13	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	220		5.0	3.7	mg/L			10/22/24 18:07	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/22/24 18:07	1
Total Dissolved Solids (SM 2540C)	450		10	4.3	mg/L			10/11/24 03:32	1
Fluoride (SM 4500 F C)	0.24		0.10	0.056	mg/L			10/18/24 16:58	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	52.27				ft			10/09/24 11:30	1
Field pH	7.16				SU			10/09/24 11:30	1
Field Temperature	21.2				Degrees C			10/09/24 11:30	1
Oxidation Reduction Potential	99.9				millivolts			10/09/24 11:30	1
Oxygen, Dissolved	1.28				mg/L			10/09/24 11:30	1
Specific Conductance	709				umhos/cm			10/09/24 11:30	1
Turbidity	7.28				NTU			10/09/24 11:30	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_47

Lab Sample ID: 500-258038-29

Date Collected: 10/09/24 12:40

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.010		0.0050	0.0020	mg/L		10/22/24 09:18	10/23/24 12:24	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:09	10/22/24 22:20	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:09	10/22/24 22:20	1
Barium	0.079		0.0025	0.00073	mg/L		10/22/24 09:09	10/22/24 22:20	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:09	10/23/24 11:41	1
Boron	0.16	B	0.050	0.013	mg/L		10/22/24 09:09	10/23/24 11:41	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:09	10/23/24 11:41	1
Calcium	91		0.20	0.044	mg/L		10/22/24 09:09	10/22/24 22:20	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:09	10/22/24 22:20	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:09	10/23/24 11:41	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:09	10/22/24 22:20	1
Magnesium	31		0.20	0.049	mg/L		10/22/24 09:09	10/22/24 22:20	1
Molybdenum	0.028		0.0050	0.0025	mg/L		10/22/24 09:09	10/22/24 22:20	1
Potassium	4.4		0.50	0.11	mg/L		10/22/24 09:09	10/22/24 22:20	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:09	10/22/24 22:20	1
Sodium	47		0.20	0.077	mg/L		10/22/24 09:09	10/22/24 22:20	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:09	10/23/24 11:41	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 10:25	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	71	B	5.0	0.58	mg/L			10/23/24 09:28	5
Sulfate (EPA 300.0)	57		5.0	1.0	mg/L			10/23/24 09:28	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	260		5.0	3.7	mg/L			10/22/24 18:16	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/22/24 18:16	1
Total Dissolved Solids (SM 2540C)	460		10	4.3	mg/L			10/11/24 03:35	1
Fluoride (SM 4500 F C)	0.26		0.10	0.056	mg/L			10/18/24 17:30	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	56.60				ft			10/09/24 12:40	1
Field pH	6.99				SU			10/09/24 12:40	1
Field Temperature	19.6				Degrees C			10/09/24 12:40	1
Oxidation Reduction Potential	118.9				millivolts			10/09/24 12:40	1
Oxygen, Dissolved	1.98				mg/L			10/09/24 12:40	1
Specific Conductance	727				umhos/cm			10/09/24 12:40	1
Turbidity	7.78				NTU			10/09/24 12:40	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_07

Lab Sample ID: 500-258038-33

Date Collected: 10/10/24 09:20

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.0096		0.0050	0.0020	mg/L		10/22/24 09:18	10/23/24 13:09	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:09	10/22/24 22:45	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:09	10/22/24 22:45	1
Barium	0.12		0.0025	0.00073	mg/L		10/22/24 09:09	10/22/24 22:45	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:09	10/23/24 12:09	1
Boron	0.069	B	0.050	0.013	mg/L		10/22/24 09:09	10/23/24 12:09	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:09	10/23/24 12:09	1
Calcium	140		0.20	0.044	mg/L		10/22/24 09:09	10/22/24 22:45	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:09	10/22/24 22:45	1
Cobalt	0.0037		0.0010	0.00040	mg/L		10/22/24 09:09	10/23/24 12:09	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:09	10/22/24 22:45	1
Magnesium	43		0.20	0.049	mg/L		10/22/24 09:09	10/22/24 22:45	1
Molybdenum	<0.0050		0.0050	0.0025	mg/L		10/22/24 09:09	10/22/24 22:45	1
Potassium	2.7		0.50	0.11	mg/L		10/22/24 09:09	10/22/24 22:45	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:09	10/22/24 22:45	1
Sodium	42		0.20	0.077	mg/L		10/22/24 09:09	10/22/24 22:45	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:09	10/23/24 12:09	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 10:44	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	54	B	5.0	0.58	mg/L			10/19/24 07:15	5
Sulfate (EPA 300.0)	57		5.0	1.0	mg/L			10/19/24 07:15	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	390		5.0	3.7	mg/L			10/22/24 22:30	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/22/24 22:30	1
Total Dissolved Solids (SM 2540C)	650		10	4.3	mg/L			10/11/24 03:53	1
Fluoride (SM 4500 F C)	0.11		0.10	0.056	mg/L			10/18/24 17:44	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	69.03				ft			10/10/24 09:20	1
Field pH	6.79				SU			10/10/24 09:20	1
Field Temperature	11.5				Degrees C			10/10/24 09:20	1
Oxidation Reduction Potential	112.7				millivolts			10/10/24 09:20	1
Oxygen, Dissolved	5.60				mg/L			10/10/24 09:20	1
Specific Conductance	1144				umhos/cm			10/10/24 09:20	1
Turbidity	5.30				NTU			10/10/24 09:20	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_08

Lab Sample ID: 500-258038-34

Date Collected: 10/10/24 09:20

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.016		0.0050	0.0020	mg/L		10/22/24 09:18	10/23/24 13:13	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:09	10/22/24 22:47	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:09	10/22/24 22:47	1
Barium	0.12		0.0025	0.00073	mg/L		10/22/24 09:09	10/22/24 22:47	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:09	10/23/24 12:12	1
Boron	0.11	B	0.050	0.013	mg/L		10/22/24 09:09	10/23/24 12:12	1
Cadmium	0.00041	J	0.00050	0.00017	mg/L		10/22/24 09:09	10/23/24 12:12	1
Calcium	210		0.20	0.044	mg/L		10/22/24 09:09	10/22/24 22:47	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:09	10/22/24 22:47	1
Cobalt	0.0024		0.0010	0.00040	mg/L		10/22/24 09:09	10/23/24 12:12	1
Lead	0.00031	J	0.00050	0.00019	mg/L		10/22/24 09:09	10/22/24 22:47	1
Magnesium	57		0.20	0.049	mg/L		10/22/24 09:09	10/22/24 22:47	1
Molybdenum	<0.0050		0.0050	0.0025	mg/L		10/22/24 09:09	10/22/24 22:47	1
Potassium	7.9		0.50	0.11	mg/L		10/22/24 09:09	10/22/24 22:47	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:09	10/22/24 22:47	1
Sodium	110		0.20	0.077	mg/L		10/22/24 09:09	10/22/24 22:47	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:09	10/23/24 12:12	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 10:46	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	240	B	20	2.3	mg/L			10/23/24 12:36	20
Sulfate (EPA 300.0)	100		5.0	1.0	mg/L			10/19/24 07:47	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	460		5.0	3.7	mg/L			10/22/24 22:40	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/22/24 22:40	1
Total Dissolved Solids (SM 2540C)	1100		10	4.3	mg/L			10/13/24 22:14	1
Fluoride (SM 4500 F C)	0.086	J	0.10	0.056	mg/L			10/18/24 17:48	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	54.52				ft			10/10/24 09:20	1
Field pH	6.47				SU			10/10/24 09:20	1
Field Temperature	13.7				Degrees C			10/10/24 09:20	1
Oxidation Reduction Potential	145.6				millivolts			10/10/24 09:20	1
Oxygen, Dissolved	1.89				mg/L			10/10/24 09:20	1
Specific Conductance	1549				umhos/cm			10/10/24 09:20	1
Turbidity	9.91				NTU			10/10/24 09:20	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_52

Lab Sample ID: 500-258038-35

Date Collected: 10/10/24 08:10

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.0094		0.0050	0.0020	mg/L		10/22/24 09:18	10/23/24 13:18	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:09	10/22/24 22:50	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:09	10/22/24 22:50	1
Barium	0.10		0.0025	0.00073	mg/L		10/22/24 09:09	10/22/24 22:50	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:09	10/23/24 12:14	1
Boron	0.32	B	0.050	0.013	mg/L		10/22/24 09:09	10/23/24 12:14	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:09	10/23/24 12:14	1
Calcium	100		0.20	0.044	mg/L		10/22/24 09:09	10/22/24 22:50	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:09	10/22/24 22:50	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:09	10/23/24 12:14	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:09	10/22/24 22:50	1
Magnesium	32		0.20	0.049	mg/L		10/22/24 09:09	10/22/24 22:50	1
Molybdenum	0.013		0.0050	0.0025	mg/L		10/22/24 09:09	10/22/24 22:50	1
Potassium	5.4		0.50	0.11	mg/L		10/22/24 09:09	10/22/24 22:50	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:09	10/22/24 22:50	1
Sodium	57		0.20	0.077	mg/L		10/22/24 09:09	10/22/24 22:50	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:09	10/23/24 12:14	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 10:48	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	72	B	5.0	0.58	mg/L			10/19/24 08:02	5
Sulfate (EPA 300.0)	63		5.0	1.0	mg/L			10/19/24 08:02	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	300		5.0	3.7	mg/L			10/22/24 22:50	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/22/24 22:50	1
Total Dissolved Solids (SM 2540C)	510		10	4.3	mg/L			10/13/24 22:17	1
Fluoride (SM 4500 F C)	0.26		0.10	0.056	mg/L			10/18/24 17:53	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	54.74				ft			10/10/24 08:10	1
Field pH	6.94				SU			10/10/24 08:10	1
Field Temperature	19.8				Degrees C			10/10/24 08:10	1
Oxidation Reduction Potential	41.7				millivolts			10/10/24 08:10	1
Oxygen, Dissolved	1.44				mg/L			10/10/24 08:10	1
Specific Conductance	1008				umhos/cm			10/10/24 08:10	1
Turbidity	3.11				NTU			10/10/24 08:10	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_54

Lab Sample ID: 500-258038-36

Date Collected: 10/10/24 08:15

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.010		0.0050	0.0020	mg/L		10/22/24 09:18	10/23/24 13:22	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:09	10/22/24 22:52	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:09	10/22/24 22:52	1
Barium	0.052		0.0025	0.00073	mg/L		10/22/24 09:09	10/22/24 22:52	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:09	10/23/24 12:16	1
Boron	0.30	B	0.050	0.013	mg/L		10/22/24 09:09	10/23/24 12:16	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:09	10/23/24 12:16	1
Calcium	79		0.20	0.044	mg/L		10/22/24 09:09	10/22/24 22:52	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:09	10/22/24 22:52	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:09	10/23/24 12:16	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:09	10/22/24 22:52	1
Magnesium	30		0.20	0.049	mg/L		10/22/24 09:09	10/22/24 22:52	1
Molybdenum	0.030		0.0050	0.0025	mg/L		10/22/24 09:09	10/22/24 22:52	1
Potassium	4.4		0.50	0.11	mg/L		10/22/24 09:09	10/22/24 22:52	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:09	10/22/24 22:52	1
Sodium	48		0.20	0.077	mg/L		10/22/24 09:09	10/22/24 22:52	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:09	10/23/24 12:16	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 10:50	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	63	B	5.0	0.58	mg/L			10/19/24 08:18	5
Sulfate (EPA 300.0)	57		5.0	1.0	mg/L			10/19/24 08:18	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	240		5.0	3.7	mg/L			10/22/24 23:00	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/22/24 23:00	1
Total Dissolved Solids (SM 2540C)	470		10	4.3	mg/L			10/13/24 22:20	1
Fluoride (SM 4500 F C)	0.26		0.10	0.056	mg/L			10/18/24 17:58	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	54.05				ft			10/10/24 08:15	1
Field pH	7.22				SU			10/10/24 08:15	1
Field Temperature	17.1				Degrees C			10/10/24 08:15	1
Oxidation Reduction Potential	88.6				millivolts			10/10/24 08:15	1
Oxygen, Dissolved	2.08				mg/L			10/10/24 08:15	1
Specific Conductance	658				umhos/cm			10/10/24 08:15	1
Turbidity	8.51				NTU			10/10/24 08:15	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_54_FD

Lab Sample ID: 500-258038-37

Date Collected: 10/10/24 08:25

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 200.7 Rev 4.4 - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	0.010		0.0050	0.0020	mg/L		10/22/24 09:18	10/23/24 13:27	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:09	10/22/24 22:55	1
Arsenic	0.00023	J	0.0010	0.00023	mg/L		10/22/24 09:09	10/22/24 22:55	1
Barium	0.053		0.0025	0.00073	mg/L		10/22/24 09:09	10/22/24 22:55	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:09	10/23/24 12:19	1
Boron	0.29	B	0.050	0.013	mg/L		10/22/24 09:09	10/23/24 12:19	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:09	10/23/24 12:19	1
Calcium	80		0.20	0.044	mg/L		10/22/24 09:09	10/22/24 22:55	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:09	10/22/24 22:55	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:09	10/23/24 12:19	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:09	10/22/24 22:55	1
Magnesium	30		0.20	0.049	mg/L		10/22/24 09:09	10/22/24 22:55	1
Molybdenum	0.030		0.0050	0.0025	mg/L		10/22/24 09:09	10/22/24 22:55	1
Potassium	4.3		0.50	0.11	mg/L		10/22/24 09:09	10/22/24 22:55	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:09	10/22/24 22:55	1
Sodium	47		0.20	0.077	mg/L		10/22/24 09:09	10/22/24 22:55	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:09	10/23/24 12:19	1

Method: SW846 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 10:52	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride (EPA 300.0)	63	B	5.0	0.58	mg/L			10/19/24 08:34	5
Sulfate (EPA 300.0)	57		5.0	1.0	mg/L			10/19/24 08:34	5
Bicarbonate Alkalinity as CaCO3 (SM 2320B)	240		5.0	3.7	mg/L			10/22/24 23:09	1
Carbonate Alkalinity as CaCO3 (SM 2320B)	<5.0		5.0	3.7	mg/L			10/22/24 23:09	1
Total Dissolved Solids (SM 2540C)	450		10	4.3	mg/L			10/13/24 22:22	1
Fluoride (SM 4500 F C)	0.26		0.10	0.056	mg/L			10/18/24 18:03	1

Method: EPA Field Sampling - Field Sampling

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	54.05				ft			10/10/24 08:25	1
Field pH	7.22				SU			10/10/24 08:25	1
Field Temperature	17.1				Degrees C			10/10/24 08:25	1
Oxidation Reduction Potential	88.6				millivolts			10/10/24 08:25	1
Oxygen, Dissolved	2.08				mg/L			10/10/24 08:25	1
Specific Conductance	658				umhos/cm			10/10/24 08:25	1
Turbidity	8.51				NTU			10/10/24 08:25	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_55 Lab Sample ID: 500-258038-39
Date Collected: 10/07/24 11:57 Matrix: Water
Date Received: 10/08/24 11:17

Method: EPA Field Sampling - Field Sampling									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	52.32				ft			10/07/24 11:57	1

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_XSG01 Lab Sample ID: 500-258038-40
Date Collected: 10/07/24 11:32 Matrix: Water
Date Received: 10/08/24 11:17

Method: EPA Field Sampling - Field Sampling									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Depth to Water (ft from MP)	10.55				ft			10/07/24 11:32	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_SG02_YSG_ILRIVER
Date Collected: 10/07/24 10:25
Date Received: 10/08/24 11:17

Lab Sample ID: 500-258038-41
Matrix: Water

Method: EPA Field Sampling - Field Sampling									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Groundwater Elevation	441.0				ft			10/07/24 10:25	1

Definitions/Glossary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Qualifiers

Metals

Qualifier	Qualifier Description
B	Compound was found in the blank and sample.
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

General Chemistry

Qualifier	Qualifier Description
B	Compound was found in the blank and sample.
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
☼	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

QC Association Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Metals

Prep Batch: 791618

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total/NA	Water	7470A	
500-258038-7	HEN_12	Total/NA	Water	7470A	
500-258038-8	HEN_13	Total/NA	Water	7470A	
MB 500-791618/12-A	Method Blank	Total/NA	Water	7470A	
LCS 500-791618/13-A	Lab Control Sample	Total/NA	Water	7470A	
LCSD 500-791618/29-A	Lab Control Sample Dup	Total/NA	Water	7470A	

Prep Batch: 791759

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total Recoverable	Water	3005A	
500-258038-7	HEN_12	Total Recoverable	Water	3005A	
500-258038-8	HEN_13	Total Recoverable	Water	3005A	
500-258038-21	HEN_16	Total Recoverable	Water	3005A	
500-258038-22	HEN_16_FD	Total Recoverable	Water	3005A	
500-258038-23	HEN_17	Total Recoverable	Water	3005A	
MB 500-791759/1-A	Method Blank	Total Recoverable	Water	3005A	
LCS 500-791759/2-A	Lab Control Sample	Total Recoverable	Water	3005A	

Prep Batch: 791760

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-28	HEN_46	Total Recoverable	Water	3005A	
500-258038-29	HEN_47	Total Recoverable	Water	3005A	
500-258038-33	HEN_07	Total Recoverable	Water	3005A	
500-258038-34	HEN_08	Total Recoverable	Water	3005A	
500-258038-35	HEN_52	Total Recoverable	Water	3005A	
500-258038-36	HEN_54	Total Recoverable	Water	3005A	
500-258038-37	HEN_54_FD	Total Recoverable	Water	3005A	
MB 500-791760/1-A	Method Blank	Total Recoverable	Water	3005A	
LCS 500-791760/2-A	Lab Control Sample	Total Recoverable	Water	3005A	

Prep Batch: 791762

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total Recoverable	Water	200.7	
500-258038-7	HEN_12	Total Recoverable	Water	200.7	
500-258038-8	HEN_13	Total Recoverable	Water	200.7	
500-258038-21	HEN_16	Total Recoverable	Water	200.7	
500-258038-22	HEN_16_FD	Total Recoverable	Water	200.7	
500-258038-23	HEN_17	Total Recoverable	Water	200.7	
MB 500-791762/1-A	Method Blank	Total Recoverable	Water	200.7	
LCS 500-791762/2-A	Lab Control Sample	Total Recoverable	Water	200.7	

Prep Batch: 791763

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-28	HEN_46	Total Recoverable	Water	200.7	
500-258038-29	HEN_47	Total Recoverable	Water	200.7	
500-258038-33	HEN_07	Total Recoverable	Water	200.7	
500-258038-34	HEN_08	Total Recoverable	Water	200.7	
500-258038-35	HEN_52	Total Recoverable	Water	200.7	
500-258038-36	HEN_54	Total Recoverable	Water	200.7	
500-258038-37	HEN_54_FD	Total Recoverable	Water	200.7	
MB 500-791763/1-A	Method Blank	Total Recoverable	Water	200.7	

Eurofins Chicago

QC Association Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Metals (Continued)

Prep Batch: 791763 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
LCS 500-791763/2-A	Lab Control Sample	Total Recoverable	Water	200.7	

Prep Batch: 791799

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-21	HEN_16	Total/NA	Water	7470A	
500-258038-22	HEN_16_FD	Total/NA	Water	7470A	
500-258038-23	HEN_17	Total/NA	Water	7470A	
500-258038-28	HEN_46	Total/NA	Water	7470A	
500-258038-29	HEN_47	Total/NA	Water	7470A	
500-258038-33	HEN_07	Total/NA	Water	7470A	
500-258038-34	HEN_08	Total/NA	Water	7470A	
500-258038-35	HEN_52	Total/NA	Water	7470A	
500-258038-36	HEN_54	Total/NA	Water	7470A	
500-258038-37	HEN_54_FD	Total/NA	Water	7470A	
MB 500-791799/12-A	Method Blank	Total/NA	Water	7470A	
LCS 500-791799/13-A	Lab Control Sample	Total/NA	Water	7470A	

Analysis Batch: 791808

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total/NA	Water	7470A	791618
500-258038-7	HEN_12	Total/NA	Water	7470A	791618
500-258038-8	HEN_13	Total/NA	Water	7470A	791618
MB 500-791618/12-A	Method Blank	Total/NA	Water	7470A	791618
LCS 500-791618/13-A	Lab Control Sample	Total/NA	Water	7470A	791618
LCSD 500-791618/29-A	Lab Control Sample Dup	Total/NA	Water	7470A	791618

Analysis Batch: 791955

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-28	HEN_46	Total Recoverable	Water	6020B	791760
500-258038-29	HEN_47	Total Recoverable	Water	6020B	791760
500-258038-33	HEN_07	Total Recoverable	Water	6020B	791760
500-258038-34	HEN_08	Total Recoverable	Water	6020B	791760
500-258038-35	HEN_52	Total Recoverable	Water	6020B	791760
500-258038-36	HEN_54	Total Recoverable	Water	6020B	791760
500-258038-37	HEN_54_FD	Total Recoverable	Water	6020B	791760
MB 500-791760/1-A	Method Blank	Total Recoverable	Water	6020B	791760
LCS 500-791760/2-A	Lab Control Sample	Total Recoverable	Water	6020B	791760

Analysis Batch: 792003

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-21	HEN_16	Total/NA	Water	7470A	791799
500-258038-22	HEN_16_FD	Total/NA	Water	7470A	791799
500-258038-23	HEN_17	Total/NA	Water	7470A	791799
500-258038-28	HEN_46	Total/NA	Water	7470A	791799
500-258038-29	HEN_47	Total/NA	Water	7470A	791799
500-258038-33	HEN_07	Total/NA	Water	7470A	791799
500-258038-34	HEN_08	Total/NA	Water	7470A	791799
500-258038-35	HEN_52	Total/NA	Water	7470A	791799
500-258038-36	HEN_54	Total/NA	Water	7470A	791799
500-258038-37	HEN_54_FD	Total/NA	Water	7470A	791799
MB 500-791799/12-A	Method Blank	Total/NA	Water	7470A	791799

Eurofins Chicago

QC Association Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Metals (Continued)

Analysis Batch: 792003 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
LCS 500-791799/13-A	Lab Control Sample	Total/NA	Water	7470A	791799

Analysis Batch: 792031

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total Recoverable	Water	200.7 Rev 4.4	791762
500-258038-7	HEN_12	Total Recoverable	Water	200.7 Rev 4.4	791762
500-258038-8	HEN_13	Total Recoverable	Water	200.7 Rev 4.4	791762
500-258038-21	HEN_16	Total Recoverable	Water	200.7 Rev 4.4	791762
500-258038-22	HEN_16_FD	Total Recoverable	Water	200.7 Rev 4.4	791762
500-258038-23	HEN_17	Total Recoverable	Water	200.7 Rev 4.4	791762
MB 500-791762/1-A	Method Blank	Total Recoverable	Water	200.7 Rev 4.4	791762
LCS 500-791762/2-A	Lab Control Sample	Total Recoverable	Water	200.7 Rev 4.4	791762

Analysis Batch: 792032

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-28	HEN_46	Total Recoverable	Water	6020B	791760
500-258038-29	HEN_47	Total Recoverable	Water	6020B	791760
500-258038-33	HEN_07	Total Recoverable	Water	6020B	791760
500-258038-34	HEN_08	Total Recoverable	Water	6020B	791760
500-258038-35	HEN_52	Total Recoverable	Water	6020B	791760
500-258038-36	HEN_54	Total Recoverable	Water	6020B	791760
500-258038-37	HEN_54_FD	Total Recoverable	Water	6020B	791760
MB 500-791760/1-A	Method Blank	Total Recoverable	Water	6020B	791760
LCS 500-791760/2-A	Lab Control Sample	Total Recoverable	Water	6020B	791760

Analysis Batch: 792033

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-28	HEN_46	Total Recoverable	Water	200.7 Rev 4.4	791763
500-258038-29	HEN_47	Total Recoverable	Water	200.7 Rev 4.4	791763
500-258038-33	HEN_07	Total Recoverable	Water	200.7 Rev 4.4	791763
500-258038-34	HEN_08	Total Recoverable	Water	200.7 Rev 4.4	791763
500-258038-35	HEN_52	Total Recoverable	Water	200.7 Rev 4.4	791763
500-258038-36	HEN_54	Total Recoverable	Water	200.7 Rev 4.4	791763
500-258038-37	HEN_54_FD	Total Recoverable	Water	200.7 Rev 4.4	791763
MB 500-791763/1-A	Method Blank	Total Recoverable	Water	200.7 Rev 4.4	791763
LCS 500-791763/2-A	Lab Control Sample	Total Recoverable	Water	200.7 Rev 4.4	791763

Analysis Batch: 792125

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total Recoverable	Water	6020B	791759
500-258038-7	HEN_12	Total Recoverable	Water	6020B	791759
500-258038-8	HEN_13	Total Recoverable	Water	6020B	791759
500-258038-21	HEN_16	Total Recoverable	Water	6020B	791759
500-258038-22	HEN_16_FD	Total Recoverable	Water	6020B	791759
500-258038-23	HEN_17	Total Recoverable	Water	6020B	791759
MB 500-791759/1-A	Method Blank	Total Recoverable	Water	6020B	791759
LCS 500-791759/2-A	Lab Control Sample	Total Recoverable	Water	6020B	791759

QC Association Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

General Chemistry

Analysis Batch: 790105

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total/NA	Water	SM 2540C	
500-258038-7	HEN_12	Total/NA	Water	SM 2540C	
500-258038-8	HEN_13	Total/NA	Water	SM 2540C	
MB 500-790105/1	Method Blank	Total/NA	Water	SM 2540C	
LCS 500-790105/2	Lab Control Sample	Total/NA	Water	SM 2540C	

Analysis Batch: 790108

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-21	HEN_16	Total/NA	Water	SM 2540C	
500-258038-22	HEN_16_FD	Total/NA	Water	SM 2540C	
500-258038-23	HEN_17	Total/NA	Water	SM 2540C	
500-258038-28	HEN_46	Total/NA	Water	SM 2540C	
500-258038-29	HEN_47	Total/NA	Water	SM 2540C	
500-258038-33	HEN_07	Total/NA	Water	SM 2540C	
MB 500-790108/1	Method Blank	Total/NA	Water	SM 2540C	
LCS 500-790108/2	Lab Control Sample	Total/NA	Water	SM 2540C	

Analysis Batch: 790148

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total/NA	Water	SM 4500 F C	
500-258038-7	HEN_12	Total/NA	Water	SM 4500 F C	
500-258038-8	HEN_13	Total/NA	Water	SM 4500 F C	
MB 500-790148/3	Method Blank	Total/NA	Water	SM 4500 F C	
LCS 500-790148/4	Lab Control Sample	Total/NA	Water	SM 4500 F C	

Analysis Batch: 790410

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-34	HEN_08	Total/NA	Water	SM 2540C	
500-258038-35	HEN_52	Total/NA	Water	SM 2540C	
500-258038-36	HEN_54	Total/NA	Water	SM 2540C	
500-258038-37	HEN_54_FD	Total/NA	Water	SM 2540C	
MB 500-790410/1	Method Blank	Total/NA	Water	SM 2540C	
LCS 500-790410/2	Lab Control Sample	Total/NA	Water	SM 2540C	

Analysis Batch: 790938

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total/NA	Water	300.0	
500-258038-7	HEN_12	Total/NA	Water	300.0	
500-258038-8	HEN_13	Total/NA	Water	300.0	
500-258038-21	HEN_16	Total/NA	Water	300.0	
500-258038-22	HEN_16_FD	Total/NA	Water	300.0	
500-258038-23	HEN_17	Total/NA	Water	300.0	
MB 500-790938/33	Method Blank	Total/NA	Water	300.0	
MB 500-790938/65	Method Blank	Total/NA	Water	300.0	
LCS 500-790938/34	Lab Control Sample	Total/NA	Water	300.0	
LCS 500-790938/66	Lab Control Sample	Total/NA	Water	300.0	

Analysis Batch: 791383

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-33	HEN_07	Total/NA	Water	300.0	
500-258038-34	HEN_08	Total/NA	Water	300.0	

Eurofins Chicago

QC Association Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

General Chemistry (Continued)

Analysis Batch: 791383 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-35	HEN_52	Total/NA	Water	300.0	
500-258038-36	HEN_54	Total/NA	Water	300.0	
500-258038-37	HEN_54_FD	Total/NA	Water	300.0	
MB 500-791383/51	Method Blank	Total/NA	Water	300.0	
LCS 500-791383/52	Lab Control Sample	Total/NA	Water	300.0	

Analysis Batch: 791579

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-21	HEN_16	Total/NA	Water	SM 4500 F C	
500-258038-22	HEN_16_FD	Total/NA	Water	SM 4500 F C	
500-258038-23	HEN_17	Total/NA	Water	SM 4500 F C	
500-258038-28	HEN_46	Total/NA	Water	SM 4500 F C	
500-258038-29	HEN_47	Total/NA	Water	SM 4500 F C	
500-258038-33	HEN_07	Total/NA	Water	SM 4500 F C	
500-258038-34	HEN_08	Total/NA	Water	SM 4500 F C	
500-258038-35	HEN_52	Total/NA	Water	SM 4500 F C	
500-258038-36	HEN_54	Total/NA	Water	SM 4500 F C	
500-258038-37	HEN_54_FD	Total/NA	Water	SM 4500 F C	
MB 500-791579/31	Method Blank	Total/NA	Water	SM 4500 F C	
LCS 500-791579/32	Lab Control Sample	Total/NA	Water	SM 4500 F C	

Analysis Batch: 791737

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total/NA	Water	SM 2320B	
500-258038-7	HEN_12	Total/NA	Water	SM 2320B	
500-258038-8	HEN_13	Total/NA	Water	SM 2320B	
MB 500-791737/3	Method Blank	Total/NA	Water	SM 2320B	
LCS 500-791737/4	Lab Control Sample	Total/NA	Water	SM 2320B	

Analysis Batch: 791804

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total/NA	Water	300.0	
500-258038-28	HEN_46	Total/NA	Water	300.0	
500-258038-29	HEN_47	Total/NA	Water	300.0	
500-258038-34	HEN_08	Total/NA	Water	300.0	
MB 500-791804/33	Method Blank	Total/NA	Water	300.0	
LCS 500-791804/34	Lab Control Sample	Total/NA	Water	300.0	

Analysis Batch: 791946

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-21	HEN_16	Total/NA	Water	SM 2320B	
500-258038-22	HEN_16_FD	Total/NA	Water	SM 2320B	
500-258038-23	HEN_17	Total/NA	Water	SM 2320B	
500-258038-28	HEN_46	Total/NA	Water	SM 2320B	
500-258038-29	HEN_47	Total/NA	Water	SM 2320B	
500-258038-33	HEN_07	Total/NA	Water	SM 2320B	
500-258038-34	HEN_08	Total/NA	Water	SM 2320B	
500-258038-35	HEN_52	Total/NA	Water	SM 2320B	
500-258038-36	HEN_54	Total/NA	Water	SM 2320B	
500-258038-37	HEN_54_FD	Total/NA	Water	SM 2320B	
MB 500-791946/28	Method Blank	Total/NA	Water	SM 2320B	

Eurofins Chicago

QC Association Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

General Chemistry (Continued)

Analysis Batch: 791946 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 500-791946/3	Method Blank	Total/NA	Water	SM 2320B	
MB 500-791946/53	Method Blank	Total/NA	Water	SM 2320B	
LCS 500-791946/29	Lab Control Sample	Total/NA	Water	SM 2320B	
LCS 500-791946/4	Lab Control Sample	Total/NA	Water	SM 2320B	
LCS 500-791946/54	Lab Control Sample	Total/NA	Water	SM 2320B	

Field Service / Mobile Lab

Analysis Batch: 791677

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total/NA	Water	Field Sampling	
500-258038-7	HEN_12	Total/NA	Water	Field Sampling	
500-258038-8	HEN_13	Total/NA	Water	Field Sampling	
500-258038-21	HEN_16	Total/NA	Water	Field Sampling	
500-258038-22	HEN_16_FD	Total/NA	Water	Field Sampling	
500-258038-23	HEN_17	Total/NA	Water	Field Sampling	
500-258038-28	HEN_46	Total/NA	Water	Field Sampling	
500-258038-29	HEN_47	Total/NA	Water	Field Sampling	
500-258038-33	HEN_07	Total/NA	Water	Field Sampling	
500-258038-34	HEN_08	Total/NA	Water	Field Sampling	
500-258038-35	HEN_52	Total/NA	Water	Field Sampling	
500-258038-36	HEN_54	Total/NA	Water	Field Sampling	
500-258038-37	HEN_54_FD	Total/NA	Water	Field Sampling	
500-258038-39	HEN_55	Total/NA	Water	Field Sampling	
500-258038-40	HEN_XSG01	Total/NA	Water	Field Sampling	
500-258038-41	HEN_SG02_YSG_ILRIVER	Total/NA	Water	Field Sampling	

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Method: 200.7 Rev 4.4 - Metals (ICP)

Lab Sample ID: MB 500-791762/1-A
Matrix: Water
Analysis Batch: 792031

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 791762

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	<0.0050		0.0050	0.0020	mg/L		10/22/24 09:15	10/23/24 11:54	1

Lab Sample ID: LCS 500-791762/2-A
Matrix: Water
Analysis Batch: 792031

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 791762

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Lithium	0.250	0.258		mg/L		103	85 - 115

Lab Sample ID: MB 500-791763/1-A
Matrix: Water
Analysis Batch: 792033

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 791763

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Lithium	<0.0050		0.0050	0.0020	mg/L		10/22/24 09:18	10/23/24 12:10	1

Lab Sample ID: LCS 500-791763/2-A
Matrix: Water
Analysis Batch: 792033

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 791763

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Lithium	0.250	0.245		mg/L		98	85 - 115

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 500-791759/1-A
Matrix: Water
Analysis Batch: 792125

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 791759

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:07	10/23/24 15:59	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:07	10/23/24 15:59	1
Barium	<0.0025		0.0025	0.00073	mg/L		10/22/24 09:07	10/23/24 15:59	1
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:07	10/23/24 15:59	1
Boron	0.0181	J	0.050	0.013	mg/L		10/22/24 09:07	10/23/24 15:59	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:07	10/23/24 15:59	1
Calcium	<0.20		0.20	0.044	mg/L		10/22/24 09:07	10/23/24 15:59	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:07	10/23/24 15:59	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:07	10/23/24 15:59	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:07	10/23/24 15:59	1
Magnesium	<0.20		0.20	0.049	mg/L		10/22/24 09:07	10/23/24 15:59	1
Molybdenum	<0.0050		0.0050	0.0025	mg/L		10/22/24 09:07	10/23/24 15:59	1
Potassium	<0.50		0.50	0.11	mg/L		10/22/24 09:07	10/23/24 15:59	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:07	10/23/24 15:59	1
Sodium	<0.20		0.20	0.077	mg/L		10/22/24 09:07	10/23/24 15:59	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:07	10/23/24 15:59	1

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 500-791759/2-A
Matrix: Water
Analysis Batch: 792125

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 791759

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Antimony	0.500	0.521		mg/L		104	80 - 120
Arsenic	0.100	0.0997		mg/L		100	80 - 120
Barium	0.500	0.520		mg/L		104	80 - 120
Beryllium	0.0500	0.0510		mg/L		102	80 - 120
Boron	1.00	1.05		mg/L		105	80 - 120
Cadmium	0.0500	0.0518		mg/L		104	80 - 120
Calcium	10.0	8.28		mg/L		83	80 - 120
Chromium	0.200	0.210		mg/L		105	80 - 120
Cobalt	0.500	0.566		mg/L		113	80 - 120
Lead	0.100	0.102		mg/L		102	80 - 120
Magnesium	10.0	10.8		mg/L		108	80 - 120
Molybdenum	1.00	1.02		mg/L		102	80 - 120
Potassium	10.0	10.8		mg/L		108	80 - 120
Selenium	0.100	0.0986		mg/L		99	80 - 120
Sodium	10.0	10.7		mg/L		107	80 - 120
Thallium	0.100	0.105		mg/L		105	80 - 120

Lab Sample ID: MB 500-791760/1-A
Matrix: Water
Analysis Batch: 791955

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 791760

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Antimony	<0.0030		0.0030	0.0013	mg/L		10/22/24 09:09	10/22/24 22:12	1
Arsenic	<0.0010		0.0010	0.00023	mg/L		10/22/24 09:09	10/22/24 22:12	1
Barium	<0.0025		0.0025	0.00073	mg/L		10/22/24 09:09	10/22/24 22:12	1
Calcium	<0.20		0.20	0.044	mg/L		10/22/24 09:09	10/22/24 22:12	1
Chromium	<0.0050		0.0050	0.0011	mg/L		10/22/24 09:09	10/22/24 22:12	1
Lead	<0.00050		0.00050	0.00019	mg/L		10/22/24 09:09	10/22/24 22:12	1
Magnesium	<0.20		0.20	0.049	mg/L		10/22/24 09:09	10/22/24 22:12	1
Molybdenum	<0.0050		0.0050	0.0025	mg/L		10/22/24 09:09	10/22/24 22:12	1
Potassium	<0.50		0.50	0.11	mg/L		10/22/24 09:09	10/22/24 22:12	1
Selenium	<0.0025		0.0025	0.00098	mg/L		10/22/24 09:09	10/22/24 22:12	1
Sodium	<0.20		0.20	0.077	mg/L		10/22/24 09:09	10/22/24 22:12	1

Lab Sample ID: MB 500-791760/1-A
Matrix: Water
Analysis Batch: 792032

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 791760

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Beryllium	<0.0010		0.0010	0.00053	mg/L		10/22/24 09:09	10/23/24 11:34	1
Boron	0.0193	J	0.050	0.013	mg/L		10/22/24 09:09	10/23/24 11:34	1
Cadmium	<0.00050		0.00050	0.00017	mg/L		10/22/24 09:09	10/23/24 11:34	1
Cobalt	<0.0010		0.0010	0.00040	mg/L		10/22/24 09:09	10/23/24 11:34	1
Thallium	<0.0020		0.0020	0.00057	mg/L		10/22/24 09:09	10/23/24 11:34	1

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 500-791760/2-A
Matrix: Water
Analysis Batch: 791955

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 791760

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Antimony	0.500	0.558		mg/L		112	80 - 120
Arsenic	0.100	0.107		mg/L		107	80 - 120
Barium	0.500	0.554		mg/L		111	80 - 120
Calcium	10.0	8.83		mg/L		88	80 - 120
Chromium	0.200	0.220		mg/L		110	80 - 120
Lead	0.100	0.109		mg/L		109	80 - 120
Magnesium	10.0	10.9		mg/L		109	80 - 120
Molybdenum	1.00	1.08		mg/L		108	80 - 120
Potassium	10.0	10.8		mg/L		108	80 - 120
Selenium	0.100	0.107		mg/L		107	80 - 120
Sodium	10.0	10.7		mg/L		107	80 - 120

Lab Sample ID: LCS 500-791760/2-A
Matrix: Water
Analysis Batch: 792032

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 791760

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Beryllium	0.0500	0.0518		mg/L		104	80 - 120
Boron	1.00	1.02		mg/L		102	80 - 120
Cadmium	0.0500	0.0512		mg/L		102	80 - 120
Cobalt	0.500	0.534		mg/L		107	80 - 120
Thallium	0.100	0.102		mg/L		102	80 - 120

Method: 7470A - Mercury (CVAA)

Lab Sample ID: MB 500-791618/12-A
Matrix: Water
Analysis Batch: 791808

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 791618

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/21/24 11:05	10/22/24 08:34	1

Lab Sample ID: LCS 500-791618/13-A
Matrix: Water
Analysis Batch: 791808

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 791618

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Mercury	0.00200	0.00202		mg/L		101	80 - 120

Lab Sample ID: LCSD 500-791618/29-A
Matrix: Water
Analysis Batch: 791808

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA
Prep Batch: 791618

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Mercury	0.00200	0.00202		mg/L		101	80 - 120	0	20

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Method: 7470A - Mercury (CVAA) (Continued)

Lab Sample ID: MB 500-791799/12-A
Matrix: Water
Analysis Batch: 792003

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 791799

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	<0.00020		0.00020	0.000076	mg/L		10/22/24 11:40	10/23/24 09:55	1

Lab Sample ID: LCS 500-791799/13-A
Matrix: Water
Analysis Batch: 792003

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 791799

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Mercury	0.00200	0.00196		mg/L		98	80 - 120

Method: 300.0 - Anions, Ion Chromatography

Lab Sample ID: MB 500-790938/33
Matrix: Water
Analysis Batch: 790938

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	<1.0		1.0	0.12	mg/L			10/16/24 23:57	1
Sulfate	<1.0		1.0	0.21	mg/L			10/16/24 23:57	1

Lab Sample ID: MB 500-790938/65
Matrix: Water
Analysis Batch: 790938

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	<1.0		1.0	0.12	mg/L			10/17/24 08:18	1
Sulfate	<1.0		1.0	0.21	mg/L			10/17/24 08:18	1

Lab Sample ID: LCS 500-790938/34
Matrix: Water
Analysis Batch: 790938

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	20.0	19.2		mg/L		96	90 - 110
Sulfate	20.0	20.6		mg/L		103	90 - 110

Lab Sample ID: LCS 500-790938/66
Matrix: Water
Analysis Batch: 790938

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	20.0	19.2		mg/L		96	90 - 110
Sulfate	20.0	20.6		mg/L		103	90 - 110

Lab Sample ID: MB 500-791383/51
Matrix: Water
Analysis Batch: 791383

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.166	J	1.0	0.12	mg/L			10/19/24 02:34	1
Sulfate	<1.0		1.0	0.21	mg/L			10/19/24 02:34	1

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Method: 300.0 - Anions, Ion Chromatography (Continued)

Lab Sample ID: LCS 500-791383/52
Matrix: Water
Analysis Batch: 791383

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	20.0	19.8		mg/L		99	90 - 110
Sulfate	20.0	20.4		mg/L		102	90 - 110

Lab Sample ID: MB 500-791804/33
Matrix: Water
Analysis Batch: 791804

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.156	J	1.0	0.12	mg/L			10/23/24 06:21	1
Sulfate	<1.0		1.0	0.21	mg/L			10/23/24 06:21	1

Lab Sample ID: LCS 500-791804/34
Matrix: Water
Analysis Batch: 791804

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Chloride	20.0	19.6		mg/L		98	90 - 110
Sulfate	20.0	20.8		mg/L		104	90 - 110

Method: SM 2320B - Alkalinity

Lab Sample ID: MB 500-791737/3
Matrix: Water
Analysis Batch: 791737

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bicarbonate Alkalinity as CaCO3	5.37		5.0	3.7	mg/L			10/21/24 11:05	1
Carbonate Alkalinity as CaCO3	<5.0		5.0	3.7	mg/L			10/21/24 11:05	1

Lab Sample ID: LCS 500-791737/4
Matrix: Water
Analysis Batch: 791737

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Alkalinity	100	102		mg/L		102	80 - 120

Lab Sample ID: MB 500-791946/28
Matrix: Water
Analysis Batch: 791946

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bicarbonate Alkalinity as CaCO3	<5.0		5.0	3.7	mg/L			10/22/24 17:46	1
Carbonate Alkalinity as CaCO3	<5.0		5.0	3.7	mg/L			10/22/24 17:46	1

Lab Sample ID: MB 500-791946/3
Matrix: Water
Analysis Batch: 791946

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bicarbonate Alkalinity as CaCO3	<5.0		5.0	3.7	mg/L			10/22/24 14:05	1

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Method: SM 2320B - Alkalinity (Continued)

Lab Sample ID: MB 500-791946/3
Matrix: Water
Analysis Batch: 791946

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Carbonate Alkalinity as CaCO3	<5.0		5.0	3.7	mg/L			10/22/24 14:05	1

Lab Sample ID: MB 500-791946/53
Matrix: Water
Analysis Batch: 791946

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bicarbonate Alkalinity as CaCO3	<5.0		5.0	3.7	mg/L			10/22/24 21:17	1
Carbonate Alkalinity as CaCO3	<5.0		5.0	3.7	mg/L			10/22/24 21:17	1

Lab Sample ID: LCS 500-791946/29
Matrix: Water
Analysis Batch: 791946

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Alkalinity	100	99.0		mg/L		99	80 - 120

Lab Sample ID: LCS 500-791946/4
Matrix: Water
Analysis Batch: 791946

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Alkalinity	100	97.0		mg/L		97	80 - 120

Lab Sample ID: LCS 500-791946/54
Matrix: Water
Analysis Batch: 791946

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Alkalinity	100	101		mg/L		101	80 - 120

Method: SM 2540C - Solids, Total Dissolved (TDS)

Lab Sample ID: MB 500-790105/1
Matrix: Water
Analysis Batch: 790105

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Dissolved Solids	<10		10	4.3	mg/L			10/11/24 01:23	1

Lab Sample ID: LCS 500-790105/2
Matrix: Water
Analysis Batch: 790105

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Total Dissolved Solids	250	254		mg/L		102	80 - 120

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Method: SM 2540C - Solids, Total Dissolved (TDS) (Continued)

Lab Sample ID: MB 500-790108/1
Matrix: Water
Analysis Batch: 790108

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Dissolved Solids	<10		10	4.3	mg/L			10/11/24 02:54	1

Lab Sample ID: LCS 500-790108/2
Matrix: Water
Analysis Batch: 790108

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Total Dissolved Solids	250	242		mg/L		97	80 - 120

Lab Sample ID: MB 500-790410/1
Matrix: Water
Analysis Batch: 790410

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Dissolved Solids	<10		10	4.3	mg/L			10/13/24 21:49	1

Lab Sample ID: LCS 500-790410/2
Matrix: Water
Analysis Batch: 790410

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Total Dissolved Solids	250	246		mg/L		98	80 - 120

Method: SM 4500 F C - Fluoride

Lab Sample ID: MB 500-790148/3
Matrix: Water
Analysis Batch: 790148

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Fluoride	<0.10		0.10	0.056	mg/L			10/10/24 11:50	1

Lab Sample ID: LCS 500-790148/4
Matrix: Water
Analysis Batch: 790148

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Fluoride	10.0	9.18		mg/L		92	90 - 119

Lab Sample ID: MB 500-791579/31
Matrix: Water
Analysis Batch: 791579

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Fluoride	<0.10		0.10	0.056	mg/L			10/18/24 15:50	1

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Method: SM 4500 F C - Fluoride (Continued)

Lab Sample ID: LCS 500-791579/32				Client Sample ID: Lab Control Sample			
Matrix: Water				Prep Type: Total/NA			
Analysis Batch: 791579							
Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Fluoride	10.0	9.83		mg/L		98	90 - 119

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_08&D

Date Collected: 10/08/24 08:15

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-6

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791762	BDE	EET CHI	10/22/24 09:15 - 10/22/24 15:15 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792031	SJ	EET CHI	10/23/24 12:03
Total Recoverable	Prep	3005A			791759	BDE	EET CHI	10/22/24 09:07 - 10/22/24 15:07 ¹
Total Recoverable	Analysis	6020B		1	792125	RN	EET CHI	10/23/24 16:03
Total/NA	Prep	7470A			791618	MJG	EET CHI	10/21/24 11:05 - 10/21/24 13:05 ¹
Total/NA	Analysis	7470A		1	791808	MJG	EET CHI	10/22/24 08:38
Total/NA	Analysis	300.0		5	790938	MM	EET CHI	10/17/24 00:44
Total/NA	Analysis	300.0		20	791804	W1T	EET CHI	10/23/24 08:42
Total/NA	Analysis	SM 2320B		1	791737	ER	EET CHI	10/21/24 13:21
Total/NA	Analysis	SM 2540C		1	790105	CLB	EET CHI	10/11/24 01:41
Total/NA	Analysis	SM 4500 F C		1	790148	SO	EET CHI	10/10/24 13:30
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/08/24 08:15

Client Sample ID: HEN_12

Date Collected: 10/08/24 09:15

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-7

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791762	BDE	EET CHI	10/22/24 09:15 - 10/22/24 15:15 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792031	SJ	EET CHI	10/23/24 12:08
Total Recoverable	Prep	3005A			791759	BDE	EET CHI	10/22/24 09:07 - 10/22/24 15:07 ¹
Total Recoverable	Analysis	6020B		1	792125	RN	EET CHI	10/23/24 16:06
Total/NA	Prep	7470A			791618	MJG	EET CHI	10/21/24 11:05 - 10/21/24 13:05 ¹
Total/NA	Analysis	7470A		1	791808	MJG	EET CHI	10/22/24 08:40
Total/NA	Analysis	300.0		5	790938	MM	EET CHI	10/17/24 01:47
Total/NA	Analysis	SM 2320B		1	791737	ER	EET CHI	10/21/24 13:31
Total/NA	Analysis	SM 2540C		1	790105	CLB	EET CHI	10/11/24 01:43
Total/NA	Analysis	SM 4500 F C		1	790148	SO	EET CHI	10/10/24 13:34
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/08/24 09:15

Client Sample ID: HEN_13

Date Collected: 10/08/24 08:20

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-8

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791762	BDE	EET CHI	10/22/24 09:15 - 10/22/24 15:15 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792031	SJ	EET CHI	10/23/24 12:12
Total Recoverable	Prep	3005A			791759	BDE	EET CHI	10/22/24 09:07 - 10/22/24 15:07 ¹
Total Recoverable	Analysis	6020B		1	792125	RN	EET CHI	10/23/24 16:08
Total/NA	Prep	7470A			791618	MJG	EET CHI	10/21/24 11:05 - 10/21/24 13:05 ¹
Total/NA	Analysis	7470A		1	791808	MJG	EET CHI	10/22/24 08:42
Total/NA	Analysis	300.0		5	790938	MM	EET CHI	10/17/24 02:18
Total/NA	Analysis	SM 2320B		1	791737	ER	EET CHI	10/21/24 13:40

Eurofins Chicago

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_13

Date Collected: 10/08/24 08:20

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-8

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	SM 2540C		1	790105	CLB	EET CHI	10/11/24 01:46
Total/NA	Analysis	SM 4500 F C		1	790148	SO	EET CHI	10/10/24 13:49
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/08/24 08:20

Client Sample ID: HEN_16

Date Collected: 10/09/24 15:05

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-21

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791762	BDE	EET CHI	10/22/24 09:15 - 10/22/24 15:15 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792031	SJ	EET CHI	10/23/24 13:28
Total Recoverable	Prep	3005A			791759	BDE	EET CHI	10/22/24 09:07 - 10/22/24 15:07 ¹
Total Recoverable	Analysis	6020B		1	792125	RN	EET CHI	10/23/24 17:12
Total/NA	Prep	7470A			791799	MJG	EET CHI	10/22/24 11:40 - 10/22/24 13:40 ¹
Total/NA	Analysis	7470A		1	792003	MJG	EET CHI	10/23/24 10:07
Total/NA	Analysis	300.0		5	790938	MM	EET CHI	10/17/24 14:03
Total/NA	Analysis	SM 2320B		1	791946	ER	EET CHI	10/22/24 16:39
Total/NA	Analysis	SM 2540C		1	790108	CLB	EET CHI	10/11/24 03:14
Total/NA	Analysis	SM 4500 F C		1	791579	SO	EET CHI	10/18/24 16:15
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/09/24 15:05

Client Sample ID: HEN_16_FD

Date Collected: 10/09/24 15:20

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-22

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791762	BDE	EET CHI	10/22/24 09:15 - 10/22/24 15:15 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792031	SJ	EET CHI	10/23/24 13:41
Total Recoverable	Prep	3005A			791759	BDE	EET CHI	10/22/24 09:07 - 10/22/24 15:07 ¹
Total Recoverable	Analysis	6020B		1	792125	RN	EET CHI	10/23/24 17:14
Total/NA	Prep	7470A			791799	MJG	EET CHI	10/22/24 11:40 - 10/22/24 13:40 ¹
Total/NA	Analysis	7470A		1	792003	MJG	EET CHI	10/23/24 10:10
Total/NA	Analysis	300.0		5	790938	MM	EET CHI	10/17/24 14:19
Total/NA	Analysis	SM 2320B		1	791946	ER	EET CHI	10/22/24 16:48
Total/NA	Analysis	SM 2540C		1	790108	CLB	EET CHI	10/11/24 03:17
Total/NA	Analysis	SM 4500 F C		1	791579	SO	EET CHI	10/18/24 16:31
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/09/24 15:20

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_17

Date Collected: 10/09/24 14:10

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-23

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791762	BDE	EET CHI	10/22/24 09:15 - 10/22/24 15:15 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792031	SJ	EET CHI	10/23/24 13:46
Total Recoverable	Prep	3005A			791759	BDE	EET CHI	10/22/24 09:07 - 10/22/24 15:07 ¹
Total Recoverable	Analysis	6020B		1	792125	RN	EET CHI	10/23/24 17:17
Total/NA	Prep	7470A			791799	MJG	EET CHI	10/22/24 11:40 - 10/22/24 13:40 ¹
Total/NA	Analysis	7470A		1	792003	MJG	EET CHI	10/23/24 10:12
Total/NA	Analysis	300.0		5	790938	MM	EET CHI	10/17/24 14:34
Total/NA	Analysis	SM 2320B		1	791946	ER	EET CHI	10/22/24 16:57
Total/NA	Analysis	SM 2540C		1	790108	CLB	EET CHI	10/11/24 03:19
Total/NA	Analysis	SM 4500 F C		1	791579	SO	EET CHI	10/18/24 16:35
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/09/24 14:10

Client Sample ID: HEN_46

Date Collected: 10/09/24 11:30

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-28

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791763	BDE	EET CHI	10/22/24 09:18 - 10/22/24 15:18 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792033	SJ	EET CHI	10/23/24 12:19
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	791955	RN	EET CHI	10/22/24 22:17
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	792032	RN	EET CHI	10/23/24 11:38
Total/NA	Prep	7470A			791799	MJG	EET CHI	10/22/24 11:40 - 10/22/24 13:40 ¹
Total/NA	Analysis	7470A		1	792003	MJG	EET CHI	10/23/24 10:22
Total/NA	Analysis	300.0		5	791804	W1T	EET CHI	10/23/24 09:13
Total/NA	Analysis	SM 2320B		1	791946	ER	EET CHI	10/22/24 18:07
Total/NA	Analysis	SM 2540C		1	790108	CLB	EET CHI	10/11/24 03:32
Total/NA	Analysis	SM 4500 F C		1	791579	SO	EET CHI	10/18/24 16:58
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/09/24 11:30

Client Sample ID: HEN_47

Date Collected: 10/09/24 12:40

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-29

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791763	BDE	EET CHI	10/22/24 09:18 - 10/22/24 15:18 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792033	SJ	EET CHI	10/23/24 12:24
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	791955	RN	EET CHI	10/22/24 22:20
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	792032	RN	EET CHI	10/23/24 11:41
Total/NA	Prep	7470A			791799	MJG	EET CHI	10/22/24 11:40 - 10/22/24 13:40 ¹
Total/NA	Analysis	7470A		1	792003	MJG	EET CHI	10/23/24 10:25

Eurofins Chicago

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_47

Date Collected: 10/09/24 12:40

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-29

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	300.0		5	791804	W1T	EET CHI	10/23/24 09:28
Total/NA	Analysis	SM 2320B		1	791946	ER	EET CHI	10/22/24 18:16
Total/NA	Analysis	SM 2540C		1	790108	CLB	EET CHI	10/11/24 03:35
Total/NA	Analysis	SM 4500 F C		1	791579	SO	EET CHI	10/18/24 17:30
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/09/24 12:40

Client Sample ID: HEN_07

Date Collected: 10/10/24 09:20

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-33

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791763	BDE	EET CHI	10/22/24 09:18 - 10/22/24 15:18 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792033	SJ	EET CHI	10/23/24 13:09
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	791955	RN	EET CHI	10/22/24 22:45
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	792032	RN	EET CHI	10/23/24 12:09
Total/NA	Prep	7470A			791799	MJG	EET CHI	10/22/24 11:40 - 10/22/24 13:40 ¹
Total/NA	Analysis	7470A		1	792003	MJG	EET CHI	10/23/24 10:44
Total/NA	Analysis	300.0		5	791383	MB	EET CHI	10/19/24 07:15
Total/NA	Analysis	SM 2320B		1	791946	ER	EET CHI	10/22/24 22:30
Total/NA	Analysis	SM 2540C		1	790108	CLB	EET CHI	10/11/24 03:53
Total/NA	Analysis	SM 4500 F C		1	791579	SO	EET CHI	10/18/24 17:44
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/10/24 09:20

Client Sample ID: HEN_08

Date Collected: 10/10/24 09:20

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-34

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791763	BDE	EET CHI	10/22/24 09:18 - 10/22/24 15:18 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792033	SJ	EET CHI	10/23/24 13:13
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	791955	RN	EET CHI	10/22/24 22:47
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	792032	RN	EET CHI	10/23/24 12:12
Total/NA	Prep	7470A			791799	MJG	EET CHI	10/22/24 11:40 - 10/22/24 13:40 ¹
Total/NA	Analysis	7470A		1	792003	MJG	EET CHI	10/23/24 10:46
Total/NA	Analysis	300.0		5	791383	MB	EET CHI	10/19/24 07:47
Total/NA	Analysis	300.0		20	791804	W1T	EET CHI	10/23/24 12:36
Total/NA	Analysis	SM 2320B		1	791946	ER	EET CHI	10/22/24 22:40
Total/NA	Analysis	SM 2540C		1	790410	CLB	EET CHI	10/13/24 22:14
Total/NA	Analysis	SM 4500 F C		1	791579	SO	EET CHI	10/18/24 17:48

Eurofins Chicago

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_08

Date Collected: 10/10/24 09:20

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-34

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/10/24 09:20

Client Sample ID: HEN_52

Date Collected: 10/10/24 08:10

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-35

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791763	BDE	EET CHI	10/22/24 09:18 - 10/22/24 15:18 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792033	SJ	EET CHI	10/23/24 13:18
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	791955	RN	EET CHI	10/22/24 22:50
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	792032	RN	EET CHI	10/23/24 12:14
Total/NA	Prep	7470A			791799	MJG	EET CHI	10/22/24 11:40 - 10/22/24 13:40 ¹
Total/NA	Analysis	7470A		1	792003	MJG	EET CHI	10/23/24 10:48
Total/NA	Analysis	300.0		5	791383	MB	EET CHI	10/19/24 08:02
Total/NA	Analysis	SM 2320B		1	791946	ER	EET CHI	10/22/24 22:50
Total/NA	Analysis	SM 2540C		1	790410	CLB	EET CHI	10/13/24 22:17
Total/NA	Analysis	SM 4500 F C		1	791579	SO	EET CHI	10/18/24 17:53
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/10/24 08:10

Client Sample ID: HEN_54

Date Collected: 10/10/24 08:15

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-36

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791763	BDE	EET CHI	10/22/24 09:18 - 10/22/24 15:18 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792033	SJ	EET CHI	10/23/24 13:22
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	791955	RN	EET CHI	10/22/24 22:52
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	792032	RN	EET CHI	10/23/24 12:16
Total/NA	Prep	7470A			791799	MJG	EET CHI	10/22/24 11:40 - 10/22/24 13:40 ¹
Total/NA	Analysis	7470A		1	792003	MJG	EET CHI	10/23/24 10:50
Total/NA	Analysis	300.0		5	791383	MB	EET CHI	10/19/24 08:18
Total/NA	Analysis	SM 2320B		1	791946	ER	EET CHI	10/22/24 23:00
Total/NA	Analysis	SM 2540C		1	790410	CLB	EET CHI	10/13/24 22:20
Total/NA	Analysis	SM 4500 F C		1	791579	SO	EET CHI	10/18/24 17:58
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/10/24 08:15

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Client Sample ID: HEN_54_FD

Date Collected: 10/10/24 08:25

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-37

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	200.7			791763	BDE	EET CHI	10/22/24 09:18 - 10/22/24 15:18 ¹
Total Recoverable	Analysis	200.7 Rev 4.4		1	792033	SJ	EET CHI	10/23/24 13:27
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	791955	RN	EET CHI	10/22/24 22:55
Total Recoverable	Prep	3005A			791760	BDE	EET CHI	10/22/24 09:09 - 10/22/24 15:09 ¹
Total Recoverable	Analysis	6020B		1	792032	RN	EET CHI	10/23/24 12:19
Total/NA	Prep	7470A			791799	MJG	EET CHI	10/22/24 11:40 - 10/22/24 13:40 ¹
Total/NA	Analysis	7470A		1	792003	MJG	EET CHI	10/23/24 10:52
Total/NA	Analysis	300.0		5	791383	MB	EET CHI	10/19/24 08:34
Total/NA	Analysis	SM 2320B		1	791946	ER	EET CHI	10/22/24 23:09
Total/NA	Analysis	SM 2540C		1	790410	CLB	EET CHI	10/13/24 22:22
Total/NA	Analysis	SM 4500 F C		1	791579	SO	EET CHI	10/18/24 18:03
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/10/24 08:25

Client Sample ID: HEN_55

Date Collected: 10/07/24 11:57

Date Received: 10/08/24 11:17

Lab Sample ID: 500-258038-39

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/07/24 11:57

Client Sample ID: HEN_XSG01

Date Collected: 10/07/24 11:32

Date Received: 10/08/24 11:17

Lab Sample ID: 500-258038-40

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/07/24 11:32

Client Sample ID: HEN_SG02_YSG_ILRIVER

Date Collected: 10/07/24 10:25

Date Received: 10/08/24 11:17

Lab Sample ID: 500-258038-41

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	Field Sampling		1	791677	DN	EET CHI	10/07/24 10:25

¹ This procedure uses a method stipulated length of time for the process. Both start and end times are displayed.

Laboratory References:

EET CHI = Eurofins Chicago, 2417 Bond Street, University Park, IL 60484, TEL (708)534-5200

Accreditation/Certification Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
15 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-10
SDG: HEN_845_803

Laboratory: Eurofins Chicago

Unless otherwise noted, all analytes for this laboratory were covered under each accreditation/certification below.

Authority	Program	Identification Number	Expiration Date
Illinois	NELAP	IL00035	05-31-25
The following analytes are included in this report, but the laboratory is not certified by the governing authority. This list may include analytes for which the agency does not offer certification.			
Analysis Method	Prep Method	Matrix	Analyte
200.7 Rev 4.4	200.7	Water	Lithium
Field Sampling		Water	Depth to Water (ft from MP)
Field Sampling		Water	Field pH
Field Sampling		Water	Field Temperature
Field Sampling		Water	Groundwater Elevation
Field Sampling		Water	Oxidation Reduction Potential
Field Sampling		Water	Oxygen, Dissolved
Field Sampling		Water	Specific Conductance
Field Sampling		Water	Turbidity
SM 2320B		Water	Bicarbonate Alkalinity as CaCO3
SM 2320B		Water	Carbonate Alkalinity as CaCO3

Temp in °C	Received on	Custody Sealed	Cooler (Y/N)	Samples Intact (Y/N)	-548-N1

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:	
Company:	Vistra Corp-Hennepin	Report To:	Brian Voelker	Attention:	Brian Voelker
Address:	13498 E 800th St Hennepin, IL 61327	Copy To:	Sam Davies samantha.davies@vistracorp.com	Company Name:	Vistra Corp
Email To:	Brian.Voelker@VistraCorp.com	Purchase Order No.:	Jason Stuckey & Michael Oille	Address:	see Section A
Phone:	(217) 753-8911	Project Name:	Jason.Stuckey@vistracorp.com	Quote Reference:	
Fax:		Requested Due Date/TAT:	10 day	Project Manager:	
		Project Number:	50023030	Profile #:	

ITEM #	Section D Required Client Information	Valid Matrix Codes MATRIX CODE DRINKING WATER WASTE WATER WASTE WATER PRODUCT SOLIDS OIL WIPE AIR OTHER TISSUE SAMPLE ID (A-Z, 0-9 / -) Sample IDs MUST BE UNIQUE	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives										Analysis Test	Y/N	Requested Analysis Filtered (Y/N)										Project No./ Lab I.D.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
					DATE	TIME			Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other	HEN-000-RAD	HEN-257-802			HEN-257-803	HEN-257-804	HEN-811-801	HEN-845-802-805	HEN-845-803	HEN-845-804	HEN-WPCP-East	HEN-WPCP-West	HEN_000	Residual Chlorine (Y/N)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
1		HEN_52																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							</

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS
HEN-24Q4 Rev 0	Sam Davies	10/17/24	0700	Sam Davies	10/18/24	0917	
	Sam Davies	10/18/24	1117	Sam Davies	10/18/24	1117	

SAMPLER NAME AND SIGNATURE		DATE SIGNED (MM/DD/YY)
PRINT Name of SAMPLER		
SIGNATURE of SAMPLER		

Sample date and default time added - dbn 102824



The Chain-of-Custody is a LEGAL DOCUMENT All relevant fields must be completed accurately

HENNEPIN POWER PLANT, EAST ASH POND

Page 1 of 3

REGULATORY AGENCY		
NPDES	GROUND WATER	DRINKING WATER
UST	RCRA	OTHER
Site Location STATE	IL	

1.6 → 1.5, 3.6 → 3.5, 3.3 → 3.2
4.3 → 4.2, 3.9 → 3.8

10/30/24

The Chain-of-Custody is a LEGAL DOCUMENT All relevant fields must be completed accurately

Page 3 of 3

[illegible]

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed (Y/N) Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER <i>Lorne Filawicz</i>					
SIGNATURE of SAMPLER <i>Lorne Filawicz</i>	DATE Signed (MM/DD/YY) <i>10-8-24</i>				

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information

Company: Visira Corp-Hennepin
Address: 13498 E 800th St
Hennepin, IL 61327
Email To: Brian.Voelker@VisiraCorp.com
Phone: (217) 753-8911 Fax: _____
Requested Due Date/TAT: 10 day

Section B Required Project Information

Report To: Brian Voelker
Copy To: Sam Davies samantha.davies@visiracorp.com
Jason Stuckey & Michael Olle
Purchase Order No.: michael.olle@visiracorp.com
Project Name: Jason.Stuckey@visiracorp.com
Project Number: 50023030

Section C Invoice Information

Attention: Brian Voelker
Company Name: Visira Corp
Address: see Section A
Quote Reference: _____
Project Manager: _____
Profile #: _____

Page 1 of 3

REGULATORY AGENCY
NPDES: _____ GROUND WATER: _____ DRINKING WATER: _____
UST: _____ RCRA: _____ OTHER: _____
Site Location: _____ IL: _____
STATE: _____



500-258038 COC

Project No./ Lab I.D.

ITEM #	Section D Required Client Information	Valid Matrix Codes MATRIX CODE DRINKING WATER DW WATER WT WASTE WATER WW PRODUCT P SOIL/SOLID SL OIL OL WIPE WP AIR AR OTHER OT TISSUE TS	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives										Analysis Test ↓	Requested Analysis Filtered (Y/N)										Residual Chlorine (Y/N)	Project No./ Lab I.D.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
					DATE	TIME			Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
1	HEN_02																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							</

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS			
HEN-24Q4 Rev 0	<i>Donna F. Lewis</i>	10/10/24	0800	<i>N.J. Elia</i>	10/10/24	0900				
	<i>N.J. Elia</i>	10/10/24	1110	<i>Stephanie Hemondy EETA</i>	10/10/24	1110				
SAMPLER NAME AND SIGNATURE							Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER <i>Donna F. Lewis</i>										
SIGNATURE of SAMPLER <i>Donna F. Lewis</i>							DATE Signed (MM/DD/YY) <i>10/10/24</i>			

5.0+4.9, 5.3+5.2, 5.4+5.3, 4.1+4.0
5.1+5.0

The Chain-of-Custody is a LEGAL DOCUMENT All relevant fields must be completed accurately

Page 2 of 3

ITEM #	Section D Required Client Information SAMPLE ID (A-Z, 0-9 / -) Sample IDs MUST BE UNIQUE	Valid Matrix Codes MATRIX CODE DRINKING WATER DW WATER WT WASTE WATER WW PRODUCT P SOIL/SOLID SL OIL OL WIPE WP AIR AR OTHER OT TISSUE TS	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C-COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives								Y/N Analysis Test ↑ HEN-000-RAD HEN-257-802 HEN-257-803 HEN-257-804 HEN-811-801 HEN-845-802-805 HEN-845-803 HEN-845-804 HEN-WPCP-East HEN-WPCP-West HEN_000	Requested Analysis Filtered (Y/N)							
					DATE	TIME			Unpreserved	H_2SO_4	HNO_3	HCl	NaOH	$Na_2S_2O_3$	Methanol	Other									
ADDITIONAL COMMENTS			RELINQUISHED BY / AFFILIATION			DATE	TIME	ACCEPTED BY / AFFILIATION			DATE	TIME	SAMPLE CONDITIONS												
1	HEN_21R				10-9-24	1425						X			X		X	H	MS/MSD						
2	HEN_22				10-9-24	1350						X			X		X	H							
3	HEN_22&D				10-9-24	1015						X			X		X	H							
4	HEN_23				10-9-24	1015						X			X		X	H							
5	HEN_27											X			X		X	H							
6	HEN_32											X			X		X	H							
7	HEN_34											X			X		X	H							
8	HEN_35											X			X		X	H							
9	HEN_35-FD											X			X		X	H							
10	HEN_40#S														X		E	SHORT HOLD - NO2							
11	HEN_45#S				10-9-24	0900						X	X			X	B	SHORT HOLD - NO2							
12	HEN_46				10-9-24	1130						X		X			G								
13	HEN_47				10-9-24	1240						X		X			G								
14	HEN_49				10-9-24	1105						X		X		X	H	MS/MSD							
15	HEN_50				10-9-24	1305						X		X		X	H								
16	HEN_51				10-9-24	0905						X		X		X	H								
ADDITIONAL COMMENTS			RELINQUISHED BY / AFFILIATION			DATE	TIME	ACCEPTED BY / AFFILIATION			DATE	TIME	SAMPLE CONDITIONS												
HEN-24Q4 Rev 0			Lorne F. Lewis			10/10/24	0900	N.J. Ellison			10/10/24	0900													
			Stephanie Hemminger			10/10/24	1110	Stephanie Hemminger			10/10/24	1110													
SAMPLER NAME AND SIGNATURE																									
PRINT Name of SAMPLER										Lorne F. Lewis															
SIGNATURE of SAMPLER:										Stephanie Hemminger															
										DATE Signed (MM/DD/YY) 10-10-24															
										Temp in °C															
										Received on Ice (Y/N)															
										Custody Sealed Cooler (Y/N)															
										Samples Intact (Y/N)															

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page 3 of 3

STATE

10/30/24

500-258038

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately

Section A
Required Client Information

Company: Visira Corp-Hennepin

Address: 13498 E 800th St

Hennepin, IL 61327

Email To: Brian.Voelker@VisiraCorp.com

Phone: (217) 753-8911 Fax: _____

Requested Due Date/TAT: 10 day

Section B
Report To: Brian Voelker

Copy To: Sam Davies samantha.davies@visiracorp.com

Address: see Section A

Purchase Order No. michael.olle@visiracorp.com

Project Name: Jason.Stuckey@visiracorp.com

Project Number: 50023030

Section C
Invoice Information.

Attention: Brian Voelker

Company Name: Visira Corp

Address: see Section A

Quote Reference: _____

Project Manager: _____

Profile #: _____

Section D Required Client Information		Valid Matrix Codes MATRIX CODE DRINKING WATER DW WATER WTL WASTEWATER WTW PRODUCT P SOIL/SOLID SL OIL OL WIPE WP AIR AR OTHER OT TISSUE TS		MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		# OF CONTAINERS	Preservatives										Analysis Test ↓ Y/N ↑	Requested Analysis Filtered (Y/N)										Project No./ Lab I.D.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
						DATE	TIME		SAMPLE TEMP AT COLLECTION	Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ SO ₃	Methanol	Other	HEN-000-RAD		HEN-257-802	HEN-257-803	HEN-257-804	HEN-811-801	HEN-845-802-805	HEN-845-803	HEN-845-804	HEN-WPCP-East	HEN-WPCP-West	HEN_000		Residual Chlorine (Y/N)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
ITEM #																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													</

RELINQUISHED BY: James Kelly DATE: 10/10/24 TIME: 12:46

ADDITIONAL COMMENTS: HEN-24Q4 Rev 0

DATE SIGNED: 10/10/24 TIME SIGNED: 12:46

PRINT Name of SAMPLER: James Kelly

SIGNATURE of SAMPLER: [Signature]

DATE SIGNED: 10/10/24 TIME SIGNED: 12:46

PRINT Name of ANALYST: James Kelly

SIGNATURE of ANALYST: [Signature]

DATE SIGNED: 10/10/24 TIME SIGNED: 12:46

PRINT Name of CLIENT: Visira Corp

SIGNATURE of CLIENT: [Signature]

DATE SIGNED: 10/10/24 TIME SIGNED: 12:46

PRINT Name of PROJECT: 50023030

SIGNATURE of PROJECT: [Signature]

DATE SIGNED: 10/10/24 TIME SIGNED: 12:46

PRINT Name of LOCATION: Hen 845-803

SIGNATURE of LOCATION: [Signature]

DATE SIGNED: 10/10/24 TIME SIGNED: 12:46

Login Sample Receipt Checklist

Client: Vistra Energy Corp

Job Number: 500-258038-10

SDG Number: HEN_845_803

Login Number: 258038

List Number: 1

Creator: Hernandez, Stephanie

List Source: Eurofins Chicago

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	Received same day of collection; chilling process has begun.(33-38 sampled 10/10)
Cooler Temperature is recorded.	True	1.5,1.5,3.5,3.2,4.2,3.8,4.9,5.2,5.3,4.0,5.0,13.8,5.9
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	False	No sample date and/or time on COC, logged in per container labels.
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	False	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	False	No date or time on COC, logged in per container labels.
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

SAR-3: Plant Sampling and Analysis Request

Event: HEN-24Q4

Date Generated: 09/12/2024

All episodic water levels on SAR-3 and SAR-4 must be collected within a 24 hour period.

Well	Unique ID	Date	Time	Measured Depth to Water (ft bmp)	Comments	Initials
02	HEN_02	10/7	1256	45.82	DTB 51.32	
04R	HEN_04R	10/7	1111	40.42	DTB 45.32	
05DR	HEN_05&DR	10/7	1102	42.27	71.24	
05R	HEN_05!R	10/7	1107	42.22	49.68 DTB	
06	HEN_06	10/7	1048	23.44	33.27	
10	HEN_10	10/7	1204	Dry	51.49 DTB	
11	HEN_11	10/7	1206	61.94	69.55 DTB	
15	HEN_15	10/7	1139	50.33	DTB 52.83	
19#SR	HEN_19#SR	10/7	1122	38.47	DTB 51.58	
19D	HEN_19&D	10/7	1125	40.94	DTB 45.47	
25	HEN_25	10/7	0825	16.65	17.88	
26	HEN_26	10/7	0820	16.84	27.32	
30	HEN_30	10/7	1430	6.97	34.72	
31	HEN_31	10/7	1433	7.23	10.02	
33	HEN_33	10/7	1012	4.21	38.22	
36	HEN_36	10/7	0830	16.09	DTB 28.86	
40S	HEN_40#S	10/7	1118	41.43	DTB 42.91	
45S	HEN_45#S	10/7	4114 16:03	21.20	DTB 38.62	
48R	HEN_48R	10/7	1115	41.72	57.15	
53	HEN_53	10/7	1215	56.52	DTB 66.68	
SG02	HEN_YSG_ILRIVER	10/7	1025	No water	at reading point	
XPW01	HEN_XPW01_pore	10/7	1220	12.24	DTB 14.68	
XPW02	HEN_XPW02_pore	10/7	1225	17.42	DTB 21.75	
XPW03	HEN_XPW03_pore	10/7	1159	7.72	DTB 21.95	

No data points

Elevation = 441.0 ft
dbn 102824

C: 9/12/24 JRK

O = Combined count.

SAR-4: Plant Sampling and Analysis Request
Event: HEN-24Q4
Date Generated: 09/12/2024

All episodic water levels on SAR-3 and SAR-4 must be collected within a 24 hour period.

Well	Unique ID	Date	Time	Measured Depth to Water (ft bmp)	Serial Number	Does Data Match?	WL Reading on Transducer (ft)	Data download	Batt CH/M/L/R	Comments	Initials
03R	HEN_03R	10/17	1052	36.01	21615140	YES	446.2183	YES	High	ANT Ned	
07	HEN_07	10/17	1324	69.10	21615139	YES	449.3102	YES	High		
08	HEN_08	10/17	1231	54.71	21615138	YES	446.8147	YES	High		
08D	HEN_08&D 10/17	10/17	1051	122.55.12	21921673	YES	446.352	YES	High	Dr	
12	HEN_12	10/17	1151	Dr	21615520	YES	446.4333	YES	High		
13	HEN_13	10/17	1153	52.22	21615515	YES	442.1015	YES	High		
16	HEN_16	10/17	1239	55.28	21615534	YES	446.2722	YES	High		
17	HEN_17	10/17	1130	56.83	21615500	YES	445.3572	YES	High	Battery replaced	
18D	HEN_18&D	10/17	1051	41.99	21615609	YES	440.4641	YES	High		
18S	HEN_18WS	10/17	1059	41.63	21615482	YES	445.472	YES	High		
21R	HEN_21R	10/17	0944	60.72	21615613	YES	445.52	YES	High		
22	HEN_22	10/17	1017	19.13	21615497	YES	445.7222	YES	High		
22D	HEN_22&D	10/17	1014	20.04	21564134	YES	446.972	YES	Med		
23	HEN_23	10/17	1026	17.62	21615600	YES	446.1040	YES	Med	Battery replaced	
27	HEN_27	10/17	1442	4.82	21615576	YES	446.1040	YES	Med		
32	HEN_32	10/17	1006	17.62	21615487	YES	446.1247	YES	High		
34	HEN_34	10/17	1027	30.20	No transducer		446.2207	YES	High		
35	HEN_35	10/17	0827	9.03	21615510	YES	446.34	YES	High		
46	HEN_46	10/17	1141	52.72	21615491	YES	446.0156	YES	High		
47	HEN_47	10/17	1208	56.71	21615505	YES	446.397	YES	High		
49	HEN_49	10/17	1011	22.35	21629307	YES	445.5178	YES	High	Battery replaced	
50	HEN_50	10/17	1021	18.99	21615489	YES	446.2062	YES	High		
51	HEN_51	10/17	1001	19.45	21615608	YES	446.397	YES	High		
52	HEN_52	10/17	1212	54.37	21615145	YES	446.397	YES	High		
54	HEN_54	10/17	1208	54.14	21615143	YES	446.397	YES	High		
55	HEN_55	10/17	1157	52.32	21615612	YES	446.397	YES	High		
5G03	HEN_5SG03	10/17	1157	27.9	21768088	YES	446.397	YES	High	No water	
XSG01	HEN_XSG01	10/17	1152	105.5	21768087	YES	446.397	YES	High	Batt. replaced	
RG01	HEN_RG01	10/17	1152	105.5	21628684	YES	446.397	YES	High		

C: 9/12/24 JRK

Hen 10
1555

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: <u>Hennepin</u>		Client: <u>Visra</u>										
Project Number: <u>0054</u>		Task #: _____		Start Date: <u>10/7/2024</u>		Time: <u>1545</u>						
Field Personnel: <u>Corne</u>		Finish Date: <u>Same</u>		Time: <u>1615</u>								
WELL INFORMATION				EVENT TYPE								
Well ID: <u>02</u>		Well Development		Low-Flow / Low Stress Sampling Other								
Casing ID: <u>2</u>		Well Volume Approach Sampling		(Specify): Low Flow								
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	<u>1545</u>		<u>44.82</u>								
Purge	5	<u>1555</u>		<u>44.89</u>		<u>13.1</u>	<u>6.93</u>	<u>716</u>	<u>7.54</u>	<u>41.92</u>	<u>118.0</u>	
	10	<u>1600</u>		<u>44.92</u>		<u>13.0</u>	<u>6.93</u>	<u>715</u>	<u>7.39</u>	<u>42.01</u>	<u>119.0</u>	
	15	<u>1605</u>		<u>44.92</u>		<u>12.9</u>	<u>6.93</u>	<u>713</u>	<u>7.38</u>	<u>43.09</u>	<u>120.6</u>	
*****	20	<u>1610</u>		<u>44.94</u>		<u>12.8</u>	<u>6.92</u>	<u>710</u>	<u>7.37</u>	<u>42.90</u>	<u>122.8</u>	
	25	<u>1615</u>	<u>46.0</u>	<u>44.95</u>				<u>708</u>	<u>7.37</u>	<u>42.02</u>	<u>125.0</u>	
	30											
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)										ABBREVIATIONS		
Sample ID: <u>02</u> Sampled @ <u>1615</u> on <u>10/7/24</u>										Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured		
										ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius		

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra		Task #: 0935								
Project Number: 0054		Start Date: 10/19/2024		Time: 1015								
Field Personnel: Larne		Finish Date: Same		Time: 1015								
WELL INFORMATION												
Well ID: 052		Well Development		Well Volume Approach Sampling		EVENT TYPE						
Casing ID: 2		Well Volume		Well Volume		Low-Flow / Low Stress Sampling Other YSI SERIAL NO: 24A 1012260 Heron Serial NO: 12DF 245316348						
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0935		35.82								
Purge	5	0940		35.95		17.8	7.15	732	2.66	29.05	84.9	Clear
	10	0945		35.85		17.7	7.14	732	1.87	9.71	86.3	
	15	0950		35.85		17.9	7.13	728	1.56	9.42	85.7	
*****	20	0955		35.95		17.8	7.12	725	1.66	9.40	83.9	
	25	1000		35.95		17.8	7.12	728	1.59	8.93	83.1	
	30	1005		35.85		17.9	7.11	729	1.50	7.21	81.9	
	35	1015	464	35.95		17.8	7.11	730	1.45	7.01	80.7	V
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: 052												
Sampled @ 1015 on 10/19/24												
Dupe @ 1030												
ABBREVIATIONS												
Cond - Actual Conductivity Temp - Temperature nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC Units Temp - Temperature °C - Degrees Celsius												



WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION

Site: Hennepin Client: Vistra
Project Number: 6054 Task #: 10/8/2024 Time: 0955
Field Personnel: Lorne Finish Date: Same Time:

WELL INFORMATION

Well ID: OSR
Casing ID: 2 (Inches)

EVENT TYPE

Well Development
Well Volume Approach Sampling

Low-Flow / Low Stress Sampling Other
(Specify): Low Flow

YSI SERIAL NO: 24A1501216
Heron Serial NO: 7DF 2403163 HB

WATER QUALITY INDICATOR PARAMETERS (continued)

Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0955		42.20								Clear
Purge	5	1000		42.20		17.7	7.40	737	3.60	12.70	36.1	
	10	1005		42.20		17.8	7.35	727	2.10	9.30	2.0	
	15	1015		42.20		17.8	7.35	727	2.01	7.04	13.2	
*****	20	1020		42.20		17.9	7.35	727	1.91	7.34	14.3	
	25	1025		42.20		17.9	7.34	727	1.86	6.88	16.8	
	30	1030		42.20		18.0	7.29	727	1.79	5.98	16.9	
	35											
	40											
	45											
	50											
	55											
	60											

NOTES (continued)

Sample ID: OSR
Sampled @ 1030 on 10/18/24

ABBREVIATIONS

Cond - Actual Conductivity
FT BTOC - Feet Below Top of Casing na -
Not Applicable
nm - Not Measured
ORP - Oxidation-Reduction Potential SEC -
Specific Electrical Conductance SU - Standard
Units
Temp - Temperature
°C - Degrees Celsius

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION

Site: Hennepin Client: Visita Start Date: 10/8/2024 Time: 0900
Project Number: 05R Task #: _____
Field Personnel: Corne Finish Date: Same Time: 0930

WELL INFORMATION

Well ID: 05D Well Development Well Volume Approach Sampling Low-Flow / Low Stress Sampling Other YSI SERIAL NO: 24A101226
Casing ID: 2 (Inches) Heron Serial NO: 12DF2403163 HB

EVENT TYPE

WATER QUALITY INDICATOR PARAMETERS (continued)

Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0905		42.19								
Purge	5	0910		42.19		17.0	7.57	738	1.73	63.91	93.0	clear
	10	0915		42.19		17.0	7.56	738	1.59	59.00	91.4	
	15	0920		42.19		17.1	7.56	738	1.84	30.10	88.8	
*****	20	0925		42.19		17.2	7.56	738	1.99	30.21	87.9	
	25	0930	36ml	42.19		17.2	7.56	738	2.03	31.01	87.6	↓
	30											
	35											
	40											
	45											
	50											
	55											
	60											

NOTES (continued)

Sample ID: 05D
Sampled @ 0930 on 10/8/24

ABBREVIATIONS

Cond - Actual Conductivity
FT BTOC - Feet Below Top of Casing no -
Not Applicable
nm - Not Measured
ORP - Oxidation-Reduction Potential SEC
Specific Electrical Conductance SU - Standard
Units
Temp - Temperature
°C - Degrees Celsius

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra		Start Date: 10/10/2024		Time: 0845						
Project Number: 0054		Task #:		Finish Date: 10/10/2024		Time: 0940						
Field Personnel: G. Arany												
WELL INFORMATION				EVENT TYPE								
Well ID: 1		Inches		Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow				
Casing ID:		YSI SERIAL NO: Heron Serial NO:										
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0850	—	69.07	—	—	—	—	—	—	—	—
Purge	5	0855	0.5	69.02	—	11.5	6.83	1145	5.96	9.84	102.5	12av
	10	0900	1	69.02	—	11.4	6.79	1150	5.74	5.78	108.6	↓
	15	0905	2	69.02	—	11.4	6.78	1147	5.61	2.44	111.7	↓
*****	20	0910	2.5	69.03	—	11.5	6.70	1143	5.66	1.83	111.9	↓
↓	25	0915	3	69.06	—	11.5	6.79	1144	5.60	5.70	112.7	↓
Sande	30	0920	4	—	—	—	—	—	—	—	—	—
	35	0925	—	—	—	—	—	—	—	—	—	—
Final	40	0930	5	69.07	—	—	—	—	—	—	—	—
	45	0935	—	—	—	—	—	—	—	—	—	—
	50	—	—	—	—	—	—	—	—	—	—	—
	55	—	—	—	—	—	—	—	—	—	—	—
	60	—	—	—	—	—	—	—	—	—	—	—
NOTES (continued)				ABBREVIATIONS								
Sample ID: Hen-7 Sampled @ 0920 on 10/10/2024				Cond - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured								
				ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degree Celsius								

Hen 7
10/10/2024
@ 0920

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION															
Site: <u>Hennepin</u>	Client: <u>Vistra</u>	Task #: <u>0054</u>	Start Date: <u>10/10/2024</u>	Time: <u>0855</u>											
Field Personnel: <u>Same</u>	Finish Date: <u>Same</u>	Time: <u>0920</u>													
WELL INFORMATION			EVENT TYPE												
Well ID: <u>08</u>	Well Development	Well Volume Approach Sampling	Low-Flow / Low Stress Sampling Other (Specify): Low Flow												
Casing ID: <u>2</u>			YSI SERIAL NO: <u>24101226</u> Heron Serial NO: <u>120P 24031634B</u>												
WATER QUALITY INDICATOR PARAMETERS (continued)															
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity			
Pre	0	0855		54.52											
Purge	5	0900				13.8	6.51	1514	2.30	7.10	143.2	Clear			
	10	0905				13.8	6.48	1532	2.00	8.60	145.3				
	15	0910				13.7	6.47	1541	1.95	9.01	145.8				
*****	20	0915				13.7	6.47	1546	1.90	9.62	146.0				
	25	0920	36.41	54.52		13.7	6.47	1549	1.89	9.91	145.6				
	30														
	35														
	40														
	45														
	50														
	55														
	60														
NOTES (continued)										ABBREVIATIONS					
Sample ID: <u>08</u> Sampled @ <u>0920</u> on <u>10/10/24</u>										Cond - Actual Conductivity			ORP - Oxidation-Reduction Potential SEC -		
										FT BTOC - Feet Below Top of Casing na -			Specific Electrical Conductance SU - Standard		
										nm - Not Measured			Units		
										Temp - Temperature			°C - Degrees Celsius		



WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vista										
Project Number: 6054		Task #: 1018		Start Date: 10/8/2024		Time: 0750						
Field Personnel: Lorne		Finish Date: Same		Time: 0815								
EVENT TYPE												
Well ID: 0812		Well Development		Low-Flow / Low Stress Sampling Other								
Casing ID: 2"		Well Volume Approach Sampling		(Specify): Low Flow								
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0750		55.09								Clear
Purge	5	0755		55.09		13.0	4.07	1680	3.95	9.66	102.9	
	10	0800		55.09		13.0	6.66	1668	1.78	9.05	118.1	
	15	0805		55.09		13.0	6.65	1670	1.61	9.01	121.0	
*****	20	0810		55.09		13.1	6.65	1674	1.60	7.00	123.0	
	25	0815	2.5	55.09		13.1	6.65	1675	1.58	6.33	123.9	↓
	30											
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)										ABBREVIATIONS		
Sample ID: 0812										Cond. - Actual Conductivity		
Sampled @ 0815 on 10/18/24										FT BTOC - Feet Below Top of Casing na -		
										Units		
										Temp. - Temperature		
										°C - Degrees Celsius		

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Visra		Task #: 7/7/2024		Time: 1530						
Project Number: 6. A3000		Start Date: 7/7/2024		Finish Date: 10 dbn 102824		Time: 1530						
Field Personnel: 6. A3000		Inches		Well Development		Well Volume Approach Sampling		Low-Flow / Low Stress Sampling Other				
Well ID: 10		Casing ID:		Event Type		YSI SERIAL NO: 401474X		Heron Serial NO:				
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1530	—			—	—	—	—	—	—	—
Purge	5	1535	0			18.4	6.84	1015	6.02	28.07	94.8	Clear
↓	10	1540	1			20.0	6.88	1004	1.00	3.95	73.1	Clear
*****	15	1545	1.5			20.1	6.88	1004	1.02	3.38	70.0	" "
*****	20	1550	2.5			25.0	6.87	1004	0.91	2.86	63.6	" "
Sample	25	1555	3									
	30											
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: on 7/7/2024 10 dbn 102824												
Sampled @												
DTD: 52.27												
ABBREVIATIONS												
Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na+ - Not Applicable nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

②1555
ID: Hen-10
Water meter Above pump (no recording)

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra										
Project Number:		Task #:		Start Date: 10/8/2024		Time: 0830						
Field Personnel: S. Aronoff		Finish Date: 10/8/24		Time:								
WELL INFORMATION				EVENT TYPE								
Well ID: 12		Inches		Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow				
Casing ID:		YSI SERIAL NO: 4101474 Heron Serial NO: 41024102										
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0830	—	No def.	—	—	—	—	—	—	—	—
Purge	5	0835	—	—	—	17.3	7.19	774	5.87	2.54	87.6	Clear
↓	10	0840	0.5	—	—	19.2	7.25	868	2.65	2.55	81.6	—
*****	15	0845	1	—	—	19.3	7.25	864	1.91	1.94	69.6	—
↓	20	0850	1.5	—	—	19.3	7.24	870	1.63	2.21	57.4	—
↓	25	0855	2	—	—	19.4	7.24	870	1.57	6.68	96.5	—
↓	30	0900	3	—	—	19.4	7.24	876	1.57	2.09	56.4	—
↓	35	0905	3.5	—	—	19.4	7.24	870	1.56	2.08	55.8	—
↓	40	0910	4	—	—	19.4	7.24	871	1.74	2.79	58.3	—
Sample	45	0915	4.5	—	—	—	—	—	—	—	—	—
	50											
	55											
	60											
NOTES (continued)												
Sample ID: 12 on 10/8/2024												
Sampled @												
Water not detectable at bottom												
52 ft												
ABBREVIATIONS												
Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing ne - Not Applicable nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC - Units Temp - Temperature °C - Degrees Celsius												

ⓐ 0915
10/8/24
Hen-12

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra		Task #: 13		Start Date: 10/8/2024		Time: 0740				
Field Personnel: Gavin Arndt		Finish Date: 10/8/24		Time: 0828								
WELL INFORMATION				EVENT TYPE								
Well ID: 13		Inches		Well Development Well Volume Approach Sampling		Low-Flow / Low Stress Sampling Other (Specify): Low Flow		YSI SERIAL NO: 4101474		Heron Serial NO: 0820		
Casing ID:												
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0745	—	52.21	—	—	—	—	—	—	—	—
Purge	5	0750	0.5	52.22	—	18.6	7.32	857	3.72	6.54	104.4	6120
↓	10	0755	1	52.21	—	19.3	7.31	864	1.55	2.65	88.8	—
	15	0800	1.5	52.19	—	18.3	7.31	865	1.54	3.38	76.2	—
*****	20	0805	2	52.20	—	18.3	7.31	865	1.34	2.17	66.8	—
Purge	25	0810	2.5	52.19	—	18.3	7.30	865	1.54	5.71	60.0	—
↓	30	0815	3.5	52.21	—	19.4	7.30	865	1.37	3.06	57.4	—
Sample	35	0820	—	—	—	—	—	—	—	—	—	—
Sample	40	0828	—	—	—	—	—	—	—	—	—	—
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: Hen-13												
Sampled @ on 10/8/2024												
ABBREVIATIONS												
Cond - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

Hen-13
0820

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra		Start Date: 10/19/2024		Time: 1440						
Project Number: 0054		Task #: 3		Finish Date: 10/19/2024		Time: 1505						
Field Personnel: Larve		Finish Date: 10/19/2024		Time: 1505								
WELL INFORMATION				EVENT TYPE								
Well ID: 16		Inches		Well Development				Low-Flow / Low Stress Sampling Other				
Casing ID: 2				Well Volume Approach Sampling				(Specify): Low Flow				
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1440		55.15		24.4	7.00	732	2.42	6.37	137.1	Clear
Purge	5	1445		55.15		21.5	6.99	735	2.18	5.63	134.6	
	10	1450		55.15		21.4	6.99	736	2.2	5.31	132.4	
	15	1455		55.15		21.5	6.99	735	2.07	5.46	132.0	
*****	20	1500		55.15		21.4	6.99	736	2.06	5.24	130.9	
	25	1505	3.64	55.15								
	30											
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: 16												
Sampled @ 1505 on 10/19/2024												
Dope (OT) 1520												
ABBREVIATIONS												
Cond - Actual Conductivity FT BTCC - Feet Below Top of Casing na - Not Applicable nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vista										
Project Number: 0054		Task #: Same		Start Date: 10/9/2024		Time: 1335						
Field Personnel: Leral		Finish Date: Same		Time: 1410								
WELL INFORMATION				EVENT TYPE								
Well ID: 17		Inches		Well Development				Low-Flow / Low Stress Sampling Other				
Casing ID: 2				Well Volume Approach Sampling				YSI SERIAL NO: 249101226				
								Heron Serial NO: 1202 240316363				
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1340		56.30			7.03	761	5.05	43.77	134.0	
Purge	5	1345		56.30		22.6	7.04	762	5.02	55.97	133.9	
	10	1350		56.30		22.5	7.04	762	4.96	93.38	133.9	
	15	1355		56.30		22.6	7.04	762	4.93	95.01	134.0	
*****	20	1400		56.30		22.6	7.04	762	4.97	94.91	134.4	
	25	1405		56.30		22.6	7.04	762	4.98	92.96	134.7	
	30	1410	36AL	56.30		22.6						
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: 17												
Sampled @ 1410 on 10/9/24												
ABBREVIATIONS												
Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degree Celsius												

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: <u>Hennepin</u>	Client: <u>Vistra</u>	Start Date: <u>10/8/2024</u>	Time: <u>1220</u>									
Project Number: <u>0054</u>	Task #: _____	Finish Date: <u>Same</u>	Time: <u>1250</u>									
Field Personnel: <u>Lozne</u>												
WELL INFORMATION				EVENT TYPE								
Well ID: <u>18D</u>	Well Development			Low-Flow / Low Stress Sampling Other								
Casing ID: <u>2</u>	Well Volume Approach Sampling			YSI SERIAL NO <u>244</u> (001226)								
				Heron Serial NO: <u>1252403163143</u>								
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1220		41.80		18.2	7.07	782	1.62	17.00	69.0	Clear
Purge	5	1225		41.85		18.1	7.07	782	1.73	18.82	71.2	
	10	1230		41.90		18.1	7.07	783	1.63	25.62	71.6	
	15	1235		41.90		18.1	7.06	784	1.54	24.22	71.4	
*****	20	1240		41.92		18.2	7.06	782	1.48	21.37	71.0	
	25	1245		41.95		18.1	7.06	781	1.47	22.20	70.7	✓
	30	1250		41.95								
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)										ABBREVIATIONS		
Sample ID: <u>18D</u>										Cond. - Actual Conductivity		
Sampled @ <u>1250 on 10/8/24</u>										FT BTOC - Feet Below Top of Casing na -		
										Not Applicable		
										Units		
										Temp - Temperature		
										°C - Degrees Celsius		

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: <u>Hennepin</u>		Client: <u>Visita</u>										
Project Number: <u>0054</u>		Task #: _____		Start Date: <u>10/8/2024</u>		Time: <u>1120</u>						
Field Personnel: <u>Corne</u>		Finish Date: <u>Same</u>		Time: <u>1150</u>								
WELL INFORMATION				EVENT TYPE								
Well ID: <u>180</u>		Well Development		Low-Flow / Low Stress Sampling Other								
Casing ID: <u>2</u>		Well Volume Approach Sampling		YSI SERIAL NO: <u>24R1001216</u> Heron Serial NO: <u>121240316314B</u>								
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1120		41.59								Clear
Purge	5	1125		41.59		18.4	7.28	769	1.79	8.75	102.0	
	10	1130		41.59		18.4	7.29	766	1.51	7.29	97.7	
	15	1135		41.59		18.3	7.29	763	1.00	7.29	89.1	
*****	20	1140		41.59		18.3	7.30	770	1.00	8.15	86.6	
	25	1145		41.59		18.4	7.30	769	1.11	9.72	84.9	
	30	1150	3.564	41.59		18.4	7.31	769	1.11	7.22	83.9	✓
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)										ABBREVIATIONS		
Sample ID: <u>185</u>										Cond. - Actual Conductivity		
Sampled @ <u>1150</u> on <u>10/8/24</u>										FT BTOC - Feet Below Top of Casing na -		
										Units		
										Temp - Temperature		
										°C - Degrees Celsius		

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

Site: Hennepin
Project Number: 0054
Field Personnel: S. Arzallay

Client: Vistra
Start Date: 10/8/2024
Finish Date: 10/8/2024

Task #: 1530
Time: 1625

WELL INFORMATION

Well ID: 21
Casing ID: _____
Inches _____

EVENT TYPE

Low-Flow / Low Stress Sampling Other
(Specify): Low Flow

YSI SERIAL NO: 41012444
Heron Serial NO: _____

WATER QUALITY INDICATOR PARAMETERS (continued)

Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1530	—	6.59	—	—	—	—	—	—	—	—
Purge	5	1535	0.5	6.63	—	15.2	7.32	1203	2.81	40.32	-133.4	2100
	10	1540	1	6.73	—	14.6	7.38	1200	2.63	43.34	-164.4	
	15	1545	1.5	6.73	—	14.5	7.39	1200	2.25	39.70	-162.4	
*****	20	1550	2	6.72	—	14.4	7.41	1205	1.20	36.91	-160.8	
Purge	25	1555	2.5	6.73	—	14.3	7.41	1203	1.26	36.92	-161.7	
Sample	30	1600	—	—	—	—	—	—	—	—	—	—
	35	1605	—	—	—	—	—	—	—	—	—	—
	40	1610	—	—	—	—	—	—	—	—	—	—
Final	45	1620	4	6.43	—	—	—	—	—	—	—	—
	50	—	—	—	—	—	—	—	—	—	—	—
	55	—	—	—	—	—	—	—	—	—	—	—
	60	—	—	—	—	—	—	—	—	—	—	—

NOTES (continued)

Sample ID: ~~21RMS~~ 21R, 21RMS, 21RMSD
Sampled @ 1600, 1605, 1610 on 10/8/2024

ABBREVIATIONS

Cond. - Actual Conductivity
FT BTOC - Feet Below Top of Casing na -
Not Applicable
nm - Not Measured
ORP - Oxidation-Reduction Potential SEC -
Specific Electrical Conductance SU - Standard
Units
Temp. - Temperature
°C - Degrees Celsius

21R 1600 10/8
21RMS 1605 10/8
21RMSD 1610 10/8

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra		Start Date: 10/9/2024		Time: 1400						
Project Number: 0054		Task #: C. Assessment		Finish Date: 10/9/24		Time: 1435						
Field Personnel: C. Assessment												
WELL INFORMATION				EVENT TYPE								
Well ID: 22		Inches		Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow				
Casing ID:		YSI SERIAL NO: Heron Serial NO:										
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0222	140	19.11	—	—	—	—	—	—	—	—
Purge	5	0225	140.5	19.29	—	16.3	7.53	1087	3.17	9.66	-62.7	clear
	10	0230	141	19.14	—	15.9	7.55	1082	0.48	7.85	-65.6	↓
	15	0235	141.5	19.10	—	15.7	7.56	1082	0.41	3.86	-61.9	↑
****	20	0240	142	19.20	—	15.9	7.56	1082	0.50	6.74	-58.1	↑
Sample	25	0245	142.5	—	—	—	—	—	—	—	—	—
Final	30	0250	143	19.10	—	—	—	—	—	—	—	—
	35	—	—	—	—	—	—	—	—	—	—	—
	40	—	—	—	—	—	—	—	—	—	—	—
	45	—	—	—	—	—	—	—	—	—	—	—
	50	—	—	—	—	—	—	—	—	—	—	—
	55	—	—	—	—	—	—	—	—	—	—	—
	60	—	—	—	—	—	—	—	—	—	—	—
NOTES (continued)												
Sample ID: 22												
Sampled @ 1425 on 10/9/24												

10/9/24
Hen-22
⑨ 1425

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: <u>Hennepin</u>		Client: <u>Vistra</u>										
Project Number: _____		Task #: _____		Start Date: <u>10/18/2024</u>		Time: <u>1315</u>						
Field Personnel: <u>C. Assalery</u>		Finish Date: <u>10/19/24</u>		Time: <u>1400</u>								
EVENT TYPE												
Well ID: <u>2280</u>		Inches		Well Development Well Volume Approach Sampling		Low-Flow / Low Stress Sampling Other (Specify): Low Flow		YSI SERIAL NO: Heron Serial NO:				
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1320	—	<u>19.82</u>	—	<u>16.9</u>	<u>7.24</u>	<u>1173</u>	<u>2.39</u>	<u>13.10</u>	<u>-108.4</u>	<u>1200</u>
Purge	5	1325	<u>0.5</u>	<u>19.99</u>	—	<u>16.3</u>	<u>7.24</u>	<u>1182</u>	<u>0.77</u>	<u>9.97</u>	<u>-120.4</u>	—
	10	1330	<u>1</u>	<u>20.11</u>	—	<u>16.2</u>	<u>7.24</u>	<u>1180</u>	<u>0.65</u>	<u>5.65</u>	<u>-130.9</u>	—
	15	1335	<u>2</u>	<u>20.00</u>	—	<u>16.1</u>	<u>7.24</u>	<u>1177</u>	<u>0.62</u>	<u>6.10</u>	<u>-130.9</u>	—
*****	20	1340	<u>2.5</u>	<u>20.03</u>	—	<u>16.1</u>	<u>7.24</u>	<u>1174</u>	<u>0.53</u>	<u>6.94</u>	<u>-131.1</u>	—
↓	25	1345	<u>3</u>	<u>20.09</u>	—	<u>16.1</u>	<u>7.24</u>					—
Sand	30	1350	<u>3.5</u>	<u>19.98</u>	—							—
Bind	35	1400										—
	40											—
	45											—
	50											—
	55											—
	60											—
NOTES (continued)										ABBREVIATIONS		
Sample ID: <u>2280</u>										Cond. - Actual Conductivity		
Sampled @ <u>1350</u> on <u>10/19/24</u>										FT BTOC - Feet Below Top of Casing na -		
										Not Applicable		
										nm - Not Measured		
										Temp - Temperature		
										°C - Degrees Celsius		

2280
10/19/24
② 1350

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vista		Task #: 0930		Start Date: 10/9/24		Time: 1020		YSI SERIAL NO: 41101474X Heron Serial NO:		
Project Number: 0053		Finish Date: 10/9/24		Time: 1020		Well Development Well Volume Approach Sampling		Low-Flow / Low Stress Sampling Other (Specify): Low Flow				
Field Personnel: G. Asanig		Inches		EVENT TYPE								
WELL INFORMATION		Well ID: 2-3		WATER QUALITY INDICATOR PARAMETERS (continued)								
Casing ID:												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0930	—	17.28	—	—	—	—	—	—	—	—
Purge	5	0935	0.5	17.24	—	13.8	7.05	1049	5.11	2.67	19.5	Clear
	10	0940	1	17.45	—	14.1	7.01	1337	4.77	2.77	21.8	↓
	15	0945	1.5	17.40	—	14.4	7.01	1338	4.54	2.14	25.1	↓
*****	20	0950	2	17.44	—	14.6	7.02	1338	4.42	2.30	27.9	↓
	25	0955	2.5	17.45	—	14.8	7.04	1339	4.33	2.44	30.7	↓
	30	1000	3	17.64	—	13.2	7.37	1374	0.17	6.55	-21.9	↓
	35	1005	3.5	17.85	—	13.2	7.39	1372	0.12	7.44	-31.3	↓
↓	40	1010	4	17.92	—	13.2	7.39	1374	0.06	8.27	-29.7	↓
Sand	45	1015	5	17.45	—	—	—	—	—	—	—	—
Finish	50	1020	5	17.45	—	—	—	—	—	—	—	—
	55											
	60											
NOTES (continued)												
Sample ID: 2-3												
Sampled @ 1015 on 10/9/24												
ABBREVIATIONS												
Cond - Actual Conductivity FT BTCC - Feet Below Top of Casing na - Not Applicable nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

Hen-23
10/9/24
@ 1015

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: <u>Visra</u>										
Project Number:		Task #: _____		Start Date: <u>10 / 3 / 2024</u>		Time: <u>1120</u>						
Field Personnel: <u>G. Assalery</u>		Finish Date: <u>10/3/2024</u>		Time: _____								
WELL INFORMATION				EVENT TYPE								
Well ID: <u>27</u>		Inches		Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow				
Casing ID: _____								YSI SERIAL NO: Heron Serial NO:				
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	<u>1125</u>	<u>—</u>	<u>4.70</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Purge	5	<u>1130</u>	<u>0.5</u>	<u>4.72</u>	<u>—</u>	<u>12.8</u>	<u>7.13</u>	<u>1175</u>	<u>0.99</u>	<u>20.95</u>	<u>-61.7</u>	<u>Clear</u>
	10	<u>1135</u>	<u>1</u>	<u>4.81</u>		<u>12.7</u>	<u>7.14</u>	<u>1177</u>	<u>0.45</u>	<u>38.21</u>	<u>-79.1</u>	
	15	<u>1140</u>	<u>1.5</u>	<u>4.75</u>		<u>12.7</u>	<u>7.14</u>	<u>1177</u>	<u>0.53</u>	<u>34.53</u>	<u>-79.8</u>	
*****	20	<u>1145</u>	<u>2.5</u>	<u>4.72</u>		<u>12.6</u>	<u>7.14</u>	<u>1178</u>	<u>0.48</u>	<u>35.53</u>	<u>-74.9</u>	
	25	<u>1150</u>	<u>3.5</u>	<u>4.74</u>		<u>12.4</u>	<u>7.15</u>	<u>1178</u>	<u>0.54</u>	<u>33.74</u>	<u>-73.3</u>	<u>↓</u>
Sample	30	<u>1155</u>	<u>—</u>	<u>4.72</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Final	35	<u>1205</u>	<u>—</u>	<u>4.68</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: <u>Hen-27</u>												
Sampled @ <u>1155</u> on <u>10/3/24</u>												
ABBREVIATIONS												
Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

Hen-27
01155

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra										
Project Number:		Task #:		Start Date: 10/18/2024		Time: 1030						
Field Personnel: G. Asbury		Finish Date: 10/30/2024		Time:								
WELL INFORMATION				EVENT TYPE								
Well ID: 32		Inches		Well Development				Low-Flow / Low Stress Sampling Other				
Casing ID:				Well Volume Approach Sampling				YSI SERIAL NO: 6101474X Heron Serial NO:				
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1030	—	5.45	—	—	—	—	—	—	—	—
Purge	5	1035	0.5	5.54	0.09	14.5	7.08	1018	0.97	8.09	297.7	Clear
	10	1040	1	5.55	0.01	14.5	7.06	1018	0.67	3.92	82.3	↓
	15	1045	2	5.59	0.04	14.5	7.07	1017	1.16	4.10	76.4	↓
*****	20	1050	2.5	5.40		14.5	7.06	1016	1.06	2.67	66.8	↓
	25	1055	3	5.62		14.5	7.06	1017	1.00	8.24	64.0	↓
	30	1100	4	5.70		14.5	7.06	1017	0.84	4.81	59.5	↓
Sample	35	1105										
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: Hen-32												
Sampled @ 1105 on 10/31/24												
Abbreviations: Good - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

Hen-32
@ 1105

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra		Start Date: 10/8/2024		Time: 1310						
Project Number: 1224100524		Task #: 34		Finish Date: 10/8/2024		Time: 1400						
Field Personnel: G. Anderson												
WELL INFORMATION				EVENT TYPE								
Well ID: 34		Inches		Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow				
Casing ID:		YSI SERIAL NO: Heron Serial NO:										
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1315	---	8.97	---	---	---	---	---	---	---	---
Purge	5	1320	0	9.19	---	12.9	6.98	1309	1.19	21.51	-108.6	Clear
	10	1325	0.5	9.31	---	12.7	6.98	1374	0.54	9.98	-124.0	
	15	1330	1.25	9.23	---	12.6	6.98	1395	0.32	6.26	-130.1	
***	20	1335	2	9.32	---	12.6	6.98	1401	0.26	5.79	-132.7	
↓	25	1340	3	9.35	---	12.4	6.98	1407	0.24	4.91	-134.0	↓
Saved	30	1345	---	9.14	---	---	---	---	---	---	---	---
Penal	35	1350	---	9.01	---	---	---	---	---	---	---	---
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: 34												
Sampled @ 1345 on 10/8/2024												
ABBREVIATIONS												
Cond - Actual Conductivity FT BTOC - Feet Below Top of Casing m - Units nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

Hen_34
⊗ 1345

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: <u>Hennepin</u>		Client: <u>Vistra</u>		Task #: <u>1405</u>		Start Date: <u>10/8/2024</u>		Time: <u>1405</u>				
Project Number: <u>2024.054</u>		Finish Date: <u>10/8/24</u>		Field Personnel: <u>G. Aschling</u>		Time: <u></u>						
WELL INFORMATION				EVENT TYPE								
Well ID: <u>B3</u>		Inches		Well Development		Well Volume Approach Sampling		Low-Flow / Low Stress Sampling Other		YSI SERIAL NO: <u>U10144X</u>		
Casing ID: <u></u>				Well Volume Approach Sampling						Heron Serial NO: <u></u>		
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1410	—	8.92	—	—	—	—	—	—	—	—
Purge	5	1415	1.0	8.92	—	17.1	6.88	2047	0.53	4.07	39.7	Clear
↓	10	1420	1.5	8.94	—	17.1	6.89	2096	0.38	3.04	41.7	Clear
↓	15	1425	1.5	8.94	—	17.0	6.88	2047	0.34	2.84	41.7	↓
****	20	1430	2.5	8.97	—	17.0	6.89	2093	0.40	3.82	42.1	↓
Sand	25	1435	—	—	—	—	—	—	—	—	—	—
Sand	30	1440	—	—	—	—	—	—	—	—	—	—
Final	35	1450	—	8.89	—	—	—	—	—	—	—	—
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: <u>Hen 35</u> on <u>10/8/24</u>												
Sampled @ <u>1435</u>												
Field Duplicate												
Hen - 35 ① 1435 10/8/24 Hen - 35 FD ② 1440 10/8/24												
ABBREVIATIONS												
Cond. - Actual Conductivity FT BTOC - Feet Below Top of Casing na Not Applicable nm - Not Measured ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra		Start Date: 10/8/2024		Time: 1400						
Project Number: 0054		Task #: Same		Finish Date: 1430		Time: 1430						
Field Personnel: Corne												
WELL INFORMATION				EVENT TYPE								
Well ID: 405		Inches		Well Development		Low-Flow / Low Stress Sampling Other (Specify): Low Flow						
Casing ID: 2				Well Volume Approach Sampling		YSI SERIAL NO: 24R1007226 Heron Serial NO: 12DR2453167148						
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1400		41.40								Clear
Purge	5	1405		41.40		18.5	7.73	681	1.92	30.29	111.5	
	10	1410		41.40		18.4	7.73	678	1.73	12.12	110.3	
	15	1415		41.40		18.3	7.73	628	1.63	8.29	108.6	
*****	20	1420		41.40		18.2	7.73	671	1.51	8.06	106.4	
	25	1425		41.40		18.1	7.73	679	1.56	9.02	104.4	
	30	1430		41.40		18.2	7.73	678	1.48	6.25	103.5	
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: 405												
Sampled @ 1430 on 10/8/24												
ABBREVIATIONS												
Cond - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra										
Project Number: 6054		Task #: 10825										
Field Personnel: Larry		Finish Date: 10/19/2024										
Time: 8:00		Time: 8:00										
EVENT TYPE												
Well Development				Low-Flow / Low Stress Sampling Other								
Well Volume Approach Sampling				(Specify): Low Flow								
Well ID: 45#5				YSI SERIAL NO: 24A101224								
Casing ID: 2				Heron Serial NO: 12RF2403163HB								
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0835		21.21		17.9	7.09	800	1.64	32.69	46.2	Clear
Purge	5	0830		21.21		18.0	7.07	791	1.71	19.64	48.9	
	10	0835		21.21		18.4	7.07	797	1.46	15.12	54.2	
*****	15	0840		21.21		18.3	7.06	797	1.44	12.20	58.6	
	20	0845		21.21		18.4	7.06	797	1.42	10.10	60.6	
	25	0850		21.21		18.4	7.06	797	1.39	9.72	62.7	
	30	0855		21.21								
	35	0900	3.56	21.21								
	40											
	45											
	50											
	55											
	60											
NOTES (continued)										ABBREVIATIONS		
Sample ID: 45#S										Cond - Actual Conductivity		
Sampled @ 0900 Don 10/19/24										FT BTCC - Feet Below Top of Casing na -		
										Not Applicable		
										nm - Not Measured		
										Temp - Temperature		
										°C - Degrees Celsius		

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

708 534 5200

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra		Start Date: 10/9/2024		Time: 1110						
Project Number: 0654		Task #:		Finish Date:		Time: 1130						
Field Personnel: Lorne		Finish Date:		Time:								
WELL INFORMATION				EVENT TYPE								
Well ID: H2		Inches		Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow				
Casing ID:								YSI SERIAL NO: 240101226 Heron Serial NO: 120F2403163453				
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1110		52.27								
Purge	5	1115		52.27		21.1	7.16	709	1.57	7.14	105.9	
	10	1120		52.27		21.1	7.15	709	1.38	7.15	104.1	
	15	1125		52.27		21.2	7.16	709	1.30	6.72	103.3	
*****	20	1130		52.27		21.2	7.16	709	1.27	6.77	100.0	
	25	1135	2.564	52.27		21.2	7.16	709	1.28	7.28	99.9	
	30											
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: 46												
Sampled @ 1130 on 10/9/2024												
ABBREVIATIONS												
Cond - Actual Conductivity FT BTCC - Feet Below Top of Casing na - Not Applicable nm - Not Measured												
ORP - Oxidation Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin	Client: Vista	Task #: 0034	Start Date: 09/10/2024	Time: 1220								
Field Personnel: Corne	Finish Date: Same	Time: 1240										
WELL INFORMATION			EVENT TYPE									
Well ID: H-2	Well Development	Well Volume Approach Sampling	Low-Flow / Low Stress Sampling Other (Specify): Low Flow									
Casing ID: 2	Well ID: 2		YSI SERIAL NO: 211A-101226 Heron Serial NO: 12DF2403/61HB									
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1220		56.60		19.7	6.99	726	2.04	7.56	120.5	Clear
Purge	5	1223		56.62		19.7	6.99	728	2.04	6.97	119.3	
	10	1230		56.62		19.6	6.98	727	2.00	6.91	119.0	
*****	15	1235		56.62		19.6	6.99	727	1.98	7.78	118.9	
	20	1240	3 Gal	56.62								
	25	1245										
	30											
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)										ABBREVIATIONS		
Sample ID: 47										ORP - Oxidation-Reduction Potential SEC -		
Sampled @ 1240 on 10/19/24										FT BTOD - Feet Below Top of Casing na -		
										Specific Electrical Conductance SU - Standard		
										Units		
										Temp - Temperature		
										mm - Not Measured		
										°C - Degrees Celsius		

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: <u>Hennepin</u>		Client: <u>Visira</u>										
Project Number: <u>2054</u>		Task #: _____		Start Date: <u>10/9/2024</u>		Time: <u>1030</u>						
Field Personnel: <u>C. Arnsperg</u>		Finish Date: <u>10/9/24</u>		Time: <u>1130</u>								
WELL INFORMATION				EVENT TYPE								
Well ID: <u>49</u>		Inches		Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow				
Casing ID: _____		YSI SERIAL NO: Heron Serial NO: _____										
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1030	—	21.21	—	—	—	—	—	—	—	—
Purge	5	1035	—	22.29	—	15.3	7.75	1150	6.64	4.77	-185.1	Clear
	10	1040	—	21.21	—	14.6	7.06	1170	0.99	28.06	-20.4	Clear
	15	1045	—	22.23	—	14.0	7.05	1169	0.66	69.92	-2.5	—
*****	20	1050	—	22.25	—	14.6	7.05	1170	0.58	70.32	3.3	—
	25	1055	—	22.27	—	14.6	7.05	1169	0.46	73.27	7.7	—
↓	30	1100	—	22.30	—	14.6	7.65	1168	0.52	73.05	11.4	—
Sample	35	1105	—	—	—	—	—	—	—	—	—	—
↓	40	1110	—	—	—	—	—	—	—	—	—	—
	45	1115	—	—	—	—	—	—	—	—	—	—
Final	50	1125	—	22.27	—	—	—	—	—	—	—	—
	55	—	—	—	—	—	—	—	—	—	—	—
	60	—	—	—	—	—	—	—	—	—	—	—
NOTES (continued)												
Sample ID: <u>Hen 49, 49MS 49MSD</u>												
Sampled @ <u>on 10/9/24</u>												
ABBREVIATIONS												
Cond - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degree Celsius												

Hen 49 Hen 49MS 49MSD
@1105 @1110 @1115
10/9/24 10/9/24 10/9/24

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: <u>Vistra</u>										
Project Number:		Task #: _____		Start Date: <u>10/9/24</u>		Time: <u>1230</u>						
Field Personnel: <u>Go Asad</u>		Finish Date: <u>10/9/24</u>		Time: <u>1310</u>								
WELL INFORMATION				EVENT TYPE								
Well ID: <u>50</u>		Inches		Well Development				Low-Flow / Low Stress Sampling Other				
Casing ID:				Well Volume Approach Sampling				YSI SERIAL NO: <u>U101474X</u> Heron Serial NO:				
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	1235	—	<u>18.9</u>	—	—	—	—	—	—	—	—
Purge	5	1240	<u>0.5</u>	<u>18.89</u>	—	<u>16.2</u>	<u>7.43</u>	<u>1065</u>	<u>1.36</u>	<u>12.13</u>	<u>8.6</u>	<u>Clear</u>
	10	1245	<u>1</u>	<u>18.92</u>	—	<u>16.2</u>	<u>7.42</u>	<u>1069</u>	<u>0.55</u>	<u>5.29</u>	<u>-8.0</u>	<u>Clear</u>
	15	1250	<u>2</u>	<u>19.02</u>	—	<u>16.1</u>	<u>7.42</u>	<u>1064</u>	<u>0.32</u>	<u>3.81</u>	<u>-16.0</u>	<u>↓</u>
****	20	1255	<u>3</u>	<u>18.96</u>	—	<u>16.1</u>	<u>7.42</u>	<u>1069</u>	<u>0.36</u>	<u>3.46</u>	<u>-22.6</u>	<u>↓</u>
	25	1300	<u>4</u>	<u>19.02</u>	—	<u>16.1</u>	<u>7.42</u>	<u>1070</u>	<u>0.48</u>	<u>5.13</u>	<u>-20.3</u>	<u>↓</u>
Sample Final	30	1305	<u>4.5</u>	<u>18.91</u>	—	—	—	—	—	—	—	—
	35	1308										
	40											
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: <u>50</u>												
Sampled @ <u>1305</u> on <u>10/9/24</u>												

Hen-50
10/9/24
⑨/1305

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra										
Project Number: 0054		Task #:		Start Date: 10/14/2024		Time: 0825						
Field Personnel: G. Asadally		Finish Date: 10/19/24		Time:								
WELL INFORMATION				EVENT TYPE								
Well ID: 51		Inches		Well Development		Well Volume Approach Sampling		Low-Flow / Low Stress Sampling Other		YSI SERIAL NO: Heron Serial NO:		
Casing ID:				Well Volume Approach Sampling								
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0830	—	19.21	—	—	—	—	—	—	—	—
Purge	5	0835	0.5	19.52	—	12.7	7.26	1188	4.39	35.72	-90.1	Clear
	10	0840	0.5	19.55	—	12.6	7.32	1193	0.95	28.72	-140.8	
	15	0845	1	19.59	—	12.6	7.32	1192	0.87	19.45	-146.0	
*****	20	0850	1.5	19.49	—	12.6	7.33	1193	0.74	15.42	-149.9	Muddy
	25	0855	2	19.55	—	12.6	7.32	1193	0.61	15.23	-152.1	Clear
	30	0900	2.5	19.71	—	12.6	7.33	1191	0.63	14.89	-153.0	Clear
Sand	35	0905	—	—	—	—	—	—	—	—	—	—
FINISH	40	0920	—	19.15	—	—	—	—	—	—	—	—
	45											
	50											
	55											
	60											
NOTES (continued)												
Sample ID: 51												
Sampled @ 0905 on 10/19/24												
ABBREVIATIONS												
Cond - Actual Conductivity FT BTOC - Feet Below Top of Casing na - Not Applicable nm - Not Measured												
ORP - Oxidation-Reduction Potential SEC - Specific Electrical Conductance SU - Standard Units Temp - Temperature °C - Degrees Celsius												

Hen_51
0905
10/19/24



WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: <u>Hennepin</u>		Client: <u>Vistra</u>		Start Date: <u>10/10/2024</u>		Time: <u>0730</u>						
Project Number: <u>00514</u>		Task #: <u>1</u>		Finish Date: <u>10/10/2024</u>		Time: <u>0820</u>						
Field Personnel: <u>E. A. S. 116g</u>												
WELL INFORMATION				EVENT TYPE								
Well ID: <u>52</u>		Inches		Well Development Well Volume Approach Sampling				Low-Flow / Low Stress Sampling Other (Specify): Low Flow				
Casing ID:		YSI SERIAL NO: <u>11101474x</u> Heron Serial NO:										
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0735	—	54.74	—	—	—	—	—	—	—	—
Purge	5	0740	0.5	54.70	—	17.2	6.88	939	4.70	4.92	75.2	clear
	10	0745	1	54.71	—	19.4	6.87	1000	1.77	3.68	69.0	↓
	15	0750	1.5	54.71	—	19.7	6.95	1007	1.47	3.03	54.8	↓
****	20	0755	2	54.71	—	19.8	6.94	1009	1.40	2.97	46.5	↓
	25	0800	2.5	54.69	—	19.8	6.94	1009	1.44	3.02	43.3	↓
↓	30	0805	3	54.70	—	19.8	6.94	1008	1.44	3.11	41.7	↓
Sample	35	0810	—	—	—	—	—	—	—	—	—	—
Final	40	0815	3.5	54.72	—	—	—	—	—	—	—	—
	45											
	50											
	55											
	60											
NOTES (continued)				ABBREVIATIONS								
Sample ID: <u>52</u>				Cond - Actual Conductivity								
Sampled @ <u>0810</u> on <u>10/10/24</u>				FT BTCC - Feet Below Top of Casing na - Not Applicable								
				Temp - Temperature								
				nm - Not Measured								
				°C - Degrees Celsius								

Hen-52
⑤0810

WELL DEVELOPMENT AND GROUNDWATER SAMPLING FIELD FORM

PROJECT INFORMATION												
Site: Hennepin		Client: Vistra										
Project Number: 0054		Task #: 0740		Time: 0815								
Field Personnel: ierne		Finish Date: Same		Time: 0815								
EVENT TYPE												
WELL INFORMATION		Well ID: 54		Well Development		Low-Flow / Low Stress Sampling Other						
Casing ID: 2		Inches		Well Volume Approach Sampling		(Specify): Low Flow						
WATER QUALITY INDICATOR PARAMETERS (continued)												
Sampling Stage	Minutes Elapsed	Time (military)	Volume Removed (gallons)	Depth to Water (Feet)	Drawdown (Feet)	Temp. (°C) +/- 0.1	pH (SU) +/- 0.1	SEC or Cond. (µs/cm) 3%	Dissolved Oxygen (mg/L) 10% or +/- 0.2	Turbidity (NTU) 10% or <10 NTU's	ORP (mV) +/- 10mV	Visual Clarity
Pre	0	0745		54.05		16.9	7.22	658	2.45	12.90	75.0	Clear
Purge	5	0750		54.05		16.8	7.27	658	2.49	12.90	75.0	
	10	0755		54.05		16.9	7.24	657	2.20	10.22	82.3	
	15	0800		54.05		17.0	7.22	657	2.09	9.76	85.3	
*****	20	0805		54.05		17.0	7.22	657	2.00	9.72	87.3	
	25	0810		54.05		17.1	7.22	658	2.10	9.50	88.2	
	30	0815	364	54.05		17.1	7.22	658	2.08	8.51	88.6	
	35											
	40											
	45											
	50											
	55											
	60											
NOTES (continued)										ABBREVIATIONS		
Sample ID: 54										ORP - Oxidation Reduction Potential SEC		
Sampled @ 0815 on 10/10/24										FT BTQC - Feet Below Top of Casing na -		
										Not Applicable		
										Units		
										Temp - Temperature		
										°C - Degrees Celsius		

Dupe @ 0825

ANALYTICAL REPORT

PREPARED FOR

Attn: Brian Voelker
Vistra Energy Corp
133 S 4th, Suite 206
Springfield, Illinois 62701

Generated 11/11/24 14:44:04

JOB DESCRIPTION

HEN-24Q4
HEN_000_RAD

JOB NUMBER

500-258038-2

Job Notes

This report may not be reproduced except in full, and with written approval from the laboratory. The results relate only to the samples tested. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Chicago Project Manager.

Authorization



Generated
11/11/24 14:44:04

Authorized for release by
Dirk Nelson, Project Management Assistant II
Dirk.Nelson@et.eurofinsus.com
(708)534-5200

Table of Contents

Cover Page	1
Table of Contents	3
Case Narrative	4
Detection Summary	5
Method Summary	7
Sample Summary	8
Client Sample Results	9
Definitions	40
QC Association	41
QC Sample Results	43
Chronicle	48
Certification Summary	56
Chain of Custody	57
Receipt Checklists	68
Tracer Carrier Summary	71



Case Narrative

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2

Client: Vistra Energy Corp
Project: HEN-24Q4

Job ID: 500-258038-2

Eurofins Chicago

Job Narrative 500-258038-2

Receipt

The samples were received on 10/08/24 11:17. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 13 coolers at receipt time were 1.5° C, 1.5° C, 3.2° C, 3.5° C, 3.8° C, 4.0° C, 4.2° C, 4.9° C, 5.0° C, 5.2° C, 5.3° C, 5.9° C and 13.8° C.

Receipt Exceptions

The Chain-of-Custody (COC) was incomplete as received and/or improperly completed. No sample date/time on COC. Added sample date/time on COC per sample labels. Sample #2- HEN_10 container label list date as 7/7-added to COC and logged as 10/7. Sample date/time confirmed via well development forms.

The following samples were received at the laboratory at 13.8 C & 5.9 C.: HEN_07 (500-258038-33), HEN_08 (500-258038-34), HEN_52 (500-258038-35), HEN_54 (500-258038-36), HEN_54_FD (500-258038-37) and HEN_FB (500-258038-38). 13.8 C is outside the required temperature criteria of < 6 C. The samples are considered acceptable since it was collected and submitted to the laboratory on the same day and there is evidence that the chilling process has begun.

The Chain-of-Custody (COC) was incomplete as received. The COC is missing the Sample Date. Login sample dates were taken from the bottles, added to the COC and verified using the well development forms. Affected samples: HEN_05&DR (500-258038-4), HEN_05!R (500-258038-5), HEN_08&D (500-258038-6), HEN_12 (500-258038-7), HEN_13 (500-258038-8), HEN_18&D (500-258038-9), HEN_18#S (500-258038-10), HEN_21R (500-258038-11), HEN_21R_MS (500-258038-11[MS]), HEN_21R-MSD (500-258038-11[MSD]), HEN_27 (500-258038-12), HEN_32 (500-258038-13), HEN_34 (500-258038-14), HEN_35 (500-258038-15), HEN_35_FD (500-258038-16) and HEN_40#S (500-258038-17)

RAD

Method 904.0: Radium-228 batch 6832258

The detection goal was not met for the following sample due to the reduced sample volume used in prep attributed to the presence of matrix interferences: HEN_21R (500-258038-11). Analytical results are reported with the detection limit achieved.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Eurofins Chicago

Detection Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_08&D	Lab Sample ID: 500-258038-6
No Detections.	
Client Sample ID: HEN_12	Lab Sample ID: 500-258038-7
No Detections.	
Client Sample ID: HEN_13	Lab Sample ID: 500-258038-8
No Detections.	
Client Sample ID: HEN_18&D	Lab Sample ID: 500-258038-9
No Detections.	
Client Sample ID: HEN_18#S	Lab Sample ID: 500-258038-10
No Detections.	
Client Sample ID: HEN_21R	Lab Sample ID: 500-258038-11
No Detections.	
Client Sample ID: HEN_27	Lab Sample ID: 500-258038-12
No Detections.	
Client Sample ID: HEN_32	Lab Sample ID: 500-258038-13
No Detections.	
Client Sample ID: HEN_34	Lab Sample ID: 500-258038-14
No Detections.	
Client Sample ID: HEN_35	Lab Sample ID: 500-258038-15
No Detections.	
Client Sample ID: HEN_35_FD	Lab Sample ID: 500-258038-16
No Detections.	
Client Sample ID: HEN_03R	Lab Sample ID: 500-258038-19
No Detections.	
Client Sample ID: HEN_03R_FD	Lab Sample ID: 500-258038-20
No Detections.	
Client Sample ID: HEN_16	Lab Sample ID: 500-258038-21
No Detections.	
Client Sample ID: HEN_16_FD	Lab Sample ID: 500-258038-22
No Detections.	
Client Sample ID: HEN_17	Lab Sample ID: 500-258038-23
No Detections.	

This Detection Summary does not include radiochemical test results.

Eurofins Chicago

Detection Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_22	Lab Sample ID: 500-258038-24
☐ No Detections.	
Client Sample ID: HEN_22&D	Lab Sample ID: 500-258038-25
☐ No Detections.	
Client Sample ID: HEN_23	Lab Sample ID: 500-258038-26
☐ No Detections.	
Client Sample ID: HEN_45#S	Lab Sample ID: 500-258038-27
☐ No Detections.	
Client Sample ID: HEN_46	Lab Sample ID: 500-258038-28
☐ No Detections.	
Client Sample ID: HEN_47	Lab Sample ID: 500-258038-29
☐ No Detections.	
Client Sample ID: HEN_49	Lab Sample ID: 500-258038-30
☐ No Detections.	
Client Sample ID: HEN_50	Lab Sample ID: 500-258038-31
☐ No Detections.	
Client Sample ID: HEN_51	Lab Sample ID: 500-258038-32
☐ No Detections.	
Client Sample ID: HEN_07	Lab Sample ID: 500-258038-33
☐ No Detections.	
Client Sample ID: HEN_08	Lab Sample ID: 500-258038-34
☐ No Detections.	
Client Sample ID: HEN_52	Lab Sample ID: 500-258038-35
☐ No Detections.	
Client Sample ID: HEN_54	Lab Sample ID: 500-258038-36
☐ No Detections.	
Client Sample ID: HEN_54_FD	Lab Sample ID: 500-258038-37
☐ No Detections.	
Client Sample ID: HEN_FB	Lab Sample ID: 500-258038-38
☐ No Detections.	

This Detection Summary does not include radiochemical test results.

Eurofins Chicago

Method Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 590-258038-2
SDG: HEN_000_RAD

Method	Method Description	Protocol	Laboratory
903.0	Radium-226 (GFPC)	EPA	EET SL
904.0	Radium-228 (GFPC)	EPA	EET SL
Ra226_Ra228 Pos	Combined Radium-226 and Radium-228	TAL-STL	EET SL
PrecSep_0	Preparation, Precipitate Separation	None	EET SL
PrecSep-21	Preparation, Precipitate Separation (21-Day In-Growth)	None	EET SL

Protocol References:

EPA = US Environmental Protection Agency
None = None
TAL-STL = TestAmerica Laboratories, St. Louis, Facility Standard Operating Procedure.

Laboratory References:

EET SL = Eurofins St. Louis, 13715 Rider Trail North, Earth City, MO 63045, TEL (314)298-8566

Sample Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
500-258038-6	HEN_08&D	Water	10/08/24 08:15	10/09/24 12:00
500-258038-7	HEN_12	Water	10/08/24 09:15	10/09/24 12:00
500-258038-8	HEN_13	Water	10/08/24 08:20	10/09/24 12:00
500-258038-9	HEN_18&D	Water	10/08/24 12:50	10/09/24 12:00
500-258038-10	HEN_18#S	Water	10/08/24 11:50	10/09/24 12:00
500-258038-11	HEN_21R	Water	10/08/24 16:00	10/09/24 12:00
500-258038-12	HEN_27	Water	10/08/24 11:55	10/09/24 12:00
500-258038-13	HEN_32	Water	10/08/24 11:05	10/09/24 12:00
500-258038-14	HEN_34	Water	10/08/24 13:45	10/09/24 12:00
500-258038-15	HEN_35	Water	10/08/24 14:35	10/09/24 12:00
500-258038-16	HEN_35_FD	Water	10/08/24 14:40	10/09/24 12:00
500-258038-19	HEN_03R	Water	10/09/24 10:15	10/10/24 11:10
500-258038-20	HEN_03R_FD	Water	10/09/24 10:30	10/10/24 11:10
500-258038-21	HEN_16	Water	10/09/24 15:05	10/10/24 11:10
500-258038-22	HEN_16_FD	Water	10/09/24 15:20	10/10/24 11:10
500-258038-23	HEN_17	Water	10/09/24 14:10	10/10/24 11:10
500-258038-24	HEN_22	Water	10/09/24 14:25	10/10/24 11:10
500-258038-25	HEN_22&D	Water	10/09/24 13:50	10/10/24 11:10
500-258038-26	HEN_23	Water	10/09/24 10:15	10/10/24 11:10
500-258038-27	HEN_45#S	Water	10/09/24 09:00	10/10/24 11:10
500-258038-28	HEN_46	Water	10/09/24 11:30	10/10/24 11:10
500-258038-29	HEN_47	Water	10/09/24 12:40	10/10/24 11:10
500-258038-30	HEN_49	Water	10/09/24 11:05	10/10/24 11:10
500-258038-31	HEN_50	Water	10/09/24 13:05	10/10/24 11:10
500-258038-32	HEN_51	Water	10/09/24 09:05	10/10/24 11:10
500-258038-33	HEN_07	Water	10/10/24 09:20	10/10/24 12:46
500-258038-34	HEN_08	Water	10/10/24 09:20	10/10/24 12:46
500-258038-35	HEN_52	Water	10/10/24 08:10	10/10/24 12:46
500-258038-36	HEN_54	Water	10/10/24 08:15	10/10/24 12:46
500-258038-37	HEN_54_FD	Water	10/10/24 08:25	10/10/24 12:46
500-258038-38	HEN_FB	Water	10/10/24 09:00	10/10/24 12:46

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_08&D

Lab Sample ID: 500-258038-6

Date Collected: 10/08/24 08:15

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0805	U	0.0682	0.0686	1.00	0.100	pCi/L	10/11/24 08:27	11/04/24 07:48	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	88.6		30 - 110					10/11/24 08:27	11/04/24 07:48	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.692		0.426	0.431	1.00	0.626	pCi/L	10/11/24 08:34	10/25/24 11:59	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	88.6		30 - 110					10/11/24 08:34	10/25/24 11:59	1
Y Carrier	74.8		30 - 110					10/11/24 08:34	10/25/24 11:59	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.773		0.431	0.436	5.00	0.626	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_12

Lab Sample ID: 500-258038-7

Date Collected: 10/08/24 09:15

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0441	U	0.0685	0.0686	1.00	0.118	pCi/L	10/11/24 08:27	11/04/24 07:48	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	87.8		30 - 110					10/11/24 08:27	11/04/24 07:48	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.823		0.398	0.405	1.00	0.522	pCi/L	10/11/24 08:34	10/25/24 11:59	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	87.8		30 - 110					10/11/24 08:34	10/25/24 11:59	1
Y Carrier	74.4		30 - 110					10/11/24 08:34	10/25/24 11:59	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.867		0.404	0.411	5.00	0.522	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_13

Date Collected: 10/08/24 08:20

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-8

Matrix: Water

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0804	U	0.0842	0.0845	1.00	0.135	pCi/L	10/11/24 08:27	11/04/24 07:48	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	94.7		30 - 110					10/11/24 08:27	11/04/24 07:48	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.783		0.435	0.441	1.00	0.628	pCi/L	10/11/24 08:34	10/25/24 11:59	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	94.7		30 - 110					10/11/24 08:34	10/25/24 11:59	1
Y Carrier	76.6		30 - 110					10/11/24 08:34	10/25/24 11:59	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.863		0.443	0.449	5.00	0.628	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_18&D

Lab Sample ID: 500-258038-9

Date Collected: 10/08/24 12:50

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.152		0.0818	0.0830	1.00	0.0987	pCi/L	10/11/24 08:27	11/04/24 07:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	87.6		30 - 110					10/11/24 08:27	11/04/24 07:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	1.28		0.577	0.589	1.00	0.773	pCi/L	10/11/24 08:34	10/25/24 13:57	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	87.6		30 - 110					10/11/24 08:34	10/25/24 13:57	1
Y Carrier	75.1		30 - 110					10/11/24 08:34	10/25/24 13:57	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	1.43		0.583	0.595	5.00	0.773	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_18#S

Lab Sample ID: 500-258038-10

Date Collected: 10/08/24 11:50

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0332	U	0.0795	0.0796	1.00	0.142	pCi/L	10/11/24 08:27	11/04/24 07:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.9		30 - 110					10/11/24 08:27	11/04/24 07:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.412	U	0.415	0.417	1.00	0.668	pCi/L	10/11/24 08:34	10/25/24 13:57	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.9		30 - 110					10/11/24 08:34	10/25/24 13:57	1
Y Carrier	78.5		30 - 110					10/11/24 08:34	10/25/24 13:57	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.445	U	0.423	0.425	5.00	0.668	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_21R

Lab Sample ID: 500-258038-11

Date Collected: 10/08/24 16:00

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.391		0.149	0.153	1.00	0.162	pCi/L	10/11/24 08:27	11/04/24 07:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	85.6		30 - 110					10/11/24 08:27	11/04/24 07:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.355	U G	0.602	0.603	1.00	1.21	pCi/L	10/11/24 08:34	10/25/24 13:57	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	85.6		30 - 110					10/11/24 08:34	10/25/24 13:57	1
Y Carrier	73.3		30 - 110					10/11/24 08:34	10/25/24 13:57	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.391	U	0.620	0.622	5.00	1.21	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_27

Lab Sample ID: 500-258038-12

Date Collected: 10/08/24 11:55

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.130		0.0787	0.0796	1.00	0.102	pCi/L	10/11/24 08:27	11/04/24 07:46	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	90.9		30 - 110					10/11/24 08:27	11/04/24 07:46	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.0641	U	0.414	0.414	1.00	0.757	pCi/L	10/11/24 08:34	10/25/24 13:58	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	90.9		30 - 110					10/11/24 08:34	10/25/24 13:58	1
Y Carrier	76.6		30 - 110					10/11/24 08:34	10/25/24 13:58	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.194	U	0.421	0.422	5.00	0.757	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
JEN 1045908
SDG: HEN_000_RAD

Client Sample ID: HEN_32

Lab Sample ID: 500-258038-13

Date Collected: 10/08/24 11:05

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0808	U	0.0653	0.0657	1.00	0.0942	pCi/L	10/11/24 08:27	11/04/24 09:28	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.1		30 - 110					10/11/24 08:27	11/04/24 09:28	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.0357	U	0.363	0.363	1.00	0.677	pCi/L	10/11/24 08:34	10/25/24 13:58	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.1		30 - 110					10/11/24 08:34	10/25/24 13:58	1
Y Carrier	77.0		30 - 110					10/11/24 08:34	10/25/24 13:58	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.116	U	0.369	0.369	5.00	0.677	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
JEN 1045908
SDG: HEN_000_RAD

Client Sample ID: HEN_34

Lab Sample ID: 500-258038-14

Date Collected: 10/08/24 13:45

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.173		0.106	0.107	1.00	0.151	pCi/L	10/11/24 08:27	11/04/24 09:28	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	86.1		30 - 110					10/11/24 08:27	11/04/24 09:28	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.621	U	0.538	0.541	1.00	0.845	pCi/L	10/11/24 08:34	10/25/24 13:58	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	86.1		30 - 110					10/11/24 08:34	10/25/24 13:58	1
Y Carrier	71.0		30 - 110					10/11/24 08:34	10/25/24 13:58	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.794	U	0.548	0.551	5.00	0.845	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_35

Lab Sample ID: 500-258038-15

Date Collected: 10/08/24 14:35

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0704	U	0.0710	0.0713	1.00	0.112	pCi/L	10/11/24 08:27	11/04/24 09:28	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	95.2		30 - 110					10/11/24 08:27	11/04/24 09:28	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.157	U	0.372	0.373	1.00	0.738	pCi/L	10/11/24 08:34	10/25/24 13:58	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	95.2		30 - 110					10/11/24 08:34	10/25/24 13:58	1
Y Carrier	76.3		30 - 110					10/11/24 08:34	10/25/24 13:58	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.0704	U	0.379	0.380	5.00	0.738	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_35_FD

Lab Sample ID: 500-258038-16

Date Collected: 10/08/24 14:40

Matrix: Water

Date Received: 10/09/24 12:00

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0787	U	0.0631	0.0635	1.00	0.0900	pCi/L	10/11/24 08:27	11/04/24 09:29	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	90.6		30 - 110					10/11/24 08:27	11/04/24 09:29	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.287	U	0.483	0.483	1.00	0.828	pCi/L	10/11/24 08:34	10/25/24 13:58	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	90.6		30 - 110					10/11/24 08:34	10/25/24 13:58	1
Y Carrier	66.2		30 - 110					10/11/24 08:34	10/25/24 13:58	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.365	U	0.487	0.487	5.00	0.828	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_03R

Lab Sample ID: 500-258038-19

Date Collected: 10/09/24 10:15

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0519	U	0.0780	0.0782	1.00	0.134	pCi/L	10/14/24 08:32	11/05/24 09:41	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	87.8		30 - 110					10/14/24 08:32	11/05/24 09:41	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.382	U	0.354	0.356	1.00	0.559	pCi/L	10/14/24 08:36	10/28/24 12:26	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	87.8		30 - 110					10/14/24 08:36	10/28/24 12:26	1
Y Carrier	79.3		30 - 110					10/14/24 08:36	10/28/24 12:26	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.434	U	0.362	0.364	5.00	0.559	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_03R_FD

Lab Sample ID: 500-258038-20

Date Collected: 10/09/24 10:30

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.187		0.0975	0.0990	1.00	0.117	pCi/L	10/14/24 08:32	11/05/24 09:41	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	80.8		30 - 110					10/14/24 08:32	11/05/24 09:41	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.748		0.452	0.457	1.00	0.653	pCi/L	10/14/24 08:36	10/28/24 12:26	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	80.8		30 - 110					10/14/24 08:36	10/28/24 12:26	1
Y Carrier	77.0		30 - 110					10/14/24 08:36	10/28/24 12:26	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.935		0.462	0.468	5.00	0.653	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
JEN 1045908
SDG: HEN_000_RAD

Client Sample ID: HEN_16

Date Collected: 10/09/24 15:05

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-21

Matrix: Water

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0589	U	0.0723	0.0725	1.00	0.119	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	79.7		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.0977	U	0.360	0.360	1.00	0.652	pCi/L	10/14/24 08:43	10/30/24 11:56	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	79.7		30 - 110					10/14/24 08:43	10/30/24 11:56	1
Y Carrier	73.6		30 - 110					10/14/24 08:43	10/30/24 11:56	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.157	U	0.367	0.367	5.00	0.652	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_16_FD

Lab Sample ID: 500-258038-22

Date Collected: 10/09/24 15:20

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0641	U	0.0715	0.0717	1.00	0.115	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	85.8		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.261	U	0.421	0.421	1.00	0.716	pCi/L	10/14/24 08:43	10/30/24 11:56	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	85.8		30 - 110					10/14/24 08:43	10/30/24 11:56	1
Y Carrier	70.7		30 - 110					10/14/24 08:43	10/30/24 11:56	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.325	U	0.427	0.427	5.00	0.716	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_17

Lab Sample ID: 500-258038-23

Date Collected: 10/09/24 14:10

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.140		0.0905	0.0914	1.00	0.121	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	80.3		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.302	U	0.447	0.448	1.00	0.755	pCi/L	10/14/24 08:43	10/30/24 11:56	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	80.3		30 - 110					10/14/24 08:43	10/30/24 11:56	1
Y Carrier	75.1		30 - 110					10/14/24 08:43	10/30/24 11:56	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.442	U	0.456	0.457	5.00	0.755	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
JEN 1045908
SDG: HEN_000_RAD

Client Sample ID: HEN_22

Lab Sample ID: 500-258038-24

Date Collected: 10/09/24 14:25

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0222	U	0.0616	0.0617	1.00	0.116	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	87.8		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.0675	U	0.319	0.319	1.00	0.620	pCi/L	10/14/24 08:43	10/30/24 11:56	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	87.8		30 - 110					10/14/24 08:43	10/30/24 11:56	1
Y Carrier	74.8		30 - 110					10/14/24 08:43	10/30/24 11:56	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.0222	U	0.325	0.325	5.00	0.620	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_22&D

Lab Sample ID: 500-258038-25

Date Collected: 10/09/24 13:50

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.620		0.167	0.176	1.00	0.150	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	87.1		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.971		0.506	0.514	1.00	0.727	pCi/L	10/14/24 08:43	10/30/24 11:56	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	87.1		30 - 110					10/14/24 08:43	10/30/24 11:56	1
Y Carrier	76.6		30 - 110					10/14/24 08:43	10/30/24 11:56	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	1.59		0.533	0.543	5.00	0.727	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_23

Lab Sample ID: 500-258038-26

Date Collected: 10/09/24 10:15

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0934	U	0.0761	0.0766	1.00	0.111	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	84.3		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.0717	U	0.365	0.365	1.00	0.668	pCi/L	10/14/24 08:43	10/30/24 11:58	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	84.3		30 - 110					10/14/24 08:43	10/30/24 11:58	1
Y Carrier	70.3		30 - 110					10/14/24 08:43	10/30/24 11:58	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.165	U	0.373	0.373	5.00	0.668	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_45#S

Lab Sample ID: 500-258038-27

Date Collected: 10/09/24 09:00

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0985	U	0.0993	0.0997	1.00	0.157	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	77.2		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.128	U	0.411	0.411	1.00	0.804	pCi/L	10/14/24 08:43	10/30/24 11:58	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	77.2		30 - 110					10/14/24 08:43	10/30/24 11:58	1
Y Carrier	68.8		30 - 110					10/14/24 08:43	10/30/24 11:58	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.0985	U	0.423	0.423	5.00	0.804	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_46

Lab Sample ID: 500-258038-28

Date Collected: 10/09/24 11:30

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.183		0.101	0.103	1.00	0.125	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	75.2		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.343	U	0.553	0.554	1.00	0.939	pCi/L	10/14/24 08:43	10/30/24 11:57	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	75.2		30 - 110					10/14/24 08:43	10/30/24 11:57	1
Y Carrier	66.2		30 - 110					10/14/24 08:43	10/30/24 11:57	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.526	U	0.562	0.563	5.00	0.939	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_47

Lab Sample ID: 500-258038-29

Date Collected: 10/09/24 12:40

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0991	U	0.0861	0.0866	1.00	0.130	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	84.8		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.649		0.431	0.435	1.00	0.645	pCi/L	10/14/24 08:43	10/30/24 11:57	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	84.8		30 - 110					10/14/24 08:43	10/30/24 11:57	1
Y Carrier	77.8		30 - 110					10/14/24 08:43	10/30/24 11:57	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.748		0.440	0.444	5.00	0.645	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_49

Lab Sample ID: 500-258038-30

Date Collected: 10/09/24 11:05

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0560	U	0.0880	0.0881	1.00	0.151	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.6		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.00561	U	0.317	0.317	1.00	0.607	pCi/L	10/14/24 08:43	10/30/24 11:57	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	91.6		30 - 110					10/14/24 08:43	10/30/24 11:57	1
Y Carrier	66.9		30 - 110					10/14/24 08:43	10/30/24 11:57	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.0560	U	0.329	0.329	5.00	0.607	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
JEN 1045908
SDG: HEN_000_RAD

Client Sample ID: HEN_50

Lab Sample ID: 500-258038-31

Date Collected: 10/09/24 13:05

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.313		0.121	0.124	1.00	0.126	pCi/L	10/14/24 08:37	11/06/24 22:44	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	78.5		30 - 110					10/14/24 08:37	11/06/24 22:44	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.603	U	0.518	0.521	1.00	0.814	pCi/L	10/14/24 08:43	10/30/24 11:58	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	78.5		30 - 110					10/14/24 08:43	10/30/24 11:58	1
Y Carrier	66.9		30 - 110					10/14/24 08:43	10/30/24 11:58	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.917		0.532	0.536	5.00	0.814	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_51

Lab Sample ID: 500-258038-32

Date Collected: 10/09/24 09:05

Matrix: Water

Date Received: 10/10/24 11:10

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.776		0.210	0.221	1.00	0.181	pCi/L	10/14/24 08:37	11/06/24 22:44	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	78.0		30 - 110					10/14/24 08:37	11/06/24 22:44	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.778	U	0.588	0.592	1.00	0.890	pCi/L	10/14/24 08:43	10/30/24 11:58	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	78.0		30 - 110					10/14/24 08:43	10/30/24 11:58	1
Y Carrier	69.9		30 - 110					10/14/24 08:43	10/30/24 11:58	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	1.55		0.624	0.632	5.00	0.890	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_07

Lab Sample ID: 500-258038-33

Date Collected: 10/10/24 09:20

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.193		0.113	0.114	1.00	0.154	pCi/L	10/14/24 08:37	11/06/24 22:44	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	81.5		30 - 110					10/14/24 08:37	11/06/24 22:44	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.213	U	0.368	0.369	1.00	0.635	pCi/L	10/14/24 08:43	10/30/24 11:59	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	81.5		30 - 110					10/14/24 08:43	10/30/24 11:59	1
Y Carrier	73.6		30 - 110					10/14/24 08:43	10/30/24 11:59	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.406	U	0.385	0.386	5.00	0.635	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_08

Lab Sample ID: 500-258038-34

Date Collected: 10/10/24 09:20

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.259		0.135	0.137	1.00	0.169	pCi/L	10/14/24 08:37	11/06/24 22:44	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	60.3		30 - 110					10/14/24 08:37	11/06/24 22:44	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.808	U	0.580	0.584	1.00	0.874	pCi/L	10/14/24 08:43	10/30/24 11:59	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	60.3		30 - 110					10/14/24 08:43	10/30/24 11:59	1
Y Carrier	73.3		30 - 110					10/14/24 08:43	10/30/24 11:59	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	1.07		0.596	0.600	5.00	0.874	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_52

Lab Sample ID: 500-258038-35

Date Collected: 10/10/24 08:10

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.125	U	0.0886	0.0893	1.00	0.126	pCi/L	10/14/24 08:37	11/06/24 22:44	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	88.6		30 - 110					10/14/24 08:37	11/06/24 22:44	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.334	U	0.372	0.374	1.00	0.609	pCi/L	10/14/24 08:43	10/30/24 11:59	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	88.6		30 - 110					10/14/24 08:43	10/30/24 11:59	1
Y Carrier	76.3		30 - 110					10/14/24 08:43	10/30/24 11:59	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.459	U	0.382	0.385	5.00	0.609	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
JEN 10/24/2024
SDG: HEN_000_RAD

Client Sample ID: HEN_54

Lab Sample ID: 500-258038-36

Date Collected: 10/10/24 08:15

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0443	U	0.0586	0.0588	1.00	0.0979	pCi/L	10/14/24 08:37	11/06/24 22:46	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	90.1		30 - 110					10/14/24 08:37	11/06/24 22:46	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.0836	U	0.313	0.313	1.00	0.568	pCi/L	10/14/24 08:43	10/30/24 11:59	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	90.1		30 - 110					10/14/24 08:43	10/30/24 11:59	1
Y Carrier	75.1		30 - 110					10/14/24 08:43	10/30/24 11:59	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.128	U	0.318	0.318	5.00	0.568	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_54_FD

Lab Sample ID: 500-258038-37

Date Collected: 10/10/24 08:25

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.0909	U	0.103	0.104	1.00	0.169	pCi/L	10/14/24 08:37	11/06/24 22:46	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	81.8		30 - 110					10/14/24 08:37	11/06/24 22:46	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.291	U	0.344	0.345	1.00	0.565	pCi/L	10/14/24 08:43	10/30/24 11:59	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	81.8		30 - 110					10/14/24 08:43	10/30/24 11:59	1
Y Carrier	79.3		30 - 110					10/14/24 08:43	10/30/24 11:59	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.382	U	0.359	0.360	5.00	0.565	pCi/L		11/08/24 12:52	1

Client Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
245 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
JEN 10/24/2024
SDG: HEN_000_RAD

Client Sample ID: HEN_FB

Lab Sample ID: 500-258038-38

Date Collected: 10/10/24 09:00

Matrix: Water

Date Received: 10/10/24 12:46

Method: EPA 903.0 - Radium-226 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	-0.000865	U	0.0480	0.0480	1.00	0.105	pCi/L	10/14/24 08:37	11/06/24 22:47	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	79.0		30 - 110					10/14/24 08:37	11/06/24 22:47	1

Method: EPA 904.0 - Radium-228 (GFPC)

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.297	U	0.378	0.379	1.00	0.629	pCi/L	10/14/24 08:43	10/30/24 11:59	1
Carrier	%Yield	Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	79.0		30 - 110					10/14/24 08:43	10/30/24 11:59	1
Y Carrier	72.5		30 - 110					10/14/24 08:43	10/30/24 11:59	1

Method: TAL-STL Ra226_Ra228 Pos - Combined Radium-226 and Radium-228

Analyte	Result	Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium 226 and 228	0.297	U	0.381	0.382	5.00	0.629	pCi/L		11/08/24 12:52	1

Definitions/Glossary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
JEN-24-5808
SDG: HEN_000_RAD

Qualifiers

Rad

Qualifier	Qualifier Description
G	The Sample MDC is greater than the requested RL.
U	Result is less than the sample detection limit.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
☼	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

QC Association Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Rad

Prep Batch: 683227

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total/NA	Water	PrecSep-21	
500-258038-7	HEN_12	Total/NA	Water	PrecSep-21	
500-258038-8	HEN_13	Total/NA	Water	PrecSep-21	
500-258038-9	HEN_18&D	Total/NA	Water	PrecSep-21	
500-258038-10	HEN_18#S	Total/NA	Water	PrecSep-21	
500-258038-11	HEN_21R	Total/NA	Water	PrecSep-21	
500-258038-12	HEN_27	Total/NA	Water	PrecSep-21	
500-258038-13	HEN_32	Total/NA	Water	PrecSep-21	
500-258038-14	HEN_34	Total/NA	Water	PrecSep-21	
500-258038-15	HEN_35	Total/NA	Water	PrecSep-21	
500-258038-16	HEN_35_FD	Total/NA	Water	PrecSep-21	
MB 160-683227/1-A	Method Blank	Total/NA	Water	PrecSep-21	
LCS 160-683227/2-A	Lab Control Sample	Total/NA	Water	PrecSep-21	
500-258038-11 MS	HEN_21R_MS	Total/NA	Water	PrecSep-21	
500-258038-11 MSD	HEN_21R-MSD	Total/NA	Water	PrecSep-21	

Prep Batch: 683228

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-6	HEN_08&D	Total/NA	Water	PrecSep_0	
500-258038-7	HEN_12	Total/NA	Water	PrecSep_0	
500-258038-8	HEN_13	Total/NA	Water	PrecSep_0	
500-258038-9	HEN_18&D	Total/NA	Water	PrecSep_0	
500-258038-10	HEN_18#S	Total/NA	Water	PrecSep_0	
500-258038-11	HEN_21R	Total/NA	Water	PrecSep_0	
500-258038-12	HEN_27	Total/NA	Water	PrecSep_0	
500-258038-13	HEN_32	Total/NA	Water	PrecSep_0	
500-258038-14	HEN_34	Total/NA	Water	PrecSep_0	
500-258038-15	HEN_35	Total/NA	Water	PrecSep_0	
500-258038-16	HEN_35_FD	Total/NA	Water	PrecSep_0	
MB 160-683228/1-A	Method Blank	Total/NA	Water	PrecSep_0	
LCS 160-683228/2-A	Lab Control Sample	Total/NA	Water	PrecSep_0	
500-258038-11 MS	HEN_21R_MS	Total/NA	Water	PrecSep_0	
500-258038-11 MSD	HEN_21R-MSD	Total/NA	Water	PrecSep_0	

Prep Batch: 683389

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-19	HEN_03R	Total/NA	Water	PrecSep-21	
500-258038-20	HEN_03R_FD	Total/NA	Water	PrecSep-21	
MB 160-683389/1-A	Method Blank	Total/NA	Water	PrecSep-21	
LCS 160-683389/2-A	Lab Control Sample	Total/NA	Water	PrecSep-21	

Prep Batch: 683390

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-19	HEN_03R	Total/NA	Water	PrecSep_0	
500-258038-20	HEN_03R_FD	Total/NA	Water	PrecSep_0	
MB 160-683390/1-A	Method Blank	Total/NA	Water	PrecSep_0	
LCS 160-683390/2-A	Lab Control Sample	Total/NA	Water	PrecSep_0	

Prep Batch: 683391

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-21	HEN_16	Total/NA	Water	PrecSep-21	

Eurofins Chicago

QC Association Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Rad (Continued)

Prep Batch: 683391 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-22	HEN_16_FD	Total/NA	Water	PrecSep-21	
500-258038-23	HEN_17	Total/NA	Water	PrecSep-21	
500-258038-24	HEN_22	Total/NA	Water	PrecSep-21	
500-258038-25	HEN_22&D	Total/NA	Water	PrecSep-21	
500-258038-26	HEN_23	Total/NA	Water	PrecSep-21	
500-258038-27	HEN_45#S	Total/NA	Water	PrecSep-21	
500-258038-28	HEN_46	Total/NA	Water	PrecSep-21	
500-258038-29	HEN_47	Total/NA	Water	PrecSep-21	
500-258038-30	HEN_49	Total/NA	Water	PrecSep-21	
500-258038-31	HEN_50	Total/NA	Water	PrecSep-21	
500-258038-32	HEN_51	Total/NA	Water	PrecSep-21	
500-258038-33	HEN_07	Total/NA	Water	PrecSep-21	
500-258038-34	HEN_08	Total/NA	Water	PrecSep-21	
500-258038-35	HEN_52	Total/NA	Water	PrecSep-21	
500-258038-36	HEN_54	Total/NA	Water	PrecSep-21	
500-258038-37	HEN_54_FD	Total/NA	Water	PrecSep-21	
500-258038-38	HEN_FB	Total/NA	Water	PrecSep-21	
MB 160-683391/1-A	Method Blank	Total/NA	Water	PrecSep-21	
LCS 160-683391/2-A	Lab Control Sample	Total/NA	Water	PrecSep-21	
500-258038-30 MS	HEN_49_MS	Total/NA	Water	PrecSep-21	
500-258038-30 MSD	HEN_49_MSD	Total/NA	Water	PrecSep-21	

Prep Batch: 683393

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-258038-21	HEN_16	Total/NA	Water	PrecSep_0	
500-258038-22	HEN_16_FD	Total/NA	Water	PrecSep_0	
500-258038-23	HEN_17	Total/NA	Water	PrecSep_0	
500-258038-24	HEN_22	Total/NA	Water	PrecSep_0	
500-258038-25	HEN_22&D	Total/NA	Water	PrecSep_0	
500-258038-26	HEN_23	Total/NA	Water	PrecSep_0	
500-258038-27	HEN_45#S	Total/NA	Water	PrecSep_0	
500-258038-28	HEN_46	Total/NA	Water	PrecSep_0	
500-258038-29	HEN_47	Total/NA	Water	PrecSep_0	
500-258038-30	HEN_49	Total/NA	Water	PrecSep_0	
500-258038-31	HEN_50	Total/NA	Water	PrecSep_0	
500-258038-32	HEN_51	Total/NA	Water	PrecSep_0	
500-258038-33	HEN_07	Total/NA	Water	PrecSep_0	
500-258038-34	HEN_08	Total/NA	Water	PrecSep_0	
500-258038-35	HEN_52	Total/NA	Water	PrecSep_0	
500-258038-36	HEN_54	Total/NA	Water	PrecSep_0	
500-258038-37	HEN_54_FD	Total/NA	Water	PrecSep_0	
500-258038-38	HEN_FB	Total/NA	Water	PrecSep_0	
MB 160-683393/1-A	Method Blank	Total/NA	Water	PrecSep_0	
LCS 160-683393/2-A	Lab Control Sample	Total/NA	Water	PrecSep_0	
500-258038-30 MS	HEN_49_MS	Total/NA	Water	PrecSep_0	
500-258038-30 MSD	HEN_49_MSD	Total/NA	Water	PrecSep_0	

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
JEN-24-500
SDG: HEN_000_RAD

Method: 903.0 - Radium-226 (GFPC)

Lab Sample ID: MB 160-683227/1-A
Matrix: Water
Analysis Batch: 686661

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 683227

Analyte	MB Result	MB Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.03637	U	0.0528	0.0529	1.00	0.0902	pCi/L	10/11/24 08:27	11/04/24 07:47	1
Carrier	MB %Yield	MB Qualifier	Limits					Prepared	Analyzed	Dil Fac
Ba Carrier	99.7		30 - 110					10/11/24 08:27	11/04/24 07:47	1

Lab Sample ID: LCS 160-683227/2-A
Matrix: Water
Analysis Batch: 686661

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 683227

Analyte		Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits
Radium-226		9.58	7.872		0.863	1.00	0.121	pCi/L	82	75 - 125
Carrier	LCS %Yield	LCS Qualifier	Limits							
Ba Carrier	96.2		30 - 110							

Lab Sample ID: 500-258038-11 MS
Matrix: Water
Analysis Batch: 686653

Client Sample ID: HEN_21R_MS
Prep Type: Total/NA
Prep Batch: 683227

Analyte	Sample Result	Sample Qual	Spike Added	MS Result	MS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits
Radium-226	0.391		12.6	13.58		1.43	1.00	0.126	pCi/L	105	60 - 140
Carrier	MS %Yield	MS Qualifier	Limits								
Ba Carrier	83.8		30 - 110								

Lab Sample ID: 500-258038-11 MSD
Matrix: Water
Analysis Batch: 686653

Client Sample ID: HEN_21R-MSD
Prep Type: Total/NA
Prep Batch: 683227

Analyte	Sample Result	Sample Qual	Spike Added	MSD Result	MSD Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits	RER	RER Limit
Radium-226	0.391		12.6	11.97		1.27	1.00	0.133	pCi/L	92	60 - 140	0.60	1
Carrier	MSD %Yield	MSD Qualifier	Limits										
Ba Carrier	89.6		30 - 110										

Lab Sample ID: MB 160-683389/1-A
Matrix: Water
Analysis Batch: 686864

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 683389

Analyte	MB Result	MB Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.05131	U	0.0621	0.0622	1.00	0.102	pCi/L	10/14/24 08:32	11/05/24 07:52	1

Eurofins Chicago

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 590-258038-2
JEN 11/14/2024
SDG: HEN_000_RAD

Method: 903.0 - Radium-226 (GFPC) (Continued)

Lab Sample ID: MB 160-683389/1-A
Matrix: Water
Analysis Batch: 686864

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 683389

	MB	MB									
Carrier	%Yield	Qualifier	Limits	Prepared	Analyzed	Dil Fac					
Ba Carrier	94.9		30 - 110	10/14/24 08:32	11/05/24 07:52	1					

Lab Sample ID: LCS 160-683389/2-A
Matrix: Water
Analysis Batch: 686864

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 683389

Analyte		Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-226		9.58	8.968		0.973	1.00	0.126	pCi/L	94	75 - 125		
Carrier	LCS	LCS										
%Yield	Qualifier	Limits										
Ba Carrier	86.6		30 - 110									

Lab Sample ID: MB 160-683391/1-A
Matrix: Water
Analysis Batch: 687156

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 683391

Analyte	MB	MB	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-226	0.02339	U	0.0627	0.0627	1.00	0.117	pCi/L	10/14/24 08:37	11/06/24 22:45	1
Carrier	MB	MB								
%Yield	Qualifier	Limits								
Ba Carrier	89.9		30 - 110					10/14/24 08:37	11/06/24 22:45	1

Lab Sample ID: LCS 160-683391/2-A
Matrix: Water
Analysis Batch: 687156

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 683391

Analyte		Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-226		9.58	8.649		0.943	1.00	0.145	pCi/L	90	75 - 125		
Carrier	LCS	LCS										
%Yield	Qualifier	Limits										
Ba Carrier	92.9		30 - 110									

Lab Sample ID: 500-258038-30 MS
Matrix: Water
Analysis Batch: 687157

Client Sample ID: HEN_49_MS
Prep Type: Total/NA
Prep Batch: 683391

Analyte	Sample Result	Sample Qual	Spike Added	MS Result	MS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-226	0.0560	U	9.65	9.233		0.993	1.00	0.138	pCi/L	95	60 - 140		
Carrier	MS	MS											
%Yield	Qualifier	Limits											
Ba Carrier	87.3		30 - 110										

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Method: 903.0 - Radium-226 (GFPC) (Continued)

Lab Sample ID: 500-258038-30 MSD
Matrix: Water
Analysis Batch: 687157

Client Sample ID: HEN_49_MSD
Prep Type: Total/NA
Prep Batch: 683391

Analyte	Sample Result	Sample Qual	Spike Added	MSD Result	MSD Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits	RER	RER Limit
Radium-226	0.0560	U	9.66	9.157		0.993	1.00	0.134	pCi/L	94	60 - 140	0.04	1
Carrier	MSD %Yield	MSD Qualifier	MSD Limits										
Ba Carrier	85.3		30 - 110										

Method: 904.0 - Radium-228 (GFPC)

Lab Sample ID: MB 160-683228/1-A
Matrix: Water
Analysis Batch: 685117

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 683228

Analyte	MB Result	MB Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.3798	U	0.330	0.331	1.00	0.518	pCi/L	10/11/24 08:34	10/25/24 11:58	1
Carrier	MB %Yield	MB Qualifier	MB Limits							
Ba Carrier	99.7		30 - 110							
Y Carrier	78.1		30 - 110							

Lab Sample ID: LCS 160-683228/2-A
Matrix: Water
Analysis Batch: 685117

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 683228

Analyte	Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits
Radium-228	8.40	10.41		1.38	1.00	0.560	pCi/L	124	75 - 125
Carrier	LCS %Yield	LCS Qualifier	LCS Limits						
Ba Carrier	96.2		30 - 110						
Y Carrier	80.4		30 - 110						

Lab Sample ID: 500-258038-11 MS
Matrix: Water
Analysis Batch: 685116

Client Sample ID: HEN_21R_MS
Prep Type: Total/NA
Prep Batch: 683228

Analyte	Sample Result	Sample Qual	Spike Added	MS Result	MS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits
Radium-228	-0.355	U G	11.1	13.37		2.00	1.00	1.08	pCi/L	121	60 - 140
Carrier	MS %Yield	MS Qualifier	MS Limits								
Ba Carrier	83.8		30 - 110								
Y Carrier	81.9		30 - 110								

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Method: 904.0 - Radium-228 (GFPC) (Continued)

Lab Sample ID: 500-258038-11 MSD
Matrix: Water
Analysis Batch: 685116

Client Sample ID: HEN_21R-MSD
Prep Type: Total/NA
Prep Batch: 683228

Analyte	Sample Result	Sample Qual	Spike Added	MSD Result	MSD Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits	RER	RER Limit
Radium-228	-0.355	U G	11.0	14.38		2.12	1.00	1.08	pCi/L	130	60 - 140	0.24	1
MSD MSD													
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	89.6		30 - 110										
Y Carrier	75.1		30 - 110										

Lab Sample ID: MB 160-683390/1-A
Matrix: Water
Analysis Batch: 685399

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 683390

Analyte	MB Result	MB Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	0.4790	U	0.362	0.364	1.00	0.554	pCi/L	10/14/24 08:36	10/28/24 12:21	1
MB MB										
Carrier	%Yield	Qualifier	Limits							
Ba Carrier	94.9		30 - 110							
Y Carrier	80.4		30 - 110							
								Prepared	Analyzed	Dil Fac
								10/14/24 08:36	10/28/24 12:21	1
								10/14/24 08:36	10/28/24 12:21	1

Lab Sample ID: LCS 160-683390/2-A
Matrix: Water
Analysis Batch: 685399

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 683390

Analyte	Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits
Radium-228	8.39	10.02		1.44	1.00	0.607	pCi/L	119	75 - 125
LCS LCS									
Carrier	%Yield	Qualifier	Limits						
Ba Carrier	86.6		30 - 110						
Y Carrier	75.1		30 - 110						

Lab Sample ID: MB 160-683393/1-A
Matrix: Water
Analysis Batch: 685861

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 683393

Analyte	MB Result	MB Qualifier	Count Uncert. (2σ+/-)	Total Uncert. (2σ+/-)	RL	MDC	Unit	Prepared	Analyzed	Dil Fac
Radium-228	-0.1309	U	0.286	0.286	1.00	0.580	pCi/L	10/14/24 08:43	10/30/24 11:56	1
MB MB										
Carrier	%Yield	Qualifier	Limits							
Ba Carrier	89.9		30 - 110							
Y Carrier	76.6		30 - 110							
								Prepared	Analyzed	Dil Fac
								10/14/24 08:43	10/30/24 11:56	1
								10/14/24 08:43	10/30/24 11:56	1

QC Sample Results

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Method: 904.0 - Radium-228 (GFPC) (Continued)

Lab Sample ID: LCS 160-683393/2-A
Matrix: Water
Analysis Batch: 685861

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 683393

Analyte			Spike Added	LCS Result	LCS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-228			8.39	8.965		1.26	1.00	0.494	pCi/L	107	75 - 125		
	LCS	LCS											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	92.9		30 - 110										
Y Carrier	78.1		30 - 110										

Lab Sample ID: 500-258038-30 MS
Matrix: Water
Analysis Batch: 685861

Client Sample ID: HEN_49_MS
Prep Type: Total/NA
Prep Batch: 683393

Analyte	Sample Result	Sample Qual	Spike Added	MS Result	MS Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits		
Radium-228	-0.00561	U	8.45	9.751		1.35	1.00	0.545	pCi/L	115	60 - 140		
	MS	MS											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	87.3		30 - 110										
Y Carrier	82.6		30 - 110										

Lab Sample ID: 500-258038-30 MSD
Matrix: Water
Analysis Batch: 685861

Client Sample ID: HEN_49_MSD
Prep Type: Total/NA
Prep Batch: 683393

Analyte	Sample Result	Sample Qual	Spike Added	MSD Result	MSD Qual	Total Uncert. (2σ+/-)	RL	MDC	Unit	%Rec	%Rec Limits	RER	RER Limit
Radium-228	-0.00561	U	8.45	8.691		1.31	1.00	0.657	pCi/L	103	60 - 140	0.40	1
	MSD	MSD											
Carrier	%Yield	Qualifier	Limits										
Ba Carrier	85.3		30 - 110										
Y Carrier	72.5		30 - 110										

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_08&D

Date Collected: 10/08/24 08:15

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-6

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686661	SWS	EET SL	11/04/24 07:48
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685117	FLC	EET SL	10/25/24 11:59
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_12

Date Collected: 10/08/24 09:15

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-7

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686661	SWS	EET SL	11/04/24 07:48
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685117	FLC	EET SL	10/25/24 11:59
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_13

Date Collected: 10/08/24 08:20

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-8

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686661	SWS	EET SL	11/04/24 07:48
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685117	FLC	EET SL	10/25/24 11:59
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_18&D

Date Collected: 10/08/24 12:50

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-9

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686653	SWS	EET SL	11/04/24 07:45
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685116	FLC	EET SL	10/25/24 13:57
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_18#S

Lab Sample ID: 500-258038-10

Date Collected: 10/08/24 11:50

Matrix: Water

Date Received: 10/09/24 12:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686653	SWS	EET SL	11/04/24 07:45
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685116	FLC	EET SL	10/25/24 13:57
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_21R

Lab Sample ID: 500-258038-11

Date Collected: 10/08/24 16:00

Matrix: Water

Date Received: 10/09/24 12:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686653	SWS	EET SL	11/04/24 07:45
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685116	FLC	EET SL	10/25/24 13:57
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_27

Lab Sample ID: 500-258038-12

Date Collected: 10/08/24 11:55

Matrix: Water

Date Received: 10/09/24 12:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686653	SWS	EET SL	11/04/24 07:46
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685116	FLC	EET SL	10/25/24 13:58
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_32

Lab Sample ID: 500-258038-13

Date Collected: 10/08/24 11:05

Matrix: Water

Date Received: 10/09/24 12:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686653	SWS	EET SL	11/04/24 09:28
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685116	FLC	EET SL	10/25/24 13:58
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_34

Date Collected: 10/08/24 13:45

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-14

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686653	SWS	EET SL	11/04/24 09:28
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685116	FLC	EET SL	10/25/24 13:58
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_35

Date Collected: 10/08/24 14:35

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-15

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686653	SWS	EET SL	11/04/24 09:28
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685116	FLC	EET SL	10/25/24 13:58
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_35_FD

Date Collected: 10/08/24 14:40

Date Received: 10/09/24 12:00

Lab Sample ID: 500-258038-16

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683227	BCE	EET SL	10/11/24 08:27
Total/NA	Analysis	903.0		1	686653	SWS	EET SL	11/04/24 09:29
Total/NA	Prep	PrecSep_0			683228	BCE	EET SL	10/11/24 08:34
Total/NA	Analysis	904.0		1	685116	FLC	EET SL	10/25/24 13:58
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_03R

Date Collected: 10/09/24 10:15

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-19

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683389	BCE	EET SL	10/14/24 08:32
Total/NA	Analysis	903.0		1	686864	CMM	EET SL	11/05/24 09:41
Total/NA	Prep	PrecSep_0			683390	BCE	EET SL	10/14/24 08:36
Total/NA	Analysis	904.0		1	685385	FLC	EET SL	10/28/24 12:26
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_03R_FD

Lab Sample ID: 500-258038-20

Date Collected: 10/09/24 10:30

Matrix: Water

Date Received: 10/10/24 11:10

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683389	BCE	EET SL	10/14/24 08:32
Total/NA	Analysis	903.0		1	686864	CMM	EET SL	11/05/24 09:41
Total/NA	Prep	PrecSep_0			683390	BCE	EET SL	10/14/24 08:36
Total/NA	Analysis	904.0		1	685385	FLC	EET SL	10/28/24 12:26
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_16

Lab Sample ID: 500-258038-21

Date Collected: 10/09/24 15:05

Matrix: Water

Date Received: 10/10/24 11:10

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687156	SWS	EET SL	11/06/24 22:45
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:56
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_16_FD

Lab Sample ID: 500-258038-22

Date Collected: 10/09/24 15:20

Matrix: Water

Date Received: 10/10/24 11:10

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687156	SWS	EET SL	11/06/24 22:45
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:56
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_17

Lab Sample ID: 500-258038-23

Date Collected: 10/09/24 14:10

Matrix: Water

Date Received: 10/10/24 11:10

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687156	SWS	EET SL	11/06/24 22:45
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:56
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_22

Date Collected: 10/09/24 14:25

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-24

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687156	SWS	EET SL	11/06/24 22:45
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:56
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_22&D

Date Collected: 10/09/24 13:50

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-25

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687156	SWS	EET SL	11/06/24 22:45
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:56
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_23

Date Collected: 10/09/24 10:15

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-26

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687156	SWS	EET SL	11/06/24 22:45
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:58
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_45#S

Date Collected: 10/09/24 09:00

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-27

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687156	SWS	EET SL	11/06/24 22:45
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:58
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_46

Date Collected: 10/09/24 11:30

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-28

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687156	SWS	EET SL	11/06/24 22:45
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:57
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_47

Date Collected: 10/09/24 12:40

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-29

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687156	SWS	EET SL	11/06/24 22:45
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:57
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_49

Date Collected: 10/09/24 11:05

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-30

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687156	SWS	EET SL	11/06/24 22:45
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:57
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_50

Date Collected: 10/09/24 13:05

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-31

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687157	SWS	EET SL	11/06/24 22:44
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:58
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_51

Date Collected: 10/09/24 09:05

Date Received: 10/10/24 11:10

Lab Sample ID: 500-258038-32

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687157	SWS	EET SL	11/06/24 22:44
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:58
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_07

Date Collected: 10/10/24 09:20

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-33

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687157	SWS	EET SL	11/06/24 22:44
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:59
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_08

Date Collected: 10/10/24 09:20

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-34

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687157	SWS	EET SL	11/06/24 22:44
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:59
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_52

Date Collected: 10/10/24 08:10

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-35

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687157	SWS	EET SL	11/06/24 22:44
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:59
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Lab Chronicle

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Client Sample ID: HEN_54

Date Collected: 10/10/24 08:15

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-36

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687133	SWS	EET SL	11/06/24 22:46
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:59
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_54_FD

Date Collected: 10/10/24 08:25

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-37

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687133	SWS	EET SL	11/06/24 22:46
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:59
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Client Sample ID: HEN_FB

Date Collected: 10/10/24 09:00

Date Received: 10/10/24 12:46

Lab Sample ID: 500-258038-38

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	PrecSep-21			683391	BCE	EET SL	10/14/24 08:37
Total/NA	Analysis	903.0		1	687133	SWS	EET SL	11/06/24 22:47
Total/NA	Prep	PrecSep_0			683393	BCE	EET SL	10/14/24 08:43
Total/NA	Analysis	904.0		1	685861	FLC	EET SL	10/30/24 11:59
Total/NA	Analysis	Ra226_Ra228 Pos		1	687605	FLC	EET SL	11/08/24 12:52

Laboratory References:

EET SL = Eurofins St. Louis, 13715 Rider Trail North, Earth City, MO 63045, TEL (314)298-8566

Accreditation/Certification Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
15 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 590-258038-2
SDG: HEN_000_RAD

Laboratory: Eurofins St. Louis

Unless otherwise noted, all analytes for this laboratory were covered under each accreditation/certification below.

Authority	Program	Identification Number	Expiration Date
Illinois	NELAP	200023	11-30-25
The following analytes are included in this report, but the laboratory is not certified by the governing authority. This list may include analytes for which the agency does not offer certification.			
Analysis Method	Prep Method	Matrix	Analyte
903.0	PrecSep-21	Water	Radium-226
904.0	PrecSep_0	Water	Radium-228
Ra226_Ra228 Pos		Water	Radium 226 and 228

The Chain-of-Custody is a LEGAL DOCUMENT All relevant fields must be completed accurately

Page 1 of 3

500-258038 COC

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:	
Company:	Vistra Corp-Hennepin	Report To:	Brian Voelker	Attention:	Brian Voelker
Address:	13498 E 800th St Hennepin, IL 61327	Copy To:	Sam Davies samantha.davies@vistracorp.com	Company Name:	Vistra Corp
Email To:	Brian.Voelker@VistraCorp.com	Purchase Order No.:	Jason Stuckey & Michael Oille	Address:	see Section A
Phone:	(217) 753-8911	Project Name:	Jason.Stuckey@vistracorp.com	Quote Reference:	
Fax:		Requested Due Date/TAT:	10 day	Project Manager:	
		Project Number:	50023030	Profile #:	

ITEM #	Section D Required Client Information		Valid Matrix Codes MATRIX CODE DRINKING WATER DW WASTE WATER WW WASTE WATER P PRODUCT SOLID OIL WPE AIR OTHER TISSUE SAMPLE ID (A-Z, 0-9 / -) Sample IDs MUST BE UNIQUE										MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives Unpreserved H₂SO₄ HNO₃ HCl NaOH Na₂S₂O₃ Methanol Other										Y	N	Requested Analysis Filtered (Y/N)										Project No./ Lab I.D.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME		DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS
HEN-24Q4 Rev 0	Sam Davies	10/17/24	0700	Sam Davies	10/18/24	0917	Temp in °C
	Sam Davies	10/18/24	1117	Sam Davies	10/18/24	1117	Received on
	Sam Davies	10/18/24	1117	Sam Davies	10/18/24	1117	Custody
	Sam Davies	10/18/24	1117	Sam Davies	10/18/24	1117	Sealed
	Sam Davies	10/18/24	1117	Sam Davies	10/18/24	1117	Intact (Y/N)

Sample date and default time added - dbn 102824

Signature of SAMPLER: *Sam Davies*

Signature of ANALYST: *Sam Davies*

Signature of WITNESS: *Sam Davies*



The Chain-of-Custody is a LEGAL DOCUMENT All relevant fields must be completed accurately

HENNEPIN POWER PLANT, EAST ASH POND

Page 1 of 3

11/11/24

The Chain-of-Custody is a LEGAL DOCUMENT All relevant fields must be completed accurately

Sample date and default time added - dbn 102824	SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
	PRINT Name of SAMPLER <i>Lorne Filmer</i>					
	SIGNATURE of SAMPLER <i>Lorne Filmer</i>	DATE Signed (MM/DD/YY) <i>10-8-24</i>				

ER Lorne Filewicz

ER. *Some files*

10-8-24

ER Lorne Filewicz

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information

Company: Visira Corp-Hennepin
Address: 13498 E 800th St
Hennepin, IL 61327
Email To: Brian.Voelker@VisiraCorp.com
Phone: (217) 753-8911 Fax: _____
Requested Due Date/TAT: 10 day

Section B Required Project Information

Report To: Brian Voelker
Copy To: Sam Davies samantha.davies@visiracorp.com
Jason Stuckey & Michael Olle
Purchase Order No.: michael.olle@visiracorp.com
Project Name: Jason.Stuckey@visiracorp.com
Project Number: 50023030

Section C Invoice Information

Attention: Brian Voelker
Company Name: Visira Corp
Address: see Section A
Quote Reference: _____
Project Manager: _____
Profile #: _____

Page 1 of 3

REGULATORY AGENCY

NPDES: _____ GROUND WATER: _____ DRINKING WATER: _____
UST: _____ RCRA: _____ OTHER: _____
Site Location: _____ IL: _____
STATE: _____



500-258038 COC

Project No./ Lab I.D.

ITEM #	Section D Required Client Information	Valid Matrix Codes MATRIX CODE DRINKING WATER DW WATER WT WASTE WATER WW PRODUCT P SOIL/SOLID SL OIL OL WIPE WP AIR AR OTHER OT TISSUE TS	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives										Y/N Analysis Test	Requested Analysis Filtered (Y/N)												Residual Chlorine (Y/N)	500-258038 COC																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
					DATE	TIME			Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other	HEN-000-RAD	HEN-257-802		HEN-257-803	HEN-257-804	HEN-811-801	HEN-845-802-805	HEN-845-803	HEN-845-804	HEN-WPCP-East	HEN-WPCP-West	HEN_000																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
	SAMPLE ID (A-Z, 0-9 / -) Sample IDs MUST BE UNIQUE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									</

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS							
HEN-24Q4 Rev 0	<i>Donna F. Lewis</i>	10/10/24	0800	<i>N.J. Elia</i>	10/10/24	0900								
	<i>N.J. Elia</i>	10/10/24	1110	<i>Stephanie Hemondy EETA</i>	10/10/24	1110								
SAMPLER NAME AND SIGNATURE							Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)				
PRINT Name of SAMPLER														
SIGNATURE of SAMPLER														
<i>Donna F. Lewis</i>														
DATE Signed (MM/DD/YY)														
10/10/24														

5.0+4.9, 5.3+5.2, 5.4+5.3, 4.1+4.0
5.1+5.0

The Chain-of-Custody is a LEGAL DOCUMENT All relevant fields must be completed accurately

11/11/24

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page 3 of 3

Site Location	IL	
STATE		

Cooler (Y/N)

Login Sample Receipt Checklist

Client: Vistra Energy Corp

Job Number: 500-258038-2
SDG Number: HEN_000_RAD

Login Number: 258038

List Number: 1

Creator: Hernandez, Stephanie

List Source: Eurofins Chicago

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	Received same day of collection; chilling process has begun.(33-38 sampled10/10)
Cooler Temperature is recorded.	True	1.5,1.5,3.5,3.2,4.2,3.8,4.9,5.2,5.3,4.0,5.0,13.8,5.9
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	False	No sample date and/or time on COC, logged in per container labels.
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	False	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	False	No date or time on COC, logged in per container labels.
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Login Sample Receipt Checklist

Client: Vistra Energy Corp

Job Number: 500-258038-2
SDG Number: HEN_000_RAD

Login Number: 258038

List Number: 4

Creator: Worthington, Sierra M

List Source: Eurofins St. Louis

List Creation: 10/10/24 11:17 AM

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	N/A	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	N/A	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Login Sample Receipt Checklist

Client: Vistra Energy Corp

Job Number: 500-258038-2
SDG Number: HEN_000_RAD

Login Number: 258038

List Number: 6

Creator: Worthington, Sierra M

List Source: Eurofins St. Louis

List Creation: 10/11/24 11:25 AM

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	N/A	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	N/A	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Tracer/Carrier Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Method: 903.0 - Radium-226 (GFPC)

Matrix: Water

Prep Type: Total/NA

		Percent Yield (Acceptance Limits)	
Lab Sample ID	Client Sample ID	Ba (30-110)	
500-258038-6	HEN_08&D	88.6	
500-258038-7	HEN_12	87.8	
500-258038-8	HEN_13	94.7	
500-258038-9	HEN_18&D	87.6	
500-258038-10	HEN_18#S	91.9	
500-258038-11	HEN_21R	85.6	
500-258038-11 MS	HEN_21R_MS	83.8	
500-258038-11 MSD	HEN_21R-MSD	89.6	
500-258038-12	HEN_27	90.9	
500-258038-13	HEN_32	91.1	
500-258038-14	HEN_34	86.1	
500-258038-15	HEN_35	95.2	
500-258038-16	HEN_35_FD	90.6	
500-258038-19	HEN_03R	87.8	
500-258038-20	HEN_03R_FD	80.8	
500-258038-21	HEN_16	79.7	
500-258038-22	HEN_16_FD	85.8	
500-258038-23	HEN_17	80.3	
500-258038-24	HEN_22	87.8	
500-258038-25	HEN_22&D	87.1	
500-258038-26	HEN_23	84.3	
500-258038-27	HEN_45#S	77.2	
500-258038-28	HEN_46	75.2	
500-258038-29	HEN_47	84.8	
500-258038-30	HEN_49	91.6	
500-258038-30 MS	HEN_49_MS	87.3	
500-258038-30 MSD	HEN_49_MSD	85.3	
500-258038-31	HEN_50	78.5	
500-258038-32	HEN_51	78.0	
500-258038-33	HEN_07	81.5	
500-258038-34	HEN_08	60.3	
500-258038-35	HEN_52	88.6	
500-258038-36	HEN_54	90.1	
500-258038-37	HEN_54_FD	81.8	
500-258038-38	HEN_FB	79.0	
LCS 160-683227/2-A	Lab Control Sample	96.2	
LCS 160-683389/2-A	Lab Control Sample	86.6	
LCS 160-683391/2-A	Lab Control Sample	92.9	
MB 160-683227/1-A	Method Blank	99.7	
MB 160-683389/1-A	Method Blank	94.9	
MB 160-683391/1-A	Method Blank	89.9	

Tracer/Carrier Legend

Ba = Ba Carrier

Tracer/Carrier Summary

Client: Vistra Energy Corp
Project/Site: HEN-24Q4

ATTACHMENT B.
845 QUARTERLY REPORT - QUARTER 4, 2024
HENNEPIN POWER PLANT, EAST ASH POND
Job ID: 500-258038-2
SDG: HEN_000_RAD

Method: 904.0 - Radium-228 (GFPC)

Matrix: Water

Prep Type: Total/NA

		Percent Yield (Acceptance Limits)	
Lab Sample ID	Client Sample ID	Ba (30-110)	Y (30-110)
500-258038-6	HEN_08&D	88.6	74.8
500-258038-7	HEN_12	87.8	74.4
500-258038-8	HEN_13	94.7	76.6
500-258038-9	HEN_18&D	87.6	75.1
500-258038-10	HEN_18#S	91.9	78.5
500-258038-11	HEN_21R	85.6	73.3
500-258038-11 MS	HEN_21R_MS	83.8	81.9
500-258038-11 MSD	HEN_21R-MSD	89.6	75.1
500-258038-12	HEN_27	90.9	76.6
500-258038-13	HEN_32	91.1	77.0
500-258038-14	HEN_34	86.1	71.0
500-258038-15	HEN_35	95.2	76.3
500-258038-16	HEN_35_FD	90.6	66.2
500-258038-19	HEN_03R	87.8	79.3
500-258038-20	HEN_03R_FD	80.8	77.0
500-258038-21	HEN_16	79.7	73.6
500-258038-22	HEN_16_FD	85.8	70.7
500-258038-23	HEN_17	80.3	75.1
500-258038-24	HEN_22	87.8	74.8
500-258038-25	HEN_22&D	87.1	76.6
500-258038-26	HEN_23	84.3	70.3
500-258038-27	HEN_45#S	77.2	68.8
500-258038-28	HEN_46	75.2	66.2
500-258038-29	HEN_47	84.8	77.8
500-258038-30	HEN_49	91.6	66.9
500-258038-30 MS	HEN_49_MS	87.3	82.6
500-258038-30 MSD	HEN_49_MSD	85.3	72.5
500-258038-31	HEN_50	78.5	66.9
500-258038-32	HEN_51	78.0	69.9
500-258038-33	HEN_07	81.5	73.6
500-258038-34	HEN_08	60.3	73.3
500-258038-35	HEN_52	88.6	76.3
500-258038-36	HEN_54	90.1	75.1
500-258038-37	HEN_54_FD	81.8	79.3
500-258038-38	HEN_FB	79.0	72.5
LCS 160-683228/2-A	Lab Control Sample	96.2	80.4
LCS 160-683390/2-A	Lab Control Sample	86.6	75.1
LCS 160-683393/2-A	Lab Control Sample	92.9	78.1
MB 160-683228/1-A	Method Blank	99.7	78.1
MB 160-683390/1-A	Method Blank	94.9	80.4
MB 160-683393/1-A	Method Blank	89.9	76.6

Tracer/Carrier Legend

Ba = Ba Carrier

Y = Y Carrier

**ATTACHMENT C
COMPARISON TO BACKGROUND
QUARTER 4, 2024**

ATTACHMENT C.
COMPARISON TO BACKGROUND - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	HSU	Event	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	Background
12	UA	E007	Antimony, total	mg/L	12/09/15 - 10/08/24	23	100	All ND - Last	0.003	0.001
12	UA	E007	Arsenic, total	mg/L	12/09/15 - 10/08/24	28	100	All ND - Last	0.001	0.001
12	UA	E007	Barium, total	mg/L	12/09/15 - 10/08/24	30	0	CI around mean	0.053	0.212
12	UA	E007	Beryllium, total	mg/L	12/09/15 - 10/08/24	22	100	All ND - Last	0.001	0.001
12	UA	E007	Boron, total	mg/L	12/09/15 - 10/08/24	31	0	CB around T-S line	0.0367	0.163
12	UA	E007	Cadmium, total	mg/L	12/09/15 - 10/08/24	32	91	CB around T-S line	0.000582	0.00230
12	UA	E007	Chloride, total	mg/L	12/09/15 - 10/08/24	31	0	CI around mean	70.6	435
12	UA	E007	Chromium, total	mg/L	12/09/15 - 10/08/24	28	97	CB around T-S line	0.0015	0.00100
12	UA	E007	Cobalt, total	mg/L	12/09/15 - 10/08/24	26	84	Most recent sample	0.001	0.0380
12	UA	E007	Fluoride, total	mg/L	12/09/15 - 10/08/24	31	2	CI around median	0.23	0.120
12	UA	E007	Lead, total	mg/L	12/09/15 - 10/08/24	28	100	All ND - Last	0.0005	0.00150
12	UA	E007	Lithium, total	mg/L	12/09/15 - 10/08/24	27	4	CB around linear reg	0.00605	0.0190
12	UA	E007	Mercury, total	mg/L	12/09/15 - 10/08/24	25	100	All ND - Last	0.0002	0.0002
12	UA	E007	Molybdenum, total	mg/L	12/09/15 - 10/08/24	30	0	CB around linear reg	0.00935	0.00170
12	UA	E007	pH (field)	SU	12/09/15 - 10/08/24	38	0	CI around mean	7.3/7.4	6.6/7.5
12	UA	E007	Radium 226 + Radium 228, total	pCi/L	12/09/15 - 10/08/24	26	0	CI around geomean	0.376	2.00
12	UA	E007	Selenium, total	mg/L	12/09/15 - 10/08/24	30	61	CI around median	0.001	0.00140
12	UA	E007	Sulfate, total	mg/L	12/09/15 - 10/08/24	31	0	CI around geomean	63.8	215
12	UA	E007	Thallium, total	mg/L	12/09/15 - 10/08/24	22	100	All ND - Last	0.002	0.001
12	UA	E007	Total Dissolved Solids	mg/L	12/09/15 - 10/08/24	27	0	CI around mean	467	1,620
13	UA	E007	Antimony, total	mg/L	12/09/15 - 10/08/24	23	97	CB around T-S line	0.001	0.001
13	UA	E007	Arsenic, total	mg/L	12/09/15 - 10/08/24	28	97	CI around median	0.001	0.001
13	UA	E007	Barium, total	mg/L	12/09/15 - 10/08/24	30	0	CI around mean	0.0433	0.212
13	UA	E007	Beryllium, total	mg/L	12/09/15 - 10/08/24	22	100	All ND - Last	0.001	0.001
13	UA	E007	Boron, total	mg/L	12/09/15 - 10/08/24	31	0	CB around linear reg	0.00209	0.163
13	UA	E007	Cadmium, total	mg/L	12/09/15 - 10/08/24	32	98	CB around T-S line	0.000582	0.00230
13	UA	E007	Chloride, total	mg/L	12/09/15 - 10/08/24	31	0	CI around mean	72.9	435

ATTACHMENT C.
COMPARISON TO BACKGROUND - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	HSU	Event	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	Background
13	UA	E007	Chromium, total	mg/L	12/09/15 - 10/08/24	28	87	CB around T-S line	0.00173	0.00100
13	UA	E007	Cobalt, total	mg/L	12/09/15 - 10/08/24	26	84	Most recent sample	0.001	0.0380
13	UA	E007	Fluoride, total	mg/L	12/09/15 - 10/08/24	31	2	CI around median	0.2	0.120
13	UA	E007	Lead, total	mg/L	12/09/15 - 10/08/24	28	97	CB around T-S line	0.000807	0.00150
13	UA	E007	Lithium, total	mg/L	12/09/15 - 10/08/24	27	0	CB around linear reg	0.00953	0.0190
13	UA	E007	Mercury, total	mg/L	12/09/15 - 10/08/24	25	100	All ND - Last	0.0002	0.0002
13	UA	E007	Molybdenum, total	mg/L	12/09/15 - 10/08/24	30	24	CI around mean	0.0139	0.00170
13	UA	E007	pH (field)	SU	12/09/15 - 10/08/24	38	0	CI around mean	7.4/7.5	6.6/7.5
13	UA	E007	Radium 226 + Radium 228, total	pCi/L	12/09/15 - 10/08/24	26	0	CI around mean	0.461	2.00
13	UA	E007	Selenium, total	mg/L	12/09/15 - 10/08/24	30	49	CI around mean	0.00134	0.00140
13	UA	E007	Sulfate, total	mg/L	12/09/15 - 10/08/24	31	0	CI around mean	75.4	215
13	UA	E007	Thallium, total	mg/L	12/09/15 - 10/08/24	22	100	All ND - Last	0.002	0.001
13	UA	E007	Total Dissolved Solids	mg/L	12/09/15 - 10/08/24	30	0	CI around mean	483	1,620
46	UA	E007	Antimony, total	mg/L	12/09/15 - 10/09/24	22	100	All ND - Last	0.003	0.001
46	UA	E007	Arsenic, total	mg/L	12/09/15 - 10/09/24	24	100	All ND - Last	0.001	0.001
46	UA	E007	Barium, total	mg/L	12/09/15 - 10/09/24	26	0	CB around linear reg	0.0668	0.212
46	UA	E007	Beryllium, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.001	0.001
46	UA	E007	Boron, total	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	0.196	0.163
46	UA	E007	Cadmium, total	mg/L	12/09/15 - 10/09/24	25	100	All ND - Last	0.0005	0.00230
46	UA	E007	Chloride, total	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	70.2	435
46	UA	E007	Chromium, total	mg/L	12/09/15 - 10/09/24	24	92	CB around T-S line	0.00172	0.00100
46	UA	E007	Cobalt, total	mg/L	12/09/15 - 10/09/24	25	100	All ND - Last	0.001	0.0380
46	UA	E007	Fluoride, total	mg/L	12/09/15 - 10/09/24	27	4	CI around median	0.24	0.120
46	UA	E007	Lead, total	mg/L	12/09/15 - 10/09/24	24	100	All ND - Last	0.0005	0.00150
46	UA	E007	Lithium, total	mg/L	12/09/15 - 10/09/24	26	4	CI around mean	0.00861	0.0190
46	UA	E007	Mercury, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.0002	0.0002
46	UA	E007	Molybdenum, total	mg/L	12/09/15 - 10/09/24	26	0	CB around T-S line	0.0107	0.00170

ATTACHMENT C.
COMPARISON TO BACKGROUND - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	HSU	Event	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	Background
46	UA	E007	pH (field)	SU	12/09/15 - 10/09/24	27	0	CB around linear reg	7.1/7.3	6.6/7.5
46	UA	E007	Radium 226 + Radium 228, total	pCi/L	12/09/15 - 10/09/24	26	0	CI around geomean	0.306	2.00
46	UA	E007	Selenium, total	mg/L	12/09/15 - 10/09/24	26	65	CI around median	0.001	0.00140
46	UA	E007	Sulfate, total	mg/L	12/09/15 - 10/09/24	27	0	CI around geomean	62.5	215
46	UA	E007	Thallium, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.002	0.001
46	UA	E007	Total Dissolved Solids	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	444	1,620
47	UA	E007	Antimony, total	mg/L	12/09/15 - 10/09/24	22	100	All ND - Last	0.003	0.001
47	UA	E007	Arsenic, total	mg/L	12/09/15 - 10/09/24	24	96	CI around median	0.001	0.001
47	UA	E007	Barium, total	mg/L	12/09/15 - 10/09/24	26	0	CI around mean	0.0791	0.212
47	UA	E007	Beryllium, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.001	0.001
47	UA	E007	Boron, total	mg/L	12/09/15 - 10/09/24	27	0	CI around geomean	0.219	0.163
47	UA	E007	Cadmium, total	mg/L	12/09/15 - 10/09/24	25	100	All ND - Last	0.0005	0.00230
47	UA	E007	Chloride, total	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	73.6	435
47	UA	E007	Chromium, total	mg/L	12/09/15 - 10/09/24	24	96	CB around T-S line	0.00181	0.00100
47	UA	E007	Cobalt, total	mg/L	12/09/15 - 10/09/24	25	84	CI around median	0.001	0.0380
47	UA	E007	Fluoride, total	mg/L	12/09/15 - 10/09/24	27	4	CB around T-S line	0.213	0.120
47	UA	E007	Lead, total	mg/L	12/09/15 - 10/09/24	24	100	All ND - Last	0.0005	0.00150
47	UA	E007	Lithium, total	mg/L	12/09/15 - 10/09/24	26	0	CI around mean	0.00855	0.0190
47	UA	E007	Mercury, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.0002	0.0002
47	UA	E007	Molybdenum, total	mg/L	12/09/15 - 10/09/24	26	0	CB around linear reg	0.0144	0.00170
47	UA	E007	pH (field)	SU	12/09/15 - 10/09/24	27	0	CI around mean	7.0/7.1	6.6/7.5
47	UA	E007	Radium 226 + Radium 228, total	pCi/L	12/09/15 - 10/09/24	26	0	CI around geomean	0.31	2.00
47	UA	E007	Selenium, total	mg/L	12/09/15 - 10/09/24	25	88	CB around T-S line	0.001	0.00140
47	UA	E007	Sulfate, total	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	64.6	215
47	UA	E007	Thallium, total	mg/L	12/09/15 - 10/09/24	21	100	All ND - Last	0.002	0.001
47	UA	E007	Total Dissolved Solids	mg/L	12/09/15 - 10/09/24	27	0	CI around mean	479	1,620
52	UA	E007	Antimony, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.003	0.001

ATTACHMENT C.
COMPARISON TO BACKGROUND - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	HSU	Event	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	Background
52	UA	E007	Arsenic, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.001	0.001
52	UA	E007	Barium, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	0.0755	0.212
52	UA	E007	Beryllium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.001	0.001
52	UA	E007	Boron, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	0.155	0.163
52	UA	E007	Cadmium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.0005	0.00230
52	UA	E007	Chloride, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	72.9	435
52	UA	E007	Chromium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.005	0.00100
52	UA	E007	Cobalt, total	mg/L	02/24/21 - 10/10/24	16	94	Most recent sample	0.001	0.0380
52	UA	E007	Fluoride, total	mg/L	02/24/21 - 10/10/24	16	6	CI around geomean	0.264	0.120
52	UA	E007	Lead, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.0005	0.00150
52	UA	E007	Lithium, total	mg/L	02/24/21 - 10/10/24	16	12	CI around mean	0.00564	0.0190
52	UA	E007	Mercury, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.0002	0.0002
52	UA	E007	Molybdenum, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	0.0111	0.00170
52	UA	E007	pH (field)	SU	02/24/21 - 10/10/24	16	0	CI around mean	7.0/7.3	6.6/7.5
52	UA	E007	Radium 226 + Radium 228, total	pCi/L	02/24/21 - 10/10/24	16	0	CI around mean	0.416	2.00
52	UA	E007	Selenium, total	mg/L	02/24/21 - 10/10/24	16	94	CB around T-S line	0.001	0.00140
52	UA	E007	Sulfate, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	60.9	215
52	UA	E007	Thallium, total	mg/L	02/24/21 - 10/10/24	16	94	CI around median	0.002	0.001
52	UA	E007	Total Dissolved Solids	mg/L	02/24/21 - 10/10/24	15	0	CI around mean	451	1,620
54	UA	E007	Antimony, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.003	0.001
54	UA	E007	Arsenic, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.001	0.001
54	UA	E007	Barium, total	mg/L	02/24/21 - 10/10/24	16	0	CB around linear reg	0.0397	0.212
54	UA	E007	Beryllium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.001	0.001
54	UA	E007	Boron, total	mg/L	02/24/21 - 10/10/24	16	0	CB around linear reg	0.0597	0.163
54	UA	E007	Cadmium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.0005	0.00230
54	UA	E007	Chloride, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	75.4	435
54	UA	E007	Chromium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.005	0.00100

ATTACHMENT C.
COMPARISON TO BACKGROUND - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Well ID	HSU	Event	Parameter	Units	Date Range	Sample Count	Percent ND	Statistical Calculation	Statistical Result	Background
54	UA	E007	Cobalt, total	mg/L	02/24/21 - 10/10/24	16	88	CI around median	0.001	0.0380
54	UA	E007	Fluoride, total	mg/L	02/24/21 - 10/10/24	16	6	CB around T-S line	0.0699	0.120
54	UA	E007	Lead, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.0005	0.00150
54	UA	E007	Lithium, total	mg/L	02/24/21 - 10/10/24	16	0	CB around T-S line	0.00491	0.0190
54	UA	E007	Mercury, total	mg/L	02/24/21 - 10/10/24	16	94	CI around median	0.0002	0.0002
54	UA	E007	Molybdenum, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	0.0224	0.00170
54	UA	E007	pH (field)	SU	02/24/21 - 10/10/24	16	0	CI around mean	7.1/7.4	6.6/7.5
54	UA	E007	Radium 226 + Radium 228, total	pCi/L	02/24/21 - 10/10/24	16	0	CI around geomean	0.123	2.00
54	UA	E007	Selenium, total	mg/L	02/24/21 - 10/10/24	16	56	CB around T-S line	0.00194	0.00140
54	UA	E007	Sulfate, total	mg/L	02/24/21 - 10/10/24	16	0	CI around mean	73.5	215
54	UA	E007	Thallium, total	mg/L	02/24/21 - 10/10/24	16	100	All ND - Last	0.002	0.001
54	UA	E007	Total Dissolved Solids	mg/L	02/24/21 - 10/10/24	14	0	CI around mean	489	1,620

ATTACHMENT C.
COMPARISON TO BACKGROUND - QUARTER 4, 2024
845 QUARTERLY REPORT
HENNEPIN POWER PLANT
EAST ASH POND
HENNEPIN, IL

Notes:

Lower Confidence Limit (LCL) or Upper Confidence Limit (UCL) exceeded the statistical background value

Throughout this document, “exceedance” or “exceedances” is intended to refer only to potential exceedances of proposed applicable background statistics or Groundwater Protection Standards (GWPSs) as described in the proposed groundwater monitoring program which was submitted to the Illinois Environmental Protection Agency (IEPA) on October 25, 2021 as part of Dynegy Midwest Generation, LLC’s (DMG’s) operating permit application for the East Ash Pond. That operating permit application, including the proposed groundwater monitoring program, remains under review by the IEPA and, therefore, DMG has not identified any actual exceedances.

Events:

E007 = Quarter 4, 2024 sampling event

HSU = hydrostratigraphic unit:

UA = Uppermost Aquifer

mg/L = milligrams per liter

ND = non-detect

pCi/L = picocuries per liter

SU = standard units

Sample Count = number of samples from Sampled Date Range used to calculate the Statistical Result

Statistical Calculation = method used to calculate the statistical result:

All ND - Last = All results were below the reporting limit, and the last determined reporting limit is shown

CB around T-S line = Confidence band around Thiel-Sen line

CB around T-S line = Confidence band around Thiel-Sen line

CB around linear reg = Confidence band around linear regression

CI around geomean = Confidence interval around the geometric mean

CI around mean = Confidence interval around the mean

CI around median = Confidence interval around the median

Most recent sample = Result for the most recently collected sample used due to insufficient data

Statistical Result = calculated in accordance with the Statistical Analysis Plan using constituent concentrations observed at each monitoring well during all sampling events within the specified date range

Statistical Result Code (if applicable):

NR¹ = Parameter not analyzed.

NS¹ = Well has been, or will be, abandoned; therefore, a sample was not collected.

NS² = Well either needs or was undergoing maintenance; therefore, a sample was not collected.

NS³ = The location was not accessible; therefore, a sample was not collected.

NS⁴ = The location could not be found; therefore, a sample was not collected.

NS⁵ = The location was damaged; therefore, a sample was not collected.

NS⁶ = Sampling pump could not yield a sample.

NS⁷ = Well was either dry or purged dry and did not recover sufficiently to yield adequate volume for a sample.

NS⁸ = A sample was not collected.

PM¹ = Parameter not analyzed as the well purged dry during sample collection and did not sufficiently recover to yield adequate sample volume for analysis.

For pH, the values presented are the lower / upper limits of the background determination