CCR Fugitive Dust Control Plan

for

Kincaid Power Plant

Prepared for:

Kincaid Generation, L.L.C.

Kincaid Power Plant 4 Miles West of Kincaid on Route 104 Kincaid, IL 62540

Prepared by:

Burns & McDonnell Kansas City, Missouri

Amendment 1 October 2021

Table of Contents

1 I	1 Introduction1-1		
1.1 1.2	Facility Information		
2 (CCR Fugitive Dust Control Measures and Appropriateness	2-1	
2.1 2.2 2.3	Handling of CCR		
 3 Procedures for Periodic Assessment of the Plan			
6	Amendments		

List of Tables

Table 2-1.	Control Measures for CCR Management in the CCR Unit	.2-1
	Control Measures for Handling CCR	
	Control Measures for Transportation of CCR	
Table 6-1.	CCR Fugitive Dust Control Plan Amendments	.6-1

1 Introduction

This Coal Combustion Residuals (CCR) fugitive dust control plan has been prepared for the Kincaid Power Plant, located in Christian County, Illinois. This plan addresses the air criteria in 40 C.F.R. § 257.80 of the United States Environmental Protection Agency's CCR rule, which requires the owner or operator of a CCR unit to "adopt measures that will effectively minimize CCR from becoming airborne at the facility" and to "prepare and operate in accordance with a CCR fugitive dust control plan." The plan also addresses the air criteria in 35 I.A.C. 845.500 of the Illinois Environmental Protection Agency's CCR rule, which contains similar requirements to the federal CCR rule.

1.1 **Facility Information**

- Facility Name: Kincaid Power Plant
- Facility Address: 4 Miles West of Kincaid on Route 104, Kincaid, IL 62540
- Owner: Kincaid Generation, L.L.C.

1.2 Certification

The owner or operator must obtain a certification from a qualified professional engineer that the initial CCR fugitive dust control plan, or any subsequent amendment of it, meets the requirements of 40 C.F.R. § 257.80 and 35 I.A.C. 845.500. See 40 C.F.R. § 257.80(b)(7); 35 I.A.C. 845.500(b)(7).

I certify under penalty of law that, to the best of my knowledge, this plan meets the requirements of 40 C.F.R. § 257.80 and 35 I.A.C. 845.500. This certification is based on my review of the document and conditions at the site and on my inquiry of the person or persons who managed the preparation of this document.

Distance of the second John R. Hesemann Printed Name of Qualified Professional Engineer Signature of Qualified Professional Engineer and Date

062.058523 - Illinois - Expires 11/30/2021 Registration Number and State

2 CCR Fugitive Dust Control Measures and Appropriateness

CCR fugitive dust has the potential to become airborne at the facility during periods of CCR management in the CCR unit, CCR handling and CCR transport. Areas at the facility that have the potential for airborne CCR fugitive dust are the CCR surface impoundment, CCR handling equipment and CCR transport in trucks. This section identifies and describes the control measures selected and adopted by the facility to minimize CCR from becoming airborne at the facility and explains how the selected measures are applicable and appropriate for site conditions. The control measures may be adjusted or modified based on observed effectiveness of minimizing CCR from becoming airborne and weather conditions.

2.1 Management of CCR in the CCR Unit

The facility manages CCR in a surface impoundment located at the facility. Table 2-1 below identifies CCR fugitive dust control measures that have been selected for use by the facility during CCR management in the CCR unit, including placement of CCR into the CCR unit, and explains how the selected measures are applicable and appropriate for site conditions. The facility will use the identified measures during CCR management in the CCR unit to minimize CCR from becoming airborne at the facility.

CCR Activity	CCR Fugitive Dust Control Measure	Applicability and Appropriateness of Control Measure
	Wet management of CCR bottom ash in the CCR surface impoundment.	Wet management of CCR minimizes the potential for CCR fugitive dust generation.
Management of CCR in the facility's CCR unit	Water areas of exposed CCR in the CCR unit, as necessary.	Water will be applied to areas of exposed CCR to maintain moisture content to minimize the potential for CCR fugitive dust generation in excessively dry or windy conditions.
	Naturally occurring grass vegetation in areas of exposed CCR in the CCR surface impoundment.	Vegetation provides a wind screen and/or cover to reduce wind entrainment of CCR.
	Reduce or halt operations during high wind events, as necessary.	Reducing or halting operations during high wind events minimizes the potential for CCR fugitive dust generation.

Table 2-1. Control Measures for CCR Management in the CCR Unit

2-2

2.2 Handling of CCR

CCR is regularly removed from the boiler system and conveyed to the CCR handling system, which includes silos and truck loading areas. CCR fly ash is pneumatically conveyed in an enclosed system from the boiler system to storage silos. CCR fly ash is loaded dry into bulk transporters utilizing a vented spout. CCR bottom ash is wet sluiced into a CCR surface impoundment. Bottom ash is periodically removed from the CCR surface impoundment and remains sufficiently wet during and after handling activities, including dewatering, associated with transfer of the CCR. Table 2-2 below identifies CCR fugitive dust control measures that have been selected for use by the facility during handling of CCR and explains how the selected measures are applicable and appropriate for site conditions. The facility will use the identified measures when handling CCR to minimize CCR from becoming airborne at the facility.

CCR Activity	CCR Fugitive Dust Control Measure	Applicability and Appropriateness of Control Measure	
	Wet sluice CCR bottom ash to the CCR surface impoundment.	Wet sluicing CCR minimizes the potential for CCR fugitive dust generation.	
	CCR bottom ash removed from the CCR surface impoundment and loaded into trucks for transport remains conditioned during handling.	Conditioning CCR allows CCR to bind together and thus minimizes the potential for CCR fugitive dust generation when CCR is handled.	
	Pneumatically convey dry CCR fly ash to storage silos in an enclosed system.	Conveying CCR fly ash in an enclosed system minimizes the potential for CCR fugitive dust generation.	
Handling of CCR at	Load CCR transport trucks from the CCR fly ash silos in a partially enclosed area.	Partial enclosure of the CCR transport truck loading area reduces the potential for wind to cause CCR fugitive dust to become airborne.	
the facility	Perform housekeeping, as necessary, in the fly ash loading area.	Good housekeeping measures, such as sweeping or wetting the loading area, minimize the potential for CCR fugitive dust generation during handling activities.	
	Operate fly ash handling system in accordance with good operating practices.	Operation in accordance with good operating practices minimizes the potential for CCR fugitive dust generation.	
	Maintain and repair as necessary dust controls on the fly ash handling and truck load-out system.	Performing maintenance and repairs as needed to maintain dust controls in good operating condition minimizes the potential for CCR fugitive dust generation.	
	Reduce or halt operations during high wind events, as necessary.	Reducing or halting operations during high wind events minimizes the potential for CCR fugitive dust generation.	

Table 2-2. Control Measures for Handling CCR

2.3 Transportation of CCR

CCR is transported via truck at the facility using a combination of paved and unpaved facility roads. Table 2-3 below identifies CCR fugitive dust control measures that have been selected for use by the facility during transport of CCR. The facility will use the identified measures when transporting CCR to minimize CCR from becoming airborne at the facility.

CCR Activity	CCR Fugitive Dust Control Measure	Applicability and Appropriateness of Control Measure
	Cover or enclose trucks used to transport CCR fly ash.	Covering or enclosing trucks transporting CCR on facility roads minimizes the potential for CCR fugitive dust generation from the CCR transport trucks.
	Limit the speed of vehicles to no more than 15 mph on facility roads.	Limiting the speed of vehicles traveling on facility roads minimizes the potential for CCR fugitive dust generation from the CCR transport trucks.
	Cover or enclose trucks used to transport CCR other than fly ash, as necessary.	Covering or enclosing trucks transporting CCR on facility roads minimizes the potential for CCR fugitive dust generation from the CCR transport trucks.
Transportation of CCR	Watering roads used to transport CCR materials, as needed.	Watering CCR haul roads minimizes the potential for CCR fugitive dust generation in excessively dry or windy conditions.
at the facility	Sweep or rinse CCR off of the outside of the trucks transporting CCR, as necessary.	Removing CCR present on the outside of the truck minimizes the potential for movement of the truck or wind to cause CCR fugitive dust to become airborne.
	Remove CCR, as necessary, deposited on facility road surfaces during transport.	Removing CCR deposited on facility road surfaces as a result of transport minimizes the potential for CCR fugitive dust generation from vehicle traffic.
	Condition CCR haul roads with water or dust suppressant, as necessary.	Watering CCR haul roads minimizes the potential for dust generation to occur as a result of CCR hauling traffic and heavy equipment use.
	Reduce or halt operations during high wind events, as necessary.	Reducing or halting operations during high wind events minimizes the potential for CCR fugitive dust generation.

Table 2-3. Control Measures for Transportation of CCR

3 Procedures for Periodic Assessment of Effectiveness of the Plan

The facility conducts inspections associated with CCR fugitive dust control. The facility also uses the procedures identified in Section 5 of this plan to log every citizen complaint involving CCR fugitive dust events at the facility. These inspections and the investigations of citizen complaints will be used to periodically assess the effectiveness of the CCR fugitive dust control plan per 40 C.F.R. § 257.80(b)(4) and 35 I.A.C. 845.500(b)(3).

The facility routinely performs inspections to verify the effectiveness of the CCR fugitive dust control measures used at the facility. Inspections are conducted during daylight working hours and include observing for the presence of CCR fugitive dust emissions from vehicles transporting CCR on facility roads, CCR handling and CCR management activities, including CCR placement in the CCR unit. Inspection records include information such as the name of the person conducting the inspection, the date and time of the inspection, the results of the inspection, and any corrective action taken.

When a CCR fugitive dust event is observed or a citizen complaint involving a CCR fugitive dust event at the facility is received, current CCR management practices will be reviewed to see that the selected control measures are being properly implemented. If the control measures are not being properly implemented, relevant operating personnel will be notified and, as warranted, retrained in the proper implementation of CCR fugitive dust control measures. If appropriate, use of revised and/or additional control measures will be evaluated. As warranted, revised and/or additional control measures found to be applicable and appropriate to control CCR fugitive dust emissions will be incorporated into an amended CCR fugitive dust control plan.

The plan also will be reassessed in the event of material changes in site conditions potentially resulting in CCR fugitive dust becoming airborne at the facility.

4 Recordkeeping, Notification, Internet Site

The written CCR fugitive dust control plan, any amendment of the written plan, and the annual CCR fugitive dust control report required by 40 C.F.R. § 257.80(c) and 35 I.A.C. 845.500(c) will be placed in the facility's written operating record and posted to the company's CCR website in accordance with 40 C.F.R. § 257.105(g), § 257.107(g) and 845.800(d)(7), (14) and 845.810(e). Notification of the availability of the CCR fugitive dust control plan, any amendment of the plan, and the annual CCR fugitive dust control plan, any amendment of the plan, and the annual CCR fugitive dust control plan, any amendment of the plan, and the annual CCR fugitive dust control plan, any amendment of the plan, and the annual CCR fugitive dust control plan will be submitted to IEPA in accordance with 40 C.F.R. § 257.106(g). Any amendment of the fugitive dust control plan will be submitted to IEPA in accordance with 845.500(b)(5).

Additionally, pursuant to 845.500(b)(6), this fugitive dust control plan is being placed in facility's operating record and posted to the company's CCR website prior to the submission of any permits for the Kincaid Power Plant.

5 Procedures to Log Citizen Complaints

In the event the owner or operator of the facility receives a citizen complaint involving a CCR fugitive dust event at the facility, relevant information about the complaint will be logged. Information that will be recorded includes, as applicable:

- Date/Time the complaint is received
- Date/Time and duration of the CCR fugitive dust event
- Description of the nature of the CCR fugitive dust event
- Name of the citizen entering the complaint
- Address & phone number of citizen entering the complaint
- Name of the personnel who took the complaint
- All actions taken to assess and resolve the complaint

All citizen complaints involving CCR fugitive dust events at the facility will be investigated promptly. As deemed appropriate or necessary, corrective measures will be taken and a follow-up response will be provided to the complainant.

Pursuant to 35 I.A.C. 845.500(b)(2), quarterly reports will be submitted to IEPA no later than 14 days from the end of the quarter for all complaints received in that quarter. At a minimum, the quarterly report will include the date of the complaint, the date of the incident, the name and contact information of the complainant (if given), and all actions taken to assess and resolve the complaint.

6 Amendments

The written CCR fugitive dust control plan may be amended at any time provided the revised plan is placed in the facility's operating record as required by 40 C.F.R. § 257.105(g)(1) and 35 I.A.C. 845.500(b)(6). Any amendment of the fugitive dust control plan will be submitted to IEPA in accordance with 845.500(b)(5). The written CCR fugitive dust control plan must be amended whenever there is a change in conditions that would substantially affect the written plan in effect.

Amendment Number and Date	Pages or Section	Description of Amendment	Professional Engineer Certifying Plan
Version 0 October 2015		Initial Plan	Wendy M. Pennington
Amendment 1 October 2021	Various	Administrative changes and adjustments to site condition controls as appropriate	John R. Hesemann

Table 6-1. CCR Fugitive Dust Control Plan Amendments