

Ted Lindenbusch Kincaid Generation, LLC Luminant 1500 Eastport Plaza Drive Collinsville, IL 62234

January 20, 2021

Mr. Darin LeCrone, P.E.
Manager, Industrial Unit
Bureau of Water, Division of Water Pollution Control, Permits Section
Illinois Environmental Protection Agency
1021 North Grand Avenue, East
Springfield, IL 62794-9276

Re: Kincaid Power Plant – Federal ELG Notice of Planned Participation to Achieve Permanent Cessation; NPDES Permit (IL0002241) Renewal Application Supplement

Dear Mr. LeCrone:

Pursuant to 40 C.F.R. 423.19(f), Kincaid Generation, LLC (Kincaid Generation) submits this Notice of Planned Participation to the Illinois Environmental Protection Agency (IEPA) demonstrating that the Kincaid Power Plant's Units 1 and 2 qualify as electric generating units that will achieve permanent cessation of coal combustion by December 31, 2028. Accordingly, Bottom Ash Transport Waters (BATW) may continue to discharge on and after October 13, 2023 under 40 C.F.R. § 423.16(g)(1). Kincaid Generation is also hereby supplementing the Kincaid Power Plant NPDES renewal application submitted in October 2019 as required by 40 C.F.R. § 423.18.

Kincaid Generation has provided below and enclosed the information required by 40 C.F.R. § 423.19(f)(2):

- Expected date that each electric generating unit is projected to achieve permanent cessation of coal combustion
 - o Kincaid Unit 1: July 17, 2027
 - o Kincaid Unit 2: July 17, 2027
- Whether each date represents a retirement or a fuel conversion
 - Retirement for Kincaid Units 1 and 2
- Whether each retirement or fuel conversion has been approved by a regulatory body, and what the relevant regulatory body is
 - o Retirement has not yet been approved. The relevant regulatory body is PJM.
- A copy of (1) the most recent integrated resource plan for which the applicable state agency
 approved the retirement or repowering of the unit subject to the ELGs, (2) certification of electric
 generating unit cessation under 40 CFR 257.103(b), or (3) other documentation supporting that
 the electric generating unit will permanently cease the combustion of coal by December 31, 2028
 - See enclosed demonstration submitted to USEPA pursuant to 40 C.F.R. § 257.103(b) on November 30, 2020.
 - o See enclosed company press release indicating a 2027 retirement date for Kincaid.

- A timeline to achieve the permanent cessation of coal combustion
 - See timeline on pages 6-2, 6-3, and 6-4 of the enclosed demonstration submitted to USEPA pursuant to 40 C.F.R. 257.103(b) on November 30, 2020.

Kincaid Power Plant's Unit 1 and 2 will cease coal combustion pursuant to § 423.19(f), and therefore, discharge of pollutants in BATW generated on and after October 13, 2023 can continue until closure, but no later than December 31, 2028. See 40 C.F.R. § 423.16(g)(1). Kincaid Generation is requesting that IEPA revise the Kincaid NPDES permit accordingly. Moreover, IEPA should include the language below in accordance with 40 C.F.R. § 423.18 which states that "All permits subject to this part shall include the following permit conditions." In addition to the language set forth at40 C.F.R. § 423.18, Kincaid Generation further offers the additional language underlined below that would include a System Support Resource designation as a qualifying event.

- a) An electric generating unit shall qualify as a low utilization electric generating unit or permanently ceasing the combustion of coal by December 31, 2028, if such qualification would have been demonstrated absent the following qualifying event:
 - 1) An emergency order issued by the Department of Energy under Section 202(c) of the Federal Power Act,
 - 2) A System Support Resource designation by PJM, or
 - 3) A reliability must run agreement issued by a Public Utility Commission, or
 - 4) Any other reliability-related order or agreement issued by a competent electricity regulator (e.g., an independent system operator) which results in that electric generating unit operating in a way not contemplated when the certification was made; or
 - 5) The operation of the electric generating unit was necessary for load balancing in an area subject to a declaration under 42 U.S.C. 5121 et seq., that there exists:
 - i. An "Emergency," or
 - ii. A "Major Disaster," and
 - iii. That load balancing was due to the event that caused the "Emergency" or "Major Disaster" in paragraph (a)(4) of this section to be declared,
- b) Any facility providing the required documentation pursuant to § 423.19(g) may avail itself of the protections of this permit condition.

If you have any questions regarding this submittal, please contact Phil Morris at 618-343-7794 or phil.morris@vistracorp.com.

Sincerely,

Kincaid Generation, LLC Kincaid Power Plant

Ted Lindenbusch Plant Manager

Enclosures

Mailroom



Dear Customer,

The following is the proof-of-delivery for tracking number: 772772650269

Delivery Information:

Status: Delivered To:

Signed for by: D.HOLLIS Delivery Location:

Service type: FedEx Standard Overnight

Special Handling: Deliver Weekday SPRINGFIELD, IL,

Delivery date: Feb 1, 2021 09:08

Shipping Information:

Tracking number: 772772650269 **Ship Date:** Jan 29, 2021

Weight: 1.0 LB/0.45 KG

Recipient: Shipper:

SPRINGFIELD, IL, US, Collinsville, IL, US,

 Purchase Order
 Baldwin,Edwards,Joppa,Kincaid

 Invoice
 & Newton: ELG NOPP and NPDES

Department Number Renewal Supplement

Proof-of-delivery details appear below; however, no signature is available for this FedEx Express shipment because a signature was not required.

CCR SURFACE IMPOUNDMENT DEMONSTRATION

W/O ATTACHMENTS



Cynthia Vodopivec Kincaid Generation, LLC Luminant 6555 Sierra Dr. Irving, TX 75039

November 25, 2020

Sent via email

Mr. Andrew R. Wheeler, EPA Administrator Environmental Protection Agency 1200 Pennsylvania Avenue, N.W. Mail Code 5304-P Washington, DC 20460

Re: Kincaid Power Station Revised Alternative Closure Demonstration

Dear Administrator Wheeler:

Kincaid Generation, LLC (Kincaid Generation) submits this revised request to the U.S. Environmental Protection Agency (EPA) for approval of a site-specific alternative deadline to initiate closure pursuant to 40 C.F.R. § 257.103(f)(2) for the Ash Pond located at the Kincaid Power Station near Kincaid, Illinois. Kincaid Generation is requesting an extension pursuant to 40 C.F.R. § 257.103(f)(2) so that the Ash Pond may continue to receive CCR and non-CCR wastestreams after April 11, 2021, and complete closure no later than October 17, 2028.

The enclosed demonstration prepared by Burns & McDonnell replaces the demonstration that was previously submitted by Kincaid Generation to EPA on September 29, 2020. This demonstration addresses all of the criteria in 40 C.F.R. § 257.103(f)(2)(i)-(iv) and contains the documentation required by 40 C.F.R. § 257.103(f)(2)(v). As allowed by the agency, in lieu of hard copies of these documents, electronic files were submitted to Kirsten Hillyer, Frank Behan, and Richard Huggins via email. The demonstration is also available on Kincaid Generation's publicly available website: https://www.luminant.com/ccr/

Sincerely,

Cynthia Vodopivec

Cynthin E Way

VP - Environmental Health & Safety

Enclosure

cc: Kirsten Hillyer Frank Behan Richard Huggins



CCR Surface Impoundment Demonstration for a Site-Specific Alternative to Initiation of Closure Deadline



Kincaid Generation, LLC

Kincaid Power Station Project No. 122702

Revision 1 11/24/2020

CCR Surface Impoundment Demonstration for a Site-Specific Alternative to Initiation of Closure Deadline

prepared for

Kincaid Generation, LLC Kincaid Power Station Kincaid, Illinois

Project No. 122702

Revision 1 11/24/2020

prepared by

Burns & McDonnell Engineering Company, Inc. Kansas City, Missouri

INDEX AND CERTIFICATION

Kincaid Generation, LLC CCR Surface Impoundment Demonstration for a Site-Specific Alternative to Initiation of Closure Deadline Project No. 122702

Report Index

<u>Chapter</u> Number	Chapter Title	Number of Pages
rumou	Chapter True	orrages
1.0	Executive Summary	1
2.0	Introduction	2
3.0	Documentation of No Alternative Disposal Capacity	6
6.0	Documentation of Closure Completion Timeframe	4
7.0	Conclusion	1
Appendix A	Site Plan	1

Certification

I hereby certify, as a Professional Engineer in the state of Illinois, that the information in this document as noted in the above Report Index was assembled under my direct personal charge. This report is not intended or represented to be suitable for reuse by the Kincaid Generation, LLC or others without specific verification or adaptation by the Engineer.

EDWARD T. TOHILL

062-056915

Church Cholid

11/24/20

LIC EXPIRES

11/30/21

Edward T. Tohill, P.E., (Illinois License No. 062-056915)

Date: 11/24/20

TABLE OF CONTENTS

			<u>Page No.</u>
1.0	EXE	CUTIVE SUMMARY	1-1
2.0	INTF	RODUCTION	2-1
3.0	DOC	CUMENTATION OF NO ALTERNATIVE DISPOSAL CAPACITY.	3-1
	3.1	Site-Layout and Wastewater Processes	
	3.2	CCR Wastestreams	
	3.3	Non-CCR Wastestreams	3-4
4.0	RIS	MITIGATION PLAN	4-1
5.0	DOC	CUMENTATION AND CERTIFICATION OF COMPLIANCE	5-1
	5.1	Owner's Certification of Compliance - § 257.103(f)(2)(v)(C)(1)	5-1
	5.2	Visual representation of hydrogeologic information - § 257.103(f)(2)((v)(C)(2) 5-1
	5.3	Groundwater monitoring results - § 257.103(f)(2)(v)(C)(3)	5-2
	5.4	Description of site hydrogeology including stratigraphic cross-section	
		§ 257.103(f)(2)(v)(C)(4)	
	5.5	Corrective measures assessment - § 257.103(f)(2)(v)(C)(5)	
	5.6	Remedy selection progress report - § 257.103(f)(2)(v)(C)(6)	
	5.7	Structural stability assessment - § 257.103(f)(2)(v)(C)(7)	
	5.8	Safety factor assessment - § 257.103(f)(2)(v)(C)(8)	5-2
6.0	DOC	CUMENTATION OF CLOSURE COMPLETION TIMEFRAME	6-1
7.0	CON	ICLUSION	7-1
		A – SITE PLAN AND NEARBY LANDFILLS B – WATER BALANCE DIAGRAM	
A TT	A C.I.I.A.A	ENT 4 DICK MITICATION DI ANI	
	_	ENT 1 – RISK MITIGATION PLAN ENT 2 – MAP OF GROUNDWATER MONITORING WELL	
AII	ACHIVI	LOCATIONS	
ATT	ACHM	ENT 3 – WELL CONSTRUCTION DIAGRAMS AND DRILLING LOGS	
ATT	АСНМ	ENT 4 – MAPS OF THE DIRECTION OF GROUNDWATER FLO	W
		ENT 5 – TABLES SUMMARIZING CONSTITUENT	
· ·		CONCENTRATIONS AT EACH MONITORING WELL	
ATT	ACHM	ENT 6 – SITE HYDROGEOLOGY AND STRATIGRAPHIC CROS	SS-

ATTACHMENT 7 – STRUCTURAL STABILITY ASSESSMENT ATTACHMENT 8 – SAFETY FACTOR ASSESSMENT ATTACHMENT 9 – CLOSURE PLAN

LIST OF TABLES

	<u>Page No.</u>
Table 3-1: Kincaid CCR Wastestreams	3-2
Table 3-2: Kincaid Non-CCR Wastestreams	3-4
Table 3-3: Non-CCR Wastestream Offsite Disposal	3-6
Table 6-1: Kincaid Ash Pond Closure Schedule	

LIST OF ABBREVIATIONS

Abbreviation Term/Phrase/Name

CCR Coal Combustion Residual

CFR Code of Federal Regulations

ELG Rule Effluent Limitations Guidelines and Standards for the Steam Electric

Power Generating Point Source Category

EPA Environmental Protection Agency

Kincaid Power Station

Kincaid Generation Kincaid Generation, LLC

POTW Publicly Owned Treatment Works

PSD Prevention of Significant Deterioration

RCRA Resource Conservation and Recovery Act

SWPPP Stormwater Pollution Prevention Plan

TSS total suspended solids

1.0 EXECUTIVE SUMMARY

Kincaid Generation, LLC (Kincaid Generation) submits this request to the U.S. Environmental Protection Agency (EPA) for approval of a site-specific alternative deadline to initiate closure pursuant to 40 C.F.R. § 257.103(f)(2) —"Permanent Cessation of a Coal-Fired Boiler(s) by a Date Certain"— for the Ash Pond located at the Kincaid Power Station (Kincaid) in Illinois. The Ash Pond is a 172-acre CCR surface impoundment used to manage CCR and non-CCR wastestreams at Kincaid. As discussed herein, the two boilers at the station will cease coal-fired operations no later than July 17, 2027, and the impoundment will complete closure no later than October 17, 2028. Therefore, Kincaid Generation is requesting an extension pursuant to 40 C.F.R. § 257.103(f)(2) so that the Ash Pond may continue to receive CCR and non-CCR waste streams after April 11, 2021, and complete closure no later than October 17, 2028.

2.0 INTRODUCTION

Kincaid is a 1,108-megawatt, two-unit, coal-fueled electric generating station near Kincaid, Illinois. The Kincaid facility includes a CCR unit (the Ash Pond) that is the subject of this demonstration. Kincaid utilizes the 172-acre Ash Pond to manage sluiced bottom ash, economizer ash, air heater ash, and non-CCR wastewaters with a majority of the water recycled back through the system. The Ash Pond was constructed in 1964-1965 and put into service in 1967. The various non-CCR wastewaters routed to the Ash Pond originate from the West Area Runoff Basin, which collects flows from coal pile runoff, tunnel ground water sump, slag tank cooling water, intake pump house sump, ammonia storage tank sump, building low volume wastewater, condensate storage area and overflows, station basement sumps, and other stormwater sources. The Ash Pond also receives boiler wash water during maintenance outage events. A site plan is provided in Appendix A, and the plant water balance diagram is included in Appendix B. Note that the Ash Pond is referred to as the Bottom Ash Sluice Water Recycle Pond on the water balance diagram.

On April 17, 2015, the Environmental Protection Agency (EPA) issued the federal Coal Combustion Residual (CCR) Rule, 40 C.F.R. Part 257, Subpart D, to regulate the disposal of CCR materials generated at coal-fueled units. The rule is being administered under Subtitle D of the Resource Conservation and Recovery Act (RCRA, 42 U.S.C. § 6901 et seq.). On August 28, 2020, the EPA Administrator issued revisions to the CCR Rule that require all unlined surface impoundments to initiate closure by April 11, 2021, unless an alternative deadline is requested and approved. 40 C.F.R. § 257.101(a)(1) (85 Fed. Reg. 53,516 (Aug. 28, 2020)). Specifically, owners and operators of a CCR surface impoundment may continue to receive CCR and non-CCR wastestreams if the facility will cease operation of the coal-fired boiler(s) and complete closure of the impoundments within certain specified timeframes. 40 C.F.R. § 257.103(f)(2). To qualify for an alternative closure deadline under § 257.103(f)(2), a facility must meet the following four criteria:

- 1. § 257.103(f)(2)(i) No alternative disposal capacity is available on-site or off-site. An increase in costs or the inconvenience of existing capacity is not sufficient to support qualification.
- 2. § 257.103(f)(2)(ii) Potential risks to human health and the environment from the continued operation of the CCR surface impoundment have been adequately mitigated;
- 3. § 257.103(f)(2)(iii) The facility is in compliance with the CCR rule, including the requirement to conduct any necessary corrective action; and
- 4. § 257.103(f)(2)(iv) The coal-fired boilers must cease operation and closure of the impoundment must be completed within the following timeframes:

- a. For a CCR surface impoundment that is 40 acres or smaller, the coal-fired boiler(s) must cease operation and the CCR surface impoundment must complete closure no later than October 17, 2023.
- b. For a CCR surface impoundment that is larger than 40 acres, the coal-fired boiler(s) must cease operation, and the CCR surface impoundment must complete closure no later than October 17, 2028.

Section 257.103(f)(2)(v) sets out the documentation that must be provided to EPA to demonstrate that the four criteria set out above have been met. Therefore, this demonstration is organized based on the documentation requirements of §§ 257.103(f)(2)(v)(A) - (D).

3.0 DOCUMENTATION OF NO ALTERNATIVE DISPOSAL CAPACITY

To demonstrate that the criteria in § 257.103(f)(2)(i) has been met, the following provides documentation that no alternative disposal capacity is currently available on-site or off-site for each CCR and non-CCR wastestream that Kincaid Generation seeks to continue placing into the Ash Pond after April 11, 2021. Consistent with the regulations, neither an increase in costs nor the inconvenience of existing capacity was used to support qualification under this criteria. Instead, as EPA explained in the preamble to the proposed Part A revisions, "it would be illogical to require [] facilities [ceasing power generation] to construct new capacity to manage CCR and non-CCR wastestreams." 84 Fed. Reg. 65,941, 65,956 (Dec. 2, 2019). EPA again reiterated in the preamble to the final revisions that "[i]n contrast to the provision under § 257.103(f)(1), the owner or operator does not need to develop alternative capacity because of the impending closure of the coal fired boiler. Since the coal-fired boiler will shortly cease power generation, it would be illogical to require these facilities to construct new capacity to manage CCR and non-CCR wastestreams." 85 Fed. Reg. at 53,547. Thus, new construction or the development of new alternative disposal capacity was not considered a viable option for any wastestream discussed below.

3.1 Site-Layout and Wastewater Processes

As shown in Figure 1 (see Appendix A), Kincaid is located between Illinois Highway 104, the Ash Pond, and Sangchris Lake. Fly ash is handled dry and beneficially used offsite. The Ash Pond receives both the bottom ash sluice flows and a portion of the non-CCR wastewater flows onsite. The plant process flows are shown in Appendix B. The remaining impoundments onsite (East Area Runoff Basins, West Area Runoff Basin, the Equalization Basins, and the Standby Pond) are not authorized to receive the CCR sluice flows and are not large enough to independently treat the total volume of the plant process water flows. The existing wastewater treatment plant is sized to treat chemical and non-chemical metal cleaning waste flows (during outages) as well as water treatment plant area runoff, condensate polisher backwash, water treatment plant floor drains, water treatment plant filler backwash, DSI building washdown, and a slip stream of the ash sluice water recycle system as needed to maintain water level and quality. The existing wastewater treatment plant also treats the East Area runoff Basin Effluent discharges which consist of boiler sample drains (i.e. main building drains), east station area stormwater runoff, ash sluice recycle water strainer backwash, mercury monitoring system condensate (to condensate pit sump), main oil water separator (main and auxiliary transformer area runoff, turbine oil pit drains, turbine room floor drains, boiler fan area floor drains), oil/water separator no. 1 (turbine room pump, D.C. heater drains condensate pit sump), and auxiliary boiler blowdown. This wastewater treatment plant is not large enough to treat the sluice flows, coal pile runoff, stormwater, and other miscellaneous low volume wastewaters onsite that currently are treated in the Ash Pond.

3.2 CCR Wastestreams

Kincaid Generation evaluated each CCR wastestream placed in the Ash Pond at Kincaid. For the reasons discussed below in Table 3-1, each of the following CCR wastestreams must continue to be placed in the Ash Pond due to lack of alternative capacity both on and off-site.

Alternative Disposal **Estimated** Capacity Currently Average Available? **CCR Flow** (MGD) YES/NO **Details** Wastestreams Currently, alternative capacity is not available, nor a feasible option as discussed below. On-site Bottom Ash, 17.6 alternative capacity would need to be designed. Economizer Ash. (recycled NO permitted, and installed. Off-site alternative and Air Heater from pond) capacity would include development of on-site Ash Sluice temporary tanks and transporting of this sluice material offsite for disposal

Table 3-1: Kincaid CCR Wastestreams

Kincaid Generation evaluated the following on-site and off-site alternative capacity options for these CCR wastestreams:

- Bottom ash, economizer ash, and non-CCR mill rejects sluice (17.6 MGD average):
 - On-site alternative capacity is currently not available and would need to be developed. The
 East Area Runoff Basins, West Area Runoff Basin, the Equalization Basins, and the Standby
 Pond are not CCR surface impoundments and cannot receive CCR materials.
 - o Development of on-site alternative capacity would require the design, permitting, and installation of a new treatment system including CCR ponds, clarifiers, and/or storage tank(s) to provide the necessary retention time to meet the NPDES permit limits. The environmental permitting would include a modification to the current individual NPDES permit (to allow for the rerouting of this wastestream to another outfall), a general NPDES stormwater construction permit (includes threatened and endangered species and historic preservation assessments), a construction & operating permit under the Illinois CCR rule (35 IAC 845), and a SWPPP at a minimum which would require a minimum of three years to implement.
 - Off-site alternative capacity is currently not available and would need to be developed. Developed off-site alternative capacity would consist of both temporary on-site wet storage (frac tanks) and off-site transportation via tanker trucks. The current average daily flow includes 17.6 MGD of sluice water, recycled from the pond with the sluice pumps operated

continuously. The plant would need to modify operations and sluice in batches to minimize this flow to approximately 8 hours per day if offsite disposal were required (ash sluiced twice per shift for one hour per sluice cycle per unit). This modification would reduce the flow to approximately 6 MGD, requiring 286 frac tanks to provide 24 hours of residence time. The boiler slag production is estimated at 13 tons per hour per unit, or 26 tons per hour for the station. This would require replacement of approximately 25 frac tanks per day during periods of peak generation. This sluice flow would be recirculated as much as possible and purged at approximately 10% per day to maintain the sluice water chemistry. This purge would require 80 daily tanker trucks (~7,500 gallons per truck to maintain DOT weight restrictions) if a local POTW could be identified to receive it. The daily tanker truck traffic would result in increased potential for safety and noise impacts and further increases in fugitive dust, greenhouse gas emissions and carbon footprint which may require a PSD permit and modification under the Clean Air Act Permit Program if the calculated increases in emissions are over the PSD limits. Setting up arrangements for a local Publicly Owned Treatment Works (POTW) to accept the wastewater would prove to be difficult since this amount of wastewater would most likely upset their treatment systems causing them to exceed their NPDES discharge limits. The potential for leaks/spills from the tank system or transportation of the wastewater offsite does exist. Furthermore, the temporary wet storage needed to accommodate off-site disposal would require reconfiguration, design, installation, and associated environmental permitting which would require a minimum of two years to implement. For all of these reasons, Kincaid Generation has determined that offsite disposal is not feasible for these flows at Kincaid.

As stated previously, because Kincaid Generation has elected to pursue the option to permanently cease the use of the two coal-fired boilers at the station by no later than July 17, 2027, developing alternative disposal capacity is "illogical," to use EPA's words, and also counterproductive to the work to cease coal-fired operations of the boilers and close the impoundment. As long as Kincaid Generation continues to wet handle the bottom ash, economizer ash and air heater ash material, there are no other onsite CCR impoundments available to receive and treat these flows and it is not feasible to dispose of the wet-handled material offsite. The remaining impoundments onsite (West Area Runoff Basin, Equalization Basins 1 & 2, the Standby Pond and East Area Runoff Basins 1 & 2) are not authorized to receive the CCR sluice flows. As EPA explained in the preamble of the 2015 rule, it is not possible for sites that sluice CCR material to an impoundment to eliminate the impoundment and dispose of the material offsite. *See* 80 Fed. Reg. 21,301, 21,423 (Apr. 17, 2015) ("[W]hile it is possible to transport dry ash off-site to [an] alternate disposal facility that is simply not feasible for wet-generated CCR. Nor can facilities immediately convert to dry handling

systems."). As a result, the conditions at Kincaid satisfy the demonstration requirement in § 257.103(f)(2)(i).

Consequently, in order to continue to operate and generate electricity, Kincaid must continue to use the 172-acre CCR surface impoundment to manage the CCR wastestreams discussed above.

3.3 Non-CCR Wastestreams

Kincaid Generation evaluated each non-CCR wastestream placed in the Ash Pond at Kincaid. These streams are collected in the West Area Runoff Basin and a portion is pumped to the Ash Pond for additional treatment (TSS removal) before being routed to junction box downstream of the existing wastewater treatment plant for discharge (the remaining portion is pumped to the waste water treatment plant). The total flow from the West Area Runoff Basin to the Ash Pond averages 1 million gallons per day up to 4.1 million gallons per day maximum. This flow rate, and the high surges from storm events, requires continued use of the Ash Pond for equalization upstream of the existing wastewater treatment system. The West Area Runoff Basin does not have a permitted outfall. For the reasons discussed below in Table 3-2, each of the following non-CCR wastestreams must continue to be placed in the Ash Pond due to lack of alternative capacity both on and off-site.

Table 3-2: Kincaid Non-CCR Wastestreams

Non-CCR Wastestreams	Estimated Average Flow (MGD)	Alternative Disposal Capacity Currently Available? YES/NO	Details
Slag Tank Cooling Water	1.5	NO	Currently, alternative capacity is not available nor is a feasible
Tunnel Ground Water Sump	0.014	NO	option for these wastestreams as discussed below. Some of these
Intake Pump House Sump	0.010	NO	flows contain high levels of TSS that would overwhelm the current
Coal Pile Runoff and Site Stormwater (includes Ammonia Storage Tank Sump and Condensate Storage Area and Overflows)	Intermittent (4.45 for 10-year, 24-hour storm)	NO	wastewater treatment system if the Ash Pond were removed from service. Therefore, on-site alternative capacity would need to be designed, permitted, and installed. Off-site alternative capacity would include development of on-site temporary tanks and transporting of these wastestreams offsite for disposal.

Kincaid Generation evaluated on-site and off-site alternative capacity options for the non-CCR wastestreams. Development of on-site alternative capacity would require the design, permitting, and installation of a new treatment system including non-CCR ponds, clarifiers, and/or storage tank(s) to provide the necessary retention time for TSS removal to meet the NPDES permit limits. The environmental permitting would include a modification to the current individual NPDES permit (to allow for the rerouting of this wastestream to another outfall), general NPDES stormwater construction permit (includes threatened and endangered species and historic preservation assessments), a construction & operating permit, and a SWPPP at a minimum which would require a minimum of three years to implement.

Development of off-site alternative capacity would consist of both temporary on-site wet storage (frac tanks) and off-site transportation via tanker trucks assuming a local POTW could be identified to receive these streams. The West Area Runoff Basin receives all of these flows but has a relatively small storage volume and does not have a permitted outfall. This pond is pumped to the Ash Pond at a rate of 4.08 MGD to prevent discharges during rain events, and this flow would need to be received by the temporary frac tanks if the Ash Pond were not available. The required daily frac tanks and tanker trucks (~7,500 gallons per truck to maintain DOT weight restrictions) for each wastestream during each sluicing event is provided in Table 3-3. The daily tanker truck traffic would result in increased potential for safety and noise impacts and further increases in fugitive dust, greenhouse gas emissions and carbon footprint which may require a PSD permit and modification under the Clean Air Act Permit Program if the calculated increases in emissions are over the PSD limits. Setting up arrangements for a local POTW to accept this wastewater could prove to be difficult if this amount of wastewater would upset their treatment systems, causing them to exceed their NPDES discharge limits. Kincaid Generation is continuing to have discussions with local POTW's to determine if they have the capacity and the infrastructure to handle these daily volumes of wastewater. This will also include efforts to characterize the waste. Kincaid Generation will update EPA in forthcoming progress reports if offsite disposal capacity becomes available. The potential for leaks/spills from the tank system or transportation of the wastewater offsite does also exist. Furthermore, the temporary wet storage needed to accommodate off-site disposal would require reconfiguration, design, installation, and associated environmental permitting which would require a minimum of one year to implement. For all of these reasons, Kincaid Generation has determined that offsite disposal is not feasible for these flows at Kincaid at this time.

Table 3-3: Non-CCR Wastestream Offsite Disposal

Non-CCR Wastestreams	Estimated Flow (MGD)	No. of Frac Tanks required (21,000 gallons each)	No. of Trucks required per day (7,500 gallons each)
Slag Tank Cooling Water	1.5	72	200
Tunnel Ground Water Sump	0.014	1	2
Intake Pump House Sump	0.010	1	2
Coal Pile Runoff and Site Stormwater	0 - 4.45	0 - 212	0 - 594
	Total	74 - 286	204 - 798

As stated previously, because Kincaid Generation has elected to pursue the option to permanently cease the use of the two coal fired boilers at the station by no later than July 17, 2027, developing alternative disposal capacity is "illogical," to use EPA's words, and also counterproductive to the work to cease coal-fired operations of boilers and close the impoundment. There is currently no available infrastructure at the plant to support reroute of these flows. For the reasons discussed above, each of the following non-CCR wastestreams must continue to be placed in the Ash Pond due to lack of alternative capacity both on and off-site. Consequently, in order to continue to operate and generate electricity, Kincaid must continue to use the Ash Pond to manage the non-CCR wastestreams discussed above.

4.0 RISK MITIGATION PLAN

To demonstrate that the criteria in § 257.103(f)(2)(ii) has been met, Kincaid Generation has prepared and attached a Risk Mitigation Plan for the Kincaid Ash Pond (see Attachment 1). Per § 257.103(f)(2)(v)(B), this Risk Mitigation Plan is only required for the specific CCR Unit(s) that are the subject of this demonstration.

5.0 DOCUMENTATION AND CERTIFICATION OF COMPLIANCE

In the Part A rule preamble, EPA reiterates that compliance with the CCR rule is a prerequisite to qualifying for an alternative closure extension, as it "provides some guarantee that the risks at the facility are properly managed and adequately mitigated." 85 Fed. Reg. at 53,543. EPA further stated that it "must be able to affirmatively conclude that facility meets this criterion prior to any continued operation." 85 Fed. Reg. at 53,543. Accordingly, EPA "will review a facility's current compliance with the requirements governing groundwater monitoring systems." 85 Fed. Reg. at 53,543. In addition, EPA will also "require and examine a facility's corrective action documentation, structural stability documents and other pertinent compliance information." 85 Fed. Reg. at 53,543. Therefore, EPA is requiring a certification of compliance and specific compliance documentation be submitted as part of the demonstration. 40 C.F.R. § 257.103(f)(2)(v)(C).

The Kincaid facility includes a CCR unit (the Ash Pond) that is the subject of this demonstration. To demonstrate that the criteria in $\S 257.103(f)(2)(iii)$ has been met, Kincaid Generation is submitting the following information as required by $\S 257.103(f)(2)(v)(C)$:

5.1 Owner's Certification of Compliance - § 257.103(f)(2)(v)(C)(1)

I hereby certify that, based on my inquiry of those persons who are immediately responsible for compliance with environmental regulations for Kincaid, the facility is in compliance with all of the requirements contained in 40 C.F.R. Part 257, Subpart D – Standards for the Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments. The Kincaid CCR compliance website is up-to-date and contains all the necessary documentation and notification postings.

On behalf of Kincaid Generation:

Cyrolin E Ubdy

Cynthia Vodopivec

VP - Environmental Health & Safety

November 24, 2020

5.2 Visual representation of hydrogeologic information - § 257.103(f)(2)(v)(C)(2)

Consistent with the requirements of $\S 257.103(f)(2)(v)(C)(2)(i) - (iii)$, Kincaid Generation has attached the following items to this demonstration:

- Map(s) of groundwater monitoring well locations in relation to the CCR unit (Attachment 2)
- Well construction diagrams and drilling logs for all groundwater monitoring wells (Attachment 3)
- Maps that characterize the direction of groundwater flow accounting for seasonal variations (Attachment 4)

5.3 Groundwater monitoring results - § 257.103(f)(2)(v)(C)(3)

Tables summarizing constituent concentrations at each groundwater monitoring well through the first 2020 semi-annual monitoring period are included as Attachment 5. Samples were taken for the second 2020 semi-annual monitoring period, but results are still under review.

5.4 Description of site hydrogeology including stratigraphic cross-sections - § 257.103(f)(2)(v)(C)(4)

A description of the site hydrogeology and stratigraphic cross-sections of the site are included as Attachment 6.

5.5 Corrective measures assessment - § 257.103(f)(2)(v)(C)(5)

Background sampling began in late 2015 and continued for eight consecutive quarters. The first semiannual detection monitoring samples were collected in November 2017. The first assessment monitoring samples were collected in May 2018. The results, through the 2020 monitoring period, indicate that the Kincaid Ash Pond is currently in assessment monitoring, with no exceedances of the Appendix IV parameters. Accordingly, an assessment of corrective measures is not currently required at the site. Kincaid will continue to conduct groundwater monitoring in accordance with all state and federal requirements.

5.6 Remedy selection progress report - § 257.103(f)(2)(v)(C)(6)

As noted above, an assessment of corrective measures and the resulting selection of remedy are not currently required for the Ash Pond.

5.7 Structural stability assessment - § 257.103(f)(2)(v)(C)(7)

Pursuant to § 257.73(d), the initial structural stability assessment for the Ash Pond was prepared in October 2016 and is included as Attachment 7, as well as a memorandum which confirms the structural stability assessment.

5.8 Safety factor assessment - § 257.103(f)(2)(v)(C)(8)

Pursuant to § 257.73(e), the initial safety factor assessment for the Ash Pond was prepared in October 2016 and is included as Attachment 8.

6.0 DOCUMENTATION OF CLOSURE COMPLETION TIMEFRAME

To demonstrate that the criteria in § 257.103(f)(2)(iv) has been met, "the owner or operator must submit the closure plan required by § 257.102(b) and a narrative that specifies and justifies the date by which they intend to cease receipt of waste into the unit in order to meet the closure deadlines." The closure plan for the Ash Pond, along with an addendum, is included as Attachment 9.

In order for a CCR surface impoundment over 40 acres to continue to receive CCR and non-CCR wastestreams after the initial April 11, 2021 deadline, the coal-fired boiler(s) at the facility must cease operation and the CCR surface impoundment must complete closure no later than October 17, 2028. As discussed below, Kincaid will begin construction of the Ash Pond closure by April 17, 2025, the two boilers will cease coal-fired operations no later than July 17, 2027, and Kincaid will cease placing wastestreams into the Ash Pond on September 17, 2027, in order for closure to be completed by this deadline.

Table 6-1 is included below to summarize the major tasks and estimated durations associated with closing the Ash Pond in place. These durations are consistent with the durations experienced with the closure of approximately 500 acres of other CCR impoundments already completed by Kincaid Generation and its affiliates to date as noted below:

- Baldwin Fly Ash Pond System 230 acres closed in-place with an approximate 30-month construction schedule
- Hennepin West Ash Ponds System 35 acres closed in-place with an approximate 24-month
 construction schedule (includes closure by removal of an adjacent 6-acre settling pond and
 installing a sheet pile wall)
- Hennepin East Ash Ponds 2 and 4 25 acres closed in-place with an approximate 6-month construction schedule
- Coffeen Ash Pond 2 60 acres closed in-place with an approximate 24-month construction schedule
- Duck Creek Ash Ponds 1 and 2 130 acres closed in-place with an approximate 24-month construction schedule

Each CCR impoundment closure indicated above utilized a coordinated passive or gravity dewatering method, which consisted of the use of trenches excavated to lower the phreatic surface in portions of the impoundment to obtain a stable ash surface to permit the safe construction of the final cover system. The phreatic water in the trenches flows by gravity to sumps constructed within the impoundment. The major benefit associated with this passive or gravity dewatering method is that the sumps are designed to provide

holding time to allow the TSS to settle within the impoundment prior to discharge (an active dewatering method with wells would result in increased amounts of unsettled TSS). After solids settling, the water is discharged through the NPDES outfall in compliance with permitted limits.

Construction progressed sequentially as the dewatering of an area stabilized the ash surface. The CCR was graded to subgrade level, then overlain with the compacted clay layers and/or geomembrane liners. Vegetative soil cover was then placed on top of the infiltration layer. As each section of the impoundment was closed, this sequencing progressed to the completion of the pond closure. A similar process will be utilized to close the Kincaid Ash Pond in order to allow the final open section of the impoundment to be large enough for the impoundment to remain in operation until the pond ceases the receipt of waste. This would provide sufficient time for closure to be completed by October 17, 2028.

The first construction effort will involve modifying the pond operations by relocating the influent lines, minimizing the pond water levels, and isolating flow to a smaller portion of the current 172-acre impoundment that can be closed during the last two construction seasons. The smaller active portion of the pond will remain in operation while Kincaid Generation begins dewatering and closing the impoundment as described above. This reduction in footprint may require the addition of chemical feeds to provide adequate treatment but that has not been the case at our other sequenced closures. This approach simultaneously allows for continued operation of the plant to maintain generating capacity for the PJM markets and minimizes the risk to the environment both by minimizing the pond size and the potential for any impacts to groundwater and by opening up a significant portion of the remaining impoundment to allow for dewatering, grading, and closure (in Phase 1).

Table 6-1 provides estimates for the durations required to close a portion of the pond footprint after the date noted to begin closure construction (Phase 1), as well as the current estimates for the closure of the active area (Phase 2, remaining 40-50 acres). In order to dewater the closure area, Kincaid Generation will likely release pond water through the existing Outfall E01.

Table 6-1: Kincaid Ash Pond Closure Schedule

Action	Estimated Timeline (Months)
Spec, bid, and Award Engineering Services for CCR Impoundment Closure	3
Finalize CCR unit closure plan and seek IEPA approval for CCR unit closure	12

Action	Estimated Timeline (Months)
Obtain environmental permits (based on IEPA approval of closure plan):	
 State Waste Pollution Control Construction/Operating Permit NPDES Industrial Wastewater Permit Modification (modification would be required to allow the associated ponded and subsurface free liquids generated before the pond closure to be discharged to Waters of the US and to allow reconfiguration of the various wastestreams to either other NPDES- permitted outfalls or newly-constructed NPDES-permitted outfalls) General NPDES Permit for Storm Water Discharges from Construction Site Activities and a SWPPP Proposed 35 III. Admin Code 845 operating permit application is due NLT September 2021. Construction permit application is anticipated to be due NLT July 2022. 	21
Spec, bid, and Award Construction Services for CCR Impoundment Closure	3
Begin Construction of Closure	April 17, 2025
Minimize Active Area of Impoundment/Dewater Phase 1 Area	6
Regrade CCR Material in Phase 1 Area	18
Install Cover System – Phase 1 Area*	13
Establish Vegetation – Phase 1 Area**	2
Cease Coal-Fired Operations of the Six Boilers onsite (No Later Than)	July 17, 2027
Begin Dewatering Impoundment – Phase 2 Area	2
Cease Placement of Waste (No Later Than, allowing for plant cleanup and dredging of impoundments following coal pile and plant closure)	September 17, 2027
Continue Dewatering Impoundment – Phase 2 Area	1

Action	Estimated Timeline (Months)
Regrade CCR Material – Phase 2 Area	6
Install Cover System- Phase 2 Area	5
Establish Vegetation, Perform Site Restoration Activities, Complete Closure, and Initiate Post- Closure Care**	2
Total Estimated Time to Complete Closure	81 months
Date by Which Closure Must be Complete	October 17, 2028

^{*} Activity expected to overlap with grading operations, finishing 2 months after grading is completed.

^{**} Activity expected to overlap with cover system installation, finishing 1 month after cover installation is completed.

7.0 CONCLUSION

Based upon the information included in and attached to this demonstration, Kincaid Generation has demonstrated that the requirements of 40 C.F.R. § 257.103(f)(2) are satisfied for the 172-acre Ash Pond at Kincaid. This CCR surface impoundment is needed to continue to manage the CCR and non-CCR wastestreams identified in Section 3.2 and 3.3 above, is larger than 40 acres, the two boilers at the station will cease coal-fired operations by no later than July 17, 2027, and the Ash Pond will be closed by the October 17, 2028 deadline. Therefore, this CCR unit qualifies for the site-specific alternative deadline for the initiation of closure authorized by 40 C.F.R. § 257.103(f)(2).

Therefore, it is requested that EPA approve Kincaid Generation's demonstration and authorize the Ash Pond at Kincaid to continue to receive CCR and non-CCR wastestreams notwithstanding the deadline in § 257.101(a)(1) and to grant the alternative deadline of October 17, 2028, by which to complete closure of the impoundment.



View All News

VISTRA ACCELERATES PIVOT TO INVEST IN CLEAN ENERGY AND COMBAT CLIMATE CHANGE

September 29, 2020

Company to break ground on nearly 1,000 megawatts of renewables and storage; announces planned retirement of entire Midwest coal fleet

Provides financial update, raises 2020 financial guidance, and announces long-term capital allocation plan from continued strong financial outlook

IRVING, Texas, Sept. 29, 2020 /PRNewswire/ -- Vistra (NYSE: VST) today announced a comprehensive plan to accelerate its transition to clean power generation sources and advance efforts to significantly reduce its carbon footprint. The company launched Vistra Zero, a portfolio of zero-carbon power generation facilities, including seven new developments announced today in its primary market of ERCOT that total nearly 1,000 megawatts. In addition, the company committed to more ambitious long-term emissions reduction targets, released its first climate report, and announced its intention to retire all of its generation subsidiaries' coal plants in Illinois and Ohio.

"The aggregate impact of these milestone initiatives is clear: Vistra's commitment to our transformation to a low-to-no-carbon future is unequivocal and offers unique opportunities for growth and innovation," said Curt Morgan, president and CEO of Vistra. "As evidenced by the actions we take and investments we make, Vistra is paving its way for a sustainable future – economically and environmentally – and we've been focused on transitioning our generation portfolio for the benefit of the environment, our customers, our communities, our people, and our shareholders."

Morgan continued, "Importantly, Vistra's leadership on these issues will not impact our core mission to provide consumers with reliable, affordable, and sustainable energy while lowering emissions. Electricity is an essential resource, and the demand for it will continue to grow as climate initiatives are implemented and the economy is further electrified. So, while the way we produce electricity is changing, our essential role in the process and core mission will not. Vistra is well-positioned to not only prove our resiliency during this important transformation to cleaner generation sources, but to lead the way. Our value proposition has never been stronger, and our sustainability has never been clearer. We are confident over time that the severe under-valuation of our stock price will be recognized, and our fair value achieved."

New Zero-Carbon Development Projects: Vistra Zero

Vistra, which is already developing the world's largest battery energy storage project, the 400-MW/1,600-MWh Moss Landing Energy Storage Facility in California, today announced that it is breaking ground on six new solar projects and one battery energy storage project. These new zero-carbon developments, which are part of a newly launched Vistra Zero portfolio, represent a capital investment of approximately \$850 million and are all located in the attractive Texas ERCOT market where Vistra has a leadership position:

Expected online in 2021

- Andrews Solar Facility, Andrews County 100 MW
- Brightside Solar Facility, Live Oak County 50 MW
- Emerald Grove Solar Facility, Crane County 108 MW
- Upton 2 Solar and Energy Storage Facility Phase III, Upton County 10 MW solar
 - Additional solar capacity to be added to the already operational facility, bringing its total solar capacity to 190 MW

Expected online in 2022

- DeCordova Energy Storage Facility, Hood County 260 MW/260 MWh
 - Co-located on site of Luminant's natural gas-fueled DeCordova Power Plant
- Forest Grove Solar Facility, Henderson County 200 MW
- Oak Hill Solar Facility, Rusk County 200 MW

The Vistra Zero portfolio also includes the company's existing nuclear, renewable, and energy storage facilities:

• Comanche Peak Nuclear Power Plant (2,300 MW)

- Upton 2 Solar (180 MW) and Energy Storage Facility (10 MW/42 MWh)
- Moss Landing Energy Storage Facility (400 MW/1,600 MWh) 300 MW Phase I expected online December 2020; 100 MW Phase II expected online by August 2021
- Oakland Energy Storage Facility (36.25 MW/145 MWh) expected online January 2022

Inclusive of its new carbon-free projects, the Vistra Zero portfolio now consists of approximately 4,000 MW of zero-carbon assets. In addition, the company continues to evaluate additional solar and battery projects, including more than 1,000 MW in Texas, more than 1,000 MW in California, and approximately 450 MW in Illinois under the Coal to Solar and Energy Storage Act. Vistra is also exploring potential future development opportunities at many of the company's existing power plant sites.

Updated 2030/2050 Emissions Reduction Targets

Consistent with its strategic priorities, the company also accelerated its greenhouse gas emissions reduction targets. Vistra is now setting out to achieve a 60% reduction, up from 50%, in CO₂ equivalent emissions by 2030 as compared to a 2010 baseline, and a long-term objective to achieve net-zero carbon emissions, up from an 80% reduction target, by 2050¹.

1 Assuming necessary advancements in technology and supportive market constructs and public policy

CO₂ Reductions Through Coal Retirements

Vistra also announced its next phase of coal plant closures in Illinois and Ohio. The company expects to retire seven Luminant power plants, of which the company owns a combined capacity of more than 6,800 MW, between 2022 and 2027.

By year-end 2022

• Edwards Power Plant, Bartonville, IL (MISO) - 585 MW previously announced

By year-end 2025 or sooner should economic or other conditions dictate

- Baldwin Power Plant, Baldwin, IL (MISO) 1,185 MW
- Joppa Power Plant, Joppa, IL (MISO) 1,002 MW (plus 239 MW of gas-fueled combustion turbines)

By year-end 2027 or sooner should economic or other conditions dictate

- Kincaid Power Plant, Kincaid, IL (PJM) 1,108 MW
- Miami Fort Power Plant, North Bend, OH (PJM) 1,020 MW
- Newton Power Plant, Newton, IL (MISO) 615 MW
- Zimmer Power Plant, Moscow, OH (PJM) 1,300 MW

These plants, especially those operating in the irreparably dysfunctional MISO market, remain economically challenged. Today's retirement announcements are also prompted by upcoming Environmental Protection Agency filing deadlines, which require either significant capital expenditures for compliance or retirement declarations.

"Our team members have gone above and beyond to make these plants viable, and they have been safely powering these communities with affordable and reliable electricity for decades," said Jim Burke, chief operating officer of Vistra. "The advance notice of these retirements provides us with ample time to work with our impacted employees and communities to ease the impact of the closures, including seeking the passage of the Illinois Coal to Solar and Energy Storage Act. We've proven ourselves in previous similar situations to live up to our core principles, taking care of our employees and communities. That will not change."

Since the company's leadership change in 2016, Vistra and its subsidiaries have closed or announced the closure of 19 coal plants totaling more than 16,000 MW across Texas (2018: Big Brown, Monticello, Sandow), Pennsylvania (2018: Northeastern Power Co.), Ohio (2018: J.M. Stuart, Killen; no later than 2027: Miami Fort, Zimmer), Illinois (2016: Wood River; 2019: Coffeen, Duck Creek, Havana, Hennepin; 2022: Edwards; no later than 2025: Baldwin, Joppa; no later than 2027: Kincaid, Newton), and Massachusetts (2017: Brayton Point). In total, Vistra and its subsidiaries have now retired or announced the retirement of more than 19,000 MW at 23 coal and natural gas plants since 2010.

1 Vistra has an 80% ownership interest in Joppa Power Plant that, when combined with its 80-100% ownership interest in the Joppa combustion turbines, totals 1,023 MW of the site's total capacity

Vistra's Climate Report

A comprehensive review of Vistra's climate strategy is contained in Vistra's first Climate Report, published today in accordance with the guidance set forth by the Task Force on Climate-related Financial Disclosures (TCFD). Among other topics, the Climate Report discusses various climate-related risks and opportunities that Vistra management has identified as influencing the company's long-term strategy. Importantly, as an innovative, market-leading integrated power company, Vistra believes global climate change mitigation will create significant opportunities for the company to grow, even as it reduces its total emissions over the next several decades.

Financial Update

Also this morning, Vistra provided certain financial updates, including raising and narrowing its 2020 financial guidance, initiating its 2021 financial guidance, and announcing its long-term capital allocation plan. Specifically, Vistra:

• Raised and narrowed its 2020 financial guidance:

(\$ in millions)	Prior 2020	Current 2020
Ongoing Ops. Adj. EBITDA ¹	\$ 3,285 – 3,585	\$ 3,485 – 3,685
Ongoing Ops. Adj. FCFbG ¹	\$ 2,160 – 2,460	\$ 2,375 - \$2,575
FCF Conversion	~67%	~69%

• Initiated its 2021 financial guidance:

(\$ in millions)	2021	
Ongoing Ops. Adj. EBITDA ¹	\$	3,075 – 3,475
Ongoing Ops. Adj. FCFbG ¹	\$	1,765 – 2,165
FCF Conversion	~60%	

• And announced its long-term capital allocation plan:

(\$ in millions)

	2021	2022
Debt Reduction	~\$550	
	~\$275	~\$350
Enhanced Dividend ²	(\$0.58/share)	(\$0.76/share)
Share Repurchases	Up to \$1,500	
Transformation Growth	~\$650	~\$500

As depicted in the table above, in September 2020 Vistra's board of directors authorized a \$1.5 billion share repurchase program. The program commences Jan. 1, 2021, does not expire, and replaces any authorization that remains at the end of 2020 under Vistra's existing repurchase plan.

With today's financial updates, Vistra is on track to beat its original guidance midpoint for the fifth year in a row and potentially even exceed the top end of its original guidance range — despite a pandemic tail event in 2020. In addition, with the continued debt reduction in 2021 and 2022 Vistra believes it is well-positioned to achieve improved credit ratings including the potential to achieve investment grade ratings over this timeframe. The company also believes it is well-positioned to consistently deliver strong long-term earnings into the future, while investing in the transformation of the company and returning a significant amount of its free cash flow to its financial stakeholders on an annual basis.

1 Excludes the Asset Closure segment. Ongoing Operations Adjusted EBITDA and Ongoing Operations Adjusted FCFbG are non-GAAP financial measures. See the "Non-GAAP Reconciliation" tables for further details.

2 Management recommendation; subject to Board of Director's approval at the applicable time.

Media

Meranda Cohn Media.Relations@vistracorp.com 214-875-8004

Analysts

Molly Sorg 214-812-0046 Investor@vistracorp.com

About Vistra

Vistra (NYSE: VST) is a leading, Fortune 275 integrated retail electricity and power generation company based in Irving, Texas, providing essential resources for customers, commerce, and communities. Vistra combines an innovative, customer-centric approach to retail with safe, reliable, diverse, and efficient power generation. The company brings its products and services to market in 20 states and the District of Columbia, including six of the seven competitive wholesale markets in the U.S. and markets in Canada and Japan, as well. Serving nearly 5 million residential, commercial, and industrial retail customers with electricity and natural gas, Vistra is the largest competitive residential electricity provider in the country and offers over 50 renewable energy plans. The company is also the largest competitive power generator in the U.S. with a capacity of approximately 39,000 megawatts powered by a diverse portfolio, including natural gas, nuclear, solar, and battery energy storage facilities. In addition, the company is a large purchaser of wind power. The company is currently constructing a 400-MW/1,600-MWh battery energy storage system in Moss Landing, California, which will be the largest of its kind in the world when it comes online. Vistra is guided by four core principles: we do business the right way,

we work as a team, we compete to win, and we care about our stakeholders, including our customers, our communities where we work and live, our employees, and our investors. Learn more about our environmental, social, and governance efforts and read the company's sustainability report at https://www.vistracorp.com/sustainability/.

Cautionary Note Regarding Forward-Looking Statements

The information presented herein includes forward-looking statements within the meaning of the Private Securities Litigation Reform Act of 1995. These forward-looking statements, which are based on current expectations, estimates and projections about the industry and markets in which Vistra Corp. ("Vistra") operates and beliefs of and assumptions made by Vistra's management, involve risks and uncertainties, which are difficult to predict and are not guarantees of future performance, that could significantly affect the financial results of Vistra. All statements, other than statements of historical facts, that are presented herein, or in response to questions or otherwise, that address activities, events or developments that may occur in the future, including such matters as activities related to our financial or operational projections, the potential impacts of the COVID-19 pandemic on our results of operations, financial condition and cash flows, projected synergy, value lever and net debt targets, capital allocation, capital expenditures, liquidity, projected Adjusted EBITDA to free cash flow conversion rate, dividend policy, business strategy, competitive strengths, goals, future acquisitions or dispositions, development or operation of power generation assets, market and industry developments and the growth of our businesses and operations (often, but not always, through the use of words or phrases, or the negative variations of those words or other comparable words of a future or forward-looking nature, including, but not limited to: "intends," "plans," "will likely," "unlikely," "believe," "confident", "expect," "seek," "anticipate," "estimate," "continue," "will," "shall," "should," "could," "may," "might," "predict," "project," "forecast," "target," "potential," "goal," "objective," "guidance" and "outlook"), are forward-looking statements. Readers are cautioned not to place undue reliance on forward-looking statements. Although Vistra believes that in making any such forward-looking statement, Vistra's expectations are based on reasonable assumptions, any such forward-looking statement involves uncertainties and risks that could cause results to differ materially from those projected in or implied by any such forward-looking statement, including, but not limited to: (i) adverse changes in general economic or market conditions (including changes in interest rates) or changes in political conditions or federal or state laws and regulations; (ii) the ability of Vistra to execute upon the contemplated strategic, capital allocation, and performance initiatives and to successfully integrate acquired businesses; (iii) actions by credit ratings agencies; (iv) the severity, magnitude and duration of pandemics, including the COVID-19 pandemic, and the resulting effects on our results of operations, financial condition and cash flows; and (v) those additional risks and factors discussed in reports filed with the Securities and Exchange Commission by Vistra from time to time, including the uncertainties and risks discussed in the sections entitled "Risk Factors" and "Forward-Looking Statements" in Vistra's annual report on Form 10-K for the year ended Dec. 31, 2019 and any subsequently filed quarterly reports on Form 10-Q.

Any forward-looking statement speaks only at the date on which it is made, and except as may be required by law, Vistra will not undertake any obligation to update any forward-looking statement to reflect events or circumstances after the date on which it is made or to reflect the occurrence of unanticipated events. New factors emerge from time to time, and it is not possible to predict all of them; nor can Vistra assess the impact of each such factor or the extent to which any factor, or combination of factors, may cause results to differ materially from those contained in any forward-looking statement.

VISTRA CORP.

NON-GAAP RECONCILIATIONS – PRIOR 2020 GUIDANCE¹

(Unaudited) (Millions of Dollars)

	Ongoing		Asset		Vistra	
	Operations		Closure		Consolidated	
	Low	High	Low	High	Low	High
Net Income (loss)	\$ 849	\$ 1,081	\$ (95)	\$ (75)	\$ 754	\$ 1,006
Income tax expense	252	320	_	_	252	320
Interest expense and related charges (a)	463	463	_	_	463	463
Depreciation and amortization (b)	1,600	1,600	_	_	1,600	1,600
EBITDA before Adjustments	\$ 3,164	\$ 3,464	\$ (95)	\$ (75)	\$ 3,069	\$ 3,389
Unrealized net (gain)/loss resulting from hedging transactions	(29)	(29)	_	_	(29)	(29)
Impacts of Tax Receivable Agreement	69	69	_	_	69	69
Non-cash compensation expenses	44	44	_	_	44	44
Transition and merger expenses	35	35	_	_	35	35
Other, net	2	2			2	2
Adjusted EBITDA guidance	\$ 3,285	\$ 3,585	\$ (95)	\$ (75)	\$ 3,190	\$ 3,510
Interest paid, net	(543)	(543)	_	_	(543)	(543)
Tax (paid)/received (c)	153	153	_	_	153	153
Tax receivable agreement payments	(3)	(3)	_	_	(3)	(3)
Working capital and margin deposits	2	2	_	_	2	2

Reclamation and remediation	(60)	(60)	(126)	(126)	(186)	(186)
Other changes in other operating assets and liabilities	(80)	(80)	31	31	(49)	(49)
Cash provided by operating activities	\$ 2,754	\$ 3,054	\$ (190)	\$ (170)	\$ 2,564	\$ 2,884
Capital expenditures including nuclear fuel purchases and LTSA Prepayments	(613)	(613)	_	_	(613)	(613)
Solar and Moss Landing development and other growth expenditures	(315)	(315)	_	_	(315)	(315)
(Purchase)/sale of environmental credits and allowances	(39)	(39)	_	_	(39)	(39)
Other net investing activities	(20)	(20)	_	_	(20)	(20)
Free cash flow	\$ 1,767	\$ 2,067	\$ (190)	\$ (170)	\$ 1,577	\$ 1,897
Working capital and margin deposits	(2)	(2)	_	_	(2)	(2)
Solar and Moss Landing development and other growth expenditures	315	315	_	_	315	315
Purchase/(sale) of environmental credits and allowances	39	39	_	_	39	39
Transition and merger expenses	38	38	_	_	38	38
Transition capital expenditures	3	3			3	3

VISTRA CORP. NON-GAAP RECONCILIATIONS – CURRENT 2020 GUIDANCE¹ (Unaudited) (Millions of Dollars)

	Ongoing		Asset		Vistra	
	Operations		Closure		Consolidated	
	Low	High	Low	High	Low	High
Net Income (loss)	\$ 897	\$ 1,053	\$ (87)	\$ (77)	\$ 810	\$ 976
Income tax expense	249	293	_	_	249	293
Interest expense and related charges (a)	657	657	_	_	657	657
Depreciation and amortization (b)	1,750	1,750	_	_	1,750	1,750
EBITDA before Adjustments	\$ 3,553	\$ 3,753	\$ (87)	\$ (77)	\$ 3,466	\$ 3,376
Unrealized net (gain)/loss resulting from hedging transactions	(364)	(364)	_	_	(364)	(364)
Fresh start / purchase accounting impacts	31	31	_	_	31	31
Impacts of Tax Receivable Agreement	47	47	_	_	47	47
Non-cash compensation expenses	59	59	_	_	59	59
Transition and merger expenses	40	40	1	1	41	41
Other, net	119	119	1	1	120	120
Adjusted EBITDA guidance	\$ 3,485	\$ 3,685	\$ (85)	\$ (75)	\$ 3,400	\$ 3,610
Interest paid, net	(514)	(514)	_	_	(514)	(514)
Tax (paid)/received (c)	136	136	_	_	136	136
Tax receivable agreement payments	(1)	(1)	_	_	(1)	(1)
Working capital and margin deposits	17	17	(5)	(5)	12	12
Reclamation and remediation	(34)	(34)	(94)	(94)	(128)	(128)
Other changes in other operating assets and liabilities	(129)	(129)	(3)	(3)	(132)	(132)
Cash provided by operating activities	\$ 2,960	\$ 3,160	\$ (187)	\$ (177)	\$ 2,773	\$ 2,983
Capital expenditures including nuclear fuel purchases and LTSA Prepayments	(704)	(704)	_	_	(704)	(704)
Solar and Moss Landing development and other growth expenditures	(377)	(377)	_	_	(377)	(377)
(Purchase)/sale of environmental credits and allowances	(253)	(253)	_	_	(253)	(253)
Other net investing activities	(1)	(1)	7	7	6	6
Free cash flow	\$ 1,625	\$ 1,825	\$ (180)	\$ (170)	\$ 1,445	\$ 1,655
Working capital and margin deposits	(17)	(17)	5	5	(12)	(12)

¹ Regulation G Table for 2020 Guidance prepared as of November 5, 2019.

⁽a) Includes unrealized gain on interest rate swaps of \$21 million.

⁽b) Includes nuclear fuel amortization of \$74 million.

⁽c) Includes state tax payments.

Solar and Moss Landing development and other growth expenditures	377	377	_	_	377	377
Purchase/(sale) of environmental credits and allowances	253	253	_	_	253	253
Transition and merger expenses	114	114	10	10	124	124
Transition capital expenditures	23	23	_	_	23	23
Adjusted free cash flow before growth guidance	\$ 2,375	\$ 2,575	\$ (165)	\$ (155)	\$ 2,210	\$ 2,420

¹ Regulation G Table for 2020 Guidance prepared as of September 29, 2020.

VISTRA CORP.

NON-GAAP RECONCILIATIONS - 2021 GUIDANCE¹

(Unaudited) (Millions of Dollars)

	Ongoing		Asset		Vistra	
	Operations		Closure		Consolidated	
	Low	High	Low	High	Low	High
Net Income (loss)	\$ 607	\$ 920	\$ (80)	\$ (60)	\$ 527	\$ 860
Income tax expense	195	283	_	_	195	283
Interest expense and related charges (a)	429	429	_	_	429	429
Depreciation and amortization (b)	1,650	1,650	_	_	1,650	1,650
EBITDA before Adjustments	\$ 2,881	\$ 3,282	\$ (80)	\$ (60)	\$ 2,801	\$ 3,222
Unrealized net (gain)/loss resulting from hedging transactions	59	59	_	_	59	59
Fresh start / purchase accounting impacts	2	2	_	_	2	2
Impacts of Tax Receivable Agreement	75	75	_	_	75	75
Non-cash compensation expenses	45	45	_	_	45	45
Transition and merger expenses	10	10	_	_	10	10
Other, net	3	2			3	2
Adjusted EBITDA guidance	\$ 3,075	\$ 3,475	\$ (80)	\$ (60)	\$ 2,995	\$ 3,415
Interest paid, net	(456)	(456)	_	_	(456)	(456)
Tax (paid)/received (c)	(60)	(60)	_	_	(60)	(60)
Tax receivable agreement payments	(3)	(3)	_	_	(3)	(3)
Working capital and margin deposits	60	60	_	_	60	60
Reclamation and remediation	(38)	(38)	(100)	(100)	(138)	(138)
Other changes in other operating assets and liabilities	1	1	(6)	(6)	(5)	(5)
Cash provided by operating activities	\$ 2,579	\$ 2,979	\$ (186)	\$ (166)	\$ 2,393	\$ 2,813
Capital expenditures including nuclear fuel purchases and LTSA Prepayments	(771)	(771)	_	_	(771)	(771)
Solar and Moss Landing development and other growth expenditures	(687)	(687)	_	_	(687)	(687)
(Purchase)/sale of environmental credits and allowances	(29)	(29)	_	_	(29)	(29)
Other net investing activities	(20)	(20)	6	6	(14)	(14)
Free cash flow	\$ 1,072	\$ 1,472	\$ (180)	\$ (160)	\$ 892	\$ 1,312
Working capital and margin deposits	(60)	(60)	_	_	(60)	(60)
Solar and Moss Landing development and other growth expenditures	687	687	_	_	687	687
Purchase/(sale) of environmental credits and allowances	29	29	_	_	29	29
Transition and merger expenses	28	28	_	_	28	28
Transition capital expenditures	9	9			9	9
Adjusted free cash flow before growth guidance	\$ 1,765	\$ 2,165	\$ (180)	\$ (160)	\$ 1,585	\$ 2,005

 $^{^{1}}$ Regulation G Table for 2021 Guidance prepared as of September 29, 2020.

⁽a) Includes unrealized loss on interest rate swaps of \$181 million (an incremental loss of \$202 million from prior 2020 guidance).

⁽b) Includes nuclear fuel amortization of \$74 million.

⁽c) Includes state tax payments.

⁽a) Includes unrealized gain on interest rate swaps of \$52 million.

⁽b) Includes nuclear fuel amortization of \$82 million.

(c) Includes state tax payments.

View original content to download multimedia:http://www.prnewswire.com/news-releases/vistra-accelerates-pivot-toinvest-in-clean-energy-and-combat-climate-change-301139377. html

SOURCE Vistra

QUICK LINKS

- > SEC Filings > Tax Form
- > FAQs
- > Sustainability